AD-A251 471

AD

2

TECHNICAL r e p o r t

USA-BRDEC-TR // 2522

Air Conditioner Requirements Validation Review of Decentralized Automated Service Support System (DAS-3)

by
Gregory F. Brainard

Report Date
May 1992

DTIC
SELECTE
JUN 09 1992
S D

Distribution unlimited; approved for public release.

92 6 05 006

92-14879

United States Army
Belvoir Research, Development and Engineering Center
Fort Belvoir, Virginia 22060-5606

**Destroy this report when it is no longer needed.
Do not return it to the originator.**

**The citation in this report of trade names of
commercially available products does not constitute
official endorsement or approval of the use of such
products.**

REPORT DOCUMENTATION PAGE			<i>Form Approved</i> <i>OMB No. 0704-0188</i>	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Service, Direction of Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE May 1992	3. REPORT TYPE AND DATES COVERED Final	
4. TITLE AND SUBTITLE Air Conditioner Requirements Validation Review of Decentralized Automated Service Support System (DAS-3) (U)			5. FUNDING NUMBERS	
6. AUTHOR(S) Gregory F. Brainard; technical and administrative input from Andrew A. Thompson, James P. Lucas, and the Systems Assessment Team				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Belvoir Research, Development & Engineering Center Logistics Equipment Division Environmental Control and Systems Support Division Fort Belvoir, VA 22060-5606			8. PERFORMING ORGANIZATION REPORT NUMBER 2522	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)			10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES POC: Gregory F. Brainard, (703) 704-2634				
12a. DISTRIBUTION/AVAILABILITY STATEMENT Distribution unlimited; approved for public release.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) This report assesses the tactical electric power and cooling requirements of the Decentralized Automated Service Support System, or DAS-3 (AN/MYQ-4A), for the "Air Conditioner Requirements Review Program."				
14. SUBJECT TERMS Systems Assessment Model (SAM) Environmental Control Unit (ECU)			15. NUMBER OF PAGES 36	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT Unlimited	

Report Number 2522

Air Conditioner Requirements Validation Review of Decentralized Automated Service Support System (DAS-3)

by
Gregory F. Brainard

**US Army Belvoir RD&E Center
Fort Belvoir, Virginia 22060-5606**

May 1992

Distribution unlimited; approved for public release.

Table of Contents

	Page
Section I Background.....	1
Section II Approach.....	2
Section III System Description	3
Section IV Discussion	4
Section V Findings.....	9
Appendix Special SSDC Report SR 90-158 Air Conditioner Requirements Review, Power Consuming Equipment Inventory, Decentralized ADPE Service Support DAS-3, November 8, 1990	

Tables

1	DAS-3 Equipment Power Demands	5
2	SAM Model Data.....	8

Figures

1	DAS-3 Shelter Diagram.....	3
2	DAS-3 Cooling Requirements, 90°F Internal.....	6
3	DAS-3 Cooling Requirements, 80°F Internal.....	7

Accession For	
NTIS GRA&I	☒
DTIC TAB	☐
Unannounced	☐
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

Section I

Background

The U. S. Army's Troop Support Command (TROSCOM) and Training and Doctrine Command (TRADOC) initiated the "Air Conditioner Requirements Review Program" to establish requirements for a new generation of environmental control equipment. TRADOC's Ordnance School; TROSCOM's Special Programs Management Offices; and Belvoir Research, Development, and Engineering Center (BRDEC), Systems Assessment Team were the program's primary participants. The Systems Assessment Team was directed to assess the electric power and cooling requirements of selected Army systems. To assist in this effort, a Special Sample Data Collection (SSDC) Project was established under the auspices of the TROSCOM Sample Data Collection Program. The SSDC Project inventories each system, paves the way for the assessment, and conducts operator interviews regarding the effectiveness of existing electric power and cooling equipment. Systems to be assessed include: DAS-3, MSE, TACMIS, FAADS, SICPS, and Patriot.

Section II

Approach

It is necessary to account for electrical power demand when determining the cooling load of a system. This process involves three steps:

First, all power consuming equipment in the system's shelter must be inventoried. This includes collecting the manufacturer's nameplate data and inspecting manuals for each item.

Second, the system's power consumption must be measured while equipment items, groups, and the entire system are powered-up and powered-down. From this data, the power demand of each piece of equipment and a predicted maximum system power demand can be derived. This technique includes power conditioner losses with the supported equipment's power demand.

Finally, the shelter's thermal characteristics and personnel and tactical requirements must be entered into the Shelter Systems Assessment Model (SAM). The computer model can then determine cooling loads and Environmental Control Unit (ECU) suitability under hypothetical ambient conditions. When test conditions allow, the ECU needs should be validated using temperature data taken during the test and by interviewing experienced system operators.

Section III

System Description

DAS-3 is designed to process data for personnel, medical and financial functions at the division, corps or theater levels of command. DAS-3:

- Reduces, manipulates and summarizes data.
- Generates reports and historical files.
- Processes interactive or batch transactions (through an electronic interface or recording media) with other management information systems.

The DAS-3 system provides tactical data processing within an operational area. It is housed in a single 5-ton XM971 semitrailer van (see Figure 1). Field power is provided by a 60 kW, 60 Hz trailer-mounted generator set (AN/MJQ-12). Four 18,000 BTUH vertical air conditioners, Line Item Number A2445 (CH-620-2), provide cooling.

DAS-3's electronic equipment includes communications, printing, and data recording and processing (see Appendix). Four soldiers operate the system.

Figure 1. DAS-3 Shelter Diagram

Section IV

Discussion

An inventory of DAS-3 was performed (see page 4 of the Appendix), and each piece of power consuming equipment was listed as a column heading on the Power Measurement Load Configuration form (see Figure 2 of Appendix). This form documents the switch position for each equipment item at each step of the test sequence. The test began with all equipment turned off. The test team took power consumption readings at the power source while operators switched on various groupings of equipment in sequence. The power readings were entered in the Power Generator Performance form (see Figure 3 of Appendix). This form records the load on each phase of the generator for each step in the test sequence.

The power consumed by each item, including associated power conditioning losses (see Table 1), is derived from the change in total power as the item is switched on. The power consumption data listed on Table 1 is grouped into several subcategories.

The first category, "Total Internal Power Demand Measured in Operational Mode," refers to equipment that was tested at its full operational capacity. The second category, "Measured Power Demand in Stand-By Mode," refers to equipment for which test conditions prevented maximum load operation. For example, a computer disk drive may not run unless certain software is available. Those subtotals are then added to achieve "Total Measured Power Demand Internal Load," which is the electric power which the ECU capacity must compensate for to maintain the desired internal temperature. The final total, "Total Estimated Generator Load," includes the electric load which does not contribute to the cooling requirement.

Power consuming items and their respective power demand were used as input for eight computer runs of SAM (see Figures 2 and 3). Cooling loads for internal temperatures of both 80°F and 90°F are considered. The equipment requires 80°F to operate continuously while Human Factors considerations require a maximum of 90°F. Internal humidity was limited to 60%. Desert conditions (environment 1, AR 70-38), tropic conditions (environment 4), and equipment power use of 5 and 10 kW were analyzed. Assumptions used in the computer analysis are found in Table 2.

Table 1. DAS-3 Equipment Power Demands

Nomenclature	(count)	Model Number	Power Demand (watts)
Light, Fluorescent ICP	(24)	BR-2009 (30W)	720
Processing Unit, Data		CP-1435	896 *
Disk Memory Unit	(6)	MV-705	2170
Keyboard Display	(3)	MX-10173	306
Converter, Frequency		CV-3661A	100
Modem****	(2)	MD-1149	
Converter****	(2)	CV-3787	
Modem****		MD-1150	
Converter****		CV-3788	1813
Isolator Unit****		—	(Total)
Total Measured Power Demand in Operational Mode			5005
Magnetic Tape Unit***	(2)	TW-430	115 **
Total Measured Power Demand in Stand-By Mode			115
Total Measured Power Demand Internal Load			5.12 kW
Cleaner, Magnet I		MX-10172	
Card Punch, Reader I***		R-0526A	
Line Printer		RP-309	
Printer Assembly		TT-804	
Dual Diskette Drive***		MV-857	
Humidifier**		6066NIO	
Total Internal Load, Estimated + Measured			8.12 kW
Environmental Control Unit	(4)	F18T-2	20.60 kW
Total Generator Load as Measured			25.72 kW
Total Estimated Generator Load			28.72 kW

* Operated in test mode

** Operated in stand-by mode

***Several equipment items were inoperative or removed for maintenance:

****A group of equipment operated (without individual switches) from a breaker was turned on and off simultaneously. Only total power demand could be calculated.

Figure 2. Cooling Requirements, 90°F Internal

Figure 3. Cooling Requirements, 80°F Internal

Table 2. SAM Model Data

SHELTER SYSTEM ASSESSMENT MODEL
HVAC, POWER, AND WEIGHT REQUIREMENTS

Run Parameters	Calculation Details	Totals
Run Config. Environ. 1 DAS-3 I ENVA	BTU/Equip.: 51195. (10 for AC, /Shelters: 8882. (0 for heat) /Sensible & latent heat due to ventilation and personnel: 9644.	BTU/hr 69721.0
Structure: X-971EL Weights: 13110.0 lbs	a) Heat: 0.00 b) AC: 20.78 c) Equip: 15.00 d) Max(Heat, AC): 20.78 e) Max(Max(Heat, MaxAC, MaxEqp): 29.94 Note: "e" accounts for the highest individual power consumer regardless of usage rate and includes the startup factor.	Adjusted Power (KW) (Max(c,d,e))
Other Settings AC Util. Conv. In. No CBR Total CFM: 80.0 Min. Interior Temp. Max. Interior Temp. 90. (°F)	Personnel Wt: 1068 lbs AC Weight: lbs Equip Wt: 0.0 lbs Generator Wt: lbs	Total Wt. Incl. Struc. (LBS)

CONFIGURATION DESCRIPTIONS				
CONFIGURATION: DAS 3 I				
Config description: DAS 3 with dummy load It is housed in a: X-971EL				
PERSONNEL LOADING				
QTY	SENSIBLE LOAD (BTU/hr)	LATENT LOAD (BTU/hr)	VENTILATION (CFM/hr)	WEIGHT/PERSON (lb)
4	315.00	325.00	2.0	267

ENVIRONMENT CHARACTERISTICS				
ENVIRONMENT NAME	TEMPERATURE OUTSIDE (°F)	HUMIDITY OUTSIDE (%)	WIND SPEED (mph)	SOLAR LOAD (BTU/hr/ft²)
ENVA	95.0	100.0	8.9	307.0
ENVI	120.0	5.0	8.9	231.0
				GROUND TEMPERATURE (°F)
				130.0
				145.0

DATA FOR STRUCTURES					
NAME		TYP	SIDE	END	BOTTOM
X-971EL	Surface area (ft ²):	283.33	582.77	124.34	283.33
	U-factor (BTU/hr/ft ² /°F):	0.23	0.23	0.23	0.23
	Solar Absorb. (BTU/hr/ft ²):	0.70	0.70	0.70	0.70
	Angle with horizontal:	0.00	90.00	90.00	180.00
	Area of Uninsulated				
	Penetration by Conduits (ft ²):	0.00	0.00	0.00	0.00
	Weight (lbs): 13110.0	Heat Capacitance (BTU/lb/°F):	1.		

Section V

Findings

The DAS-3 power demand, with all available equipment operating, measured 25.72 kW, including 20.6 kW for ECUs and 5.12 kW for equipment. In this configuration, a 30 kW generator set and three of the 18,000 BTUH air conditioners would provide more than the required power and cooling for DAS-3's electronic equipment even with an 80°F limit. When an additional 3 kW load is added to account for equipment not available for measurement at the time of this test, the fourth ECU will be needed to maintain 80°F.

Operator interviews confirm that the generator set and air conditioners provided with the DAS-3 are appropriate for mission operations.

Appendix

SR90-158

November 8, 1990

Special Report

Air Conditioner Requirements Review
Power Consuming Equipment Inventory
Decentralized ADPE Service Support
DAS3

PREPARED FOR:

U.S. Army Belvoir Research,
Development & Engineering Center
Attention: STRBE-FEA
Fort Belvoir, Virginia 22060

PREPARED BY:

COBRO Corporation
Suite 850, North Tower
7799 Leesburg Pike
Falls Church, Virginia 22043

Suite 850, North Tower • 7799 Leesburg Pike • Falls Church, VA 22043 • (703) 448-3350 • (Fax) (703) 448-8360

TABLE OF CONTENTS

	<u>Page</u>
Introduction	1
Program Overview	1
Data Collection Infrastructure	1
Data Objectives.	2
Collection Methodology	2
Power Analysis	3
CTASC II Description	3
CTASC II Power Consuming Equipment Inventory	3
Debriefing	5

List of Figures

<u>Figure</u>	<u>Title</u>	<u>Page</u>
1	System Inventory Form	6
2	Power Measurement Load Configuration Form	7
3	Power Generator Performance Data Form	8

SPECIAL REPORT
AIR CONDITIONER REQUIREMENTS REVIEW

DAS3 ASSESSMENT

INTRODUCTION

This special report on field data collected has been prepared to provide Belvoir Research, Development and Engineering (RD & E) Center's Systems Assessment Team selected information about DAS3, an Army system designated by U.S. Army Ordnance Center and School (Letter, ATSL-CD-MS, Subject: Air Conditioner Requirements Review, dated 19 September 1990) as a system best suited to provide input to an air conditioner requirements analysis.

PROGRAM OVERVIEW

The collected information from each of nine systems will be summarized by the Systems Assessment Team in a concise, meaningful form, and conveyed to the Training and Doctrine Command (TRADOC) Air Conditioner Requirements Review (ACRR) Team at the U. S. Army Ordnance Center and School for consideration as the team addresses and recommends attributes for a new standard family of tactical air conditioners.

The specified systems are:

TACFIRE	-Direction Center, Artillery
FAADS	-Forward Area Air Defense System
JTIDS	-Joint Tactical Information Distribution System
SICPS	-Standardized Integrated Command Post System
MSE	-Mobile Subscriber System
PATRIOT	-Air Defense Missile System
DAS3	-Decentralized Automated Service Support System
HAWK	-Air Defense Missile System
TACMIS	-CTAS-2 Corps/Theater ADP Service Center)

Coordination to gain access to the target systems is done at command levels. Local schedules and task interpretation at the owning unit is done by COBRO representatives on site.

DATA COLLECTION INFRASTRUCTURE

The data collection phase of the ACRR program utilizes Belvoir's Tactical Assessment of Power (TAP) Sample Data Collection (SDC) Program. The TAP program was selected to support the ACRR program because all of the field data can be obtained in similar fashion and without adding additional people.

TAP is supported in the field using the contracted support infrastructure for SDC. COBRO Corporation provides the support to TAP and to ACRR through its offices at Fort Belvoir, Fort Bragg, Fort Hood, and others, depending upon where the target systems can be located.

DATA OBJECTIVES

The collection is focussed on the equipment listed under Program Overview. The purpose is to develop detailed data on tactical power consumers, tactical shelters, tactical air conditioners mounted on the tactical shelters, shelterized system crew staffing, system environmental capability, system operating profiles, and crew training and experience.

COLLECTION METHODOLOGY

Data are collected on site by a team of people organized to perform a subsystem inventory, conduct a controlled, power-up procedure, measure operating and environmental parameters, and debrief operators about their training on the system, their field experience with the system, and the system's operating modes.

The field team consists of a Senior Technician and an Engineer from the Systems Assessment Team at Fort Belvoir. A Field Monitor from a COBRO Corporation field office and the COBRO Senior Technical Analyst for the TAP SDC Program at Fort Belvoir completes the team.

At the field site the team accomplishes the following:

Assistance of the system operator(s) is solicited to identify the separate power consuming subsystems/components of the system housed in the shelter. The inventory data are posted to the Power Using Inventory form (Figure 1).

The interrelationships and power supply lash-up is reviewed as a basis for developing the measurement test plan. Initially the plan is tentative and can be sensitive to the unexpected. The plan is modified as necessary and posted to the Power Measurement Load Configuration form (Figure 2) as a sequence of power-up events. Measured results of the power-up sequences are posted by input power phase (A,B, and C) to the Power Generator Performance Data form (Figure 3).

Notes about shelter size, trailer information, prime movers, generators, and air conditioners are taken. Operators and crew members are debriefed to gain insight to operating modes, operating conditions, training, and field experiences. Debriefings are based on the format presented in Figure 4.

The team reviews the information gathered and conducts a verification analysis to insure values of voltage, current, and wattage can be determined for each component on the inventory; either measured directly or calculated from other measured values.

POWER ANALYSIS

Values recorded on the Power Generator Performance Data Form are verified by the Systems Assessment Team at Fort Belvoir using procedures calculated to establish the power values to be used later in Fort Belvoir's Shelter Systems Assessment Model (SAM).

SAM is utilized to determine cooling requirements that maintain Human Engineering habitability conditions (MIL-STD-1472) at various climate conditions.

DAS3 DESCRIPTION

The DAS3 (Decentralized Automated Service Support System) is used at division and corps to perform automatic data processing functions. The system accomplishes data reduction, data manipulation and summarization, generation of reports and historical files, processing of transactions of an interactive or batch basis, and has the capability to interface, electronically or through the use of some recording media, with other levels of management information systems.

DAS3 POWER USING EQUIPMENT INVENTORY

The DAS3 (D/C) (AN/MYQ-4A) is based on the DAS3 field system, AN/MYQ-4. The AN/MYQ-4A includes additional automatic data processing equipment (ADPE) to facilitate support at division and corps headquarters.

The DAS3 assessed is housed in an XM971, mobile van. At the time of inventory the system was parked on hardstand and cabled for power to a commercial, 120 VAC, disconnect. The generator assigned to support the system in the field is the 60KW, PU-650B/G (MEP-006A). Environmental control is provided by four, front-mounted, vertical, 18K BTU, 208 VAC, 60Hz air conditioners.

At the time of inventory one air conditioner was disintalled for maintenance action. One of the three installed in the van was not working. The system was being deprocessed for turn-in. As a consequence, the mass storage disk system and the magnetic tape system were not operational. The humidifier was also non-operational.

POWER CONSUMING EQUIPMENT

<u>System Code</u>	<u>Line Number</u>	<u>Nomenclature</u>	<u>Model</u>	<u>Stock Number</u>
BD044	D78325	System, Auto Data Proc	AN/MYQ-4A	7010-01-158-5397
BD045	None	Unit, Data Processing	CP-1435	5895-01-092-2549
BD046	None	Unit, Magnetic Tape	TW-430	5895-01-092-2550
BD047	None	Printer, Line	RP-309	7010-01-177-0646
BD048	None	Unit, Disk Memory	MV-705	7025-01-092-2745
BD049	None	Cleaner, Magnetic	MX-10172	7045-01-016-4147
BD050	None	Card, Punch, Reader I	R-0526A	5999-01-092-2551
BD051	None	Display, Keyboard	MX-10173	5895-01-092-2552
BD052	None	Drive, Dual Diskette	MV-857	None available
BD053	None	Humidifier	6066N10	None available
BD054	None	Heater, Space, Electric	H-52641	4520-00-177-6198
BD055	None	Assembly ssembly	TT-804	6675-01-153-0775
BD056	None	Converter, Frequency	CV-3661A	5895-01-092-2649
AA006	None	Light, Flourescent, ICP	BR-2009	None available
AK001	A24455	Conditioner, Air	F 18T-2	4120-01-089-4053
BD057	None	Converter	CV-3787	None available
BD058	None	Modem	MD-1149	None available
BD059	None	Converter	CV-3738	None available
BD060	None	Modem	MD-1150	None available
BD061	None	Unit, Isolator	None	None available

DEBRIEFING

An operator was debriefed on DAS3 operational modes and areas of interest about the environmental control system. The information provided by the briefee, in response to questions asked, follows:

Demographics

Briefee	System operator
Military Occupational Specialty	76PM6 DAS3 skill identifier
Training	DAS3 Course, Fort Lee, 1989
Time on DAS3	Approximately 4 years
Field exposure during DAS3 assignment	Five training exercises

Modes of Operation

What are the DAS3's modes	Standby - System up, no proc Operating - Job processing
Number of operators required	One - Minimum jobs Three - Moderate number jobs Four - Maximum jobs simultaneously
Define minimum operation	Administrative procedures filing, labelling
Define moderate operation	One job at a time
Define maximum operation	Processing one job, preparing for others under time constraints
Duration of maximum operation	Three to five days
Longest required duration	As required
Modes you have operated	All three
Status of shelter door	Closed during operation

NBC

Collective protection for NBC

No

Environmental Control

Shelter has ECU

Yes

ECU nomenclature

Vert A/C, 60Hz, 208VAC, 3Ph

Model

F 18T-2

Heating

13,000 BTU

Cooling

18,000 BTU

How often ECU used

Full time

Comfort during hot weather

Reasonable

Comfort during cold weather

Reasonable

Proper operating temperatures

Yes, with all four ECUs

Proper operating temperatures (Cold)

Adequate

Operation of ECU unit

Easy

Your problems with ECU

No indicators of freon leak
Noisy

Maintenance

Adequate - Had priority

Other comments pertinent

A/C output not adequately
distributed

SYSTEMS INVENTORY FORM

[illegible]

Figure 1. System Inventory Form

[illegible]

Figure 2. Power Measurement Load Configuration

Date / /

System

Figure 3. Power Generator Performance Data

Air Conditioner Requirements Review

INTRODUCTION

The information in this completed debriefing is supplemental to and becomes part of the unbundled system data file.

The data for this portion of the Air Conditioner Requirements Review will be obtained by a member of the TAP program Unbundling Team during an informal discussion with an assigned operator of the unbundled system. The following sections should be used to guide the discussion.

SYSTEM DESCRIPTION

1. Date: _____
2. System Unbundled: _____
3. Location: _____
4. Site Description: _____

SYSTEM POWER REQUIREMENTS

5. What Type of Power Does the System Require? ____ 60Hz; ____ DC;
____ 400Hz; Single Phase? ____ 120v; ____ 240v; Three Phase?
____ 208v; ____ 416v?
6. For DC Systems, What Equipment Requires the DC Power? _____

7. For 400Hz Systems, What Equipment Requires the 400Hz Power? _____

DEMOGRAPHICS

8. Briefer: _____
9. Briefee: _____ MOS: _____
10. Training: ____ School ____ OJT ____ When? _____
11. Length of Assignment to System: Years ____ Months ____
12. Field Exposure While Assigned: _____

Figure 4. Debriefing Format

Air Conditioner Requirements Review

MODES OF OPERATION

13. What are the System's Mode(s) of Operation?

14. How Many Operators Required For Each Mode?

15. Low _____

16. Moderate _____

17. High _____

18. Your Understanding of Low Intensity Operation. _____

19. Your Understanding of Mid Intensity Operation. _____

20. Your Understanding of High Intensity Operation. _____

21. What Is the Expected Duration for High Intensity Operation? _____

22. What Is the Longest Required Duration for High Intensity Operation

Figure 4. Debriefing Format (Continued)

Air Conditioner Requirements Review

23. Which of the Three Operational Levels Have You Operated the System? ____ Low ____ Mid ____ High
24. Do You Normally Operate the System With the Shelter Door Open ____ Or Closed ____?

NBC

25. Is the Shelter Equipped with Collective Protection for NBC (CBR) conditions? ____
26. How Well Does the Collective Protection System Work? _____

ENVIRONMENTAL CONTROL UNIT

27. Does the Shelter Have An ECU? ____ Yes ____ No
28. ECU Nomenclature: _____
29. Model: _____
30. Heating: _____ BTU
31. Cooling: _____ BTU
32. How Often Do You Use the ECU? _____

33. What Is Your Assessment Of the Interior Comfort When Your System Is Being Operated For Extended Periods During Hot Weather? _____

34. What Is Your Assessment Of the Comfort When Your System Is Being Operated For Extended Periods During Cold Weather? _____

Figure 4. Debriefing Format (Continued)

Air Conditioner Requirements Review

-
35. Do You Think the ECU Adequately Maintains Proper Equipment Operating Temperatures?
36. During Hot Weather? _____
37. During Cold Weather? _____
38. How Would You Categorize Operation (Operator Interface) Of the ECU?
39. Easy _____
40. Difficult _____
41. Complex _____
42. What Problems Have You Experienced With the ECU? _____
43. 1. _____

44. 2. _____

45. 3. _____

46. What Other Comments Regarding the System, Its operation, Air Conditioning, Heating, Or Collective (NBC/CBR) Protection Would You Like To Note? _____

Figure 4. Debriefing Format (Continued)

Distribution for Report No. 2522

-
1	Director, Technical Information
Defense Advanced Research Projects Agency
1400 Wilson Blvd.
Arlington, VA 22209	1	HQ Air Force Civil Engineering Support Agency,
RAAE
ATTN: C. Calobrisi
Tyndall AFB, FL 32403-6001
2	Defense Technical Information Center
Cameron Station
ATTN: DTIC-FDAC
Alexandria, VA 22304-6145		Product Manager, PEO, Air Defense
1	DOD Project Manager
Mobile Electric Power
7500 Backlick Road
Springfield VA 22150	1	ATTN: SFAE-AD-GSL
1	Commander
US Army Missile Research and
Development Command
ATTN: AMSMI-PR
Redstone Arsenal, AL 35809	1	ATTN: SFAE-AD-LU
1	Director
US Army Materiel System Analysis Agency
ATTN: AMXSJ-MP
Aberdeen Proving Ground, MD 21010-5071	1	ATTN: SFAE-AD-FM
1	US Army Tank Automotive Command
ATTN: DRSTA-TSL
Warren, MI 48090	1	ATTN: SFAE-AD-PA
1	Commander
US Army Electronics Research and
Development Command
ATTN: DELSD-L
Fort Monmouth, NJ 07703-5301	1	ATTN: SFAE-AD-AUG
1	Commander
Rock Island Arsenal
ATTN: SARRI-LPL
Rock Island, IL 61299-7300	1	ATTN: SFAE-CC-AD
Redstone Arsenal, AL 35898-5796
	Project Manager, PEO,
Communication Systems	1	Project Manager, PEO,
Armored Systems Modernization
1	ATTN: SFAE-CM-ADD		ATTN: SFAE-ASM-BV
1	ATTN: SFAE-CM-EP		ATTN: SFAE-ASM-CV
1	ATTN: SFAE-CM-MSE		ATTN: SFAE-ASM-SS
1	ATTN: SFAE-CM-MCS		Warren, MI 48397-5000
1	ATTN: SFAE-CM-SC
Fort Monmouth, NJ 07703-5000	1	Project Manager, PEO,
Command Control Systems
		1	ATTN: SFAE-CC-CHS
		1	ATTN: SFAE-CC-FS
		1	ATTN: SFAE-CC-MVR
Fort Monmouth, NJ 07703-5000
			Project Manager, PEO,
Intelligence and Electronic Warfare
		1	ATTN: SFAE-IEU-EU
		1	ATTN: SFAE-IEU-JS
		1	ATTN: SFAE-IEU-RD
Fort Monmouth, NJ 07703-5000
			Product Manager, PEO,
Intelligence and Electronic Warfare
		1	ATTN: SFAE-IEU-SG
Vint Hill Farms Station
Warrenton, VA 22186-5116
		1	Commander
Ordnance Center and School
ATTN: ATSL-CD
Aberdeen Proving Ground, MD 21005-5201
		1	HQDA, FARD-TT
Washington, DC 20310-0103
-

Belvoir RD&E Center

Circulate

- 1 Commander STRBE-Z
 - Technical Director STRBE-ZT
 - Assoc Tech Dir (E&A) STRBE-ZTE
 - Assoc Tech Dir (R&D) STRBE-ZRE
 - Sergeant Major STRBE-ZM
 - Advanced Systems Concept Dir STRBE-H
- 4 STRBE-F
- 3 STRBE-FE
- 20 STRBE-FEA
- 2 Tech Reports Ofc ASQNK-BVP-G
- 3 Security Ofc (for liaison officers) STRBE-WS
- 2 Technical Library STRBE-BT
- 1 Public Affairs Ofc STRBE-IN
- 1 Ofc of Chief Counsel STRBE-L