# NAVAL AIR DEVELOPMENT CENTER

WARMINSTER, PA. 18974

REPORT NO. NADC-72049-VT

29 MARCH 1972

TEST PLAN FOR A STRUCTURAL INTEGRITY INVESTIGATION FOR THE CH-46 AFT TRANSMISSION PLANETARY CARRIER BEARING NUT IN SUPPORT OF THE ANALYTICAL REWORK PROGRAM

FINAL REPORT

NAVAIR WR-25145/24, Work Unit GA8-2

APPROVED FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED

. .



a state of the second

AD74307



وأنفقته وستعملان ومستكر ومستكر ومستكر ومعارك والمتحد ومناجع ومحمد والمراجع والمحمول والمحاور والمحاور			
Security Classification			
	T CONTROL DATA		
Security class fication of title holiv of abstract_un POINATING ACTIVIT: (Corporate author)	Findexing annotation must b	the second s	ECURITY CLASSIFICATION
VAL AIR DEVELOPMENT CENTER		UNCLASSIFIED	
R VEHICLE TECHNOLOGY DEPARTMENT		2b. GROUP	
RMINSTER, PENNSYLVANIA 18974			
T PLAN FOR A STRUCTURAL INTEGRITY NETARY CARRIER BEARING NUT IN SUPP			
ESCRIPTIVE HOTES (Type of report and inclusive dates)	)	·	
nal Report			
NALD P. SWARTZ			
PORT DATE	78. TOTAL NO	OF PAGES	TH NU OF REFS
MARCH 1972			2
ONTRACT OR GRANT NO	· .	-72049-VT	A{+E, R(5)
PROJECT NO	I MADC.	" <i>1 6</i> 047"VL	
AVAIRSYSCOM Work Request			
-25145/24, Work Unit GA8-2	this report)	PORT NO(S) (Ani	other numbers that may be assigned
IS INBUTION STATEMENT			
OPPLENENTARY NOTES	NAVAL A DEPARTM	G MILITANY ACT	Co <b>m</b> and Navy
BSTRACT	WASHING	ION, D. C.	20360
The CH-46D mishaps in 1967 and 1 the aft transmission planetary of tests to determine if a mode of could be present. Static and fa and modified versions.	arrier bearing nu failure other tha	ut. This t an that ass	est plan proposes umed by the concracion
The CH-46D mishaps in 1967 and 1 the aft transmission planetary o tests to determine if a mode of could be present. Static and fa	arrier bearing nu failure other tha	ut. This t an that ass	est plan proposes umed by the concracion

「本語」とないとなるなどでなる言語

UNCLASSIFIED Security Classification



DEPARTMENT OF THE NAVY NAVAL AIR DEVELOPMENT CENTER JOHNSVILLE WARMINSTER, PA. 18974

CONTRACTOR OF A DESCRIPTION OF A DESCRIP

Air Vehicle Technology Department

REPORT NO. NADC-72049-VT

29 MARCH 1972

TEST PLAN FOR A STRUCTURAL INTEGRITY INVESTIGATION FOR THE CH-46 AFT TRANSMISSION PLANETARY CARRIER BEARING NUT IN SUPPORT OF THE ANALYFICAL REWORK PROGRAM

The CH-46D mishaps in 1967 and 1971 precipitated a contractor designed fix of the aft transmission planetary carrier bearing nut. This test plan proposes tests to determine if a mode of failure other than that assumed by the contractor could be present. Static and fatigue tests are proposed on both the original and modified versions.

SMARTZ Reported by

Released by

Associate Director, Aero Structures

APPROVED FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED

NODC- 72049-VT

and the second

and the second second

4

1

storener in each and the second

# TABLE OF CONTENTS

Sine N.

product State some ways

	Page
INTRODUCTION	1
SFECIMEN DESCRIPTION	2
INVESTIGATIVE APPROACH	2
REFERENCES	3

a meters of the second second second

1.5

355

# NADC-72049-VT

# LIST OF FIGURES

Figure		<u>Page</u>
1	Pin Fix Modification	4
2	Test Specimen	5
3	Test Setup	6

## NADC-72049-VT

#### INTRODUCTION

ngeneral sen her her server and and her server and and the server and the server of the ser

During the investigation of a CH-46D helicopter crash S/N153967 at New River in 1967, it was determined that the cause of the crash was the disengagement of the planetary gear carrier self-locking nut, P/N BACN 10GR39, which allowed the planetary gear carrier assembly to drop. This resulted in complete disengagement from the sun driving gear splines with consequent loss of power to the aft rotor shaft. It was also determined during this investigation that rotation of the bearing on the planetary carrier, due to a low locking torque, would produce a rotational force on the self-locking nut in the loosening direction, thereby contributing to its removal.

Reference (a) stated that the recommended fix of increased torque values of 1320-1570 lb-ft should provide adequate clamping force to adequately retain the bearing inner ring regardless of the amount (within blueprint tolerance) of interference fit. As a result, the increased torque values were used in all CH-46 helicopters.

In December 1971, rotor desynchronization in CH-46D, S/N 154804, during approach to Yokota Air Base in Japan caused a second crash. Again the cause was traced to a disengaged planetary gear carrier self-locking nut. The threads on the planetary gear carrier and the self-locking nut were in good condition with no burrs.

As a result of this mishap, a contractor designed fix of pinning the self-locking nut to the planetary gear carrier through the threads, figure (1), was incorporated in CH-46 helicopters. During the installation of this fix, it was noted that torque values on the self-locking nut varied from 300 to 1800 lb-ft. During a meeting between NARF CHPT (Naval Air Rework Facility, Cherry Point) and NADC (Naval Air Development Center) personnel, it was discussed that another cause of nut loosening might be shock loads imposed during hard landings. It is considered possible that the loading condition could cause to be developed, axial loads of sufficient magnitude to pop the nut off the planetary carrier, or at least over a single thread, thereby relieving the torque. Subsequent axial shock loads might pop off the nut one thread at a time. At the time of the investigation of the 1967 accident NARF CHPT had performed a test and determined that the bearing retaining nut could be removed from the planetary carriers by an axial force without damaging the threads. However, records of this test have been destroyed. If this is the case, pinning as shown in figure 1, would not eliminate the problem since the forces would be along the pin.

NARF CHPT requested through reference (b) that an investigation into the force required to remove the nut, both in the unpinned and pinned version, be performed to determine the efficacy of pinning the selflocking nut.

### NADC-72049-VT

#### SPECIMEN DESCRIPTION

Two configurations of the planetary gear carrier assembly will be required for this investigation. The first test specimen will consist of the planetary gear carrier P/N A02D2419, bearing P/N A02DS270 and planetary gear carrier locking nut P/N BACN lOGR39. These parts are shown in figure 2 in their relative positions. The threads of the locking nut and the planetary gear carrier engage only 3-4 threads when assembled. The specimen will be received from NARF CHPT assembled and torqued to the high torque value.

The second test specimen will be identical to the first specimen except that the self locking nut will be pinned in two places 180 degrees apart as shown in figure 1.

#### INVESTIGATIVE APPROACH

An unpinned specimen of the planetary carrier assembly will be mounted in a suitable rigid test fixture. Axial loads will be applied to the bearing to determine the force required to pop the nut off the planetary carrier, figure 3. This test will be performed on both the unpinned and pinned versions of the planetary carrier assembly to determine the difference in force required to remove the nut.

The second part of the test will be to apply a repeated shock load with the specimen mounted in the same test fixture. These loads will be of a lower magnitude than that obtained from the static test. Periodically during the cycling the torque value of the nut will be checked to determine if there has been a change. The nut will then be retorqued and the test continued. Again, both pinned and unpinned versions of the planetary carrier assembly will be tested.

In the event of a bearing failure during the test it will be replaced with a dimensionally identical solid ring which will be considered as part of the test fixture.

NADC-72049-VT

and and the state of the state

ちょうはない いちょういちょう ちょうちょうしょう ちょうしょうちょうちょうちょう ちょうしょう しゅうしん

1. S. V.V.

1.00

the constant was

# REFERENCES

-

ž

į.

ž

- (a) NAVAIKSISCOM letter AIR-536411/11:TA of 16 April 1969
- (b) NAVAIREWORKFAC CHERPT MSG 212141Z March 1972

بنرا فلللت متلج

و محمد الرک ا



Figure 1. Pin Fix Modification



Load

C. A. PALE (MADADED)



Ť

