

AD/A-007 244

HEAVY LIFT HELICOPTER - CARGO HANDLING  
ATC PROGRAM. VOLUME II. FABRICATION  
OF TEST HARDWARE AND FIXTURES (INTE-  
GRATED TEST RIG)

Joseph Shefrin, et al

Boeing Vertol Company

Prepared for:

Army Air Mobility Research and Development  
Laboratory

December 1974

DISTRIBUTED BY:

**NTIS**

National Technical Information Service  
U. S. DEPARTMENT OF COMMERCE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE   |                       | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM   |  |
|---|-----------------------|---|--|
| 1. REPORT NUMBER<br>USAAMRDL-TR-74-97B  | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER<br><b>ADIA-007244</b>                                   |  |
| 4. TITLE (and Subtitle)<br>HEAVY LIFT HELICOPTER - CARGO<br>HANDLING ATC PROGRAM, VOLUME II<br>FABRICATION OF TEST HARDWARE AND FIXTURES<br>(INTEGRATED TEST RIG)   |                       | 5. TYPE OF REPORT & PERIOD COVERED<br>Final Report<br>June 1971 - June 1974           |  |
| 7. AUTHOR(s)<br>Joseph Shefrin<br>Wendell F. Hill (Wichita Division)  |                       | 6. PERFORMING ORG. REPORT NUMBER  |  |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS<br>Boeing Vertol Company<br>(A Division of the Boeing Company)<br>Philadelphia, Pa. 19142   |                       | 8. CONTRACT OR GRANT NUMBER(s)<br>Contract<br>DAA 101-71-C-0840 (P6A)                 |  |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>U. S. Army Aviation Systems Command<br>P. O. Box 209, St. Louis, Missouri 63166<br>Attn: AMSAV-PDAC  |                       | 10. PROGRAM ELEMENT, PROJECT, TASK<br>AREA & WORK UNIT NUMBERS<br>Para. F.4d. (3) (a) |  |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)<br>Eustis Directorate<br>U.S. Army Air Mobility R&D Laboratory<br>Fort Eustis, Va. 23604  |                       | 12. REPORT DATE<br>December 1974  |  |
|   |                       | 13. NUMBER OF PAGES<br>22   |  |
|   |                       | 15. SECURITY CLASS. (of this report)<br>Unclassified                                  |  |
|   |                       | 15a. DECLASSIFICATION/DOWNGRADING<br>SCHEDULE   |  |
| 16. DISTRIBUTION STATEMENT (of this Report)<br><br>Approved for public release; distribution unlimited.   |                       |   |  |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)  |                       |   |  |
| 18. SUPPLEMENTARY NOTES<br><br>NATIONAL TECHNICAL<br>INFORMATION SERVICE  |                       |   |  |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br>Helicopters                      Test Equipment:                      Container Handling<br>Heavy Lift Helicopters              Air Cargo Handling<br>Cargo Handling                      Hoist Systems<br>Cargo System Test Rig              Pneumatic Systems<br>Integrated Test Rig                  Suspension Systems  |                       |   |  |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br><br>This report formally documents the efforts and results of the cargo handling system segment of the Heavy Lift Helicopter (HLH) Advanced Technology Component (ATC) development program.<br><br>The purpose of the HLH/ATC was to minimize technical, cost and schedule risks associated with future HLH system research. |                       |   |  |

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

PRICES SUBJECT TO CHANGE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. Abstract (continued)

development, test and evaluation (RDTE) and production programs. This was achieved by design, fabrication, and testing of specific ATC hardware in three critical air vehicle subsystems:

- a. Rotor/Drive System
- b. Flight Control System
- c. Cargo Handling System

This report covers only the cargo handling system and consists of three volumes:

Volume I - Detail Design, Structural and Weights Analysis, and Static and Dynamic Load Analysis

Volume II - Fabrication of Test Hardware and Fixtures (Integrated Test Rig)

Volume III - Results of Tests, Inspections and Evaluations

Volume II contains the design criteria, physical description, stress analysis, fabrication and supporting data for the Integrated Test Rig which was used to conduct system testing of the full-scale cargo-handling ATC hardware.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

TABLE OF CONTENTS

|  | <u>Page</u> |
|--|-------------|
| LIST OF ILLUSTRATIONS . . . . .                          | v           |
| LIST OF TABLES. . . . .                                  | ix          |
| INTRODUCTION. . . . .                                    | 1           |
| GENERAL DESCRIPTION OF INTEGRATED TEST RIG. . . . .      | 2           |
| Major Elements of Test Fixture . . . . .                 | 2           |
| Full-Scale Static Simulation - HLH Installation. . . . . | 2           |
| Rig Location . . . . .                                   | 6           |
| DESIGN REQUIREMENTS AND CRITERIA. . . . .                | 6           |
| Hardware Compatibility . . . . .                         | 6           |
| Suspension and Hoist Span Arrangement. . . . .           | 6           |
| Design Loads . . . . .                                   | 7           |
| Failure Criteria . . . . .                               | 7           |
| Load Size and Access . . . . .                           | 9           |
| Load Lift. . . . .                                       | 9           |
| Hoisting Speed . . . . .                                 | 9           |
| Utilities and Communication. . . . .                     | 9           |
| Control Room . . . . .                                   | 10          |
| Safety Considerations. . . . .                           | 10          |
| Transportability Considerations. . . . .                 | 10          |
| Pneumatic Power Generator. . . . .                       | 10          |
| Data Requirements. . . . .                               | 10          |
| <u>DETAIL DESIGN</u> . . . . .                           | 10          |
| Design Considerations. . . . .                           | 10          |
| Configuration Description. . . . .                       | 12          |
| Material Design Criteria . . . . .                       | 13          |
| Trade-Offs/Cost Reduction. . . . .                       | 13          |
| Member Sizing. . . . .                                   | 13          |
| Tower Structures . . . . .                               | 14          |
| Overhead Structure . . . . .                             | 14          |
| Hoist Assembly Modules . . . . .                         | 15          |
| Control-Room Operator's Station. . . . .                 | 15          |
| Site Location and Foundation . . . . .                   | 17          |
| Stress Analysis. . . . .                                 | 17          |
| Utilities and Communication. . . . .                     | 17          |
| Pneumatic Power Generator. . . . .                       | 19          |
| Instrumentation. . . . .                                 | 22          |
| Design Layouts . . . . .                                 | 36          |

|   | <u>Page</u> |
|---|-------------|
| FABRICATION . . . . .   | 38          |
| Structure Prefabrication . . . . .  | 38          |
| Foundation . . . . .  | 38          |
| Hoist Module Installation. . . . .  | 56          |
| PPG and Air Supply Installation. . . . .                                      | 56          |
| Instrumentation Installations. . . . .  | 56          |
| Proof Loading. . . . .  | 70          |
| SPECIMEN INSTALLATION AND REMOVAL . . . . .                                   | 70          |
| USE OF THE INTEGRATED TEST RIG. . . . .                                       | 70          |
| CONCLUSIONS AND RECOMMENDATIONS . . . . .                                     | 72          |
| APPENDIXES:   |             |
| I Integrated Test Rig - Stress Analysis . . . . .                             | 79          |
| II Drawings - Design Layouts . . . . .  | 135         |
| III Pneumatic Power Generator - Starting and<br>Operating Procedure . . . . . | 187         |
| IV Instrumentation Calibration Procedure . . . . .                            | 190         |

LIST OF ILLUSTRATIONS

| <u>Figure</u> |  | <u>Page</u> |
|---------------|--|-------------|
| 1             | HLH Cargo Handling System Integrated Test Rig (ITR) Hoisting - 29-Ton Load . . . . . | 3           |
| 2             | Single-Point Mode - Hoist Installation in HLH .                                      | 4           |
| 3             | Dual-Point Mode - Hoist Installation in HLH . .                                      | 5           |
| 4             | Multi-Point and Single-Point Static Loading Schematic. . . . .                       | 8           |
| 5             | Test Rig, Showing Load-Controlling Crewman's View of Cargo. . . . .                  | 16          |
| 6             | Schematic - HLH/ATC Pneumatic Power Generator (PPG) and Generator Location . . . . . | 20          |
| 7             | PPG Gearing Arrangement. . . . .   | 21          |
| 8             | Instrumentation Rack Console ST30855-1 . . . .                                       | 27          |
| 9             | Cable Angle Sensor Mechanism . . . . .   | 30          |
| 10            | Cable Payout Sensor. . . . .   | 31          |
| 11            | Galvo Input Networks . . . . .   | 34          |
| 12            | Maximum Load Test Network. . . . .   | 37          |
| 13            | Excavation for ITR Foundation. . . . .   | 39          |
| 14            | Preparation of Footings and Foundation . . . .                                       | 40          |
| 15            | Three Ground Tiedown Points in Foundation. . .                                       | 41          |
| 16            | Rig Components and Raising of Lower Main Frames . . . . .                            | 42          |
| 17            | Complete Tower Frames Erection . . . . .   | 43          |
| 18            | Overhead and Stairway Installation . . . . .   | 44          |
| 19            | End View of Aft Tower. . . . .   | 45          |
| 20            | End View of Forward Tower. . . . .   | 46          |

| <u>Figure</u> |  | <u>Page</u> |
|---------------|--|-------------|
| 21            | Under View of Overhead Structure and Hoist<br>Module Location . . . . .      | 47          |
| 22            | Hoist Modules (Inverted). . . . .  | 48          |
| 23            | Control Room Area - Top of Forward Tower. . .                                | 49          |
| 24            | View of Overhead Section From LCC Position;<br>Forward Tower . . . . .       | 50          |
| 25            | Work Platform and Davit Looking Forward,<br>Control Room Location . . . . .  | 51          |
| 26            | Completed ITR Framework on Foundation . . . .                                | 52          |
| 27            | Control Room Enclosure Assembly . . . . .                                    | 53          |
| 28            | Aerial View of Complete Structure and Hot Air<br>Distribution Duct . . . . . | 54          |
| 29            | Hoist System Installed in ITR . . . . .                                      | 57          |
| 30            | PPG Pad at Aft Tower. . . . .  | 58          |
| 31            | Forward Hoist - Hoist and Signal Reel Air<br>Supply. . . . .                 | 59          |
| 32            | Insulated Air Header and Riser. . . . .                                      | 60          |
| 33            | Complete PPG Enclosure and Air Distribution<br>Line. . . . .                 | 61          |
| 34            | Side View of PPG. . . . .  | 62          |
| 35            | Three-Quarter View of Load Compressor and<br>Engine Inlet. . . . .           | 63          |
| 36            | Hoist Controls and Displays at LCC Station. .                                | 64          |
| 37            | Instrumentation, PPG and LCC Station. . . . .                                | 65          |
| 38            | PPG Control Console . . . . .  | 66          |
| 39            | Aft Hoist Drive and Instrumentation . . . . .                                | 67          |
| 40            | Instrumentation Attachment for Weighing<br>Ballasted MILVAN. . . . .         | 68          |
| 41            | Static Load Test Instrumentation. . . . .                                    | 69          |

| <u>Figure</u> |   | <u>Page</u> |
|---------------|---|-------------|
| 42            | Hoist System Test Installation . . . . .  | 71          |
| 43            | Control Room During Test . . . . .  | 73          |
| 44            | LCC View - Hoist and Couplings . . . . .  | 74          |
| 45            | LCC View of Two Individual Loads Near Top of<br>Lift Cycle . . . . .                        | 75          |
| 46            | 29-Ton Multi-Point Test. MILVAN With Con-<br>tainer Handling Device During 50-Foot Lift . . | 76          |
| 47            | Lifting a 29-Ton Load With Single-Point<br>Adapter - Hoist Span Was 16 Feet . . . . .       | 77          |
| 48            | Unloading MILVAN Through Base of Aft Tower . .  | 78          |
| 49            | Structures Installation- HLH Hoist Test. . . .  | 137         |
| 50            | HLH Hoist Tower Assembly . . . . .  | 139         |
| 51            | HLH Overhead Assembly . . . . .   | 145         |
| 52            | Site Plan - Paving and Utilities, Plan<br>and Sections . . . . .                            | 149         |
| 53            | Foundations - Plans, Sections and Details. . .  | 151         |
| 54            | Pneumatic Power Generator Shelter HLH/ATC<br>Cargo Handling System . . . . .                | 153         |
| 55            | Control Room Plans, Elevations and Section . .  | 155         |
| 56            | Control Room Section and Details . . . . .  | 157         |
| 57            | Removable Handrail Details . . . . .  | 159         |
| 58            | Piping Arrangement, Test Tower Top Section . .  | 161         |
| 59            | Piping Arrangement, Test Tower Base . . . . .   | 163         |
| 60            | Fuel Piping Arrangement - PPG Unit . . . . .  | 165         |
| 61            | Electrical Single Line Diagram . . . . .  | 167         |
| 62            | Electrical HLH/ATC Cargo Handling Test Rig . .  | 169         |
| 63            | Control Room Electrical Layout . . . . .  | 171         |



| <u>Figure</u> |   | <u>Page</u> |
|---------------|---|-------------|
| 64            | Load-Controlling Crewman Platform - Integrated Test Rig . . . . . | 173         |
| 65            | System Test - Drawing Tree . . . . .                              | 175         |
| 66            | Lifting Sling, Hoist/Module . . . . .                             | 177         |
| 67            | Hoist Lifting Fixture . . . . .                                   | 179         |
| 68            | Integrated Test Rig - System Wiring . . . . .                     | 183         |
| 69            | Instrumentation Drawing Tree . . . . .                            | 185         |

LIST OF TABLES

| <u>Table</u>   | <u>Page</u> |
|--|-------------|
| I ITR - Test Data and Instrumentation Requirements . . . . .                       | 11          |
| II Component Listing, Instrumentation System - HLH Cargo Handling System . . . . . | 23          |
| III ITR Instrumentation System - Recorded Data Format. . . . .                     | 28          |
| IV ATM Shaft Speed Related to Cable Payout Speed by System Gearing . . . . .       | 33          |
| V Integrated Test Rig Weight Breakdown. . . . .                                    | 55          |
| VI Tower Assembly - Fore-Aft Frame Loads (KIPS). . . . .                           | 107         |
| VII Tower Assembly - Inboard/Outboard Frame . . . . .                              | 116         |
| VIII Reaction Loads - 70-Ton Failure Condition . . . . .                           | 130         |
| IX Reaction Loads - 70-Ton Failure Condition . . . . .                             | 130         |
| X Reaction Loads - Impact of Load Container on Tower . . . . .                     | 131         |
| XI Deadweights . . . . .   | 132         |
| XII Normal PPG Operating Limits . . . . .  | 189         |

## INTRODUCTION

Final design ATC hardware was based on subsystem design development testing. Verification of the cargo handling system ATC design goals, accomplished in advance of an aircraft installation, required a test fixture with which system performance could be demonstrated.

Since no suitable evaluation fixture existed, the ATC program included preparation of such a fixture. This fixture, the integrated test rig (ITR), was designed to permit: operation of the ATC developed hardware through all its functions; verification of performance and reliability characteristics, failure modes and effects, and maintenance characteristics; demonstration of 1800 hoisting cycles using both suspension modes at design load and speed and demonstration of maximum static load.

Although the ITR was erected on Boeing Vertol property, its design provided for dismantlement and reerection at another site. To support use at another location, appendixes to this document include foundation loads, descriptive drawings, air supply operating instructions, and an instrumentation calibration procedure.

## GENERAL DESCRIPTION OF INTEGRATED TEST RIG (ITR)

### MAJOR ELEMENTS OF TEST FIXTURE

The integrated test rig is shown in Figure 1. It consists of two steel I-beam towers, 14x14 feet square, supporting a pair of horizontal internally braced 30-inch-deep wide-flange I-beams with a 40-foot span and a 70-foot vertical clearance. Lateral outriggers buttress the towers.

The major elements of the ITR are:

1. Main structure consisting of towers and overhead section.
2. Footings and foundation with provisions for three ground tiedown points ("dead men").
3. Pneumatic power generation (hoist drive air supply) including fuel supply.
4. Utility power and communication.
5. Control room and enclosure.
6. Instrumentation and data recording system.
7. Stairway to control room and work platform.
8. Provisions for utility hoist.
9. Site improvements including access roads.

### FULL-SCALE STATIC SIMULATION - HLH INSTALLATION

The test rig simulates a full-scale installation of the cargo handling system (CHS) in the Heavy Lift Helicopter (HLH), Figures 2 and 3, in the following respects:

1. Two steel frames simulate the a/c mounting structure for the hoists and signal conductor reels. These are removable to permit complete ground buildup of individual hoists and associated assemblies including the wiring to form a "hoist module". The assembled "modules" are raised with the overhead utility hoist and installed between the main overhead and auxiliary horizontal I-beams. Each hoist module also mounts the span positioning equipment and has space provisions for hoist separations of 16, 22 and 26 feet.




Figure 1. HLI Cargo Handling System Integrated Test Rig  
Hoisting - 29-Ton Load.




Figure 2. Single-Point Mode - Hoist Installation in HLH.




Figure 3. Dual-Point Mode - Hoist Installation in HLH.

2. Power, control, geometry and physical spacing of hoist assemblies.
3. Fuselage level attitude.
4. Relative location, type of hoist controls and displays, and layout of the rear-facing, load-controlling-crewman (LCC) station.
5. A 50-foot cable deployment with full-scale, rigged loads.

#### RIG LOCATION

The ITR is located at the Boeing Vertol Company facility, Ridley Park, Pennsylvania.

#### DESIGN REQUIREMENTS AND CRITERIA

##### HARDWARE COMPATIBILITY

The test rig design shall be compatible with the following full-scale cargo handling system hardware to be installed and operated in the test rig:

- Hoist and tension member assembly
- Hoist drive unit
- Load isolators
- Span positioning system
- Signal conductor reels
- Controls and displays systems
- Coupling
- Single-point adapters
- Cable cutters
- Pneumatic distribution system

and the following GFE (non-CHS) auxiliary equipment:

- 8' x 8' x 20' MILVAN
- Container handling device

##### SUSPENSION AND HOIST SPAN ARRANGEMENT

Both single-point and two-point suspension arrangements shall be provided. Hoist span positioning space and functional provisions shall be incorporated for both 16- and 26-foot suspension spans.



## DESIGN LOADS

### Steady Vertical Loads

The individual hoists must support vertical loads and accommodate a 60/40 load split based on the two-point suspension. The loads to be supported are:

|  |             |
|--|-------------|
| System design operating load                   | = 28.0 tons |
| Hoist design operating load (28x0.6)           | = 16.8 tons |
| System maximum static load (28x2.5g)           | = 70.0 tons |
| Hoist maximum static load (28x2.5gx0.6)        | = 42.0 tons |
| Failure case (single hoist, any span position) | = 70.0 tons |

### Transient Vertical Loads

Some transient vertical loads may be encountered under differential hoisting (load levelling). The normal load tilt (multipoint mode) will not exceed  $\pm 15^\circ$ . Load release transients are insignificant (loads above 1,000 lb cannot be released).

### Side, Overturning, and End Loads

The hoists are "single-point payout"; therefore, tension member loads shall always act through the longitudinal (fore-aft) centerline of the test rig. No side, end, or overturning loads are anticipated due to testing except as may be encountered from load swinging ( $+5^\circ$ , est.) or wind. Load motion shall not result in the loads striking the rig structure.


### Maximum Static Load Provisions

Tiedown provisions in the ITR foundation are required for application of the maximum design static load to either individual or both hoists as shown in Figure 4.

The loading member, ring or bar, with a maximum 2-1/2 inch diameter, is to be compatible with CHS coupling. Space must be provided for coupling attachment/release.

## FAILURE CRITERIA

Failure simulation involving severe load transients or high load release tests was not a requirement of the ATC program.



LOAD CAPACITIES:  $M_1, M_2 = 42$  Tons  
 SP = 70 Tons

Figure 4. Multi-Point and Single-Point Static Loading Schematic.

Rig survival - no collapse - was provided in the design in the event of a sling or other failure under maximum static load. The vertical columns are the main support for the control room and are independent of the column struts in case of strut removal by impact of the test load (due to a suspension failure).

#### LOAD SIZE AND ACCESS

The standard test load size is an 8' x 8' x 20' container. A 40-foot clear span between overhead supports is required to provide vehicular clearance around the load for load placement and removal. Direct access is required along the fore-aft centerline and between the supports and superstructure of one tower to accommodate a MILVAN on a flatbed trailer.

#### LOAD LIFT

The test rig is to have a clear height of 70 feet.

#### HOISTING SPEED

Design hoisting and lowering speed (with load) is 60 fpm. Design payout speed (without load) is 120 fpm.

#### UTILITIES AND COMMUNICATION

The following provisions shall be made for utilities:

1. Equipment hoist - 6,000 lb capacity
2. Intercom - LCC station to ground and test areas
3. Storage area
4. Cooling water for PPG heat exchanger
5. Work platforms around hoists
6. Lightning protection
7. Aircraft warning signals
8. Weather protection for cargo system and PPG
9. Electrical requirements for the cargo system, pneumatic power generator, related instrumentation, general utility and equipment hoist, and the cargo handling device shall be as follows:

|             |                                |
|-------------|--------------------------------|
| 28V DC      | Direct current                 |
| 5V AC       | Single-phase, 400 Hz           |
| 26V AC      | Single-phase, 400 Hz           |
| 115V AC     | Single-phase, 60 Hz, regulated |
| 120/208V AC | Three-phase, 60 Hz             |
| 120/280V AC | Three-phase, 400 Hz            |

Compliance with MIL-STD-704 is required.

## CONTROL ROOM

The control room shall house the LCC station, with a full view of the cargo in the ground and hoisted positions, the controls for the PPG and all related instrumentation. The floor loading criteria of 125-150 psf (light industrial) shall be used.

## SAFETY CONSIDERATIONS

In addition to ITR failure criteria, the structure and location of operating equipment and utilities shall meet OSHA\* requirements. The personnel stairway shall be remote from the test load.

\*Williams - Stieger Industrial Safety, Oct. 1970.

## TRANSPORTABILITY CONSIDERATIONS

The rig design shall incorporate provisions for dismantlement and reerection at another site.

## PNEUMATIC POWER GENERATOR

A pneumatic power generator (PPG), located at ground level, and air distribution system shall be used to supply air to the hoists at a pressure ratio of 4.3 and a temperature of 450°F. Operating controls, pressure regulation and safety devices are required.

## DATA REQUIREMENTS

Recordings are to be made of the following parameters (as delineated in Table I):

- Ambient conditions - temperature and pressure
- Supply air - temperature and pressure
- Air turbine operation - temperature, pressure and speed
- Control inputs and functions
- Tension member - load, angle, payout length
- Cargo system noise

## DETAIL DESIGN

### DESIGN CONSIDERATIONS

Selection of the ITR configuration was based on the following design considerations:

1. Control room requirement
  - Access to hoist test location
  - Simulation of HLH LCC station
  - Drinking water, but no lavatory or toilet facilities

TABLE I. ITR - TEST DATA AND INSTRUMENTATION REQUIREMENTS.

| Data Requested                     | Unit        | Max. Range      | Reqd. Accuracy | No. of Transducers | Oscil Monitor | Visual Scope | W.R. FM. |
|------------------------------------|-------------|-----------------|----------------|--------------------|---------------|--------------|----------|
| <u>PNEUMATIC POWER GENERATOR</u>   |             |                 |                |                    |               |              |          |
| Supply Air Temp.                   | °F          | 0-500           | ±1%            | 1                  | X             |              |          |
| Supply Air Pressure                | PSIA        | 0-60            | ±1%            | 1                  | X             |              |          |
| <u>HOIST DRIVE</u>                 |             |                 |                |                    |               |              |          |
| Turbine Inlet Pressure             | PSIG        | 0-50            | +1%            | 4                  | X             |              |          |
| Turbine Inlet Temp.                | °F          | 32-500          | +1%            | 4                  | X             |              |          |
| Turbine Exhaust Temp.              | °F          | 32-500          | +1%            | 2                  | X             |              |          |
| Turbine Motor RPM                  | +VDC        | 5               | +2%            | 1                  | X             |              |          |
| <u>HOIST CABLE DATA</u>            |             |                 |                |                    |               |              |          |
| Cable Tension                      | lb          | 0-30000         | .1%            | 4                  |               | X            |          |
| Cable Angle-Longitudinal           | DEG         | 30° Fwd/40° Aft | .1%            | 2                  |               | X            |          |
| Cable Angle-Lateral                | DEG         | 30              | .1%            | 2                  |               | X            |          |
| Cable Payout                       | FT          | 100             | +2%            | 2                  |               | X            |          |
| Hoist RPM (Load Velocity)          | RPM         | 25              | +2%            | 2                  |               | X            |          |
| <u>CABLE LENGTH INDICATOR</u>      |             |                 |                |                    |               |              |          |
| Hoist Position (Fwd)               | FWD/MID/AFT | N/A             |                | 0                  |               | X            |          |
| Hoist Position (Aft)               | FWD/MID/AFT | N/A             |                | 0                  |               | X            |          |
| <u>HOIST CONTROL</u>               |             |                 |                |                    |               |              |          |
| Command Velocity                   | +VDC        | 5               | +2%            | 2                  | X             |              |          |
| <u>CARGO COUPLING</u>              |             |                 |                |                    |               |              |          |
| Mech. Release Signal               | +VDC        | 28              | +2%            | 2                  |               | X            |          |
| <u>NEAR- &amp; FAR-FIELD NOISE</u> |             |                 |                |                    |               |              |          |
|                                    | db          | 140             |                | 1                  |               |              | X        |
| <u>WIND VELOCITY</u>               |             |                 |                |                    |               |              |          |
|                                    | MPH         | 60              |                | 1                  |               | X            |          |
| <u>AMBIENT AIR TEMPERATURE</u>     |             |                 |                |                    |               |              |          |
|                                    | °C          | -10+40          |                | 1                  |               | X            |          |

2. Span/overhead structure

Vehicle clearance for manipulating load  
Variable cargo hoist span  
Center mount for davit

3. Safety

OSHA standards  
Stairway remote from test load - single egress  
location

4. Outriggers

Wind loading requirement  
Access to test load through base of tower

5. Transportability

Possible use of ITR at another site required  
inclusion of splices and bolted joints at significant  
locations

6. Footings and foundation

Detail design based on known local rock formations  
determined by site borings.

CONFIGURATION DESCRIPTION

Because of height requirements of the towers and the relative low design loads, a trussed frame configuration was selected. Requirements for a control room made the selections of a 14-foot-square tower desirable. Easy installation of stairways on this type of tower was also a factor in the selection. Outriggers were used on each leg of the tower in the inboard-outboard plane for two reasons:

1. Wind loading, and
2. Need to remove secondary **bracing** in lower portions of tower to permit a loaded truck to drive through the tower.

Outriggers in the fore-aft plane were not required because the criteria used were not factors in this plane. Also, horizontal components of test loads are reacted by four frames in the fore-aft plane, while in the inboard-outboard direction only the two inner frames will react the horizontal component of loading.

Highlights of the ITR design including layouts of the test fixture and equipment are discussed in the following text.

## MATERIAL DESIGN CRITERIA

### Structure

Structural steel - Commercial A36 (AISC Specification)

Allowable 22,000 psi  
Yield 36,000 psi  
Ultimate 60,000 psi

Welding practice - AISC

Bolts - ASTM A325

Design loads - per requirement section.

Environmental factors - Wind - 30 psf (loaded)  
50 psf (unloaded)  
Snow - NE local standard

Safety factor - 1.5 (on maximum/failure load using material allowable.)

### Footings and Foundation

Concrete - 3,000 psi compressive strength at 28 days - reinforced, continuous pour

Reinforcing steel - per ASTM A61

Anchor bolts - ASTM Spec A325

Footings - 3,000 psi concrete on bedrock

Anchor beams - to mate with Crosby-Laughlin round pin shackles

## TRADE-OFFS/COST REDUCTION

An alternative A-frame configuration for the structure was considered. It was rejected in favor of the selected design since higher column stiffness requirements would have resulted in a heavier design. Also, bolted and riveted construction was eliminated as more costly than the welded design used. Use of a 60-foot span to accommodate a 40-foot load length was also considered. This option was not implemented due to an estimated cost increase of approximately 20%.

## MEMBER SIZING

|                                 | <u>Size</u> | <u>Type</u> | <u>Lb/Ft</u> |
|---------------------------------|-------------|-------------|--------------|
| Main beams                      | 30x14       | WF          | 172          |
| Main vertical supports (towers) | 8x8         | WF          | 40           |
| Tower bracing                   | (2) 4x3-1/2 | Angles      | 9.1          |

## TOWER STRUCTURES

### Transportability

To facilitate disassembly and reerection, each of the tower columns included splices which consisted of a combination of welding and bolting at the joints, bolted connections at each of the four diagonal struts in the adjacent bay, and bolted joints at the outrigger struts.

Using this construction configuration, each tower could be dismantled into two discrete sections and the supporting outriggers could be disassembled for shipping without the necessity for welding cuts.

### Stairways

Stairways were enclosed by 42-inch guardrails on both sides with a 32-inch handrail being incorporated on the inside guardrail. The handrail was located 3 inches into the 30-inch stairway.

The stairway was located entirely outside the outboard tower columns for safety considerations. This removed it as far as possible from the test load in the event of any failure in the suspension system.

### Utility Connection to Tower Column

An outboard column was used as the terminating point for the utility connection from an adjacent building. The connection was made between the 28-foot and 42-foot levels with an attachment force of approximately 1,000 lb.

### Warning Beacons

Beacon type lights normally required atop the structure for the protection of low-flying aircraft were not required for the site selected because of higher structures in the adjacent area.

## OVERHEAD STRUCTURE

### Overhead Beam Location Holes

The tower/beam assembly was predrilled to simplify assembly. The tower/beam holes are close fitting. The hoist module attachment was also predrilled.

Slots were not provided for temperature changes as estimated changes were small.



Camber was not specified in the overhead beams, since only 0.7 inch beam deflection was anticipated at the 70-ton static load.

#### Work Platform

Grip strut, an expanded-metal, nonslip surface, was used for the open work platforms around the hoists. A uniform floor loading of 235 psf was used.

#### Davit Assembly

The davit assembly or jib crane reach was 12 feet. It had a 6,000-lb hoisting capability. This satisfied the need for lifting the hoist modules and other equipment from the ground, over the side, or through the hoist location to the overhead structure.

The hoist cable reach was 89 feet. Maximum hoisting rate was 40 fpm. Guardrails surrounding the hoist module locations had sections which were removable for hoist installation and removal by the over-the-side method.

#### HOIST ASSEMBLY MODULES

The hoist module consisted of a simple welded framework and lift points including the hoist main support fittings and hoist positioning tracks. The function of the module was to facilitate preinstallation and checkout of each hoist assembly on the ground (similar to engine quick prep-packages). The module weight was minimized to keep the davit and utility hoist size down. Web material was 1-inch and flanges were .75-inch plate.

Each hoist was removable from its module. Both modules were identical and provided a hoist span positioning travel of 60 inches.

#### Hoist Shelters

A portable shelter (tarpaulin) was provided for each hoist test location. Each section was removable during hoist testing.

#### CONTROL-ROOM OPERATOR'S STATION

The control-room operator's station eye level duplicated the HLH LCC position as shown on Figure 5.

The control room floor area was approximately 130 sq ft. A solid, precast-concrete, nonslip floor was used with a design




Figure 5. Test Rig, Showing Load-Controlling Crewman's View of Cargo.

floor loading of 172 psf.

LCC load viewing windows, looking aft and downward, were constructed of high-impact-strength polycarbonate (Lexan). A removable protective bar was installed across the main window. Side observation windows were of thermopane.

Except for doors and windows, the enclosure was fully insulated. Heat was furnished by a 3-kw thermostatically controlled space unit. A 5,000-Btu window-mounting airconditioner was provided for summer operation.

#### SITE LOCATION AND FOUNDATION

The test rig site location was selected to make maximum use of local rock foundations. To minimize service roads, the test rig was oriented adjacent to existing roadways.

The service road included a "Y" with one branch through the base of one tower and the other parallel to the overhead structure for truck pickup or deposit of a load within the reach of the jib crane.

The service road also provided for servicing of the fuel tank located 100 feet from the PPG unit.

Underground static load points in the concrete surface between the towers, along the hoist centerline, provided a 70-ton loading capability at the center point and 42 tons at each of the multi-point loading points. Slots were provided for entry of the cargo hooks, and covers were used to allow the surface traffic over these points.

The working surface around the test rig was asphalt covered, for vehicular traffic and surface drainage.

#### STRESS ANALYSIS

A stress analysis was performed to substantiate the design strength of the towers and overhead structure, using a Boeing Watfor "plain frame" computer program. An analysis of the hoist module frames and foundation reaction loads was also made. Analysis details are provided as Appendix I.

#### UTILITIES AND COMMUNICATION

Primary electrical service to the ITR was 277/480 volts AC 3Ø 60 Hz supplied from an adjacent building bus via a utility pole. Four distribution panels were provided in the control room: 480-volt, lighting, regulated-power, and 28-VDC.

Raceways and conduit were provided between the control room, the work platform and the PPG location.

Specific power requirements were serviced from the following sources:

115-Volt Regulator - Stabiline EMT 4115

15 KVA  
Input: 95-135V  
Output: 115V 50/60 cy. 1Ø  
110-120V adjustable  
Long-range amps: 130.0

400-Hz Electronic Inverter - Sorensen FCD 3P1000

1000 VA - 3 Ø  
Input: 208/230V 48 to 65 cy 3 Ø  
Output volts: +10% 115/200V  
3 Ø 4 wire  
115V L-L 3 Ø 3 wire  
Output volt reg: +1%  
Output freq.: 360-440 cy +1%  
Load range: 0-1000 VA  
Distortion unity PF load: (360-400 CPS) 3%

28VDC - Instrumentation

Solid-state power supply - Sorensen MA28-125

Output:

| <u>Volts</u><br><u>(DC)</u> | <u>Current</u><br><u>(AMPS)</u> | <u>Reg.</u> | <u>Metered</u> |
|-----------------------------|---------------------------------|-------------|----------------|
| 18-36                       | 0-125                           | .2%         | Yes            |

28VDC - PPG Starting System

4-12VDC heavy duty truck batteries

Communication provisions included:

1. Telephone linking the control room, plant switch-board and base of tower.
2. Powered intercom system including four headsets, two keyed and two noise-cancelling microphones, and five interconnect boxes.

## PNEUMATIC POWER GENERATOR (PPG)

Four possible PPG locations were considered: two on the overhead structure and two on the ground level. The two locations at the top of the structure were eliminated due to the additional structure required. In comparing the ground locations - the bay below the control room and the ground bay of the opposite tower - the latter was selected for the following reasons:

1. Elimination of:
  - a. fire hazard in vicinity of stairway for operating personnel.
  - b. the need for a fireproof structure around the air supply unit and special ducting, and
  - c. the need for an alternate stairway or secondary means of egress.
2. Simplification of PPG fuel system.
3. Ease of servicing and isolation from personnel.
4. Provision of direct view of PPG from upper-level control room during operation.

The pneumatic power generator unit (air supply) was self-contained and consisted of the following components described in the system schematic, Figure 6:

1. 250-C20 Allison engine rated @ 294 HP at sea level 95°F, serving as a power unit. Additional components include a starter/generator, voltage regulator, 24VDC battery pack, fuel boost pump, oil reservoir, and oil/water heat exchanger.
2. A T-63 compressor with a modified T-63 gearbox.
3. An interface gearbox (step-up) and power transfer shaft as shown in the overall gearing arrangement, Figure 7.
4. A surge control valve designed to prevent compressor surge under all operating ambients from zero to maximum capacity of the compressor. The valve was controlled by a vacuum switch located in the compressor inlet bell mouth.
5. A pressure controller compatible with the cargo system pneumatic power distribution system. This valve was controlled by pressure sensed in the header upstream of the hoists.




Figure 6. Schematic - HLH/ATC Pneumatic Power Generator (PPG) and Generator Location.




Figure 7. PPG Gearing Arrangement.

6. PPG control panel located adjacent to the LCC station, which included engine/compressor gearbox speeds, temperature and pressure instrumentation, fuel and battery charger controls, and emergency shutdown devices.
7. A 275-gallon fuel tank with manual and emergency valving with spark-arresting provision.
8. Approximate pressure gages and gearbox chip warning sensors and 150-foot control cable.

#### Air Distribution System

The air distribution system, constructed of Schedule 5 304 stainless steel, was rated for 60 psi at 543°F. The system consisted of:

- |    |               |   |
|----|---------------|---|
| 1. | Main riser    | 6-inch I D  |
| 2. | Main header   | 6-inch, upstream of both hoists                               |
| 3. | Supply risers | 3-inch, feeder between hoists                                 |
| 4. | Insulation    | 2-1/2-inch flexible ducts                                     |
|    |               | 3-1/2-inch, with weatherproofed aluminum jacket               |
| 5. | Dump valve    | 2-1/2 globe, manually operated (for start and warmup control) |
| 6. | Drain valve   | for removal of line condensation.                             |

A total pressure pickup and a thermocouple (I/C junction) were included in the 6-inch header to measure air supply conditions.

#### INSTRUMENTATION

The ITR instrumentation system was specifically designed to record and display the parameters necessary to evaluate the function and performance of the HLH cargo handling system. The parameters recorded and displayed were in addition to the load-controlling crewman station monitoring equipment.

An instrumentation console located in the ITR control room contained the equipment necessary to monitor and record the temperatures, pressures, isolator loads, cable angles and other auxiliary signals.

A listing of the instrumentation equipment used is shown in Table II. For wiring and other detail, refer to the Instrumentation Family Tree ST30861 listed under Design Layouts and shown in Appendix II.



TABLE II. COMPONENT LISTING, INSTRUMENTATION SYSTEM - HLH CARGO HANDLING SYSTEM.

| Equipment  | Model   | Characteristics   | Function   | Warning | Comments  |
|--|---------|---|--|---------|---|
| Temp. Indicator,<br>Love Controls (7ea)            | 100-818 | Range 0-600 Deg<br>T/C Type "J" (I/C)<br>Accuracy $\pm 1\%$ of<br>scale Recorder<br>output 0-1V         | Indicates exhaust<br>temp; supply air<br>temp & hoisting &<br>rev. valve temp. | No      | Auxiliary output<br>used to drive<br>recording galvo.   |
| Temp. Indicator<br>Love Controls (1ea)             | Same    | Same  | Indicates ATM<br>temp. for operator<br>monitoring                              | No      | Operates thru<br>selector switch for<br>ATM temp.   |
| Temp. Selector<br>Switch Thermo-<br>Electric (1ea) | 33112   | No. channels-12   | Switches ATM T/C<br>inputs   | -       | -   |
| Temp. Probe;<br>Thermo-Elec. (1ea)                 | 5J2120L | Accuracy $\pm 0.5^\circ$<br>Probe Length 6"<br>Type Iron-<br>Constantan                                 | Temp transducer<br>for temp indicators   | -       | -   |
| Pressure Ind.<br>Dynisco (5ea)                     | ER466A2 | Range 0-100 PSI<br>Accuracy $\pm 1\%$<br>full scale<br>Response time<br>1.5 sec Aux.<br>output 0-1 Volt | Indicates supply<br>air, hoisting &<br>rev. air pressures                      | Yes     | Auxiliary output<br>used to drive<br>recording galvo,<br>conditions & ampli-<br>fies pressure<br>transducer signal. |
| Pressure<br>Transducer (5ea)                       | 103     | Range 0-75 PSI,<br>112.5 PSIA Max.  | Press. transducer<br>for press. indicators                                     | -       | -   |
| Load Isolator<br>panel                             | ST30869 | Range 0-100KIP<br>Accuracy $\pm 0.1\%$<br>of input  | Indicates compres-<br>sion load in each<br>of four load iso-<br>lators         | No      | Receives load<br>signal & ref. from<br>cable tension &<br>angle interface<br>electronics                            |

TABLE II. CONTINUED.

| Equipment                             | Model   | Characteristics   | Function  | Warning | Comments                                       |
|---------------------------------------|---------|---|---|---------|--|
| Cable Angle Ref. Panel                | ST30873 | Range 0-100 Deg. Accuracy $\pm 0.1^\circ$                                 | Indicates angle of four-hook cables   | No      | Same as above                                  |
| Closed-Circuit TV System Hitachi Ltd. | ST30852 | Range-50 yards Field of view 3ft x 3ft                                    | Used to observe moving parts on cargo handling modules & container position | No      | —  |
| Intercom System                       | ST30859 | No. of stations-4 Type-Headset with mike                                  | Used for communication between the operator & crewmen                       | —       | —  |
| Oscillograph Recorder CEC (3ea)       | 5-124   | No. channels-18 Speeds 0.25, 1, 4, 16, 64 IPS                             | Used as graphic recording devices   | No      | —  |
| Pressure Probe United Sensor          | PTC12   | Adjustable immersion length Max. operating temp-1600°F Same as above      | Static pressure transmitter   | No      | —  |
| Galvo CEC (21ea)                      | PTC8    | Same as above   | Total pressure transmitter  | No      | See dwg. ST30854A for recorder parameter info. |
| Galvo CEC (21ea)                      | 7-315   | Frequency response 0-60 Hz (+2%) Sensitivity 12.2 UA/IN Impedance 26 Ohms | (Used as transducers for graphic recording oscillograph)                    | No      | See dwg. ST30854A for recorder parameter info. |
| Galvo CEC (2ea)                       | 7-319   | Frequency response 0-350 Hz (+2%) Sensitivity 426 UA/IN Impedance 26 Ohms | Same as above   | —       | Same as above                                  |

TABLE II. CONCLUDED.

| Equipment  | Model        | Characteristics   | Function                                   | Warning | Comments  |
|--|--------------|---|--|---------|---|
| Galvo CEC (7ea)                                  | 7-351        | Frequency response 0-12 Hz (+2%) Sensitivity 2.66 UA/IN Impedance 33 Ohms | Same as above                              | -       | Used to record outputs of temp. indicators-see ST30854A.        |
| Oscillator H-P (1ea)                             | 200CDR       | Range 0-600 kHz Output 0-40 Volts   | Used as time event marker source           | -       | -   |
| Amplifier Burr-Brown (6ea)                       | 2088/16      | Frequency range 0-10 kHz Gain ADJ 1-1000 CMR ADJ 40-140 DR                | Used as buffer amplifier-see ST30860       | No      | -   |
| D.C. Null Meter H-P                              | 413A/R       | Range 1mV-1000 V Accuracy $\pm 0.1\%$ of input                            | Used as an auxiliary monitor               | No      | -   |
| Power Supply Kepco                               | ABC 10.C.75M | Range 0-10V 0-0.75A   | Used as a calibration voltage source       | No      | -   |
| Load Cell Bud (2ea)                              | T3P2B        | Range 0-50K lb Sens 3mV/V   | Used to measure hook load                  | No      | -   |
| Meter Panel Simpson                              | -            | Range 0-50mA Accuracy $\pm 1\%$   | Used to indicate cable speed               | No      | Receives cable length signals from hoist interface electronics. |
| Anemometer-Taylor Instrument Co. Rochester, N.Y. | -            | Dual range-zero adjust 0-25 mph 0-100 mph                                 | Used to indicate wind velocity & direction | No      | -   |

The instrumentation system was configured, as shown on Figure 8, in a two-bay console designated rack "A" and rack "B". Rack "A" included the equipment to monitor and record hoisting and reversing air turbine motor (ATM) temperatures, exhaust temperatures, main supply air temperature, hoisting and reversing air pressures, supply pressure, isolator loads, and cable angles. The recording oscillograph, closed-circuit television (CCTV) system switch panel, +15 volt power supply, event oscillator, and intercom station were also located in rack "A". The CCTV monitor, DC null voltmeter, hoist control unit, hoist interface electronics, cable tension and length interface electronics, recording oscillograph and buffer amplifiers were located in rack "B". The data recording format is shown in Table III. Additional equipment added to the system included a recording oscillograph "C" used for recording cable tensions, two null panel meters for observing cable payout speed, an oscillograph control box with event button, a brake release counter, eight chip detectors, and a 12-channel temperature panel with selector switch. During initial checkout, supply pressure and antisurge valve characteristics were investigated. An x-y plotter, B&F conditioner with amplifier, and a dekabox were used to plot supply pressure.

#### Temperature Instrumentation

Temperature probes were inserted into the air ducts of each hoist drive unit to measure the turbine inlet, exhaust and supply air temperatures. They acted as transducers for the seven temperature indicators in the instrumentation system.

Evaluation of the hoist duty cycle required monitoring of the surface temperatures of the hoist main bevel gear casing, the secondary forward and aft bevel gear casings, the hoist brake casing, the ATM oil pressure line, and the ATM oil return line of each hoisting module. Silver-soldered T/C junctions were attached to each of the six surfaces with Caulk grip cement (dental cement) and routed to a 12-channel T/C selector switch via a six-lead thermocouple cable. The selected channel temperature was displayed on a separate indicator. The selector switch and temperature indicator were located on a panel which was positioned in front of the hoist operator.

#### Pressure Instrumentation

Pressure probes were inserted into the air duct at the same location as the temperature thermocouples in the ATM inlet and were connected by flexible tubing to the pressure transducers.




Figure 8. Instrumentation Rack Console ST30855-1.

TABLE III. ITR INSTRUMENTATION SYSTEM - RECORDED DATA FORMAT.

| Recorder A |                       | Recorder B |                        | Recorder C            |
|------------|-----------------------|------------|------------------------|-----------------------|
| Chnl.      | Measurement Parameter | Chnl.      | Measurement Parameter  | Chnl.                 |
| 1          | T1-Fwd,hoisting, °F   | 1          | P2-Fwd,hoisting,psig   | <u>Load Isolators</u> |
| 2          | Time/event            | 2          | P4-Aft,hoisting,psig   | 1 Fwd hoist, fwd      |
| 3          | T2-Fwd,reverse, °F    | 3          | A1-Fwd,turbine speed   | 2 Fwd hoist, aft      |
| 4          | T3-Aft,hoisting, °F   | 4          | -- Blank               | 3 Aft hoist, fwd      |
| 5          | T4-Aft,reverse, °F    | 5          | A2-Fwd,cable payout    | 4 Aft hoist, aft      |
| 6          | T5-rwd,exhaust, °F    | 6          | A5-Aft,turbine speed   | 5 Load cell           |
| 7          | -- Blank              | 7          | -- Blank               | 6 Time/event          |
| 8          | T6-Supply air, °F     | 8          | A6-Aft,cable payout    |                       |
| 9          | T7-Aft,exhaust, °F    | 9          | -- Blank               |                       |
| 10         | P1-Supply air,psia    | 10         | Fwd,speed command      |                       |
| 11         | P5-Aft,reverse,psig   | 11         | A7-Aft,H,Mod.Valv.amps |                       |
| 12         | Aft,torque sw.        | 12         | Aft,speed command      |                       |
| 13         | Aft,brake sw.         | 13         | -- Blank               |                       |
| 14         | P3-Fwd,reverse,psig   | 14         | A3-Fwd,H,Mod.Valv.amps |                       |
| 15         | -- Blank              | 15         | -- Blank               |                       |
| 16         | Fwd,torque sw.        | 16         | -- Blank               |                       |
| 17         | Fwd,brake sw.         | 17         | Sync.Signal            |                       |
| 18         | -- Blank              | 18         | Time/event             |                       |

### Load Isolator Instrumentation (Cable Tension)

A load cell for axial load sensing was an integral part of each load isolator. The output from the 350-ohm strain gage bridge on the cell was amplified and conditioned by the hoist cable tension and cable length interface electronics.

### Cable Tension and Load Instrumentation

The load isolator reference panel located in rack "A" had a five-position rotary selector switch, four calibration adjustment potentiometers and a three-place digital panel meter which displayed the selected axial load.

An auxiliary method of measuring cable tension was employed using two load cells in series with each coupling and a BLH universal percentage indicator.

### Cable Angle Instrumentation

The cable angle sensing mechanism employed two linear transformers (see Figure 9) which produced electrical signals proportional to the longitudinal and/or lateral angles that the cable made with the vertical centerline of the hoist.

The cable angle reference panel had a five-position selector switch, four angle adjustment potentiometer, and a digital panel meter for readout.

### Cable Payout Instrumentation

The cable length sensing mechanism (see Figure 10) employed a linear transformer whose electrical output signal was a function of the number of turns of the cable drum from the cable up (stow) position.

Two cable length signals, one for each hoist assembly, were recorded. By relating the cable payout trace deflection to oscillograph paper speed, a cable payout rate or load velocity could be determined.

### Hoist Input Command Instrumentation

The hoist operator's control grip thumb switch supplied a command signal to the hoist controller logic. The command signal, conditioned to a 0-5VDC output for 0-100% command and interfaced with other controller network logic, determined the hoisting or lowering rate. In the single hoist mode, each command signal was recorded on rack "B" oscillograph.




Figure 9. Cable Angle Sensor Mechanism.






Figure 10. Cable Payout Sensor •

In the sync mode, only the forward hoist command signal was recorded since the aft hoist unit was commanded from the forward grip thumb switch.

#### Cargo Coupling Instrumentation (Mechanical Release Signal)

The hoist operator's cargo system control panel mechanical release switch was used for recording the command signal to the coupling solenoids and was recorded on rack "B" oscillograph.

#### Cable Payout Speed Instrumentation

The cable payout was derived from a sensing mechanism employing two magnetic pickups (MPU) which sensed ATM shaft speed. The ATM shaft speed was directly related to cable payout speed by the system gearing as represented in Table IV.

The MPU analog signal was conditioned and recorded on the rack "B" oscillograph.

#### Cable Speed Instrumentation

The payout speed signal was also fed to two zero center panel meters directly in front of the hoist operator. This provided the operator with a visual indication of cable payout speed and rate change or load velocity.

#### Power Requirements

The instrumentation system required 115 VAC 50-60 Hz and 28 VDC power supplies.


#### Recording Instrumentation

The recording instrumentation consisted of the galvanometer input network, the galvanometer, and the recording oscillograph which housed the galvos. The galvo input networks were as shown in Figure 11. The networks were installed on the terminal boards on the junction panel located in rack "A". All the recorded signals from each source were terminated in the same manner with the matching networks located on the rack "A" junction panel.

The recording galvanometers selected for pressure, rpm and modulating valve measurements had a minimum upper frequency response limit of 200 Hz to permit observation of oscillatory, fluctuating or step input signals.

TABLE IV. ATM SHAFT SPEED RELATED TO CABLE PAYOUT  
SPEED BY SYSTEM GEARING.

| Cable<br>Speed<br>(fpm) | Shaft<br>Speed<br>(rpm) | MPU<br>Frequency<br>(Hz) | Speed<br>Signal<br>(VDC) |
|-------------------------|-------------------------|--------------------------|--------------------------|
| 120                     | 8,000                   | 5,250                    | 5.00                     |
| 60                      | 4,000                   | 2,625                    | 2.50                     |
| 30                      | 2,000                   | 1,313                    | 1.25                     |
| 15                      | 1,000                   | 656                      | 0.625                    |
| 7.5                     | 500                     | 328                      | 0.312                    |
| 3.75                    | 250                     | 164                      | 0.156                    |



Resistor values were derived from the following formula:

$$R_s = \frac{V_{in}}{D I_g} \quad \text{where}$$

- $R_s$  = calculated source resistance
- $V_{in}$  = input voltage
- $D$  = desired deflection in inches; usually 2.0
- $I_g$  = galvo undamped D-C sensitivity in UA or MA/IN.  
(see manufacturer's specs)
- $R_d$  = required damping resistance, from manufacturer's spec sheet

Figure 11. Galvo Input Networks.

Galvanometers with a lower frequency response limit were used for the temperature, cable payout and command signal instrumentation.

Six Burr-Brown amplifiers located in rack "B" were used as buffer amplifiers to isolate those signal sources which did not have sufficient current magnitude to drive the recording galvanometers directly.

A 5-Hz signal was fed to one recording channel on each oscillograph to provide an accurate time/data correlation. The signal was in series with an event switch which served to correlate the start time on each of the three recording oscillographs. The event switch was located at the LCC station, with two recorder "on" lights and two recorder start switches.

#### Closed-Circuit TV System (CCTV)

A CCTV system was installed to monitor the moving parts on the hoist assembly during system testing. The system consisted of a monitor, a switch panel, and a camera enclosed in an environmental housing. The switch panel was located in rack "A", while the monitor was at the top of rack "B". The camera zoom lens is manually adjustable for the desired field of view.

#### Intercom System

A four-station intercom system was provided to enable the LCC station to have constant communications with three other stations. They were:

1. Ground crewman station
2. Rack "B" instrumentation monitor
3. Hoist assembly station

Each station was fitted with a dynamic mike and headset combination.

#### Calibration Procedures

Each system was calibrated daily, prior to PPG startup and post-calibrated when the days testing has been accomplished, as described in Appendix IV. Periodic calibrations were in compliance with MIL-C-45662. All instrumentation calibrations were traceable to the National Bureau of Standards.

### Container Weighing Instrumentation

The weighing instrumentation for the loaded MILVAN container consisted of two 50,000-lb Baldwin-Lima-Hamilton load cells and a Baldwin-Lima-Hamilton universal percentage indicator. The cargo handling system was in the two-point suspension configuration with one load cell in series with each hook. The SR4 universal percentage indicator was used to measure the individual loads. Connections to the load cells were made using two 70-foot eight-conductor cables from the load cells up to the test rig control room. The measured load using the load cells was within 0.7% of the calculated load.

### Maximum Load Test Instrumentation

Three of the load isolator transducers from the hoist units were used for the maximum static load demonstration test. The calibrated transducers were used as the main load-sensing elements during the test.

The isolator load signals which represented the hook load were conditioned and recorded on the CEC recording oscillograph, "C". The conditioned load signal was also displayed for the LCC on a digital voltmeter which indicated the load directly in pounds. The equipment is shown schematically in Figure 12.

### DESIGN LAYOUTS

The integrated test rig is described by the engineering drawings given in Appendix II. Besides the basic ITR structural design, additional subsystems were required for the assembly, installation, functional operation and test of the cargo system. Each of the required design items is identified on the following drawings:

#### System Test Drawing Tree - SK301-11676 (See Figure 65 in Appendix II)

- Hoist installation, including
  - Hoist module
  - Span positioning
- Control system wiring
- Assembly/handling fixtures
- LCC station platform
- Miscellaneous test fixtures and wiring




Figure 12. Maximum Load Test Network.

System Wiring - SK301-11694  
(See Figure 68 in Appendix II)

A schematic showing the electrical integration of the cargo handling system is shown in Figure 67.

FABRICATION

STRUCTURE PREFABRICATION

The following items were prefabricated and yard assembled prior to delivery to the test site:

1. Fore-aft frames
2. Control room enclosure
3. Hoist modules
4. Overhead beams
5. Overhead lateral beams and davit supports
6. Control room floor
7. Stairway sections
8. Outriggers and frame bracing
9. Footing pads

FOUNDATION

Excavations, exact site location, and footing designs were adjusted to utilize available rock strata. Figures 13 and 14 show the excavation, location of bedrock, and foundation preparation. Figure 15 shows the ground tiedowns provided in the foundation.

The rig was erected with prefabricated fore-aft frames joined at the splices and supported by outriggers. Inboard and outboard frames were assembled between the main columns on alignment pins and welded in place.

The main overhead beams were drilled and bolted on assembly. The lateral beam components and davit supports were then welded in place. Figures 16 through 26 illustrate the assembly method and main features of the structure. The control room enclosure assembly, Figure 27, was hoisted in place and joined to the main column pads. Figure 28 shows the ITR after complete erection, including the air distribution duct. For reassembly at another site, the towers (split into four units at the splice joints), the overhead structure disassembled to its basic components, the davit, outriggers, and control room shelter can be shipped as individual items. Table V delineates weight breakdown of the ITR structural assemblies.





Figure 13. Excavation for ITR Foundation.



Figure 14. Preparation of Footings and Foundation.




Figure 15. Three Ground Tiedown Points in Foundation.

| <u>Number</u> | <u>Component</u>              | <u>Number</u> | <u>Component</u> |
|---------------|-------------------------------|---------------|------------------|
| 1.            | Lower Inboard-Outboard Frames | 7.            | Rails            |
| 2.            | Upper Inboard-Outboard Frames | 8.            | Frame Struts     |
| 3.            | Overhead Beams                | 9.            | Modules          |
| 4.            | Work Platforms                | 10.           | Davit Mast       |
| 5.            | Outrigger Members             | 11.           | Davit Platform   |
| 6.            | Stairways and Landings        |               |                  |



Figure 16. Rig Components and Raising of Lower Main Frames.




Figure 17. Complete Tower Frames Erection.




Figure 18. Overhead and Stairway Installation.




Figure 19. End view of tower (1961).




Figure 20. End View of Forward Tower.






Figure 21. Under View of Overhead Structure and Hoist Module Location.




Figure 22. Hoist Modules (Inverted).




Figure 23. Control Room Area - Top of Forward Tower.




Figure 24. View of Overhead Section From LCC Position; Forward Tower.



Figure 25. Work Platform and 14710 located between Control Room location.




Figure 26. Completed ITR Framework on Foundation.




Figure 27. Control Room Enclosure Assembly.



FIGURE 10. Aerial View of Complete Structure and Hot Air Distribution Duct.



| TABLE V. ITR WEIGHT BREAKDOWN.    |                           |      |                 |                   |
|-----------------------------------|---------------------------|------|-----------------|-------------------|
| Drawing No.                       | Nomenclature              | Qty. | Wt/Assy<br>(lb) | Total Wt.<br>(lb) |
| SK301-11304-1                     | Tower Assy.               | 1    | 38,723          | 38,723            |
| SK301-11304-2                     | Tower Assy.               | 1    | 42,750          | 42,750            |
| SK301-11302-1                     | Hoist Module              | 2    | 2,470           | 4,940             |
| SK301-11302-2                     | Davit Mount               | 1    | 6,207           | 6,207             |
| SK301-11302-3                     | Module Support            | 2    | 6,274           | 12,548            |
| SK301-11302-4                     | Platform Assy.            | 1    | 831             | 831               |
| SK301-11302-6                     | Platform Assy.            | 1    | 831             | 831               |
| SK301-11302-5                     | Beam Assy.                | 2    | 8,081           | 16,162            |
| Aux. Hoist - 6,000-Lb Load Lifter |                           | 1    | 3,365           | 3,365             |
| Mast (Jib Crane)                  |                           | 1    | 3,965           | 3,965             |
| X73-003-AS-Y03                    | Control Room<br>Enclosure | 1    | 15,000          | 15,000            |
|                                   |                           |      | TOTAL           | 145,322           |

## HOIST MODULE INSTALLATION

Each module was hoisted over the side of the ITR work platform from a truckbed using the overhead davit and a short-reach, adjustable-cg sling, ST40972. The side and module handrails were removed at each module location. Hoisting clearance between the jib crane hook and the work platform kick plates was 9 feet 4 inches. (Note: Safety harnesses were worn by personnel on the ITR platform; hard hats below.) Figure 29 shows both modules enplacements. Each module was secured with four bolts, each torqued in place to AISC requirements. The hoist enclosure handrails were used to support a tarpaulin for protection against the weather.

"Open loop" operation of each hoist was required to accomplish installation of the cargo coupling and attachment of the signal conductor cable. Test instrumentation and lash-up of control room equipment followed.

The following cargo system components were removable from the ITR overhead work platform without requiring operation of the system:

1. Hoist drive
2. Pneumatic valves and ducting
3. Signal conductor reel
4. Hoist
5. Span actuator
6. Rails (with hoist removed)

The following components were removable, but they required operation of the PPG and control system:


1. Hoist cables
2. Cable cutter assemblies
3. Signal conductor disconnect

## PPG AND AIR SUPPLY INSTALLATION

The air supply installation consisted of the pneumatic power generator (power unit, load compressor and controls) prepared as a separate package and the air distribution system. The PPG location and air distribution insulated piping are shown in Figures 30 through 35.

## INSTRUMENTATION INSTALLATIONS

The LCC station and test rig instrumentation installations are shown in Figures 36 through 41.



File  
CRANE



Figure 29. Hoist System Installed in ITR.




Figure 31. 200 Pad at Aft Tower.




Figure 21. A view of the industrial facility from the supply.




Figure 32. Insulated Air Header and Riser.




Figure 33. Complete PPG Enclosure and Air Distribution Line.




Figure 34. Side View of PPG.





PHOTOGRAPH BY THE NATIONAL AERONAUTICS AND SPACE ADMINISTRATION







Figure 37. Instrumentation, P20 and P200 Station.



0  
1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99








Figure 41. Static load test instrumentation.

## PROOF LOADING

Handling fixtures and the utility hoist were proof-loaded in accordance with the following schedule:

| <u>Fixture</u>   | <u>Rated Load, lb</u> | <u>Proof Load, lb</u> |
|--|-----------------------|-----------------------|
| Hoist sling ST-51273   | 2,000                 | 4,000                 |
| Hoist and module sling ST-40972  | 6,000                 | 12,000                |
| Utility hoist-load lifter<br>Series 700 and jib crane<br>(davit) model no.990740 | 6,000                 | 9,000                 |

## SPECIMEN INSTALLATION AND REMOVAL

The cargo system demonstration hardware was initially installed in the individual hoist modules at ground level. Only small hand tools and a sling were required. The modules were elevated on 4-foot workstands to provide access below the assembly. The module buildup started with the span positioning track and drive. The installation of the hoists (with cable) followed, with addition of the equalizer bar, angle and payout sensors, load isolators, hoist drives, pneumatic ducting, and system wiring. Figure 42 shows the hoist/module assembly before emplacement in the TTR.

## USE OF INTEGRATED TEST RIG

The integrated test rig was used to perform the following general categories of cargo handling system tests:

1. Functional check of components
2. Control system studies (open and closed loop)
3. System performance
  - a. No load - speed
  - b. Constant load - speed
  - c. Stall torque (live loads)
4. Static loads to maximum (ground tiedown)
5. Individual hoist operation
6. Endurance
7. Asymmetric load
8. PPC regulator valve development
9. General operating indoctrination
10. Dynamic analysis (high-speed photography)
11. Load acquisition demonstrations using a container handling device

The PPC starting and operating procedures used are outlined in Appendix III. The instrumentation calibration procedure used is given in Appendix IV.





• JOHN F. KENNEDY •  
• JOHN F. KENNEDY •  
• JOHN F. KENNEDY •  
• JOHN F. KENNEDY •  
• JOHN F. KENNEDY •

Test operations were performed under the prevailing weather conditions for the Philadelphia area during the months of October through April, which included rain, freezing temperatures, snow, hail, and winds up to 35 miles per hour with higher gusts.

Typical events in the TTR program are illustrated in the following figures.

Figure 43 shows a view of the control room during a typical operation. One man is monitoring the instrumentation, one is monitoring the PPG control panel, and the third is operating the hoists from the simulated LCC station.

Figure 44 shows a view of the cargo couplings from the LCC station. The forward coupling, which is nearest the viewer, is in the stowed position. The aft coupling is in the full-up position.

Figure 45 shows a view over the LCC operator's left shoulder during synchronous hoisting of two separate kirksite block loads.

Figure 46 shows a U.S. Army MILVAN container being hoisted using the GPE helicopter-transported container handling device.


Figure 47 shows a kirksite block load being hoisted using the single-point adapter and sheave system, which is designed to large-load vertical lifts of up to 35 tons.


Figure 48 shows the drive-through capability of the aft test rig tower. A MILVAN container on a standard high-bay flatbed trailer is being positioned for hoisting.

#### CONCLUSIONS AND RECOMMENDATIONS

The integrated test rig was a viable fixture for the cargo handling ATC program from the viewpoints of compliance with contractual design objectives, design simplicity, fabrication, erection, system installation, and instrumentation.

Uses of the integrated test rig could be expanded to include maintenance training if work platforms were added beneath the overhead structure to provide access to the hoist assemblies similar to what will exist in the actual helicopter. Improvements are needed in the PPG system; to increase its air supply capacity and equipment reliability.








Figure 45. Top View of Two Individual Loads Near Top of Lift Cycle.




Figure 4b. 20' x 6' MILLI-CORR TOWER. MILLVAN WITH CONTAINER  
BEING LOWERED INTO POOL 1011.




Figure 47. Lifting a 29-Ton Load With Single-Point Adapter - Hoist Spar  
W 3 16 Feet.




Figure 47. Unloading MPMAR through Base of Aft Tower.



APPENDIX 1  
INTEGRATED TEST RIG STRESS ANALYSIS

TABLE OF CONTENTS

|   | <u>Page</u> |
|---|-------------|
| LIST OF SYMBOLS . . . . .                       | 80          |
| SUMMARY . . . . .                               | 81          |
| STRESS ANALYSIS - OVERHEAD ASSEMBLIES . . . . . | 83          |
| Hoist Module Assembly. . . . .                  | 83          |
| Auxiliary Hoist Mount. . . . .                  | 87          |
| Hoist Module Support Assembly. . . . .          | 89          |
| Work Platform Assembly . . . . .                | 91          |
| Main Fore-and-Aft Beams. . . . .                | 92          |
| STRESS ANALYSIS - TOWER ASSEMBLIES. . . . .     | 102         |
| Fore-Aft Frame - Member Loads. . . . .          | 103         |
| Inboard-Outboard Frame - Member Loads. . . . .  | 113         |
| Column and Strut Splice. . . . .                | 120         |
| Outrigger Tiedown Assembly . . . . .            | 121         |
| FAILURE LOADS . . . . .                         | 124         |
| FOUNDATION LOADS. . . . .                       | 128         |
| DEAD WEIGHTS . . . . .                          | 132         |
| CONTROL ROOM SHELTER. . . . .                   | 133         |

LIST OF SYMBOLS

|                 |   |
|-----------------|---|
| A               | Cross Section Area - In. <sup>2</sup>               |
| c               | Distance from Neutral Axis to Extreme Fiber of Beam |
| d               | Depth of Beam or Girder - Inches                    |
| E               | Modulus of Elasticity of Steel - KSI                |
| e               | Load Eccentricity - Inches                          |
| F <sub>A</sub>  | Allowable Stress for Compression Members - KSI      |
| f <sub>a</sub>  | Computed Axial Stress - KSI                         |
| f <sub>b</sub>  | Computed Bending Stress - KSI                       |
| F <sub>CR</sub> | Failure Stress - KSI                                |
| f <sub>v</sub>  | Computed Shear Stress - KSI                         |
| I               | Moment of Inertia of Section - In. <sup>4</sup>     |
| J               | Polar Moment of Inertia - In. <sup>4</sup>          |
| L               | Span Length - Inches                                |
| l               | Actual Unbraced length - In.                        |
| M               | Moment - In. KIPS                                   |
| M.S.            | Margin of Safety                                    |
| P               | Applied Load - KIPS                                 |
| q               | Shear Flow - lb./In.                                |
| R               | Reaction - KIPS                                     |
| r               | Governing Radius of Gyration - In.                  |
| S <sub>s</sub>  | Section Modulus - In. <sup>3</sup>                  |
| T               | Torsional Moment - In. K                            |
| V               | Static Shear on Beam - KIPS                         |
| Δ               | Deflection - Inches                                 |
| τ               | Torsional Shear Stress - KSI                        |

APPENDIX I  
INTEGRATED TEST RIG STRESS ANALYSIS

SUMMARY

This appendix is presented to substantiate the strength of towers and overhead steel structure designed for use during testing of cargo hoists of the heavy lift helicopter. It is intended that the data contained herein be used as a basis for establishing the structural integrity of the structure for load changes during IIIH testing and/or for tests other than the IIIH tests.

A-36 type steel was used throughout since it is common for the steel industry and affords an economical design. American Institute of Steel Construction, Inc., Allowable Stresses and Design Practices, as printed in the sixth edition of their manual, were used. ASTM A325 bolts were used for all connections.


Strength requirements were based upon cargo system loads: 28-ton, design; 70-ton, limit. Rig survival - no collapse - is one of the provisions in the design in the event of a sling or other failure during testing. The towers were designed using 1.5 factors of maximum test load, or failure loads, with a horizontal load resulting from a 5° component in both cases. All horizontal load components were considered reversible. Stairways, walkways, and work platforms were designed to meet the requirements of the Occupational Safety and Health Standards (Code of Federal Regulations, Title 29, Chapter XVII, Part 1910).

Because of height requirements of the towers and the relative low design loads, a trussed frame configuration was selected. Requirements for a control room in a location near the hoists so that the hoist operator could be located in the same relative position as he would be in the helicopter made the selection of a 14-foot-square tower desirable. Easy installation of stairways on this type of tower was also a factor in the selection of this configuration. Outriggers were used on each leg of the tower in the inboard-outboard plane for two reasons:

1. The possibility of an enclosure being erected over the top of the towers which would result in considerable wind loading.
2. The requirement that the secondary bracing be removed in the lower portions of the tower to permit a loaded truck to drive through the tower.

Outriggers in the fore-aft plane were not required because the two conditions stated above are not factors in this plane. Also, horizontal components of test loads are reacted by four frames in the fore-aft plane, while in the inboard-outboard direction only the two inner frames will react the horizontal component of loading.

The tower assemblies as delivered by the fabricator were not of the configuration as intended in the original design. This optional construction was analyzed and found to have adequate strength for the requirements of the hoist test tower loads. The reaction loads on the foundation are not as evenly distributed in the optional construction as in the original design; however, since the foundations are resting on bedrock, the optional configuration is sufficient for all test requirements. The configuration as delivered is referred to in the stress analysis as the optional construction configuration.




$$\sum M_{R_A} = 105(21.75) + 105(59.75) + 2.5(40.75) - R_B(141.5)$$

$$2280 + 6280 + 102 = 141.5 R_B$$


$$R_B = \frac{8661}{141.5} = 61.2K$$

$$R_A = 61.2 + 105 + 105 + 2.5 = 151.3K$$



$$M_{MAX} = 81.75(61.2) = 5000 \text{ in}\cdot\text{K}$$

$$S \text{ Req'd} = \frac{5000 \text{ in}\cdot\text{K}}{50 \text{ PSI}} = 100 \text{ in}^3$$



|     |          |   |          |                        |
|-----|----------|---|----------|------------------------|
| (2) | 3/4 x 19 | 1 | 428.7(2) | 857.4 in <sup>4</sup>  |
| (4) | 1 x 4.5  | 1 | 200 x 9  | 1800.0 in <sup>4</sup> |
|     |          |   |          | 2657.4 in <sup>4</sup> |

$$S = \frac{I}{c} = \frac{2657.4}{10} = 265.74 \text{ in}^3$$

$$f_b = \frac{5000 \text{ in}\cdot\text{K}}{265.74 \text{ in}^3} = 18.85 \text{ K/In Bending Stress}$$

Max Test Load = 1/2 Failure Condition

$$f_b = 9.4 \text{ K/In Bending Stress}$$

SK301-11302-1

Cross-Sectional Area at Point of Max Shear

$$A = (2)11(.75) = 16.50 \text{ in.}^2$$

$$f_s = \frac{V}{A} = \frac{151.3}{16.5} = 9.17 \text{ KSI Shear Stress}$$

$$\text{M.S.} = \frac{14.5}{9.17} - 1 = .58$$

Long. Shear  $f_s = \frac{VQ}{Ib}$  at weld (4) 3/8 welds


$$Q = 9(10) = 90 \text{ in.}^4$$

$$f = \frac{151.3(90)}{2657(1.5)} = 3.42 \text{ KSI Long. Shear}$$

SK301-11302-1  
Torsional Shear

| <u>Element</u> | <u>b</u> | <u>t</u>        | <u>bt<sup>3</sup></u> |
|----------------|----------|-----------------|-----------------------|
| Flange         | 4.125    | 1.0             | 4.125                 |
| Flange         | 4.125    | 1.0             | 4.125                 |
| Web            | 20.0     | .75             | 8.43                  |
|                |          | $\Sigma bt^3 =$ | 16.680                |

$$J = \frac{2bt^3}{3} = \frac{16.68}{3} = 5.56$$



$$\text{Torsion} = (1.97 - c) 52.5K = 1.35(52.5) = 70.8 \text{ in. K}$$

$c = .622$

Torsional Shear Stress

$$\tau = \frac{Tt}{J} = \frac{70.8(.75)}{5.56} = 9.55 \text{ KSI}$$

$$P = \frac{F.S. \cdot 70T(1.5)}{4} = 52.5K$$

M.S. - Margin of safety based on allowable design stress  
 (22 KSI tension, 14.5 KSI shear)

Bending


$$\text{M.S.} = \frac{F_a}{\bar{F}_a} - 1 = \frac{22}{18.85/1.5} - 1 = .75$$

(F.S.)

Shear

$$\frac{14.5}{9.55/1.5} - 1 = 1.28$$

SK301-11302-1  
Shear Center



Flange  $q = 528(1.0 \times)$  when  $x=0$   $q=0$   
 $\times 4.125$   $q = 2175$  lb/in. at corner

Web  $q = 2175 + 528(10) \frac{.75}{2} = .667y (.75y)$

$$2175 + 1982 = 250y^2$$

$$4157 = 250y^2$$

$$2175(20) + 1982(20) .667 = 70,000$$


$$70,000 = 4.12(528)(20) + 43500$$

$$e = \frac{43500}{70000} = .622$$




SK301-11302-2 Assembly  
 Auxiliary Hoist Mount

DJ Wt Hoist 3.37  
 Max. Load 6.00  
 9.37K



$$-R_A = R_B = \frac{14.05(168)}{168} = 14.08K \text{ (2 beams)}$$

7.64K/beam




$$R_A = R_B = \frac{P}{2} = \frac{14.05}{2} = 7.02K$$

$$\begin{aligned} \text{Total Moment} &= 14.05 (168) + 7.02 (84) - 2 \text{ beams} \\ &= 2360 + 592 \\ &= 2952 \text{ In K} - 2 \text{ beams} \\ &= 1476 \text{ In K/beam} \end{aligned}$$

$$f_b = \frac{M}{S_x} = \frac{1476}{121.1} = 12.2 \text{ KSI} - 14 \text{ W}^F 78$$

SK301-11302-2




$$M = \frac{wl^2}{8} = \frac{.05(168)^2}{8} = 176 \text{ In. K}$$

$$f_b = \frac{M}{S_x} = \frac{176}{121.1} = 1.45 \text{ KSI}$$

Total Stress - Uniform Load + Hcist Load

$$f_b = 12.2 + 1.45 = 13.65 \text{ KSI}$$


SK301-11302-3  
Hoist Module Support Assembly



$$P = \frac{151.3}{2} + \frac{DD \text{ Wt}}{2} =$$

$$= 75.65 + \frac{2.5(100.75)}{141.5} = 75.65 + 1.9 = 77.55$$

$$R_A = R_B = 77.55$$



$$f_s = \frac{P}{A} = \frac{77.55}{41.85} = 86 \text{ KSI Shear Stress}$$


$$M_{MAX} = 77.55(53) = 4120 \text{ In}\cdot\text{K}$$

$$f_b = \frac{M}{S_x} = \frac{4120}{226.7} = 18.15 \text{ KSI}$$

Max. Test Load = 1/2 Failure Condition

$$f_b = 9.1 \text{ KSI}$$


SK301-11302-3



$$-32 \quad 6[8.2 \text{ Lb} \quad S_x = 4.3 \text{ In.}^3$$

$$M_{\text{MAX}} = \frac{wl^2}{8} = \frac{33.3(144)^2}{8} = 86.3 \text{ In. K}$$

$$f_b = \frac{M}{S_x} = \frac{86.3}{4.3} = 20.07 \text{ KSI}$$



$$M_{\text{MAX}} = \frac{Pl}{4} = \frac{1.000(144)}{4} = 36 \text{ In. K}$$


$$f_b = \frac{M}{S_x} = \frac{36}{4.3} = 8.38 \text{ KSI}$$

Grip Strut Flooring Capacity (members tack welded together)

|                      |                        |
|----------------------|------------------------|
| Concentrated load    | 1100 Lb.               |
| Uniformly dist. load | 353 Lb/Ft <sup>2</sup> |

SK301-11302-4  
Work Platform Assembly

Design load 200 Lb/Ft.




$$M_{MAX} = \frac{wl^2}{8} = \frac{.05(168)^2}{8} = 176.2 \text{ In. K}$$

$$f_b = \frac{M}{S_x} = \frac{176.2}{16.2} = 10.88 \text{ KSI}$$

Grip strut on this assembly has a capability of 235 Lb/Ft<sup>2</sup> of uniformly distributed load and a concentrated load of 633 Lb at the midpoint.

SK301-11302-5  
 Main Fore & Aft Beam Assembly  
 30WF172  
 $A = 50.72 \text{ In}^2$   
 $S_x = 528.2 \text{ In}^3$

Dead Wt Only  
 16' position



$$M_E = -5.1(38.25) = -195.2$$

$$-4.27(55.25) = -236.0$$


$$-2.97(196.75) = -584.0$$

$$21.94(240) = 5270.0$$

$$f_b = \frac{4254.8 \text{ In} \cdot K}{S_x}$$

$$(528.2)$$

$$f_b = 8.07 \text{ KSI}$$



$$M_A = -2.97 \times 141.5 = -420.0 \text{ In} \cdot K$$

$$7.39 \times \frac{184.75}{2} = -682.0 \text{ In} \cdot K$$


$$21.94 \times 184.75 = 4050.0 \text{ In} \cdot K$$

$$\frac{2943}{S_x} = 5.58 \text{ KSI}$$

$$(528.2)$$

SK301-11302-5  
30 WF172

Test load -  
Failure condition  
16' hoist position  
28-ton load @ 1.5 F.S.



$$\sum M_{R_A} = 29.75(295.25) + 12.25(436.75) - 30 R_B$$

$$R_B = \frac{8780 + 53.50}{480} = \frac{141.30}{480} = 29.5K$$

$$R_A = 12.5$$

$$M_A = -141.5(12.25) + 184.75(29.5) \\ -1732 + 5450 = 3718 \text{ In. K}$$

$$f = \frac{M_A}{S_x} = \frac{3718}{528.2} = 7.04 \text{ KSI Failure load} \\ \frac{5.58 \text{ KSI DD Wt}}{12.62 \text{ KSI}}$$

SK301-11302-5

30 WF172

Proof load


26' hoist position

70-ton load @ 1.5 F.S.

.60-.40 load split

40% proof load

60% proof load




$$\Sigma M_{R_A} = 29.75(43.25) + 12.25(184.75) + 18.3(295.25) + 44.7(436.75)$$

$$\frac{2575}{2} + \frac{4530}{2} + \frac{10800}{2} + \frac{39000}{2} \qquad -480R_B$$

$$R_B = \frac{2845.2}{480} = 59.25K$$

$$R_A = 45.75K$$



$$M_A = \frac{89.4(141.5)}{2} - \frac{118.5(184.75)}{2}$$

$$\frac{-12660}{2} + 21900 = \frac{9240}{2}$$

$$f_b = \frac{4620}{528.8} = 8.75 \text{ KSI Load}$$

$$\frac{5.58 \text{ KSI DD Wt}}{14.33 \text{ KSI}}$$



SK301-11302-5


30 WF172

Proof load

26' hoist position

70-ton load @ 1.5 F.S.

.50-.50 load split



$$M_{MAX} = -52.5(184.75) + 37.2(141.5)$$

$$= 9700 + 5270 = 4430 \text{ In.K}$$

$$f_b = \frac{M_{MAX}}{S_x} = \frac{4430 \text{ In.K}}{528.2 \text{ In.}^3} = 8.75 \text{ KSI load}$$


$$8.07 \text{ KSI DD Wt}$$

$$\underline{16.82 \text{ KSI}}$$

30 WF172  
 A = 50.72  
 Sx = 528.2 In<sup>3</sup>

SK301-11302-5

Failure Condition  
 at 16' position  
 70-ton proof load  
 (DD Wt included)




$$\begin{aligned} \sum M_{R_A} &= 19.20(240) + 2.97(43.25) + 4.27(184.75) + 5.1(201.75) + 5.1(278.25) \\ &\quad + 81.82(295.25) + 33.87(436.75) - 480R_B \\ &= 4608 + 128.45 + 788.88 + 1028.93 + 1419.08 + 24157.36 + 14792.72 \\ R_B &= \frac{46923.42}{480} = 97.76K \end{aligned}$$


$$\begin{aligned} \sum F_u &= +19.20 + 2.97 + 4.27 + 5.1 + 5.1 + 81.82 + 33.87 - 97.76 - R_A \\ R_A &= 54.57 \end{aligned}$$

SK301-11302-5

Failure condition  
at 16' span  
70-ton proof load



Shear Diagram-Concentrated Load



Uniformly Distributed Load

30 WF172

SK301-11302-5

Failure condition  
at 16' span  
70-ton proof load

Moment is Max. at PT. "A"

Solving for Max. Mom.

$$\begin{aligned}M_A &= -86.16(184.75) - 9.6(184.75) + 33.87(141.5) - 400.45 \\ &= 12498.6 \text{ In. K}\end{aligned}$$

$$f_b = \frac{12498.6}{528.2} = 23.7 \text{ KSI}$$

30 WF172  
 A = 50.72 In<sup>2</sup>  
 Sx = 528.2 In<sup>3</sup>

SK301-11302-5

Failure condition  
 at 26' position  
 70-ton proof load  
 (DD Wt. included)




Figure A




Figure B

Figure A

$$\sum M_{RA} = 128.45 + 788.88 + 1028.93 + 1419.08 + 33.87(295.25) + 81.82(436.75) - 480R_B$$

(10000.12)

$$+ 81.82(436.75) - 480R_B$$

(35734.89)


$$R_B = \frac{49,100.34}{480} = 102.29K$$

$$R_A = 30.84K$$


Shear and Moment Diagram on  
 Page 100.

SK301-11302-5

at 26' location  
70-ton proof load



V  
Fig.A



V  
Fig.B

SK301-11302-5

Failure condition  
at 26' position  
70-ton proof load

Moment is Max. at PT. "A"


$$M_{MAX} = -102.29(184.75) - 9.6(184.75) + 81.82(141.5) + 400.45$$

$$= \frac{8693.72}{528.2} = 16.45 \text{ KSI}$$

SK301-11304-1  
Tower Assembly


The tower assembly is analyzed using the plain frame computer program.\* The fore-aft frame is analyzed using three separate loads: wind loads, test loads, and deadweight. The total load from the three combined loads and stress is computed for each member. The inboard-outboard frame is analyzed in the same way. To obtain the maximum stress in the main vertical columns it is necessary to add the stress found in the inboard-outboard frame to the stress of the fore-aft frame found as a result of the horizontal test loads only. The tower component identification is shown below.

(\*Boeing-Wichita Watfor computer program.)







Tower Assembly - Fore-Aft Frame



Tower Assembly






## GLOSSARY - COMPUTER ANALYSIS

Coordinates of Joints - Location of joints of frame using X and Y coordinate axes, the X axis being the line formed by base of towers and the Y axis the left-hand column centerline.

Member End Action - Nodes 1 and 2 define coordinate axis system of each member (see example). Node 1 represents "A" end of member; Node 2 represents "B" end of member. The line 3-6 is the Y axis of the member. The X



axis is 90° to the Y axis. Negative "X" action at the "A" end, and positive "X" action at the "B" end would indicate tension (KIPS) in member. "Y" action indicates shear (KIPS) in member. MZ action indicates moment (In.K.) about X axis of member.

### Member Information:

Area - Cross-sectional area (In.<sup>2</sup>) of member.

Inertia - Moment of inertia (In.<sup>4</sup>) of member.

Modulus - Modulus of elasticity of member.

Length - Length in inches.

Actions applied at joints - load applied at joints.

Support Reactions - foundation loads.

X Reaction - Shear

Y Reaction - Positive (down load)  
- Negative (up load)

TABLE VI. TOWER ASSEMBLY - FORE-AFT FRAME LOADS (KIPS).

| Member | Size             | Area  | Moment | Wind Load | Test Load | Dead-weight | Horiz. Test Only | Total Load |
|--------|------------------|-------|--------|-----------|-----------|-------------|------------------|------------|
| 1      | (7F) 4x3-1/2x3/8 | 5.34  | .00    | .00       | .00       | .00         | .00              | .00        |
| 2      | 8 WF 31          | 9.12  | 18.73  | 12.27     | 25.99     | 5.92        |                  | 44.18      |
| 3      | 7F 4x3-1/2x3/8   | 5.34  | .49    | 5.92      | 9.13      | 2.08        |                  | 17.13      |
| 4      | 8 WF 40          | 11.76 | 13.47  | -16.24    | 25.63     | 7.28        | 14.56            | 16.67      |
| 5      | 7F 4x3-1/2x3/8   | 5.34  | 1.94   | -3.93     | -6.74     | -1.54       |                  | -12.21     |
| 6      | 8 WF 31          | 9.12  | 1.82   | 8.63      | 19.82     | 4.52        |                  | 33.07      |
| 7      | 7F 4x3-1/2x3/8   | 5.34  | 1.41   | 5.41      | 9.18      | 2.09        |                  | 16.68      |
| 8      | 8 WF 40          | 11.76 | 6.29   | -12.26    | 31.77     | 8.68        | 11.75            | 28.19      |
| 9      | 7F 4x3-1/2x3/8   | 5.34  | 1.58   | -3.53     | -6.87     | -1.57       |                  | -11.97     |
| 10     | 8 WF 31          | 9.12  | 6.50   | 5.45      | 13.61     | 3.10        |                  | 22.16      |
| 11     | 7F 4x3-1/2x3/8   | 5.34  | 1.48   | 4.73      | 9.23      | 2.10        |                  | 16.06      |
| 12     | 8 WF 40          | 11.76 | 4.35   | -8.62     | 37.94     | 10.08       | 8.97             | 39.40      |
| 13     | 7F 4x3-1/2x3/8   | 5.34  | 1.95   | -2.93     | -6.64     | -1.51       |                  | -11.08     |
| 14     | 8 WF 31          | 9.12  | 6.43   | 2.76      | 7.53      | 1.72        |                  | 12.01      |
| 15     | 7F 4x3-1/2x3/8   | 5.34  | .44    | 4.00      | 9.05      | 2.06        |                  | 15.11      |
| 16     | 8 WF 40          | 11.76 | 35.35  | -5.44     | 44.15     | 11.50       | 6.16             | 50.21      |
| 17     | 7F 4x3-1/2x3/8   | 5.34  | 1.42   | -2.75     | -7.51     | -1.71       |                  | -11.97     |
| 18     | 8 WF 31          | 9.12  | 36.70  | .36       | .98       | .22         |                  | 1.56       |
| 19     | 7F 4x3-1/2x3/8   | 5.34  | 6.71   | 3.55      | 9.72      | 2.22        |                  | 15.49      |
| 20     | 8 WF 40          | 11.76 | 115.96 | -2.75     | 50.22     | 12.88       | 3.39             | 60.35      |
| 21     | 7F 4x3-1/2x3/8   | 5.34  | .00    | .00       | .00       | .00         |                  | .00        |

TABLE VI. Continued.

| Member | Size           | Area  | Moment | Wind Load | Test Load | Dead-weight | Horiz. Test Only | Total Load |
|--------|----------------|-------|--------|-----------|-----------|-------------|------------------|------------|
| 22     | 8 WF 40        | 11.76 | -10.75 | 16.08     | 9.21      | 7.28        |                  | 32.57      |
| 23     | 7F 4x3-1/2x3/8 | 5.34  | -.28   | -5.87     | .88       | 2.08        |                  | -2.91      |
| 24     | 8 WF 31        | 9.12  | -12.05 | -12.15    | 2.45      | 5.92        |                  | -3.78      |
| 25     | 7F 4x3-1/2x3/8 | 5.34  | 1.05   | 4.39      | -.64      | -1.54       |                  | -2.21      |
| 26     | 8 WF 40        | 11.76 | -2.48  | 12.13     | 9.80      | 8.68        |                  | 30.61      |
| 27     | 7F 4x3-1/2x3/8 | 5.34  | .49    | -5.36     | .86       | -2.09       |                  | -2.41      |
| 28     | 8 WF 31        | 9.12  | 1.60   | -8.53     | 1.87      | 4.52        |                  | -6.66      |
| 29     | 7F 4x3-1/2x3/8 | 5.34  | .75    | 3.99      | -.65      | -1.57       |                  | 1.77       |
| 30     | 8 WF 40        | 11.76 | 1.62   | 8.52      | 10.38     | 10.08       |                  | 28.98      |
| 31     | 7F 4x3-1/2x3/8 | 5.34  | .45    | -4.68     | .87       | 2.10        |                  | -1.71      |
| 32     | 8 WF 31        | 9.12  | -2.31  | -5.38     | 1.29      | 3.10        |                  | -.99       |
| 33     | 7F 4x3-1/2x3/8 | 5.34  | .77    | 3.40      | -.63      | -1.51       |                  | 1.26       |
| 34     | 8 WF 40        | 11.76 | -7.14  | 5.37      | 10.96     | 11.50       |                  | 27.83      |
| 35     | 7F 4x3-1/2x3/8 | 5.34  | .23    | -3.96     | .85       | 2.06        |                  | -1.05      |
| 36     | 8 WF 31        | 9.12  | 2.39   | -2.72     | .72       | 1.72        |                  | -.28       |
| 37     | 7F 4x3-1/2x3/8 | 5.34  | .73    | 3.21      | -.71      | -1.71       |                  | .79        |
| 38     | 8 WF 40        | 11.76 | -14.64 | 2.71      | 11.53     | 12.88       |                  | 27.12      |
| 39     | 7F 4x3-1/2x3/8 | 5.34  | 1.83   | -3.50     | .93       | 2.22        |                  | -.35       |
| 40     | 8 WF 31        | 9.12  | 13.57  | -.36      | .09       | .22         |                  |            |
| 41     | 8 WF 31        | 9.12  | 34.21  | -.11      | .02       | .06         |                  |            |
| 42     | 8 WF 31        | 9.12  | 149.98 | .12       | .29       | .06         |                  | .47        |

| TABLE VI. Concluded |           |       |             |           |           |             |                  |            |  |
|---------------------|-----------|-------|-------------|-----------|-----------|-------------|------------------|------------|--|
| Member              | Size      | Area  | Moment      | Wind Load | Test Load | Dead-weight | Horiz. Test Only | Total Load |  |
| 43                  | 30 WF 172 | 50.65 | See Page 99 |           |           |             |                  |            |  |
| 44                  | 30 WF 172 | 50.65 | See Page 99 |           |           |             |                  |            |  |
| 45                  | 30 WF 172 | 50.65 | See Page 99 |           |           |             |                  |            |  |
| 46                  | 8 WF 31   | 9.12  | -27.86      | 2.36      | 7.91      | 1.84        |                  | 12.11      |  |
| 47                  | 8 WF 31   | 9.12  | -16.40      | -2.33     | .92       | 1.84        |                  |            |  |
| 48                  | 8 WF 40   | 11.76 | -34.44      | -1.33     | 52.70     | 13.41       |                  | 64.78      |  |
| 49                  | 8 WF 40   | 11.76 | -17.11      | 1.31      | 11.60     | 13.41       |                  | 26.32      |  |
| 50                  | 8 WF 31   | 9.12  | 116.95      | -1.85     | -5.81     | -1.34       |                  | -9.00      |  |
| 51                  | 8 WF 31   | 9.12  | 50.44       | 1.83      | -0.64     | -1.34       |                  |            |  |

SK301-11304-1  
Tower Assembly - Fore-Aft Frame

The following calculations are for stress in the members of the frame (see page 103 for member numbers).

General Equation:

$$f = \frac{\text{Moment} \times 1.5}{\text{Section Modulus}} + \frac{\text{Total Axial Load} \times 1.5}{\text{Area}}$$

Member 19

$$f = \frac{6.71 \times 1.5}{3.0} + \frac{15.49 \times 1.5}{5.34} = 3.36 + 4.36 = 7.72\text{KSI}$$

$$\frac{L}{r} = \frac{226.5}{1.25} = 181 \quad Fa = 6.56$$

Member 20

$$f = \frac{115.96 \times 1.5}{35.5} + \frac{60.35 \times 1.5}{11.76} = 4.92 + 7.70 = 12.62\text{KSI}$$

$$\frac{L}{r} = \frac{152}{2.04} = 74.5 \quad Fa = 14.89 \text{ KSI}$$


Member 42

$$f = \frac{149.98 \times 1.5}{27.4} + \frac{.47 \times 1.5}{9.12} = 8.23 + .08 = 8.31\text{KSI}$$


$$\frac{L}{r} = \frac{168}{2.01} = 83.5 \quad Fa = 14.03 \text{ KSI}$$




Tower Assembly  
(Optional Construction)



Tower Assembly  
(Optional Construction)



Tower Assembly - Inboard-Outboard Frame



Tower Assembly

53.57K

53.57K


9.35K

$$53.57 + 53.57 = 107.14$$

$$\text{SIN } 5^\circ (107.14) =$$

$$.0871 (107.14) = 9.35\text{K}$$

Failure Condition  
70-ton proof load  
26' hoist position



Deadweight Load

Tower Assembly




TABLE VII. TOWER ASSEMBLY - INBOARD/OUTBOARD FRAME.

| Member | Size           | Area  | Sect.Mod. | Moment     | Wind Ld | Test Ld | Dead-weight | Total |
|--------|----------------|-------|-----------|------------|---------|---------|-------------|-------|
| 1      | 10 WF 33       | 9.71  | 9.2       | Very small | +14.94  | 31.03   | 4.85        | 50.86 |
| 2      | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | -.68    | 4.38    | 1.24        | 4.94  |
| 3      | 8 WF 40        | 11.76 | 12.1      |            | +8.72   | 40.27   | 8.65        | 57.64 |
| 4      | 8 WF 40        | 11.76 | 12.1      |            | -8.35   | 28.28   | 9.92        | 29.85 |
| 5      | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | 1.02    | 3.92    | 1.02        | 5.96  |
| 6      | 10 WF 33       | 9.71  | 9.2       |            | -15.63  | 3.04    | 4.50        | -8.09 |
| 7      | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | .60     | -3.90   | -1.10       | -4.40 |
| 8      | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | .65     | -2.01   | -.62        | -1.98 |
| 9      | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | -.90    | -3.48   | -.90        | -4.78 |
| 10     | 10 WF 33       | 9.71  | 9.2       |            | -14.75  | 6.40    | 5.37        | -2.98 |
| 11     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | -.19    | 4.70    | 1.46        | 5.97  |
| 12     | 8 WF 40        | 11.76 | 12.1      |            | -7.16   | 23.75   | 8.36        | 24.95 |
| 13     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | -1.52   | .19     | .03         | -1.30 |
| 14     | 8 WF 40        | 11.76 | 12.1      |            | 8.61    | 35.08   | 7.34        | 51.03 |
| 15     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | .13     | 5.55    | 1.41        | 7.09  |
| 16     | 10 WF 33       | 9.71  | 9.2       |            | 14.35   | 34.77   | 5.95        | 55.07 |
| 17     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | -.07    | -3.79   | -.97        | -4.83 |
| 18     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | 1.09    | -3.86   | -1.17       | -3.94 |
| 19     | 7F 4x3-1/2x3/8 | 5.34  | 3.0       |            | .62     | -3.23   | -1.00       | -3.61 |
| 20     | 10 WF 33       | 9.71  | 9.2       |            | -14.90  | 11.08   | 6.81        | 2.99  |
| 21     | 8 WF 40        | 11.76 | 12.1      |            | -6.74   | 23.21   | 6.21        | 24.68 |

TABLE VII. Concluded.

| Member | Size          | Area  | Sect.Mod. | Moment | Wind Ld | Test Ld | Dead-weight | Total  |
|--------|---------------|-------|-----------|--------|---------|---------|-------------|--------|
| 22     | 7/4x3-1/2x3/8 | 5.34  | 3.0       | 1.11   | - .68   | .84     | .25         | .41    |
| 23     | 8 WF 40       | 11.76 | 12.1      | 9.37   | 7.64    | 35.29   | 7.55        | 50.48  |
| 24     | 10 WF 33      | 9.71  | 9.2       | 1.29   | 14.44   | 40.23   | 7.34        | 62.01  |
| 25     | 7/4x3-1/2x3/8 | 5.34  | 3.0       | 3.71   | 5.42    | 13.16   | 2.34        | 20.92  |
| 26     | 8 WF 40       | 11.76 | 12.1      | 12.29  | -11.67  | 42.01   | 14.60       | 44.94  |
| 27     | 7/6x3-1/2x3/8 | 6.84  | 6.5       | 3.50   | -13.47  | -12.49  | .01         | -25.96 |
| 28     | 8 WF 40       | 11.76 | 12.1      | 9.06   | 20.71   | 73.58   | 14.60       | 108.89 |
| 29     | 7/4x3-1/2x3/8 | 5.34  | 3.0       | 2.87   | 10.10   | 9.36    | -.01        | 19.45  |
| 30     | 8 WF 40       | 11.76 | 12.1      | 22.95  | -2.77   | 50.68   | 14.58       | 63.49  |
| 31     | 7/6x3-1/2x3/8 | 6.84  | 6.5       | 8.17   | -13.20  | -12.86  | .02         | -26.04 |
| 32     | 8 WF 40       | 11.76 | 12.1      | 12.05  | 11.66   | 65.16   | 14.60       | 91.42  |
| 33     | 8 WF 31       | 9.12  | 27.4      | 246.90 | 5.15    | 4.98    | .05         | 10.18  |
| 34     | 8 WF 31       | 9.12  | 27.4      | 5.01   | 11.80   | 11.30   | -.11        | 21.99  |
| 35     | 8 WF 31       | 9.12  | 27.4      | 205.44 | -1.84   | -2.96   | -.15        | 4.95   |
| 36     | 8 WF 40       | 11.76 | 12.1      | 112.70 | -6.03   | 46.58   | 14.38       | 54.93  |
| 37     | 8 WF 40       | 11.76 | 12.1      | 97.71  | 5.91    | 58.95   | 14.40       | 79.81  |
| 38     | 8 WF 31       | 9.12  | 27.4      | 24.51  | -8.58   | -7.96   | .25         | -16.29 |
| 39     | 8 WF 31       | 9.12  | 27.4      | 35.46  | 8.92    | 10.27   | .29         | 29.48  |
| 40     | 8 WF 40       | 11.76 | 12.1      | 143.68 | -.49    | 53.09   | 14.60       | 67.20  |
| 41     | 8 WF 40       | 11.76 | 12.1      | 133.90 | .49     | 54.11   | 14.60       | 69.20  |
| 42     | 8 WF 31       | 9.12  | 27.4      | 83.72  | 4.55    | 4.52    | -.05        | 9.02   |

SK301-11304-1  
Tower Assembly - Inboard/Outboard Frame

$$f = \frac{M \times 1.5}{S} + \frac{P \times 1.5}{A}$$

Member 1  $f = \frac{50.86 \times 1.5}{9.71} = 7.86 \text{ KSI}$

$$\frac{L}{r} = \frac{162.0}{1.94} = 83.5 \quad F_A = 14.03 \text{ KSI}$$

Member 2  $f = \frac{.90 \times 1.5}{3.0} + \frac{4.94 \times 1.5}{5.34} = .45 + 1.39 = 1.84 \text{ KSI}$

$$\frac{L}{r} = \frac{189}{1.25} = 151 \quad F_A = 7.69$$

Member 3  $f = \frac{3.28 \times 1.5}{12.1} + \frac{57.64 \times 1.5}{11.76} = .41 + 7.36 = 7.77 \text{ KSI}$

$$\frac{L}{r} = \frac{152}{2.04} = 74.5 \quad F_A = 14.89$$

Member 15  $f = \frac{1.03 \times 1.5}{3} + \frac{7.09 \times 1.5}{5.34} = .52 + 1.99 = 2.51 \text{ KSI}$

$$\frac{L}{r} = \frac{162}{1.25} = 129.6 \quad F_A = 9.30 \text{ KSI}$$

Member 23  $f = \frac{9.37 \times 1.5}{12.1} + \frac{50.98 \times 1.5}{11.76} = 1.16 + 6.44 = 7.60 \text{ KSI}$

$$\frac{L}{r} = 74.5 \quad F_A = 14.89 \text{ KSI}$$

Member 24  $f = \frac{1.29 \times 1.5}{9.2} + \frac{62.01 \times 1.5}{9.71} = .21 + 9.58 = 9.79$

$$\frac{L}{r} = 83.5 \quad F_A = 14.03$$



$$\text{Member 25 } f = \frac{3.71 \times 1.5}{3.0} + \frac{20.92 \times 1.5}{5.34} = 1.85 + 5.88 = 7.73 \text{KSI}$$

$$\frac{L}{r} = \frac{168}{1.25} = 134 \quad F_A = 8.94$$

$$\text{Member 28 } f = \frac{9.06 \times 1.5}{12.1} + \frac{108.89 \times 1.5}{11.76} = 1.12 + 13.90 = 15.02 \text{KSI}$$

$$\frac{L}{r} = \frac{152}{2.04} = 74.5 \quad F_A = 15.90 \text{ KSI (A-36 steel)}$$

$$\text{Member 31 } f = \frac{8.17 \times 1.5}{6.5} + \frac{26.04 \times 1.5}{6.84} = 1.88 + 5.50 = 7.38 \text{KSI}$$

$$\frac{L}{r} = \frac{227}{1.39} = 163 \quad F_A = 7.16 \text{ KSI} \quad \text{Over}$$

$$\text{Member 32 } f = \frac{12.05 \times 1.5}{12.1} + \frac{91.42 \times 1.5}{11.76} = 1.49 + 11.65 = 13.14 \text{KSI}$$

$$\frac{L}{r} = 74.5 \quad F_A = 15.90 \text{ KSI}$$

$$\text{Member 35 } f = \frac{205.4 \times 1.5}{27.4} + \frac{4.95 \times 1.5}{9.12} = 11.24 + .81 = 12.05 \text{KSI}$$

$$\frac{L}{r} = \frac{38.0}{1.61} = 23.6 \quad F_A = 20.35 \text{ KSI}$$

#### Maximum Stress in Main Vertical Columns

$$f = f(\text{Inbd-Outbd Frame}) + f(\text{Fwd-Aft Frame Horiz. Test Only})$$

$$\text{Member 28 } f = 15.02 + \frac{6.16 \times 1.5}{11.76} = 15.80 \text{ KSI}$$

$$\frac{L}{r} = \frac{152.0}{2.01} = 75.62 \quad F_A = 15.90 \text{ KSI}$$

SK301-11304-1  
Tower Assembly - Column Splice - Friction

Design splice load =  $70.98 \times 1.5 = 106.4\text{K}$   
(Max.load)  $70.98 = 8.97 + 62.01$

16 Ea. 3/4 Dia. Bolts/Splice

Friction Load/Bolt =  $19.2\text{K}(.35) = 6.73\text{K}$

$$16 \times 6.73\text{K} = 107.6\text{K}$$

(2) 3/4 x 9.0 Plate  $A = 13.5 \text{ In.}^2$

$$f = \frac{P}{A} = \frac{106.4}{13.5} = 7.88 \text{ KSI}$$

32 In. of 3/8 Fillet Weld (3.6 K/In.) = 115K

Diagonal Strut Splice - Friction


Design Splice Load =  $16.06 \times 1.5 = 24.1\text{K}$   
(Max.load)

(2) Ea. 3/4 Dia. Bolts/Splice - Double Friction

Friction Load/Bolt =  $2 \times 6.73 = 13.46\text{K}$

$$2 \text{ Bolts} = 26.92\text{K}$$

SK301-11304-10  
Outrigger Base Plate Assembly



SK301-11304-10 Assembly  
-82 Assembly  
Outrigger Tiedown Assembly

-1C Assembly Shear Out

$$\text{Shear Area} - 1.5 \times 2 \times 2 = 6.0 \text{ In.}^2$$

$$\text{Shear Stress} = \frac{P}{A} = \frac{76.3}{6} = 12.7 \text{ KSI}$$

Tension at 2.0 Diameter Hole -82 Assembly

$$\text{Area} = 2 \times 3 = 6.0 \text{ In.}^2$$

$$f_t = \frac{P}{A} = \frac{76.3}{6.0} = 12.7 \text{ KSI}$$

Double Shear Pin 2.0 Diameter A307


$$A = 2 \quad r^2 = 6.28 \text{ In.}^2$$

$$S = \frac{P}{A} = \frac{76.3}{6.28} = 12.14 \text{ KSI}$$

Inches of 3/8 Inch weld required.

$$\frac{76.3}{3.6} = 21.2 \text{ In.}$$

Failure Loads @ 0°, 10°, 20° & 30°  
Single-Point - 26-Ft Hoist Position



Location of Failure

|                            |  |
|----------------------------|--|
| Failure Load 0° -- 537.0K  | Member 30<br>Friction splice in<br>main vertical column<br>(8 WF 40) |
| Failure Load 10° -- 297.0K | Member 31<br>Friction splice in<br>diagonal brace                    |
| Failure Load 20° -- 180.0K | Member 31<br>Friction splice in<br>diagonal brace                    |
| Failure Load 30° -- 135.0K | Member 31<br>Friction splice in<br>diagonal brace                    |

Towers would not collapse from these failure conditions.

### Failure Loads

$$F_{cr} = \frac{C \pi^2 E}{\left(\frac{L}{r}\right)^2} = \text{Critical stress}$$

Use a value for c of 1.5 which corresponds to an effective length of .815L in the x-x axis.

K = 1.0 in the y-y axis

x-x Axis

$$F_{cr} = \frac{286 \times 10^6}{\left[\frac{.815(226)}{1.25}\right]^2} = 13 \text{ KSI}$$

y-y Axis

$$F_{cr} = \frac{286 \times 10^6}{\left[\frac{226}{1.56}\right]^2} = 13.6 \text{ KSI}$$

x-x Axis is critical  $F_{cr} = 13.0 \text{ KSI}$  for double angle struts

### 30° Load Angle

Moment in diagonal member - 9.10 In. K

Axial load in diagonal member - 20.92K

Above values are member loads as a result of a 50K load applied on fwd-aft frame.

$$f_a = \frac{P}{A} = \frac{20.92}{5.34} = 3.92 \text{ KSI}$$

$$f_b = \frac{M}{S} = \frac{9.10 \text{ In. K}}{3.0 \text{ In}^3} = 3.03 \text{ KSI}$$

$$(3.03 + 3.92) \times = 13.0 \text{ KSI}$$

$$x = \frac{13.0}{6.95} = 1.87$$

$$50K(1.87) = 93.40K/\text{Frame}$$

$$93.40K(2) = 186.80K \text{ total failure load}$$

### 20° Load Angle

Member loads as a result of a 50K load applied on fore-aft frame:

$$M = 6.82 \text{ In. K}$$

$$P = 15.65 \text{ K}$$

$$f_b = \frac{M}{S} = \frac{6.82}{3.0} = 2.27 \text{ KSI}$$

$$f_a = \frac{P}{A} = \frac{15.65}{5.34} = 2.94 \text{ KSI}$$

$$(2.27 + 2.94)x = 13.0 \text{ KSI}$$

$$x = \frac{13.0}{5.21} = 2.49$$

$$50\text{K}(2.49) = 125\text{K/Frame}$$

250K total failure load

### 10° Load Angle

Member loads as a result of a 50K load applied on fore-aft frame:

$$M = 4.12 \text{ In. K}$$

$$P = 9.5 \text{ In. K}$$

$$f_b = \frac{M}{S} = \frac{4.12}{3.0} = 1.37 \text{ KSI}$$

$$f_a = \frac{P}{A} = \frac{9.5}{5.34} = 1.78 \text{ KSI}$$

$$(1.37 + 1.78)x = 13.0 \text{ KSI}$$

$$x = \frac{13.0}{3.15} = 4.12$$

$$50\text{K} \times 4.12 = 206 \text{ K/Frame}$$

412K Total failure load


### 0° Load Angle

412K total failure load





Test Tower Assembly  
(Optional Construction)



### Foundation Requirements

The following pages show foundation requirements in KIPS. In the load column, five separate load requirements are listed:


1. Foundation requirements as a result of side wind loads.
2. Foundation requirements as a result of test failure loads.
3. Foundation requirements as a result of positive or negative horizontal component of test load in the fore-aft direction.
4. Foundation requirements as a result of deadweight of overhead structure.
5. Foundation requirements as a result of deadweight of tower.

All horizontal loads are considered to be reversible, and therefore maximum foundation requirements are symmetrical about  $\bar{C}$  in both X and Y planes.

Load Table VIII is the same as load Table IX except that the horizontal component of test load is reversed.

Table X shows foundation requirements as a result of the empty load container swinging into the tower at maximum possible height of 58 feet. This condition results in maximum uplift requirement.

Foundation Loads  
Actual Loads - No Factors



| TABLE VIII. REACTION LOADS - 70-TON FAILURE CONDITION. |                     |              |              |              |              |              |             |              |
|--|---------------------|--------------|--------------|--------------|--------------|--------------|-------------|--------------|
|  | Column No. ○ (KIPS) |              |              |              |              |              |             |              |
|  | ①                   |              | ②            |              | ③            |              | ④           |              |
|  | X                   | Z            | X            | Z            | X            | Z            | X           | Z            |
| (1) Wind Load  | 2.57                | 6.99         | .19          | 3.88         | .24          | -3.30        | 2.79        | -7.57        |
| (2) Test Load  |                     | 4.47         |              | 14.01        |              | 10.05        |             | 3.22         |
| (3) + Horiz.Comp.Test                                  |                     |              | -3.09        | -14.56       | -3.09        | -14.56       |             |              |
| (4) Deadwt. Overhead                                   |                     |              |              | 4.28         |              | 4.48         |             |              |
| (5) Deadwt. Tower                                      |                     |              |              | 10.70        |              | 10.70        |             |              |
| <b>TOTAL</b>   | <b>2.57</b>         | <b>11.46</b> | <b>-2.90</b> | <b>18.31</b> | <b>-2.85</b> | <b>7.37</b>  | <b>2.79</b> | <b>-4.35</b> |
|  | ⑤                   |              | ⑥            |              | ⑦            |              | ⑧           |              |
| (1)  | 5.17                | 14.02        | .42          | 8.18         | .62          | -7.53        | 5.40        | -14.67       |
| (2)  | 10.73               | 29.12        | -2.59        | 29.80        | 2.33         | 21.40        | -1.05       | 2.85         |
| (3)  |                     |              | .01          | 14.56        | -.01         | 14.56        |             |              |
| (4)  |                     | 2.85         |              | 7.12         |              | 7.48         |             | 2.99         |
| (5)  |                     |              |              | 10.70        |              | 10.70        |             |              |
| <b>TOTAL</b>   | <b>15.90</b>        | <b>45.99</b> | <b>-1.96</b> | <b>70.36</b> | <b>2.94</b>  | <b>46.61</b> | <b>4.35</b> | <b>-8.83</b> |

| TABLE IX. REACTION LOADS - 70-TON FAILURE CONDITION. |               |              |              |              |             |              |             |              |
|--|---------------|--------------|--------------|--------------|-------------|--------------|-------------|--------------|
|  | ①             |              | ②            |              | ③           |              | ④           |              |
|  | X             | Z            | X            | Z            | X           | Z            | X           | Z            |
|  | (1) Wind Load | 2.57         | 6.99         | .19          | 3.88        | .24          | -3.30       | 2.79         |
| (2) Test Load  |               | 4.47         |              | 14.01        |             | 10.05        |             | 3.22         |
| (3) -Horiz.Comp.Test                                 |               |              | 3.09         | 14.56        | 3.09        | 14.56        |             |              |
| (4) Deadwt. Overhead                                 |               |              |              | 4.28         |             | 4.48         |             |              |
| (5) Deadwt. tower                                    |               |              |              | 10.70        |             | 10.70        |             |              |
| <b>TOTAL</b>   | <b>2.57</b>   | <b>11.46</b> | <b>3.28</b>  | <b>47.43</b> | <b>3.33</b> | <b>36.49</b> | <b>2.79</b> | <b>4.35</b>  |
|  | ⑤             |              | ⑥            |              | ⑦           |              | ⑧           |              |
| (1)  | 5.17          | 14.02        | .42          | 8.18         | .62         | -7.53        | 5.40        | -14.67       |
| (2)  | 10.73         | 29.12        | -2.59        | 29.80        | 2.33        | 21.40        | -1.05       | 2.85         |
| (3)  |               |              | .01          | 14.56        | -.01        | 14.56        |             |              |
| (4)  |               | 2.85         |              | 7.12         |             | 7.48         |             | 2.99         |
| (5)  |               |              |              | 10.70        |             | 10.70        |             |              |
| <b>TOTAL</b>   | <b>15.90</b>  | <b>45.99</b> | <b>-2.16</b> | <b>41.24</b> | <b>2.94</b> | <b>17.49</b> | <b>3.35</b> | <b>-8.83</b> |


TABLE X. REACTION LOADS - IMPACT OF LOAD CONTAINER ON TOWER.

|   | Column No. ○ KIPS |       |   |       |   |       |   |       |
|---|-------------------|-------|---|-------|---|-------|---|-------|
|   | ①                 |       | ② |       | ③ |       | ④ |       |
|   | X                 | Z     | X | Z     | X | Z     | X | Z     |
| (1) Impact Load   |                   | 22.6  |   | 52.7  |   | 52.7  |   | 22.6  |
| (2) Deadweight  |                   | 15.5  |   | 11.0  |   | 11.0  |   | 5.5   |
| TOTAL   |                   | 28.1  |   | 63.7  |   | 63.7  |   | 28.1  |
|   | ⑤                 |       | ⑥ |       | ⑦ |       | ⑧ |       |
| (1)   |                   | -22.6 |   | -52.7 |   | -52.7 |   | -22.6 |
| (2)   |                   | 5.5   |   | 11.0  |   | 11.0  |   | 5.5   |
| TOTAL   |                   | -17.1 |   | -41.7 |   | -41.7 |   | -17.1 |
|   | ⑨                 |       | ⑩ |       | ⑪ |       | ⑫ |       |
| (1)   |                   | 22.6  |   | 52.7  |   | 52.7  |   | 22.6  |
| (2)   |                   | 5.5   |   | 11.0  |   | 11.0  |   | 5.5   |
| TOTAL   |                   | 28.1  |   | 63.7  |   | 63.7  |   | 28.1  |
|   | ⑬                 |       | ⑭ |       | ⑮ |       | ⑯ |       |
| (1)   |                   | -22.6 |   | -57.7 |   | -52.7 |   | -22.6 |
| (2)   |                   | 5.5   |   | 11.0  |   | 11.0  |   | 5.5   |
| TOTAL   |                   | -17.1 |   | -41.7 |   | -41.7 |   | -17.1 |
| <p>(1) 8.0K weight moving horizontally strikes tower at a velocity of 20.6 Ft/Sec. Resulting reaction at base of tower is shown in KIPS.</p> <p>(2) Deadweight of overhead steel and deadweight of tower acting at base of tower in KIPS.</p> |                   |       |   |       |   |       |   |       |


TABLE XI DEADWEIGHTS.

| Dwg. No.      | Nomenclature   | Qty. | Dead Wt/Assy. | Total Dead Wt. |
|---------------|----------------|------|---------------|----------------|
| SK301-11304-1 | Tower Assy.    | 1    | 38723         | 38723          |
| SK301-11304-2 | Tower Assy.    | 1    | 42750         | 42750          |
| SK301-11302-1 | Hoist Module   | 2    | 2470          | 4940           |
| -2            | Davit Mount    | 1    | 6207          | 6207           |
| -3            | Module Support | 2    | 6274          | 12548          |
| -4            | Platform Assy. | 1    | 831           | 831            |
| -6            | Platform Assy. | 1    | 831           | 831            |
| SK301-11302-5 | Beam Assy.     | 2    | 8081          | 16162          |
| —             | —              | —    | —             | —              |
| Test Hoist    |                | 2    | 1700          | 3400           |
| Aux. Hoist    |                | 1    | 3365          | 3365           |
| Mast          |                | 1    | 3965          | 3965           |
| —             | —              | —    | —             | —              |
| TOTAL         |                |      |               | 133,722#       |

Control Room Shelter



Control room shelter designed for a 50-Lb/Ft<sup>2</sup> wind load on projected frontal area. Roof is designed for 30-Lb/Ft<sup>2</sup> snow load on vertical projected area.



$$M = \frac{wl^2}{8} = \frac{2.5 \text{ Lb/In.} (45)^2}{8}$$

$$M = .634 \text{ In. K}$$

$$f = \frac{M}{S} = \frac{.634}{.0532} = 11.9 \text{ KSI}$$


$$S = .0532 \text{ In.}^3 \text{ per ft of width}$$

Standard 2-2/3 x 1/2  
Galvanized Corr. Sheet

Control Room Shelter

Roof Load/Running In. of Rafter

5.0 Lb Snow  
 .6  
 5.6 Lb




$$M = \frac{Wl^2}{8} = \frac{5.6(180)^2}{8} = 22.7 \text{ In.-Lb}$$

$$f = \frac{M}{S} = \frac{22.7}{1.1} \text{ In. K} = 20.6 \text{ KSI}$$

Wind Load/Stud

100 Lb/Ft 8.32 Lb/In.




$$M = \frac{Wl^2}{8} = \frac{8.32(96)^2}{8} = 9.6 \text{ In. K}$$

$$f = \frac{M}{S} = \frac{9.6}{1.1} = 8.73 \text{ KSI}$$

Sill Wind Load


250 Lb/Ft. 20.8 Lb/Ft



$$M = \frac{Wl^2}{8} = \frac{20.8(168)^2}{8} = 73.3 \text{ In. K}$$

$$f = \frac{M}{S} = \frac{73.3}{1.732} = 42.3 \text{ KSI}$$

Add Horizontal Braces @ 8-Ft Level





APPENDIX II  
DRAWINGS - DESIGN LAYOUTS

The integrated test rig is described by the following drawings which are provided as the listed figures.

| <u>Figure</u> | <u>Drawing No.</u> | <u>Title</u>  |
|---------------|--------------------|---|
| 49            | SK301-11277        | Structures Installation - HLH Hoist Test                        |
| 50            | SK301-11304        | HLH Hoist Tower Assembly  |
| 51            | SK301-11302        | HLH Overhead Assembly   |
| 52            | X72-002-AS-YD3/1   | Site Plan - Paving and Utilities, Plan and Sections             |
| 53            | X72-002-AS-YD3/2   | Foundations - Plans, Sections and Details                       |
| 54            | X73-003-AS-YD3/2   | Pneumatic Power Generator Shelter HLH/ATC Cargo Handling System |
| 55            | X73-003-AS-YD3/3   | Control Room Plans, Elevations and Section                      |
| 56            | X73-003-AS-YD3/4   | Control Room Section and Details                                |
| 57            | V73-003-AS-YD3     | Removable Handrail Details                                      |
| 58            | X73-003-M-YD3/1    | Piping Arrangement, Test Tower Top Section                      |
| 59            | X73-003-M-YD3/2    | Piping Arrangement, Test Tower Base                             |
| 60            | X73-003-M-YD3/3    | Fuel Piping Arrangement - PPG Unit                              |
| 61            | V73-001-E-YD3      | Electrical Single Line Diagram                                  |
| 62            | X73-003-E-YD3/1    | Electrical HLH/ATC Cargo Handling Test Rig                      |
| 63            | X73-003-E-YD3/2    | Control Room Electrical Layout                                  |
| 64            | SK301-11564        | Load Controlling Crewman Platform - Integrated Test Rig         |

| <u>Figure</u> | <u>Drawing No.</u> | <u>Title</u>                           |
|---------------|--------------------|--|
| 65            | SK301-11676        | System Test - Drawing Tree             |
| 66            | ST40972            | Lifting Sling, Hoist/Module            |
| 67            | ST51273-1          | Hoist Lifting Fixture                  |
| 68            | SK301-11694        | Integrated Test Rig - System<br>Wiring |
| 69            | ST30861            | Instrumentation Drawing Tree           |





Figure 49. Structures Installation - HLH Hoist Test.

A

80% RECRETE PRECASTE PANEL

BOLT AS REQD

DRILL 1/2" DIA HOLE  
IN SK 301-11302-2  
TO MATCH WAST ASSY  
1/2" DIA 1/2" GRIP  
WAST BOLT  
WASTER AS REQD  
1/2" DIA HEAVY HEX NUT  
(TYP 2 PLACES)




DRILL 1/2" DIA HOLE  
IN SK 301-11302-2  
TO MATCH WAST ASSY  
1/2" DIA 1/2" GRIP  
WAST BOLT  
WASTER AS REQD  
1/2" DIA HEAVY HEX NUT  
(TYP 2 PLACES)

SECT 105  
A-18

WAST ASSY

SECTION 1A9



40% RECRETE PRECASTE PANEL


LOCATE AS REQUIRED FOR  
TIE-DOWN OF FLOORING PANEL  
(TYP 8 PLACES)

CUTOUT GRAB IN FLOORING SLAB (2 PLACES)

SK 301-11304-2 ASSY  
(STAIRWAY & LANDING  
NOT SHOWN FOR CLARITY)

DRILL 1/2" DIA HOLE  
IN SK 301-11302-2  
TO MATCH WAST ASSY  
1/2" DIA 1/2" GRIP  
WAST BOLT  
WASTER AS REQD  
1/2" DIA HEAVY HEX NUT  
(TYP 2 PLACES)


SECT 205  
A-18



END


SK301-11277 1

B




10. 9907MO MAST ASSY

DRILL 1/2" DIA. HOLE  
IN SK 301-11302-1 TO MOUNT  
TO MAST SK 301-11302-2  
1/2" DIA. HOLE IN SK 301-11302-3  
TO MOUNT SK 301-11302-4  
TO MOUNT SK 301-11302-5  
(2 PLACES)



END VIEW  
NO SIZE

3/4" DIA. "E" DOWN BOLTS (2 PLACES) (1X1)




SK301-112

C

GENERAL NOTES:

1. ALL FABRICATION & ERECTION PER AISC SPECIFICATIONS.
2. SEE VERTICAL WORK STATEMENT FOR FINISH PAINT COLOR REQUIREMENTS.

3. PLANE 'A', PLANE 'B', PLANE 'C' & PLANE 'D' TO BE PERPENDICULAR TO PLANE 'A' WITHIN  $\pm 1/8"$  OR 0.010.
4. SHIM AS REQD TO PROVIDE PROPER ALIGNMENT OF SK 301-11302-1 HOIST MODULE.
5. SHIM 'F' AS REQD TO INSURE PROPER ALIGNMENT OF SK 301-11302-5.
6. TORQUE PER AISC SPECIFICATIONS.
7. WELD TO SK 301-1302-9 AND BOLT TO SK 301-1302-7 WITH  $3/8"$  DIA. BOLTS.



| QTY | DESCRIPTION         | UNIT               | REMARKS                             | DATE |
|-----|---------------------|--------------------|-------------------------------------|------|
| 1   | 4                   | 100' - 5           |                                     |      |
| 4   | 1 40' x 10'         | STEEL DECK PANEL   | SA. HANCE STEEL PRODUCTS COMPANY    |      |
| 1   | CAT NO 770740       | JIB CRANE          | ORANGE RANGE HOIST & TOWER DIVISION |      |
| 4   | 1 1/2"              | NUT                | HEAVY HEX                           |      |
| 40  | 1                   | NUT                | HEAVY HEX                           |      |
| 6   | 3/4"                | NUT                | HEAVY HEX                           |      |
| 8   | 3/4"                | NUT                | HEAVY HEX                           |      |
| 16  | 2 DIA 1/2" GRIP     | BOLT               | A325 HEX HD                         |      |
| 16  | 2 DIA 1/2" GRIP     | BOLT               | A325 HEX HD                         |      |
| 8   | 2 DIA 1/2" GRIP     | BOLT               | A325 HEX HD                         |      |
| 8   | 2 DIA 1/2" GRIP     | BOLT               | A325 HEX HD                         |      |
| 4   | 1 1/2 DIA 1/2" GRIP | BOLT               | A325 HEX HD                         |      |
| 1   | 1                   | ANGLE              | 3" x 3" x 1/2" C                    |      |
| 8   | 2                   | CHANNEL            | 6" C & L 70# x 400                  |      |
| 1   | SK 301-1302-7       | STAIRWAY ASSY      | 04                                  |      |
| 1   | SK 301-1302-6       | PLATFORM ASSY      | 05                                  |      |
| 2   | SK 301-1302-5       | BEAM ASSY          | 06                                  |      |
| 1   | SK 301-1302-4       | PLATFORM ASSY      | 04                                  |      |
| 2   | SK 301-11302-3      | WORK PLATFORM ASSY | 10                                  |      |
| 1   | SK 301-1302-2       | DAVY HANGING ASSY  | 09                                  |      |
| 2   | SK 301-1302-1       | HOIST MODULE ASSY  | 09                                  |      |
| 1   | SK 301-1304-2       | TOWER ASSY         | 04                                  |      |
| 1   | SK 301-1304-1       | TOWER ASSY         | 05                                  |      |
| 1   | 1                   | STRUCTURE'S INSTL  |                                     |      |

| DATE | BY | DESCRIPTION | REV |
|------|----|-------------|-----|
|      |    |             |     |

|  |   |
|--|---|
| STRUCTURES INSTL<br>HLM HOIST TEST<br>J77212 SK301-11277 | DATE: 11/27/88<br>TIME: 10:30 AM<br>BY: [Signature]<br>CHECKED: [Signature] |
|--|---|

E




Figure 50. HLH Hoist Tower Assembly (Sheet 1)



139

A

Preceding page blank







**GENERAL NOTES**

- 1. SEE P/L FOR DIMENSIONS NOT SHOWN
- 2. BREAK ALL SHARP CORNERS
- 3. ALL WELDS TO BE MADE IN ACCORDANCE WITH AISC AND AWS STANDARDS.
- 4. ALL STEEL WILL BE A572 OR AN APPROVED EQUIVALENT
- 5. MAXIMUM STRAIGHTNESS DEVIATION PER 100' OF THE OVERALL LENGTH
- 6. ANY CUTTING IS PERMISSIBLE ON ALL PARTS EXCEPT THAT THE HOLES ARE NOT TO BE FLAME CUT
- 7. PAINT PER AISC SPECIFICATION (FIELD PAINT). SEE VERTICAL WHEN STATEMENT FOR PAINT REQUIREMENTS
- 8. ALL CONNECTIONS MAY BE MADE IN THE FABRICATION OF TOWERS
- 9. STRUCTURAL TOLERANCES TO BE PER AISC STANDARD UNLESS OTHERWISE NOTED ON DWG
- 10. ALL WELD & RILLLET WELD UNLESS OTHERWISE NOTED

- 11. ALL WELDS TO BE MADE BY TACK WELDING
- 12. ALL WELDS TO BE MADE BY TACK WELDING
- 13. OPTIONAL TO CHAMFER UNDER EDGES (R<sub>2</sub> = 1/8") CLEAR RADIUS
- 14. ALL WELDS TO BE MADE BY TACK WELDING
- 15. SEE FOR KEYWAYS AS REQD.
- 16. MAKE SECONDARY STEEL & BRACE BOLTED CONNECTIONS BOLTED AT APPROPRIATE PLACES FOR ORIENTATION OF TOWER
- 17. SEE DETAIL 387-100 IN PART 2
- 18. ALL WELDS TO BE MADE BY TACK WELDING
- 19. ALL WELDS TO BE MADE BY TACK WELDING
- 20. ALL WELDS TO BE MADE BY TACK WELDING
- 21. ALL WELDS TO BE MADE BY TACK WELDING
- 22. ALL WELDS TO BE MADE BY TACK WELDING
- 23. ALL WELDS TO BE MADE BY TACK WELDING
- 24. ALL WELDS TO BE MADE BY TACK WELDING
- 25. ALL WELDS TO BE MADE BY TACK WELDING
- 26. ALL WELDS TO BE MADE BY TACK WELDING
- 27. ALL WELDS TO BE MADE BY TACK WELDING
- 28. ALL WELDS TO BE MADE BY TACK WELDING
- 29. ALL WELDS TO BE MADE BY TACK WELDING
- 30. ALL WELDS TO BE MADE BY TACK WELDING
- 31. ALL WELDS TO BE MADE BY TACK WELDING
- 32. ALL WELDS TO BE MADE BY TACK WELDING
- 33. ALL WELDS TO BE MADE BY TACK WELDING
- 34. ALL WELDS TO BE MADE BY TACK WELDING
- 35. ALL WELDS TO BE MADE BY TACK WELDING
- 36. ALL WELDS TO BE MADE BY TACK WELDING
- 37. ALL WELDS TO BE MADE BY TACK WELDING
- 38. ALL WELDS TO BE MADE BY TACK WELDING
- 39. ALL WELDS TO BE MADE BY TACK WELDING
- 40. ALL WELDS TO BE MADE BY TACK WELDING
- 41. ALL WELDS TO BE MADE BY TACK WELDING
- 42. ALL WELDS TO BE MADE BY TACK WELDING
- 43. ALL WELDS TO BE MADE BY TACK WELDING
- 44. ALL WELDS TO BE MADE BY TACK WELDING
- 45. ALL WELDS TO BE MADE BY TACK WELDING
- 46. ALL WELDS TO BE MADE BY TACK WELDING
- 47. ALL WELDS TO BE MADE BY TACK WELDING
- 48. ALL WELDS TO BE MADE BY TACK WELDING
- 49. ALL WELDS TO BE MADE BY TACK WELDING
- 50. ALL WELDS TO BE MADE BY TACK WELDING

|  |  |  |  |  |    |     |             |  |      |
|--|--|--|--|--|----|-----|-------------|--|------|
|  |  |  |  |  | 6  | 120 | STREET      |  | 4.0  |
|  |  |  |  |  | 5  | 115 |             |  |      |
|  |  |  |  |  | 5  | 115 |             |  |      |
|  |  |  |  |  | 20 |     |             |  |      |
|  |  |  |  |  |    |     |             |  |      |
|  |  |  |  |  | 4  | 100 | STREET      |  | 4.0  |
|  |  |  |  |  | 4  | 100 | SPACER      |  | 5.0  |
|  |  |  |  |  | 4  |     | GUSSET      |  | 10.0 |
|  |  |  |  |  |    |     | HOLEY       |  | 20.0 |
|  |  |  |  |  |    |     | BASE PLATE  |  | 10.0 |
|  |  |  |  |  | 4  |     | BRACKET     |  | 10.0 |
|  |  |  |  |  |    |     | BRACE       |  | 10.0 |
|  |  |  |  |  |    |     | BRACE       |  | 10.0 |
|  |  |  |  |  |    |     | STUB BEAM   |  | 10.0 |
|  |  |  |  |  |    |     | BEAM        |  | 10.0 |
|  |  |  |  |  |    |     | BEAM        |  | 10.0 |
|  |  |  |  |  |    |     | COLUMN      |  | 10.0 |
|  |  |  |  |  |    |     | COLUMN      |  | 10.0 |
|  |  |  |  |  |    |     | TOWER PLATE |  | 10.0 |
|  |  |  |  |  |    |     | TOWER PLATE |  | 10.0 |

|  |  |  |  |  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |  |  |
|  |  |  |  |  |  |  |  |  |  |  |  |

**SK-301-304**




C

D

6 5 4 3 2 1

317

H  
G  
F  
E  
D  
C  
B  
A



IN AISC AND AWS STANDARDS.  
 EQUIVALENT  
 300 OF THE OVERALL LENGTH  
 PARTS EXCEPT THAT THE HOLES ARE NOT TO BE FLAME CUT  
 (PAINT). SEE VERTICAL WORK STATEMENT FOR ALL REQUIREMENTS  
 LOCATION OF JOINTS  
 DATED UNLESS OTHERWISE NOTED ON DWG  
 OTHERWISE NOTED.

1057 N...  
 14 41...  
 455 47... CLEAR RADIUS

... CONNECTING... NOTED AT SPUR PLATE

LOCATION:  
 10 JACK WELLS...  
 165...  
 2...  
 3...  
 4...

|   |  |  |  |  |  |  |   |            |    |    |  |  |  |
|---|--|--|--|--|--|--|---|------------|----|----|--|--|--|
| 6 |  |  |  |  |  |  | 6 | TRUT       | 40 | 40 |  |  |  |
| 5 |  |  |  |  |  |  | 5 |            | 4  | 4  |  |  |  |
| 4 |  |  |  |  |  |  | 4 |            |    |    |  |  |  |
| 3 |  |  |  |  |  |  | 3 |            |    |    |  |  |  |
| 2 |  |  |  |  |  |  | 2 |            |    |    |  |  |  |
| 1 |  |  |  |  |  |  | 1 |            |    |    |  |  |  |
|   |  |  |  |  |  |  | 4 |            |    |    |  |  |  |
|   |  |  |  |  |  |  | 4 | TRUT       | 40 | 40 |  |  |  |
|   |  |  |  |  |  |  | 4 | SPAKER     | 40 | 40 |  |  |  |
|   |  |  |  |  |  |  | 4 | JUMPER     | 40 | 40 |  |  |  |
|   |  |  |  |  |  |  |   | BASE PLATE |    |    |  |  |  |
|   |  |  |  |  |  |  | 4 | BRACKET    | 40 | 40 |  |  |  |
|   |  |  |  |  |  |  |   | PLACER     |    |    |  |  |  |
|   |  |  |  |  |  |  |   | PLACE      |    |    |  |  |  |
|   |  |  |  |  |  |  |   | STUB BEAM  |    |    |  |  |  |
|   |  |  |  |  |  |  |   | BEAM       |    |    |  |  |  |
|   |  |  |  |  |  |  |   | BEAM       |    |    |  |  |  |
|   |  |  |  |  |  |  |   | COLUMN     |    |    |  |  |  |
|   |  |  |  |  |  |  |   | COLUMN     |    |    |  |  |  |

SK 301-11304


|   |   |   |   |   |   |
|---|---|---|---|---|---|
| 6 | 5 | 4 | 3 | 2 | 1 |
|   |   |   |   |   |   |
|   |   |   |   |   |   |
|   |   |   |   |   |   |
|   |   |   |   |   |   |
|   |   |   |   |   |   |

SK-301-1304


| REV | DESCRIPTION | DATE | BY | CHECKED | APPROVED | SCALE | TITLE |
|-----|-------------|------|----|---------|----------|-------|-------|
|     |             |      |    |         |          |       |       |
|     |             |      |    |         |          |       |       |
|     |             |      |    |         |          |       |       |
|     |             |      |    |         |          |       |       |

**THE BOEING COMPANY**  
 COMMERCIAL AIRPLANE DIVISION  
**HEAVY LIFT HELICOPTER**  
 TOWER ASSEMBLY  
 SK-301-1304


6 5 4 3 2 1



TOWER ASSY  
REAR VIEW



BRACKET ASSY



DETAIL 1B7  
(TYPE B PLACES)

VIEW 1A  
1011-1013  
1014-1016  
1017-1019  
1020-1022  
1023-1025  
1026-1028  
1029-1031  
1032-1034  
1035-1037  
1038-1040  
1041-1043  
1044-1046  
1047-1049  
1050-1052  
1053-1055  
1056-1058  
1059-1061  
1062-1064  
1065-1067  
1068-1070  
1071-1073  
1074-1076  
1077-1079  
1080-1082  
1083-1085  
1086-1088  
1089-1091  
1092-1094  
1095-1097  
1098-10100

A

B

Figure 50. HLH Hoist Tower Assembly (Sheet 2).

Preceding page blank

ALL DIMENSIONS  
ARE IN INCHES  
UNLESS OTHERWISE  
SPECIFIED  
DIMENSIONS TO CENTER  
UNLESS OTHERWISE  
SPECIFIED

2. PREPARE ASSEMBLY  
DRAWING

1. PREPARE  
DRAWING

2

210

-B: ASSY

VIEW A10  
25 E-32 WASHERS FOR CLARITY

DETAIL 23  
(4 PLACES)

EW 00

10-00

2. DIA HOLE  
2. DIA PLACES  
2. DIA PLACES  
2. DIA PLACES  
2. DIA PLACES  
2. DIA PLACES  
2. DIA PLACES

DETA 07

WASHERS FOR CLARITY  
20 TO WASHER (2 PLACES)

VIEW A8  
(NO ASSY NOT SHOWN FOR CLARITY)

A8-AS

DETAIL A7  
(10 PLACES)

NOT 37 TO ACCOMMODATE  
25 E-32

10 ASSY


WASHERS FOR CLARITY  
20 TO WASHER (10 PLACES)  
CHAMFER 45° R 1/16 PLACES

SK301-11304 121

B

C

SECTION 304  
PAGE 10  
OF 12




SECTION 3A4  
(1 OF 4 PAGES)

2 DIA HOLE THRU  
2 DIA 1/2 IS LIP  
2 1/2 S STEEL  
2 1/2 IN DIA  
2 1/2 DIA HOLE THRU  
2 1/2 DIA HOLE THRU  
(11)

DETAIL 3B7

DETAIL 3C4

DETAIL 3C7



-1 TOWER ASSY


1A7  
(1 OF 5)

1A6-04





C

SK 304130

D



SECTION 3A4  
(TYP 4 PLACES)





VIEW 1A6  
OF STRUCT ASSY NOT SHOWN  
IN THIS VIEW FOR CLARITY




SK-30-H1304 12

D

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |






CHAMFER 45° (RPL)



|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |

|   |   |  |
|---|---|--|
| APPROVED BY: _____<br>DATE: _____<br>DRAWN BY: _____<br>CHECKED BY: _____<br>TITLE: _____ | PART NO: _____<br>QUANTITY: _____<br>UNIT: _____<br>MATERIAL: _____<br>FINISH: _____<br>WEIGHT: _____<br>DIMENSIONS: _____<br>TOLERANCES: _____<br>SURFACE: _____<br>MARKING: _____<br>STORAGE: _____<br>HANDLING: _____<br>INSPECTION: _____<br>TESTING: _____<br>RECORDS: _____ | HEAVY LIFT HELICOPTER<br>HOIST TOWER ASSY<br>J77275K-301-1130A |
|---|---|--|

E



VIEW IC12-2  
 -39 LANDING ASSY.  
 -40 ASSY OPP.  
 ALL WELDED CONST

SK-30-11304-13

Figure 50. HLH Hoist Tower Assembly (Sheet 3).

A

B

Preceding page blank














Figure 51. HLH Overhead Assembly.

GENERAL NOTE  
 1. SEE DRAWING Q11  
 2. BREAK ALL SHAPES  
 3. ALL WELDS TO  
 4. ALL STEEL WITH  
 5. MAXIMUM STAIN  
 6. FLAME CUTTING  
 7. TO BE FLAME C  
 8. 1/4" PER A.S.C.  
 9. AT SECTION OF I  
 10. STRUCTURAL TOU


L1 340 OPENING  
 L2 USE FOR KICK



1. 144 A TO DIE (NPI)  
 2. 143 A TO DIE (NPI)  
 3. 142 A TO DIE (NPI)

8. 141 A TO DIE (NPI)  
 9. 140 A TO DIE (NPI)  
 10. 139 A TO DIE (NPI)  
 11. 138 A TO DIE (NPI)  
 12. 137 A TO DIE (NPI)  
 13. 136 A TO DIE (NPI)  
 14. 135 A TO DIE (NPI)  
 15. 134 A TO DIE (NPI)  
 16. 133 A TO DIE (NPI)  
 17. 132 A TO DIE (NPI)  
 18. 131 A TO DIE (NPI)  
 19. 130 A TO DIE (NPI)  
 20. 129 A TO DIE (NPI)  
 21. 128 A TO DIE (NPI)  
 22. 127 A TO DIE (NPI)  
 23. 126 A TO DIE (NPI)  
 24. 125 A TO DIE (NPI)  
 25. 124 A TO DIE (NPI)  
 26. 123 A TO DIE (NPI)  
 27. 122 A TO DIE (NPI)  
 28. 121 A TO DIE (NPI)  
 29. 120 A TO DIE (NPI)  
 30. 119 A TO DIE (NPI)  
 31. 118 A TO DIE (NPI)  
 32. 117 A TO DIE (NPI)  
 33. 116 A TO DIE (NPI)  
 34. 115 A TO DIE (NPI)  
 35. 114 A TO DIE (NPI)  
 36. 113 A TO DIE (NPI)  
 37. 112 A TO DIE (NPI)  
 38. 111 A TO DIE (NPI)  
 39. 110 A TO DIE (NPI)  
 40. 109 A TO DIE (NPI)  
 41. 108 A TO DIE (NPI)  
 42. 107 A TO DIE (NPI)  
 43. 106 A TO DIE (NPI)  
 44. 105 A TO DIE (NPI)  
 45. 104 A TO DIE (NPI)  
 46. 103 A TO DIE (NPI)  
 47. 102 A TO DIE (NPI)  
 48. 101 A TO DIE (NPI)  
 49. 100 A TO DIE (NPI)  
 50. 99 A TO DIE (NPI)  
 51. 98 A TO DIE (NPI)  
 52. 97 A TO DIE (NPI)  
 53. 96 A TO DIE (NPI)  
 54. 95 A TO DIE (NPI)  
 55. 94 A TO DIE (NPI)  
 56. 93 A TO DIE (NPI)  
 57. 92 A TO DIE (NPI)  
 58. 91 A TO DIE (NPI)  
 59. 90 A TO DIE (NPI)  
 60. 89 A TO DIE (NPI)  
 61. 88 A TO DIE (NPI)  
 62. 87 A TO DIE (NPI)  
 63. 86 A TO DIE (NPI)  
 64. 85 A TO DIE (NPI)  
 65. 84 A TO DIE (NPI)  
 66. 83 A TO DIE (NPI)  
 67. 82 A TO DIE (NPI)  
 68. 81 A TO DIE (NPI)  
 69. 80 A TO DIE (NPI)  
 70. 79 A TO DIE (NPI)  
 71. 78 A TO DIE (NPI)  
 72. 77 A TO DIE (NPI)  
 73. 76 A TO DIE (NPI)  
 74. 75 A TO DIE (NPI)  
 75. 74 A TO DIE (NPI)  
 76. 73 A TO DIE (NPI)  
 77. 72 A TO DIE (NPI)  
 78. 71 A TO DIE (NPI)  
 79. 70 A TO DIE (NPI)  
 80. 69 A TO DIE (NPI)  
 81. 68 A TO DIE (NPI)  
 82. 67 A TO DIE (NPI)  
 83. 66 A TO DIE (NPI)  
 84. 65 A TO DIE (NPI)  
 85. 64 A TO DIE (NPI)  
 86. 63 A TO DIE (NPI)  
 87. 62 A TO DIE (NPI)  
 88. 61 A TO DIE (NPI)  
 89. 60 A TO DIE (NPI)  
 90. 59 A TO DIE (NPI)  
 91. 58 A TO DIE (NPI)  
 92. 57 A TO DIE (NPI)  
 93. 56 A TO DIE (NPI)  
 94. 55 A TO DIE (NPI)  
 95. 54 A TO DIE (NPI)  
 96. 53 A TO DIE (NPI)  
 97. 52 A TO DIE (NPI)  
 98. 51 A TO DIE (NPI)  
 99. 50 A TO DIE (NPI)  
 100. 49 A TO DIE (NPI)  
 101. 48 A TO DIE (NPI)  
 102. 47 A TO DIE (NPI)  
 103. 46 A TO DIE (NPI)  
 104. 45 A TO DIE (NPI)  
 105. 44 A TO DIE (NPI)  
 106. 43 A TO DIE (NPI)  
 107. 42 A TO DIE (NPI)  
 108. 41 A TO DIE (NPI)  
 109. 40 A TO DIE (NPI)  
 110. 39 A TO DIE (NPI)  
 111. 38 A TO DIE (NPI)  
 112. 37 A TO DIE (NPI)  
 113. 36 A TO DIE (NPI)  
 114. 35 A TO DIE (NPI)  
 115. 34 A TO DIE (NPI)  
 116. 33 A TO DIE (NPI)  
 117. 32 A TO DIE (NPI)  
 118. 31 A TO DIE (NPI)  
 119. 30 A TO DIE (NPI)  
 120. 29 A TO DIE (NPI)  
 121. 28 A TO DIE (NPI)  
 122. 27 A TO DIE (NPI)  
 123. 26 A TO DIE (NPI)  
 124. 25 A TO DIE (NPI)  
 125. 24 A TO DIE (NPI)  
 126. 23 A TO DIE (NPI)  
 127. 22 A TO DIE (NPI)  
 128. 21 A TO DIE (NPI)  
 129. 20 A TO DIE (NPI)  
 130. 19 A TO DIE (NPI)  
 131. 18 A TO DIE (NPI)  
 132. 17 A TO DIE (NPI)  
 133. 16 A TO DIE (NPI)  
 134. 15 A TO DIE (NPI)  
 135. 14 A TO DIE (NPI)  
 136. 13 A TO DIE (NPI)  
 137. 12 A TO DIE (NPI)  
 138. 11 A TO DIE (NPI)  
 139. 10 A TO DIE (NPI)  
 140. 9 A TO DIE (NPI)  
 141. 8 A TO DIE (NPI)  
 142. 7 A TO DIE (NPI)  
 143. 6 A TO DIE (NPI)  
 144. 5 A TO DIE (NPI)  
 145. 4 A TO DIE (NPI)  
 146. 3 A TO DIE (NPI)  
 147. 2 A TO DIE (NPI)  
 148. 1 A TO DIE (NPI)

PLATFORM ASSY  
 100 CONST. L.M.A. HEAD



1. 480 A TO DIE (NPI)  
 2. 470 A TO DIE (NPI)

3. 460 A TO DIE (NPI)  
 4. 450 A TO DIE (NPI)

5. 440 A TO DIE (NPI)  
 6. 430 A TO DIE (NPI)

7. 420 A TO DIE (NPI)  
 8. 410 A TO DIE (NPI)

9. 400 A TO DIE (NPI)  
 10. 390 A TO DIE (NPI)

11. 380 A TO DIE (NPI)  
 12. 370 A TO DIE (NPI)

PLATFORM ASSY

|     |     |      |      |      |      |    |      |      |
|-----|-----|------|------|------|------|----|------|------|
| 301 | 302 | BANK | BVET | CODE | DATE | BY | CHKD | APPD |
|-----|-----|------|------|------|------|----|------|------|


B












3 WORK PLATFORM ASSY

B

SK-30-11302 2

C



← SYM




4" x 12" x 960" LONG GRIP STRUT SAFETY GRATING  
(TYP 32 PLACES)

TACK WELD 3 PLACES EACH PLANK (TYP)

1" DIA 3/8" DIA HOLE  
THRU LWR FLANGE ONLY  
(TYP 8 PLACES)

20 (TYP)


20 (TYP)



- 3 WORK PLATFORM ASSY

C

D





- 1 W.D. HOIST MOUNTING ASSY

ALL WELDED CONST - 3/8 MIN WELD

REV ISN DATE BY

|  |  |  |  |  |
|--|--|--|--|--|
|  |  |  |  |  |
|  |  |  |  |  |
|  |  |  |  |  |
|  |  |  |  |  |
|  |  |  |  |  |
|  |  |  |  |  |
|  |  |  |  |  |

D



1 FWD HOIST MOUNTING ASSY  
ALL WELDED CONST 1/4 MIN WELD

|        |  |      |  |                       |  |      |  |       |  |
|--------|--|------|--|-----------------------|--|------|--|-------|--|
| REV    |  | DATE |  | BY                    |  | CHKD |  | APP'D |  |
|        |  |      |  |                       |  |      |  |       |  |
| STALEY |  |      |  | HEAVY LIFT HELICOPTER |  |      |  |       |  |
|        |  |      |  | OVERHEAD ASSY         |  |      |  |       |  |
|        |  |      |  | J772725K-301-1130Z    |  |      |  |       |  |
|        |  |      |  | 1 of 2                |  |      |  |       |  |

E



TEST STRUCTURE

4" WOOD PLANT FROM E.P.C.  
 23' 0" CENTERLINE ON ACCESS ROAD


ASPHALT WEAR  
 SCALE 1"=3' 0"

8" 3A MODIFIED STONE  
 COMPACTED TO 95% MAX  
 DENSITY AT OPT. MOISTURE


EXISTING SUBGRADE

SECTION (C)  
 SCALE 1"=10'

SECTION (B)  
 SCALE 1"=3' 0"




SECTION (A)  
 SCALE 1"=3' 0"



SECTION (D)  
 SCALE 1"=10'

ALL NEW PAVEMENT TO BE SMOOTH  
 AND STRAIGHT EDGE.



SECTION (E)  
 SCALE 1"=3' 0"

|                  |            |  |                       |             |
|------------------|------------|--|-----------------------|-------------|
| DRAWN BY: LIS/SR | DATE: 8/72 | TITLE:                                     | IR 223660             | SHEET NO. 1 |
| CHECKED BY:      | DATE:      | HLH/ATC CARGO HANDLING SYSTEM              |                       |             |
| APP. BY: WJ/NC   | DATE: 8/72 | SITE PLAN                                  |                       |             |
| APP. BY:         | DATE:      | PAVING CUTS AND PLAN LOCATIONS             | B                     | REVISIONS   |
| APP. BY:         | DATE:      |  | A                     | AS SHOWN    |
| APP. BY:         | DATE:      | PLANT ENGINEERING                          | REV.                  | DATE        |
| SCALE: AS SHOWN  |            | THE BERINO COMPANY                         |                       |             |
|                  |            | 10700 BROADWAY, PHILADELPHIA, PENNSYLVANIA |                       |             |
|                  |            |  | DWG NO. X72007 AS YD3 |             |

B







Figure 53. Foundations - Plans, Sections and Details.

Preceding page blank

A



GENERAL NOTES

1. ALL REINFORCING STEEL SHALL BE SUPPLIED BY THE MANUFACTURER'S NAME AND SHALL BE CONFORMANT WITH THE REQUIREMENTS OF THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION, INC. (AISC) TABLE 3.1, AS PER THE AISC CODE OF PRACTICE, AND SHALL BE FURNISHED WITH PROPER CERTIFICATION TO THE CONTRACTOR.
2. REINFORCING STEEL SHALL BE FURNISHED WITH PROPER CERTIFICATION TO THE CONTRACTOR.
3. ANCHOR BOLTS TO BE USED SHALL BE FURNISHED WITH PROPER CERTIFICATION TO THE CONTRACTOR.
4. EMBEDMENT AND PROTECTION SHALL BE AS SHOWN ON THE DRAWINGS.
5. FORMS SHALL BE USED TO CAST THE CONCRETE AND SHALL BE CAPABLE OF WITHSTANDING THE FULL WEIGHT OF THE CONCRETE AND THE WEIGHT OF THE FORMS.
6. THE CONCRETE SHALL BE PLACED AND COMPACTED TO THE FULL DEPTH AND WIDTH OF THE FORMS.
7. EXCAVATIONS TO BE MADE TO EXPOSE THE ANCHOR BOLTS SHALL BE MADE TO THE FULL DEPTH AND WIDTH OF THE ANCHOR BOLTS.
8. EACH ANCHOR BOLT TO BE PLACED AS A CENTRE LINE WITH A TOLERANCE OF ±1/4" FROM THE CENTRE LINE.
9. EACH ANCHOR BOLT TO BE FURNISHED WITH PROPER CERTIFICATION TO THE CONTRACTOR.
10. MATERIALS TO BE USED FOR THE ANCHOR BOLTS SHALL BE FURNISHED WITH PROPER CERTIFICATION TO THE CONTRACTOR.
11. EXCESSIVE SAND OR DIRT TO BE REMOVED FROM THE AREA SURROUNDING THE ANCHOR BOLTS AND WETTED THOROUGHLY PRIOR TO PLACEMENT OF CONCRETE AGAINST IT.



ANCHOR PITS - PLAN & SECTION  
SCALE: 1/2"=1'-0"

Reproduced from best available copy.



SUPPLEMENTARY REIN. AT ANCHOR PITS  
SCALE: (NO SCALE)

40 # 1/2" REIN. TOP  
40 # 1/2" REIN. BOTTOM  
TH THIN SLAB REIN.





|                 |                   |                   |
|-----------------|-------------------|-------------------|
| DESIGN BY: [ ]  | DATE: [ ]         | PROJECT: [ ]      |
| CHECK BY: [ ]   | DATE: [ ]         | PROJECT: [ ]      |
| APP. BY: [ ]    | DATE: [ ]         | PROJECT: [ ]      |
| SCALE: AS NOTED | PLANT ENGINEERING | DWG. NO. X-22-460 |

etails.

B








|                   |      |       |
|-------------------|------|-------|
| DESIGNED BY       | DATE | SCALE |
| CHECKED BY        | DATE | SCALE |
| APPROVED BY       | DATE | SCALE |
| PLANT ENGINEERING |      |       |
| BOEING            |      |       |

ter, HLH/ATC

B



Reproduced from  
best available copy.



A

Figure 55. Control Room Plans, Elevations and Section.

Reproduced from  
best available copy.




SECTION  
A-A

|   |  |                         |
|---|--|-------------------------|
| DRAWN BY<br>CHECKED BY<br>APP. BY<br>DATE | TITLE<br><b>CONTROL ROOM<br/>         MAILING &amp; DETAIL</b> | EP 115-100-100-100      |
| SCALE 1/4" = 1'-0"                        | <b>PLANT ENGINEERING</b><br><b>BOEING</b>                      | REV. DATE APPROVAL      |
|   |  | DWG NO. 115-100-100-100 |

B

Section.




A


Figure 56. Control Room Section and Details.

NOTES:

1. ALL STRUCTURE SHALL BE 100% STEEL UNLESS OTHERWISE SPECIFIED.
2. WELDED CONNECTIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED. ALL WELDS SHALL BE FULL PENETRATION WELDS UNLESS OTHERWISE SPECIFIED.
3. WELDED CONNECTIONS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED. ALL WELDS SHALL BE FULL PENETRATION WELDS UNLESS OTHERWISE SPECIFIED.
4. ALL WELDS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED. ALL WELDS SHALL BE FULL PENETRATION WELDS UNLESS OTHERWISE SPECIFIED.
5. ALL WELDS SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED. ALL WELDS SHALL BE FULL PENETRATION WELDS UNLESS OTHERWISE SPECIFIED.



INTERIOR ELEVATION  
SCALE 1/8" = 1'-0"



PARTIAL PLAN  
SCALE 1/8" = 1'-0"

|          |              |                    |           |
|----------|--------------|--------------------|-----------|
| DRAWN BY | DATE         | PROJECT            | DRG NO.   |
| CHECK BY | DATE         | CONTROL ROOM       | DRG NO. 4 |
| APP. BY  | DATE         | BOEING ENGINEERING |           |
| SCALE    | 1/8" = 1'-0" | BOEING ENGINEERING | DRG NO. 4 |

tails.





Figure 57. Removable Handrail Details.




|                     |      |                    |          |          |             |
|---------------------|------|--------------------|----------|----------|-------------|
| DRAWN BY            | DATE | TITLE              |          |          |             |
| CHKD. BY            | DATE | REMOVABLE HANDRAIL |          |          |             |
| APP. BY             | DATE | DETAILS            |          |          |             |
| APP. BY             | DATE | REMOVABLE          |          |          |             |
| APP. BY             | DATE | CTR 7              |          |          |             |
| APP. BY             | DATE |                    |          |          |             |
| SCALE: 1/4" = 1'-0" |      | PLANT ENGINEERING  | REV      | DATE     | DESCRIPTION |
|                     |      | THE BOEING COMPANY |          |          |             |
|                     |      | VENTOL DIVISION    | DWG. NO. | 73-0-721 |             |

B







NOTE 1

1. ALL PIPING TO BE SCH 40 304 SS.
2. ALL INSULATION TO BE 3" MIN (EXCEPT CAREY TEMP 1500 WITH 6\"/>

PART PLAN TOWER

2  
CY  
4 STD CUPS (2)  
1 1/2\"/>


40  
1/2\"/>

SINGLE ROD HOIST  
HANGER W/ GR WHEEL  
SPRINKL HANGER  
FIG 1-60 TYPE A  
SEE 1-1

SEE 2-1 304 3 1/2\"/>

WELD  
ALL AROUND


ELEVATION



SECTION B-B

|  |  |                      |
|--|--|----------------------|
| DRAWN BY<br>CHECKED BY<br>APP BY<br>APP BY<br>APP BY<br>APP BY<br>APP BY<br>SCALE 3/4" = 1'-0" | PROJECT TITLE<br>AUTOMATIC CARGO HELICOPTER<br>TOWER TOP SECTION<br>PIPING ARRGT<br>PLANT ENGINEERING<br><b>BOEING</b><br>BOEING COMPANY<br>3800 CENTRE EXPLORATION BLVD<br>PHOENIX, ARIZONA 85046 | SHEET NO. 5<br>OF 10 |
|--|--|----------------------|

p Section.



A

Figure 59. Piping Arrangement, Test Tower Base.

NOTES

1. ALL TYPING TO BE IN INK.
2. ALL DIMENSIONS TO BE TO CENTER UNLESS SPECIALLY NOTED.
3. ALL TYPING TO BE WEATHERED BY THE CONTRACTOR.
4. ALL GASKETS TO BE IN COMPRESSED ASPECTS TO BE TO QUINCY TIGHTENING.
5. ALL STAINLESS STEEL PIPE FITTINGS TO BE HELIUM WELDED. SEE WELDING SPECIFICATIONS.
6. ALL INSULATION Joints TO BE SEALED WITH FUMICHA BANDS.



WELD TO  
EXISTING

14' 0" LONG  
1 1/2" PIPE SLEEVE

PIPE GUIDE TOP  
(2-HELD)

PLAN

30' 0"

INSULATION TO  
STOP SHORT  
OF ANCHOR  
4" TO THE  
SUPPORT FRAMING

8" VEL. PIPE SLEEVE  
4' 0" LONG WELD  
TO 4"

PIPE  
SEALER

ANCHOR  
SEE DETAIL

FINISHED  
SURFACE


ANCHOR  
SEE DETAIL

SECTION

| NO. | DESCRIPTION             | DATE    | BY        | CHECKED   |
|-----|-------------------------|---------|-----------|-----------|
| 1   | ISSUED FOR CONSTRUCTION | 10/1/50 | J. H. ... | J. H. ... |
| 2   | REVISION                |         |           |           |
| 3   | REVISION                |         |           |           |
| 4   | REVISION                |         |           |           |
| 5   | REVISION                |         |           |           |
| 6   | REVISION                |         |           |           |
| 7   | REVISION                |         |           |           |
| 8   | REVISION                |         |           |           |
| 9   | REVISION                |         |           |           |
| 10  | REVISION                |         |           |           |

BOEING PLANT ENGINEERING


B



A

Figure 60. Fuel Piping Arrangement - PPG Unit.

Preceding page blank




JP-4 SUPPLY PIPING DETAILS  
 (NO SCALE)

NOTES:  
 PPG UNIT & FUEL PUMP BY OTHERS.

13-5 5009


|  |                              |   |                    |          |  |  |  |
|--|------------------------------|---|--------------------|----------|--|--|--|
| PR 215660                              |                              |   |                    | SHT 3473 |  |  |  |
| DRAWN BY<br>CHECK BY<br>APP BY<br>DATE | DATE<br>DATE<br>DATE<br>DATE | TITLE<br>1/2" SUPPLY<br>PIPE LEADOUT<br>TO TEST ENGINE<br>ADPWT |                    |          |  |  |  |
| BOEING PLANT ENGINEERING               |                              |   | SCALE 1/2" = 1'-0" |          |  |  |  |
| COW NO 2-1003 IN YD. 3                 |                              |   |                    |          |  |  |  |

*B*



A






Figure 61. Electrical Single Line Diagram.




| DRAWN BY | DATE     | TITLE   |  |  |
|----------|----------|---|--|--|
| AVM      | 12-11-77 | SINGLE LINE DIAGRAM<br>HLH/ATC<br>CARGO HANDLING TEST PIG |  |  |
| CHKD. BY | DATE     |   |  |  |
| APP. BY  | DATE     |   |  |  |
| APP. BY  | DATE     |   |  |  |
| APP. BY  | DATE     |   |  |  |
| APP. BY  | DATE     |   |  |  |
| SCALE:   |          | PLANE ENGINEERING   |  |  |
|          |          | THE <b>DRESSING</b> COMPANY<br>VENTNOR, ILLINOIS          |  |  |







- NOTES
1. RUN #2 BARE COPPER CABLE IN ALL OF THE 3/4" W. REWAY AND LEAD TO THE CABLE TO PANEL #17.
  2. GROUND PANEL #17 TO E.G. STRUCTURE WITH #6 BARE COPPER CABLE.
  3. FOR SHAPING AND OTHER NOTES SEE SHEET #102.




Reproduced from best available copy.

| DRAWN BY          | CHKD BY | TITLE |
|-------------------|---------|-------|
| APP BY            |         |       |
| APP BY            |         |       |
| APP BY            |         |       |
| APP BY            |         |       |
| APP BY            |         |       |
| SCALE             |         |       |
| <b>BGEING</b>     |         |       |
| PLANT ENGINEERING |         |       |
| OWG NO. 1         |         |       |

B

Test Rig.




A

Figure 63. Control Room Electrical Layout.

Preceding page blank

N




POWER PLAN

SYMBOLS

- 1. PAC FLOOR UNIT
- 2. 20A, 20V, 15, 20, 25, 30, 35, 40, 45, 50, 55, 60, 65, 70, 75, 80, 85, 90, 95, 100, 105, 110, 115, 120, 125, 130, 135, 140, 145, 150, 155, 160, 165, 170, 175, 180, 185, 190, 195, 200, 205, 210, 215, 220, 225, 230, 235, 240, 245, 250, 255, 260, 265, 270, 275, 280, 285, 290, 295, 300, 305, 310, 315, 320, 325, 330, 335, 340, 345, 350, 355, 360, 365, 370, 375, 380, 385, 390, 395, 400, 405, 410, 415, 420, 425, 430, 435, 440, 445, 450, 455, 460, 465, 470, 475, 480, 485, 490, 495, 500, 505, 510, 515, 520, 525, 530, 535, 540, 545, 550, 555, 560, 565, 570, 575, 580, 585, 590, 595, 600, 605, 610, 615, 620, 625, 630, 635, 640, 645, 650, 655, 660, 665, 670, 675, 680, 685, 690, 695, 700, 705, 710, 715, 720, 725, 730, 735, 740, 745, 750, 755, 760, 765, 770, 775, 780, 785, 790, 795, 800, 805, 810, 815, 820, 825, 830, 835, 840, 845, 850, 855, 860, 865, 870, 875, 880, 885, 890, 895, 900, 905, 910, 915, 920, 925, 930, 935, 940, 945, 950, 955, 960, 965, 970, 975, 980, 985, 990, 995, 1000

NOTES

1. APPROXIMATE LOCATIONS OF EQUIPMENT ARE SHOWN BY DASHED LINES.
2. ALL ELECTRICAL SYMBOLS ARE TO BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.
3. ALL ELECTRICAL SYMBOLS ARE TO BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.



Reproduced from best available copy.

|             |      |       |
|-------------|------|-------|
| DESIGNED BY | DATE | TITLE |
| DRAWN BY    | DATE |       |
| CHECKED BY  | DATE |       |
| APP. BY     | DATE |       |
| APP. BY     | DATE |       |
| APP. BY     | DATE |       |
| SCALE       |      |       |

**PLANT ENGINEERING**

**BDEING**

*C*

-1128411  
 C  
 B  
 A




Figure 64. Load Controlling Crewman Platform - Integrated Test Rig.

173


Preceding page blank

A



- 1 MATERIALS & HARDWARE MAY BE SUBSTITUTED TO SUIT AVAILABILITY
- 2 GLUE & SCREW - 2 ASSY AS NECESSARY
- 3 GLUE & SCREW - 3 ASSY AS NECESSARY
- 4 - 1 TO BE ASSEMBLED IN ITR CONTROL ROOM
- 5 INDICATORS, SWITCHES CONTROLLER & PANEL SHOWN FOR REF ONLY
- 6 PAINT 'LOCKPIT GREY'

MOST CONTROL PANELS  
 1 E E ROTATED CW 46°



|     |     |                             |               |                             |  |
|-----|-----|-----------------------------|---------------|-----------------------------|--|
|     | 2   | BAC 522 A18                 | DIUS RAIL     |                             |  |
|     | 8   | MS 21061-06                 | PLATE NUT     |                             |  |
|     | 4   | MS 21060-L3                 | PLATE NUT     |                             |  |
|     | 40  | MS 20470A3-4                | RIVET         |                             |  |
|     | 5   | MS 20470A3-5                | RIVET         |                             |  |
| REF | REF | N° 10 x 1.0 RND HD WOODSREW | COMML         |                             |  |
|     | 18  | AN 520-10-10                | SCREW         |                             |  |
|     | 8   | MS 21045-3                  | NUT           |                             |  |
|     | 18  | AN 560-10-L                 | WASHER        |                             |  |
|     |     |                             |               |                             |  |
|     | 1   | -18                         | MTG PLATE     | 125-25-25 2024 T4 AL ALY    |  |
|     | 2   | -7                          | ANGLE         | 1/2-10-10 AL ALY ANGLE - 70 |  |
|     |     | -10                         | SWITCH PANEL  | EXISTING                    |  |
|     | 1   | -5                          | MTG PLATE     | 125-6-2-B-C 2024 T4 AL ALY  |  |
|     | 1   | -4                          | OPD - 13      |                             |  |
|     | 1   | -3                          | BRACKET       | OSO-6-8 2024 T4 AL ALY      |  |
|     |     | -2                          | CLIP          | 1/2-10-10 AL ALY ANGLE - 60 |  |
|     | 1   | -7                          | ARM REST      | 1/2-6-1/8 SPRING RUBBER     |  |
|     | 1   | -10                         | REINFORCING   | 17-31-1/8 COMM L PLY        |  |
|     | 2   | -9                          | SIDE PLATE    | 26-37-1/8 COMM L PLY        |  |
|     |     | -3                          | FRAME         | 313-565-1/8 COMM L PLY      |  |
|     | 2   | -7                          | ANGLE         | 1/2-10-10 AL ALY ANGLE - 30 |  |
|     |     | -6                          | PLATE         | 613-71-1/8 COMM L PLY       |  |
|     | 2   | -5                          | COVER         | 32-36-1/8 COMM L PLY        |  |
|     | 4   | -4                          | FRAME         | 2-3 LUMBER COMM L 1/2 G LG  |  |
|     |     | -3                          | PLATFORM ASSY |                             |  |
|     | 2   | -2                          | ARM ASSEMBLY  |                             |  |
|     |     | -1                          | ASSEMBLY      |                             |  |

SK 301-11564

| Part | Quantity | Material | Description | Notes |
|------|----------|----------|-------------|-------|
|      |          |          |             |       |
|      |          |          |             |       |

REVISIONS


|    |      |             |
|----|------|-------------|
| NO | DATE | DESCRIPTION |
| 1  |      |             |
| 2  |      |             |
| 3  |      |             |

PROJECT: SK 301-11564

DATE: 1772

SK 301-11564

C




A Figure 65. System Test - Drawing Tree .

Preceding page blank









**A**

Figure 66. Lifting Sling, Hoist/Module.


Preceding page blank

NOTES  
 1. SPECIFICATIONS AND STANDARDS FOR THE CONTAINERS OF MANUFACTURING OPERATIONS (AS APPLICABLE)  
 SURFACE REQUIREMENTS SYMBOLS PER SAC 8007  
 THE QUALITY AND QUALITY CONTROL SYMBOLS PER SAC 8002  
 MAINTENANCE SYMBOLS PER SAC 8003  
 MATERIAL SUBSTITUTIONS & EQUIVALENTS PER SAC 8004  
 PART MARKING PER SAC 8001  
 PARTS INSTALLATION PER SAC 8005  
 FINISH COATING PER DOCUMENT 8006  
 RIVET INSTALLATION & SYMBOLS PER SAC 8008

| REV | DESCRIPTION | DATE | APPROVED |
|-----|-------------|------|----------|
|     |             |      |          |



Moist Module [REF]



| QTY  | QTY    | CODE IDENT | PART OR               | MANUFACTURE OR DESCRIPTION  | MATERIAL AND SPECIFICATION   | REF | FINISH | FINISH | REPLACEMENT | REV  |
|------|--------|------------|-----------------------|---|--|-----|--------|--------|-------------|------|
| REQD | ASSEMB | NUMBER     | IDENTIFICATION NUMBER |   |  |     |        |        | PLAN NUMBER | DATE |
| 4    |        |            |                       | 7/8 DIA 181.5 STAINLESS STEEL WIRE ROPE - 60' LENGTH ACCU WIRE ROPE WITH INTERIOR THAWT CABLE | RD 2552-12 ONE END-TRIANGLE PLAIN LOOP OTHER END 2 1/2 S MINIMUM DIA. WIRE CABLE 1/2 |     |        |        |             |      |
| 2    |        |            |                       | 5213-1/2 SHACKLE  | CROSBY-LAUGHLIN CHESTER HARDWARE   |     |        |        |             |      |
| 1    |        |            |                       | 5213-7/8 SHACKLE  | CROSBY-LAUGHLIN  |     |        |        |             |      |
| 1    |        |            |                       | MS21049N16 NUT  |  |     |        |        |             |      |
| 8    |        |            |                       | MS21049N16 NUT  |  |     |        |        |             |      |
| 8    |        |            |                       | AN17-25A BOLT   |  |     |        |        |             |      |
| 1    |        |            |                       | AN17-25A BOLT   |  |     |        |        |             |      |
| 2    |        |            |                       | -7 SPACER   | 3/16 x 1 1/2 x 4 - STEEL PLATE COMM'L  |     |        |        | 1020        |      |
| 1    |        |            |                       | -6 CENTER PLATE   | 1 x 4 x 12 - STEEL PLATE COMM'L  |     |        |        | 1020        |      |
| 2    |        |            |                       | -5 SPACER   | 7/16 x 1 1/2 x 4 - STEEL PLATE COMM'L  |     |        |        | 1020        |      |
| 2    |        |            |                       | -4 LIFT PLATE   | 3/4 x 3 x 1 1/2 - STEEL PLATE COMM'L   |     |        |        | 1020        |      |
| 4    |        |            |                       | -3 SPACER   | 1/8 x 3 x 8 - STEEL PLATE COMM'L   |     |        |        | 1020        |      |
| 2    |        |            |                       | -2 CHANNEL  | 8x115 7/8 FT 100' LENGTH STEEL CHANN A-36  |     |        |        |             |      |
| X    |        |            |                       | -1 SLING ASSY   |  |     |        |        |             |      |

-B ENDS

|   |   |                                      |  |
|---|---|--------------------------------------|--|
| DIMENSIONS & TOLERANCES PER<br>ANSI Y14.1-1947<br>UNLESS OTHERWISE SPECIFIED<br>DIMENSIONS ARE IN INCHES<br>TOLERANCES UNLESS SPECIFIED:<br>DECIMALS .015<br>FRACTIONS 1/32<br>HOLE & SHAFT FITS PER ANSI B9.1-1967<br>HOLE & SHAFT FITS PER ANSI B9.1-1967<br>HOLE & SHAFT FITS PER ANSI B9.1-1967<br>HOLE & SHAFT FITS PER ANSI B9.1-1967 | DATA REVIEW<br>DATE: 7/10/72<br>BY: [Signature]<br>TITLE: [Title] | CONTRACT NUMBER<br>[Contract Number] | THE BOEING COMPANY<br>CORPORATE OFFICES SEATTLE WASHINGTON 98124<br>SLING ASSEMBLY<br>SLING MODULE |
| PART NUMBER<br>[Part Number]  | DATE OF ISSUE<br>[Date]   | PROJECT APPROVAL<br>[Signature]      | FILE CODE IDENT NO<br>D 77072 SF-10972   |

B

Hoist/Module.








Figure 67. Hoist Lifting Fixture (Sheet 1).

Preceding page blank







|   |                  |                  |
|---|------------------|------------------|
| A | 4                | 5                |
|   | 22 $\frac{3}{4}$ | 10 $\frac{3}{8}$ |





ER 3162-B (2) (WITH PINS)  
 TRU-LOC OR EQUIV.

(4) & (5) CABLE ASSY  
 (FULL SCALE)





| LENGTH A | DRILL B       | DRILL C       |
|----------|---------------|---------------|
| 6        | $\frac{1}{8}$ | $\frac{5}{8}$ |
| 7        | $\frac{1}{8}$ | $\frac{3}{8}$ |

(6) & (7) PLATE  
 (FULL SCALE)



(8) PLATE  
 (1/2 SCALE)





5751273

B

C

NOTE (UNLESS OTHERWISE SPECIFIED)

1. MANUFACTURER AND DIMENSIONS FOR THE CHOICE OF MANUFACTURER SPECIFIED OR APPROVED. DIMENSIONS SHOWN ARE FOR THE CHOICE OF MANUFACTURER SPECIFIED OR APPROVED. DIMENSIONS SHOWN ARE FOR THE CHOICE OF MANUFACTURER SPECIFIED OR APPROVED. DIMENSIONS SHOWN ARE FOR THE CHOICE OF MANUFACTURER SPECIFIED OR APPROVED.
2. PAINT - APPLY TWO COATS STEEL MEMBER & TWO COATS OF YELLOW EXTREME ENAMEL.
3. RATED LOAD 2000 #
- PROOF LOAD 4000 #
- APPLY PROOF LOAD AT LOCATION INDICATED BY \*.
- MANUFACTURER MUST GUARANTEE THE CABLE ASST TO BE ABLE TO SUSTAIN 1500 LBS WITHOUT RUPTURE



| QTY | DESCRIPTION | UNIT                | QTY | DESCRIPTION                           | UNIT |
|-----|-------------|---------------------|-----|---------------------------------------|------|
| 1   | AN 21084N6  | NUT                 | 8-8 |                                       |      |
| 1   | AN 960-1616 | WASHER              | 8-8 |                                       |      |
| 5   | AN 21084N10 | NUT                 | 8-8 |                                       |      |
| 8   | AN 21084N6  | NUT                 | C-8 |                                       |      |
| 3   | AN 21084N6  | NUT                 | 8-8 |                                       |      |
| 1/2 | AN 960-1016 | WASHER              | 8-8 |                                       |      |
| 1/2 | AN 960-816  | WASHER              | C-8 |                                       |      |
| 1/2 | AN 960-616  | WASHER              | 8-8 |                                       |      |
| 5   | AN 10-15A   | BOLT                | 8-8 |                                       |      |
| 8   | AN 6-15A    | BOLT                | C-8 |                                       |      |
| 1   | AN 6-15A    | BOLT                | 8-8 |                                       |      |
| 2   | AN 6-16A    | BOLT                | 8-8 |                                       |      |
| 1   | AN 17-16A   | BOLT                | 3-8 |                                       |      |
| 2   |             | -18 SPACER          | 8-8 | 9-1/2 x 1/2 x 1/2 CES PLATE           |      |
| 3   | 6408-5/8    | SHIM                | 8-8 | CROSBY-LAUGHEIM SHACKLE               |      |
| 1   | 6213-7/8    | SHACKLE             | C-8 | CROSBY-LAUGHEIM SHACKLE               |      |
| 1   | 6213-5/8    | SHACKLE             | 8-8 | CROSBY-LAUGHEIM SHACKLE               |      |
| 1   |             | -17 TUBE            | 8-8 | 1 1/2 x 1 1/2 x 22 LBS 3000 PSI       |      |
| 1   |             | -16 TUBE            | 8-8 | 1 1/2 x 1 1/2 x 20 LBS 3000 PSI       |      |
| 1   |             | -15 TUBE            | C-8 | 1 1/2 x 1 1/2 x 20 LBS 3000 PSI       |      |
| 2   |             | -18 CHANNEL         | D-7 | 8 x 1 1/2 x 5/8 x 21 x 22             |      |
| 2   |             | -13 PLATE           | 8-8 | 7 x 5 1/2 x 1/2 CES PLATE             |      |
| 1   |             | -12 PLATE           | D-7 | 10 x 7 1/2 x 1/2 CES PLATE            |      |
| 4   |             | -11 SHIM            | D-7 | 3 1/2 x 8 x 1/2 CES PLATE             |      |
| 1   |             | -10 PLATE           | C-7 | 7 x 4 x 5/8 CES PLATE                 |      |
| 1   |             | -9 PLATE            | D-7 | 7 x 4 x 5/8 CES PLATE                 |      |
| 1   |             | -8 PLATE            | D-6 | 7 x 4 x 1/2 CES PLATE                 |      |
| 2   |             | -7 PLATE            | D-6 | 7 x 2 1/2 x 1/2 CES PLATE             |      |
| 4   |             | -6 PLATE            | D-6 | 6 x 2 x 1/2 CES PLATE                 |      |
| 2   |             | -5 CABLE ASSY       | C-8 | 1/2 x 1 1/2 x 1 1/2 x 22 LBS 3000 PSI |      |
| 1   |             | -4 CABLE ASSY       | C-8 | 1/2 x 1 1/2 x 1 1/2 x 20 LBS 3000 PSI |      |
| 1   |             | -3 BEAM ASSY        | 8-8 |                                       |      |
| 1   |             | -2 CRADLE WELD ASSY | D-6 |                                       |      |
| 1   |             | -1 SLING ASSY       | 8-8 |                                       |      |

(1) SLING ASSY  
 WOST ASSY, CR60 3YS  
 (1/4 SCALE)

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|--|--|--|--|--|--|

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|--|--|--|--|--|--|

C

D

NOTES UNLESS OTHERWISE SPECIFIED

1. MATERIALS SHALL BE PROVIDED FOR THE DESIGNER, THIS OPERATES AS FOLLOWS:  
 SUPPLIER SHALL BE RESPONSIBLE FOR QUOTE AND DELIVERY OF MATERIALS FOR THIS JOB  
 SUPPLIER SHALL BE RESPONSIBLE FOR QUOTE AND DELIVERY OF MATERIALS FOR THIS JOB  
 SUPPLIER SHALL BE RESPONSIBLE FOR QUOTE AND DELIVERY OF MATERIALS FOR THIS JOB  
 SUPPLIER SHALL BE RESPONSIBLE FOR QUOTE AND DELIVERY OF MATERIALS FOR THIS JOB  
 SUPPLIER SHALL BE RESPONSIBLE FOR QUOTE AND DELIVERY OF MATERIALS FOR THIS JOB
2. PAINT - APPLY TWO COATS STEEL 1 GALLON & TRIM COATS OF YELLOW EXTERIOR ENAMEL
3. WATED 1000 2000 #  
 PROOF LOAD 4000 #  
 APPLY PROOF LOAD AT LOCATION INDICATED BY R.L.
4. MANUFACTURER MUST GUARANTEE THE CABLE ASSY TO BE ABLE TO SUSTAIN 6150 LBS WITHOUT RUPTURE



BEAM ASSY

613-3/8 CROSBY 1/2 INCH OR EQUIV

CABLE ASSY (2)

403-5/8 (3 PLCS) CROSBY LANGKIN OR EQUIV  
 PLATE (4)  
 AN10HSD BOLT (5 PCS)  
 AN960-1018 WASHER (6 PCS)  
 MS2108B10 NUT (5 PCS)

DRUM PICK UP (REF)

BEAM (REF)

| QTY | UNIT | DESCRIPTION        | QTY  | UNIT | DESCRIPTION  |
|-----|------|--------------------|------|------|--|
| 1   |      | MS2108B16 NUT      | 4    |      |  |
| 1/2 |      | AN960-1616 WASHER  | 8    |      |  |
| 5   |      | MS2108B10 NUT      | 8    |      |  |
| 8   |      | MS2108B8 NUT       | C-8  |      |  |
| 3   |      | MS2108B6 NUT       | 8    |      |  |
| 1/2 |      | AN960-1016 WASHER  | 8    |      |  |
| 1/2 |      | AN960-816 WASHER   | C-8  |      |  |
| 1/2 |      | AN960-616 WASHER   | 8    |      |  |
| 5   |      | AN10-15A BOLT      | 8    |      |  |
| 8   |      | AN8-17A BOLT       | C-8  |      |  |
| 1   |      | AN6-15A BOLT       | 8    |      |  |
| 2   |      | AN6-16A BOLT       | 8    |      |  |
| 1   |      | AN7-16A BOLT       | 8    |      |  |
| 2   |      | -18 SPACER         | 8    |      | 4x1/2x1/2 CBS PLATE - CHANNEL 1020                     |
| 3   |      | 403-5/8 SWIVEL     | 8    |      | CROSBY LANGKIN OR EQUIV                                |
| 1   |      | 613-3/8 SHACKLE    | C-4  |      | CROSBY LANGKIN OR EQUIV                                |
| 1   |      | 613-3/8 SHACKLE    | 8    |      | CROSBY LANGKIN OR EQUIV                                |
| 1   |      | -7 TUBE            | 8    |      | 1 1/2 x 1 1/2 x 22 LONG SHAKLE 530 THE L. CHANNEL 1020 |
| 1   |      | -16 TUBE           | 8    |      | 1 1/2 x 1 1/2 x 22 LONG SHAKLE 530 THE L. CHANNEL 1020 |
| 1   |      | -15 TUBE           | C-4  |      | 1 1/2 x 1 1/2 x 22 LONG SHAKLE 530 THE L. CHANNEL 1020 |
| 2   |      | -14 CHANNEL        | D7   |      | 4 x 1 1/2 x 5/8 x 22 LONG SHAKLE CHANNEL 1020          |
| 2   |      | -13 PLATE          | B-8  |      | 7 x 5 x 5/8 CBS PLATE - CHANNEL 1020                   |
| 1   |      | -12 PLATE          | D7   |      | 10 x 7 x 1/2 x 1/2 CBS PLATE - CHANNEL 1020            |
| 4   |      | -11 SWIM           | D7   |      | 5 1/2 x 4 x 3/8 CBS PLATE - CHANNEL 1020               |
| 1   |      | -10 PLATE          | C7   |      | 7 x 4 x 5/8 CBS PLATE - CHANNEL 1020                   |
| 1   |      | -9 PLATE           | E7   |      | 7 x 4 x 5/8 CBS PLATE - CHANNEL 1020                   |
| 1   |      | -8 PLATE           | A-10 |      | 7 x 4 x 5/8 CBS PLATE - CHANNEL 1020                   |
| 2   |      | -7 PLATE           | B-6  |      | 7 x 2 x 1/2 CBS PLATE - CHANNEL 1020                   |
| 4   |      | -6 PLATE           | A-6  |      | 6 x 2 x 1/2 CBS PLATE - CHANNEL 1020                   |
| 2   |      | -5 CABLE ASSY      | C-6  |      |  |
| 1   |      | -4 CABLE ASSY      | C-6  |      |  |
| 1   |      | -3 BEAM ASSY       | B-8  |      |  |
| 1   |      | -2 CABLE WELD ASSY | A-4  |      |  |
| 1   |      | -1 SLING ASSY      | A-4  |      |  |

5151273

|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |


|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |

|  |                                |                                |                                |
|--|--------------------------------|--------------------------------|--------------------------------|
| <p>REVISIONS</p> <p>NO. 1</p> <p>DATE</p> <p>DESCRIPTION</p> | <p>DATE</p> <p>DESCRIPTION</p> | <p>DATE</p> <p>DESCRIPTION</p> | <p>DATE</p> <p>DESCRIPTION</p> |
|--|--------------------------------|--------------------------------|--------------------------------|

SLING ASSY -  
 HOIST ASSY, CARGO 3V3.  
 HLH

J77273 5151273



D  
C  
B  
A



A Figure 67. Hoist Lifting Fixture (Sheet 2).

Preceding page blank





(2) CIRCULAR WELD ASSEMBLY  
(IN SCRAB)

|        |      |    |      |                           |
|--------|------|----|------|---------------------------|
| REV    | DATE | BY | CHKD | DESCRIPTION               |
| 1      |      |    |      | SLINK ASSY.               |
| 2      |      |    |      | ADJUST ASSY. CORE 40 SYS. |
| 3      |      |    |      | HLH                       |
| J7127A |      |    |      | 5751273                   |

5751273

B

Sheet 2).




Figure 68. Integrated Test Rig - System Wiring.

STEM  
EL  
A6

109-172-P3  
DISPLAY IEU  
ELECTRONICS  
P3 P4 A5

109-170  
CABLE  
TENSION  
IND A6  
P5

109-171  
CABLE  
LENGTH  
IND A7  
P6

| REVISIONS |                   |        |          |
|-----------|-------------------|--------|----------|
| LTR       | DESCRIPTION       | DATE   | APPROVAL |
| A         | COMPLETE REVISION | 8/2/13 |          |

W2  
01-11699 SMT2

W3A,B,C  
SK 301-11699 SMT5

W4  
SK 301-11699 SMT4

W5

W6  
SK 301-11699 SMT7

SK 301-11695 SMT1 & 2  
INTERFACE  
CONSOLE  
P31-P33 (SIG COND)  
SK 301-11714  
P27-P25 (CONT.)  
SK 301-11713  
P28-P26 (LOGIC)  
SK 301-11712  
A8

W14

SK 301-11699 SMT6

W8

SK 301-11699 SMT3

W10-12

W16

SK 301-11699 SMT6

SK 301-11699 SMT3

ATM  
CONTROLLER  
P16  
A9


AFT  
HOIST  
MODULE  
SK 301-11699  
A15

AFT  
SPAN  
POS  
MODULE  
SK 301-11693  
A13

P12 P10  
AFT SIG COND  
REEL  
A11

Wiring.

B




A


Figure 69. Instrumentation Drawing Tree.

Preceding page blank

| REVISIONS |                               |      |          |
|-----------|-------------------------------|------|----------|
| TR        | DESCRIPTION                   | DATE | APPROVAL |
| A         | RELEASED SINGLE INSTL ST30850 | 7/26 |          |
| B         | REVISED TO SP. SYSTEM ST30852 | 7/27 |          |





CABLES TO OPERATORS CONSOLE, TEST ARTICLE AND POWER SEE SK301-11679



| ADDITIONAL T.U.R. RELEASE |                                      |         |
|---------------------------|--------------------------------------|---------|
| T.U.R. NO.                | EFFECTIVITY                          | DATE    |
| 301-490001-11             | REVA DWG ST30855 & ST30846           | 4/16/73 |
| 301-49001-18              | REVA DWG ST30856 FAB - 5 ASSY        | 4/20/73 |
| 301-49001-19              | ST30851 PURCHASE SYSTEM              | 4/12/73 |
| 301-49001-28              | ST30846 REV B PURCHASE SWITCH        | 5/21/73 |
| 301-49001-29              | ST30848 REV A                        | 5/21/73 |
| 301-49001-31              | TEST BKG ASSEMBLY INSTRUCTIONS       | 5/25/73 |
| 301-49001-34              | FABICATION OF ALL COMPONENT PARTS    | 5/28/73 |
| 301-49001-41              | REVISE TO SYS SCHEMATIC ST30852 REVA | 5/28/73 |

LAB SUPPORT DWG'S.



DWG RELEASED

CONCT NO. 02401-110-0860 (R-40)  
 INSTRUMENTATION DRAWING TREE  
 CARGO HANDLING SYSTEM TEST  
 ST 30851  
 7772

B

APPENDIX III  
PNEUMATIC POWER GENERATOR - STARTING AND OPERATING PROCEDURE

PRERUN CHECKOUT

1. Remove all covers from unit:
  - a. Unit covers
  - b. Exhaust cover
  - c. Bleed valve wooden plug
2. Turn on water for oil cooler.
3. Turn on hand shutoff valve in fuel line at 275-gal. tank.
4. Check all switches on control panel for "OFF" position.
5. Attach all electrical connectors:
  - a. 2 control lines at engine
  - b. 3 thermo couple leads at engine
  - c. 2 control lines at console
  - d. 3 thermo couple leads at console
  - e. 110-VAC line at console
  - f. 14-VDC connector from batteries to APU
  - g. 28-VDC connectors from batteries to APU

STARTING PROCEDURE - CONTROL CONSOLE

1. Turn power "ON".
2. Turn fuel valve "ON".
3. Turn fuel pump "ON" (requires 10 seconds to pressurize line).
4. Turn starter and ignition "ON".
5. When gas producer speed reaches 13-15%, increase throttle control with momentary jog. Observe engine starting limits.
6. When gas producer speed reaches 52-58%, turn "OFF" starter and ignition. Allow engine to warm up at idle for 1 minute.
7. Increase throttle control to "full speed" with momentary jog. Observe engine continuous run limits.

**Preceding page blank**

#### STOP PROCEDURE

1. Decrease throttle control to idle position with momentary jog. Run for 2 minutes at "idle" position.
2. Decrease throttle control to "stop" position.
3. When gas producer speed is less than 15%, turn "OFF" fuel pump and fuel valve.
4. Turn "OFF" power.

#### POST-RUN SHUTDOWN

1. Turn "OFF" water to oil cooler.
2. Turn "OFF" hand fuel valve at 275-gal. tank.
3. Disconnect electrical connectors:
  - a. 110-VAC at console
  - b. 14-VDC from batteries to APU
  - c. 28-VDC from batteries to APU
4. Install covers after unit has cooled:
  - a. Exhaust covers
  - b. Bleed valve wooden plug
  - c. Unit cover

TABLE XII. NORMAL PPG OPERATING LIMITS.

| Parameter       | Run Condition     | Range or Limit* |
|-----------------|-------------------|-----------------|
| T <sub>T5</sub> | GI                | 700°-900°F      |
| T <sub>T5</sub> | Max Continuous    | 1430°F          |
| N1              | Start             | 12%-15%         |
| N1              | GI                | 59%-65%         |
| N1              | Max Continuous    | 104%            |
| N2              | GI                | 74.8%-104.7%    |
| N2              | Max Continuous    | 103.8%          |
| P Turb.GB       | GI                | 50-130 psi      |
| P Turb.GB       | Max Continuous    | 115-130 psi     |
| T Turb.GB       | GI-Max Continuous | 130-225°F       |
| P Compressor GB | GI                | 90 psi          |
| P Compressor GB | Max Continuous    | 110 psi         |
| T Compressor GB | Max Continuous    | 225°F           |

\*Values are for S.L. Standard operation. For information on transient limitations, consult the GMC Allison Div. 250-C20 Engine Operation and Maintenance Manual.



APPENDIX IV  
INSTRUMENTATION CALIBRATION PROCEDURE

The following represents the basic calibration steps carried out before and after daily hoist system operation.

TEMPERATURES

| <u>Operating Mode</u> | <u>Power Source</u> | <u>Osc A</u> | <u>Chanl. Selection</u> |
|-----------------------|---------------------|--------------|-------------------------|
| Cal.                  | R.C.                | .25 ips      | 1 thru 7; then zero     |
| Normal                | On                  | .25 ips      | Zero                    |

PRESSURES

| <u>Operating Mode</u> | <u>Input</u> | <u>Osc A</u> | <u>Cal. Pushbutton</u> |
|-----------------------|--------------|--------------|------------------------|
| Cal.                  | Depress Cal. | .25 ips      | 1-5 depress each       |
| Normal                | --           | --           | ---                    |

LOAD ISOLATORS

| <u>Operating Mode</u> | <u>Input</u>  | <u>Indication</u> | <u>Adjust</u>   |
|-----------------------|---------------|-------------------|-----------------|
| Cal.                  | Depress sense | 30.0              | Adjust each pot |

CABLE ANGLE

| <u>Operating Mode</u> | <u>Input</u>       | <u>Read Voltage At</u> | <u>Adjust</u>   |
|-----------------------|--------------------|------------------------|---|
| Normal                | .25V/DEC Fwd/Pitch | CTB4 Pins 1&2          | Adj. each pot for panel reading in accordance with CTB4 voltage reading |
|                       | Fwd/Roll           | CTB4 Pins 4&5          |   |
|                       | Aft/Pitch          | CTB4 Pins 7&8          |   |
|                       | Aft/Roll           | CTB4 Pins 10&11        |   |

CABLE PAYOUT SPEED

| <u>Operating Mode</u> | <u>Input</u>   | <u>Apply To</u>                | <u>Adjust</u>  |
|-----------------------|----------------|--------------------------------|--|
| Normal                | 5.0VDC=120 FPM | CTB3 Pins 1&2<br>CTB3 Pins 4&5 | Adj.A1 gain for 2.0" trace deflection<br>Adj.A2 gain for 2.0" trace deflection |

CABLE PAYOUT LENGTH

| <u>Operating Mode</u> | <u>Input</u>  | <u>Apply To</u>                    | <u>Adjust</u>  |
|-----------------------|---------------|------------------------------------|--|
| Normal                | 5.0VDC=100 Ft | CTB4 Pins 14&15<br>CTB4 Pins 18&19 | Adj.A5 gain for 2.0" deflection<br>Adj.A6 gain for 2.0" deflection |

SPEED COMMAND CAL.

| <u>Operating Mode</u> | <u>Input</u> | <u>Indication</u>  | <u>Adjust</u>                                   |
|-----------------------|--------------|--------------------|---|
| Normal                | 6.0V=100%    | 2.0" trace deflec. | Press fwd then aft control grip thumb switches. |

MOD. VALVE CURRENT CAL.

| <u>Operating Mode</u> | <u>Input</u> | <u>Apply At</u>                   | <u>Adjust</u>                                    |
|-----------------------|--------------|-----------------------------------|--|
| Normal                | 1.5VDC-100%  | CTB3 Pins 24&25<br>CTB3 Pins 9&10 | A3 gain for deflection<br>A7 gain for deflection |