

AD-A1ub 315

SCHNABEL ENGINEERING ASSOCIATES RICHMOND VA
NATIONAL DAM SAFETY PROGRAM, LEATHERWOOD CREEK NUMBER 2A (INVEN--ETC(U))
JUL 81 R E MARTIN, C S ANDERSON, J G STARR

F/G 13/13

DACW65-81-D-0020

UNCLASSIFIED


MI

Page 1
AD-A
11-81


END
DATE
FILMED
11-81
DTIC

LEATHERWOOD CREEK BASIN

Name Of Dam: LEATHERWOOD CREEK NO. 1
Location: HENRY COUNTY, VIRGINIA
Inventory Number: VA. NO. 06905



PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



Disc FILE COPY
AD A106315

Disc FILE COPY
AD A106315

PREPARED FOR
NORFOLK DISTRICT CORPS OF ENGINEERS
803 FRONT STREET
NORFOLK, VIRGINIA 23510

BY
SCHNABEL ENGINEERING ASSOCIATES, P.C./
J. K. TIMMONS AND ASSOCIATES, INC.

JULY 1981

81 10 27 295

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1 REPORT NUMBER VA 08905	2 GOVT ACCESSION NO. AD 716 C	3 RECIPIENT'S CATALOG NUMBER 713
4 TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Leatherwood Creek No. 2A Henry County, VA		5 TYPE OF REPORT & PERIOD COVERED Final
		6 PERFORMING ORG REPORT NUMBER
7 AUTHOR(s) Schnabel Engineering Associates, P. C. J. K. Timmons and Associates, Inc.		8 CONTRACT OR GRANT NUMBER(s) DACW-65-81-D-0020 <i>see</i>
9 PERFORMING ORGANIZATION NAME AND ADDRESS Schnabel Engineering Associates, P. C. J.K. Timmons and Associates, Inc.		10 PROGRAM ELEMENT PROJECT, TASK AREA & WORK UNIT NUMBERS
11 CONTROLLING OFFICE NAME AND ADDRESS U. S. Army Engineer District, Norfolk 803 Front St., Norfolk, VA 23510		12 REPORT DATE July 1981
		13 NUMBER OF PAGES
14 MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15 SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION DOWNGRADING SCHEDULE
16 DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited		
17 DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18 SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151		
19 KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams - VA National Dam Safety Program Phase I Dam Safety Dam Inspection		
20 ABSTRACT (Continue on reverse side if necessary and identify by block number) (See Reverse Side)		

20. Abstract

Pursuant to Public Law 92-367, Phase I Inspection Reports are prepared under guidance contained in the recommended guidelines for safety inspection of dams, published by the Office of Chief of Engineers, Washington, D. C. 20314. The purpose of a Phase I Inspection is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general conditions of the dam is based upon available data and visual inspection. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

Based upon the field conditions at the time of the field inspection and all available engineering data, the Phase I report addresses the hydraulic, hydrologic, geologic, geotechnic, and structural aspects of the dam. The engineering techniques employed give a reasonably accurate assessment of the conditions of the dam. It should be realized that certain engineering aspects cannot be fully analyzed during a Phase I inspection. Assessment and remedial measures in the report include the requirements of additional indepth study when necessary.

Phase I reports include project information of the dam appurtenances, all existing engineering data, operational procedures, hydraulic/hydrologic data of the watershed, dam stability, visual inspection report and an assessment including required remedial measures.

ROANOKE RIVER BASIN

NAME OF DAM: LEATHERWOOD CREEK NO. 2A
LOCATION: HENRY COUNTY, VIRGINIA
INVENTORY NUMBER: VA. NO. 08905

National Dam Safety Program. Leatherwood
Creek Number 2A (Inventory Number VA
08905), Roanoke River Basin, Henry
County, Virginia. Phase I Inspection
Report.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

1-1 ACW 2-1-1
3-1-1
PREPARED FOR
NORFOLK DISTRICT CORPS OF ENGINEERS
803 FRONT STREET
NORFOLK, VIRGINIA

BY

SCHNABEL ENGINEERING ASSOCIATES, P.C./
J. K. TIMMONS AND ASSOCIATES, INC.

TABLE OF CONTENTS

	<u>Page</u>
Preface	i
Brief Assessment of Dam	1
Overview Photos	5
Section 1: PROJECT INFORMATION	6
Section 2: ENGINEERING DATA	10
Section 3: VISUAL INSPECTION	14
Section 4: OPERATIONAL PROCEDURES	17
Section 5: HYDRAULIC/HYDROLOGIC DATA	19
Section 6: DAM STABILITY	23
Section 7: ASSESSMENT/REMEDIAL MEASURES	28

Appendices:

- I - Maps and Drawings
- II - Photographs
- III - Field Observations
- IV - Design Report
- V - Stability Data
- VI - References

Accession for	<input checked="" type="checkbox"/>
NTIS Cross	<input type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By _____	
Distribution/	
Availability Codes	
_____ and/or	
Dist _____	
Special	
A	

DISCUSSION

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D. C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

BRIEF ASSESSMENT OF DAM

Name of Dam: Leatherwood Creek No. 2A Dam
State: Virginia
Location: Henry County
USGS Quad Sheet: Martinsville East
Coordinates: Lat 36°-44.3' Long 79°-48.6'
Stream: West Fork, Leatherwood Creek
Date of Inspection: July 1, 1981

Leatherwood Creek No. 2A dam is a zoned earthfill structure about 400 ft long and 51.9 ft high. The principal spillway consists of a reinforced concrete riser and a 36 inch diameter concrete outlet pipe which extends through the structure. An earth emergency spillway is located at the left abutment with a 30 ft wide bottom and 3H:1V side slopes. The structure is classified intermediate in size and is assigned a significant hazard classification. The dam is located on the West Fork of Leatherwood Creek approximately 3.5 miles west of Leatherwood, Virginia. The dam is used for irrigation, flood control and recreational purposes, and is owned and maintained by Mr. Thomas F. Walker.

Based on criteria established by the Department of the Army, Office of the Chief of Engineers(OCE), the appropriate Spillway Design Flood (SDF) is the $\frac{1}{2}$ PMF. The spillways will pass 30 percent of the Probable Maximum Flood (PMF) or 60 percent of the SDF without overtopping the dam. During the SDF, the dam will be overtopped for four hours up to a maximum of 3 feet and reach a maximum velocity of 7.4 fps. A dam breach during the SDF would significantly increase the hazard to loss of life downstream of the dam over that which would exist just before overtopping failure. The spillway is judged seriously inadequate. Overtopping is considered detrimental to the embankment with respect to erosion.

Due to the inadequacy of the spillway and the resulting overtopping of the dam during the SDF, the potential for a breach of the dam exists. Based upon the possibility of a dam breach caused by overtopping during the SDF, the dam is assessed "unsafe, non-emergency."

The classification of "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean, however, that based on an initial screening, and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream from the dam.

It is, therefore, recommended that a qualified engineering firm be retained to perform a detailed hydrologic/hydraulic analysis of the downstream damage reach with a dam breach simulation. The owner is required to engage the services of a qualified engineering firm within two months of the issuance of the approved Phase I inspection report. The owner is required to have the consultant's report and to have reached an agreement with the Commonwealth of Virginia regarding required remedial measures within six months of the date of the issuance of the approved Phase I inspection report.

The visual inspection did not reveal any problems which would require immediate attention. Field measurements indicate the embankment crest is 5 ft narrower than shown on the "as built" drawings. The dam is considered stable for normal pool conditions and the review of design stability data indicates the structure is stable as designed.

It is recommended that the owner implement an emergency action plan measure immediately as of the date of this report in order to warn downstream dwellings of any dangers which may be imminent. In the interim the dam and reservoir should be monitored during periods of heavy precipitation and runoff.

The following routine maintenance and observation functions should be initiated as part of an annual maintenance program:

All brush growing on the embankment should be cut to the ground and removed from the embankment. The area of sloughing in the right abutment should be stabilized. The minor sloughing located above the outlet works should be monitored during maintenance. If increased erosion should occur, this area should be stabilized by backfilling and reseeding. Debris should be removed from the trash rack and the broken bar on the trash rack should be replaced. A staff gage should be installed to monitor water levels.

SCHNABEL ENGINEERING ASSOCIATES, P.C./
J. K. TIMMONS & ASSOCIATES, INC.



Ray E. Martin, Ph.D., P.E.
Commonwealth of Virginia

Submitted by:

Original signed by:
Carl S. Anderson, Jr.

Carl S. Anderson, Jr., P.E.
Acting Chief, Design Branch

Approved:

Original signed by:
Ronald E. Hudson

Ronald E. Hudson
Colonel, Corps of Engineers
Commander and District Engineer

Recommended by:

Original signed by
JACK G. STARR

Jack G. Starr, P.E.
Chief, Engineering Division

Date

SEP 23 1981



View of the bridge from the river



View of the bridge from the river

SECTION 1 - PROJECT INFORMATION

1.1 General:

1.1.1 Authority: Public Law 92-367, 8 August 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of safety inspection of dams throughout the United States. The Norfolk District has been assigned the responsibility of supervising the inspection of dams in the Commonwealth of Virginia.

1.1.2 Purpose of Inspection: The purpose is to conduct a Phase I inspection according to the Recommended Guidelines for Safety Inspection of Dams (see Reference 1, Appendix VI). The main responsibility is to expeditiously identify those dams which may be a potential hazard to human life or property.

1.2 Project Description:

1.2.1 Dam and Appurtenances: Leatherwood Creek No. 2A Dam is a zoned earthfill structure approximately 400 ft long and 51.9 ft high.* The crest of the dam is 12 ft wide, and side slopes are approximately 2.5 horizontal to 1 vertical (2.5H:1V) on the upstream and downstream slopes of the dam. A 10 ft wide berm occurs between elevation 782.7 and 783.7 msl on the upstream slope. The upstream slope is 3H:1V below the berm. The crest of the dam is at elevation 813.4 msl. "As built" drawings show the presence of a core trench which extends to "firm rock" and a seepage drain beneath the downstream slope. There is no slope protection on the upstream face of the dam.

*Height is measured from the top of the dam to the downstream toe at the centerline of the stream.

The principal spillway consists of a reinforced concrete riser inlet. The riser has an internal opening of 9 ft by 3 ft, and is approximately 34 ft high. The riser has a low flow orifice (3 ft by .75 ft) at an invert elevation of 782.2 msl and two overflow weirs (9 ft by 1.5 ft) at elevation 794 msl. A 36 inch diameter slide gate in the riser at an invert elevation of 763 msl is used to drain the lake. The outlet pipe is a 36 inch diameter concrete pipe which outlets at an elevation of 761.5 msl into a Bradley Perterka impact basin. (See Plates 5 and 7, Appendix I).

The emergency spillway (EMS) consists of a vegetated earth and rock channel spillway located at the left abutment, having a crest elevation of 804 msl. The EMS has a bottom width of 30 ft at the control section and 3H:1V side slopes, and is entirely in a cut section. (See Plates 2 and 3, Appendix I).

1.2.2 Location: Leatherwood Creek No. 2A Dam is located on the West Fork of Leatherwood Creek, 3.5 miles west of Leatherwood, Virginia. (See Plate 1, Appendix I.)

1.2.3 Size Classification: The dam is classified as an intermediate size structure based on its height and maximum lake storage potential as defined in Reference 1, Appendix VI.

1.2.4 Hazard Classification: The dam is located in a rural area; however, based upon the proximity of an inhabited dwelling located 2 miles downstream, and several dwellings 5 miles downstream, the dam is assigned a "significant" hazard classification. The hazard

classification used to categorize a dam as a function of its height and has nothing to do with its stability or probability of failure.

13.1.5 Ownership: The dam is owned and maintained by Mr. Thomas Walker of Pichline, Karnataka.

13.1.6 Design and Construction: The dam was constructed in 1977 by Mr. Thomas Walker. The dam is a gravity dam with a height of 10.5 m. The dam was constructed on a foundation of sandstone. The dam has a crest width of 1.5 m and a top width of 2.5 m. The dam has a spillway with a crest width of 1.5 m and a top width of 2.5 m. The dam was constructed with a concrete core and a masonry shell.

13.1.7 Material: The dam is constructed with concrete. The dam has a crest width of 1.5 m and a top width of 2.5 m. The dam has a spillway with a crest width of 1.5 m and a top width of 2.5 m. The dam was constructed with a concrete core and a masonry shell.

13.1.8 Drainage:

13.1.8.1 Drainage Area: The drainage area is 600 square meters.

13.1.8.2 Discharge at Dam Site: According to the owner, the maximum known flood at the dam site occurred in April 1977 when an estimated pool elevation of 799 msl was observed. This corresponds to an approximate discharge of 182 CFS.

1. The following information is being furnished to you:

1. The following information is being furnished to you: (b) (5) - DPP

2. The following information is being furnished to you:

2. The following information is being furnished to you: (b) (5) - DPP

3. The following information is being furnished to you:

STATE OF NEW YORK DEPARTMENT OF TAXATION

INVESTMENT

TABLE

	1974	1975	1976	1977	1978
1. The following information is being furnished to you:					
2. The following information is being furnished to you:					
3. The following information is being furnished to you:					
4. The following information is being furnished to you:					
5. The following information is being furnished to you:					

Chemical structure

Various chemical structures and reactions are shown, including diagrams of molecules and chemical equations.

Figure

Chemical structures and reactions are described in detail, with references to specific figures and plates.

Plate 3 of Appendix I indicates that the dam is founded on overburden and includes a cutoff trench which extends through alluvial and residual soils to "firm rock." The cutoff also extends to the same materials in both abutments. The cutoff trench is 12 ft wide and has 1H:1V side slopes. No field permeability tests were taken during the subsurface investigation, however, permeability rates of 1.0 ft/day to 10.0 ft/day were assumed for the foundation soil materials as determined from tests conducted for the Leatherwood Creek No. 5 dam site. The underlying bedrock was described as less weathered than that encountered at the No. 5 site and was considered to be impervious.

An internal drainage system was also constructed beneath the downstream slope to collect any seepage passing through the dam. The seepage drain was to consist of a 4 ft minimum width trench with 1 1/2 ft of 6 inch diameter perforated cast iron perforated pipe enclosed in a mandarin envelope. Details of the seepage drain are provided on Plate 4 of Appendix I.

The principal spillway was designed as a high crest structure constructed of reinforced concrete masonry on rock contact and a filtered riprap basin at the outlet end of the conduit. Eight anti-siphon outlets on 12 ft centers were included in construction. Details are presented on Plate 5 of Appendix I. The principal spillway was designed to accommodate a 50 year flood without discharge occurring in the EMS.

The emergency spillway is located in a moderately sloping hillside in the left abutment. The spillway is a 30 ft wide trapezoidal rock and earthen channel bounded by 3H:1V cut slopes. The spillway is entirely

in the laboratory, using the undisturbed and weathered materials from all of the approved sections and levels on sites 1 and 2 of Appendix 1.

The design report and supplementary data provided by the DCS include detailed laboratory test data describing the physical properties of the materials used to construct the embankment. A summary of this information is provided in Appendix 2. Data was also obtained on the consistency of the lake density of the loesslike soils. The design S_u assumed strong and slightly compressible soils similar to those encountered at the Leathemud Creek No. 1 dam site. Shear strength parameters used in design of the embankment were determined by consolidated undrained triaxial compression tests as follows:

SITE NO.	SOIL	SHEAR STRENGTH PARAMETERS	
		Angle ϕ Internal Friction	Cohesion
EMBANKMENT	S _u	16°	1000 psf
	M ₁	16°	1000 psf
	S _u **	16°	1000 psf

* From Leathemud Creek No. 1 site

Embankment stability was checked by the Swedish Circle Method Analysis and a factor of safety of 1.28 was calculated for full drawdown on the upstream slope (vertical with no berm). A minimum factor of safety of 1.43 was calculated for steady seepage on the downstream slope (2.5H:1V with no berm and no drain). The design report stated, "An analysis of a 50 foot embankment with the shear strength found in these embankment tests and one from Site 5 show acceptable safety factors for the proposed slopes."

2.2 Construction: The construction records were not furnished by the SCS office in Richmond, but they are available from the SCS office in Washington, D. C.

2.3 Evaluation: "As built" drawings are generally representative of the structure. Field measurements indicate that the embankment crest is 5 ft narrower than shown on the "as built" drawings. Hydrologic and hydraulic calculations were available for evaluation. There is sufficient information to evaluate foundation conditions and embankment stability.

STATION 3 - VISUAL INSPECTION

3.1 Findings: At the time of inspection, the dam appeared to be in excellent condition. Field observations are outlined in Appendix III.

3.1.1 General: An inspection was made on July 1, 1981 and the weather was cloudy with a temperature of 75°F. The pool and tailwater levels at the time of inspection were 782.5 and 761.5 msl, respectively, which corresponds to normal pool and tailwater elevations. Ground conditions were dry at the time of the inspection. Maintenance inspections are performed jointly by SCS and the Blue Ridge Soil and Water Conservation District on an annual basis. Inspection reports are available in the Soil and Water Conservation District office in Collinsville, Virginia.

3.1.2 Dam and Spillway: The embankment slopes and crest were grassed and well maintained. Cattle are allowed to graze on the embankment. Scattered patches of brush 1 to 2 inches in diameter were growing 5 to 10 ft[±] above pool level on the upstream slope to the right of the intake structure. A few small bushes and weeds were also present on the downstream slope.

Essentially no sloughing or erosion was noted on the embankment. Scattered shrinkage cracks were observed on the embankment, particularly near the right abutment. They were generally "pencil mark" in width and are probably the result of local drought conditions. A very small area of sloughing was noted on the downstream slope directly above the outlet works. The right abutment has an area of sloughing located 15 ft[±] below the crest of the dam. The area is 15 ft[±] long and 5 ft[±] high. This area is bare and has experienced some washing.

The downstream toe of the embankment was dry and no seepage was encountered. Two 6 inch CMP toe drains were encountered, one on the left side and one on the right side of the energy dissipater. Iron staining was noted at the end of the pipes, however, flow from the outlets could not be observed since the inverts were below the stilling basin pool level.

Except for a broken steel bar on the trash rack, the riser structure and outlet pipe showed no signs of deterioration and were functioning properly at the time of inspection. Debris was present in the low flow intake trash rack. According to the owner, the slide gate has not been operated since it was installed. The impact basin and outlet channel indicated no signs of deterioration. The emergency spillway was well vegetated except for where weathered bedrock was exposed in the approach channel.

3.1.3 Reservoir Area: The reservoir area was free of debris and the perimeter was wooded except on the right side where pasture exists. The reservoir is located in a valley with side slopes at approximately 4H:1V. Water was murky and a sedimentation buildup was reported by the owner.

3.1.4 Downstream Area: The downstream channel consists of a 15 ft wide channel located in a valley with side slopes of 3H:1V. This valley is heavily wooded except for an area 100 ft right of the channel which is a pasture. Approximately 2 miles downstream there is a dwelling about 15 ft above the stream channel, and 5 miles downstream there are several dwellings about 10 ft above the stream channel and several commercial facilities 15 ft above the channel.

3.1.5 Instrumentation: No instrumentation (monuments, observation wells, piezometers, etc.) was encountered for the structure. There is no staff gage.

3.2 Evaluation:

3.2.1 Dam and Spillway: Overall, the dam was in excellent condition at the time of the inspection. The presence of brush on the embankment, particularly those at pool level on the upstream slope, may promote the development of deep rooted vegetation and this type growth can encourage piping within an embankment. All brush growing on the embankment should be cut to the ground and removed from the embankment.

The scattered shrinkage cracks on the embankment are apparently the result of local drought conditions and require no special attention. The small area of sloughing located above the outlet does not require any attention at this time; however, if increased erosion should occur, this area should be stabilized by backfilling and reseeding. The area of sloughing in the right abutment does not inhibit the proper performance of the dam. It is recommended that attempts be made to stabilize the area in order to prevent its migration toward the embankment.

The outlet pipe and intake structures are in good structural condition. Debris should be removed from the trash rack and the broken bar repaired. A staff gage should be installed to monitor water levels.

3.2.2 Downstream Area: A breach in Leatherwood Creek No. 2A Dam during extreme flooding would possibly create a hazard to the downstream dwellings.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 Procedures: The normal storage pool is elevation 782.5 msl or 0.3 ft above the crest of the principal spillway low flow inlet. The lake provides an irrigation supply, flood control and recreation. Water automatically passes through the principal spillway as the water level in the reservoir rises above the low level orifice. Water will also pass automatically through the overflow crest when the water level in the reservoir exceeds elevation 794 msl and automatically through the emergency spillway when the pool level exceeds elevation 804 msl. A 36 inch slide gate at the low point in the riser structure is provided to drawdown the reservoir below normal pool.

4.2 Maintenance of Dam and Appurtenances: Maintenance is the responsibility of the owner and the Blue Ridge Soil and Water Conservation District. Maintenance is accomplished by a joint annual inspection by SCS and Soil and Water Conservation District personnel. Maintenance deficiencies are noted and recommended remedial measures are made to the owner. If the owner fails to comply with these recommendations, maintenance is then performed by the Blue Ridge Soil and Water Conservation District.

4.3 Warning System: At the present time, there is no warning system or evacuation plan for the dam. The dam is monitored by SCS personnel during periods of heavy precipitation and runoff.

4.4 Evaluation: The dam and appurtenances are in good operating condition, and maintenance of the dam appeared to be excellent. An emergency operation and warning plan should be developed. It is recommended that a formal emergency procedure be prepared and furnished to all operating personnel. This should include:

- a. How to operate the dam during an emergency.
- b. Who to notify, including public officials, in case evaluation from the downstream area is necessary.

STATION 2 - IRRIGATION HEADWORKS

5.1 Design: Leatherwood Creek Dam No. 21 Dam was designed by the U.S. Conservation Service (SCS) as a multi-purpose dam, and hydrologic and hydraulic data is available. Floods to 1940 and stage data were used in the evaluation. This structure is a class "A" dam according to the SCS classification method.

5.2 Hydrologic Records: There are no records available.

5.3 Flood Experience: According to Mr. Thomas E. Wagner, an estimated maximum pool elevation of 1189 feet occurred in April 1940. This corresponds to a peak flow of approximately 100 CFS.

5.4 Flood Potentials: In accordance with the established guidelines, the Spillway Design Flood (SDF) is based on the estimated "Probable Maximum Flood" for the region (1100 discharges that may be expected from the most severe combination of physical meteorologic and hydrologic conditions that are reasonably possible in the region) or fractions thereof. The Probable Maximum Flood (PMF) and 5 PMF hydrographs were developed by the IBM-7090 Computer Program (Reference 4, Appendix VI). Precipitation amounts for the flood hydrograph of the PMF were taken from the U. S. Weather Bureau Information (Reference 5, Appendix VI). Appropriate adjustments for basin size and shape were accounted for. These hydrographs were routed through the reservoir to determine maximum pool elevations.

5.5 Reservoir Regulations: For routing purposes, the pool at the beginning of flood was assumed to be at elevation 782.2 msl. Reservoir stage-storage data and stage-discharge data were utilized from the existing design report. Floods were routed through the reservoir using the principal spillway discharge up to a pool storage elevation of 804 msl and a combined principal and emergency discharges for pool elevations above 813.4 msl. Pool elevations above 813.4 msl were routed over the non-overflow section of the dam.

5.6 Overtopping Potential: The predicted rise of the reservoir pool and other pertinent data were determined by routing the flood hydrographs through the reservoir as previously described. The results for the flood conditions ($\frac{1}{2}$ PMF and PMF) are shown in the following Table 5.1:

TABLE 5.1 - RESERVOIR PERFORMANCE

	Normal Flow	Hydrograph	
		1/2 PMF	PMF
Peak Flow, CFS			
Inflow	6	11,578	23,156
Outflow	6	10,193	22,726
Maximum Pool Elevation Ft, msl	782.5	816.43	819.35
Non-Overflow Section (Elev 813.4 msl)			
Depth of Flow, Ft	-	3.0	4.2
Duration, Hours	-	4	4
Velocity, fps *	-	0.4	0.5
Tailwater Elevation Ft, msl	761.5	761.4	761

*Critical velocity

5.7 Reservoir Emptying Potential: A reservoir maintained at an elevation 763 msl is capable of draining to the invert of the drawdown outlet pipe. Assuming that the draw is at normal pool elevation (782.5 msl) there is 6 cfs inflow, it would take approximately 10 days to lower the reservoir elevation to 761 msl. This is equivalent to an approximate drawdown rate of 1.5 ft/day based on the hydraulic height measured from normal pool to the invert of the drawdown pipe divided by the time to drawwater the reservoir.

5.8 Evaluation: The U. S. Army, Corps of Engineers' guidelines indicate the appropriate Spillway Design Flood (SDF) for an intermediate size, significant hazard dam is the $\frac{1}{2}$ PMF to PMF. Because of the risk involved, the $\frac{1}{2}$ PMF has been selected as the SDF. The spillway will pass 30 percent of the PMF without overtopping the crest of the dam (60 percent of the SDF). During the SDF, the dam will be overtopped for four hours up to a maximum of 3 feet and reach a maximum velocity of 7.4 fps.

Hydrologic data used in the evaluation pertains to present day conditions with no consideration given to future development.

The site is located on the eastern side of the Rich Acres Formation. The Rich Acres Formation is a sequence of igneous rocks that is approximately 100 million years old. The Rich Acres Formation is composed of coarse-grained granites, metamorphosed gabbros and diorites. These rocks are similar in appearance to granites, but are comprised of more basic or darker colored minerals. The Leatherwood Granite, typically a coarse-grained to porphyritic granite, usually occurs as dikes or thin sheets on top of the Rich Acres Formation. Both rock units are believed to be from the same magma. Detailed geologic maps of the area do not indicate the presence of any faults in the site vicinity. Site geology is presented in more detail in the Design Geologic Report, which is included as Appendix IV.

The subsurface investigation indicated that along centerline of the dam the site was underlain by shallow alluvial and residual soils over weathered bedrock. The "firm bedrock" surface ranges in depth from 5 to 14 ft below the ground surface along the principal spillway. Bedrock was encountered at ground surface near the center of the section, at depths of 2 to 6 at the abutments, and below 10 ft at the principal spillway outlet. Hard unfractured rock underlies the toe drain at generally 2 to 7 ft below

the design of the dam. The design of the dam was based on the results of the tests and the design of the dam was based on the results of the tests.

The design of the dam was based on the results of the tests and the design of the dam was based on the results of the tests. The design of the dam was based on the results of the tests and the design of the dam was based on the results of the tests.

The potential for seepage through the foundation was recognized and a cutoff extending into the rock was specified. Moderate permeabilities ranging from 10 to 100 gpd were anticipated for the foundation soils and the designer expected some seepage through all weathered bedrock.

iii. Embankment:

1.1.1. Materials: "As built" drawings describe the dam as a zoned structure. Section No. 1 of the dam, consisting of the cutoff and interior core, was constructed with soils classifying as SM and MH. Section No. 2 (the upstream slope and crest) was constructed with SM and ML materials, while Section No. 3 (the downstream slope) was constructed with SM materials. All fill materials were excavated from select borrow areas. Materials in all three sections were to be compacted to 95% of maximum dry density in accordance with ASTM Standard D-698 (Standard Proctor). Compacted densities and shear strength values for the embankment

materials are summarized on page 2 of Appendix V. Specifications for maximum lift thickness and maximum rock sizes were not observed in the design data provided.

No one-dimensional consolidation test was performed, however, the SCS soils mechanics laboratory estimated from the consolidation phase of the shear tests that at least 6% settlement would be expected or an average of 3% based on fill height.

6.2.2 Subdrains and Seepage: In attempt to control seepage, a cutoff was constructed to "firm bedrock" below the more permeable alluvial soils in the floodplain and extending into the abutments. The bottom of the cutoff trench is 12 ft wide and side slopes are 1H:1V. An internal drainage system was also constructed, consisting of approximately 140 ft of 6 inch perforated bituminous coated corrugated metal pipe enclosed in an envelope of graded drain fill of variable depth. Drainage pipes were provided for transmitting the collected water to the plunge pool. Details are presented on Plate 4 of Appendix I. During the field inspection, it could not be determined if the drains were functioning properly because the drain inverts were slightly below the discharge pool level. In attempt to prevent piping around the principal spillway pipe, 8 anti-seep collars were included as shown on Plate 5 of Appendix I.

6.2.3 Stability: A stability analysis was performed for this structure and the report describing the engineering design data used is included as Appendix V. These data were reviewed along with the stability analysis and were found to be acceptable. The factor of safety of the upstream slope for the full drawdown condition is 1.28 as given in Appendix V. Reference 1, Appendix VI recommends a factor of safety of 1.2.

The factor of safety for the downstream slope is indicated to be 1.43. The required factor of safety is 1.5 according to Reference 1. The design report stated, "An analysis of a 50 ft embankment, with the shear strength found in these embankment tests and one from Site 5 show acceptable safety factors for the proposed slopes."

The dam is 52 ft high and has a crest width of 12 ft. "As built" drawings show a crest width of 17 ft. The upstream slope is 2.5H:1V with a 10 ft wide berm at pool level between elevations 782.7 and 783.7 msl. The upstream slope then continues at a 3H:1V slope below normal pool. The downstream slope is 2.5H:1V. The dam is subjected to a sudden draw-down since the lake level can be drawn down at a rate of 18 ft/day. This exceeds the critical rate of 0.5 ft per day for earth dams.

6.2.4 Seismic Stability: The dam is located in Seismic Zone 2. Therefore, according to the Recommended Guidelines for Safety Inspection of Dams, the dam is considered to have no hazard from earthquakes provided static stability conditions are satisfactory and conventional safety margins exist.

6.3 Evaluation: Based upon the visual inspection and the design report, the foundation is considered sound. The factor of safety for the upstream slope during the drawdown condition meets the U. S. Army, Corps of Engineers guidelines. Although the factor of safety of 1.43 calculated for the downstream slope under steady seepage condition is slightly less than the 1.5 factor of safety recommended in Reference 1, Appendix VI, this difference is considered minor, particularly in lieu of the performance history of this structure.

Overtopping is considered detrimental to the dam with respect to erosion because of the depth and duration of flood and also the velocity is greater than 6 fps, the effective eroding velocity for a vegetated earth embankment. Furthermore, the embankment crest appears to be 5 ft narrower than shown on the "as built" drawings.

Since no undue settlement, cracking or sloughing was noted at the time of inspection, it appears that the embankment is adequate for maximum control storage with water at elevation 782.5 msl.

SIXTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment: Sufficient engineering data is available for assessing the dam. The visual inspection revealed no findings that proved the dam to be unsound. There is an annual inspection and maintenance program for this structure, but there is no emergency operation and warning plan. Overall, the dam was in excellent condition at the time of inspection. U. S. Army, Corps of Engineers guidelines indicate the appropriate Spillway Design Flood (SDF) for this dam is the $\frac{1}{2}$ PMF. The spillway will pass 30 percent of the PMF (60 percent of the SDF) without overtopping the crest of the dam. Flows overtopping the dam at a maximum velocity of 7.4 fps during the SDF are considered detrimental to the embankment with respect to erosion. A dam breach during the SDF would significantly increase the hazard to loss of life downstream of the dam over that which would exist just before overtopping failure. The spillway is judged seriously inadequate. Review of available stability data indicates the structure is stable as designed. Field measurements indicate the embankment crest is 5 ft narrower than shown on "as built" drawings.

Due to the inadequacy of the spillway and the resulting overtopping of the dam during the SDF, and also the narrow crest width, the potential for a breach of the dam exists. Based upon the possibility of a dam breach caused by overtopping during the SDF, the dam is assessed "unsafe, non-emergency."

The classification of "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for

a structural deficiency. It does mean, however, that based on an initial screening, and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard to loss of life downstream from the dam.

7.2 Recommended Remedial Measures: A qualified engineering firm should be retained to perform a detailed hydrologic/hydraulic analysis of the downstream damage reach with a dam breach simulation. The owner is required to engage the services of a qualified engineering firm within two months of the issuance of the approved Phase I inspection report. The owner is required to have the consultant's report and to have reached an agreement with the Commonwealth of Virginia regarding required remedial measures within six months of the date of the issuance of the approved Phase I inspection report.

7.3 Required Maintenance: A formal emergency procedure should be prepared and furnished to all operating personnel. This should include how to operate the dam during an emergency, and who to notify including public officials, in case evacuation from the downstream area is necessary. In the interim the dam and reservoir should still be monitored during periods of heavy precipitation and runoff. Also, the inspection revealed the following maintenance items that should be scheduled by the owner during a regular maintenance period within the next 12 months:

- a) All brush growing on the embankment should be cut to the ground and removed from the embankment.
- b) The area of sloughing in the right abutment should be stabilized.
- c) The minor sloughing located above the outlet works should be monitored during maintenance. If increased erosion should occur, this area should be stabilized by backfilling and reseeding.
- d) Debris should be removed from the trash rack.
- e) The broken bar on the trash rack should be repaired.
- f) A staff gage should be installed to monitor water levels.

APPENDIX I
MAPS AND DRAWINGS





LEATHERWOOD
NO. 2A



PLATE I
SCALE: 1" = 24,000'


MARTINSVILLE EAST, VA.
NO. 115 W 1945 75





TOP OF DAM ELEV 8134
TOP WIDTH 17.0

LIA' GATE



GENERAL NOTES

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.

2. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES.

3. ALL WORK SHALL BE COMPLETED WITHIN THE SPECIFIED TIME FRAME.

4. THE CONTRACTOR SHALL MAINTAIN THE EXISTING UTILITIES AND STRUCTURES UNLESS OTHERWISE SPECIFIED.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING TREES AND LANDSCAPE FEATURES.

6. ALL MATERIALS AND METHODS SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

7. THE CONTRACTOR SHALL MAINTAIN RECORDS OF ALL WORK DONE AND SUBMIT THEM TO THE ENGINEER UPON COMPLETION.

8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL WORKERS AND THE PUBLIC DURING THE CONSTRUCTION PERIOD.

9. THE CONTRACTOR SHALL MAINTAIN THE WORK AREA CLEAN AND FREE OF OBSTACLES AT ALL TIMES.

10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL ADJACENT PROPERTIES AND UTILITIES.

11. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES.

12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING TREES AND LANDSCAPE FEATURES.

13. THE CONTRACTOR SHALL MAINTAIN RECORDS OF ALL WORK DONE AND SUBMIT THEM TO THE ENGINEER UPON COMPLETION.

14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL WORKERS AND THE PUBLIC DURING THE CONSTRUCTION PERIOD.

"AS BUILT"


ENGINEER: JOHN W. GREEN, CIVIL ENGINEER
 LEADSVILLE, GREEN MOUNTAIN, VA
 PLAN (FOR USE BY EMBLEM ONLY)

U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE


DATE: 8-23-64
 DRAWN BY: J.W.G.
 CHECKED BY: J.W.G.

PLATE 2


VA-482-P



PROFILE ALONG STREAM CENTER AS SHOWN BY DOTTED LINE







PROFILE ALONG CENTER AS SHOWN BY DOTTED LINE



PROFILE ALONG CENTERLINE OF PRINCIPAL SPILLWAY.


NOTE
 1. The dam is designed to be built with concrete.
 2. The dam is designed to be built with a crest width of 10 feet.
 3. The dam is designed to be built with a crest height of 10 feet.
 4. The dam is designed to be built with a crest length of 10 feet.
 5. The dam is designed to be built with a crest width of 10 feet.
 6. The dam is designed to be built with a crest height of 10 feet.
 7. The dam is designed to be built with a crest length of 10 feet.
 8. The dam is designed to be built with a crest width of 10 feet.
 9. The dam is designed to be built with a crest height of 10 feet.
 10. The dam is designed to be built with a crest length of 10 feet.



"AS BUILT"
 "AS BUILT"

DAM NO 24 LEATHERWOOD CREEK
 LEATHERWOOD CREEK WATERFURNING
 PROJECT, COLORADO
 PROFILES
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

PLATE 3




NOTES


1. THE STAINLESS STEEL SHALL BE AT THE DESIGNATED LOCATION TO BE IN PLACE.
2. THE STAINLESS STEEL SHALL BE 1/4" THICK.
3. THE STAINLESS STEEL SHALL BE 1/4" THICK.
4. THE STAINLESS STEEL SHALL BE 1/4" THICK.

SECTION NO. 1
 1/2" 5M 8 MM MATERIAL
 REPRESENTED BY THE LOGS OF
 EMERGENCY SPILLWAY TO 100
 AND 200 TO 100



SECTION NO. 2
 1/2" 5M 8 MM MATERIAL REPRESENTED
 BY THE LOGS OF EMERGENCY SPILLWAY
 TO 100 TO 200 TO 200 & 100
 AND 200 TO 100 & 100








SECTION OF TRENCH DRAIN
 NOT TO SCALE



SECTION ALONG CENTERLINE OF TRENCH DRAIN







"AS BUILT"

"As Built"
 DAM NO 2A LEATHERWOOD CREEK
 LEATHERWOOD CREEK WATERSHED
 HENRY COUNTY, VIRGINIA
 SEEPAGE DRAIN DETAILS
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE
 J. M. QUINN 12/63
 C. B. FORD 12-63
 S. C. ...
PLATE 4
 VA-482-P

11 14



NATURAL BOUNDARY LINE



SECTION 2.2


AS BUILT

AS BUILT

U.S. DEPARTMENT OF WAR
ENGINEERING DIVISION
CONSTRUCTION DIVISION
SOUTH PACIFIC AREA
SOUTH PACIFIC DIVISION
SOUTH PACIFIC DIVISION
SOUTH PACIFIC DIVISION
SOUTH PACIFIC DIVISION

PLATE 5

17650



On the left side of the page, there is a vertical column of text that is mostly illegible due to the high contrast and noise of the scan. It appears to be a list or index of items, possibly related to the plate's content.




—

PLATE 6



1. 2" DIA. STEEL PIPE
 TO BE CONTINUOUS ABOUT
 2" DIA. W. 4" DIA. ST. BAR
 JOINTS
 2. WALL TO BE:


2" DIA. STEEL PIPE

1. 2" DIA. STEEL PIPE
 TO BE CONTINUOUS ABOUT
 2" DIA. W. 4" DIA. ST. BAR
 JOINTS
 2. WALL TO BE:



1. 2" DIA. STEEL PIPE
 TO BE CONTINUOUS ABOUT
 2" DIA. W. 4" DIA. ST. BAR
 JOINTS
 2. WALL TO BE:






"AS BUILT"
 DRAWN BY LAURENCE...
 ENGINEERED THEIR...
 A NEW DESIGN

APPENDIX II

PHOTOGRAPHS



Photograph No. 1 - Upstream Slope



Photograph No. 2 - Downstream Slope



Photomicrograph of *Trichostema*



Photomicrograph of *Trichostema*



View of the ... railway

APPENDIX III
FIELD OBSERVATIONS

Check List
Visual Inspection
Phase I

Lat 36°-44.3'
Long 79°-48.6'

Name Dam Leatherwood No. 2A County Henry State Virginia Coordinates _____

Date(s) Inspection July 1, 1981 Weather Partly Cloudy Temperature 72°f

Pool Elevation at Time of Inspection 782.5 msl Tailwater at Time of Inspection 761.5 msl

Inspection Personnel:

Schnabel Engineering Associates, P.C.
James J. Sell
Stephen G. Werner
Raymond A. DeStephen, P.E.*

J. K. Timmons & Associates
Robert G. Roop, P.E.
Steve Oddi

Recorders
Stephen G. Werner
Steve Oddi

State Water Control Board
Leon Musselwhite
Owner
Thomas F. Walker

* Not present during this inspection, but visited site on August 17, 1981.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SURFACE CRACKS

Scattered shrinkage cracks were observed on the embankment; particularly near the right abutment. They were generally "pencil mark" in width and are the result of drought conditions. Ground conditions were dry at the time of the inspection.

No problem.

UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE


No unusual movements were noted on the dam or beyond the downstream toe.

SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES

A very small area of sloughing was noted on the downstream slope directly above the outlet works. The right abutment has an area of sloughing located 15 ft± below the crest of the dam. The area is 15 ft± long and 5 ft± high. This area is bare and has experienced some washing. It is in the abutment and does not create any problem.

VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST

The vertical and horizontal alignment of the dam appeared to be good. Note adjacent field measurements.



RIPRAP FAILURES

There was no riprap on the upstream slope. Riprap consisting of 1 to 2 ft± granite blocks was located below the discharge section at the end of the energy dissipator. The riprap was functioning properly and appeared to be in good condition.


EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SECTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND GUY	Both ends of the embankment tie in properly with the abutments. The right abutment is vegetated and includes numerous outcrops downstream. The emergency spillway occupies the left abutment.	-
ANY NOTICEABLE SEEPAGE	No seepage was encountered. The downstream toe is dry.	-
CRACKS	Two 6 inch c.p. drains with 5 reinforcing bars over each end exist on the left and right sides of the emergency dissipator. Iron staining was noted at the end of the pipes, but couldn't tell if there was flow since the pipe invert was below the stilling basin pool level.	-
MATERIALS	The embankment surface consists of light brown to red fine to medium sandy silt with mica (M). Includes scattered gravel and small boulders less than 1 ft long.	-
VEGETATION	The embankment is grassed and is well maintained. Cattle are allowed to graze on the embankment. Scattered patches of brush (1" - 2" diameter) are growing 5 to 10 ft ⁺ above pool level on the upstream slope to the right of the intake structure. A few small bushes and weeds also occur on the downstream slope.	The brush should be removed.

PRINCIPAL SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONTROL SECTIONS	Concrete riser type structure with low level orifice and high level weir. In good condition but 1 bar is broken on the trash rack. There was some debris present in the low flow intake trash rack.	The debris should be removed from the trash rack and the broken bar on the rack should be repaired.
APPROACH CHANNEL	-	-
DISCHARGE CHANNEL	13 ft wide energy dissipater. The plunge pool is lined with riprap. The outlet is a 36 inch concrete pipe.	-
RAILS AND PIERS	-	-
EMERGENCY GATE	-	-
GATES AND OPERATION	Has a crank drain system, which according to the owner, has never been used.	-

EFFICIENCY SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONTROL SECTIONS	The left side of the control section contains slightly to highly weathered leatherwood granite, same as described below. Gneissic portion has foliation strike of N85E and vertical dip.	-
APPROACH CHANNEL	The basal 15 ft of the approach channel includes large flat outcrops of leatherwood granite. It includes slightly weathered, gray or ash - grained granite with xenoliths and flow banding.	-
DISCHARGE CHANNEL		
BRIDGE AND PIERS		
MISCELLANEOUS		Good vegetation. No erosion.

GENERAL INFORMATION

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATION
CONCRETE SURVEYS	-	-
OBSERVATION WELLS	-	-
WELLS	-	-
PUMPMEYERS	-	-
STATWAYS	-	Should be installed.
OTHER	-	-

RESERVOIR

VISUAL EXAMINATION

OBSERVATIONS

REMARKS AND RECOMMENDATIONS

Shoreline appears stable - no erosion observed.
40:17± side slopes bound the reservoir.
Left side - moderate, densely wooded slopes
Right side - grassed 100 - 200 ft above the
lake then wooded, moderate slopes.
Scattered granite outcrops occur at pool level
along the left side. The reservoir area was
free of debris.

SLOPES

According to Mr. Walter several fishermen have
commented that the lake appears to be silting
up in the upper reaches. The water is very murky.

SEDIMENTATION

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF OBSERVATIONS REMARKS OR RECOMMENDATIONS

CONDITION 15 ft wide and 5 ft high, tree-lined, 100 ft wide flood-plain. Road crosses 500 ft downstream, 14 ft above stream bed. $n = 0.06$
(CONSTRUCTIONS, DEBRIS, ETC.) $n = 0.05 - 0.1$

SLOPES 3H:1V⁺ side slopes. Pasture on left, $n = 0.05$
Woods on right, $n = 0.06$

APPROXIMATE NO. OF HOMES AND POPULATION Approximately 2 miles downstream there is a dwelling 15 ft⁺ above the stream channel. Approximately 5 miles downstream there are several dwellings 10 ft⁺ above the channel and several commercial facilities 15 ft⁺ above the channel.

CHECK LIST
 ENGINEERING DATA
 DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
REGIONAL VICINITY MAP	Martinsville East 7, minute topographic map (U.S.G.S.)
DESIGN/CONSTRUCTION HISTORY	Designed by USDA SCS. Constructed by Curtis S. Horton and completed in 1964.
PLAN OF DAM	See Appendix I
TYPICAL SECTIONS OF DAM	See Appendix I
OUTLETS - PLAN DETAILS CONSTRAINTS DISCHARGE RATINGS	See Appendix I
SPILLWAY- PLAN SECTION DETAILS	See Appendix I
OPERATING EQUIPMENT - PLAN DETAILS	See Appendix I

ITEM	REMARKS
MONITORING SYSTEMS	-
RAINFALL/RESERVOIR HIGHPOOL RECORDS	-
GEOLOGY REPORTS	See Appendix I and Reference 3, Appendix VI
BORROW SOURCES	-
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY-FIELD TEST DATA	-
HYDROLOGIC/HYDRAULIC DATA	Design data available at USDA, SCS office in Piedmont, Virginia

ITEM	REMARKS
DESIGN REPORTS	<p>Summary included as Appendix IV. Complete Design Report available at USDA, SCS office in Richmond, Virginia -</p>
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULIC DAM STABILITY SEEPAGE STUDIES	<p>Available at USDA, SCS office in Richmond, Virginia -</p>
POST CONSTRUCTION ENGINEERING STUDIES RECORDS, SURVEYS	<p>As built drawings included in Appendix I -</p>
MODIFICATIONS	<p>None -</p>
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	<p>None -</p>
MAINTENANCE OPERATION RECORDS	<p>None -</p>

APPENDIX IV
DESIGN REPORT

LEATHERWOOD
FLOOD RETENTION PROJECT
LEATHERWOOD, VA
HARRIS COUNTY, VIRGINIA

This floodwater retaining wall is located on the West Fork of Leatherwood Creek approximately 3-1/2 miles west of Leatherwood, Virginia. Sheet 2 of this report, together with the Martinsville, Virginia-North Carolina 15-minute quadrangle published by the U.S. Geological Survey, may be used to locate the structure.

A summary of pertinent design information is given on sheet 2 of this report.

Criteria and procedures used in this design are given in the following Soil Conservation Service publications:

National Engineering Memorandum No. 27, Limiting Criteria for the Design of Earth Dams
National Engineering Memorandum No. 42, Reinforced Concrete Pipe Drop Inlet Barrels
National Engineering Handbook No. 4, Hydrology
National Engineering Handbook No. 5, Hydraulics
National Engineering Handbook No. 6, Structural Design
Engineering Division Technical Release No. 2, Earth Spillways
Engineering Division Technical Release No. 5, Structural Design of Underground Conduits
Engineering Division Technical Release No. 10, Storage--Floodwater Retarding Structures
Engineering Division Technical Release No. 12, Procedure for Computing Seepage Requirements for Retarding Reservoirs
Engineering Division Technical Release No. 18, Joint Gap Computation for Reinforced Concrete Pipe Drop Inlet Barrels

This is one of five flood retention structures designed to reduce flooding in the Leatherwood valley. It will retard a 50-year frequency storm without discharge occurring in the emergency spillway.


The results of hydrologic and hydraulic computations are given on sheet 3 of this report.

The structure consists of a compacted earth fill with a cutoff through alluvial sands in the foundation. A drainage system is located under the downstream portion of the earth fill to collect seepage.

The principal spillway is a drop inlet structure consisting of a reinforced concrete riser, 36-inch diameter concrete water pipe, and a Bradley Perterka impact basin to dissipate energy at the outlet end of the conduit.

The emergency spillway is designed as an earth and rock cut in the left abutment with the control section on Leatherwood Granite.

I. Watershed Data			
A. Structure class (Refer to Engineering Manual)		(6)	
B. Drainage Area			A.
C. Line of concentration -			ft.
D. Hydrologic curve number -			
1. Moisture condition II		7	
2. Moisture condition III		5.5	
II. Principal spillway			
A. Conduit			
1. Size (D.I.)		17	in.
2. Length		10.0	ft.
B. Piler			
1. Size		5.0	ft.
2. Height		11.0	ft.
C. Weir length		12.0	ft.
D. Grillage size		12.0	in.
E. Pond drain size		2	in.
F. Type of energy dissipator - concrete impact basin			
III. Emergency spillway			
A. Width		80	ft.
B. Side slopes - 1/1.1 in rock, 1.1 in soil			
C. Length of level section		10	ft.
D. Exit slope		1/1.1	ft./ft.
E. Maximum velocity at control section (I.H.W.)		1.5	ft./sec.
F. Duration of flow (I.H.W.) through emergency spillway		10	hrs.
G. Frequency of use		once in 10 years	
IV. Earth fill			
A. Height		5	ft.
B. Volume		1000	cu. yd.
C. Compaction		95%	



Typical Cross Section

U S DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

Estimated 2.4

Element of Structure	Determining Factor	Elevation	Surface Area Acres	Storage		Inflow		Peak Outflow c.f.s.
				Acre-Feet	Inches*	Volume Inches*	Rate c.f.s.	
Invert of orifice	50-year sediment accumulation	740.0	20.4	122 ^{1/2}	-	-	-	-
Crest of riser	1 inch of runoff	734.0 ^{2/3}	40.3	346 ^{2/3}	1.06	-	-	-
Crest of emergency spillway	50-year frequency storm, moisture condition II	684.0 ^{3/4}	67.2	882 ^{3/4}	2.69	-	-	140
Design high water	0.6 X 6-hour point rainfall, moisture condition II	676.5	74.5	908 ^{2/3}	2.84	5.85	2,634	450
Top of dam	1.0 X 6-hour point rainfall, moisture condition II	615.4	-	1,452 ^{2/3}	4.44	8.02	5,455	3,900

*Inches of runoff from controlled area of 4,000 acres.
Time required to empty flood storage is 9.4 hrs.

- 1/ Does not include 14 acre-feet of sediment allocated to flood pool.
- 2/ Does not include storage allocated to sediment.
- 3/ Established by procedure described in technical release No. 10.


U S DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

LEATHERWOOD CREEK WATERSHED PROTECTION PROJECT

SITE NO. 2A

VA-482

HENRY COUNTY, VIRGINIA



Reference

MARTINSVILLE, VA-NC

15' QUAD

1947

ENGINEERING & WATERSHED PLANNING UNIT, UPPER DARBY, PA

U S DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

Reports concerning soil engineering tests and the geologic conditions at this site are included in this design folder.

Copies of the publications referred to in this report may be obtained from Mr. Tom F. McGourin, State Conservationist, USDA, Soil Conservation Service, Richmond, Virginia.

Concurred:

Stanley C. Rossier
for
Gerald E. Oman
Design Engineer

R. C. Barnes, Jr.
State Conservation Engineer

Joseph W. Keever
for
Vincent McKeever
Hydrologist

Robert F. Fonner
Robert F. Fonner
Geologist

DETAILED GEOLOGIC INVESTIGATION OF DAM SITES

GENERAL

State Virginia County Henry Sec. T. R. Watershed Leatherwood Creek
 Subwatershed Fund class FP-08 Site number 2A Site group I Structure class
 (FP-2, WF-1, etc.)
 Investigated by L.A. Gorman, Geologist Equipment used Case backhoe Date 4/63
 (signature and title) (Type, size, make, model, etc.)
T. Mack, Soil Scientist

SITE DATA

Drainage area size 6.14 sq. mi. 3929 acres Type of structure Earth Fill Purpose Flood Prevention
 Direction of valley trend (downstream) ESE Maximum height of fill 40.7 feet Length of fill 355 feet
 Estimated volume of compacted fill required 47,201 cubic yards

STORAGE ALLOCATION

	Volume (ac. ft.)	Surface Area (acres)	Depth at Dam (feet)
Sediment	<u>124</u>	<u>20.4</u>	<u>14</u>
Floodwater	<u>850</u>	<u>66.0</u>	<u>33</u>

SURFACE GEOLOGY AND PHYSIOGRAPHY

Physiographic description Piedmont Province Topography rolling Attitude of beds Dip none Strike none
 Steepness of abutments Left 37 percent Right 35 percent Width of floodplain at centerline of dam 170 feet

General geology of site The site is underlain by Leatherwood granite which is of Paleozoic age. In this area this formation is a syenite. Minerals in this syenite are feldspar, biotite, muscovite, and some quartz. As outcrops of a migmatite occur northeast of the dam site, there appears to have been lit-par-lit action present. These outcrops are scattered which shows that the interspersing of igneous and metamorphic rocks is fine. Minerals present in the injection gneiss are feldspar, hornblende and garnet. Deeply weathered areas that contain a high content of phlogopite, and sericite mica are present. In other areas the residual soil is extremely shallow.

The west fork of Leatherwood Creek flows through a comparatively narrow stream valley at the dam site. The floodplain here is filled with recent stream alluvium which is unconsolidated SM with some ML. The stream channel is slowly degrading. This process is retarded by colluvial material moving into the stream channel from the adjacent hillsides. This stream flows in a strongly entrenched dendritic pattern. The topography has reached early maturity.

Centerline -

The right and left abutments of the dam centerline are underlain by syenite. On both

2 - Detailed Geologic Investigation of Dam Sites - Leatherwood Creek - Site 2A

abutments the lower elevations (770 to 790 feet) have shallow soils with the root zone ranging from 2 to 6 feet below the ground surface. The higher elevations on the centerline (790 feet and above) have deeply weathered soils. Recent stream alluvium to a depth of 10 feet fills the flood plain on the centerline.

No fractures were observed in the granite outcrops in the area of the dam centerline. This unfractured condition is characteristic of the Leatherwood granite. This formation is used for large stone monuments.

Hard unfractured rock underlies the toe drain at generally 1 to 7 feet below the original ground surface. The lower parts of both abutments have shallow soils on the centerline of the toe drain. A granite spine underlies the toe drain in the flood plain. However, this spine drops off sharply within 5 feet upstream of the toe drain.

Emergency Spillway -

The emergency spillway is located in the left abutment. A rockline of massive igneous rock that ranges from 2 to 11 feet below the ground surface underlies the spillway from station 1 + 50 ~~to station~~ to station 3 + 30. Between these stations the left side of spillway will have a rock floor. From station 3 + 30 to 1 + 70 deeply weathered micaceous soil underlies the spillway. In this area no rockline was found although one test pit (TP 215) was dug to depth of 17 feet.

Shallow Louisburg soil occurs on the left slope from station 1 + 50 to 3 + 30. It is red and silty with a blocky structure of interspersed clay films. Permeability and low waterlogging properties for this soil appear to be better than for any other soil in the spillway cut. The area comprising the right side of spillway and the left slope downstream from station 3 + 30 has micaceous to highly micaceous soil present. These soils appear elastic and hard to compact. Soil of this type also occurs on the entire length of the right slope.

A few outcrops of hornblende gneissiferous granite were observed in the emergency spillway area. No fracture zones can be expected in the contact zone between the granite.

Principal Spillway -

Granite underlies the center line of the principal spillway. It is firm. In places the ranges in depth from 5 to 14 feet below the ground surface. The deepest section is under the riser and the outlet. The closest this rockline is to the ground surface is under the toe drain. A rockline cross section is included in the plans.


The waterline ranges from 10 to 6 feet below the surface of the ground. A gray reduced zone of SC is present 7 to 12 feet below the ground surface. This zone ranges from 1 to 2 feet in thickness. It is slightly organic, wet, and unstable.

Borrow Area -


Two borrow areas were investigated. One is located 300 yards upstream from the dam centerline. This area is underlain by recent stream alluvium bordering both banks of the west fork of Leatherwood Creek. It is in the permanent pool area. Only the upper 5 feet of this alluvium are useable. This is the brownish oxidized zone of ML and SM that makes the Congaree soil. Below this is a dark gray reduced zone of SC that is unstable and unuseable. In wet weather this lower reduced gray zone will limit the amount of material that can be taken from the upper zone. This is due to the danger

of heavy equipment mining down in the lower unstable alluvium.


The second borrow area is located upstream on the right side of the road. The upper 5 to 6 feet of this soil is good construction material. The lower part is a fine sand that can be used but is not as good as the upper material. This area is close to the dam and has a down-grade haul.



Leatherwood granite and gneiss with
deposited conglomerates



Leatherwood granite with orthoamphibolite
structure (boundary diffuse)



GEOLOGIC MAP OF THE AREA SURROUNDING SITE NO. 2A
LEATHERWOOD CREEK W/S, HENRY COUNTY, VIRGINIA

APPENDIX V
STABILITY DATA

UNITED STATES GOVERNMENT

Memorandum

TO : R. C. Barnes, State Conservation
Engineer, SCS, Lincoln, Nebraska

DATE: August 27, 1968

FROM : Rey S. Decker, Head, Soil Mechanics Laboratory,
SCS, Lincoln, Nebraska

SUBJECT: Virginia WP-08, Leatherwood Creek, Site No. 2-A

ATTACHMENTS

1. Form SCS-354, Soil Mechanics Laboratory Data, 2 sheets.
2. Form SCS-355, Triaxial Shear Test Data, 2 sheets.
3. Form SCS-352, Compaction and Penetration Resistance Report, 10 sheets.
4. Form SCS-353, Filter Material, 1 sheet.
5. Form SCS-357, Summary - Slope Stability Analysis, 1 sheet.
6. Form SCS-372, Recommended Use of Excavated Material, 1 sheet.
7. Geologic Plans and Profiles.

INTERPRETATION AND DISCUSSION OF DATA

FOUNDATION MATERIALS

- A. Classification and Description: The site is on slightly weathered granite. The soil cover ranges up to 14 feet thick. Soils class as CL, SC, MH, ML and SM and are slightly to highly micaceous.
- B. Consistency, Strength and Compressibility: No information on the consistency or in-place density of the foundation soils was submitted. We have assumed them to be as strong and as slightly compressible as cores submitted from Site 5. The stability is checked on this basis and should be reviewed if our assumption is considered to be wrong.
- C. Permeability: Rates of 0.1 ft./day to 10 ft./day are assumed for the foundation soil materials as found from tests on Site 5.

This rock is described as less weathered and is considered impermeable.

EMBANKMENT MATERIALS

- A. Classification: Borrow samples submitted were MH, ML and SM. Most of them are deep vertical composites and the surface 3 to 4 feet in places may class as CL or SC. Those areas described as red and non-micaceous or only slightly micaceous may be in this class.

2 -- R. C. Barnes -- 2/27/63

Ray S. Decker

Subj: Virginia WP-08, Leatherwood Creek, Site No. 2-A

- B. Compacted Dry Densities: Standard Proctor compaction yielded maximum dry densities of 86.0 p.c.f. to 93.0 p.c.f. for MH, 86.0 p.c.f. to 108.0 p.c.f. for ML and 92.0 p.c.f. to 110.0 p.c.f. for SM.
- C. Permeability: No tests were made. Rates will be low except in the low-density SM, Sample 63W3849, and in the low-density ML, Sample 63W3853. Rates would be expected in a range of .01 ft./day to 2.0 ft./day in the compacted material.
- D. Shear Strength: Two samples from the emergency spillway were tested, an SM and an MH. Specimens were molded at 95% of Standard and soaked before testing in consolidated, undrained triaxial shear. Parameters from the tests are $\phi = 30^\circ$, $c = 425$ p.s.f. for the SM and $\phi = 23^\circ$, $c = 550$ p.s.f. for the MH. These values are recommended for design.
- E. Consolidation: No one-dimensional test was made; however, from the consolidation phase of the shear tests it appears that at least 6% would be expected, or an average of 3% based on fill height.

STABILITY ANALYSIS

An analysis of a 50-foot embankment with the shear strength found in these embankment tests and one from Site 5 show acceptable safety factors for the proposed slopes.

FORM SCS-357
10-58

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

SOIL MECHANICS LABORATORY
SUMMARY - SLOPE STABILITY ANALYSIS

State Virginia Project Leatherwood Camp
Date 5-14-62 Analysis Made By T. H. H. Checked By H.
Method of Analysis Summed Moments

Location of Material	1		2		3			
	γ _d	γ _m	γ _s	γ _b	γ _d	γ _m	γ _s	γ _b
Sample No.								
γ _d			1075	1075	1145			
γ _m			1145	1145	1215			
γ _s			1215	1215	1285			
γ _b			1285	1285	1355			
Condition	Opt.	Sat.	Opt.	Sat.	Opt.	Sat.	Opt.	Sat.
φ				25°		22°		22°
Tan φ				0.577		0.424		0.414
K								
C				1175		1175		1175

UPSTREAM SLOPE

Trial	Slope	Conditions	Fs
2	2 1/2'	Fill draw emb - 10' high - 1:1 slope - Fill draw emb - 10' high - 1:1 slope - Fill draw emb - 10' high - 1:1 slope -	1.15


DOWNSTREAM SLOPE

Trial	Slope	Conditions	Fs
1	2 1/2'	No draw - 10' berm - Arc cut 5' high - Fill draw emb 6' x 11' 2' x 11' - 1:1 - Fill draw emb 6' x 11' 2' x 11' - 1:1 -	1.15
1A	2 1/2'	Same as 1 except emb 6' x 11' 2' x 11' - 1:1 -	1.15
1B	2 1/2'	Same as 1 except emb 6' x 11' 2' x 11' - 1:1 -	1.15

To be used to report to field offices data used for slope stability analyses and the results of the analyses.
The right side of the form will be used for a sketch of the embankment on which the analyses have been made.

Continuation of report 1st (from 503-357)
 Potomac Creek Site #2A
 Virginia

Maximum Section
 Sta. 2+25



820

750

760


Scale 1 inch = 100 feet

SCS-377
(3/50)

RECOMMENDED USE OF EXCAVATED MATERIAL

Formal Zoning Plan Selective Placement Plan

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
Project No. _____
State _____
Date _____
By _____



TYPICAL EMBANKMENT SECTION

Embankment Section No.	Description	Source of fill material	Location	Ave. Depth		Lab. Sample No.	Lab Test	Composition for Minimum Class of Fill			
				From	To			Minimum Density	Moisture Range	Maximum Compaction	
1	Fill	Local	...	1	7	345
2	Fill	Local	...	1	6	345
3	Fill	Local	...	1	7	345
4	Fill	Local	...	1	11	345
5	Fill	Local	...	1	11	345
6	Fill	Local	...	1	11	345
7	Fill	Local	...	1	11	345

APPENDIX - BIBLIOGRAPHY

1. Manual for Safety Inspection of Dams, Department of Army, Office of the Chief of Engineers, 46 pp.
2. Design of Small Dams, U. S. Department of Interior, Bureau of Reclamation, 1964, 816 pp.
3. Failure of the Snow Creek, Martinsville East, Price and Spray Dams, Lee, Virginia by J. I. Morley and W. S. Henika, Virginia Division of Mineral Resources Reports of Investigations 33, 71 pp.
4. HEC-1 Dam Break Version, Flood Hydrograph Package, Users Manual for Dam Safety Investigations, the Hydrologic Engineering Center, U. S. Army Corps of Engineers, September, 1978.
5. Hydrometeorological Report No. 33, U. S. Department of Commerce, Weather Bureau, U. S. Department of Army, Corps of Engineers, Washington, D. C., April, 1956.
6. Technical Paper No. 40, U. S. Department of Commerce, Weather Bureau, Washington, D. C., May, 1961.