


PHOTOGRAPH THIS SHEET

AD A 126288

DTIC ACCESSION NUMBER



LEVEL



INVENTORY

Rept. No. 006-007, Rev. 0

DOCUMENT IDENTIFICATION

Final, Mar. - Apr. 81

Contract N00014-80-C-0821

9 Oct. '81

**DISTRIBUTION STATEMENT A**

Approved for public release;  
Distribution Unlimited

**DISTRIBUTION STATEMENT**

ACCESSION FOR	
NTIS	GRA&I <input checked="" type="checkbox"/>
DTIC	TAB <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION /	
AVAILABILITY CODES	
DIST	AVAIL AND/OR SPECIAL
A	23 CP

DISTRIBUTION STAMP

**DTIC ELECTED**

S APR 1 1983 D

D

DATE ACCESSIONED



Supersedes AD-A106991

Copy available to DTIC does not permit fully legible reproduction

83 03 30 063

350

DATE RECEIVED IN DTIC

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDA-2

RPT 006-007  
REV 0

**ADA 126283**

MARINE SEISMIC SYSTEM  
AT-SEA-TEST DEPLOYMENT OPERATION

ROBERT L. WALLERSTEDT  
GLOBAL MARINE DEVELOPMENT INC  
2302 Martin Street  
Irvine, California 92715

9 OCT 1981

FINAL REPORT FOR PERIOD MARCH 1981

UNCLASSIFIED/UNLIMITED DISTRIBUTION

SPONSORED BY  
DEFENSE ADVANCED RESEARCH PROJECTS AGENCY (DoD)  
ARPA ORDER NO. 3693

MONITORED BY  
NAVAL OCEAN RESEARCH AND DEVELOPMENT ACTIVITY  
UNDER CONTRACT N00014-80-C-0821

The views and conclusions contained in this document are those of the authors and should not be interpreted as necessarily representing the official policies, either expressed or implied, of the Defense Advanced Research Projects Agency or the U.S. Government.

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY PRACTICABLE. THE COPY FURNISHED TO DTIC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.**


RPT 006-007  
REV 0  
9 OCT 81

FINAL REPORT  
FOR  
MARINE SEISMIC SYSTEM AT-SEA-TEST DEPLOYMENT OPERATION

JULY 1, 1981

PREPARED FOR  
NAVAL OCEAN RESEARCH AND DEVELOPMENT ACTIVITY  
NSTL STATION, MISSISSIPPI 39529

PREPARED BY  
GLOBAL MARINE DEVELOPMENT INC  
2302 MARTIN STREET  
IRVINE, CALIFORNIA 92715



Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER RPT 006-007 - REV 0	2. GOVT ACCESSION NO. ADA126 283	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Marine Seismic System At-Sea-Test Deployment Operation		5. TYPE OF REPORT & PERIOD COVERED Technical - March-April 1981
		6. PERFORMING ORG. REPORT NUMBER RPT 006-007
7. AUTHOR(s) R. Wallerstedt	8. CONTRACT OR GRANT NUMBER(s) N00014-80-C-0821	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Global Marine Development Inc 2302 Martin Street Irvine, CA 92715		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS ARPA Order 3693
11. CONTROLLING OFFICE NAME AND ADDRESS Defense Advanced Research Projects Agency (DOD) ARPA Order 3693		12. REPORT DATE 09 OCT 1981
		13. NUMBER OF PAGES Approx. 200
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Naval Ocean Research and Development Activity NSTL, Bay St. Louis, Mississippi		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) <div style="border: 1px solid black; padding: 5px; text-align: center;"><b>DISTRIBUTION STATEMENT A</b> Approved for public release; Distribution Unlimited</div>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Marine Seismic System Deep Ocean Seismic Instrumentation Deployment Borehole Instrumentation Package		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report summarizes the MSS At-Sea-Test Deployment Operations conducted from the <u>DSDP Glomar Challenger</u> during late March 1981. The BIP seismic package was successfully emplaced into and recovered from a 15,000 foot water depth borehole located in the Mid-Atlantic. Gpod reentry and downhole seismic data was obtained.		

DD FORM 1473  
1 JAN 73

EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

Distribution of Technical Reports

<u>Addressee</u>	<u>DODAAD Code</u>	<u>Number of Copies Unclassified/ Limited and Classified</u>
Director, Advanced Research Project Agency 1400 Wilson Blvd. Arlington, VA 22209 Attn: Program Management	HX1241	3
Scientific Officer (James K. Ballard) Director (Code 500) Ocean Programs Office NORDA NSTL Station Bay St. Louis, MS 39529		6
Director, Naval Research Laboratory, Attn: Code 2627 Washington, DC 20375	N00173	1
Defense Technical Information Ctr. Bldg. 5, Cameron Station Alexandria, VA 22314	S47031	2

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
1.0	SUMMARY	1-1
2.0	INTRODUCTION	2-1
3.0	TEST EVALUATION & RECOMMENDATIONS	3-1
4.0	MSS DOWNHOLE INSTRUMENTATION SYSTEM	4-1
	4.1 SYSTEM DESCRIPTION	4-1
	4.2 FUNCTIONAL DESCRIPTION OF BIP	4-1
	4.3 FUNCTIONAL DESCRIPTION OF STC	4-8
5.0	REENTRY SITE	5-1
6.0	GLOMAR CHALLENGER	6-1
7.0	DEPLOYMENT EQUIPMENT	7-1
	7.1 GENERAL DESCRIPTION	7-1
	7.2 SHIPBOARD EQUIPMENT	7-1
	7.3 SUBSEA EQUIPMENT	7-6
	7.3.1 Reentry Sub Design	7-6
	7.3.2 Reentry Sub Fabrication	7-12
	7.3.3 Inspection and Testing	7-14
8.0	OPERATIONS SUMMARY	8-1
9.0	TEST DATA EVALUATION	9-1
	9.1 IMPACT FORCES	9-1
	9.2 CABLE DYNAMICS	9-10
	9.2.1 Analysis	9-10
	9.2.2. Cable Load Evaluations	9-20

TABLE OF CONTENTS

(Continued)

<u>SECTION</u>	<u>PAGE</u>
10.0 MOBILIZATION/DEMOBILIZATION	10-1

REFERENCES

GLOSSARY

<u>FIGURE NO.</u>	<u>LIST OF FIGURES</u>	<u>PAGE</u>
4-1	BIP ON CASING RACK	4-2
4-2	AT-SEA-TEST BIP FUNCTIONAL BLOCK DIAGRAM	4-3
4-3	AT-SEA-TEST BIP MECHANICAL OUTLINE	4-4
4-4	AT-SEA-TEST BIP PCM DATA FORMAT	4-7
4-5	STC INSTALLATION	4-9
4-6	STC INSTRUMENTATION CONSOLE	4-10
5-1	MSS AT-SEA-TEST DSDP SITE 395A	5-2
5-2	BATHYMETRIC CHART SITE 395	5-3
5-3	SCHEMATIC OF REENTRY CONE & CASING AT MUD-LINE HOLE 395A	5-4
6-1	GLOMAR CHALLENGER	6-2
7-1	EM WINCH/A-FRAME/HEAVE COMPENSATOR INSTALLATION	7-2
7-2	LOADING EM WINCH	7-3
7-3	A-FRAME & SHEAVE BLOCK AS INSTALLED	7-5
7-4	REENTRY SUB SHOWING RELEASE & REENTRY CONFIGURATIONS	7-9
7-5	FIELD TEST OF REENTRY SUB	7-10

TABLE OF CONTENTS

(Continued)

LIST OF FIGURES

<u>FIGURE NO.</u>		<u>PAGE</u>
8-1	SHIPYARD HANDLING OF REENTRY SUB	8-2
8-2	BIP IN DERRICK	8-3
9-1	SHIPBOARD HANDLING	9-4
9-2	REENTRY	9-6
9-3	POST REENTRY	9-7
9-4	STANDBY IN CONE	9-8
9-5	BIP SHEAR RELEASE	9-9
9-6	LOWERING BIP IN BOREHOLE	9-11
9-7	BIP BOTTOM OF BOREHOLE	9-12
9-8	DEFLECTED SHAPE OF THE EM CABLE DUE TO CURRENT FOR 5,000, 10,000, 15,000 AND 20,000 FT OF  WATER DEPTH	9-15
9-9	EM CABLE & DRILL PIPE DEFLECTED SHAPES	9-16
9-10	EM CABLE DYNAMICS FULLY DEPLOYED PIPE STRING (~15,000 FT)	9-24
9-11	CABLE DYNAMICS RECOVERY OF BIP (~16,000 FT)	9-25
9-12	CABLE DYNAMICS REENTRY	9-26
9-13	CABLE DYNAMICS EFFECT OF HC (~14,000 FT)	9-27
9-14	CABLE DYNAMICS RELEASE OF BIP	9-28
9-15	EM CABLE DYNAMICS RECOVERY OF BIP (~8,000 FT)	9-30
10-1	SCHEDULE	10-2

LIST OF TABLES

<u>TABLE NO.</u>		<u>PAGE</u>
9.1	EM CABLE NATURAL PERIOD OF LONGITUDINAL OSCILLATION	9-18
9.2	UPPER LIMIT OF MAXIMUM CABLE DYNAMIC TENSIONS	9-19
9.3	CABLE TENSION EFFECT WITH CURRENT (15,000 FT)	9-21
9.4	LEG 78B, HOLE 395A CABLE TENSIONING CHARACTERISTICS	9-22

TABLE OF CONTENTS

(Continued)

APPENDICE

APPENDIX

TITLE

PAGE

A	MSS SEISMIC SYSTEM PROGRAM AT-SEA-TEST PLAN SYNOPSIS	A-1
B	MSS PROGRAM AT-SEA-TEST BASELINE DEPLOYMENT SYSTEM INTERFACE AND REQUIREMENT SPECIFICATIONS	B-1
C	MSS AT-SEA-TEST OPERATIONAL PROCEDURES	C-1
D	EQUIPMENT LIST	D-1
E	FIELD IMPACT TEST	E-1
F	REENTRY SUB INSPECTION AND TEST	F-1
G	WEATHER SUMMARY	G-1
H	AT-SEA-TEST CHRONOLOGY	H-1
I	TYPICAL CHALLENGER SHIP MOTIONS	I-1
J	AT-SEA-TEST DRAWINGS	J-1

## SECTION 1.0 - SUMMARY

In March of 1981, GMDI successfully deployed a large Borehole Instrumentation Package (BIP). This was accomplished under ONR Contract N00014-80-C-0821, issued as part of the Defense Advanced Research Projects Agency (DARPA) sponsored Marine Seismic System (MSS) Program. The Naval Ocean Research and Development Activity (NORDA) directed the program. Testing was conducted in cooperation with the National Science Foundation (NSF) Deep Sea Drilling Project (DSDP) who provided the drillship Glomar Challenger and her crew. The BIP was, in fact, lowered into an existing borehole (DSDP Site No. 395A) previously drilled by the Glomar Challenger.

This report summarizes the part of the overall MSS Program associated with the design, fabrication, mobilization, logistic support, modification, planning of the deployment hardware and the actual conduct of the BIP operational deployment At-Sea. After only 9 months of effort commencing in June of 1980, the actual 14,712 foot (4,484 meters) sea depth deployment and recovery operations from the 1,667 foot (508 meters) borehole took less than 4 days to complete. The deployment went very smoothly with no serious problems encountered.

The following list depicts some of the major accomplishments and highlights of the deployment operation. Each item is discussed in further detail throughout the body of the report.

- o Operations successfully demonstrated the feasibility of emplacing large instrumentation packages into holes pre-drilled in the ocean floor.
- o Handling, deployment, release and retrieval of the BIP, EM Cable and drill string were successful.
- o Deployment equipment designs were proven.
- o Deployment procedures were verified.
- o High quality seismic data was obtained.
- o Impact forces were within design criteria.
- o Cable entanglement was apparently not a problem.

The MSS equipment was mobilized in San Juan, Puerto Rico and was installed on the Glomar Challenger. It departed for the test site on March 27, 1981. Once onsite and with the ship dynamically holding position, the BIP, suspended from the drill string, was lowered to the ocean floor. An existing acoustic reentry cone placed over the borehole was used to guide the BIP into the hole where it was lowered an additional 1,998 feet (609 meters) into the basalt layer. Over the next two days a series of tests were performed using explosive charges dropped from the USNS Lynch. The BIP was subsequently retrieved from the borehole. There was only minimal damage to the BIP, EM Cable or deployment hardware. The entire onsite operation was completed in 73 hours.

The successful test demonstrations testified to the cooperative planning efforts of NORDA, Geotech, DSDP and GMDI personnel. The experience of the Glomar Challenger marine and drilling crews was invaluable. The overall operation went very smoothly considering the number of new equipment items required, their complexity and the untried procedures involved. Deployment, reentry and recovery of the BIP were all achieved without any significant difficulties. Based upon this actual experience, with only minor modifications, the existing procedures can be used with confidence for future deployments.

High quality seismic data was recorded by both the BIP and Ocean Bottom Seismographs (OBS) (2). The propagation source was an explosive device dropped from the support vessel USNS Lynch at various distances from the Glomar Challenger. A total of 113 explosive charges, ranging in size from 0.5 to 120 kg, were dropped by the USNS Lynch. The distance from the BIP installation site was approximately 10 to 65 km. The seismic refraction records obtained from the downhole BIP exhibited good first and secondary arrival. There was little of the complexity and long reverberation due to converted phases, surface waves and/or channeled waves that normally contaminate OBS explosion records. The data quality was excellent and should

---

(2) The data measurement aspect of the program are the subject of a separate report (TR 81-6) by Teledyne-Geotech.

provide some new and very detailed information on velocity structure of the oceanic crust. The background noise level recorded by the downhole seismometer appeared to be very low.

This report covers the design of the deployment equipment, the At-Sea operational procedures utilized, deployment test data and evaluation, mobilization/demobilization considerations, plus the At-Sea-Test Plan, Interface Specification, and drawings of deployment equipment.

## SECTION 2.0 - INTRODUCTION AND BACKGROUND

The Marine Seismic System (MSS) Program is sponsored by the Defense Advanced Research Projects Agency (DARPA). The program is for development, installation, and operation of a broadband, triaxial, ocean bottom borehole seismometer station similar in capabilities to landbased Seismic Research Observatories (SRO). The Naval Ocean Research and Development Activity (NORDA), a field activity of the Chief of Naval Research, is directing the task under Contract N000104-80-C-0821. Global Marine Development Inc (GMDI) is the integration and deployment engineering contractor. Deployment was carried out in conjunction with the NSF Deep Sea Drilling Project using the D/V Glomar Challenger. The downhole BIP instruments are designed and built by Teledyne-Geotech, Inc.

Present schedules provide for the installation of a prototype operational station in the North Pacific during the Summer of 1982. This MSS installation will permit the seismic observatory to be established within regional distances of the Northwest Pacific subduction zone (Japan-Kuril-Kamchatka Trench).

A semi-permanent observatory on the leading edge of a convergent margin will provide seismologically unique data. A wideband, wide dynamic range SRO in a low ambient noise marine environment will provide information capable of contributing to the following scientific objectives:

- o Obtain data from a wide range of earthquake magnitudes, first motions and focal depths. This will help to clarify processes associated with subduction such as defining possible areas of tensional, compressional and strike-slip faulting.
- o Determine the magnitude of changes of seismic properties of the ocean crust with increasing age by establishing more precise epicentral locations and by recording signals from events whose propagation paths are undistorted by seamount chains or island roots.

- o Measure signal absorption and propagation characteristics of both long-period and short-period body and surface waves. This data would determine plate structure and evaluate source mechanisms within regional distances of an actively subducting plate boundary.
- o Measure anisotropy of the crust and upper mantle and anisotropic variations within crustal layers.
- o Determine the relationship of seismic background noise beneath the seafloor as a function of such environmental parameters as bottom currents, tidal cycles, convective heat flow and sediment thickness and lithification.
- o Measure elastic and rheological properties of converging plates.
- o Obtain long-term borehole temperature measurements which will permit determination of steady state heat flow rates.

Uncertainties associated with deep ocean reentry impact, controlled lowering of BIP within a borehole, and the potential for cable entanglement made it desirable to perform an early deep water At-Sea demonstration. Accordingly, DARPA requested NSF to provide 10 days for special mobilization plus test time of the Glomar Challenger during the Spring period of 1981. Specific objectives of this At-Sea-Test were:

- o Demonstrate capability of deep ocean large package emplacement using drill string technique.
- o Define reentry and handling shock levels imposed on BIP.
- o Determine the effects of surface and bottom currents on cable/drill pipe entanglement.
- o Establish whether the sensor state-of-health monitoring function can perform within design limits in a borehole environment.

- o Compare borehole seismometer signal and noise levels with similar signals recorded on conventional OBS records.

DSDP reentry site 395A, a borehole originally drilled over 5 years ago, was utilized for the At-Sea-Test demonstration. The site had previously been selected for special scientific downhole instrumentation investigations. The At-Sea-Test Plan plus the Associated Interface and Requirements Specification are included as Appendix A and B respectively.

### SECTION 3.0 - TEST EVALUATION AND RECOMMENDATIONS

The overall BIP deployment and recovery operations went very smoothly, with no major problems encountered. No cable entanglement difficulties requiring the use of the emergency backup equipment occurred. A potential problem encountered was the partial closing of reentry stinger cable release slot due to bending of the stinger. The slotted reentry stinger is required for deployment when using existing DSDP reentry cones. Recovery of the reentry sonar tool and emplacement of the Otis/Baker tool, between reentry and release of the BIP, requires approximately 5 hours. The long time period makes this system marginal for rough weather reentries. In this installation, the stinger tube bent approximately 5 degrees and the slot permanently closed down 0.375 inches at the stinger flange. Fortunately, there was adequate clearance remaining for cable exit. For future operations, the reentry sub should be seated more firmly into the cone, have continuous support around the periphery, and if possible provide for reduced time in the cone. The stinger slot should be deleted, if possible.

With the present load cell instrumentation, determination of accurate static and dynamic loading was difficult since the cable tension was not directly monitored. The load cell records sheave loading which is affected by both heave compensator position and sheave cable angles. A direct readout of cable tension which defines an accurate measure of static loading plus dynamic oscillatory loads is desirable.

The present communications system was very noisy due primarily to the unmuffled winch diesel engine. For extended periods of operation, and in the event of an emergency, an improved system is necessary and reduced engine noise is desirable. In all other areas, the winch operated satisfactorily.

The Otis/Baker "fishing" tool did not operate correctly. The Baker plug stuck in the control carriage sub causing the Otis release pin to inadvertently shear. Neither could be retrieved. This resulted in time lost in an unsuccessful fishing operation and a bothersome and slow "wet" drill string recovery.

Relatively high shock loads (but below criteria) were experienced during shipboard handling and release of the carriage. In particular, the shipboard handling environment will be considerably more severe in the North Pacific. The BIP should be handled always within a shock mounted cannister.

In order to reduce future operational time, limit handling shocks, and improve overall deployment reliability the following recommendations should be considered:

- o Incorporate a design which leaves stinger in the borehole and does not require a cable release slot. This will decrease deployment time, and strengthen the stinger assembly.
- o Provide full peripheral seating of reentry sub into reentry cone.
- o Adapt dynaline type in-line cable tension/cable counter equipment instead of present load cell. Provide damped gauge readout plus a two track analog recorder for cable tension.
- o Design a new BIP carriage with built-in shock isolation unit that can be used as a BIP shipping container and then later fitted into the reentry carriage on the rig floor.
- o Reduce lateral shock to BIP caused by modifying offset shear pin release technique.
- o Reduce operational time by adding an azimuth capability to the sonar reentry tool.

## SECTION 4.0 - BOREHOLE INSTRUMENT SYSTEM

### 4.1 SYSTEM DESCRIPTION\*

The MSS instrumentation consisted of two functional subsystems. These were the Borehole Instrumentation Package (BIP) and the Shipboard Test Console (STC). The STC system supplied power to the BIP, performed data recording and monitoring, and displayed selected data plus state of health information in real time. The BIP and STC were connected by an electro-mechanical (EM) cable and slip rig assembly on an EM Cable winch. DC power is applied to the BIP and digital data is transmitted to the STC via this cable. The EM Cable armor provides the necessary mechanical strength to assist in the borehole installation and retrieval of the BIP.

### 4.2 FUNCTIONAL DESCRIPTION OF BIP

The BIP, Teledyne Geotech Model 53100, is an assemblage of acceleration, seismic, temperature, pressure and state of health sensor along with associated signal conditioning and control electronics.

The BIP was 28 feet 6 inches in total length with an OD of 8 inches. It basically consisted of a pressure vessel enclosed instrumentation section plus a ballast weight section. Total weight was approximately 3,500 pounds (2,700 pounds wet). Figure 4-1 shows the BIP during installation. Figure 4-2 is a functional block diagram of the BIP. The mechanical configuration outline is shown in Figure 4-3.

The acceleration sensors consist of two sets of three component orthogonal sensors, each component output being preconditioned by a charge amplifier and an antibiasing filter. The acceleration ranges are 50 g peak for all channels except for the 2-3 axis channel which has a range of 100 g peak. The seismic sensor system consists of two Teledyne Geotech S-700 short period piezoelectric type seismometers, and associated frequency filters which provide the desired response

\*More details can be found in Teledyne-Geotech Report 81-6.





FIGURE 4-1 BIP ON CASING RACK



0006-042

FIGURE 4-2 AT-SEA-TEST BIP FUNCTIONAL BLOCK DIAGRAM




FIGURE 4-3 AT-SEA-TEST BIP MECHANICAL OUTLINE

0006-040

shaping as well as antibiasing. Each seismometer drives three frequency filters. The voltage gains are staggered such that a total dynamic range of approximately 144 db is achieved, with an overlap of approximately 12 db between adjacent channels. On Leg 78B only vertical axis seismic data was provided.

Four temperature sensors are provided, each having a range of 0 to 100°C. The sensors are as follows:

- CVTEMP Attached to the BIP DC to DC converter;
- PTEMP BIP internal ambient temperature monitor located near the mid-portion of the electronics stack;
- ATEMP BIP internal ambient temperature monitor located near the bottom of the electronics stack;
- SEISTEMP BIP pressure vessel temperature monitor located near the bottom of the seismometer package.

A pressure sensor is located in the electronics stack to provide internal pressure of BIP, and provides an output range of 9 to 40 PSIA. The BIP is evacuated and backfilled with helium to a nominal 16 PSIA during final assembly.

BIP State of Health (SOH) monitors are provided to monitor its condition, and to assist in any system fault analysis.

The State of Health monitors include:

- V1 Voltage monitor for the bipolar (+ 12V) supply for the 1X, 1Z and 2Z accelerometer filters;
- V2 Voltage monitor for the bipolar (+ 12V) supply for the 1Y, 2Y and 2X accelerometer filters;
- V3 Voltage monitor for the bipolar (+ 12V) supply for the U1, U2 and U3 seismometer filters;

- V4 Voltage monitor for the bipolar ( $\pm$  12V) supplies for the L1, L2 and L3 seismometer filters;
- V5 Voltage monitor for two bipolar ( $\pm$  12V) supplies for the accelerometer charge amplifiers;
- V6 Voltage monitor for two bipolar ( $\pm$  12V) supplies for the two S-700 seismometers;
- VREF Voltage monitor for the BIP temperature sensor bridge reference voltage;
- DCIN Voltage monitor for the BIP 150 Vdc input voltage level;
- CAL A negative (when active) monitor of the seismic channel calibration circuit output.

The data output from all sensor and state of health channels are input as analog signals to a pulse code modulated (PCM) encoder which time division multiplexes and digitizes the data, then formats and outputs the data as a 54 KHz PCM digital data stream, with appended synchronization data. Three levels of subcommutation are used to permit the desired sampling rates for the various data types. Figure 4-4 illustrates the PCM data format.

The output of the PCM encoder is preconditioned by a PCM amplifier for transmission via the EM Cable. This circuit also separates the high voltage DC component on the cable providing BIP power (150 Vdc). This input DC is converted to the various voltages required by the subassemblies by a DC to DC converter module. The outputs of this device are further conditioned via outboard current limited series regulators, which isolate the converter from external subassembly failures, thereby minimizing the risk of catastrophic system failures caused by minor module failures.

WORD																	
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
FRAME SYNC	FRAME SYNC	SUB-FRAME I.D.	ACCEL. #12 ± 50g	ACCEL. #11 ± 50g	ACCEL. #22 ± 100g	ACCEL. #21 ± 50g	ACCEL. #2Y ± 50g	ACCEL. #2X ± 50g	S.O.H.	UPPER SETS.	LOWER SETS.	ACCEL. #12	ACCEL. #11	ACCEL. #1X	ACCEL. #22	ACCEL. #1Y	ACCEL. #1X

\*SUB-FRAME WORD

FRAME	
0	CV TEMP 0-100°C L1
1	P TEMP 0-100°C μ1 L2
2	A TEMP 0-100°C μ2 L3
3	SETS TEMP 0-100°C SPARE
4	PRESS 0-40 PSI μ1 L1
5	CAL. μ2 L2
6	VREF ±2Vdc μ3 L3
7	DC IN ±150 Vdc SPARE
8	V1 μ1 L1
9	V2 μ2 L2
10	V3 μ3 L3
11	V4 SPARE
12	V5 μ1 L1
13	V6 μ2 L2
14	SPARE μ3 L3
15	SPARE SPARE

DATA RATES:

- 18 WORDS/FRAME
- 10 BITS/WORD
- 300 FRAMES/SECOND
- 5,400 BITS/SECOND

SAMPLE RATES:

- ACCELERATION = 600 SAMPLES/SEC.
- SEISMIC = 75 SAMPLES/SEC.
- S.O.H. = 18.75 SAMPLES/SEC.

SENSITIVITIES:

- TEMP = 0.10 C/BH
- PRESS. = 0.08 PSI/BH
- VREF & VI-VC = 0.01 V/BH
- DC IN = 1.0 V/BH
- μ1 = 0.11 mV/BH
- μ2 = 1.63 mV/BH
- μ3 = 3.48 mV/BH
- L1 = 51.5 mV/BH
- L2 = 110.1 mV/BH
- L3 = 1629 mV/BH
- 1Y, 1X, 2Y & 2X = 0.19/mV
- 2Z = 0.2g/BH

FIGURE 4-4 AT-SEA-TEST BIP PCM DATA FORMAT

#### 4.3 FUNCTIONAL DESCRIPTION OF STC

The STC is an assemblage of primarily off-the-shelf commercial data decoders, timers and recorders mounted in standard relay racks in an approximate 8 feet x 12 feet (2.5 meters x 3.5 meters) environmentally controlled equipment van. Figure 4-5 shows the STC as installed on the CHALLENGER. Major functional items of the STC are:

- o Line receiver (special)
- o Tape recorders (2 each), Ampex, Model PR-2230
- o Decommulator, Aydin Vector, Model PLD-400
- o Time Code Generator/Translator, Datum, Model 9300-100
- o Strip Chart Recorder (3 each), Hewlett Packard, Model 7404, 4 channel
- o Teletypewriter, Texas Instruments, Model KSR 743
- o Patch Panel (Special)
- o Power Supply, (4 each), Kepco, Model OPS 100-1m
- o Uninterruptable Power System (UpS), (2 each), Topaz, Model 82102-12 with battery modules, Model 2566-2

PCM data is received from the BIP via the receiver, preconditioned, then applied in parallel to each of the two magnetic tape machines (analog 14 track) and to each of the two data decommutators. The raw PCM data and an IRIG B time signal generated by the time code generator/translator are recorded on the selected magnetic tape (or both) on the even and odd channels respectively. Figure 4-6 shows partially the instrumentation recorders.

Through the use of a "stitch back" mode and a modification allowing the activation or deactivation of selected record heads (tracks), data is recorded in 7 passes as follows:

PASS 1	TRACKS 1 & 2
PASS 2	TRACKS 3 & 4




FIGURE 4-5 STC INSTALLATION




FIGURE 4-6 STC INSTRUMENTATION CONSOLE

PASS 3	TRACKS 5 & 6
PASS 4	TRACKS 7 & 8
PASS 5	TRACKS 9 & 10
PASS 6	TRACKS 11 & 12
PASS 7	TRACKS 13 & 14

Each pass, at 3-3/4 IPS, will accommodate approximately 3-1/2 hours of 50 KHz digital data.

The two PCM data decommutators allow real time monitoring of data and the state of health of the BIP. The Conic D-Pad III uses a CRT display and 12 user, programmable digital to analog output ports to display and make available to external recorders this data and SOH information. Hard copy outputs of any CRT display are available upon operator request via the teleprinter. All D/A output ports are hardwired to the patch panel where they can be patched to any of 12 strip chart channels. The Aydin Vector PLD-400 device is limited to 12 firmware programmed D/A ports and one front panel D/A port whose input is operator selectable via front panel switches.

Three analog strip charge recorders, Hewlett Packard Model 7404, are provided for recording up to a total of 12 channels of real time or playback analog data. Each recorder has an additional edge marker pen for use as a time or event marker. A time code will normally be applied to the input of this channel.

The time code generator/translator, Datum Model 9300-100 outputs an IRIG B time code (Julian day of year, hours, minutes and seconds) in the generator mode for recording on magnetic tape. Additionally, a SLO CODE output is available for inputting to the marker pens of the strip chart recorders. In the translate mode, the timer serves as a time code reader for off-line tape playback. The time code generator will be synchronized to WMV for accurate time measurements.

The BIP power supply system consists of redundant sets of series-connected DC power supplies providing 150 vdc @ 300 mA

maximum. A front panel switch is provided to select the back-up power supply set in the event of a failure.

The STC technical system power is supplied by two Topaz uninterruptable power systems to isolate the technical load from ship's power surges and provides up to 19 minutes of technical power in the event of a total loss of ship's AC power.

## SECTION 5.0 - REENTRY SITE

DSDP site 395A is located at about 81 nautical miles (150 km) west of the mid-Atlantic Ridge at latitude 22° 45.34' N, longitude 46° 04.90' W as shown by Figure 5-1. This borehole was drilled in December of 1975 by the D/V Glomar Challenger. The water depth is 14,712 feet (4,489 meters). Figure 5-2 depicts the general bathymetry of the site.

A hole was cored and cased through the sediment and drilled out through the basalt to a depth of 2,178 feet (664 meters). The sediment was of calcareous brown clay nature. The basement was predominately asphyric and basalt units. The hole was encased with 16 inch and 11-3/4 inch casing as shown by Figure 5-3. Also shown is the basic geometry of the reentry cone. The cone was fitted with three steel passive reflectors. In addition, between the steel reflectors, spherical, hollow glass balls were fitted on 15 foot tethers in case the cone should settle.

Five joints of 16 inch casing were run and hung off in or on reentry cone below the moonpool and then lowered to the bottom. The casing was then jettied into the sediment and the 14-7/8 inch hole was washed down to accommodate the casing. Three hundred thirty two feet of 11-3/4 inch casing was then made up, reentered into the site and attached by hangers. Successive reruns (six) were then made to drill the basalt down to approximately a total depth of 16,890 feet (5,148 meters). The bottom portion of the borehole was unstable in places. The bottom of the hole was partially cemented. During these activities, a hydrophone was inadvertently dropped in the hole.




FIGURE 5-1 MSS AT-SEA-TEST DSDP SITE 395A




FIGURE 5-2 BATHYMETRIC CHART SITE 395




FIGURE 5-3 SCHEMATIC OF RE-ENTRY CONE & CASING AT MUD-LINE HOLE 395A

## SECTION 6.0 - GLOMAR CHALLENGER


The D/V Glomar Challenger, utilized for the MSS At-Sea-Test, is a specially constructed, dynamically-positioned drillship operated by Global Marine Drilling Co. under direction of Scripps Institution of Oceanography, University of California, San Diego. Scripps operates the Deep Sea Drilling Project (DSDP) on behalf of the Joint Oceanographic Institution for Earth Sampling (JOIDES).

The Glomar Challenger, Figure 6-1, was placed in service in 1967. It has a length of 400 feet, beam of 65 feet, draft of 20 feet and displaces 10,500 long tons. It is powered by twin screws, each driven by 3 - 750 hp electric motors. Maximum speed is 12.5 knots. Four tunnel thrusters are provided for lateral positioning. A total of 13 AC and DC diesel generators provide basic power.

The drilling equipment is characterized by the 142 foot, 1 million pound derrick. Approximately 38,000 feet of special S-135, 5 inch drill pipe is carried plus associated drill collars, bumper subs, swivels, etc. A passive action heave compensator can be utilized in the drill string with some difficulty. Two large 5,000 psi mud pumps are available. A 50 ton plus a 15 ton crane can handle deck loads.

An early version Delco type ASK (Automatic Stationkeeping) system is used to maintain position over a deployed short baseline beacon. Automatically, the ship's propulsion screws and/or thrusters are directed to maintain desired position. For deep water depths, stationkeeping positions of  $\pm 10$  feet can be normally achieved within an offset distance of approximately 3,000 feet of the beacon.

A total crew of 74 marine, drilling and scientific personnel can be accommodated. Typical legs last about 2 months at which time a complete crew changeover is accomplished.



P-044

FIGURE 6-1 GLOMAR CHALLENGER

## SECTION 7.0 DEPLOYMENT EQUIPMENT

### 7.1 GENERAL DESCRIPTION

The MSS At-Sea-Test deployment equipment can be broken down into two basic categories, shipboard and subsea. The shipboard equipment consisted of a dual "bull" drum EM Cable winch supplied by the U.S. Navy, a specially constructed overside A-Frame, a single cylinder heave compensator adapted from a guideline tensioner, and a large swiveled sheave block. This equipment was mounted on the portside main deck area located between the derrick subbase and the casing support rack structure.

Figure 7-1 is a perspective layout of the shipboard installation. The subsea equipment basically consisted of a reentry sub which was attached to the lower end of the drill string and a specially designed coaxial EM Cable provided by the U.S. Navy. The reentry subassembly was made up of a carriage, carriage housing, stinger and control sub. The reentry subassembly accommodated a shock mounting for the BIP for impact reentry into the borehole. Refer to Appendix J for drawings of the At-Sea-Test deployment equipment.

### 7.2 SHIPBOARD EQUIPMENT

The EM Winch was originally to be a new single "bull" wheel manufactured by the Pengo Co. of Ft. Worth, Texas. Unfortunately, this specific winch could not provide the required traction on the EM Cable, a problem later attributed to the EM Cable coating "slipperiness". Fortunately, an existing Pengo dual "bull" wheel winch of the same general size and capability was available at the Roosevelt Roads, U.S. Navy Base, in Puerto Rico. Both winches were tested against each other in the San Juan shipyard with the dual "bull" wheel winch proving superior. Accordingly, this latter winch was refurbished and installed as shown by Figure 7-2. The winch is mounted to a specially welded deck foundation.

A-FRAME/HEAVE COMPENSATOR




FIGURE 7-1 EM WINCH/A-FRAME/HEAVE COMPENSATOR INSTALLATION

0006-039




FIGURE 7-2 LOADING EM WINCH

The A-Frame structure was of simple design, mounted on two pinned inboard pedestals and attached to a central heave compensator cylinder. The A-Frame projected out above the deck about 8 feet high and overhung the side approximately 15 feet. The A-Frame was rated at and tested to 28,000 pounds. The A-Frame and support structure was fabricated at Puerto Rico Drydock and Marine Terminals shipyard. The heave compensator was operated off a single accumulator bottle interconnected to 4 standard pressurized nitrogen bottles. The stroke of the heave compensator was approximately 7.5 feet. The system was rated at 2,500 psi. The effective load area was approximately 2<sup>9</sup> square inches. The system was controlled manually at the manifold console.

The 48 inch sheave block was adapted from an existing NCEL block by regrooving. The snatch block was supported at the outboard end of the A-Frame by a tension type Martin Decker load cell transducer. Figure 7-3 shows the A-Frame, HC cylinder and sheave block installed for the At-Sea-Test.

The load cell could be read out at either a large gage dial or a digital recorder both mounted at the heave compensator console. In addition, an analog chart recorder was provided in the STC that operated for a portion of the test. The load cell indicated an effective loading of approximately 1.7 times the actual cable tension.

Other MSS deployment equipment onboard but not utilized consisted of:

- o A subsea TV camera designed for mounting through the moonpool to view the upper drill string area in the advent of cable entanglement.
- o A Helle acoustic release system, plus a special sheave were onboard to provide a "dual" ship capability also in the advent of cable entanglement.
- o Eastman stoking tools for alignment of the individual drill string sections during deployment.




FIGURE 7-3 A-FRAME & SHEAVE BLOCK AS INSTALLED

### 7.3 SUBSEA EQUIPMENT

#### 7.3.1 Reentry Sub Design

The primary function of the reentry sub was to deliver a working BIP into the top of a borehole. This function can be broken down as follows:

- o Carry the BIP during drill string deployment in a protective enclosure.
- o Support and position the sonar reentry tool to locate the reentry cone, in the same manner as during normal drilling operations.
- o Stab into the reentry cone while preventing BIP accelerations in excess of 10 Gs.
- o Release the BIP, allowing it to be lowered into the borehole.
- o Allow the EM Cable to run freely into the borehole.
- o Release the EM Cable after the reentry sub is pulled out of the cone.

In order to use existing shipboard equipment and methods, there were certain dimensional limitations on the design of the reentry sub as follows:

- o The reentry sub weight must be similar to the normal downhole assembly weights.
- o The reentry sub must be able to pass through the rotary table and the moonpool guide horn structure on the Glomar Challenger. This limits the OD to 31 inches maximum.
- o The reentry sub must stab into an existing reentry cone and casing. The cone base has an ID of 24 inches down to a depth of 57 inches, where the casing hanger begins. The casing has an ID of 11 inches.
- o The reentry sub stinger must be able to support the sonar reentry tool which has an OD of 3.75 inches. This conflicts with the BIP diameter, so a removable support is needed.

In addition, there was the uncertainty associated with the exact configuration of the reentry cone emplaced 5 years ago.

The materials used in the reentry sub needed to be readily available so as to not delay fabrication in an already tight schedule. The steels were of varying strength levels in order to accomplish the specific purposes of each component of the reentry sub. In addition, the steels could not be of a type which would become brittle at the seafloor temperature. The other materials used (rubber) should not exhibit markedly altered characteristics, due to temperature or pressure.

The design concept used met the requirements under the sea conditions encountered. To understand the functional methods and sequence of the concept, the reader is referred to the MSS OPERATIONAL PROCEDURES (Appendix C). The requirements of Section 7.3.1 above, were met as follows:

- o The BIP was deployed inside a carriage, with rubber shock rings, for protective enclosure.
- o The Hydraulic Plug/Sonar Adaptor (HP/SA) was positioned initially in the tip of the stinger to locate and support the sonar reentry tool, subsequently it was raised to the control sub, where it acted as a hydraulic packer.
- o The stinger, with HP/SA inside its tip, stabbed into the cone. Under the conditions encountered, the stinger attenuated part of the shock, and the rubber isolation rings attenuated part of the shock. The peak accelerations seen were 4 to 5 Gs. It would appear that more isolation capacity will be needed for rougher sea conditions.
- o The BIP was released by shifting the carriage to center over the stinger and borehole, after the HP/SA had been raised clear and locked into the control sub for hydraulic pressurization. The BIP was then lowered on the EM Cable.
- o The carriage, carriage housing and stinger were slotted (1/4 inch) to allow the EM Cable to run freely downhole even when the reentry sub was being raised.

- o The EM Cable release cylinder, at the lower end of the carriage, retained the cable inside the stinger until the stinger was well clear of the cone, to prevent possible crushing of the cable within the borehole between the outside of the stinger and the casing. During drill string recovery, when the stinger was sufficiently clear of the cone, the hydraulic pressure in the system was increased to release the cable.

Figure 7-4 shows a sketch of the reentry sub before and after release. A photo of the complete reentry sub is shown in Figure 7-5 during field test.

The reentry sub weight was about 16,600 pounds, the BIP weighed 3,300 pounds and there were four bumper subs with a small drill collar on top. This gave a reentry assembly weight similar to the weight of the downhole assembly normally used.

The maximum OD of the reentry sub was 30½ inches in areas of the carriage housing. However, these areas were not faired in, and there were several points which could (and did) hang up on the lip of the moonpool guide horn. This can be alleviated in the future by providing a long lead-in ramp to any projections.

The stinger OD was 10.5 inches at the tip for about 4 feet, and 10 inches for the remaining 20 feet. The 16 inch diameter flanges joined the section of the existing site 395A cone base. To meet the last two dimensional constraints, the stinger ID was 9 inches for the top 22 feet, with an ID of 8.5 inches in the bottom 2 feet of the tip. This provided a support ledge for the HP/SA. The inside profile of the HP/SA was the support for the sonar reentry tool. When the cone has been reentered and the sonar tool has been retrieved, the HP/SA was shifted upward to the control sub leaving the stinger bore clear for the BIP.

MARINE SEISMIC SYSTEM  
BIP AND REENTRY SUB




FIGURE 7-4 REENTRY SUB SHOWING RELEASE & REENTRY CONFIGURATIONS

0006-005



FIGURE 7-5 FIELD TEST OF REENTRY SUB  
7-10

In order to satisfy the material requirements and to provide the various strength levels needed, several different alloys were used:

- o The stinger tip required 80,000 psi yield strength at the point of impact. ASTM A-543 CL1 (HY85) forging steel was used, with an 85,000 psi yield strength. This provided the necessary resistance to impact crushing.
- o The stinger tube was made from AISI 1020 WDOM tubing with a 60,000 psi yield. This strength level was required to survive the bending moment induced by impact. However, it is apparent from the At-Sea-Test that more strength is needed just below the flange, since there was a permanent bend in this area after retrieval. The cause of this bend is thought to be ship-offset induced moments. More stiffness will be needed in this area.
- o The carriage tube was 14 inch Sch 40 pipe of ASTM A-53, Grade B. This material was chosen primarily for availability and cost. Bulk and stiffness were more important than yield strength for this piece.
- o The carriage housing was 16 inch sch 40 pipe of API-5LX, Grade X-52, split lengthwise, with  $\frac{1}{2}$  inch x  $11\frac{1}{2}$  inch plate inserted, made of ASTM A-131, (ABS AH-36) with a yield strength of 51,000 psi. The section and steel were for stiffness and strength to resist bending moments.
- o The control sub was made of AISI 4140 with a yield strength of 100,000 psi. The section and strength of this component were needed for high dimensional stability to provide a positive seal for the hydraulic system, and to provide sufficient strength for the lock ring groove shoulder. Also, this material was selected for compatibility with the drill pipe material for corrosion and gall resistance at the threaded joint.
- o The Hydraulic Plug/Sonar Adaptor was made of AISI 4140 with a yield strength of 100,000 psi for the same reasons as the control sub. The lock ring was also AISI 4140, but was heat treated to a BHN 235 for high shear strength.

- o Buna-N and natural rubber were the preferred shock ring elastomers because they were relatively stable down to the seafloor temperatures, and would not compress to any appreciable degree under the deep ocean ambient pressures encountered.

### 7.3.2 Reentry Sub Fabrication

The reentry sub consisted mainly of weldments, made up from steel plate, pipe and shapes. For specific steels used, and the weld procedure and heat treatment, please refer to the drawings of the various components. Some of the problems involved in the fabrication were as follows:

- o Stinger tube, carriage tube and carriage housing were made from pipe or tubing, and each had a slot (1½ inch wide) longitudinally. When the cuts were made for these slots, each piece tended to warp or twist, relieving residual stresses of manufacture. Fortunately, in no case was this warping beyond repair. Each piece was pressed into the proper straightness and concentricity.
- o The carriage housing, in addition to the slot, had to be cut in half and have 1½ inch wide plates inserted to produce the desired oval shape. The welds required were very long, (32 feet - 9 inches) continuous pass welds, which could 'draw' the assembly out of the desired shape. With great care and luck, this problem was kept to a minimum, and the carriage housings were acceptably straight.
- o Maintaining concentricity of welded sections relative to each other was a problem, particularly between the stinger tube and the stinger tip piece. It was found that some grinding was required at this point, when the hydraulic plug/sonar adaptor failed to traverse this area at first. The problem was overcome fairly easily, but could have been major due to the tight tolerances of the adaptor and stinger tip.
- o The shear pin installation was changed during fabrication due to a material problem. The steel pins originally designated failed to shear at the required point and did not exhibit any

consistency of shear point. It was decided to go to 6061 T-6 aluminum due to the more predictable properties. This required some changes in the mount design for the pins as well, but the change was successfully accomplished.

There were three components which required machining to achieve the desired tolerances: the control sub, the hydraulic plug/sonar adaptor and the stinger tip. The HP/SAs and the stinger tips did not present any major problems, but the control subs delayed completion somewhat. The problem areas were as follows:

- o The size of the piece presented a problem in finding a machine shop with the ability to handle it, and the open time on the machine to do the job in time. When a shop was found, and the control subs were machined, severe quality control problems developed, and completion was delayed.
- o The large bore (the lower end) of the control sub was trepanned to 8 inches ID, then a boring bar was used to turn the diameter out to 8.6 inches. The final step was to hone the bore to finished size. The honing was done at a different shop, so when the quality problem with the boring was discovered, the piece had to be transported again. The problem was due to the long reach into the bore (3 feet - 11 inches) allowing the boring bar to deflect from the desired position. This long reach also presented a problem in measurement, but a special tool was located and utilized.
- o The lock ring groove also presented a problem in the machine work. The location made it difficult to cut the proper contour with the boring bar, but it was finally accomplished. Because of its location so deep in the bore, and the narrowness of the groove, it was also difficult to measure directly. A clay impression had to be made, and then the clay was measured.

### 7.3.3 Inspection and Testing

Dimensional inspection and testing for function was done in accordance with Appendix F. Items 3, 5 and 8 have a dimension in parentheses. These indicate dimensions used in place of those originally called for, reflecting changes made late in the fabrication.

When a problem developed with the original shear pin installation, several samples were sent out to a testing lab. The shear pin configuration had to be redesigned to aluminum.

The reentry sub was instrumented and impact tested per the attached report in Appendix E from Datacraft, Inc.

To satisfy the operating personnel, and give them a practice run opportunity, the reentry sub was assembled and functionally tested while in transit to the site. The tests consisted of the fit, running and function tests indicated in the tables above, and were successful. The practice was very valuable to the operating personnel, and resulted in some minor changes in procedure for easier, faster operation.

Basically, the testing confirmed the design and its associated analysis. Slow motion video tapes are available to provide a detailed analysis of the impact motions if so desired. In addition, accelerometer traces are available to provide corresponding transient force characteristics.

## SECTION 8.0 - OPERATIONS SUMMARY

At 0200, Friday, March 27, 1981, the initial deep ocean seafloor deployment test of the MSS began. The sea state and vessel movement (refer to weather summary in Appendix G) were favorable for passing the equipment through the rotary table and moonpool structures. The original sequence of procedures (refer to Appendix C) used to assemble the carriage and to insert the BIP were partially modified to permit better control of the instrument impacts during the insertion into the carriage. The modified operational sequences were performed as follows:

The EM Cable was initially keelhailed and tied off at the moonpool work platform. The carriage control sub was first made up to the reentry housing carriage and the attachment nuts welded while on the casing rack. The reentry assembly was picked up on the traveling blocks, lowered and aligned to the stinger flange, bolted and all of the nuts welded. The total assembly was then deployed to the rotary table and hung off on drill collar slips and safety clamp. Four 8½ inch OD Baash Ross Bumper Subs, weight of 1,800 pounds each with 5 feet of stroke, were made up to the carriage control sub tool joint and torqued to API specs. Next, the total reentry assembly was suspended on traveling blocks and the drill collar slips removed (tugger and cat lines were used to snub assembly to forward side of rotary table), while the EM Cable was passed through and rigged into a sheave hanging from the derrick on a tugger line. The carriage assembly was lifted until the top of the carriage was approximately 3 feet above the rotary table. Figure 8-1 shows the reentry assembly while being raised in the derrick.

The BIP was then placed on the catwalk, the EM Cable connected and systems checks were made. The BIP was picked up with crane and tugger until load could be taken vertically on EM Cable then carefully lowered into the carriage. Figure 8-2 is a photo of the BIP just before being lowered into the reentry sub carriage. The carriage shear pins and hydraulic connection lines were installed at moonpool work platform. The total assembly was lowered approximately 20 feet and snubbed off with tugger and cat line, while hand feeding the EM Cable through the rotary table.




FIGURE 8-1 SHIPBOARD HANDLING OF REENTRY SUB




FIGURE 8-2 BIP IN DERRICK

The bight of EM Cable on rig floor was removed from the sheave and passed through the rotary down to the lower work platform and secured. The assembly was then lowered and slips set around the top bumper sub. One 30 foot - 7½ inch OD drill collar, weight 3,000 pounds, was made up to the bumper sub and the assembly was lowered and landed on slips. One stand of drill pipe was then made up above the drill collar.

The slot in BIP carriage assembly was oriented facing the A-Frame sheave and orientation marks scribed on rotary table and tool joint for reference during deployment. The pipe was lowered 30 feet where the EM Cable bight was removed from guard and passed through the piccolo base and released. The EM Cable was not tensioned during the first 1,180 feet of deployment, but was kept taut to prevent entanglement. At 1,180 foot depth, footage counters were set to correspond with assembly measurements, weight indicators were checked, recorders started and the heave compensator raised to mid-stroke. The tension on EM Cable was increased to 500 pounds during the deployment of the next 9 stands of drill pipe to a depth of 2,017 feet where it was raised to 2,000 pounds, and then increased to 3,000 pounds at a depth of 2,947 feet. Refer to Appendix H for specific data from test. The tensions were somewhat lower than previously planned because there was no indication of current acting upon the EM Cable or drill string. We continued pipe deployment until the sea bottom was reached, while increasing cable tension to a maximum of 7,200 pounds.

The three major concerns at the start were (1) coordination between the driller and winch operator, (2) keeping the BIP carriage orientated and (3) avoiding cable entanglement. The first two concerns soon disappeared due to the skill and dedication of the Challenger's fine crew.

At 1900, the reentry tool was run in on the Schlumberger line, and scanned for reentry. Reentry was accomplished in the usual DSDP manner by maneuvering the Challenger using range data from the sonar reentry tool. The drill string acts as a heavily damped pendulum tending to oscillate in a figure eight motion. After a series of iterative ship motions, the reentry sub was positioned over the conical shaped reentry cone. The drill string was then lowered rapidly at the rig floor allowing a 60 foot drop of the reentry sub into the reentry cone and associated casing. At 1257, 30 March, reentry was

smoothly accomplished. We recovered the sonar tool, rigged down the Schlumberger equipment and reset footage counters to correspond with measurements of drill pipe and assembly deployed. This took about 5 hours to accomplish.

The major remaining concern at that time and one which had been with us from the beginning, "cable entanglement" would soon be resolved. The tension on EM Cable was slacked to 7,000 pounds in order to leave approximately half the weight of the BIP setting down on the carriage, thus allowing the BIP to fall a short distance when the pins were sheared. Using the cement pump, pressure was brought up slowly to approximately 2,200 psi with no indication of shear observed on pressure gauge or weight indicator. However, the BIP data indicated shear had been accomplished. The anxious moment had arrived, would the BIP payout freely or were we entangled? The winch began slowly paying out cable with all eyes glued to weight indicators and recorders. The weight began to decrease indicating the BIP was initially not falling. Then, the weight indicators stabilized and the winch smoothly began paying out. No entanglement and the BIP was on it's way to bottom. The BIP was run to the bottom (16,738 feet) and held for data, pulled back 1,000 feet and lowered again to take further lowering data characteristics.

The ship was moved 200 feet upstream to the current and then the reentry assembly was pulled out of the reentry cone approximately 90 feet above cone. The hydraulic system was repressured to 3,400 psi releasing the EM Cable gate. The BIP was returned to the bottom of the borehole. The running string was pulled out, and the reentry assembly was retrieved, disassembled, and returned to the storage rack. The ship was then moved 2,990 feet downstream to current while paying out EM Cable on seafloor with approximately 2,000 feet additional cable laid out.

At 2300 on 28 March seismic experiments were begun, with all systems working well. At 0800, the next morning, an additional 2,400 feet of cable was payed out to help isolate the cable noise at the BIP. The seismic survey was completed at 0300, Sunday, 29 March and preparations made for recovering the BIP.

The slack cable was taken up from seafloor, with approximately 3,000 pounds tension on cable, as the ship moved back over the entry cone. An attempt to pick the BIP off the bottom, with approximately 4,000 pounds over-pull, was not successful. However, the seismic instruments indicated some vibrations were getting to BIP. The conclusion was that the EM Cable was probably fouled or caught under a sonar reflector. With this in mind, the ship was moved 200 feet East, cable slacked approximately 30 feet and then immediately pulled back in tension. The cable came free and the BIP was pulled from the bottom freely. The cable was reeled in and the BIP recovered onboard ship. The frontispiece depicts the final successful recovery of the BIP while alongside the ship preparatory for bringing aboard. The DARPA program was completed at 0445, Monday, 30 March, approximately 72 hours and 45 minutes from start to successful conclusion.

## SECTION 9.0 - TEST DATA EVALUATION

### 9.1 IMPACT FORCES

The long period seismometers scheduled for inclusion in subsequent borehole instrument packages can be subjected to a maximum of 10 Gs dynamic impact loading. In order to determine the actual magnitude of impact loading that these instruments are likely to register during a normal reentry and borehole deployment, this test BIP was equipped with triaxial accelerometers which were continuously recorded during deployment. They are installed on 6 inch diameter bolted tube segments approximately 10 inches and 20 inches long respectively above the pressure vessel base. The bolted tube segments are fixed at the base and are laterally spring-stabilized approximately 60 inches above the base. The mountings thus are much more rigid in the longitudinal direction than along the lateral Y and X axes.

During the deployment of the BIP into the borehole, a variety of shipboard handling, lowering, and reentry shock impacts were recorded. In general, they were of the same general 2 to 6 G (at the BIP) level of magnitude. The most severe forces occurred during initial reentry; however, these impacts were concentrated at the bottom of stinger approximately 30 feet below the carriage housing which supported the BIP. These forces were somewhat attenuated by the cantilevered stinger structure. The other shock loading occurred on the BIP directly on, or in the general area of the carriage housing.

The original analysis of reentry impact was reported in Reference 4. A summary of the predicted characteristics is as follows:

	<u>Rigid Joint</u>
Impact Velocity	10 ft/sec
Impact Impulse	1,158 lbs-sec
Duration of Impact	.011 sec
Max. Impact Force	164,000 lbs
Angular Velocity of RS	0.2 rad/sec
BIP Loading	6 - 8 G

The shock analysis for a complex structure such as a reentry sub attached to a long drill string is a difficult problem. Due to the short impulse time, the effective length of the body reacting to the impulse is difficult to determine. In particular, the joint stiffness above the reentry sub is critical. In general, the test data confirms the original analysis. This analysis can be extrapolated to the more severe 1982 conditions.

The following is a brief description and evaluation of the accelerations recorded for each phase:

- o Shipboard Handling - This step included removing the BIP from its shipping container, standing upright, and inserting it into the carriage housing on the rig floor.
- o Lowering the reentry assembly to the seafloor - Accelerations were recorded while drill pipe was added and lowered. Cable was payed out at a rate which maintained a relatively constant tension at the BIP.
- o Reentry into the cone and cased borehole - Accelerations were recorded while the stinger was stabbed into the cone from about a 6 foot height. It was lowered quickly for about 20 feet; then lowered more slowly for an additional 40 feet to ensure that the stinger was fully in the borehole casing.
- o Reentry assembly standing in cone - Drill string motions were imparted to the reentry assemble during the 6-hour period required to retrieve the sonar tool and run in and latch the Baker plug.
- o BIP carriage shift and release - Accelerations registered when the BIP carriage was shifted horizontally 12 inches in order to align the BIP over the borehole.

- o Lowering the BIP in the borehole - Irregularities in the borehole induced shocks to the instrument housing.
- o Landing the BIP at the bottom of the borehole - When the BIP contacted the bottom of the borehole large, vertical accelerations were expected.
- o Lifting the BIP - Recovery of the BIP caused shocks because of forces required to free the instrument plus random irregularities in the borehole walls.

The accelerometer output, as recorded in real time on a strip chart, are analyzed and briefly described below for each of the above phases of deployment.

Loading: Random impacts occurred throughout the duration of the approximately 15 minute loading phase. Initial lift by the crane occurred at 10:03:26 and registered a maximum 3.5 G shock. The natural transverse frequency of the BIP is approximately 12.5 Hz. Handling impacts were also noted when the BIP struck the rig floor. Typical X-axis impacts of 3.2 Gs, obtained when the BIP was lowered into the carriage, are shown by Figure 9-1. The plots are Z, Y and X respectively from the top. The bottom trace is a GMT time signal. The apparent lateral fundamental frequency is about 40-50 Hz, but this ringing exhibited in the lateral accelerometer traces may be due to resonant vibration of the accelerometer mounts.

Lowering of the Reentry Sub: Vertical accelerations were recorded each time pipe was added to the drill string. With 4,000 feet deployed, the apparent pipe string fundamental frequency was noted at slightly less than 2 cps. As the drill string length was extended, the recorded shocks were increasingly attenuated.




FIGURE 9-1 SHIPBOARD HANDLING (PRIOR TO DEPLOYMENT)

Reentry: Figure 9-2 is the reentry accelerometer record. First contact with the cone occurred at 02:57:26 GMT (1157 local time) with the major impact of about 6 Gs at 02:57:32.7. By 02:57:50 (Figure 9-3) motions had decreased indicating that the bumper subs had set. The predominant X-axis frequency was about 40-50 Hz while the Y-axis frequency was in the 80-90 Hz range. The major vertical shock impulse lasted approximately 15 msec. The initial 40 feet of stab was estimated at about 6 ft/sec with the latter portion estimated at 1-2 ft/sec. The sharp horizontal shock, followed immediately by a sharp vertical shock was the impact of major concern during system design. It may have occurred as the carriage seated in the bottom of the cone. For rougher weather, more shock absorption is undoubtedly required.

Standby in Cone: Figure 9-4 is a representative record of accelerations which occurred while the assembly was standing in the cone. These small events appear to occur with 4-1/2 to 6-1/2 second periods or roughly concurrent with ship and drill string motion. Figure 9-4 shows the record of one event and indicates a small vertical acceleration followed by a larger horizontal acceleration. These motions are probably due to the shock of fully closing or fully opening of one of the bumper subs just above the reentry assembly, although ship heave was slight at this time.

BIP Release: Figure 9-5 is the record of accelerations occurring when the BIP carriage was shifted laterally to the release position. This motion induced large accelerations of about 5 plus Gs for about 0.8 sec on the horizontal axis and smaller accelerations for 0.25 sec on the vertical axis. The accelerometers continued to show motion for several seconds on the horizontal axis, indicating resonance within the BIP case or the reentry assembly or both. The predominant lateral frequency appears to be in the 50-60 Hz range with the X-axis indicating slightly lower frequencies but higher amplitudes than the Y-axis.




FIGURE 9-2 REENTRY




FIGURE 9-3 POST REENTRY




FIGURE 9-4 STANDBY IN CONE

0 1 2 SECONDS




FIGURE 9-5 BIP SHEAR RELEASE

Lowering the BIP Down Hole: Figure 9-6 is a representative record of the accelerations occurring during the lowering of the BIP in the borehole. These shocks of 1 to 4 Gs were probably caused by the BIP striking rock ledges and rebounding. They are not considered a serious threat to the safety of the instrument.

Landing the BIP: The accelerometer record of the BIP making contact with the bottom of the borehole is shown in Figure 9-7. The peak acceleration was 4 Gs. Because bits, tools, and other items remained at the bottom of the hole from previous work, a purely vertical shock was not necessarily expected. Horizontal accelerations, however, were higher than expected indicating that the BIP made a sharp horizontal motion just as it was reaching the bottom. The horizontal accelerations may have been caused by the BIP tilting over and striking the side of the borehole.

In summary, the reentry accelerations were slightly less than expected, but other deployment accelerations were higher than the expected but within the allowable range. The horizontal or lateral axes (X-axis in particular) may have been recording slightly magnified accelerations due to mounting characteristics. Improved shock isolation is desirable for the expected more severe weather conditions of the 1982 deployment.

A detailed analysis of the various shock characteristics has not been performed pending better definition of the future deployment requirements. The data is available for future evaluation when deemed necessary.

## 9.2 CABLE DYNAMICS

### 9.2.1 Analysis

Since the inception of the MSS program, the potential problem of cable entanglement has been a major controversy. Proper cable tension was considered necessary to avoid cable/drill string




FIGURE 9-6 LOWERING BIP IN BOREHOLE




FIGURE 9-7 BIP BOTTOM OF BOREHOLE

entanglement during deployment. An extensive study (Ref. 5) conducted by E. Gershunov of Global Marine Development Inc, investigated the static and dynamic stresses induced in an electro-mechanical cable by horizontal currents and by ship motions responding to various sea surface conditions. In our application at Site 395A, the lower end of the cable was initially secured to the lower end of the drill pipe and the upper portion of the cable was controlled by a ship mounted constant tension winch. The weights, lengths, and tensions discussed are all applicable to the entry of an existing borehole with a seismometer package having an external cable and carried on a reentry sub. The cable was subjected to all the motions induced in the pipe by ship roll, pitch, heave, and yaw plus additional stresses induced independently on the cross-sectional profile of the cable by currents in the water column.

The EM Cable is hytrel jacketed, spaced armored and torque balanced with coaxial conductors. It has an outside diameter of 0.692 inches, breaking strength of about 21,000 pounds, and longitudinal stiffness (product of modulus of elasticity and cross-sectional area) of  $2 \times 10^6$  pounds. Dry and wet weights are approximately 0.5 and 0.3 lbs/ft respectively.

While it was not possible to describe all wave, sea, and current conditions likely to be imposed on the cable and pipe during deployment; average and limiting conditions serve as useful guides. Surface conditions assumed for Site 395A included an average wave height of 4 feet and an average wave period of 5 seconds. Seas in excess of 5 feet occurred less than 20% of the time. Typical surface currents were 0.34 - 0.66 knots while mid-water currents were not expected to exceed 0.19 - 0.29 knots. There was no evidence for a significant frequency of strong bottom currents. Appendix I contains a short plot of actual ship motion data taken just prior to reentry.

These studies were initiated to determine the maximum tensioning characteristics of the cable and to examine the probability of entanglement between the drill pipe and the cable. Thus, they estimate the tension in the cable, the deflected shape of the cable due to currents and ship motions, and specify requirements for a tensioning system. Understanding and controlling these factors were

expected to aid in reducing the dynamic oscillations experienced during deployment and in reducing the probability of cable/drill pipe entanglement. The current is considered as static and planar for these analyses, but in reality are slowly time dependent in direction and magnitude.

The following paragraphs summarize the results of the dynamic and static cable analyses:

- o Tension in the cable is controlled primarily by its own weight, current, ship roll, pitch and heave motion and reentry sub release. Surge, sway and yaw generated tensions are small and may be neglected.
- o Cable weight and current generate static tension; ship motion and reentry sub release cause dynamic tension in the cable.
- o Maximum static tension is dependent on cable length and current and occurs at the upper end of the cable. For linear current with 2 knots at the surface and 0 at the bottom, the maximum tension is about 7,500 pounds. The main contributor to static tension is the weight of the cable. Total cable drag ranges on the order of 500 to 1,500 pounds. Additional tension due to current is thus in the range of 10-20% of the tension caused by cable weight. Minimum static tension occurs at the lower end of the cable where the tension is limited to above 500 pounds to avoid entanglement. Figure 9-8 shows the deflected shape of the cable for various deployed depths.
- o Generally, dynamic tension applied to the upper end of the cable causes changes in the deflected shape in addition to the elongation of the cable. Conservative evaluation of the upper limit of the dynamic tension is based on the assumptions: (1) dynamic tension transforms completely into strain energy of the cable or causes elongation only, and (2) the lower end of the cable is attached to the reentry sub/drill pipe and is immovable for each cable length. Figure 9-9 shows the effect of tension on cable configuration.
- o Dynamic tension depends on the wave frequency, cable length and velocity of the strain propagation in the cable. Strain propagation is evaluated to be 11240 ft/sec. Maximum dynamic tension occurs at the lower end of the cable.




FIGURE 9-8 DEFLECTED SHAPE OF THE EM CABLE DUE TO CURRENT FOR 5000, 10000, 15000 AND 20000 FT OF WATER DEPTH




FIGURE 9-9 EM CABLE AND DRILL PIPE DEFLECTED SHAPES

- o The first natural frequency of the cable in longitudinal oscillation is determined to be in the range of 0.88 - 3.53 radians/sec. which corresponds to a natural period of 1.8 - 7.1 secs, depending on length of the cable. Frequency and period of the second mode are in the range of 2 - 11 radian/sec and 0.6 - 2.4 secs, respectively. The highest modes have the periods in the range of less than 2 seconds corresponding to very low energy of the sea energy spectrum (Table 9.1).
- o The upper limit of dynamic tension as caused by ship motions is a function of deployed depth as indicated by Table 9.2.
- o For 15,000 foot water depth and the ship location of 3,000 feet downstream of the borehole, the slacked length of the cable is about 1,000 feet and tension at the borehole is estimated in the range of 800 to 900 pounds for sea state 5 condition and linear current profile. For the planned total cable payout of 20,000 feet, approximately 1,600 feet will be laid on the ocean floor to aid in sensor decoupling.
- o After BIP release and lowering, the cable remains captured by the reentry sub after the two cases were investigated:
  - (1) Cable is locked in the reentry sub
  - (2) Cable is pulled through the reentry sub

If the cable is locked at the reentry sub, tension, as registered by the shipboard dynamometer, will have a tendency to decrease as the pipe is withdrawn. If the cable is pulled through the reentry sub, the observer will note an increase in tension.

- o Possible interference between the drill pipe and the cable after BIP release may occur only in cases of no ship offset. If the reentry sub is raised 60 feet, the ship is moved 500 feet up current in the presence of a 1 knots current, the pipe and cable will be offset by about 380 feet. Other offset and current conditions do not indicate real tendency for interference between the drill pipe and the cable after the BIP release.
- o In the case of ship maneuver upstream at a speed of 0.25 knots, deflected shape of the drill pipe and the cable suggest enough separation to avoid any interference between the two deflected shapes.

TABLE 9.1

EM CABLE NATURAL PERIOD OF LONGITUDINAL OSCILLATION

N NODE	Cable Length FT	5,000	10,000	15,000	20,000
0	Frequency RAD/SEC	3.53	1.77	1.17	0.88
	Period SEC	1.8	3.5	5.4	7.1
1	Frequency RAD/SEC	10.6	5.3	3.5	2.6
	Period SEC	0.6	1.2	1.8	2.4

**TABLE 9.2**  
**UPPER LIMIT OF MAXIMUM CABLE DYNAMIC TENSION**

SIGNIFICANT WAVE HEIGHT FT	SHIP MOTION	TENSION IN LBS FOR LENGTH OF THE CABLE			
		20,000 FT	15,000 FT	10,000 FT	5,000 FT
4	ROLL	97	129	193	387
	PITCH	152	203	305	610
	HEAVE	305	407	610	1,220
6	ROLL	145	196	290	580
	PITCH	227	305	458	915
	HEAVE	458	610	915	1,830
8	ROLL	193	257	387	770
	PITCH	305	407	610	1,220
	HEAVE	610	813	1,220	2,440

- o If the demonstrated length of the cable is equal to the water depth, the ocean currents may cause additional substantial tension in the cable and result in elongation. This additional tension is distributed along the cable length.
- o To avoid kink formation in the cable and snap loading, the maximum tension controlled at the upper end is recommended to be maintained at approximately 10% more than the weight of the deployed length of the cable.
- o No snap loads or 0 tension characteristics appeared in the cable for any of the conditions tested and described based upon a special time domain cable program run.

On board the Challenger, a special static cable deflection computer program was established utilizing a HP-41 CV calculator. Cable tension adjustments were derived from a 15 node representation which allows for variable current forces with depth, end tensions, end positions and cable wet weight input. This program provided a quick reference for on-the-spot checks of real data.

Table 9.3 indicates the effect of current (assumed decreasing proportionally with depth) on control parameters. Table 9.4 was tabulated as a guide to cable payout and tensioning limits for the expected 1 or 0.5 knot current conditions. The indicated cable tension needed to be corrected by an approximate 1.7 load cell correlation factor to take into account cable angle over the sheave which varies with both load and heave compensator position.

#### 9.2.2 Cable Load Evaluations

In general, the dynamic cable tensioning characteristics followed the estimates. Experimental data were derived from the hydraulic load cell gauge, a digital readout and from analog recorder records.

Relatively high oscillatory loads induced by ship motion occurred when there was only a short cable/drill string deployed out.

**TABLE 9.3**  
**CABLE TENSION EFFECT WITH CURRENT**  
**(15,000 FT)**

CURRENT	TENSION (TOP)	LAT. DISP. (max)	STRETCHED LENGTH	CABLE ELONG.	CORR. LENGTH	TENSION (BOTT.)
Knots	lbs	ft	ft	ft	ft	lbs
0.1	4,426	93	15,020	20	15,000	3
0.5	4,984	331	15,021	21	15,000	555
1.0	8,000	509	15,043	43	15,000	3,518
1.5	12,000	650	15,074	74	15,000	7,822
2.0	17,100	796	15,109	109	15,000	12,490

TABLE 9.4  
LEG 78B, HOLE 395A  
CABLE TENSIONING CHARACTERISTICS

15,000 FT

TOP CABLE TENSION	1 knot (surface)					½ knot (surface)				
	LAT DISP.	CABLE LENGTH	ELONG	CORRECTED LENGTH	TENS. (BUTT)	LAT. DISP.	CABLE LGTH.	ELONG	CORRECTED LENGTH	TENSION BUTT
LBS	FT	FT	FT	FT	LBS	FT	FT	FT	FT	LBS
5,000	1,201	15,316	20	15,296	371	308	15,016	21	14,995	570
6,000	782	15,111	28	15,083	1,510	228	15,008	28	14,978	1,572
7,000	614	15,065	36	15,029	2,611	178	15,004	36	14,968	2,573
8,000	509	15,043	43	15,000	3,518	159	15,003	43	14,960	3,573
9,000	436	15,031	51	14,980	4,536	144	15,002	51	14,951	4,573
10,000	384	15,023	58	14,965	5,543	132	15,001	58	14,943	5,573

As depth increased the cable stiffness decreased, resulting in less amplitude tensions at the surface for the same approximate ship motions. At reentry depth, the natural cable frequency approached 0.16 Hz (6 second period) which is similar to ship motion periods. At 14,600 feet, cable dynamic tension amplitude (significant) appeared to be about  $\pm$  250 pounds with a fixed end. With the drill string constrained in the reentry cone, the significant amplitude appeared to increase to about 350 pounds. For the deployment phase, sea conditions remained approximately constant. More detailed cable characteristics could be correlated to ship motion data taken concurrently by DSDP (Appendix I).

Figures 9-10 and 9-11 illustrate the typical deep deployment characteristics of the cable when the BIP is restrained to the drill pipe and free, respectively. Reentry is shown on Figure 9-12. An initial reduction in tension occurs as approximately 33 feet of cable was payed out in preparation for the approximate 60 foot stab. The HC/A-frame system fluctuates widely during the actual reentry stab.

The nitrogen gas pressurized passive heave compensator (HC) had a spring constant in the range of 50 to 170 lbs/ft using the fixed accumulator. The gas HC cylinder retains a partial hardened spring action even when locked out. Typically, during the shallow to middle deployment depths, locking out the HC cylinder slightly increased the oscillations at the deepest depths, and decreased oscillation with HC locked indicated that the HC/cable system was near resonance. A preliminary calculation for the HC/cable system indicates a natural frequency of about 0.12 Hz (8.3 second period). Figure 9-13 illustrates the effect of partially locking out the HC by closing the valve to the accumulator.

The initial lowering of the BIP approximately 10 minutes after reentry sub carriage release is shown in Figure 9-14. The BIP was apparently momentarily not released, as indicated by the reduction in load cell reading during initial cable payout, which was followed by an increase in load and free ended vertical oscillation during subsequent lowering.




FIGURE 9-10 EM CABLE DYNAMICS FULLY DEPLOYED PIPE STRING (~15,000 FT)





FIGURE 9-11 CABLE DYNAMICS RECOVERY OF BIP (~16,000 FT)



HEATH COMPANY

FIGURE 9-12 CABLE DYNAMICS REENTRY




FIGURE 9-13 CABLE DYNAMICS EFFECT OF HC (~14,000 FT)

PAYOUT CABLE




FIGURE 9-14 CABLE DYNAMICS RELEASE OF BIP

During the BIP lowering within the borehole, cable dynamic amplitude appeared to be about  $\pm 900$  pounds (significant) at an average frequency of 0.15 Hz. With the BIP at the bottom of the borehole and the cable tensioned, the significant dynamic amplitude ranged from  $\pm 350$  pounds to  $\pm 600$  pounds and the average frequency ranged from 0.13 to 0.19 Hz. For the BIP at the bottom of the borehole and the cable slacked, the dynamic amplitude was  $\pm 350$  pounds at an average frequency of 0.16 Hz. During BIP retrieval, the dynamic amplitude was initially 800 pounds, with an average frequency of 0.11 Hz when 15,000 feet of cable was deployed. At the 4,000 foot cable length, the dynamic amplitude averaged  $\pm 350$  pounds with an average frequency of 0.16 Hz. A majority of data were taken with the HC system operating, except when momentarily locked out to record specific data. Figure 9-15 shows the typical oscillatory characteristics during final recovery.

The indicated cable loads, static and dynamic, were well within the ranges predicted by the analysis. No unusual reactions were noted. The noted increase in dynamic load amplitude at the deeper depths during initial deployment of the drill string correlated with a probable HC resonance regime. Limited data is now available which is representative of both locked and free ended cable configurations down to approximately 17,000 feet.




FIGURE 9-15 EM CABLE DYNAMICS RECOVERY OF BIP (~8,000 FT)

## SECTION 10.0 - MOBILIZATION/DEMOBILIZATION

The Mobilization/Demobilization effort for the MSS At-Sea-Test was a major complex operation due to the specific foreign field site locations and the amount of shipment required. In addition, the varying equipment availability and DSDP Challenger schedules required continuous replanning of the mobilization tasks. Figure 10-1 outlines the overall schedule of major activities.

Mobilization was accomplished at San Juan, Puerto Rico starting in late December 1980 and lasting through early March 1981. The mobilization was accomplished at the Puerto Rico Marine Terminal and Drydock shipyard. Almost all MSS equipment was shipped to San Juan by truck and trailer barge although some structural units were fabricated at the shipyard. Initial installation of MSS equipment foundations plus the A-Frame were accomplished during the regular DSDP February 1981 four day Challenger port call. The final loading and checkout test of the MSS equipment was successfully accomplished in the special March 1981 MSS two day Challenger San Juan port call. Appendix D provides a listing of major equipment items onboard. In general, we were quite pleased with the support by the Puerto Rico Marine Rico Terminal and Drydock Organization.

There was a continuing problem with clearance of the MSS equipment through Puerto Rico customs. Through prior correspondence with the Excise Tax Board, no Puerto Rican taxes were charged. However, it was quite time-consuming to deal with the Tax Board for each bill of lading.

A major problem was due to the temporary "loss" of BIP #2 Ryder by the trucking firm. It had to be specially reshipped using air freight. Some major damage to the BIP occurred during this reshipment.

The removal of MSS equipment was accomplished very expeditiously in the shipyard in Las Palmas, Canary Islands. The shipment back to the U.S. was very slow (taking approximately two months) and expensive to accomplish. The Geotech equipment was returned to Dallas, Texas; while the remainder was shipped to NOSC San Diego, California for interim storage.

SUMMARY MSS AT-SEA-TEST SCHEDULE




FIGURE 10-1 SCHEDULE

REFERENCES

1. MSS Deployment Program Phase II Report  
GMDI Report-001-005 dated 15 January 1981.
2. Summary of Scientific Results of Leg 78B  
DSDP Report dated 16 March 1981.
3. Geotech Report - At-Sea-Test - TR81-6
4. MSS Reentry Impact  
GMDI Report 001-001 dated 25 September 1980.
5. MSS EM Cable Static and Dynamic Response due to Current and Glomar Challenger motion.  
GMDI Report 006-002 dated 2 February 1981.

GLOSSARY

BASELINE CONCEPT	Reentry Concept Based Upon Lowering BIP at End of Drill String into Borehole
BIP	Borehole Instrumentation Package - Seismic Downhole Instrument
CONFIG. I	Prototype Short Period MSS Configuration
CONFIG. II	Long Period MSS Configuration With 5 Year Capability
DARPA	Defense Advanced Research Projects Agency
DSDP	Deep Sea Drilling Program Project Office Scripps Institute of Oceanography
EM CABLE	Electromechanical Cables - Used with BIP and Reentry Tool
FLY-IN CONCEPT	Reentry Concept that flies in BIP on End of Cable into Borehole
GEOTECH	Geotech Teledyne, Dallas, Texas
GMDI	Global Marine Development Inc, Newport Beach, California
GMDC	Global Marine Drilling Company, Houston, Texas - Operator of GLOMAR CHALLENGER
GOULD	Gould Chesapeake Instrument Division, Glen Burnie, Maryland
JOIDES	Joint Oceanographic Institution for Deep Earth Sampling
MSS	Marine Seismic System
NSF	National Science Foundation
NORDA	Naval Ocean Research & Development Agency, Bay, St. Louis, Mississippi
REENTRY CONE	Special Cone Developed by DSDP for Borehole Reentry
REENTRY SUB	Special Lower End Fixture which Supports the BIP
REENTRY TOOL	SONAR/Reentry Control Sensor

APPENDIX A

MSS SEISMIC SYSTEM PROGRAM AT-SEA-TEST PLAN SYNOPSIS



DEPARTMENT OF THE NAVY  
NAVAL OCEAN RESEARCH AND DEVELOPMENT ACTIVITY  
NSTL STATION, MISSISSIPPI 39529

NO. REF. REFER TO

Revised 12 December 1980

MARINE SEISMIC SYSTEM PROGRAM  
AT-SEA-TEST PLAN SYNOPSIS

APPROVED BY:

*J. A. Ballard*  
NORDA

PREPARED BY  
GLOBAL MARINE DEVELOPMENT INC.  
2302 MARTIN STREET  
IRVINE, CALIFORNIA 92715

MSS DEPLOYMENT  
AT-SEA-TEST PLAN SYNOPSIS

I. OBJECTIVES

The primary objective is to provide a proof of principal demonstration for the deepwater borehole BIP concepts, specific goals are:

- 1) Demonstrate deepwater instrumented package deployment
- 2) Collect data for BIP final design
- 3) Demonstrate sub-seabed instrumentation effectiveness

Deepwater BIP reentry into a borehole will be demonstrated utilizing the baseline concept which lowers the BIP at the end of a drill string. Reentry impact shock levels are to be measured. Cable entanglement data will also be measured as applicable. Short period seismic data from within the existing borehole is also to be provided over a 24 hour period to confirm sub-seabed installation effectiveness. Subbottom vertical reflection survey, air gun seismic echo recording and slant range explosive testing is to be accomplished using the USS Bartlett (AGOR). Recovery of the test BIP is to be attempted.

\*II. ORGANIZATION RESPONSIBILITIES

The following responsibilities are :

Program Management

NORDA

Test System Integration and Technical Coordination GMDI

\* Denotes revised areas

Support Ship	NORDA/GMDI
CHALLENGER Operations	DSDP/NSF/GMDC
Reentry Test Equipment	GMDI
BIP Test Package	GEOTECH
Reentry Data Monitoring Equipment	GMDI
EM Cable and Winch	GEOTECH
Seismic and Acceleration Data Monitoring Equipment	GEOTECH
CHALLENGER Modifications	GMDC/GMDC
Test Procedures	GMDI
Test Logistic Support in San Juan	GMDI
Current Meter Equipment	NORDA
Demobilization in Las Palmas	GMDI
MSS OBS Calibration Experiment	NORDA
USS Bartlett Operations	NORDA

### III. LOCATION


The proposed tests will tentatively be accomplished in the mid-Atlantic area utilizing an existing hole/reentry cone installed earlier by the CHALLENGER DSDP. Site 395A will be the primary hole with Site 396B as alternate. These sites are located along the 23 degree North parallel at the 46 degree West and 43-1/2 degree West Meridians respectively.

### \*IV. SCHEDULE

The proposed test will tentatively take place in the early part of March 1981 during the CHALLENGER transit leg 78B to Las Palmas. Total estimated site time of CHALLENGER at-sea involvement is 6 days for the MSS Test. Fig. IV-1 depicts the current overall schedule. There is also an integrated test schedule updated bimonthly.

12 DEC 1980

# SUMMARY MSS AT-SEA-TEST SCHEDULE



0006-031

Ship modifications plus installation of the foundation and cabling for test equipment will be accomplished in parallel to other regular DSDP logistic efforts in the January 23, 1981 San Juan port call. In late February 1981 the CHALLENGER will return from the Martinique area to San Juan for a 2 day final installation of the MSS equipment. Unloading in Las Palmas should take 1/2 day if full retrofit is not required. A receiving and test facility at San Juan is to be available 1 month before installation.

The USS BARTLETT will mobilize in Mayport. Jacksonville during the last week in February 1981. A special mobilization period of several days will be required to outfit a Navy vessel for support operations. The USS BARTLETT will arrive on station at the same time as the GLOMAR CHALLENGER.

\*V. TEST AGENDA

The following preliminary Scientific and MSS test agenda has been tentatively established.

	<u>Est. Time</u>	
1. Locate site and run in drill string	2 days	
2. Borehole logging program	2 days	
3. Fracturing experiment	2 days ***	} Scientific Testing
4. Oblique seismic and magnetometer testing	2 days ***	
5. Multiple reentry demonstration baseline concept	1-1/2 days	
6. Lower BIP into borehole and record data	1-1/2 days	} MSS Testing
7. Recovery Test BIP	1/2 days	
**8. Weather and malfunction contingency	2-1/2 days	

Some of the listed scientific tests denoted by triple astericks may not be performed.

\*\* Installation of cement plug and subsequent drill out has been deleted.

\*VI. EQUIPMENT REQUIREMENTS

The following At-Sea-Test equipment has been defined for the baseline system.

<u>1) BIP Lowered at End of Pipe (Baseline)</u>	<u>Responsibility</u>	<u>Remarks</u>
BIP reentry test package	GEOTECH	
EM Cable	GEOTECH	NORDA supplied
Reentry tool (sonar) and readout console	-	Onboard
Reentry sub (15,000 ft. depth) includes impact stinger, release mechanism, reentry tool support and control manifold	GMDI	
BIP recording console van (STC)	GEOTECH	
Reentry tool winch and cable	-	Onboard Schlumberger Winch/Cable
BIP EM Cable Winch	GEOTECH	Navy spec.
A-Frame including foundations	GMDI	
Cable tension and measurement equipment	GMDI	
Reentry Cone	-	Use existing cone
Miscellaneous handling equipment	GMDI	
Deployable current meter (3000 ft)	NORDA	
Bottom current meter (reliable)	NORDA	
OBS Seismic Packages (4)	NORDA	
ASK Beacons	DSDP	
A-Frame Heave Compensator	GMDI	
Sub surface TV system	GMDI	

VII. TEST DATA OBJECTIVES

1) Reentry Demonstration

Reentry sub velocity (lateral)

Reentry sub position relative to ship and reentry cone

Ship stationkeeping characteristics

Shock impact

Current profile with depth

Cable tension

Reentry stabbing velocity

2) Lowering Demonstration

BIP lowering velocity

Surface cable payout

Lowering cable tension

3) Seismic in Hole Demonstration (24 Hours Real Time)

Short period seismic data 3 vertical channels/sensor - 2 sensors

OBS comparative data

Noise of ship affect

BIP State of Health Instrumentation - 4 temperature

1 pressure

2 short circuits

6 voltage

\*VIII. SPECIAL CONSIDERATIONS

- 1) The use of the high strength drill string is an expensive and long lead procurement item. Present responsibility for the drill string lies with DSDP
- 2) Both 395A and 396B boreholes are filled with mud which must be flushed out and replaced with light gel.
- 3) Cementing the BIP into the borehole is not included.

- 4) A spare test BIP and reentry sub will be provided.
- 5) Special training for operation of the EM cable winch must be provided for 2 GMDC personnel.
- 6) The shipping facilities to San Juan are limited.

\*IX

TEST PERSONNEL

Accommodations for At-Sea-Test personnel will be as follows:

NORDA	1
GMDI	3
GEOTECH	3
DARPA	1
	<hr/>
	8

APPENDIX B

MSS PROGRAM AT-SEA-TEST BASELINE DEPLOYMENT SYSTEM

INTERFACE AND REQUIREMENT SPECIFICATIONS

SPC-001-001  
MARINE SEISMIC SYSTEM PROGRAM  
AT-SEA-TEST  
BASELINE DEPLOYMENT SYSTEM INTERFACE & REQUIREMENTS SPECIFICATION  
(JOB 00006-325000)

REVISION 4

12 DEC 1980

Approved

  
GMDI

PREPARED BY

GLOBAL MARINE DEVELOPMENT INC.  
2302 MARTIN STREET  
IRVINE, CALIFORNIA 92715



# GLOBAL MARINE DEVELOPMENT INC.

Newport Beach, Calif.

## REVISION RECORD

REV	DATE	AUTHORIZATION	CHANGE DESCRIPTION	PAGES AFFECTED
A	16 Aug 80	R. Wallerstedt	Preliminary Release for NORDA Review	ALL
1	05 Sep 80-	R. Wallerstedt	2.0 Revised References	1
			4.2 Added Note About Filled in Borehole	2
			4.7 Added New Operational Criteria	3
			5.2 Deleted 10 days of Remotely Recorded Seismic Data	5
			6.1 Revised BIP Configuration Dimensions	5
			6.2 Revised Weight of BIP	5
			6.5 Deleted Magnetic Azimuth	7
			6.6 Deleted Magnetic Azimuth	7
			6.8 Reduced Mag. Tape Capability to 5 days	8
			6.9 Added EM Cable Design Data	8
			7.1.5 Deleted Optional Mechanical Actuation	10
			7.1.6 Reduced Lowering Speed to 20 ft./min.	10
			7.4 Deleted Lowering Cable Requirement	12
			8.2 Deleted Reentry Tool Console	12
			8.5 Deleted Lowering Cable Winch	12
			8.7 Added Rack for 2 BIPS	13
			8.8 Added Rack for 2 Reentry Subs	13



# GLOBAL MARINE DEVELOPMENT INC.

Newport Beach, Calif.

## REVISION RECORD

REV	DATE	AUTHORIZATION	CHANGE DESCRIPTION	PAGES AFFECTED
2	22 SEP 80	R. Wallerstedt <i>R. Wallerstedt</i>	2.0 Revised references 4.2 Added note about mud and equip. in borehole revised dimensions 4.3 Deleted note on mud and equip. in borehole 4.5 Correct comment to "a maximum lowering speed with hydromatic brake" 6.1 Corrected dimensions add Geotech Ref. dwg. 6.2 Revised weight to 3350 lbs. 6.3 Changed "Release" to "Handling" 6.6 Changed 3 shock accelerometers to 5 6.7 Added van dimensions and weight 6.9 Minor revisions 7.1.1 Revised dimensions, added ref dwg. 7.1.2 Revised weight from 15,000 to 20,000 lbs. 7.1.3 Added "the existing Glomar Challenger onboard" 7.1.8 Reduced shock loads to 24G's 7.1.9 Added "impact" 7.6 Added "Dynamic Tensioning Equipment" 8.3 Corrected location and cable length 8.6 Added ships electrical power and communication requirements  APPENDIX Revised Sect. 2 and 4 per Geotech recommendations.	1 2 3 3 5 5 5 7 7 8 8 10 10 10 11 12 12 13  -



# GLOBAL MARINE DEVELOPMENT Inc.

Newport Beach, Calif.

## REVISION RECORD

REV	DATE	AUTHORIZATION	CHANGE DESCRIPTION	PAGES AFFECTED			
3	12 NOV 80	R. Wallerstedt <i>R. Wallerstedt</i>	2.0 Added Revised Reference Dwgs	1			
			4.8 New Added Site Weather and Sea Conditions	4-11			
			5.2 Changed Test Time to 4 days. Selected Cement Plug pending borehole logging	12			
			6.3 Added Screwed in plugs	12			
			6.4 Added Improved Description of Termination	14			
			6.6 Revised Completely Data Monitoring	14			
			7.1.5 Added Improved description of Release Actuation	17			
			7.3.5 New Structure Description	18			
			7.3.6 New Size and Weight Definition	18			
			7.7 New STC Description	19			
			10.0 New Support Ship	21			
			4	12 DEC 80	R. Wallerstedt <i>R. Wallerstedt</i>	Reference Added New	1
						6.2 Chgd weight to 3500 lbs	12
6.3 Added power requirements	12						
Fig. 6.1 Revised BIP configuration	13						
6.4 Removed reference to shrinkable coating	14						
6.5 Added Tx rate of 54 K bps	14						
7.5 Add description of A-Frame	19						
7.6 Add description of heave compensator	19						
7.7 Chgd STV van dim. to 8 ft by 8 ft by 14 ft	19						
7.7.5 Change STV power to 12 KW	20						

MSS DEPLOYMENT PROGRAM  
AT-SEA-TEST BASELINE INTERFACE SPECIFICATION

1.0 OBJECTIVES

The objective of this interface specification is to define the performance and interface requirements for the BIP test package, reentry equipment, CHALLENGER equipment and data recording instrumentation for the baseline system demonstration. The test is to be performed at an existing DSDP reentry cone site utilizing the GLOMAR CHALLENGER.

\*2.0 REFERENCE

- 1) MSS At-Sea-Test Plan Synopsis dated revised 12 December 1980
- 2) Reentry Cone Assembly
- 3) GLOMAR CHALLENGER Plans (D-377-A002, -A003 and -A004)
- 4) Reentry Assembly Control Dwg. E-001-A002
- 5) BIP/Reentry Sub with Stinger Control Dwg. A-001-A001
- 6) CHALLENGER MSS At-Sea-Test Interface Drawing - E-001-A012
- 7) BIP Control Drawings 990-53100
- 8) BIP Assembly Drawing 990-53100-0101
- 9) At-Sea-Test Mobilization Plan GMDI RPT-001-004
- 10) MSS (BIP) Test Plan Phase I Geotech date 2 Dec 1980
- 11) MSS At-Sea-Test Operational Procedures GMDI RPT 006-003
- 12) EM Cable Winch Geotech Dwg. 990-53554-0101

### 3.0 TEST OBJECTIVES

The test objectives are to:

- 1) Demonstrate the baseline BIP reentry technique
- 2) Determine impact shock levels
- 3) Provide cable entanglement data for evaluation
- 4) Measure seismic data within a deep sea borehole
- 5) Recover BIP and examine


### 4.0 GENERAL REQUIREMENTS

#### 4.1 Site

Reentry cone site #395A (DSDP leg 45) to be utilized is located at latitude  $22^{\circ}45.35'N$ , at longitude  $46^{\circ}04.90'W$ . Site water depth is approximately 4484 meters deep. The alternate site will be #396B located at  $22^{\circ}55.81'N$ ,  $43^{\circ}30.95'W$  at a water depth of 4450 meters.

#### 4.2 Borehole Characteristics

The existing site #395A borehole has a drilled out diameter of 10 inches to approximately 2178 feet below the seabed. There is a 16 inch diameter by 200 feet conductor casing in the upper unconsolidated sediment area. The central portion of the borehole has been cased down to 360 feet with 11-3/4 inch casing. Refer to Fig. 4.1 for general configuration. The borehole may be caved in and/or filled upto the encased area. There is probably some broken equipment items at the bottom of the borehole.



Schematic of re-entry cone and casing at mud-line Hole 395A.

Fig. 4.1

#### 4.3 Reentry Cone

A standard DSDP reentry cone (Ref. 2) was emplaced and is expected to be in good condition.

#### 4.4 Drilling String

A standard DSDP 5 inch diameter S-135 drilling string is to be utilized. Maximum allowable load (static plus dynamic) is 600,000 lbs.

#### 4.5 Reentry Velocity

The design maximum reentry velocity will be 10 ft/sec. based upon a maximum lowering speed with the Hydromatic brake.

#### 4.6 Pressure

Subsea equipment is to be designed to 10,000 psi pressure capability.

#### 4.7 Operational Criteria

Objective weather and operational criteria are tabulated on Table 4.1.

#### 4.8 Site Weather and Sea Conditions (From Norda Tech. Report 74)

##### 4.8.1 Atmospheric Pressure

Average atmospheric pressure corrected to sea level is 1020-1021 mb. The site lies on the edge of a broad 1020-1022 mb

TABLE 4.1

GLOMAR CHALLENGER

TENTATIVE MSS DEPLOYMENT LIMITS

	<u>SEA STATE</u>	<u>SIGN. WAVE (FT)</u>	<u>WIND SPEED (KNOTS)</u>
HANDLING MODE	5	12	24
DRILLING MODE	6	22	30
REENTRY MODE	4	17	19
POSITIONING	7	?	40
KEELHAULING	3	4	19

ULTIMATE PITCH/ROLL ANGLE  $\pm 9^\circ$

SAFETY PITCH/ROLL ANGLE  $\pm 7^\circ$  (NEW DSDP CRITERIA)

DRILL STRING TENSILE LOAD 600,000 LBS (22,500 FT PIPE STRING - CALM)

MAXIMUM BENDING STRESS (25,000 PSI)

MAXIMUM DYNAMIC AXIAL STRESS (17,000 PSI)

high centered at 28°N, 35°W. On the average, two highs per month pass over the site, and are centered over the site 10% of the time. These highs follow a west-to-east course, no low pressure centers pass within 15° of the site from December to May. No storm tracks or hurricane tracks pass in the vicinity of the site. Storm frequency is well under 5%.

#### 4.8.2 Winds

The site lies 3° north of the average limit of the NE trades. Prevailing winds are NE, Force 4, with 26-50% constancy. Average wind speed is 6 m/sec (11.7 kn). The percentage frequency of winds of Beaufort Force 3 or less is 55%; Beaufort Force 4 or greater is 55%; winds of Beaufort Force 8 or more have a percentage frequency well under 5%.

Average winds are tabulated below:

<u>Direction</u>	<u>% Frequency</u>	<u>Mean Beaufort Force</u>
N	7	3
NE	33	4
E	26	4
SE	9	3
S	7	3
SW	8	3
W	5	Data not given
NW	5	Data not given
Calm	4	----

#### 4.8.3 Air Temperature

The mean sea surface air temperature is between 21.1° - 23.3°C (70°-74°F). Average maximum temperature is 28° (82°F); average minimum temperature is 12°C (54°F). Maximum and minimum air temperatures of record are given as 78°F (25.6°C) and 63°F (17.2°C), respectively. Frequency of temperatures under 0°C (32°F) is under 5%, presumably 0%.

#### 4.8.4 Water Temperature

The mean surface water temperature is 22.2 - 23.6°C (72 - 74.5°F)

#### 4.8.5 Relative Humidity

Relative humidity at the sea surface in March is expected to be 75%.

#### 4.8.6 Precipitation

Frequency of observations reporting precipitation ranges from 5-9%, whereas precipitation frequency has been estimated at less than 1%. In any case, precipitation is infrequent, and presumably occurs as local showers. Of observed precipitation, about 80% is weak and 20% is intense. No solid precipitation has been observed.

#### 4.8.7 Cloudiness

Percentage frequency of total cloud amounts of 2/10 or less is 28%; 2/8 or less, 35%; 5/8 or more, 30%. Percentage frequency of low cloud amounts of 7/8 or less is 98%; 4/8 or less, 80%, 6/10 or more, 20%. Values of 30% for clouded sky frequency and 33% for clear sky for February have also been reported. Frequency of total cloud cover is 4.5%.

Cloudiness is associated with winds from the NE quadrant.

The area is generally partly cloudy.

#### 4.8.8 Visibility

The frequency of visibility over 5 nm (9.26 km) is well over 95%. The frequency of visibility under 2 nm (4.63 km) is less than 0.5%. Fog frequency (visibility under 1 km (0.54 nm)) is estimated from well under 5% to less than 1%.

#### 4.8.9 Tides

The tidal range at the site is about 0.4 m.

#### 4.8.10 Waves

Average wave height is 1.1 m (3.6 ft) and average wave period is 5 sec. Maximum height of waves (highest 1%) is 8 m (26 ft) and maximum average wave period is 12 sec.

Detailed wave data for the 5° square are shown in

Predominant wave direction is from the ENE with wave periods of 6-9 sec predominating. Interpolated wave heights are:

<u>Wave Height Equal or Exceeding</u>	<u>Percentage of All Waves</u>
4 ft	48%
8 ft	11%
12 ft	2%

#### 4.8.11 Sea State

Predominant sea direction is from the NE, with a constancy of 40-60%. Frequency of seas by height is:

<u>Sea Equal or Exceeding</u>	<u>Percent Frequency</u>
5 ft	20 %
8 ft	5%
12 ft	2%
20 ft	1%

Highest seas come from the northeast and east.

#### 4.8.12 Swell

Predominant swell direction is from the NE with less than 40% constancy. Percent frequency of swell greater than 12 ft is 5%. There is a substantial component of swell from the NW.

#### 4.8.13 Currents

Except for surface drift, data on currents at the site are scarce and current conditions must be largely inferred. The following water masses are found at the site:

- 0-500 m Surface water (North Atlantic Central Water)
- 500-1500 m Atlantic Intermediate Water and northern most portion of Antarctic Intermediate Water
- 1500-4500 m North Atlantic Deep and Bottom Water
- <4500 m Antarctic Bottom Water

Depth within a range of  $0.25^\circ$  of the site are about 2900-4500 m. Antarctic Bottom Water would therefore not normally be found at the site. The rugged relief, however, may cause some local fluctuation in the water masses. Currents below 500 m are nonseasonal and the information presented applies to the entire year.

#### 4.8.14 Surface Currents

The site lies within the North Equatorial Current. Current direction is W to WNW; current speeds are 0.25-0.5 kn (13-26 cm/sec), with a constancy of 33-66%. The predominant current to be westward, but significant NW and SW components are present. Resultant currents near the site have been

reported as high as 15-16 nm/day (28-30 km/day). These drift speeds suggest that 1-2 kn (100-200 cm/sec) currents may be expected occasionally, but that currents in excess of 2 kn (200 cm/sec) would be rare and would occur only in association with extreme winds.

#### 4.8.15 Intermediate Currents

Since the site does not lie within a strong oceanic current system, currents are generally sluggish, but subject to short-term fluctuations. Between 100 and 500 m average annual current speeds are less than 10 cm/sec (0.2 kn) to the SW and WSW. Based on transport calculations, long-term average current flow is 1-3 cm/sec northward on the upper west flank of the Mid-Atlantic Ridge at 13° N, 10° S of the site.

Short term fluctuations in current speed may be expected, however. These are caused by passing eddies and by tidal forcing due to the topographic expression of the Mid-Atlantic Ridge. Root-mean-square speeds of 10-15 cm/sec (0.19-0.29 kn) and occasional maximum speeds of 30-40 cm/sec (0.58-0.78 kn) may be expected at the site. Typically, maximum speeds may have durations of several hours and occupy only a portion of the water column.


#### 4.8.16 Bottom Currents

No specific data exist on bottom currents near the site, but some general information can be gained by examining the character of the bottom. Several bottom-photograph stations on the west flank of the Mid-Atlantic Ridge show no evidence of sediment ripples or scour, suggesting that bottom currents over 20 cm/sec (0.39 kn) are uncommon. Seismic profiles in the area show horizontally stratified sediment ponds filling lows, and a thin sediment cover on highs [6], [8]. Similarly, these profiles show no evidence of sediment scour on drifts; thus indicating an absence of strong and continuous bottom currents. The presence of horizontal stratification in the ponds, however, indicates that sediments have slumped or were transported from the highs to the ponds by turbidity currents. Turbidity currents in the sediment ponds would be relatively small but could produce current pulses in excess of 200 cm/sec (4 kn). However, annual turbidity current frequency for a pond is probably around  $10^{-3}$  and thus should not be a problem.

## 5.0 SCHEDULE REQUIREMENTS

### 5.1 Test Period

The test period will be early March 1981.



BRUNST  
WEIGHT  
(BLAST STRIKE)  
1000 LB


PROTECTIVE  
VOLANTS  
(ALUMINE COATED)  
EST. WT. 290 LB. MIN.  
SHIELDING WEIGHT

10 WIRE 28 X 1.750  
CABLE TYPE 6  
1.5 IN. DIA.  
(FOR SHIELDING)

EST. TOTAL WT. 5950 LB.  
(NO CABLE)

NOTE: FOR MORE DETAILS SEE 530-53100-0101

TELETYPE GEOTECH	
NO. (SHEETS)	1
DATE	8/10/78
BY	BIP
PROJECT NO.	D 99019 990-53100
SCALE	AS SHOWN
APPROVED	
DATE	



BIP CABLE DIMENSIONS

UP FRONTAGE OR ON THE MAIN  
WALLS OR UNDER UPWARD

### \*5.2 Test Time

The available time for actual baseline testing is 6 days. The tentative test scenario is now 4 days which does not allow for weather delays or major malfunctions. 24 hours of inhole continuously sampled and recorded seismic data will be obtained. Installation and drill out of a cement plug (estimate at 52 hours) has been deleted pending logging of borehole.

## 6.0 BIP TEST PACKAGE

### \*6.1 Configuration

The BIP test package will be 8 inches diameter maximum by 28 feet 6 inches long. The package will have a spherical shaped bottom nose. Geotech drawing 990-53100 - Fig. 6.1 defines the general outline of the BIP test package. Two screwed in attachment plugs are available for shipboard handling.

### 6.2 Weight

The maximum weight of the test package will be 3500 lbs. This weight includes fairings, pressure vessels and all instrumentation and ballast.

### \*6.3 Power

Input power requirements will be 25 W at 150 VDC.

\*6.4 EM Cable Termination

A water tight termination compatible with an armored coax conductor cable will be utilized. The mechanical connector will be a pinned connection. The electrical connection is a water-tight connection. A sealant will be provided in the termination area.

6.5 The following instruments will be provided in the BIP. (See Appendix A)

- 1) 3 axis shock accelerometer
- 2) 2 short period - vertical seismometers
- 3) State of Health Instrumentation
- 4) Multiplexer  
Data Tx Rate will be 54 K bps.

\*6.6 Data Monitoring

The following BIP data will be real time and mag tape monitored and recorded on the CHALLENGER during deployment.

<u>Parameter</u>	<u>Deployment</u>	<u>Operational</u>
5 channel acceleration	Waveform	-
2 channel SP seismic	-	Waveform
2 pressure	Alphanumeric	Alphanumeric
2 temperature	Alphanumeric	Alphanumeric
2 moisture	Alphanumeric	Alphanumeric
5 power	Alphanumeric	Alphanumeric
Other SOH	Alphanumeric	Alphanumeric

## \*6.7 EM Cable

The BIP EM Cable will be specially constructed 0.692 inch diameter armored coax conductor cable. 34,000 feet are to be provided. This allows for current, station keeping allowance, plus slacking off during data recording. Refer to Table 6.1 for design data.

## 6.8 Shock Capability

The BIP will be capable of surviving 10 G's of shock input along any axis.

## 7.0 DEPLOYMENT EQUIPMENT

### 7.1 BIP Reentry Sub

#### 7.1.1 Configuration

The reentry sub will be an approximate 16 x 27 inch by 68 feet long subassembly. Dwg. E-001-A009 defines the reentry sub.

#### 7.1.2 Weight

The BIP reentry sub plus BIP package and reentry plug will weigh a maximum of 20,000 pounds.

#### 7.1.3 Reentry Tool

The reentry tool will be the existing GLOMAR CHALLENGER on-board sonar reentry tool.

The following measurements are provided:


- 1) Search sonar - max. 500 ft. range - 360° Azimuth
- 2) Azimuth sector
- 3) Short range scanning

TABLE 6.1

A30084. REV. 8

**Descriptions:**

A SUBMARINE TOW CABLE CONSISTING OF (1) #10 AWG COAX WITH AN OVERALL DOUBLE-CAGED ARMOR AND HYTREL JACKET.



**Specifications:**

**ELECTRICAL: NOM CONDUCTOR DC RESISTANCE**

@20°C: #10 AWG: 1.08 OHMS/KFT

COAX RETURN BRAID: 1.40 OHMS/KFT

VOLTAGE RATING: 2,500 VOLTS RMS

CHARACTERISTIC IMPEDANCE: 40 OHMS (REF)

ATTENUATION AT 500 KC: 1.4 DB/KFT

**MECHANICAL: FILLED SHIELD:**


TEMPLUBE BLKNG COMPOUND.

BREAK STRENGTH: 21,000#

WEIGHT IN AIR: 462 #/KFT

WEIGHT IN WATER (SG = 1.027) 295 #/KFT

TORQUE BALANCED DESIGN



#### 7.1.4 BIP

The BIP will be securely attached by a BIP carriage inside the reentry sub.

#### 7.1.5 BIP Release Mechanism

A BIP release mechanism will be provided as part of the reentry sub. The BIP will be released by salt water hydraulic actuation of 2 cylinders. Four shear pins are simultaneously released causing use carriage to move to the reentry sub center release position.

#### 7.1.6 BIP Lowering

The BIP will be guided into the center of reentry sub and lowered into the borehole at a controlled rate not to exceed 20 ft/min. The lowered position is to be monitored.

#### 7.1.7 Drill Pipe Attachment

The reentry sub will attach through a standard tool joint to the 5 inch drill string.

#### 7.1.8 Shock Capability

The reentry sub will be designed to withstand the shock loads during reentry for maximum of 24 G's. In addition, shock isolation for the BIP will be provided to limit shock loading to 10G's.

#### 7.1.9 Data Monitoring

The reentry tool impact data will be monitored and recorded as real time during the reentry.

#### 7.1.10 Cable Interference

The reentry sub will be designed to prevent wear on the EM Cable during lowering and avoid contact during withdrawal.

\*7.2 Sonar Reentry Tool EM Cable (Internal)

7.2.1 Size and Configuration

The sonar reentry tool EM Cable will be a standard Schlumberger 5/8 inch diameter by 7 conductor cable.

7.2.2 Strength

Max cable tensile strength is 21,000 pounds.

\*7.3 BIP EM Cable Winch

7.3.1 Capability

An EM Cable Winch with slip rings will be provided to accommodate 34,000 feet of 0.692 inch coax cable.

7.3.2 Tensioning Capability

A variable constant EM Cable tensioning capability of up to 15,000 pounds is to be provided.

7.3.3 Payout Capability

A variable speed payout capability up to 20 feet per second is to be provided.

7.3.4 Monitoring

Cable tension, payout speed and length is to be recorded.

7.3.5 Structure Mounting

The winch 8 x 6 steel tubing frame will be welded directly to the special ship mounted foundation piece.

7.3.6 Size and Weight

The EM Cable Winch will be approximately 110 inches high , 91 inches wide with an overall length of 232 inches. A clearance of 30 inches on the right hand side is required for slip rings and hydraulic motor. It will weigh an approximate 38,000 lbs loaded with wire.

#### 7.4 Lowering Cable (External)

Deleted

#### 7.5 Overside A Frame Structure

##### 7.5.1 Size and Configuration

A removable 28 foot long cantilevered A Frame extends approximately 18 foot over the Port side. The A-Frame is rated for 20,000 pound load. The A-Frame is supported off the casing rack and subbase structure and by a center mounted heave compensator.

##### 7.5.2 Deployment

The A-Frame is to be deployed overside during the test.

#### 7.6 Dynamic Tensioning Equipment

##### 7.6.1 Description

A static heave compensation system will be attached to the cantilevered A-Frame to reduce the dynamic EM cable loading.

##### 7.6.2 Equipment

A refurbished air/oil guideline tensioner will be utilized to provide a variable stroke support to the A-Frame. The 5 inch dia by 6 foot stroke tensioner is rated at 64,000 lbs. A 60 cubic foot accumulator will be utilized. Four nitrogen bottles will be provided. A manifold console will be provided.

##### 7.6.3 Operation

An approximate mid position will be established by the normal static loading condition and gas pressurization levels.

Increased/decreased dynamic loadings will lower/raise the A-Frame end position thereby momentarily effectively paying out or pulling in more cable.

## 7.7 Shipboard Test Console (STC)

### \*7.7.1 Size and Weight

The STC will be 8 feet by 8 feet by 14 feet. It will weigh an estimated 9000 lbs loaded.

### 7.7.2 Shipboard Mounting

The STC shall be capable of being either bolted or welded to the deck foundation frame.

### 7.7.3 Construction

The STC shall be constructed so as to be completely water tight. All inside and outside wall, ceiling and floor spares shall be metal or high strength glass. Interior walls and/or components shall be constructed of fire proof material.

### \*7.7.4 Electrical Interface

The STC to ship electrical interface shall include the following interface signals.

- a) STC Input Power
- b) Voice Communications
- c) Universal Standard Time (WWV) Signal

### \*7.7.5 STC Input Power

The input power capability will be 60 cycle 12 KW 208 VAC, 3 Phase, 4 wire WYE connected with safety ground.

## 8.0 CHALLENGER MODIFICATION

### 8.1 General Requirements

The below defined equipments installation are to be quickly accomplished in Port and must be capable of being retrofitted to original condition.

8.2 Reentry Tool Console

Deleted

8.3 EM Cable Winch (External)

Install on main deck area a new 34,000 feet diesel powered EM cable winch assembly.

8.4 A Frame

Install an approximate 10 ton outside A-Frame deployable structure amidships on the Port side.

8.5 Lowering Cable Winch

Deleted

\*8.6 BIP Data Console Van

Install a real time data log and recorder van. Provide 12 KVA, 220/440V 3 phase, 60 Hz ships power to van. Also connect to ship's communication network.

8.7 BIP

A horizontal rack for 2 BIP units will be provided in the casing rack area.

8.8 Reentry Sub

A rack for 2 reentry subs will be provided.

9.0 AUXILIARY MEASUREMENT

9.1 Current Meter Array

A 1000 meter depth capability current meter, will be deployed from the support ship during the reentry tests. Current data will be provided, to GLOMAR CHALLENGER via radiotelephone from the support ship.

9.2 OBS

Two OBS (Ocean Bottom Seismic) package will be launched during the test and recovery by the support ship.

10.0 SUPPORT SHIP

10.1 Name and Type

The USS Bartlett, an AGOR type research vessel has been committed as the support ship.

APPENDIX C

MSS AT-SEA-TEST OPERATIONAL PROCEDURES

RPT-006-003  
REV-2  
FEB. 80

MARINE SEISMIC SYSTEM  
AT-SEA-TEST  
OPERATIONAL PROCEDURES



TABLE OF CONTENTS

1.0	Pre-Operational Checks
2.0	Scientific Testing
3.0	Deployment Procedure
4.0	Reentry Procedure
5.0	BIP Release Procedure
6.0	Seismic Test Procedure
7.0	Recover BIP
8.0	Disentanglement Procedure
9.0	Dual Ship Procedure
10.0	Operating Instructions for the A-Frame Heave Compensator

1.0 PRE-OPERATIONAL CHECKS

1.1 EM WINCH PRE-CHECKOUT (DOCKSIDE)

.1 Steps

- Rig up EM Cable through A-Frame over A-Frame block.
- Hookup weight 4,000 lbs to EM Cable.
- Set HC at midposition (refer to Section 10).
- Lift weight approximately 5 ft and hold 5 minutes.
- Calibrate load sensors and cable payout counter.
- Repeat above with 7,000 and 10,000 lb weights.
- Hookup 15,000 weight and lift slightly and set tension relief setting.

.2 Responsibility - GMDI

- EM Winch Operator
- Rig Crew
- Shipyard Crane Operator

.3 Operational Restrictions

.4 Precautions/Hazards

- Maintain EM Cable loading to below 12,000 lbs except during final relief setting.

.5 Special Equipment

- 4,000, 7,000, 10,000 (approx.) and 15,000 lb weights
- Weight terminal connection to EM Cable (Geotech)




FIGURE 1-2. EM WINCH PRE-CHECKOUT

1.2 EM WINCH PRE-CHECKOUT

.1 Steps

- Rig up EM Cable through A-Frame over A-Frame block.
- Hookup known weight to EM Cable termination.
- Set HC at midposition.
- Payout and take in at minimum and maximum speeds.
- Check calibration of load sensors and cable payout counter.

.2 Responsibility - GMDI

- EM Winch Operator
- Rig Crew
- Crane Operator

.3 Operational Restrictions

.4 Precautions/Hazards

- Maintain EM Cable loading to below 12,000 lbs.

.5 Special Equipment

- Known shipboard weight
- Weight terminal connection to EM Cable (Geotech)




FIGURE 1-3. EM CABLE CIRCUITRY PRE-CHECK

1.3 EM CABLE CIRCUITRY PRE-CHECKOUT

.1 Steps

- Rig EM Cable through A-Frame and pull cable to reach BIP where stored.
- Connect EM Cable to BIP.
- Install interconnecting Cable between EM Winch slip rings and STC Van.
- Check all signals per Teledyne Geotech Test Plan.

.2 Responsibility - Geotech

- STC Van Operator
- Rig Crew
- EM Winch Operator

.3 Operational Restrictions

.4 Precautions/Hazards

.5 Special Equipment

- EM Interconnecting Cable
- EM Cable Winch
- STC Van
- BIP

INTENTIONALLY LEFT BLANK

1.4 REENTRY SUB RELEASE DEMONSTRATION

.1 Steps

- Install hydraulic plug adaptor and Baker tool in control sub.
- Install special hydraulic sub/handling fixture on reentry control sub.
- Set reentry sub (without stinger) vertically on main deck and support off adjacent structure.
- Connect up EM Cable to BIP and check circuitry.
- Raise BIP using crane and guide into reentry sub.
- Set release pins.
- Set carpenter's clamp on EM Cable to restrict vertical fall.
- Attach Koomey pump.
- Pressurize SW hydraulics to 2200 psi and actuate release.
- Pressurize SW hydraulics to 2800 psi and actuate gate release.
- Lower reentry sub, disassemble, and remove BIP.

.2 Responsibility - GMDI

- Rig Crew
- Van Operator

.3 Operational Restrictions

.4 Precautions/Hazards

- Pressurized system of 2800 psi
- Safe handling of BIP

.5 Special Equipment

- Hydraulic Sub/Handling Fixture
- Koomey Pump

INTENTIONALLY LEFT BLANK

2.0 SCIENTIFIC TESTING

2.1 PROCEDURES

- No specific MSS procedures involved.




FIGURE 3-1 PREPARING RIG FLOOR

*more check pieces stinger  
control sub*

3.0 DEPLOYMENT PROCEDURE

3.1 PREPARING RIG FLOOR

.1 Steps

- Move reentry tool stinger, BIP carriage housing, control sub and hydraulic plug to rig floor.
- Move BIP with cradle to ramp area.
- Assemble hydraulic plug in stinger.
- Assemble control sub and carriage housing with drill collar handling sub.
- Tack weld bolts.

.2 Responsibility - GMDI

- Crane Operator
- Rig Crew

.3 Operational Restrictions

- Sea State 4

.4 Precautions/Hazard

- Avoid slamming items into structure.

.5 Special Equipment

- Slings
- Reentry Subassembly, GMDI E-001-A001, E-001-A009
- BIP
- Tag Lines
- Drill Collar Handling Sub




FIGURE 3-2 KEELHAUL EM CABLE

## 3.2 KEELHAUL EM CABLE

### .1 Steps

- Attach tag line to EM Cable watertight connector.
- Payout EM Cable 200 ft.
- Pull EM Cable through horn.
- Place cable protector within horn.
- Lead EM Cable through derrick mounted sheave.

### .2 Responsibility

- EM Winch Operator
- Rig Crew

### .3 Operational Restrictions

- Sea State 4

### .4 Precautions/Hazards

- Keep terminal connector dry.
- Keep cable in protector.
- Keep enough tension to maintain cable away from thrusters and propellers.
- Try to minimize cable rubbing on bilge keel and guide hornlip.

### .5 Special Equipment

- Tag Line
- EM Cable Winch
- A-Frame
- Derrick Sheave
- Cable Protector, GMDI E-001-A013, E-001-A014
- Cable Pull Assembly, Geotech 990-53574-0101




FIGURE 3-3 SET REENTRY SUB ON RIG FLOOR

3.3 SET REENTRY SUB ON RIG FLOOR

.1 Steps

- Install stinger in slips on rotary table.
- Insure EM Cable is protected in stinger slot, use tape to secure.
- Install handling sub on carriage control sub.
- Move carriage to rig floor and vertically erect on stinger and bolt up.
- Tack weld bolts.

.2 Responsibility - GMDC/GMDI

- Crane Operator
- Rig Crew

.3 Operational Restrictions

- Sea State 4

.4 Precautions/Hazards

- Avoid slamming reentry sub into steel structure.

.5 Special Equipment

- Reentry Sub Handling Sling, GMDI D-001-A031
- Carriage Control Sub, GMDI E-001-A008
- SW Hydraulic Test Pump
- Tag Lines
- Drill Collar Handling Sub
- 12" Casing Slips
- Stinger/Slips Adaptor, GMDI D-001-A033




FIGURE 3-4 MOVE BIP TO RIG FLOOR

3.4 MOVE BIP TO RIG FLOOR

.1 Steps

- BIP is in shipping fixture and on pipe ramp.
- Remove covers and install lifting lug.
- Make up mechanical EM Cable attachment.
- Install EM Cable grip near sheave.
- Attach BIP ballast weight.

.2 Responsibility - GMDC/Geotech

- EM Winch Operator
- Crane Operator
- Rig Crew

.3 Operational Restrictions

- Sea State 4

.4 Precautions/Hazards

- Prevent BIP from slamming into steel structure.

.5 Special Equipment

- BIP Shipping Fixture
- BIP Weight
- EM Cable Grip
- Lifting Sub
- BIP Handling T-bar, GMDI D-001-A032

INTENTIONALLY LEFT BLANK

3.5 ATTACH EM CABLE TO BIP

.1 Steps

- Make up electrical EM Cable connection.
- Apply sealant.
- Test BIP through STC Van.
- Attach BIP handling strap.

.2 Responsibility - Geotech

- Rig Crew
- STC Van Operator

.3 Operational Restrictions

- Sea State 4

.4 Precautions/Hazards

- No hard handling of BIP.

.5 Special Equipment

- Sealant (Geotech)
- BIP Handling Strap




FIGURE 3-6 ERECT AND INSTALL BIP

3.6 ERECT & INSTALL BIP

.1 Steps

- Remove steel transit pins from shear pin holes.
- Lift BIP from horizontal position & erect vertically using crane and tuggers.
- Transfer BIP load to EM Cable support sheave.
- Using tugger, raise BIP 50 ft and guide into reentry sub (refer to sequence diagram).
- Position reentry sub carriage slide and install shear pins.
- Tighten reentry sub release cable tension.
- Test BIP through STC Van.

.2 Responsibility - GMDC/GEOTECH/GMDI

- Crane Operator
- Rig Crew
- STC Van Operator

.3 Operational Restrictions

- Sea State 4

.4 Precaution/Hazards

- Prevent BIP from slamming into steel structure.
- Do not damage EM Cable with high side loads.

.5 Special Equipment

- Shear Pins, Aluminum with Milled Flats
- Carriage Cable Adjustment Tool
- BIP T-bar, GMDI D-001-A032




FIGURE 3-7 MAKE-UP LOWER REENTRY ASSEMBLY

3.7 MAKE UP LOWER REENTRY ASSEMBLY

.1 Steps

- Lower Carriage Control Sub top to rig floor level.
- Remove EM Cable from sheave.
- Work EM Cable down through rotary table.
- Set slips and safety clamp.
- Make up lower downhole assembly to reentry sub.
- Lower reentry sub to main deck area.
- Install upper section of hydraulic tubing.
- Orient drill string.

.2 Responsibility - GMDC

- Normal Rig Crew
- EM Cable Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 3

.4 Precautions/Hazards

.5 Special Equipment

- 12" Casing Slips (for Control Sub)
- Safety Clamp
- Lowering Line




FIGURE 3-8 MAKE-UP UPPER REENTRY ASSEMBLY

3.8 MAKE UP UPPER REENTRY ASSEMBLY

.1 Steps

- Add Drill Collars and Bumper subs (see Ref. Dwg. E-001-A002).
- Lower reentry sub below horn.
- Secure drill collar to one side of horn.
- Remove EM Cable protector.
- Lower downhole assembly approx. 300 ft.
- Work EM Cable loop down through horn using soft line.
- Establish lbs tension loading on EM Cable winch (refer to separate EM Cable/HC Instructions).
- Check BIP signals.
- Set orientation for reentry sub.

.2 Responsibility - GMDC

- Rig Crew
- EM Cable Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 3

.4 Precautions/Hazards

- Keep cable away from thruster and screws.
- Limit side loading on EM Cable termination.

.5 Special Equipment





FIGURE 3-9 DEPLOY DRILL STRING

3.9 DEPLOY DRILL STRING TO NEAR BOTTOM

.1 Steps

- Set A-Frame HC at midposition.
- Make up and lower standard drill string sections.
- Orient pipe string at each stand using stoking tool.
- Deploy 14,650 ft of 5" drill string, including 340 ft (Bumper subs are open when lowering) of downhole assembly.
- Reentry assembly using normal procedures, and maintaining string orientation.
- Install upper horn sections (if required).
- Maintain cable tension at BIP equivalent to 1,000 lbs (see EM Winch/HC Instructions).

.2 Responsibility - GMDI

- Normal Rig Crew
- EM Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 5

.4 Precautions/Hazards

- Maintain alignment of drill string.
- Do not allow cable tension to exceed 3,000 lbs at BIP.

.5 Special Equipment

- Stoking Tool




FIGURE 3-10 POSITION DRILL STRING ABOVE REENTRY CONE

3.10 POSITION DRILL STRING ABOVE REENTRY CONE

.1 Steps

- Establish stinger altitude above cone at objective 15 ft above cone.
- Add drill string heave compensator (tentative).
- Prepare upper drill string for sonar reentry.
- Lower sonar reentry tool down to stinger position over reentry cone in accordance with standard procedures.
- Prepare to stab 60 ft.
- Maintain cable tension at BIP equivalent to 1,000 lbs.

.2 Responsibility - GMDC

- Normal Rig Crew
- EM Cable Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 5

.4 Precautions/Hazards

.5 Special Equipment

- Sonar Reentry Tool




FIGURE 4-1 INITIAL REENTRY STABBING

4.0 REENTRY PROCEDURE

4.1 PERFORM INITIAL REENTRY STABBING

.1 Steps

- Reduce EM Cable tension applicable to 500 lbs at BIP.
- Lower DP 60 ft and stab into reentry cone (quickly accelerate to 6 ft per second and then slowly decelerate).
- During reentry, observe payout of EM Cable.
- Record impact forces.
- Maintain hook load 30,000 lbs\* lighter after reentry than before reentry.
- Raise and lower 10 ft to verify partial transfer of load to reentry cone.
- Increase EM Cable tension to 1,500 lbs at BIP.

.2 Responsibility - GMDC

- Rig Crew
- EM Winch Operator
- STC Van Operator
- Reentry Technician

.3 Operational Restrictions

- Sea State 3
- Max stabbing velocity of 10 FPS.
- Max unloading of drill string 50,000 lbs.

.4 Precautions/Hazards

- Maintain minimum tension on EM Cable as defined by operating instructions.
- Initial altitude above seafloor should be 40 ft.
- Minimum hook load of            lbs. should be maintained.

.5 Special Equipment

\*This may be modified dependent on weather and specific configuration.




FIGURE 4-2 MULTIPLE REENTRY STABBING

4.2 PERFORM MULTIPLE REENTRY STABBINGS

.1 Steps

- Raise drill string 60 ft.
- Perform stabbing operations (4.1) in accordance with the noted criteria.
- Test 2: \*Repeat initial reentry stab-in with CHALLENGER maintaining position over cone.
- Test 3: \*Repeat Test 2 but from objective 10 ft above cone.
- Test 4: \*Repeat reentry from 20 ft above cone.
- Test 5: Repeat reentry as directed.

.2 Responsibility - GMDC

- Rig Crew
- EM Cable Winch Operator
- STC Van Operator
- Reentry Technician

.3 Operational Restrictions

- Sea State 5

.4 Precautions/Hazards

.5 Special Equipment

- EM Cable Winch

\*Tests objectives may be changed as a result of impact data.




FIGURE 5-1 RELEASE BIP

5.0 BIP RELEASE PROCEDURE

5.1 PERFORMING BIP RELEASE

.1 Steps

- Remove reentry sonar tool.
- Lower Baker Lock subassembly with Otis GS running tool.
- Jar in and lock Baker tool to adaptor plug.
- Raise hydraulic plug to carriage control sub.
- Verify that lock ring has engaged.
- Release Otis tool by jarring down hard and retrieve.
- Attach cement unit to DP tee crossover.
- Set EM Cable winch tension to 3,000 lbs. tension at BIP.
- Pressurize drill pipe to 2300 psi to actuate release hydraulic cylinders.

.2 Responsibility - GMDC

- EM Winch Operator
- STC Van Operator
- Rig Crew

.3 Operational Restrictions

- Sea State 3

.4 Precautions/Hazards

.5 Special Equipment

- Baker "K" Lock Subassembly
- Baker Special Probe
- Otis "4" pulling tool
- Otis Wire Line Stuffing Box with Tee Crossover to DP
- Koomey Test Unit (backup)
- Jarring Tool




FIGURE 5-2 LOWER BIP INTO BOREHOLE

5.2 LOWER BIP INTO BOREHOLE

.1 Steps

- EM Cable should slowly payout.
- Reduce tension to minimum 500 lbs. at BIP in 250 lb stages.
- When cable starts to payout, set tension to neutralize payout.
- Reduce tension by 500 lbs and lower BIP to borehole bottom (2,200 ft) and record time.
- Increase tension to start raising BIP and bring up 100 ft.
- Reduce tension by 1,000 lbs and lower to bottom and record time.
- Increase tension and raise BIP to 100 ft.
- Reduce tension by 2,000 lbs and lower to bottom and record time.

.2 Responsibility - GMDC

- EM Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 5

.4 Precautions/Hazards

- Cable entanglement
- BIP binding in stinger

.5 Special Equipment




FIGURE 5-3 DISENGAGE EM CABLE

### 5.3 DISENGAGE EM CABLE

#### .1 Steps

- Set EM Cable winch tension to 500 lbs at BIP.
- Observe any change in EM Cable tension or payout/takein during operation.
- Establish ship position over borehole.
- Rotate ship/drill string to orient reentry sub groove downstream (if necessary).
- Raise drill string quickly 90 ft.
- Raise hydraulic pressure to 3000 psi to release hydraulic gate.
- Rotate pipe string 180° in both directions.
- Position vessel 500 ft upstream of borehole.
- Repeat above rotation 360° in both directions, if tension increases or payout was indicated.
- Watch fleet angle of EM Cable.

#### .2 Responsibility - GMDC

- Rig Crew
- Ship's Crew
- EM Winch Operator
- STC Van Operator

#### .3 Operational Restrictions

- Sea State 4

#### .4 Precautions/Hazards

- Limit EM Cable tension load to 15,000 lbs.
- Maintain EM Cable away from thrusters and screws.

#### .5 Special Equipment

- EM Cable Winch




FIGURE 5-4 RECOVER DRILL STRING AND REENTRY SUB

5.4 RECOVER DRILL STRING & REENTRY SUB

.1

Steps

- Maintain CHALLENGER 500 ft upstream of borehole.
- Maintain EM Cable winch tension applicable to water depth.
- Recover pipe string under normal procedures.
- Raise reentry sub to drill rig floor.
- Attach handling sling to reentry sub.
- Remove stinger and move to casing rack.
- Move reentry sub to casing rack.

.2

Responsibility - GMDC

- Rig Crew
- Ship's Crew
- EM Winch Operator
- STC Van Operator

.3

Operational Restrictions

- Sea State 4

.4

Precautions/Hazards

- Limit EM Cable load to water depth weight of cable.

.5

Special Equipment

- Reentry Sub Handling Equipment




FIGURE 6-1 VESSEL MOVING TO TEST STATION

6.0 SEISMIC TEST PROCEDURES

6.1 VESSEL MOVING TO TEST STATION

.1 Steps

- Move CHALLENGER downstream 3,000 ft from borehole maintaining general orientation into wind & weather.
- Maintain EM Cable tension applicable to 0 lbs at ocean floor (refer to EM Cable/HC detail instructions).

.2 Responsibility - GMDC

- Ship's Crew
- EM Winch Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 6

.4 Precautions/Hazards

- Maintain cable away from thruster and screws.

.5 Special Equipment

- Drop a new ASK Beacon (if necessary).




FIGURE 6-2 PERFORM SEISMIC TESTS

6.2 PERFORM SEISMIC TESTS

.1 Steps

- Release 2 OBS units 250 & 500 meters away from bore-hole.
- Record background noise for 4 hours.
- \*Perform air gun tests for 4 hours using USS BARTLETT.
- Perform slant range detonation tests for 5 hours using USS BARTLETT.
- Run silent ship operation (turn off thrusters & screws) for 15 minutes.
- Record background noise for 8 hours.

.2 Responsibility - GMDC/NORDA

- Ship's Crew
- EM Winch Operator
- STC Van Operator
- Navy AGOR Vessel

.3 Operational Restrictions

- Sea State 6
- Maintain minimum 2,000 ft between ships.

.4 Precautions/Hazards

- Use of high explosive detonations

.5 Special Equipment

- USS BARTLETT (AGOR) Support Ship

\*Specific test sequence may change.




FIGURE 7-1 REMOVE SIP FROM BOREHOLE

7.0 RECOVER BIP FORM BOREHOLE

7.1 REPOSITION VESSEL & RETRIEVE CABLE

.1 Steps

- Position CHALLENGER over borehole.
- Slowly increase EM Winch tensioning loading until equivalent BIP tension of 2,500 lbs is established.
- Slowly increase the EM Winch tensioning loading until an equivalent BIP tension of 3,000 lbs is established. Constant cable take-up speed should be observed.
- Slowly take up approx. 2,500 ft of cable.
- Set take-up speed at 200 FPM.
- With every 1,000 ft. of cable take-up, the EM Winch tensioning load should be decreased to maintain an equivalent BIP tension of 3,500-4,000 lbs.
- As BIP reaches surface, EM Winch tensioning load should be reduced to 3,500 lbs.

.2 Responsibility - GMDC

- EM Winch Operator
- Crane Operator
- STC Van Operator

.3 Operational Restrictions

- Sea State 6

.4 Precautions/Hazards

- Limit take-up speed to 200 FPM.

.5 Special Equipment




FIGURE 7-2 RETRIEVE BIP ONBOARD

7.2 RETRIEVE BIP ONBOARD

.1 Steps

- Attach tag line and bring BIP close alongside.
- Attach sling to BIP.
- Lift BIP with crane and place in shipping fixture located on casing rack.
- Release EM Cable mechanical and electrical connections.
- Pull in EM Cable to winch.
- Dismantle A-Frame.

.2 Responsibility - GMDC

- EM Winch Operator
- Crane Operator
- Rig Crew

.3 Operational Restrictions

- Sea State 5

.4 Precautions/Hazards

- Maintain cable away from thrusters and screws.
- Limit take-up speed to 200 FPM.

.5 Special Equipment

- BIP Handling Sling
- Crane

INTENTIONALLY LEFT BLANK

8.0 CABLE DISENTANGLEMENT PROCEDURE

- .1 Cable Entanglement can be potentially indicated by:
  - Negative fleet angle of EM Cable toward ship
  - High relative dynamic cable loads
  - Failure of BIP to lower into borehole
- .2 If the cable is entangled around the drill string it probably is either:
  - A single wrap caught up on an obstruction.
  - Wrapped two or three revolutions near the top and the bottom with a large "D" loop streaming in between.
  - A few wraps near the center with reverse belly of "D" adjacent to pipe.
- .3 First, bring cable tension to normal and compare cable counter and load cell readings. Mark Cable.
- .4 Tighten cable tension in 500 lbs increments upto 12,000 lbs (if not released) or 8500 lbs (after release) and record static plus dynamic loads and compare with earlier data. If entangled there will be only a minimal cable take in. Watch for sudden load reduction and/or BIP motion denoting cable disentanglement. Return to normal loading.
- .5 Raise drill string slightly to lift reentry off of landing position.
- .6 Marking initial position, rotate drill string slowly clockwise 1 revolution then counter clockwise 2 revolutions and then clockwise 1 revolution back to initial position.
- .7 A slow rotation of the Ship could also be considered at this point.
- .8 Decision point as to whether to retrieve pipe string and disentangle while raising or to proceed positioned in borehole.

- .9 Mark initial position, rotate slowly drill string for upto 3 complete revolutions in expected directional rotation of entanglement. Upper cable tension should slowly increase with subsequent slow payout. This step unwrap the bottom wraps only to enable the BIP to be partially lowered.
- .10 Proceed with normal cable release procedure but maintaining ship above reentry cone.
- .11 Rotate drill string in opposite direction to the initial position plus up to 3 revolutions which should unwrap the upper wraps and result in a completed lowering of BIP.
- .12. At this time raise pipe string noting whether cable payout remains constant or reduced. indicating entanglement.
- .13 If entangled raise pipe string until problem can be observed by special MSS subsurface TV system.

9.0

MARINE SEISMIC SYSTEM DEPLOYMENT PROCEDURE  
FOR RUNNING FAIRLEADER ON EM CABLE

These procedures are to be employed when it appears that there is the potential for a cable entanglement problem with the drill string, or in case of suspected entanglement, to assist in disentangling the EM cable from the drill string. These conditions are apt to appear when the EM cable is being deployed up current from the drill string. These procedures assume that the current is more or less uni-directional and varies approximately linearly from surface current velocity to zero at the bottom (15,000 ft deep).

Two procedures are provided. The first, Procedure A, is to be used for the case where the drill string, BIP and EM cable are already at or near the 15,000 ft depth. The second, Procedure B, is to be used when the drill string and BIP deployment are being initiated and at a shallow depth (less than 1,000 ft from the surface).

CONCEPT OF ELIMINATING CABLE ENTANGLEMENT PROBLEM




FIGURE 9-1

9.1 DEPLOYMENT PROCEDURE A - DRILL STRING & EM CABLE  
FULLY DEPLOYED

- .1 CHALLENGER rigs fairleader on EM Cable and supports fairleader on tag line over the A-Frame.
- .2 CHALLENGER rigs acoustic release to fairleader and attaches 50 ft and 300 ft nylon pendants end to end to acoustic release. Nylon pendants stored on deck with free end available.
- .3 USS BARTLETT prepares ballast weight assembly with 1/2 inch diameter wire over stern A-Frame.
- .4 BARTLETT sends messenger line to CHALLENGER.
- .5 BARTLETT takes position 350 ft up current from CHALLENGER A-Frame.
- .6 BARTLETT recovers messenger and 350 ft nylon pendants and couples to 50 ft nylon pendant from ballast weight.
- .7 BARTLETT lowers ballast weight 50 ft keeping slight tension in nylon pendant.
- .8 CHALLENGER lowers fairleader to the water surface and then releases it. Fairleader sinks slowly, being slightly negatively buoyant.
- .9 BARTLETT moves up current until wire tension increases by approximately 150 lbs (valid for 1 ft surface current). The objective is to maintain the ballast weight wire tension fleet angle between  $10^{\circ}$  and  $30^{\circ}$ .
- .10 CHALLENGER checks EM Cable tension and vertical flute angle. Tension should not go up and angle should be nearly vertical.
- .11 BARTLETT moves in 50 ft increments until CHALLENGER observes the EM Cable fleet angle to be  $0^{\circ}$  to  $10^{\circ}$  away from side with respect to vertical.
- .12 BARTLETT pays out 950 ft of wire and moves up current 300 ft concurrently.

- .13 Repeat steps 10 and 11 as required.
- .14 BARTLETT pays out 1,100 ft of wire and moves up current 400 ft concurrently. Total 2,100 ft wire payed out. Repeat steps 10 and 11 as required.
- .15 Repeat step 14 for total of 3,200 ft wire payed out.
- .16 Further direction at this step may be given by CHALLENGER.
- .17 BARTLETT maintains final position  $\pm$ 100 ft from CHALLENGER A-Frame.
- .18 CHALLENGER maintains watch on cable tension and vertical flute angle and notifies BARTLETT of any changes. Repeat steps 11 and 18 as required.
- .19 CHALLENGER actuates release on:
- Emergency order of Captain of CHALLENGER or USS BARTLETT.
  - Conclusion of test.
  - Preparatory to stab and lowering of BIP into hole.
  - Change in current direction negating need for assist.

9.2 DEPLOYMENT PROCEDURE B - DRILL STRING & EM CABLE PARTIALLY DEPLOYED AT SHALLOW DEPTH

- .1 Drill string and EM Cable deployed at approximately 1,000 ft.
- .2 CHALLENGER rigs fairleader on EM Cable and supports fairleader on tag line over the A-Frame.
- .3 CHALLENGER rigs acoustic release to fairleader and attaches 50' and 300' nylon pendants end to end to acoustic release. Nylon pendants stored on deck with free end available.
- .4 U.S.S. BARTLETT prepares ballast weight assembly with 1/2" diameter wire over stern A-Frame.
- .5 BARTLETT sends messenger line to CHALLENGER.
- .6 BARTLETT takes position 350' up current from CHALLENGER A-Frame.
- .7 BARTLETT recovers messenger and 350' nylon pendants and couples to 50' nylon pendant from ballast weight.
- .8 BARTLETT lowers ballast weight 50', keeping slight tension in nylon pendant.
- .9 CHALLENGER lowers fairleader to the water surface and then releases it. Fairleader sinks slowly, being slightly negatively buoyant.
- .10 BARTLETT moves up current until a slight wire tension increased is noted 150 lbs (valid for 1 kt surface current). The objective is to maintain ballast weight wire cable fleet angle between 10° and 30°.
- .11 CHALLENGER checks EM Cable tension and vertical fleet angle. Tension should not go up and angle should be nearly vertical.

- .12 BARTLETT moves in 50 ft increments until CHALLENGER observes the EM Cable fleet angle to be  $0^{\circ}$  to  $10^{\circ}$  with respect to vertical.
- .13 BARTLETT pays out 450 ft of wire to total 500 ft and moves up current 150 ft concurrently.
- .14 Repeat steps 11 and 12.
- .15 CHALLENGER runs 1,000 ft of drill string and EM Cable to give total of 2,000 ft.
- .16 BARTLETT pay out 500 ft of wire to total 1,000 ft and moves up to current 150 ft.
- .17 Repeat steps 11 and 12.
- .18 Repeat step 15 to total 3,000 ft.
- .19 Repeat step 16 to total 1,500 ft.
- .20 Repeat steps 11 and 12.
- .21 CHALLENGER runs 2,000 ft of drill string and EM Cable to give total of 5,000 ft.
- .22 Repeat step 16 to give total 2,000 ft.
- .23 Repeat steps 11 and 12.
- .24 CHALLENGER runs 5,000 ft of drill string and EM Cable to give total of 10,000 ft.
- .25 BARTLETT pays out 1,200 ft of wire to give 3,200 ft total.
- .26 Repeat steps 11 and 12.
- .27 Further direction may be given at this step from CHALLENGER.
- .28 BARTLETT maintains final position  $\pm 100$  ft from CHALLENGER A-Frame.
- .29 CHALLENGER maintains watch on cable tension and vertical fleet angle and notifies Bartlett of any changes. Repeat steps 12 and 29 as required.

.30 CHALLENGER actuates release on:

- Emergency order of Captain of CHALLENGER or USS BARTLETT.
- Conclusion of test.
- Preparatory to stab and lowering of BIP into hole.
- Change in current direction negating need for assist.

INTENTIONALLY LEFT BLANK

## 10.0 OPERATING INSTRUCTIONS FOR THE A-FRAME HEAVE COMPENSATOR

### SECTION 1 - SAFETY PRECAUTIONS

Because of high pressures involved in the MSS Heave Compensator system, the following safety precautions should be observed.

- All personnel associated with the operation and maintenance of the equipment must be familiar with the safe operation of the system, and all safety devices must be maintained in proper working order.

Because the following safety precautions apply only to normal operating conditions, supervisors or others in authority may find it necessary to issue supplementary or special precautions to cover local conditions and unusual circumstances. Furthermore, conditions not covered by these safety precautions may arise, which in the opinion of the supervisor may render further operation of the equipment unsafe. Under these conditions, none of the following safety precautions are to be construed as an authorization for such further operation.

The operator shall be familiar with all personnel and equipment safety precautions before attempting to operate the equipment. Authorized personnel only shall be permitted to operate the control panel.


#### HYDRAULIC SAFETY PRECAUTIONS:

- Always verify that line pressure is zero before disconnecting hydraulic lines.
- Never torque leaking connections or fittings while lines are pressurized. Application of torque to fitting or connections while lines are pressurized may rupture lines and result in injury to personnel.
- Mop up spilled hydraulic fluid immediately. Investigate and correct the cause of any leakage of hydraulic fluid.
- If clothing becomes drenched with hydraulic fluid, change immediately to dry clothing, prolonged contact with hydraulic fluid is injurious to health.

2 KNOT CURRENT DOUBLE BULLWHEEL WINCH

<u>DEPLOYED DRILL STRING LENGTH(FT)</u>	<u>*HEAVE COMPENSATOR GAS PRESSURE(PSI)</u>	<u>AVERAGE LOAD CELL GAGE READING(LBS)</u>
2000	350	2700
4000	500	4400
6000	640	6000
8000	790	8000
10000	930	9600
12000	1080	11400
14000	1220	13000
16000	1360	14800
18000	1500	16400
20000	1640	18000

\*THE FORCE EXERTED BY THE HEAVE COMPENSATOR = THE GAS PRESSURE X THE PISTON AREA ( $\pi/4 \times 6^2$ ),  
THESE VALUES ARE FOR ASSUMING THAT THE CABLE LENGTH IS EQUAL TO 110% OF THE LENGTH OF DRILL PIPE DEPLOYED.



DIAGRAMMATIC OF MSS HEAVE COMPENSATOR SYSTEM

SK: M.P. 1-1-14 '81

PNEUMATIC SAFETY PRECAUTIONS:

- Always verify that line pressure is zero before disconnecting pneumatic lines.
- Never torque leaking connections or fittings while lines are pressurized. Application of torque to fittings or connections while lines are pressurized may rupture lines and result in injury to personnel.
- WARNING - DIRECT DISCHARGE OF HIGH PRESSURE AIR OR GAS CAN SERIOUSLY INJURE NOT ONLY SENSITIVE AREAS SUCH AS EYES AND EAR DRUMS BUT ALSO THROW AN ARM AND HAND WITH GREAT FORCE AGAINST A WALL OR MACHINERY. OPEN DISCHARGE VALVES CAUTIOUSLY AFTER STANDING CLEAR AND WARNING OTHERS AWAY. MAKE CERTAIN DUST AND DEBRIS WHICH COULD BE BLOWN TOWARD PERSONNEL ARE SWEEPED CLEAR OF DISCHARGE AREA.

SECTION 2 - SYSTEM DESCRIPTION (See Dia. MSS Heave Comp. Sys. Page 2)

This section contains a functional description of the MSS Heave Compensator system and its subsystem components. Its purpose is to describe their general operation and relationship within the system.

The MSS Heave Compensator maintains constant tension on the EM Cable by taking up or paying out cable through the rise and fall of the A-Frame in accordance with movements on the vessel due to sea action. Tension is maintained on the line through the A-Frame movement which is generated by nitrogen gas pressure in the compensator cylinder, this tends to extend the cylinder thus reducing the free length of the cable being controlled.

When upward movement of the ship causes an increase in tension, the cylinder retracts (thus increasing the free length of the cable) and maintains the selected line tension. The reverse movement, tending to decrease line tension, allows the cylinder to extend (thus shortening the free length of the cable) to maintain the tension. Fast, accurate response in paying out or taking up cable with minimum tension variations is due to the use of moment arm of the A-Frame which has a movement that is a fraction of the wire cable

movement. The pressure in the tensioner cylinder determines the tension that is achieved. To limit the range of pressure variation in the cylinder as the cylinder position changes, the heave compensator is interconnected with a Power Gas Pressure Vessel. The volume of this pressure vessel determines the variation in tension with the movement of the cylinder.

An gas-oil reservoir is mounted on the tensioner and is connected to the cylinder. Oil fills the rod end of the cylinder and partially fills the reservoir, which has a low pressure air charge. This feature provides continuous lubrication, system damping, and safety control by means of a restrictor in the line. In the event of a cable failure, the cylinder extends to its full stroke, but at a controlled velocity, thus preventing any damage to the tensioner or adjacent equipment.

Complete control of heave compensator system is accomplished at the centralized control panel. This panel enables a single operator to start-up, set controls, monitor and shut-down the entire system.

#### SECTION 2.1 - OPERATING CONTROLS (See Dia. MSS Heave Comp. Sys. Page 2)

A number of controls beyond those on the control panel are necessary. The following describes each operating control on the heave compensator assembly.

1. Heave Compensator Shut-Off Valve

A valve enabling the operator to isolate heave compensator high pressure gas line. During all normal operations it remains in an OPEN position.

CAUTION - DO NOT CLOSE THIS VALVE WHILE THE WIRE LINE LOAD IS ACTIVE -

2. Vent Valve

A valve enabling the operator to vent gas pressure from the heave compensator. Its position during normal operation is CLOSED.

3. Oil Shut-Off Valve

This valve on the gas-oil reservoir can shut-off the oil flow from the cylinder to the gas-oil reservoir. It may be used to lock the compensator in a retracted position. By the proper application of gas pressure through the HP shut-off valve and closing of the oil shut-off valve, the cylinder may be locked in any position between retracted and fully extended. The normal operating position is fully OPEN.

CAUTION - DO NOT LOCK THE COMPENSATOR WHEN THE WIRE LINE LOAD IS ACTIVE -

4. Flow Speed Control Valve

This valve on the gas-oil reservoir limits the extension speed of the cylinder.

5. Gas Shut-Off - Gas-Oil Reservoir

This valve on the gas-oil reservoir is a local control for the precharge gas into the gas-oil reservoir. Its normal operating position is CLOSED.

6. Oil Reservoir Drain

This valve drains oil from the gas-oil reservoir. Its normal position is CLOSED.

7. Gas-Oil Reservoir Relief Valve

This relief valve prevents the gas pressure in the gas-oil reservoir from exceeding a preset safe value. Always maintain its original setting (normally 95 to 120 psi).

8. Rupture Disc

This safety rupture disc is installed to insure against exceeding the safe operating pressure of the gas-oil reservoir. The rupture disc should be intact during operation. Infrequent replacement does not indicate a system problem.

9. Oil Level Sight Gauge

This gauge indicates the oil level in the gas-oil reservoir. The gauge at the reservoir's bottom is the correct oil level when the cylinder is fully retracted.

Oil Types: Pydraul-150 (Monsanto), Fyrquel-150 or petroleum based.

- DO NOT OVER-FILL OR OPERATE BELOW PROPER LEVEL -

10. Gas Pressure Vessel

This unit is connected to the compensator during operation and normally operates up to 1500 psi. This pressure determines the tension level of the heave compensator. During normal operation the gas pressure vessel and compensator are always interconnected.

2.2 - OPERATING CONTROLS

There are three controls listed below which are mounted directly on or at the the heave compensator. All other controls are a part of the control panel.

1) Drain Valve

The gas pressure vessel is provided with a drain valve. The valve should be opened periodically to drain-off any condensate water. During normal operation it remains CLOSED.

2) Heave-Compensator Shut-Off Valve

This valve isolates the heave compensator in a set position should the gas supply line burst. But should be left OPEN during normal operation.

3) Low Pressure Gas Charge Valve

This is for pre-charging the oil-gas reservoir. It is normally set at 40-50 psi when the heave compensator is fully retracted.

### 2.3 - CONTROL PANEL

The best understanding of each control on the panel can be derived from the schematic. The main control functions are briefly described below:

#### 1. High Pressure Charge Valve

This valve controls supply from the high pressure source to bleed into the gas pressure vessel. Before opening this valve, be sure that the gas source is active as indicated by the supply pressure gauge. During normal operation this valve is CLOSED, but is opened to increase cylinder pressure when the heave compensator load requirements increase during deployment.

#### 2. Vent Valve

This valve vents the unit to reduce cylinder pressure when the heave compensator load requirements decrease during recovery operations. During normal operation this valve is CLOSED.

#### 3. Pressure Gages

- a) There is a HP supply gauge which indicates the pressure level of the high pressure source.
- b) There is a heave compensator pressure gauge. This gauge reads directly the heave compensator charge pressure.

### 2.4 - GAS-OIL RESERVOIR

The reservoir, partially filled with oil, has a 40-50 psi gas charge piped to the rod end cavity of the cylinder. This arrangement provides system damping, continuous lubrication and safety controlled stroke velocity in the event of cable failure. Incorporated in the reservoir is a disc designed to rupture at 150 psi.

### SECTION 3 - PREOPERATIONAL CHECK LIST

#### PRELIMINARY TASKS

These tasks should be performed before putting the heave compensator into operation:

1. Inspect all piping to insure a proper hookup.
2. Check oil level in gas-oil reservoir on heave compensator. Correct if necessary. (Pydraul-150, Fyrquel-150 or petroleum based).
3. Pressurize the gas-oil reservoir to 40-50 psi. Cylinder should be fully retracted.
4. Open oil shut-off valve.
5. Open air-vent valve on cylinder.
6. Open heave compensator shut-off valve on cylinder.
7. Open all valves on control panel.
8. Open nitrogen storage valves. Set pressure regulator and allow gas pressure to build-up in the system until a pressure of 150-200 psi is registered and the vent valve is OPEN. A few seconds will suffice to insure clean and clear lines. Nitrogen supply is limited, don't vent unnecessarily.
9. Direct gas to heave compensator so that it vents through the heave compensator local vent valve.
10. Close gas input to the heave compensator at the control panel and close the heave compensator local vent valve.
11. Charge the system to the desired pressure for the length of cable deployed (see Page 9).
12. Check that all rotating points are well lubricated.
13. Open heave compensator shut-off valve and establish cylinder stroking about cylinder mid-point. The compensator is now fully operating.

SECTION 4 - OPERATING INSTRUCTIONS (See Dia. of Gage Board Pg 11 & MSS A-Frame Reeving Plan Pg 12)

Before leaving the shipyard, the EM Cable should be reeved under the 36" lead block mounted on the top of the Pengo winch. To do this the wheel will have to be removed. Then the cable should be reeved through the snatch block at the end of the A-frame.

This should be done at the Jetty with the heave compensator retracted.

The heave compensator should be brought into operation after the EM cable has been keelhailed; the necessary connections have been made to the BIP; the stinger and the EM cable have passed down through the 30" restricted area of the moonpool horn and about 1000 ft of cable has been paid-out. The gas pressure in the heave compensator should be about 250 psi at this stage and should be increased with the increase of cable deployed in accordance with the valves shown on Page 9 and graph on Page 9A.

The maximum tension spin-off control on the Pengo winch should be set to pay-out at load cell tensions corresponding to the drill pipe deployed, see Page 9 & 9A, so that the EM cable will not exceed this recommended maximum loading while the EM cable is being payed out. Pressure in the heave compensator is increased by opening valve (1) slowly and observing the pressure increase on the heave compensator gas pressure gage (see Page 11).


When recovering the cable, the heave compensator gas pressure is lowered by venting to atmosphere by opening valve (2) (see Page 11).

W. BUCHANAN

JOB 00006 TASK 323000

16 JAN 1981


MSS HEAVE COMP INSTRUCTIONS.



\* THE INDICATOR IS CALIBRATED TAKING INTO CONSIDERATION THE OPERATING ANGLE OF THE "A" FRAME.

DIAGRAM OF GAGE BOARD.

SK. W.B-1-16-81-1



N.B. 1-12-81-2

MSS "A" FRAME REEVING PLAN.

MSS HEAVE COMP INSTRUCTIONS  
JOB 00006 TASK 323000

W. BUCHANAN  
 16 JAN 81

## SECTION 5 - DE-COMMISSIONING

On recovery of the BIP the heave compensator should be de-commissioned in the following manner:

- Close all the nitrogen bottles shut-off valves.
- Check that the high pressure charge valve is closed. This is valve ① on Sketch, Page 11.
- Open the gage board vent valve and vent system. This is valve ② on Sketch, Page 11. This will cause the heave compensator to retract.
- When the heave compensator pressure gage indicates that the system is at atmospheric pressure, close the heave compensator shut-off valve.
- Open the drain on the 11 gallon gas pressure vessel.
- If desired, the Synflex hose connecting the gage board to the 11 gallon gas pressure vessel can now be removed.
- The A-Frame and the EM Cable can be secured in this position until the vessel reaches port.

SECTION 6 - REFERENCES

The information in these instructions was derived from the following sources.

- 1) Rucker-Shaffer Technical Manual TM42023
- 2) Instrumentation & Controls Installation  
GMDI Dwg. E-001-A020.
- 3) Heave Compensator Piping Diagram  
GMDI Dwg. E-001-P001
- 4) MSS Glomar Challenger Equipment Installation Arrangement  
GMDI Dwg. E-001-A028 Two Sheets.

APPENDIX D  
EQUIPMENT LIST

APPENDIX D  
MSS AT-SEA-TEST EQUIPMENT LIST

<u>NUMBER</u>	<u>DESCRIPTION</u>	<u>REMARKS</u>
1	INSTRUMENTATION VAN (STC)	TELEDYNE GEOTECH
2	PENGO BULL WHEEL WINCH	TELEDYNE GEOTECH
3	2 - BIP & CONTAINERS	TELEDYNE GEOTECH
4	2 - BALLAST WEIGHT (WD CRATE)	TELEDYNE GEOTECH
5	POWER CABLE & SNATCH BLOCK	TELEDYNE GEOTECH
6	PORTABLE A-FRAME ASS'Y	TELEDYNE GEOTECH
7	WINCH PARTS	TELEDYNE GEOTECH
8	MISC. TOOLS	TELEDYNE GEOTECH
9	A-FRAME	TELEDYNE GEOTECH
10	3 SNATCH BLOCKS	NAVOCEANO
11	UNDERWATER TELEVISION	
12	UNDERWATER T.V. REEL	
13	MISC. TOOLS AND FITTINGS	
14	SHEAVE & DECK SUPPORT STAND	
15	UNDERWATER T.V. GUIDE FRAME	
16	HEAVE COMPENSATOR CONTROL BOARD	
17	WEIGHT INDICATOR	
18	NYLON SHEAVE	
19	KOOMEY UNIT	
20	48" A-FRAME SHEAVE	NCEL
21	ACCUMULATOR BOTTLE	
22	GUIDELINE TENSIONER	
23	2 BIP CARRIAGE ASSY'S	
24	2 HYD. CONTROL SUB ASSY'S	
25	2 REENTRY STINGERS	
26	CABLE - PROTECTOR 3" SPLIT PIPE	
27	TENSION LOAD CELL	
28	4 - NITROGEN BOTTLES	
29	DIGITAL LOAD READOUT	
30	ANALOG LOAD RECORDER	
31	SUBSEA ACOUSTIC RELEASE EQUIP.	

APPENDIX E  
FIELD IMPACT TEST



United Fabricators  
Marine Sismic Systems Test  
January 22, 1981

#### PURPOSE

This report describes the instrumentation and video motion analysis uses for testing of a marine seismic system. The tests were performed on January 22, 1981, at United Fabricators facility in Santa Fe Springs, CA. All instrumentation including strain gages and accelerometers were provided by Datacraft. Datacraft personnel operated the recording equipment and video system. United Fabricators operated the test specimen, crane, forklift etc., required to provide the necessary impact conditions.

#### INSTRUMENTATION SYSTEM

The instrumentation system used by Datacraft for recording data is shown in the attached block diagram. Statham strain gage type accelerometers were mounted at appropriate locations on the test specimen as well as single active arm strain gages and dual strain gages for the measurement of bending. The output signals of these transducing elements were fed to a amplifying system. The signal conditioning system provides the appropriate excitation voltages, balancing and calibration. The output of the signal conditioners were fed to Bell & Howell light beam oscillographs. The records produced by these oscillographs are on a light sensitive paper. The paper is exposed by an ultraviolet light source in the recording unit and intensified under florescent lights. The resulting record should never be exposed



### Marine Sesmic Systems Test (Continued)

to sunlight or incandescent lights. To do so, would bleach out the record. The recording oscillographs incorporated galvanometers which limited the frequency response of the data to 300 Hz. This was done to eliminate spurious signals from local resonances and other sources and to make the desired data more clearly visible.

### VIDEO SYSTEM

The purpose of this system is to provide stop action high resolution video images for determination of time and position data. This data can be recorded for later use on a magnetic tape recorder Panasonic model NV8410 or the data can be analyzed on the spot by using the Sony model SVM1010 motion analyzer.

### SYSTEMS FEATURES

#### Rotary Shutter Camera

This camera is equipped with a shutter which rotates at high speeds synchronized to the video signal. This shutter cuts off excess light input producing a shot the same as would be obtained using a shutter speed of 1/500 of a second.

#### Video Motion Analyzer SVM1010

The most outstanding feature of this analyzer is its capability to display information for any length of time without damage to the disc or deterioration of the information. The SVM1010 has the capability of playing back in real time 1/7 or 1/15 slow motion playback. It also, has the capability of displaying still frame for any length of time.



### Marine Sesmic Systems Test (Continued)

#### VIDEO DATA FORMAT

The impact data was recorded with a black and white video camera with a shutter speed of 1/500 of a second at 60 frames per second. The camera was placed 50 feet from the specimen. In the background there is a backboard with a synchronous motor attached to a clock face. This motor rotates at 600 rpm. The backboard also has lines, horizontally and vertically, that are six inches apart. When provided, a wide angle color shot of the impact data will precede the black and white impact data. Each impact is numbered with a piece of paper taped to the target itself. The above data was placed on a video cassette recorder VHS type.

#### TEST DATA


The data supplied with this report includes the records from the recording oscillograph, a video tape and a reduced data sheet for strain and acceleration measurements, a reduced data sheet for swing impact velocity obtained from the video tape. The reduced data sheets contain a single reading from each of the data channels. The maximum of each channel is shown as well as the time from impact to the maximum. A sketch is included showing the various transducer locations and axis.

UNITED FABRICATORS  
VIDEO TAPE REDUCED DATA

Event No.	VELOCITY AT IMPACT (FPS)	DROP HEIGHT (Inches)
1	Indeterminate	1
2	Indeterminate	3
3	Indeterminate	7
4	5	12
5	6	19

Event No.	(FPS)	HORIZONTAL DISTANCE FROM TARGET (FT)
6	.33	12
7	1.15	28
8	1.50	40
9	1.76	52
10	2.72	64



MARINE SEISMIC SYSTEM (MSS)

TEST SET-UP.

UNITED FABRICATORS  
JANUARY 22, 1981

Meas#	EVENT #1	EVENT #2	EVENT #3	EVENT #4	EVENT #5	EVENT #6	EVENT #7	EVENT #8	EVENT #9	EVENT #10										
AC.DZ	1.7	2.8	5.1	-3.7	1.2	1.2	-2.5	1.1	5.0	.47	0	0	0	0	1.7	.32	1.7	.31	3	
AC.TY	2.0	.08	2.8	.19	3.3	.36	2.8	.26	3.3	.18	0	0	0	0	0	0	0	0	0	
AC.DX	-1.0	.07	-1.7	.52	8.3	1.2	0.5	1.1	5.8	1.0	0	0	0.8	.09	1.7	.09	1.7	.09	4.8	
AC.CZ	0	0	0	0	-1.7	.81	1.0	.08	-1.2	.1	0	0	0	0	0	0	-0.8	4.0	-1.0	1.7
AC.CY	-2.0	.08	-2.5	.19	-3.0	.35	-2.5	.25	-3.3	.18	0	0	0	0	0	0	0	0	0	.83
AC.CX	0	0	0	0	-3.3	.81	1.7	.05	3.0	.12	0	0	0	0	0	-1.3	.02	-1.7	.01	2.2
AC.EZ	0	0	0	0	1.7	.81	1.7	.2	-2.5	.06	0	0	0	0	0	1.3	.6	1.7	.01	2.3
AC.BY	1.7	.14	3.3	.20	3.3	.38	2.5	.25	5.0	.19	0	0	0	0	0	1.3	.04	-15.	.04	1.7
AC.BX	4.2	.02	6.7	.02	6.3	.02	3.3	.05	10.	.02	1.5	.02	3.3	.03	4.6	.02	6.5	.01	8.3	
SG.BEN	S	T	S	T	S	T	S	T	S	T	S	T	S	T	S	T	S	T	S	
	-.50	.11	-.67	.10	-.90	.12	-1.0	.12	-1.3	.11	0	0	-.33	.11	-.33	.11	-.70	.12	-.87	
SG.I	-.23	.11	-.33	.10	-.50	.1	-.40	.11	-.67	.11	0	0	.17	.11	1.7	.11	-.33	.11	-.37	
SG.I+90°	0	0	0	0	0	0	.23	.10	.23	.10	0	0	0	0	0	0	0	0	.17	
SG.I+180°	.50	.10	.67	.10	.83	.12	1.0	.12	1.0	.12	0	0	.33	.12	.33	.11	.67	.11	.67	
SG.I+270°	0	0	0	0	-.50	.12	-.33	.10	.50	.10	0	0	0	0	0	0	-.30	.08	.33	

T = Seconds (FOR PEAK CHARACTERISTICS) G = 1 Gravity S = In/In X 1000

AC = Accelerometer I = Impact or +x Axis  
 B = Bottom Location SG = Strain Gage  
 Ben = Bending T = Top Location  
 C = Center Location X,Y,Z = Axis  
 D = Dummy Bip

Datacraft, Inc.  
Gardena, CA 90249  
323-9120


UNITED FABRICATORS SET-UP SHEET  
January 22, 1981

Meas.	Location	Range F.S.	Sig. Con.	Tape Recorder		Reducer S/N	Cal. = 1.5 inch
				R	Ch		
AC.DZ		25 G	1	1	1	624	19.8K = 25 G
AC.TY		25 G	2	1	2	12102	19.0K = 25 G
AC.DX		25 G	3	1	3	627	19.8K = 25 G
AC.CZ		25 G	4	1	4	7536	19.5 = 25 G
AC.CY		25 G	5	1	5	7537	19.9 = 25 G
AC.CX		25 G	6	1	6	1560	19.9 = 25 G
AC.BZ		25 G	7	1	7	7614	19.9 = 25 G
AC.BY		25 G	8	2	1	7538	19.3 = 25 G
AC.BX		25 G	9	2	2	7535	19.7 = 25 G
SG.Ben		5000 Min/in	10	2	3		34.6 = 5000 Min/in
SGI		5000 Min/in	11	2	4		34.6 = 5000 Min/in
SGI+90		5000 Min/in	12	2	5		34.6 = 5000 Min/in
SGI+180		5000 Min/in	13	2	6		34.6 = 5000 Min/in
SGI+270		5000 Min/in	14	2	7		34.6 = 5000 Min/in

Blank trace on Recorder 2

Datacraft, Inc.  
Gardena, CA 90249  
321-2320

MOTION ANALYZER SYSTEM



Datacraft, Inc.  
Gardena, CA 90249  
321-2320

APPENDIX F  
REENTRY SUB INSPECTION AND TEST

## MSS REENTRY ASSEMBLY - FIT, RUNNING &amp; FUNCTION TESTS

## A) FIT TESTS - COMPONENT TO COMPONENT FIT-UP CHECKS:

<u>ITEMS TO BE FIT</u>	FIT UNIT#1	FIT UNIT#2	UNIT #1 vs UNIT #2	UNIT #2 vs UNIT #1
1) Baker Plugs vs Otis Tools	✓	✓	✓	✓
2) Baker Plugs vs Hyd Plug/Sonar Adap	✓	✓	✓	✓
3) Dummy Sonar Tool vs Hyd Plug/Sonar Adap	✓	✓	N/A	N/A
4) Hyd Plug/Sonar Adap vs Stingers	✓	✓	✓	✓
5) Hyd Plug/Sonar Adap vs Control Subs	✓	✓	HP/SA 1 NOT CHECKED W/CS2	✓

## B) RUNNING TESTS - RAISE &amp; LOWER COMPONENTS INSIDE ASSEMBLY:

<u>ITEMS TO BE RUN IN ASSEMBLY</u>	CLEAR UNIT#1	CLEAR UNIT#2	UNIT #1 vs UNIT #2	UNIT #2 vs UNIT #1
6) Sonar Tool Down then Up	✓	✓	N/A	N/A
7) Baker Plug & Otis Tool Down	✓	✓	✓	✓
8) Baker Plug & Otis Tool W/HP/SA Up	✓	✓	✓	✓

## C) FUNCTION TESTS

<u>TEST TO BE RUN</u>	UNIT #1	UNIT #2
9) Pressure Test; HP/SA in Control Sub 3500 to 4000 psi	✓	✓
10) Hydraulic System Test	✓	✓
Shear - Uniform, Clean	✓	✓
Traverse - Smoothly, Evenly	✓	✓
Drop Gate - Correct Pressure	✓	✓

## MSS REENTRY ASSEMBLY - CRITICAL DIMENSIONS

<u>INSPECTED ITEM</u>	DESIGN	UNIT #1	UNIT #2
<u>E-001-A003: CARRIAGE CONTROL SUB</u>			
1) LOWER BORE	$\frac{8.877}{8.880}$	8.878"	8.879"
2) UPPER BORE	4.12 ±.03"	4.125"	4.125"
3) LOCK RING GROOVE DIA. (DEPTH)	9.258 ±.005" (0.190 ±.003")	(0.193)	(0.193)
4) BOX THREADS GO/NO-GO GAGE	6-5/8 FH	GAGED	GAGED
5) LONGITUDINAL CLEARANCE ABOVE LOCKING GROOVE - MINIMUM	6-3/4 (5-7/8)	6-1/16	6
<u>D-001-A004: BIP CARRIAGE</u>			
6) LONGITUDINAL EAR TO EAR	22'1"	22'1"	22'1"
<u>E-001-A005: BIP CARRIAGE HOUSING</u>			
7) LONGITUDINAL EAR SLOT TO EAR SLOT	22'1"	22'1-1/16"	22'1"
8) TOP & BOTTOM CONE OPENINGS	$\frac{8.96}{9.04} \left( \frac{9.00}{9.10} \right)$	9.1"	9.1"
<u>C-001-A006: LATERAL SHOCK RING</u>			
9) RING ID	8-1/8"	8-1/8"	8-1/8"
10) RING OD	13-1/8"	13-1/8"	13-1/8"
<u>D-001-A007: REENTRY TOOL STINGER</u>			
11) LOWER BORE	$\frac{8.53}{8.50}$	8.52"	8.52"
12) CONCENTRICITY OF SECTIONS	TO CLEAR	✓	✓
<u>E-001-A008: BIP CARRIAGE HOUSING ASSEM.</u>			
13) CLEARANCE BEHIND CARRIAGE FOR HP/SA	TO CLEAR	✓	✓
<u>D-001-A010: HYDRAULIC PLUG/SONAR ADAPTOR</u>			
14) SNAP RING OD	9.25"	9.25"	9.25"
15) SNAP RING HEIGHT	0.75"	0.75"	0.75"
16) INSIDE PROFILE	TO FIT SONAR TOOL & BAKER	✓	✓
17) OUTSIDE PROFILE	TO FIT STINGER & CONTROL SUB	✓	✓

APPENDIX G  
WEATHER SUMMARY

MSS-AT-SEA-TEST  
WEATHER SUMMARY

DATE	TIME	HEADING	WIND		SEA		SWELL		ROLL	PITCH
			DIR.	MPH	FT.	SEC	FT.	SEC		
3/27	1200	135		airs		rippled	3	10	1	1
	1800	135	WNN	10	1	4	3	10	1	1
	2400	135	ENE	10	1	4	3	10	2	1
3/28	0600	090	ENE	20	3	4	3	10	3	2
	1200	125	E	18	3	4	3	10	4	2
	1800	110	E	20	3	4	3	10	2	2
	2400	100	ENE	18	3	4	3	10	4	2
3/29	0600	140	SSE	18	3	4	4	10	5	2
	0200	140	SSE	20	3	4	4	10	3	2
	1800	175	W	8	1	4	6	11	3	2
	2400	160		airs	---	---	6	11	2	1
3/30	0200	130	NE	13	2	4	6	11	4	2
	0600	155	N	10	1	4	5	11	2	2

APPENDIX H  
AT-SEA-TEST CHRONOLOGY

STEP	DRILL STRING LENGTH	CABLE LENGTH (MON.)	CABLE TENSION OBJ.	WINCH HYD PRESS	HC PRESS PSI	LOAD CELL LBS	DRILL PIPE TRIPLES	TIME	REMARKS
								3/27/81	
3.2	-0-	200 +	slack		220 0	-0-	---	0200 0400	START Did not raise HC
3.3	-0-	200 +	slack		-0-	-0-	---	0800	
3.4	-0-	200 +	slack		-0-	-0-	---		
3.5	-0-	200 +	slack		-0-	-0-	---		
3.6	-0-	200 +	slack		-0-	-0-	---	0930	
3.7	68	200 +	slack		-0-	-0-	---		
3.8	165 158	~100	taut		220	-0-	---	1000	
3.9	165 158	~100	taut		220	~200 210	---	1130	2 ft HC ext.
	535	440	500		450	800	4		

STEP	DRILL STRING LENGTH	CABLE LENGTH (NOV.)	CABLE TENSION OBJ.	WINCH - HYD PRESS	HC PRESS PSI	LOAD CELL LBS	DRILL PIPE TRIPLES	TIME	REMARKS
3.9 (Cont'd)	995	887/911			300	450	9		
	<u>1001</u> 995	920 1944/2000	2000		450 410	3300 3000	9 9	1200	
	2015	1935	3000		570	5100	20		
	<u>3033</u> 3041	<u>2953</u> 2570/2650	3000		<u>570</u> 570	<u>5100</u> 5400	<u>31</u> 31	0300	
	<u>3958</u> <u>3971</u>	<u>3878</u> <u>3727/3836</u>	4000		<u>670</u> <u>540</u>	<u>7000</u> <u>200</u>	<u>41</u> <u>41</u>	1320	+ 500 lbs load cell
	<u>4975</u> <u>4994</u>	<u>4895</u> <u>4699/4837</u>	4000		<u>670</u> <u>610</u>	<u>7000</u> <u>6500</u>	<u>52</u> <u>52</u>	1345	
	<u>5993</u> <u>6017</u>	<u>5913</u> <u>5683/5854</u>	4000		<u>670</u> <u>650</u>	<u>7000</u> <u>6800</u>	<u>63</u> <u>63</u>	1410	
	<u>7010</u> <u>7040</u>	<u>6930</u> <u>6657/6858</u>	5000		<u>780</u> <u>690</u>	<u>8700</u> <u>7300</u>	<u>74</u> <u>74</u>	1435	+ 400 lbs load cell
	<u>8028</u> <u>8063</u>	<u>7948</u> <u>7633/7864</u>	5000		<u>780</u> <u>620</u>	<u>8700</u> <u>7000</u>	<u>85</u> <u>85</u>	1500	
	<u>9045</u> <u>9086</u>	<u>8965</u> <u>8613/8873</u>	5000		<u>780</u> <u>620</u>	<u>8700</u> <u>7300</u>	<u>96</u> <u>96</u>	1523	

STEP	DRILL STRING LENGTH	CABLE LENGTH (NOM.)	CABLE TENSION OBJ.	WINCH HYD PRESS	HC PRESS PSI	LOAD CELL LRS	DRILL PIPE TRIPLES	TIME	REMARKS
3.9 (Cont'd)	10016	9501/9790			610	6300	106	1537	slight recal of digit. HC calib.
	9970	9890	6000		900	10600	106	1550	
	10016	9690/9990			750	8900	106		
	10988	10908	6000		900	10600	117	1620	
	11039	10506/10869			800	10000	117		
	12005	11925	6000		900	10600	128	1646	
	12062	11346/11845			845	10200	128	1656	
	12248	11608/11963			890	10400	130		
	13023	12943	7000		1020	12400	141	1812	
	13271	12594/12981			875	11000	141		
4.1	14040	13960	7000		1020	12400	150	1830	calib. HC-Reset count. Reset sea Mac
	14139	14148/14813					150+1/3	1835	
	14668	14588	8000		1110	14200	157*	1959	56 ft above rig floor
	14640	14598/14599			865	12400	156+1/3	2072	
	14640	14603/14604				11400	156+1/3		
	14728	14643	7000		1020	12400	158*		60 foot stab payout 54/56 feet STAB - 56 feet
5.1	14696	14657/14660			750	10000	156+1/3	2357	Entanglement test
	14696	14699/14700			845	11500	156+1/3		
	14728	14643	8000		1110	14200	158*	3/28/81	
	14696	14686/14691			865	12000	156+1/3	0520	
	14696	14686/14691			870	11800			
	14728	14643	6000		900	10600	158*	0620	release carriage
14696	14686/14691					156 1/3			


STEP	DRILL STRING LENGTH	CABLE LENGTH (NOM.)	CABLE TENSION OBJ.	WINCH HYD PRESS	HC PRESS PSI	LOAD CELL LBS	DRILL PIPE TRIPLES	TIME	REMARKS
5.2	14728	16643	7500		1050	13300	158*	0624	lower 2000 ft slowly
	14696	16577/16640			860	11800	156 1/3		
	14728	~16000	6500		950	11500	158*		
	14696	15774/15611 16070/16125			950		156 1/3		
5.3	14638	16143	7800		1100	12400	157*	1910 1930	Raise BIP 500 feet, raise drill string 90 ft, release gate
	14603	16070/16125			925	12300	155 1/3		
	14603				940	12300	155 1/3		
	14668	18000	6000		900	10600	157*		
6.0	14603	16576/16651 16596/16672 16596/16672			835	11400	155 1/3	2023 2028	lower BIP to bottom recover drill string 900 ft of hole remove HC
		16596/16672 16894/18847			750	9000			
		18694/18847 21015/21250			0	7700			
						7700			
7.0		21015/21250 16530/16600 00762/10227			670	7800		3/30/81 0000 0215 0332	moved vessel to 3000 ft off hole  payout 2321 feet  + 1500 lbs - BIP raising BIP alongside
					---	12000			
					---	4250			

DRILL STRING LENGTH - BASED ON 90 FOOT STANDS DEPLOYED  
 CABLE LENGTH - READ OFF TWO FOOTAGE LINE COUNTERS  
 CABLE TENSION - TEST CRITERIA  
 HC PRESSURE - INLET PRESSURE TO ACCUMULATOR  
 LOAD CELL - READS SHEAVE LOADING WHICH MUST BE CORRECTED TO CABLE LOADS

APPENDIX I  
TYPICAL CHALLENGER SHIP MOTIONS

SIMS 385A 27 MAR 81

DATA CONTEXT OF WAMP



APPENDIX I TYPICAL GLOWAR CHALLENGER WAVE RESPONSE


APPENDIX J  
AT-SEA-TEST DRAWINGS

APPENDIX J  
DRAWING LIST


E-001-A001	BIP Reentry Sub W/Stinger Control Dwg. Alt 2
E-001-A002	Reentry Assy Control Dwg. Alt 3
E-001-A003	BIP Carriage Control Sub Details & Assy Alt 1
D-001-A004	BIP Carriage Assy & Details Alt 1
E-001-A005	BIP Carriage Housing Assy & Details Alt 2
C-001-A006	Lateral Shock Absorber Ring Detail Alt 2
D-001-A007	Reentry Tool Stinger Assy Details Alt 2
E-001-A008	BIP Carriage Housing Main Assy Alt 2
E-001-A009	BIP Reentry Tool Assy Alt 1
D-001-A010	Hydraulic Plug/Sonar Adaptor Details Alt 2
E-001-A013	Marine Seismic System EM Cable Protector Details & Assy Alt 1
E-001-A014	MSS EM Cable Protector Installation Arrangement Alt 1
E-001-A018	MSS Heave Compensator Control Board, Details & Assy Alt 1
E-001-A020	MSS Instrumentation & Controls Installation Alt 2
E-001-P001	MSS Heave Compensator Piping Diagram Alt 0
E-001-A022	MSS A-Frame Details & Assy Alt 1
E-001-A023	MSS A-Frame Support to Sub Base Details & Assy Alt 1
E-001-A024	MSS A-Frame Support to Casing Rack Details Alt 1
E-001-A025	MSS Winch Foundation Details & Arrangement Alt 0
E-001-A028	MSS GLOMAR CHALLENGER Equip. Install. Arrangement Alt 0
E-001-A030	MSS Accumulator Supports Details & Assy. Alt 0
E-001-E001	MSS GLOMAR CHALLENGER Electrical Installation Alt 2
D-001-A031	MSS BIP Handling T-Bar Details Alt 0
E-001-A034	MSS TV Guide Frame Assy and Details Alt 0
D-001-A033	Slip Adaptor for Stinger Details Alt 0
D-001-A032	MSS Handling Tool for Stinger & Carriage Housing Details Alt 0
E-001-A026	Marine Seismic Sys Idler Sheave Support Details & Assy Alt 0
E-001-A027	Marine Seismic Sys Sheave Beam to Winch Assy & Install Alt 0
E-001-A029	Marine Seismic Sys Heave Compensator Bracket Mod. & Details Alt 0
D-001-A035	Marine Seismic Sys Running Fairleader Details Alt 1
D-001-A037	Marine Seismic Sys Dual Ship Entanglement Sys Assy Alt 0

**Best  
Available  
Copy**






ELEVATION 2-C  
SCALE: 1/2" = 1'-0"



DETAIL 4-D  
BIP  
SCALE: 1/2" = 1'-0"



VIEW 3-D  
SCALE: 1/2" = 1'-0"

VIEW 3-D  
SCALE 1/2" = 1'-0"

3-D

10 501.06 DA

3-D

HYDRAULIC PUMP  
SONAR ADAPTER

EDD WESTERN  
MODEL 816 SONAR  
HOLE ENTRY  
SYSTEM

ELEVATION 2-C  
SCALE 1/2" = 1'-0"

LIST OF MATERIALS


NO.	QTY.	DESCRIPTION	REMARKS

REFERENCE DRAWINGS:


1. EDD-1-A009 MACHINE SONAR SYSTEM  
BIP SE-ENTRY TOOL ASSEMBLY

TELETYPE ABBTECH DRAWINGS:


2. 970-55100 BIP  
3. 970-55100-010 BIP LAYOUT



4 5



ELEVATION 2-C  
SCALE: 1/2"=1'-0"



2									
1									
0	1.0000	0.0000	1.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
ALT. (SECTION ONE) INDICATED.									
ALTERATION APPROVAL									
APPROVED	DESIGNED OR REVISED	BY	DATE	REVISION	NO.	TOTAL NET WT			
ASB						TOTAL NET WT			
5226						TOTAL NET WT			


4 3 2

5

C

B

A



ELEVATION 2-C  
SCALE: 1/2"=1'-0"

**REFERENCE DRAWINGS:**

- 1. E-001-A009 MARINE SEISMIC SYSTEM (MSS)  
BIP RE-ENTRY TOOL ASSEMBLY

**TELEDYNE GEOTECH DRAWINGS**

- 2. 990-53100 BIP
- 3. 990-53100-010 BIP LAYOUT

NO.	DATE	BY	DESCRIPTION	APP. AUTH.	APP.
2	10/25/80	HW	CHG. HYD. CBL. PLACEMENT, MOD. CABLE RUN & ADDED BIP PICK-UP POINTS	DOG - E-001-A009	HW
1	9/17/80	HW	REVISED PER BID PACKAGE	DO1 - E-001-A009	HW
0	8/14/80	HW	INITIAL RELEASE	DO1 - E-001-A009	HW
5	7/17/80	HW	REDESIGNED & REDRAWN	DO001 - E-001-A009	HW
A	7/1/80	HW	PRELIMINARY RELEASE	DO001 - E-001-A009	HW

NO. REV.	DATE	DESCRIPTION	BY	CHKD.
2	10/25/80	CHG. HYD. CBL. PLACEMENT, MOD. CABLE RUN & ADDED BIP PICK-UP POINTS	HW	DOG
1	9/17/80	REVISED PER BID PACKAGE	HW	DO1
0	8/14/80	INITIAL RELEASE	HW	DO1
5	7/17/80	REDESIGNED & REDRAWN	HW	DO001
A	7/1/80	PRELIMINARY RELEASE	HW	DO001

NO. REV.	DATE	DESCRIPTION	BY	CHKD.
2	10/25/80	CHG. HYD. CBL. PLACEMENT, MOD. CABLE RUN & ADDED BIP PICK-UP POINTS	HW	DOG
1	9/17/80	REVISED PER BID PACKAGE	HW	DO1
0	8/14/80	INITIAL RELEASE	HW	DO1
5	7/17/80	REDESIGNED & REDRAWN	HW	DO001
A	7/1/80	PRELIMINARY RELEASE	HW	DO001

APPROVED	DRAWING OR REVISION	REV. NO.	LETTER	DATE	FILE NO.
AS					
AS					

**GLOBAL MARINE DEVELOPMENT INC.**  
Newport Beach, Calif.

THE DESIGN AND THE WEIGHT OF MATERIALS AND THE CONSTRUCTION OF THIS DRAWING ARE THE PROPERTY OF GLOBAL MARINE DEVELOPMENT INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF GLOBAL MARINE DEVELOPMENT INC. THE DESIGN SHALL BE RETURNED TO GLOBAL MARINE DEVELOPMENT INC. ON REQUEST.

**MARINE SEISMIC SYSTEM (MSS)  
BIP RE-ENTRY SLIP WITH STINGER -  
CONTROL DRAWING**

DESIGNER	CHECKED	DATE	SCALE	TOLERANCES UNLESS OTHERWISE NOTED
DR. H.G. WAGNER	AS	10/25/80	AS NOTED	FRACTIONS - 1/16" DECIMALS - 0.001"
CHL. P. [unclear]	AS	10/25/80		1. UNLESS OTHERWISE SPECIFIED
APP. [unclear]	AS	10/25/80		
NO. [unclear]	AS	10/25/80		

NO.	DATE	BY	DESCRIPTION	APP. AUTH.	APP.
2	10/25/80	HW	CHG. HYD. CBL. PLACEMENT, MOD. CABLE RUN & ADDED BIP PICK-UP POINTS	DOG - E-001-A009	HW

6

DRILL PIPE


CROSSOVER SUB  
176'

6" HEAVY WT PIPE  
700'

(2) DRILL COLLARS  
8,400'

(3) BUMPER SUBS  
18,000'

DRILL COLLAR  
4,200'



1

2


1

4

3

2

RE-ENTRY SUB W/ STINKER  
67 FT - 7 1/2 INCHES  
16,000 # APPROX



22.10' APPROX  
1,800# (DRY)  
7,700# (WET)

2

1

36

2

1


LIST OF MATERIALS

NO.	DESCRIPTION	QTY.	UNIT

D

C

REMARKS:  
14,000 APPROX



C

DRILL PIPE


CROSSOVER SUB  
175#

6 5/8" HEAVY WT PIPE  
1,600#

(2) DRILL COLLARS  
8,400#

(3) BUMPER SUBS  
1,800#

DRILL COLLAR  
4,200#



B

A


6

5

4



10,000 APPROX



C

B

3	3-4-80	REVISED BOTTOM HOLE ASSY	006-383000
2	10-11-80	DELETED HEAVY WT. D.P.; ADDED LIGHT WT. D.C.; CHG. BUMPER SUBS WAS 1 & CHG. TOTAL WT.	006-886000 201-210500
1	9-11-80	REVISED PER BID PACKAGE	001-210500
0	8-11-80	INITIAL RELEASE	001-210500
A	7-10-80	PRELIMINARY RELEASE	001-210500
NO. DATE BY	DESCRIPTION		ISS. AUTH. APPR.

2									
1									
0	11/10/80	11/10/80	11/10/80	11/10/80	11/10/80	11/10/80	11/10/80	11/10/80	11/10/80
ALTERATION APPROVAL									
APPROVED	DESIGNED	ALT. NO.	LETTER	REV. NO.	TOTAL NET WT. (GROSS)	TOTAL NET WT. (NET)			
ASA					45400*				
ASDA									

**GLOBAL MARINE DEVELOPMENT INC.**  
 Newport Beach, Calif

**MARINE SEISMIC SYSTEM (MSS)  
 RE-ENTRY ASSEMBLY  
 CONTROL DRAWING**

BY: N.G. WAGNER	DATE: 7/10/80	SCALE: NONE	TOLERANCES UNLESS OTHERWISE NOTED
CHKD: [Signature]	DATE: 7/15/80		FINISHES - 1/8"
APP'D: [Signature]	DATE: 7/15/80		COLLIMETERS - 1/8"
DATE: 7/15/80	ISS. AUTH: 001-210500	ISS. NO. E-001	APPROX. 'A002
NO. 101			3

A


3

2


1

6

14  
P.T. BA  
M<sub>T</sub> 6 7/8" PH MOORED IN ACCORDANCE  
W/ UC-60-DRILL CO BACK BOX, USE



242 MATL: A53 4140  
250: 100,000 PSI




DETAIL 6-D  
SCALE: HALF SIZE



A 1/4" DC. (SAME PATTERN AS 10-150 PLUNGER)

BOTTOM VIEW 3-D



LIST OF MATERIALS				
QTY	SIZE	QTY	DESCRIPTION	QTY

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

- 1 ALL MACHINE SURFACES TO BE  $25\mu$
- 2 ALL INTERNAL DIAMETERS TO BE CONCENTRIC TO TIR .050, ONLY BORE LENGTH L<sub>1</sub>
- 3 BREAK ALL MACHINE CORNERS AND RADI TO 0.01" MIN
- 4 MACHINE TOLERANCES TO BE .XX±.1, .XX±.05, .XXX±.010
- 5  $\Delta$  TRANSITION STEP IS TO BE SMOOTH TO AVOID ROLLING OUT O-RING IN HYDRAULIC PLUG/SONAR ADAPTOR (REF DWG #2)
- 6  $\Delta$  ALL WELDS TO BE IN ACCORDANCE WITH AWS D11 STRUCTURAL WELD CODE - STEEL

REFERENCE DRAWINGS:

- 1. C-0635 UNIV. OF CALIF. DEEP SEA DRILLING PROJECT U78 FULL HOLE MODIFIED BOX (DRILCO BORE-BACK BOX RELIEF)
- 2. D-001-A010 MACHINE SEISMIC SYSTEM (MSS) HYDRAULIC PLUG/SONAR ADAPTOR DETAILS

1	1	1	CHANGED AMOUNT OF HOLES	000
---	---	---	-------------------------	-----

AP 6 7/8" PH HOOPED IN  
W/ UC 50-DRILL CO BACK E  
REF. 1

45° ± 10°

1/2" DRILL THRU TAP  
FOR 1/2" NPT (2 REQ'D)

- SEE DETAIL 4-D

1 1/4" DIA

1 1/2" DIA


3/8" DIA

3/8" DIA  
3/8" DIA  
3/8" DIA


10.5: SAC MAT. AISI 4140  
MIN. YIELD: 100,000 PSI

SEE

4







FACE B WITH  $\frac{1}{4}$  TUBE

$\frac{1}{4}$ " R CUT TO FIT

PIPE  
SCH 40  
ASTM A99

1/2" SCH 40  
PIPE-MAT'L:  
ASTM A-99  
GRADE B

3 WELDS ONLY  
TOP & BOTTOM (2 PLCS)

PLUG WELD-IT REQ'D  
TOP AND BOTTOM (2 PLCS)

GTAW PROCESS  $\frac{1}{4}$ "

1/4" PIPE (REF)

ELEVATION 5-C  $\Delta_2$

SCALE: 1/8" = 1'-0"

ELEVATION 6-A  $\Delta_1, \Delta_2$

SCALE: 1/8" = 1'-0"

ELEVATION 4-R  $\Delta_2, \Delta_3$

SCALE: 1/2" = 1'-0"

STD 30°

D

C

B


A

6


5

4


CUT TO FIT



**SECTION 3-C**  
SCALE: 3/8" = 1"



**DETAIL 3-B**  
SCALE: HALF SIZE



LIST OF MATERIALS				
QUANTITY	ITEM	QTY	DESCRIPTION	REMARKS
	1	2	LATERAL SHOCK ABSORBER	REF 1
Δ	2	2	RUBBER CRAFT CAT # 140 TO DUREMETER	NATURAL RUBBER
Δ	3	1	RUBBER CRAFT CAT # 110 TO DUREMETER	

**GENERAL NOTES:** (UNLESS OTHERWISE N

- ▷ TO BOND: USE WATER RESISTANT ADHESIVE PER MANUFACTURERS RECOMMENDATION.
- Δ 2. PAINT EXTERIOR IN ACCORDANCE WITH GMDI SPEC. 001-002.
- Δ 3. ALL PLATES & SHAPES TO BE ASTM A56.
- Δ 4. BREAK ALL SHARP EDGES & REMOVE ALL BURR!

**REFERENCES**

- 1. C-001-0006 MARINE SEISMIC SYSTEM (MSS) LATERAL SHOCK ABSORBER 2NG DETAIL

NO	REQ'D	DATE	BY	DESCRIPTION	REVISION
2	B.F.	2/83		ROTATED 180°, CHANGE BEVEL (ADDED CONTOUR IN ELEV 4-A) ADDED TAPER AT TOP 1/4" PIPE IN ELEV 5-C & ELEV 6-A	006 32300
1	11-80	NW		CHANGED MATERIAL CALLOUT FOR ITEMS 2 & 3 IN L/M WAS NATURAL RUB	006- 323000
0	10-80	NW		5. ADDED NOTE #4 4 CHANGE NOTE #2 TO EXTERIOR ONLY 3 ADDED SHEAR HOLE IN SEC. 3-C 2 BEVELED BOTTOM OF TUBE ELEV. 4-A 1 ADDED CALLOUT TO MAKE 1/4" W/4 TUBE IN ELEV. 5-C	001- 210900
B	7-78	NW		CLARIFY L/M - OPEN UP TOL.	001- 210900
A	10-80	MM		RELEASE PER RD	001- 210900

**GLOBAL MARINE DEVELOPMENT Inc.**  
Newport Beach, Calif

WE WARRANT AND WE AGREE TO HOLD OURSELVES AND OUR SUBCONTRACTORS RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THIS PROJECT AND WE AGREE TO HOLD OURSELVES AND OUR SUBCONTRACTORS RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THIS PROJECT AND WE AGREE TO HOLD OURSELVES AND OUR SUBCONTRACTORS RESPONSIBLE FOR THE DESIGN AND CONSTRUCTION OF THIS PROJECT.

**MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE ASSEMBLY AND DETAILS**


DATE	BY	SCALE	TOLERANCES UNLESS OTHERWISE NOTED
2/83	B.F.	AS NOTED	FRACTIONS: 1/32" ANGULAR: 1/4"
11/80	NW		UNLESS OTHERWISE SPECIFIED
10/80	MM		
7/78	NW		

NO	REQ'D	DATE	BY	DESCRIPTION	REVISION
2				ALTERATION	
1				DATE	
10				CONSTRUCTION	
1				DESIGN	
1				CONSTRUCTION	
1				DESIGN	
2				ALTERATION	

APPROVED	DESIGNED OR REVISED	ALT NO	LETTER DATE	PLT REF NO	TOTAL NET WT (G)	TOTAL NET WT (LBS)	TOTAL NET WT (KG)
ABE							
USCB							

6

5



MIN  $1\frac{1}{16}$ " THK  
AFTER MACHINING

11-13

11-13

11A.070

TO BE WELDED  
AT NEXT ASSY

16" SCH 40 PIPE  
MATL: API-5LX  
GRADE X-52

FLAT BAR  $1\frac{1}{4}$ " x  $\frac{1}{2}$ "  
MATL: MPM A-13;  
Q&Q A1-36) 51, DOC) PM  
MIN. YIELD  $\Delta_s$

3-A

3-A

12" RADII

BAR 1"  $\phi$

MAINTAIN  
SLOT, AS  
CLEANED  
SPATTER

22-11 $\frac{1}{8}$ "

22-11 $\frac{1}{2}$ "

2 $\frac{1}{2}$ " TYP



2

2

1

3

LIST OF MATERIALS

QTY	NO.	QTY.	DESCRIPTION	UNIT


ALL A-A

10-13

3" THK ELASTOMER PAD  
SEE DETAIL 10-D

10-A

10-13



GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL WELDING TO BE IN ACCORDANCE WITH AWS D.11 STRUCTURAL WELDING CODE - STEEL
2. BREAK ALL SHARP EDGES AND REMOVE ALL BURRS & ALL MACHINE SURFACES TO BE 125.
3. ALL WELDS THIS ASSEMBLY TO HAVE E 7018 ELECTRODE EXCEPT AT END FLANGES (A-035) ARE TO BE WELDED WITH E 6010 ELECTRODE AND PRE HEAT @ 175° F.

REFERENCE DRAWINGS:

1. 001-A003 MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE CONTROL SUB DETAILS & ASSEMBLY
2. 001-A007 MARINE SEISMIC SYSTEM (MSS) REENTRY TOOL STINGER ASSEMBLY & DETAILS

2	<p>ADDED DETAIL 10-A</p> <p>1 CHANGED DIM IN DETAIL 10-D WAS 3/4" &amp; 6 3/8"</p> <p>2 ADDED BOTTOM VIEW 10-D</p> <p>3 ADDED GUSSET 2 - SECT 11-A &amp; TOP VIEW 11-B</p> <p>4 CHANGED 3" ELASTOMER PAD ATTACHMENT SECT 3-B, SECT 10-B DET 10-D &amp; SECT 10-A</p> <p>5 CHANGED SLOT LENGTH WAS 1 3/8 - SECT. 3A</p> <p>6 CHANGED LOCKING EAR DIM</p>
---	---

TOP 3 PLACES

MATL: API-5LX  
GRADE X-52

FLAT BAR 1 1/4 x 1/2"  
MATL: ASTM A-131  
(ABS 34-36) 51,000 PSI  
MIN. YIELD

MAINTAIN  
SLOT, AREA  
CLEANED &  
SPLATTER

3-A

3-A

3-A

3-A

3-13

TO BE WELDED  
AT NEXT ANCH

A. 12-D

EX 12-D

MIN 1.20 THK  
AFTER MACHINING

A1A1.610

3-13

ELEVATION 4-A

SCALE: 1"=1'-0"

SEE NOTE #6

MAINTAIN  $\frac{1}{2}$ " OPEN  
SLOT, AREA MUST BE  
CLEANED OF ALL WELD  
SPATTER & ROUGHNESS

$\frac{1}{2}$ " R MATL  
ASTM A-36  
5 REQ'D

$\frac{1}{2}$ " x 45° SNIPE

GRIND  
SMOOTH

$\frac{1}{2}$ " x 45° SNIPE


GRIND  
SMOOTH

$\frac{1}{4}$ " \*

4" SCH 40 PIPE  
CUT TO SUIT, SIM  
TO SECTION 11-A

$\frac{1}{2}$ " R REF

**SECTION 3-B**  $\Delta_1, \Delta_3$   
SCALE: 5"=1'-0"



TO BE WELDED  
AT NEXT ASSEMBLY

$\frac{1}{4}$ " RAD. IN  
CORNERS (TYP)

TYP 3 PLACES

BAR 1" HALF ROUND  
REF

$\frac{1}{2}$ " CLR

**SECTION 3-A (ROTATED)**  $\Delta_2$

SCALE: 5"=1'-0"  
\* SEE NOTE #4

3-13

3-13

**VARIATION 4-A**  $\Delta_1, \Delta_2$

SCALE: 1"=1'-0"  
\* SEE NOTE #4

APPROVED	DESIGNED BY	DATE	REVISION

5



12

11

1 1/2" MAT'L ASTM A-36 (NORMALIZED) 50,000 PSI MIN YIELD

12-19/16" HOLES ON A 14 1/4" O.C. MATCH DRILL WITH REF. DWG. #2 (API 10" ISO PLG HOLE PATTERN MODIFIED)

10" TO FIT TUBE O.D.

3/16" NET

30° TYP

23 1/2°

21 1/2°

15°

1/2" SLOT

1/2-13 UNC 2A X 2 1/2" FULL THREAD STUD

BOTTOM VIEW 12-D  $\Delta_5$   
SCALE: 3"=1'-0"

C

1 1/4" MAT'L ASTM A-36 (NORMALIZED) 50,000 PSI MIN YIELD

1/2" MAT'L ASTM A-36 (AS BUILT) 50,000 PSI MIN YIELD  $\Delta_5$

10" TO FIT TUBE O.D.

15°  $\uparrow$  11-A

11-A  $\downarrow$

12-19/16" HOLES EQUALLY SPACED ON A 14 1/4" O.C. MATCH DRILL WITH REF. DWG. #1 (HOLE PATTERN SAME AS API 10" ISO PLG)

TOP VIEW 11-B  $\Delta_4$   
SCALE: 3"=1'-0"

8 1/2" 10  
9 0/8" 10

1/2-13 UN  
HEX BOL  
PLAIN  
LOCK W  
1/2"-13  
NUT (2)

10

9

LOW 02



TO BOND USE WATER RESISTANT ADHESIVE AS PER MANUFACTURERS RECOMMENDATIONS

\* 2 GACS #1  
1) REQ'D AS SHOWN  
2) REQ'D OPPOSITE HAND

1/2

6 x 1/2

UD



ON

1/2

2 AS

1/2"-13 UNC 2A x 2 1/4" HEX BOLT (2 REQ'D)  
PLAIN WASHER (2 REQ'D)  
LOCK WASHER (2 REQ'D)  
1/2"-13 UNC 2B HEX NUT (2 REQ'D)

16" PIPE ABOVE

5/8" MAT'L: ASTM A-36

7  
**LIST OF MATERIALS**

ITEM	QTY.	DESCRIPTION	UNIT


NATURAL RUBBER

△

2.34

$\frac{1}{8} \times 45^\circ \pm 10^\circ$  CHAMFER

BUNGLE OR NATURAL RUBBER. 50 TO 70 DIAMETER - 1 REQ'D AS SHOWN & 1 REQ'D OPPOSITE HAND





$\frac{3}{16}$ " DRILL THRU - CORE TO DEPTH SHOWN

(REQ) &  
 (NUT (REQ))




A-26

C




B

1/2"-15 UN  
HEX BOL  
PLAIN  
LOCK W  
1/2"-5  
NUT (2



3-13

A




**SECTION 10-B**  $\Delta 1,2$

SCALE: 3"=1'-0"  
\* SEE NOTE #4

1/2" ASTM A-36  
(2 REQ)


1/2" LOCK WASHER (4 REQ)  $\ddagger$   
1/2"-13 UNC 2B HEX NUT (4 REQ)

1/2"-13 UNC 2A x 2 1/4"  
HEX BOLT (2 REQ)  
PLAIN WASHER (2 REQ)  
LOCK WASHER (2 REQ)  
& 1/2"-13 UNC 2B HEX  
NUT (2 REQ)



**SECTION 10-A**  $\Delta 3$


SCALE: 3"=1'-0"  
\* SEE NOTE #4



**DETAIL**  
SCALE: FULL


5

A-36




$\frac{1}{4}$ " x 45° ± 10° CHAMFER

BUNA-N OR NATURAL RUBBER. 50 TO 70 DUROMETER - 1 REQ'D AS SHOWN & 1 REQ'D OPPOSITE HAND



$\frac{3}{16}$ " DRILL THRU -  $\frac{1}{2}$ " CORE TO DEPTH SHOWN

ER (REQ) &  
HEX NUT (REQ)



TM A-36  
ROOTH  
1/4 RAD

DETAIL B-A  $\Delta_1$   
SCALE: FULL SIZE

SEE SHEET 1 FOR NOTES, REFERENCES, AND ALTERNATIONS



GLOBAL MARINE DEVELOPMENT INC.  
Houston, Texas, U.S.A.


MARINE SEISMIC SYSTEM (MSS)  
DIE CARRIAGE HOUSING  
ASSEMBLY AND DETAILS

REVISIONS  
DATE NOTED BY  
2/25/90  
REV. NO. 001  
NO. 0005  
-1/2

12.79 I.D.  
C.S. BACKING  
O.D. RUBBER



SYMM ABT

3/8"



1/4"

1/4"



OWNER	ITEM
FURN	

4M ABT

50 DUROMETER NATURAL RUBBER OR BUTYL RUBBER  
(ISOBUTENE ISOPRENE) OR EQUAL  
(2 REQ'D PER NEXT ASSY)

# 12 GA. CS BACKING  
VULCANIZE I.D.

1 3/8" O.D.  $\Delta$   
C.S. BACKING

1/4"

2	2-11-81	CP	ADC
1	11-4-80	NW	CHAP
0	10/10/80	NW	REI
2	07/08/80	NW	REI

L 3


## LIST OF MATERIALS

OWNER FURN	ITEM	QTY	DESCRIPTION	MATERIAL OR DWG NO.
------------	------	-----	-------------	---------------------

NATURAL RUBBER OR BUTYL RUBBER  
(NE) OR EQUAL  
(XT ASSY)

ING  
D.


2	2-11-81	CP	ADDED C.S. BACKING	006- 323000	AW-3
1	11-4-80	NW	CHANGED MAT'L CALLOUT WAS NATURAL RUB	006- 323000	AW-3
0	10/10/80	NW	RELEASE FOR CONSTRUCTION	001- 210300	AW-3
B	9/27/80	NW	CLARIFY L/M - OPEN UP TOL.	001- 210300	AW-3
A	8/11/80	NW	RELEASE FOR BID	001- 210300	AW-3



SECTION A-A'  $\nabla$   $\triangle$

	APPRC
A.B.S.	
U.S.C.G.	

3/8



# 12 GA. CS BACKING  
VULCANIZE I.D.

13 1/8" O.D.  $\Delta$   
C.S. BACKING


1/4"

2	2-11-81	CP	ADDED
1	11-4-80	NW	CHANGES
0	10/10/80	NW	RELEASE
B	9/27/80	NW	CLARIFY
A	8/11/80	NW	REL

NO.	DATE	BY
-----	------	----

D:001-A004

NO.	REQ'D	NEXT ASSEMBLY
	2	ALTERATION
	2581	DATE
		LOS ANGELES
		NEWPORT BEACH
		HOUSTON
		PURCHASING
		CONSTRUCTION
		ENGINEERING
		USCG
	10	CUSTOMER
	1	WALLERSTEDT
	1	EYE
	1	BUCHANAN
	1	MITCHELL
	1	FARNHAM
	2	LIBRARY



THIS DRAWING  
GLOBAL MARINE  
TO OTHERS OR  
WRITTEN CON  
RETURNED TO

MARINE S  
LATERAL

	APPROVED	EXAMINED OR REVIEWED	ALT. NO.	LETTER DATE	FILE REF. NO.
A.B.S.					
U.S.C.G.					

TOTAL NET WGT. MAT'L	_____
TOTAL NET WGT. EQUIP.	_____
TOTAL NET WEIGHT	_____

Initial	D:
DFT. N. WAGNER	B/11
ENGR. PRR	FK2
CHK. FARNHAM	305
APPR. PRR	10/
REL. R. WAGNER	10/

ING  
D.

NO.	DATE	BY	DESCRIPTION	JOB AUTH.	APPR
2	2-11-81	CP	ADDED C.S. BACKING	006-323000	RAW
1	11-4-80	NW	CHANGED MAT'L CALLOUT WAS NATURAL RUB.	006-323000	RAW
0	10/10/80	NW	RELEASE FOR CONSTRUCTION	001-210300	RAW
B	9/2/80	NW	CLARIFY L/M - OPEN UP TOL.	001-210300	RAW
A	8/11/80	NW	RELEASE FOR BID	001-210300	RAW

001-A004

- NEXT ASSEMBLY
- ALTERATION
- DATE
- LOS ANGELES
- NEWPORT BEACH
- HOUSTON
- PURCHASING
- CONSTRUCTION
- ENGINEERING
- SCG
- CUSTOMER
- WALLERSTEDT
- BYE
- BUCHANAN
- MITCHELL
- EARNHAM
- LIBRARY



## GLOBAL MARINE DEVELOPMENT INC.

Newport Beach, Calif.

THIS DRAWING AND THE DESIGN IT DISCLOSES ARE THE CONFIDENTIAL PROPERTY OF GLOBAL MARINE DEVELOPMENT, INC. AND MAY NOT BE REPRODUCED OR DISCLOSED TO OTHERS OR USED FOR MANUFACTURE OR OTHER PURPOSES WITHOUT THE PRIOR WRITTEN CONSENT OF GLOBAL MARINE DEVELOPMENT, INC. THE DRAWING SHALL BE RETURNED TO GLOBAL MARINE DEVELOPMENT, INC. ON REQUEST.

# MARINE SEISMIC SYSTEM (MSS)

## LATERAL SHOCK ABSORBER RING

### DETAIL

Initial DFT. N. WAGNER ENGR. PRR / CHK. EARNHAM APPR. PRR / REL. R. WAGNER	Dates 8/11/80 9/2/80 30/5/80 10/18/80	SCALE: <b>NONE</b>	TOLERANCE UNLESS OTHERWISE NOTED FRACTION ± 1/16" ANGULAR ± 1/2° MILLIMETER ± 1. MM ( ) DESIGNATES MILLIMETER DIMENSIONS	JOB AUTH. 001-210300	DWG. NO. <b>C • 001 • A006</b>	SHT 1 OF 1	ALT 2
---	---	-----------------------	---	-------------------------	-----------------------------------	---------------	----------



LIST OF MATER

OWNER	ITEM	QTY	DESCRIPTION

10" OD x 9.000" ID TUBING  
 MATL: A191 1020 STEEL (WDOM)  
 MIN YIELD = 60,000 PSI  
 CLIT OFF PIECE & TEST  
 FOR MATERIAL PROPERTIES

MIN THK 1/16"  
 AFTER MACHINING

1/2" x 25" SHPL  
 DO NOT WELD

E-B01B ROD  
 PRE-HEAT 175°

SMOOTH ENTRY

1/2" R MATL: ASTM A-36  
 (5 REQ'D)

E-T-C ROD  
 PRE-HEAT 175°

E-B01B ROD  
 9/16"

SECTION 2-D  
 SCALE: 3/8" = 1"

SECTION 4-D  
 SCALE: 3/8" = 1"

1/2" R MATL: ASTM A-36  
 GR-B (NORMALIZED)  
 MIN YIELD = 60,000 PSI

E-B01B CS ELECTRODE  
 PRE-HEAT 300°F


12-15/16" DIA HOLES  
 ON 14" W.C. TYP (REQ)  
 10" CLASS 150°  
 SP STEEL FLG.

GRIND SMOOTH  
 APPROX 1/2" RAD

TOP VIEW 2-B  
 SCALE: 3/8" = 1"

GENERAL NOTES: (UNLESS

1. ALL WELDING TO BE IN ACCORDANCE WITH AWS D1.1 STRUCTURAL WELDING CODE
2. BREAK ALL EDGES AND CHAMFER
3. MACHINE EDGES AND SURFACES
- 4.
5. PAINT IN ACCORDANCE WITH SPEC. 001-002.



DETAIL 4-A  
 SCALE: 1/2" = 1"

NO.	DATE	BY	DESCRIPTION	ALTERATIONS
2	2-11-81	CP	2. DELETED ITEM 1	
1	11-4-80	NW	REVISED BOLT PATTERN IN TOP VIEW CHANGED MATERIAL CALLOUT ITEM 1 IN L/M WAS N/A	
0	10-16-80	NW	2. CHANGED MAT'L & WELD CALLOUTS IN DET. 4-A SEC. 2-D & TOP VIEW 2-B	
B	7-17-80	NW	1. DELETED GEN. NOTE #4	
A	9-17-80	NW	CLARIFY L/M - OPEN L	
A	9-17-80	NW	RELEASE FOR BID	

E-001-0009

NO.	REQ'D	NEXT ASSEMBLY
1	2	ALTERATION
2	3	DATE
3	4	LOS ANGELES
4	5	NEWPORT BEACH
5	6	HOUSTON
6	7	PURCHASING
7	8	CONSTRUCTION
8	9	ENGINEERING
9	10	USCG
10	11	C. STUMER
11	12	WALL STREET
12	13	BTE
13	14	SILVERMAN
14	15	FITCHELL
15	16	FISHER
16	17	LEWIS



MARINE SEISMIC SURVEILLANCE  
 CENTRAL TOOL STATION  
 ASSEMBLY AND DETAIL

APPROVED	EXAMINED OR REVIEWED	ALT. NO.	LETTER	DATE	FILE REF. NO.	TOTAL NET WT. MAT'L	TOTAL NET WT. EQUIP.	TOTAL NET WEIGHT
ASB								
U.S.C.G.								

CHKD	DATE	SCALE	TOLERANCE
PKR	9/1/79	3/8" NOTED	
PKR	9/1/79		
PKR	9/1/79		
PKR	9/1/79		



6

5

TO BE COMPLETED  
AFTER BIP CARRIAGE  
ASSEMBLY (REF<sup>1</sup>) IS  
INSERTED IN PLACE  
(SEE NOTE #6)

SEE DETAIL 10-D  
NEARSHOE - OPPOSITE  
RHSIDE - SHOWN

SIMILAR TO DETAIL 4-A

① 2 PLACES

⑧ 4 R600 } 2 PLACES  
⑨ 4 R600 }

MATCH DRILL & TAP 1-12UNF-28 THRU  
BIP CARRIAGE HSG, REF DWG #2;  
USING ITEM ① AS A GUIDE  
4 HOLES, 2 PLACES

3/16" 2 PLACES

1/2" x 1/4" x 2 1/2" BAR  
2 PLACES  
BUTTED TO ITEM ①

7/8" 2 PCS

SEE DETAIL 3-D

3 SIDES AWAY  
FROM ITEM ①  
2 PLACES

2 R600 ⑦  
2 PLACES

10' 9" 2 PLACES  
11' 4" 2 PLACES

5 3/16" 2 PLACES

5 3/16" - 2 PLACES

SKID PLATES TO BE SIZED  
AND LOCATED AFTER ASSY

BIP CARRIAGE ASSY.  
SEE REF DWG #1

SEE DETAIL 8-A

SEE DETAIL 12-D  
2 PLACES

SEE DETAIL 8-A

SEE DETAIL 11-D  
SEE DETAIL 2-A  
8 PLACES


BIP CARRIAGE HOUSING  
ASSEMBLY. SEE REF DWG #2


SEE DETAIL 4-A

1" - 6.0 1 WRC  
ETPS GALV  
WIRE ROPE


C

B






**DETAIL 3-D**  
**CONNECTOR PLATE**  
 2 REQD  
 SCALE: HALF SIZE



**DETAIL 2-D**  
 (CYCLOC CHAIN REMOVED FOR SCALE: 3/4"=1'-0")

UNF-2B THRU  
 F DWG 2,  
 GUIDE



REAR HOLE TO .8754 ± .0003  
 THRU UPPER & LOWER PROTECTOR  
 PLATES. 2 HOLES IN LINE -  
 4 PLACES

1/16 WELD THRU  
 W/ 1/4 BEVEL ALL  
 AROUND  
 THIS SIDE ONLY  
 MATCH DRILL  
 DETAIL 2-D

WELD TO TOP  
 OF BAR ONLY

1/2 x 1/2 x 4 LG BAR (4 REQD)  
 REAR HOLE TO .8754 ± .0003 THRU  
 BIP CARRIAGE ASSY  
 2 HOLES IN LINE - MATCH DRILL  
 AND PROTECTOR PLATES - REF DWG 01  
 4 PLACES  
 1/2 x 2 1/2 x 1/8 DIA.  
 (4 REQD)

2 REQD } 8 PLACES  
 2 REQD }


**DETAIL 2-C**  
**CABLE RETENTION PLATE**  
 SCALE: 3/4"=1'-0"

3/16 CHAIN, 36" LONG  
 HOT DIPPED GALVANIZED

-TACK WELD


.3221.005"  
 DIA THRU  
 2 HOLES

1/2 R  
 2 PLACES



DETAIL 2-D

(HYDRAULIC CYLINDER REMOVED FOR CLARITY)  
SCALE: 3"=1'-0"



DETAIL 2-C  
CABLE RETENTION PLATE  
SCALE: 3"=1'-0"

LIST OF MATERIALS			
ITEM	QTY	DESCRIPTION	REMARKS
1	2	4" BORE, 12" STROKE SERIES "2H" HEAVY DUTY HYDRAULIC CYLINDER STYLE C (NPPA MP) W/SS ROD & THREAD STYLE 42 200 END 1 1/4-12 THREAD W/AM NUT CUSHIONED BLIND END	AS BUILT
2	1	2" BORE, 2" STROKE SERIES "2H" HEAVY DUTY HYDRAULIC CYLINDER STYLE J (NPPA MP) W/SS ROD & END STYLE 9	
3	16	WASHER, LOCK - 1/4" I.D. X 1/2" THK	SS
4	16	BOLT, HEX HD, 1/4-20 THD X 1 1/2" LONG	SS
5	4	1/2" CLOSED SPILTER SOCKET	
6	4	1/8" COTTER PIN	
7	4	BOLT, ELEVATOR SOCKET FOR 1/2" DIA WIRE ROPE 8" SHANK W/4" THD LENGTH	94777-5 BERNER-TITENBERG COPPER EQUAL
8	8	WASHER, LOCK - 1" I.D. X 1/8" THK	SS
9	8	BOLT, HEX HD, 1-12 UNF -2A X 1 3/4" LG	SS

LIST OF MATERIAL CONT ON SHIT 2

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36 OR EQUIV.
2. ALL WELDING TO BE IN ACCORDANCE WITH AWS D1.1 STRUCTURAL WELDING CODE - STEEL.
3. ALL MACHINE SURFACES TO BE 125.
4. BREAK ALL SHARP EDGES & REMOVE ALL BURRS.
5. PAINT IN ACCORDANCE WITH ENO'S SPEC 001, P02.
6. ALL WELDS THIS ASSY SHALL USE E 7018 ELECTRODE.
7. GENERAL TOLERANCES ON DECIMAL DIMENSIONS:  
 .X = .01  
 .XX = .02  
 .XXX = .010

REFERENCE DRAWINGS

- 1. D-001-A004 MARINE GEINAC SYSTEM (NPPA) SHIP CARRIAGE HOUSING (SEE DETAILS)
- 2. E-001-A005 MARINE GEINAC SYSTEM (NPPA) SHIP CARRIAGE HOUSING ASSEMBLY AND DETAILS

ALTERATIONS CONT ON SHIT 2 ZONE 7-A

1	7	ADDED S/N 7.	
2	8	ADDED SKID PLATES.	
3	9	REMOVED PICTURE TO AGREE W/SHORE SUPPORT CHG.	
4	10	DELETED TUBE CALLOUT.	
5	11	CHANGED CALLOUT FOR NEW PIN.	

.8221.005" DIA THRU 2 HOLES  
1/8" R 2 PLACES

8 SIDES AWAY FROM ITEM ①  
2 PLACES

2 REED ⑦  
2 PLACES

10'9" 2 PLACES  
11'4" 2 PLACES

TYP 3/8

5 7/8" 2 PLACES

5 7/8" - 2 PLACES

SKID PLATES TO BE SIZED AND LOCATED AFTER ASSY

DIP CARRIAGE ASSY. SEE REF DWG #1

SEE DETAIL 8-A

SEE DETAIL 12-D  
6 PLACES

SEE DETAIL 8-A

SEE DETAIL 11-D  
SEE DETAIL 2-A  
8 PLACES

DIP CARRIAGE HOUSING ASSY. SEE REF DWG #2

1" - 6.2" 1 WRC  
ETPS GALV  
WIRE ROPE

SEE DETAIL 4-A

SEE DETAIL 10-D  
NEAR SIDE - SHOWN  
FAR SIDE - OPPOSITE

SEE DETAIL 2-D

2 7/8" REF

TO BE COMPLETED AFTER DIP CARRIAGE ASSEMBLY (REF #1) IS INSERTED IN PLACE (SEE NOTE #6)

12-A

12-A

3 3/8" 4 PLACES

ELEVATION 6-A  
SCALE: 1"=1'-0"

6

5

4



0003  
ECTOR

1/16" HOLE THRU  
W/1/4" BEVEL ALL  
AROUND  
THIS SIDE ONLY  
MATCH DRILL  
DETAIL 2-D

1/16" CHAIN, 30" LONG  
HOT DIPPED GALVANIZED

- TACK WELD

**DETAIL 2-C**  
CABLE RETENTION PLATE  
SCALE: 3/4"=1"

**GENERAL NOTES:** (UNLESS OTHERWISE NOTED)


1. ALL MATERIAL TO BE ASTM A-26 OR EQNAC.
2. ALL WELDING TO BE IN ACCORDANCE WITH AWS D1.1 STRUCTURAL WELDING CODE - STEEL.
3. ALL MACHINE SURFACES TO BE 125.
4. BREAK ALL SHARP EDGES / REMOVE ALL BURRS.
5. PAINT IN ACCORDANCE WITH ENGI SPEC COM-100.
6. ALL WELDS THIS ASSY SHALL USE E 7018 ELECTRODE.

7. GENERAL TOLERANCES ON DECIMAL DIMENSIONS
- .K = .01
  - .IX = .03
  - .XXX = .010

**REFERENCE DRAWINGS**

- 1. D-001-A004 MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE HOUSING ASSEMBLY AND DETAILS
- 2. E-001-A005 MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE HOUSING ASSEMBLY AND DETAILS

0)  
003 THRU  
DRILL  
REF DWG #1



**DETAIL 2-A**  
COVER  
SCALE: FULL

**ALTERATIONS CONT ON SHT 2 ZONE T-A**

1	1/16" R	11. ADDED G/A 7. 10. ADDED SKID PLATES. 9. REVISED PICTURE TO ADD W/SHEAVE SUPPORT CHS. 8. DELETED TUBE CALLOUT. 7. CHANGED CALLOUT FOR NEW PIN. 6. COMPLETELY REVISED PIN. 5. REVISED DIMENSIONS / 7/16 TO DECIMALS. 4. REVISED GUSSET / CHG DIMS. 3. REVISED DIMENSIONS. 2. ADDED VIEW. 1. REVISED SHEAVE SUPT. GUSSETS	001-210800
0	1/16" R	ONE COMPLETELY REVISED ADDED SHEET 2 RELEASED FOR CONSTRUCTION	001-210800
B	1/16" R	CLARIFY LAM - OPEN UP TOL	001-210800
A	1/16" R	RELEASE FOR BID	001-210800

NO.	DESCRIPTION	REVISED	DATE
1	1/16" R	11. ADDED G/A 7.	
2	1/16" R	10. ADDED SKID PLATES.	
3	1/16" R	9. REVISED PICTURE TO ADD W/SHEAVE SUPPORT CHS.	
4	1/16" R	8. DELETED TUBE CALLOUT.	
5	1/16" R	7. CHANGED CALLOUT FOR NEW PIN.	
6	1/16" R	6. COMPLETELY REVISED PIN.	
7	1/16" R	5. REVISED DIMENSIONS / 7/16 TO DECIMALS.	
8	1/16" R	4. REVISED GUSSET / CHG DIMS.	
9	1/16" R	3. REVISED DIMENSIONS.	
10	1/16" R	2. ADDED VIEW.	
11	1/16" R	1. REVISED SHEAVE SUPT. GUSSETS	

**GLOBAL MARINE DEVELOPMENT INC.**  
Morgan Road, Calif


**MARINE SEISMIC SYSTEM (MSS)  
BIP CARRIAGE HOUSING  
MAIN ASSEMBLY**

REVISED	DATE	BY	DESCRIPTION
001-210800			

4


12

11




**DETAIL 12-D**


**SHEAVE**  
 S REQD - MAT'L: TOBIN BRONZE  
 PER QQ-N-35  
 SCALE: HALF SIZE



1/4-20 UNC-2B  
 THRU - 2 HOLES




**DETAIL 11-D**  
**SHEAVE PIN**  
 S REQD - MAT'L: S16 CRES  
 SCALE: HALF SIZE



**DETAIL 12-C**  
**SPACER**  
 SCALE: HALF SIZE

5 PLACES  $\frac{3}{16}$  V



1/4-20 UNC-2B -  
 THRU - 2 HOLES

1/2 x 1/2 x 2 1/4 BAR


1/2" R  
 TYP

TYP ALL CONTACT SURFACES BETWEEN PLATES  $\frac{1}{8}$  V

10


9

8




DETAIL 10-D

SHEAVE SUPPORT  
SHEAVE AND PIN OMITTED FOR CLARITY  
SCALE: HALF SIZE




DETAIL 8-B

SHEAR PIN  
4 REQUIRED  
SCALE: FULL SIZE




BIP CARRIAGE HSG  
REF #2

TYP ALL CONTACT  
SURFACES BETWEEN PLATES



DETAIL 8-C

4 PLACES  
SCALE: FULL SIZE




2

1

3

7




1/2" RND BAR  
MATERIAL: ALUM. 6061-T-6  
40,000 PSI YIELD

DETAIL 8-D

SHEAR PIN  
4 REQUIRED  
SCALE: FULL SIZE

LIST OF MATERIALS			
ITEM	QTY	DESCRIPTION	NOTE
10	4	.5156 ID $\frac{1}{8}$ DD 1 1/4 DRILL BUSHING 30° BEVEL AMERICAN OR EQV	
11	8	.5156 ID $\frac{1}{8}$ DD 1 1/4 DRILL BUSHING AMERICAN OR EQUIV	
12	8	.5156 ID $\frac{1}{8}$ DD 1 1/4 DRILL BUSHING 30° BEVEL AMERICAN OR EQUIV	
13	4	1/8 x 1 1/2 16 CUTTER PIN	
14	4	1/8 13 UNC 2 RA 1 1/2 IN HEX BOLT	SS
15	4	1/8 LOCK WASHER	SS




DETAIL 8-C

4 PLACES  
SCALE: FULL SIZE


D

C




B



**DETAIL 12-C**  
**SPACER**  
 SCALE: HALF SIZE



**SECTION 12-A**  
 SCALE: 3"=1'-0"





12


4

11



1/4" x 45



**DETAIL 8-C**  
 4 PLACES  
 SCALE: FULL SIZE



**DETAIL 10-B**  
**SHEAVE SUPPORT**  
 4 REQD  
 2 ORIENTATED AS SHOWN  
 2 ROTATED  $90^\circ$   
 SHEAVE, PIN & COVER OMITTED FOR CLARITY  
 SCALE: HALF SIZE




**DETAIL 8-A**  
**THRUST WASHER**  
 MATERIAL:  $\frac{1}{4}$  HARD BRASS  
 16 REQD  
 SCALE: HALF SIZE

10

9


11

5




**DETAIL 8-C**

1 PLACES  
SCALE: FULL SIZE



2



**DETAIL 8-A  
THRUST WASHER**

MATERIAL: 1/2 HARD BRASS  
16 REQD  
SCALE: HALF SIZE

2	2	REVISED DETAIL 2-C	006-
23	23	CHANGED SHEAR PINS IN	329000
6	6	DET. 4-A, DELETED DET. 4-B	
		REVISED DETAILS 8-C, 8-D	
		ADDED 1/2" DIA. J. W.R.C.	
		WIRE ROPE, DET. 6-A	
		ADDED ITEM 13 (HYDRAULIC	
		CYLINDER) IN DET. 6-A	
		DETAIL 2-D & SECT. 12-A	
		3 REVISED SHEAVE SUPPORTS	
		DETAIL 10-B & 10-D	
		CHANGED HOLE DIA TO 2 1/2"	
		ADDED 1 1/2" DIA. DETAIL 12-C	
		ADDED ITEM 12, 13, 14, 15	
		DETAIL OF MATERIALS COMPLETE	
REVISED BY		DESCRIPTIONS	DATE
		BY: [Signature]	

**GLOBAL MARINE DEVELOPMENT INC.**  
Rising Star, Calif.

**MARINE SEISMIC SYSTEM (MS)**  
BIP CARRIAGE HOUSING  
MAIN ASSEMBLY

REV. NO. 001-20000  
E-001-A008-32

C  
B  
A

6


6

5

D

C

B



DIP CARTRIDGE CONTROL SUB  
SEE REF DWG#1

121

DIP CARTRIDGE HOUSING  
MAIN ASSY SEE REF DWG#2

DIP  
SEE REF DWG#5


67-711 REF

CONTROL SUB

2

4

3



2

3

2


1

LIST OF MATERIALS				
ITEM NO.	QTY.	DESCRIPTION	UNIT	REMARKS
1	24	7/8"-14 UNC 2A x 9 1/2" LH ACERONON RESISTING BOLT		ASTM A325 TYPE 3
2	24	7/8" FLAT WASHERS		
3	24	7/8" LOCK WASHER		
4	24	7/8"-14 UNC 2B COBOLTS RESISTING NUT		ASTM A325 TYPE 3
F-1	6	6-6-10TX-MALE ELBOW		
F-2	2	6-6-10TX UNION		
F-3	1	6-6-10TX MALE BRANCH TEE		
F-4	1	1/2" RIPTURE DMK. SOLID DISK SET AT 2800 PSI		
F-5	2	6-6-10TX MALE CONNECTOR		
F-6		1/2" x .065 SEAMLESS TUBING, 10-8 TYPE 304 1/8" HARD		

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

- 1. ALL TUBING FITTING ARE JK 37 1/2° FLAIR TYPE DESCRIPTION IS PER PARKER HANNIFIN CATALOG 4310 REV. SEPT 1968
- 2. HYDRAULIC PIPING RUN TO BE DETERMINED BY MANUFACTURE.

ELEVATION 2-C




HYDRAULIC FLUG/SONAR ADAPTOR  
SEE REF. DRAW. 4

REFERENCE DRAWINGS:


- 1. E-001-A005 MARINE SEISMIC SYSTEM (MSS) SHIP CARRIAGE CONTROL SUB DETAILS AND ASSEMBLY
- 2. E-001-A006 MARINE SEISMIC SYSTEM (MSS) SHIP CARRIAGE HOUSING MAIN ASSEMBLY
- 3. D-001-A007 MARINE SEISMIC SYSTEM (MSS) REENTER TOOL STRIKE ASSEMBLY AND DETAILS
- 4. D-001-A010 MARINE SEISMIC SYSTEM (MSS) HYDRAULIC FLUG/SONAR ADAPTOR DETAILS

TELEPHONE GEOTECH DRAWINGS.

C



D




6

5

4

DIP  
-SEE REF DWG #1




4 3 2 1

RECHINA TOOL STINGER  
SEE REF DWG #3

HYDRAULIC FLUID/SOONAR ADAPTOR  
SEE REF DWG #4

VENT TO SEA

HYDRAULIC CYLINDER  
4" BORE, 12" STROKE  
2 REQ'D. SEE REF DWG #2



DRILL 1/8" DIA HOLE  
IN TUBING BELOW  
SURFACE OF SEA &  
ABOVE 2" BORE  
HYDRAULIC CYLINDER

HYDRAULIC CYLINDER  
2" BORE, 12" STROKE  
SEE REF DWG #2

### HYDRAULIC SCHEMATIC NT-5


REV	DATE	BY	CHK	APP


U13

**GENERAL NOTES: (UNLESS OTHERWISE NOTED)**

1. ALL TUBING FITTING ARE JIC 37 1/2 FLAIR TYPE DESCRIPTION IS PER PARKER HANNIFIN CATALOG 4310 REV. SEPT 1968

2. HYDRAULIC PIPING RUN TO BE DETERMINED BY MANUFACTURE.



ELEVATION 2-C

HYDRAULIC PLUG/SONAR ADAPTOR  
SEE REF DWG #4

**REFERENCE DRAWINGS:**

- 1. E-001-A003 MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE CONTROL SUB DETAILS AND ASSEMBLY
- 2. E-001-A008 MARINE SEISMIC SYSTEM (MSS) BIP CARRIAGE HOUSING MAIN ASSEMBLY
- 3. D-001-A007 MARINE SEISMIC SYSTEM (MSS) REENTRY TOOL STINGER ASSEMBLY AND DETAILS
- 4. D-001-A010 MARINE SEISMIC SYSTEM (MSS) HYDRAULIC PLUG/SONAR ADAPTOR DETAILS

**TELETYPE GEOTECH DRAWINGS:**

5. 990-53100 BIP

NO.	DATE	BY	DESCRIPTION	JOB NO.	APP.
1	07/18/68	HW	CHANGED ITEM R-4 TO 2800PSI WAS 3500	205-275000	HW
0	07/18/68	HW	2. ADDED NOTE #2 1. REVISED ELEV. 2-C PER REF. DWG #2 CHANGES	001-210300	HW
0	07/18/68	HW	REDRAWN FOR CLARITY	001-210300	HW
A	07/18/68	HW	RELEASE FOR BID	001-210300	HW

NO. REV.	NEXT ASSEMBLY
1	ALTERNATION
1-14	DATE
	PURCHASING
	CONSTRUCTION
	ENGINEERING
	WELD
	ASS
10	CUSTOMER
1	WALLER/DEPT
1	PYS
1	BUCHHEIM
1	MITCHELL
1	FARRIS
2	LEIGHT



**GLOBAL MARINE DEVELOPMENT INC.**  
Newport Beach, Calif.

THIS DRAWING AND THE DESIGN OF ANYTHING THEREON ARE THE PROPRIETARY PROPERTY OF GLOBAL DEVELOPMENT, INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT EXPRESS PERMISSION. ALL THE DRAWING SHALL BE RETURNED TO GLOBAL DEVELOPMENT, INC. UPON REQUEST.

**MARINE SEISMIC SYSTEM (MSS)  
BIP REENTRY TOOL  
ASSEMBLY**

APPROVE	DESIGNED OR REVISED	DWT. NO.	LITTER DATE	FILE NO.	TOTAL NET WT. SHT.
AWB					TOTAL NET WT. SHIP
BACE					TOTAL NET WEIGHT





DATE	BY	SCALE	TOLERANCE UNLESS OTHERWISE NOTED
07/18/68	N. WAGNER	1/2" = 1" 0	FRACTIONS - 1/8" ANGULAR - 1/2"
07/18/68	HW	AS NOTED	UNLESS OTHERWISE SPECIFIED
07/18/68	HW	001	UNLESS OTHERWISE SPECIFIED
07/18/68	HW	210300	

2

1

6

GROOVE DETAIL  
2 REQ'D  
NTS



SECTION A-A  
② SNAP RING

2	2-1981	3 DELETED NOTE # 5 2 ADDED (1) MORE O-RING & GROOVE TO L/M & PLUG 1 ADDED 4 SLOTS RT BOTTOM OF PLUG
1	11-80	3. CHANGED: WAS 8.120/8.123 2. ADDED: M&R, 14°, 8.230 1. DELETED: 8 DIA, 6.50, 15°, 30°, 8, 4.160/4.175
NO.	DATE BY	DESCRIPTION ALTERATIONS








4

3

2



**DETAIL 3-C**  
**LOWER SHOE**




2

B

2


1

LIST OF MATERIALS				
QUANTITY	ITEM	QTY.	DESCRIPTION	MATERIAL OR SPEC. NO.
1	2		BOLT, $\frac{3}{4}$ "-10UNC-1A x $1\frac{3}{4}$ " LONG, HOT DIP GALV	
2	2		NUT, $\frac{3}{4}$ "-10UNC-1B HOT DIP GALVANIZED	



GENERAL NOTES: (UNLESS OTHERWISE NOTED)


1. ALL PLATES & SHAPES TO BE PER ASTM A-36.
2. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.
3. BREAK ALL SHARP EDGES & REMOVE ALL BURRS.



D

C


B



TACK WELD IN PLACE BOTH SIDES

BREAK INTERNAL EDGE WITH GENEROUS BLEND RADIUS

**ELEVATION 6-A**  
WELDMENT




6 5 4


4

1

**DETAIL 3-C**  
**LOWER SHOE**



**DETAIL 3-B**  
**UPPER SHOE**



APPROVED	DESIGNED OR REVISED	ACT. NO.	LETTER	FILE NO.
ASA				
USA				


5



15-A




SEE REF DWG #2

PLAN 4-  
PICCOLO SUPP  
SCALE: 3/4"




2

2



**DETAIL 3-C**  $\Delta$   
SCALE: 5" = 1'-0"



SEE DETAIL 3-C

SEE REF DWG #1  
CABLE PROTECTOR

SEE DETAIL 3-A



2

3

2

1

LIST OF MATERIALS			
QTY	NO.	QTY	DESCRIPTION
△	1	2	3/8"-10 UNF 2A x 2" LH HEX BOLT - HOT DIP GALV
	2	4	WASHER, FLAT, 3/8" HOT DIP GALVANIZED
△	3	6	3/8"-10 UNF 2B HEX NUT - HOT DIP GALV
△	4	2	3/4"-10 UNF 2A x 2 1/2" LH HEX BOLT - HOT DIP GALV




LOCATE FROM UPPER SHOE  
& TACK WELD IN PLACE

SEE REF DWG #1, DETAIL 3-B  
UPPER SHOE

**3-C** △  
3'-1'-0"

GUIDE SHOE - SEE REF DWG #3




REFERENCE DRAWINGS

1. E-001-AD13 EM CABLE PROTECTOR AND DETAILS AND ASBY
2. E-377-5040 GLOMAR II SUPPORT - SOFT PICCOLO AND GUIDE SHOE
3. E-377-3004 GLOMAR II GUIDE SHOE ARRANGEMENT & DETAILS

D

C

PLAN 4-0  
PICCOLO SUPPO  
SCALE:  $\frac{3}{4}$ " = 1'-0"




SEE REF DWG #2


SECTION 4  
SCALE:  $\frac{3}{4}$ " = 1'-0"

4


**PLAN 4-C**  
**PICCOLO SUPPORT**  
SCALE:  $\frac{3}{4}$ " = 1'-0"



**DETAIL 3-C**  $\Delta$   
SCALE: 5" = 1'-0"



SEE REF DWG #1  
CABLE PROTECTOR



SEE DETAIL 3-A

SEE REF DWG #2

GUIDE SHOE - SEE REF DWG #3

**SECTION 4-A**  $\Delta$   
SCALE:  $\frac{3}{4}$ " = 1'-0"

**DETAIL 3-A**  
SCALE: 2" = 1'-0"


C


B

A

3-C  $\Delta$

3'-1'-0"

GUIDE SHOE - SEE REF DWG #3



REFERENCE DRAWINGS

- 1. E-001-A013 EM CABLE PROTECTOR AND DETAILS AND ASSY
- 2. E-377-5040 GLOMAR II SUPPORT-SOFT PICCOLO AND GUIDE SHOE
- 3. E-377-5004 GLOMAR II GUIDE SHOE ARRANGEMENT & DETAILS

GUIDE SHOE - SEE REF DWG #3

$\Delta$   
3'-1'-0"

NO.	DATE	BY	DESCRIPTION	APP.
1	3-5-81	NW	REVISED SECT 4-A, DET 2-C, ITEM #1 & ADDED ITEMS #3 & 4	006-528000
0	11-18-80	ND	RELEASE FOR CONSTRUCTION	006-528000 (A)

1	3-5-81	NW	REVISED SECT 4-A, DET 2-C, ITEM #1 & ADDED ITEMS #3 & 4	006-528000
0	11-18-80	ND	RELEASE FOR CONSTRUCTION	006-528000 (A)

**GLOBAL MARINE DEVELOPMENT INC.**  
Support Boat, Calif.

**MARINE SEISMIC SYSTEM (MSS)  
EM CABLE PROTECTOR  
INSTALLATION ARRANGEMENT**


APPROVED	CHANGED OR REVISED	BY	DATE	TOTAL NET WT. SHIP

NOTED	00006-528000	E-001-A014	1


2

1




6




**DETAIL 6-D**  
SCALE: 3/4"=1'-0"





**SECTION**  
2"



2



**SECTION 6-D**  
2 REQUIRED



RELATE TO  
6-D

RELATE TO  
74-D

2

1

3

## LIST OF MATERIALS

ORDER PLUM	ITEM	QTY.	DESCRIPTION	REMARKS OR SPEC. REQ.
	1	10	$\frac{1}{2}$ "-18 UNC 2A x $1\frac{3}{4}$ " LG HEX BOLT	
	2	10	$\frac{1}{2}$ " PLAIN WASHER	
	3	10	$\frac{1}{2}$ " LOCK WASHER	
	4	10	$\frac{1}{2}$ "-18 UNC 2B HEX NUT	

GENERAL NOTES: (UNLESS OTHERWISE NOTED)


1. ALL MATERIAL TO BE ASTM A-36.
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. ALL WELDS TO BE  $\frac{3}{16}$ " CONTINUOUS FILLET TYPE.
4. FOR DECK LOCATION ON GLOMAR CHALLENGER SEE REF. DWG #1.

REFERENCE DRAWINGS:

- 1 E-001-A02B MARINE SEISMIC SYSTEM (MSS)  
GLOMAR CHALLENGER EQUIPMENT  
INSTALLATION ARRANGEMENT

2'-0"

B




1/2 TYP

VIEW 6-A

A

15'-6"

6'-0"




6

5

4

2'-0"



ELEVATION 4-A

	APPROVED	EXAMINED OR REVIEWED	ALT. NO.	LETTER DATE	FILE NO.
AAA					
BAE					

4

3

2


5



6

5

D




C

B

4-1D

4-1L

9





DRILL HOLE, 4 PLCS  
MATCH DRILL W/  
ITEM 2

7 1/2

6-3A


3





VIEW 4-D

TO HEAVE COMPENSATOR



2

L

2

3

1

LIST OF MATERIALS				
QUANTITY	ITEM	QTY.	DESCRIPTION	REMARKS OR SUPP. NO.
X	1	1	LINE TENSION MONITOR	MARTIN DECKER
X	2	1	LINE SPEED & LENGTH MONITOR	MARTIN DECKER
X	3	4	NITROGEN BOTTLE	
	4	8	$\frac{5}{16}$ "-18 UNC 2A x $1\frac{1}{2}$ " LG HEX BOLT	
	5	8	$\frac{5}{16}$ " PLAIN WASHER	
	6	8	$\frac{5}{16}$ " LOCK WASHER	
	7	8	$\frac{5}{16}$ "-18 UNC 2B HEX NUT	
	8	10	$\frac{1}{2}$ " PIPE SUPPORT CLAMP	
	9	1	12" GAUGE (W/12 INDICATOR W/CONNECTOR 30,000 CAP.)	MARTIN DECKER

REFERENCE DRAWINGS:

- 1.E-001-A018 MARINE SEISMIC SYSTEM (MSS)  
HEAVE COMPENSATOR CONTROL  
BOARD - DETAILS & ASSEMBLY
- 2.E-001-P001 MARINE SEISMIC SYSTEM (MSS)  
HEAVE COMPENSATOR PIPING  
DIAGRAM (SUPPLIED BY OTHER)


C

B

C


B

A



VIEW G-A

HOLE, 4 PLS  
MATCH DRILL W/  
ITEM ②



G-A

ELEVATION

PIPING & VALVES  
SEE ELEC. DRAW. 2

TO HEAVE COMPENSATOR

3/8" HOLE, 4 PLCS  
MATCH DRILL W/  
ITEM ①

2 1/2"

④ ⑤ ⑥ ⑦

HEAVE COMPENSATOR  
CONTROL BOARD - SEE  
REF DWG # 1

④ REF  
⑤ REF  
⑥ REF  
⑦ REF

⑨

ELEVATION 6-A




4 1 3 1 2

5

**REFERENCE DRAWINGS:**

- 1. E-001-A01B MARINE SEISMIC SYSTEM (MSS) HEAVE COMPENSATOR CONTROL BOARD - DETAILS & ASSEMBLY
- 2. E-001-P001 MARINE SEISMIC SYSTEM (MSS) HEAVE COMPENSATOR PIPING DIAGRAM (SUPPLIED BY OTHER)

2	03/21/81	ADDED ITEM 9 TO LHM ELEV 4-A	006 029000
1	11/24/80	CHANGED NEXT ASSY WAS E-001-A01B	006 029000
0	11/24/80	RELEASE FOR CONSTRUCTION	006 029000

E-001-A02D	
NO. REV'S	REVISIONS
1	ISSUE
2	DESIGN
3	CONSTRUCTION
4	ENGINEERING
5	ISSUE
6	ISSUE
7	ISSUE
8	ISSUE
9	ISSUE
10	ISSUE
11	ISSUE
12	ISSUE
13	ISSUE
14	ISSUE
15	ISSUE
16	ISSUE
17	ISSUE
18	ISSUE
19	ISSUE
20	ISSUE



**GLOBAL MARINE DEVELOPMENT INC.**  
*Mariposa Beach, Calif.*

THIS DRAWING AND THE DATA IT CONTAINS ARE THE CONFIDENTIAL PROPERTY OF GLOBAL DEVELOPMENT, INC. AND ARE NOT TO BE REPRODUCED OR DISCLOSED TO OTHERS WITHOUT THE WRITTEN PERMISSION OF GLOBAL DEVELOPMENT, INC. THE GLOBAL GROUP OF COMPANIES IS AN EQUAL OPPORTUNITY AND AFFIRMATIVE ACTION EMPLOYER.

**MARINE SEISMIC SYSTEM (MSS)  
INSTRUMENTATION & CONTROLS  
INSTALLATION**

APPROVED	DESIGNED BY	REV. NO.	LETTER	DATE	REV. NO.	DATE
AAA						
SSS						

BY: N. WILSON	DATE: 11-23-80	SCALE: 1/4" = 1'-0"	TOLERANCE UNLESS OTHERWISE NOTED FRACTIONS - 1/32" ANGLES - 1/4"
CHK: N. WILSON	DATE: 11-24-80	DATE: 11-24-80	RELEASED - 11/24/80
APP: [Signature]	DATE: 11/24/80	DATE: 11/24/80	ISSUED BY: [Signature]
		006 029000	E-001-A02D


2

1

6

6

5




**DETAIL G-D**

SCALE: HALF SIZE  
2 REQ'D

D

C


B



65E


1'

2




**SECTION 3-11**

SCALE: 1 1/2" = 1'-0"




**SECTION 3-12**

4 1/16" DRILL THRU



SCALE

SEE DETAIL 6-13



**SECTION 3-13**

SCALE: 1 1/2" = 1'-0"

9/16" @ TOP & BOTTOM (4 REQ'D)

3-13


3

2

1


LIST OF MATERIALS

QTY	ITEM	CITY	DESCRIPTION	DATE



SECTION 3-1D

SCALE: 1 1/2" = 1'-0"




GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36.
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GMDI SPEC. 001-002.
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.

C

B



**PLAN 5-A**  
SCALE: 1/2" = 1'-0"

1/2" x 45° S.W.P.B.

C


B

6

5

4

SCALE: 3" = 1'-0"




SEE DETAIL 6-13


9"x16" @ TOP & BOTTOM (4 REQ'D)

**SECTION 3-B**


SCALE: 1/2" = 1'-0"



SCALE: 3" = 1'-0"



SCALE: 3" = 1'-0"



SCALE: 1/4" = 1'-0"

NO.	APPROVED	REVISIONS OR COMMENTS	DATE	LETTER	BY	TOTAL
1	ASA					TOTAL
2	ASA					TOTAL

4

3


2

1

5

**GENERAL NOTES: (UNLESS OTHERWISE NOTED)**

1. ALL MATERIAL TO BE ASTM A-56.
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GMDI SPEC. 001-002.
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.



WEEP HOLE

DRILL THRU

**E-001-AD25**

NO.	DATE	BY	DESCRIPTION	ALTERATIONS
1			DESIGN	
2			CONSTRUCTION	
3			INSPECTION	
4			AS BUILT	
5			REVISION	
6			REVISION	
7			REVISION	
8			REVISION	
9			REVISION	
10			REVISION	
11			REVISION	
12			REVISION	
13			REVISION	
14			REVISION	
15			REVISION	
16			REVISION	
17			REVISION	
18			REVISION	
19			REVISION	
20			REVISION	

NO.	DATE	BY	DESCRIPTION	ALTERATIONS
1	5/18/81	ADT	ADDED SECT. 3-D	
2	7/28/81	NW	RELEASE FOR CONSTRUCTION	000-515000
3	7/28/81	NW	PRELIMINARY RELEASE	000-515000



**GLOBAL MARINE DEVELOPMENT INC.**  
Marport Beach, Calif.

THIS DRAWING AND THE DESIGN IT SHOWS ARE THE PROPERTY OF GLOBAL MARINE DEVELOPMENT, INC. AND SHOULD BE KEPT IN CONFIDENCE AND NOT REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF GLOBAL MARINE DEVELOPMENT, INC. AND SHOULD BE DESTROYED IF NOT KEPT IN CONFIDENCE.

**MARINE SEISMIC SYSTEM (MSS)  
A-FRAME  
DETAILS & ASSEMBLY**

APPROVED	DESIGNED OR REVISED	DATE	LETTER	DATE	BY	DATE
ADT						
ADT						
ADT						


NO.	DATE	BY	DESCRIPTION	ALTERATIONS
1	7-28-81	ADT	AS BUILT	
2	7-28-81	ADT	AS BUILT	
3	7-28-81	ADT	AS BUILT	
4	7-28-81	ADT	AS BUILT	
5	7-28-81	ADT	AS BUILT	
6	7-28-81	ADT	AS BUILT	
7	7-28-81	ADT	AS BUILT	
8	7-28-81	ADT	AS BUILT	
9	7-28-81	ADT	AS BUILT	
10	7-28-81	ADT	AS BUILT	
11	7-28-81	ADT	AS BUILT	
12	7-28-81	ADT	AS BUILT	
13	7-28-81	ADT	AS BUILT	
14	7-28-81	ADT	AS BUILT	
15	7-28-81	ADT	AS BUILT	
16	7-28-81	ADT	AS BUILT	
17	7-28-81	ADT	AS BUILT	
18	7-28-81	ADT	AS BUILT	
19	7-28-81	ADT	AS BUILT	
20	7-28-81	ADT	AS BUILT	

NO. 001-AD25

6


5

D



ACTUAL LOCATION OF MOUNTING LUGS C TO BE DETERMINED DURING ABOARD SHIP INSTALLATION

C



B

1

2

1


6" ANGLE (TYR)

PLATE (2-PL'S)

2" DIA. DRILL THRU (TYR. & R.S.)

1 1/2"

AS NOTED



1


3

2

1

LIST OF MATERIALS

QUANTITY	ITEM	QTY.	DESCRIPTION	INTERNAL OR EXTERNAL



DERRICK SUB BASE  
SEE REF DNG #1

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36
2. BREAK ALL EDGES & REMOVE ALL BURRS
3. PAINT IN ACCORDANCE WITH GMDI SPEC. 001-002
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES
5. ALL WELDS TO BE 3/8" CONTINUOUS FILET

REFERENCE DRAWING:

1-T-54-54-SIG DERRICK SUB BASE  
DETAILS

(REF)





DERRICK SUB BASE  
SEE REF DWG #1

5D

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36
2. BREAK ALL EDGES & REMOVE ALL BURRS
3. PAINT IN ACCORDANCE WITH GMDI SPEC 001-002
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES
5. ALL WELDS TO BE  $\frac{3}{8}$ " CONTINUOUS FILET

REFERENCE DRAWING:

- 1-T-34-54-SIG DERRICK SUB BASE  
DETAILS

4 1/2" (REF)

(4) GUSSETS 1/2" PLT

12" (TYR)

MAIN DECK

BULKHEAD AT 20'-0" OF  $\phi$  SHIP  
(REF)

ELEVATION-2C (LOOKING FWD- PORT SIDE)  
SCALE: NONE

1	3-30-87	ADDED 1/2" GUSSET DETAIL	006-323000
0	7-20-86	RELEASE FOR CONSTRUCTION	006-323000
A	12-5-86	PRELIMINARY RELEASE	006-323000

E001 A028

NO.	REV.	DESCRIPTION
1		REVISION
2		REVISION
3		REVISION
4		REVISION
5		REVISION
6		REVISION
7		REVISION
8		REVISION
9		REVISION
10		REVISION
11		REVISION
12		REVISION
13		REVISION
14		REVISION
15		REVISION
16		REVISION
17		REVISION
18		REVISION
19		REVISION
20		REVISION

**GLOBAL MARINE DEVELOPMENT INC.**  
Shannon Bank, Calif.

MARINE SEISMIC SYSTEM (MMS)  
A FRAME SUPPORT TO SUB BASE  
DETAILS AND ASSEMBLY

APPROVED	DESIGNED OR REVISED	ALT. NO.	LETTER	DATE	NO. OF SHEETS	TOTAL NO. SHEETS	DATE	NO.	DESCRIPTION	DATE	NO.	DESCRIPTION

2

1

6

6

5

15-A

LGXG $\frac{1}{2}$   
FITTED TO PLACE  
AT NEXT ASSY.


(RE

INSTALL )  
AT NEXT

$\frac{1}{2}$ "X45° SNIP

D

C



3-C

15-A

INSTALL 1/2" STIFFNER  
TO W36X170  
AT NEXT ASSY.

PLAN 5-C

NOTE:  
LUGS TO BE  
LOCATED AT  
NEXT ASSY.

$\frac{1}{2}$ " R

$\frac{1}{2}$ " R

W10x49  
(REF.) NEXT ASSY.

INSTALL  $\frac{1}{2}$ " STIFFENERS  
AT NEXT ASSY. (2 REQ'D)

$\frac{1}{2}$ "x45° SNIPE (TYP)

$1\frac{1}{8}$ " DRILL THRU  
(2 PLCS)

3" R

$\frac{1}{2}$ " (TYP)

$1\frac{1}{2}$ "

$\frac{3}{4}$ "

4 $\frac{1}{2}$ "

5"

10"

3-C

PLAN 5-C

ELEVATION 5-C

NOTE:  
LUGS TO BE  
LOCATED AT  
NEXT ASSY.

1" R (TYP)

$\frac{1}{2}$ " R (TYP)

$\frac{1}{2}$ " R END PIECE

2 $\frac{1}{2}$ "

1

3

2

1

LIST OF MATERIALS

QUANTITY	ITEM	QTY.	DESCRIPTION	UNIT
----------	------	------	-------------	------

5" R



GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36.
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GMDI SPEC. 001-002.
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.
5. ALL WELDS TO BE 3/8" CONTINUOUS FILLET.


REFERENCE DRAWINGS:

1. T-54-54-316 CASING RACK LOCATION & DETAILS

C

B

A



3-C

3-C

PLAN 5-C

5-A

INSTALL 1/2" Ø STIFFNER TO W36x170 AT NEXT ASSY.

NOTE: LUGS TO BE LOCATED AT NEXT ASSY.

1/2" Ø

4 1/2"

CASING RACK SEE REF # 1

1/2" Ø 5 LOCAT NEXT NS #

1/2" Ø

3'-5 1/2"


ELEVATION 5-A

6

5


4

$\frac{1}{2}$ " (TYP)  
 $-\frac{1}{2}$ "  
 $\frac{3}{4}$ "



ELEVATION-S-C

↑  
**3-C**



	APPROVED	DESIGNED BY	DATE	SCALE	NO.
ASA					
SSA					


4

3

2

5





GLOWAR CHALLENGER  
SEE REF DWG'S 1 & 2

GENE PLO  
(RM)

2'-0"

4'-7"

3-A

3-B

3-B

3-C

3-C

3-A

2


H

4


3

2


CHALLENGER  
NO 1 & 2



**SECTION 3-C**  
SCALE 1/8" = 1'-0"



**SECTION 3-B**  
SCALE 1/8" = 1'-0"



4'-0"  
SCALE  
TO FACE

2

1

3

2

1

LIST OF MATERIALS

QUANTITY	UNIT	QTY.	DESCRIPTION	REMARKS
----------	------	------	-------------	---------

GENERAL NOTES: (UNLESS OTHERWISE NOTED)


- 1 ALL MATERIAL TO BE ASTM A-56.
- 2 FRAME SPACING IS 2'-0" IN AREA CONCERNED.
- 3 DECK HAS CAMBER BUT NO SHEER.
- 4 ALL MATERIAL TO BE  $\frac{3}{8}$ " PLATE.

REFERENCE DRAWINGS:

- 1 D-577-A078 GLOMAR CHALLENGER ARRANGEMENT-MAIN DECK & BELOW
- 2 T-54-54-H126 DECK PLATING & FRAMING SECTIONS & DETAILS

ENGINE YARD  
(RMP)

C




PLAN VIEW 3-A

WINCH FOUNDATION PORT SIDE AT MAIN DECK


SCALE 3/8"=1'-0"

4



**SECTION 3-B**

SCALE: 3/8" = 1'-0"



**SECTION 3-A** (2)

PORT SIDE FRAME 110 LOOKING AFT

SCALE: 3/8" = 1'-0"

SHIP  
FWD


NO.	APPROVED	DESIGNED OR REVISIONS	D.T. NO.	LETTER DATE	PLT. NO.

4 3 2  
1 5

- 1 ALL MATERIAL TO BE ASTM A-50.
- 2 FRAME SPACING IS 2'-0" IN AREA CONCERNED.
- 3 DECK HAS CAMBER BUT NO SHEER.
- 4 ALL MATERIAL TO BE  $\frac{3}{8}$ " PLATE.

**REFERENCE DRAWINGS:**

- 1 D-577-A025 GLOMAR CHALLENGER ARRANGEMENT-MAIN DECK & BELOW
- 2 T-54-54-H126 DECK PLATING & FRAMING SECTIONS & DETAILS



ING AFT

**E-001-A025**

NO. REV.	REVISION
1	ALTERATION
2-5B	DATE
	FORWARDING
	CONSTRUCTION
	ENGINEERING
	WORK
	APP
10	CUSTOMER
1	WALKER STEEL
1	PTE
1	GLOBAL MARINE
1	WALKER STEEL
2	LIBRARY

D 12100 NW	RELEASE FOR CONSTRUCTION	006 - 025000
A 03400 NW	PRELIMINARY RELEASE	006 - 025000
NO. DATE BY	DESCRIPTION	JOB NO. DATE APPRO.
	ALTERATIONS	



**GLOBAL MARINE DEVELOPMENT INC.**  
Whisper Beach, Calif.

THIS DRAWING AND THE DESIGN IS UNLESS OTHERWISE NOTED THE SOLE PROPERTY OF GLOBAL DEVELOPMENT, INC. AND NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM GLOBAL DEVELOPMENT, INC. THE COMPANY SHALL BE RESPONSIBLE TO OTHER DRAWING APPLICANTS AND CONTRACTORS.

**MARINE SEISMIC SYSTEM (M6S)  
WINCH FOUNDATION  
DETAILS AND ARRANGEMENT**

APPROVED	DESIGNED OR REVISIONS	D.T. NO.	LETTER DATE	FILE NO. NO.	TOTAL NET WT. (LBS.)	TOTAL NET WT. (KGS.)	TOTAL NET WT. (TONS)	DR. P.L. WALKER	REV. 006	NO. 006	NOTED	TOLERANCES UNLESS OTHERWISE NOTED FRACTIONS - 1/16" ANGULAR - 1/2" DECIMALS - 1/32"	JOB NO.	DATE	APPRO.
APP.								APP. P.L. WALKER	1/2/70	006	NOTED		E-001-A025		
DATE								NO. 006	025000						

2

6



2

1



4

3

2

3.000 DRILL THRU  
SLIP FIT

5/8" DIA  
CS



DETAIL 3-D

SPINDLE  
SCALE: HALF SIZE



DETAIL  
SCALE:

3-A

SEE DETAIL 3-D

2.5MM ACT

3/8\"/>



2



1

3

2

1

LIST OF MATERIALS				
ITEM	QTY	DESCRIPTION	UNIT	REMARKS
1	1	3/8" DIA SHEAVE (PROVIDED BY NORCA)	CAMPBELL MOOSEBLOK	
2	1	1/2" x 3/4" L4 COTTER PIN		



**DETAIL 2-D**

PIN

SCALE: HALF SIZE


**3-D**

LE


1/2" SIZE

**GENERAL NOTES:** (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36.
2. BREAK ALL SHARP EDGES AND REMOVE ALL BURRS.
3. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.
4. PAINT IN ACCORDANCE WITH GMD SPEC. 001-002.
5. IF POSSIBLE USE SPINDLE & PIN SUPPLIED WITH THE CAMPBELL SNATCH BLOCK.
6. DETAILS OF SIZE & EXACT LOCATION OF PROBE TO BE DETERMINED BY "SEA-MAC".
7. LUBRICATE SPINDLE WITH MARINE GREASE BEFORE ASSEMBLY.



PLAN VIEW 5-C  
(GREAVE & SPINDLE REMOVED FOR CLARITY)



ELEVATION 5-A


4






6

5



**DETAIL 6-11**  
SCALE: 8"=1'-0"




1

2

4

3

2



MATCH THE ASSEMBLY REF. DRAWING

19" DRILL THRU 2 WALLS - 2 PLS

13" 16 DRILL THRU BOTH WALLS - MATCH DRILL W/ REP #1 - USE

12" DRILL THRU - MATCH DRILL W/ REP #1 - USE

**VIEW 3-13**

SCALE: 1"=1'-0"

2

2


3

1

LIST OF MATERIALS				
ITEM	REQ	QTY	DESCRIPTION	UNIT
	1	6	1/2"-10 UNC 2A x 2 1/2" L4 HEX BOLT	
	2	12	3/4" LOCK WASHER	
	3	12	1/2"-10 UNC 2B HEX NUT	
	4	2	1/2"-10 UNC 2A x 7" L4 HEX BOLT	
	5	6	3/4" FLAT WASHER	
	6	4	1/2"-10 UNC 2A x 2 1/2" L4 HEX BOLT	

GENERAL NOTES: UNLESS OTHERWISE NOTED

1. ALL MATERIAL TO BE ASTM A-56.
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. SHIMS SHOULD BE USED WHERE NECESSARY FOR ALIGNING IDLER SHEAVE SUPPORT.
4. IDLER SHEAVE SUPPORT, & WINCH ARE OWNER FURNISHED.
5. SHIP YARD TO SUPPLY BEAM ASSEMBLY & ALL FASTENERS.



REFERENCE DRAWINGS:

1. E-001-0026 MACHINING SHEAVE SYSTEM DRIVE IDLER SHEAVE SUPPORT DETAILS & ASSEMBLY
2. E-001-1008-000 FRAME ASSEMBLY

3-15  
↓

IDLER SHEAVE SUPPORT  
SEE REF DWG #1

SEE DETAIL 6-12

3-13  
↓


PENGO WINCH  
FRAME ASSEMBLY  
SEE REF DWG #2

7-114

ELEVATION 3-A

SCALE: 1/2"=1'-0"

4  
↓



**VIEW 3-13**

SCALE: 1" = 1'-0"

IN  
 DIMENLY  
 16" 2

7'-11 1/2"


5



6

5

D

C

HEAVE COMPENSATOR  
(SEE REF 'G)

G-OLAR CHALLENGER  
(SEE REF 'D')

WALKWAY TO BE  
REMOVED FOR  
A-FRAME CLEARANCE

CRANE PED (REF)


A-FRAME SUPPORT TO CASING BACK  
(SEE REF 'S')

CASING BACK  
(SEE REF 'Q')

BOOBY HATCH

CRANE WHEEL


BOOBY



20

4

3



20

3

2

1

LIST OF MATERIALS			
QTY	NO.	DESCRIPTION	REMARKS
	1	7/8" BULK 2A 5 LGS HEX BOLT	
	2	7/8" BULK 2B HEX NUT	
	3	7/8" STD FLAT WASHER	
	4	1/2" 7 UNC 2A 5 LG HEX BOLT	
	5	1/2" LOCK WASHER	
	6	1/2" 7 UNC 2B HEX NUT	
	7	ANCHOR SHACKLE	CROSS OR B
X	8	CRANE LOAD CELL	MANUFACTURE
X	9	36 DA SHEAVE BLOCK	

1

D

GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1 SHACKLE SIZE TO BE DETERMINED BY ITEM 9.

REFERENCE DRAWINGS:

1. E 001-A022 MARINE SEISMIC SYSTEM (MSS) A-FRAME DETAILS & ASSEMBLY
  2. E 001-A023 MARINE SEISMIC SYSTEM (MSS) A-FRAME SUPPORT TO S/B BASE DETAILS & ASSEMBLY
  3. E 001-A024 MARINE SEISMIC SYSTEM (MSS) A-FRAME SUPPORT TO CASING RACK DETAILS
  4. E 001-A025 MARINE SEISMIC SYSTEM (MSS) WINDY FOUNDATION DETAILS & ARRANGEMENT
  5. E 001-A027 MARINE SEISMIC SYSTEM (MSS) SHEAVE SUPPORT TO WINDY ASSY
  6. E 001-A029 MARINE SEISMIC SYSTEM (MSS) HEAVE COMPENSATOR BRACKET MODIFICATION & DETAILS
  7. E 001-A030 MARINE SEISMIC SYSTEM (MSS) ACCUMULATOR SUPPORT DETAILS & ASSEMBLY
  8. E 001-A020 MARINE SEISMIC SYSTEM (MSS) INSTRUMENTATION & CONTROLS INSTALLATION
  9. D377-A008 GLOMAR CHALLENGER ARRANGEMENTS MAIN DECK & BELOW
- LEVINSTON SHIPBUILDING CO.
10. T54-54-315 CASING RACK LOCATION & DETAILS
  11. T54-54-316 DEERICK SUB BASE DETAILS

SUPPORT

PORT TO SUB BASE

C

B

HEAVE COMPENSATOR  
(SEE REF # 6)

GLIDER CHALLENGER  
(SEE REF # 9)

WALKWAY TO BE  
REMOVED FOR  
A-FRAME CLEARANCE

CRANE PED (REF)

A-FRAME SUPPORT TO CASING RACK  
(SEE REF # 3)

CASING RACK  
(SEE REF # 10)

FOOBY MATCH

20'-0"  
OFF 2' (REF)

BRING W/WHICH

ACTUAL LOCATION OF MOUNTING  
INSTRUMENTATION & CONTROLS (REF # 8)  
TO BE DETERMINED DURING ABOARD  
SHIP INSTALLATION

I-C ←

AC POWER INLET

YAW

INSTRUMENT STUFFING  
BOX PANEL

← I-C


130 129 128 120

PLAN VIEW 5-A

8

5

4



NO.					
NO.					



4 3 2

5




12


11



B



**PLAN VIEW 9-C**  
**REENTRY TOOL & MISC EQUIPMENT STORAGE**  
 SCALE: 1/8" = 1'-0"



B

8

7

LIST OF MATERIALS

NO.	DESCRIPTION	QTY.	REMARKS

CRANE PED

INSTRUMENTATION & CONTROLS

PENGO W/CR

WINCH CONTROL PANEL

(2) REENTRY STINGER  
(24'-0" LQ)

SHIP

110

FWD

(2) BOXED BIP (GEOTECH)  
(2'-0" x 2'-0" x 30'-0")

BOXED MISC EQUIPMENT

10'-0" (REF)


2'-5 1/2"

4'-3"  
(REF)

A-FRAME  
(REF #1)

A-FRAME SUPPORT  
TO VASILE  
(REF #2)

ASO



PLAN  
REENTRY TOOL  
SCALE

SHIP  
EXS. STING CASING  
RACK - SEE REF #10

10'-0"  
OFF SHIP

PENGO WINCH

17'-3-9"

5'-0" (REF)

WINCH FOUNDATION  
SEE REF DWG #4

SECTION II-A  
FORT SIDE FRILL LOOKING AFT



B

A

12

4

**PLAN VIEW 9-C**  
**TRY TOOL & MISC. EQUIPMENT STORAGE**  
 SCALE: 1/8" = 1'-0"




**ELEVATION 9-A**  
 FRONT SIDE (LOOKING INBO)  
 (CRANE PED REMOVED FOR CLARITY)

10

9

5



**ELEVATION 9-A**

PORT SIDE (LOOKING INBD)  
 (CRANE PED REMOVED FOR CLARITY)

SEE SHEET 1 FOR NOTES, REVISIONS, AND ALTERNATES



**GLOBAL MARINE DEVELOPMENT INC.**  
Atlanta, Georgia, U.S.A.

**MARINE SEISMIC SYSTEM (MSS)**  
**GLOBAL CHALLENGER**  
 INSTALLATION ARRANGEMENT

REV 110 DATE 06/08/00 BY E-001 APP A028 SCALE 1/2"=1'-0"

C  
B  
A

7






3


2

1



**DETAIL 3-D**

SCALE: 5" = 1'-0"  
TENSIONER REMOVED FOR CLARITY



**DETAIL 3-C**

SCALE: HALF SIZE


LIST OF MATERIALS				
ITEM	QTY	DESCRIPTION	UNIT	REMARKS
1	1	2-4 1/2 UNC 2A x 1 1/2" LG HEX BOLT		
2	1	2" PLAIN WASHER		
3	1	2" LOCK WASHER		
4	1	2-4 1/2 UNC 2B HEX NUT		
5	2	1/2-13 UNC 2A x 1 1/2" LG HEX BOLT		
6	2	M6 NUTS-CARR HOOKS & STRAIGHT GRINDS FITTING ORB		
7	6	1/2-13 UNC 2A x 1 1/2" LG HEX BOLT		
8	6	1/2" PLAIN WASHER		
9	6	1/2" LOCK WASHER		
10	6	1/2-13 UNC 2B HEX NUT		

**GENERAL NOTES: (UNLESS OTHERWISE NOTED)**

1. ALL MATERIAL TO BE ASTM A-36
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GM DI SPEC. 001-002
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.

**REFERENCE DRAWINGS**


JOE STINE INC.  
 10 0486 3 GUIDE LINE TENSIONER  
 HORIZONTAL CEILING MOUNT



1/2" HOLE  
B RECD \*



VERIFY  
W/CYL



GLOMAR CHALLENGER  
MIN OR (REF) NEXT  
ASSY

HEAVE COMPENSATOR  
(BUCKER MODEL HCM 6-7.5-8-75)  
SEE REF DWG #1

MODIFIED ROD  
END GUNBAVE ASSY


**ELEVATION 3-A**  
SCALE: 1/2" = 1'-0"

4

SCALE: 3/4"=1'-0"  
(TENSIONER REMOVED FOR CLARITY)

Ø 1/2" HOLE  
Ø REQ'D \*

Ø 3/4" ABT  
Ø 1/2" ABT




**VIEW 4-C**

SCALE: 3/4"=1'-0"

\* VERIFY HOLE SPACING  
W/CYL FLIND END


2 1/4" ROD x 15" L<sub>4</sub>



**DETAIL 3-C**

SCALE: HALF SIZE

WATOR  
NCM (6-7.5-8-7.5)  
WG #1




Ø 3/4" ABT

2' x 3' x 1/2" L<sub>4</sub> BAR

2.06 ± .03 DRILL  
THRU-INLINE

DO NOT WELD  
TO ROD END

MODIFIED ROD -  
END CHAMFER 4MM



**DETAIL 3-A**

SCALE: 3/4"=1'-0"


(A-FRAME REMOVED FOR CLARITY)

REV	DATE	BY	CHK

# DETAIL 3-D


SCALE: 3" = 1'-0"

(TENSIONER REMOVED FOR CLARITY)



# TAIL 3-C

SCALE: HALF SIZE



# TAIL 3-A

SCALE: 3" = 1'-0"  
(REMOVED FOR CLARITY)

## GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-36
2. BREAK ALL EDGES & REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GMDI SPEC.001-002
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.

## REFERENCE DRAWINGS

JOE STINE INC.  
E.O. 0486 GUIDE LINE TENSIONER  
HORIZONTAL CEILING MOUNT.

E-001A02B

NO.	REV.	DESCRIPTION
1	0	INITIAL
2	1	CHANGE
3	2	CHANGE
4	3	CHANGE
5	4	CHANGE
6	5	CHANGE
7	6	CHANGE
8	7	CHANGE
9	8	CHANGE
10	9	CHANGE
11	10	CHANGE
12	11	CHANGE
13	12	CHANGE
14	13	CHANGE
15	14	CHANGE
16	15	CHANGE
17	16	CHANGE
18	17	CHANGE
19	18	CHANGE
20	19	CHANGE
21	20	CHANGE
22	21	CHANGE
23	22	CHANGE
24	23	CHANGE
25	24	CHANGE
26	25	CHANGE
27	26	CHANGE
28	27	CHANGE
29	28	CHANGE
30	29	CHANGE
31	30	CHANGE
32	31	CHANGE
33	32	CHANGE
34	33	CHANGE
35	34	CHANGE
36	35	CHANGE
37	36	CHANGE
38	37	CHANGE
39	38	CHANGE
40	39	CHANGE
41	40	CHANGE
42	41	CHANGE
43	42	CHANGE
44	43	CHANGE
45	44	CHANGE
46	45	CHANGE
47	46	CHANGE
48	47	CHANGE
49	48	CHANGE
50	49	CHANGE
51	50	CHANGE
52	51	CHANGE
53	52	CHANGE
54	53	CHANGE
55	54	CHANGE
56	55	CHANGE
57	56	CHANGE
58	57	CHANGE
59	58	CHANGE
60	59	CHANGE
61	60	CHANGE
62	61	CHANGE
63	62	CHANGE
64	63	CHANGE
65	64	CHANGE
66	65	CHANGE
67	66	CHANGE
68	67	CHANGE
69	68	CHANGE
70	69	CHANGE
71	70	CHANGE
72	71	CHANGE
73	72	CHANGE
74	73	CHANGE
75	74	CHANGE
76	75	CHANGE
77	76	CHANGE
78	77	CHANGE
79	78	CHANGE
80	79	CHANGE
81	80	CHANGE
82	81	CHANGE
83	82	CHANGE
84	83	CHANGE
85	84	CHANGE
86	85	CHANGE
87	86	CHANGE
88	87	CHANGE
89	88	CHANGE
90	89	CHANGE
91	90	CHANGE
92	91	CHANGE
93	92	CHANGE
94	93	CHANGE
95	94	CHANGE
96	95	CHANGE
97	96	CHANGE
98	97	CHANGE
99	98	CHANGE
100	99	CHANGE

0	1/28/84	RELEASE FOR CONSTRUCTION	000	01/28/84	000
A	02/01/84	PRELIMINARY RELEASE	000	02/01/84	000
NO.	DATE	DESCRIPTION	BY	DATE	BY
		ALTERED			



**GLOBAL MARINE DEVELOPMENT INC.**  
Newport Beach, Calif.

**MARINE SEISMIC SYSTEM (MSS)  
HEAVE COMPENSATOR BRACKET  
MODIFICATIONS & DETAILS**

APPROVED	REVISIONS OR REWORKED	DWG. NO.	LETTER	DATE	BY	TOTAL NET WT. (LBS.)
AAA						TOTAL NET WT. (LBS.)
AAA						TOTAL NET WT. (LBS.)

DATE	BY	REVISIONS	DATE	BY
01/28/84	AS	NOTED	01/28/84	AS
02/01/84	AS	NOTED	02/01/84	AS
02/01/84	AS	NOTED	02/01/84	AS
02/01/84	AS	NOTED	02/01/84	AS
02/01/84	AS	NOTED	02/01/84	AS


E-001-A02B-0

2 1 6

6

5

1/2" UNF 2A  
2" LG THD



**DETAIL 5-11**

**BOTTLE CLAMP**


SCALE 3/4" = 1'-0"

GLOMAR CHALLENGER  
SEE REF #1

BULWARKS  
SEE REF #2

**3-13**

DECK F  
SEE REF #



CASING RACK  
SEE REF #3

DERRICK SUB BASE  
SEE REF #4

D


C

B



LIST OF MATERIALS


QTY	NO.	QTY.	DESCRIPTION	STANDARD
1	2	1/2"	15 LINC 20 HEX NUT	
2	2	1/2"	LOCK WASHER	



GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. ALL MATERIAL TO BE ASTM A-56.
2. BREAK ALL EDGES AND REMOVE ALL BURRS.
3. PAINT IN ACCORDANCE WITH GMDI SPEC. 001-002.
4. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES.
5. ALL WELDS TO BE  $\frac{3}{8}$ " CONTINUOUS FILLET.

BOTTLE CLAMP  
SEE DETAIL 5-11




REFERENCE DRAWINGS:

- DAT. A-05 GLOWAR CHALLENGER ARRANGEMENTS - MH ON BELOW
- 2.T-54-54-550 BULLWARKS & FASHION PLATE MAP. DECK ARRANGEMENTS & DETAILS
- 3.T-54-54-515 CAGING RACK LOCATION & DETAILS
- 4.T-54-54-516 DERRICK SUB BARGE DETAILS
- 5.T-54-54-519 DECK FITTINGS LOCATIONS & DETAILS

0  
3-13

CASING RACK  
SEE REF #3

DERRICK SUB BASE  
SEE REF #4



PLAN VIEW 5-A  
PORT SIDE FR 109 TO FR 121  
ACCUMULATOR SUPPORT LOCATION  
SCALE: 3/8"=1'-0"

C  
B  
A

6

5

4

(12)

5' R W 5' PLG  
REF

1" TIP

2 1/2" R W 2 1/2" PLG  
REF

2"

10 3/4"

11"

11" REF

5' R W 5' PLG  
REF

### SECTION 3-13

PORT SIDE PR III LOOKING FWD

SCALE: 3/8"=1'-0"

SHIP  
FWD

AAA				
AAAA				

3


5





LIST OF MATERIALS

TYPE	QTY	DESCRIPTION	UNIT
------	-----	-------------	------



BIP REF DWG #1

**GENERAL NOTES:** (UNLESS OTHERWISE NOTED)  
 1. BREAK ALL EDGES & REMOVE ALL BURRS.

**REFERENCE DRAWINGS:**  
TELEPHONE GEOTECH  
 I. D-990-53100 BIP  
GMDI  
 E. E-001-1002 MARINE SEISMIC SYSTEM (MSS)  
 BIP LOADING SEQUENCE

NO.	REV'S	REVISION
1	8	ALTERATION
2	7	DATE
3	6	PURCHASE
4	5	CONSTRUCTION
5	4	CONSTRUCTION
6	3	ISSUE
7	2	ISSUE
8	1	CM STRONG
9	1	WELLER STEBY
10	1	DYE
11	1	EM. HANSEN
12	1	MITCHELL
13	1	J. BENHAR
14	2	LIBRARY

0	1-15-81	MM	RELEASE FOR CONSTRUCTION	006-225000	1/1
NO.	DATE	BY	DESCRIPTION	REV. NO.	QTY

**GLOBAL MARINE DEVELOPMENT INC.**  
 Newport Beach, Calif.

THE ENGINEER AND THE ARCHITECT WILL BE RESPONSIBLE FOR THE PROPER INSTALLATION OF THE WORK SHOWN ON THIS DRAWING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER FABRICATION AND INSTALLATION OF THE WORK SHOWN ON THIS DRAWING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER MAINTENANCE OF THE WORK SHOWN ON THIS DRAWING.

**MARINE SEISMIC SYSTEM (MSS)  
 BIP HANDLING T-BAR  
 DETAILS**

APPROVED	DATE	BY	REV.	QTY	UNIT	TOTAL NET WT. (LBS.)	TOTAL NET WT. (KGS.)	TOTAL NET WT. (TONS)
AW								
AW								


BY: N. WAGNER	DATE: 1-15-81	SCALE: HALF SIZE	PROJECT: MSS
CHK: S. DYE	DATE: 1-13-81		
APP: [Signature]	DATE: 1-15-81		
APP: [Signature]	DATE: 1-15-81		

PROJECT: MSS	REV. NO. 1	QTY: 1	UNIT: EACH
PROJECT: MSS	REV. NO. 1	QTY: 1	UNIT: EACH

D • 001 • A031







3

2


2

LIST OF MATERIALS

ITEM NO.	QTY	DESCRIPTION	UNIT PRICE	TOTAL PRICE
----------	-----	-------------	------------	-------------

GENERAL NOTES: UNLESS OTHERWISE NOTED

1. ALL MATERIAL TO BE ASTM A-36 OR EQUAL.
2. BREAK ALL SHARP EDGES & REMOVE ALL BURRS.



ELEVATION 2-13

REFERENCE DRAWINGS:

1. D-001-A001 MARINE SEISMIC SYSTEM (MSS) REENTRY TOOL STINGER ASSEMBLY & DETAILS
2. E-001-T002 MARINE SEISMIC SYSTEM (MSS) DIP LOADING SEQUENCE

0	1-15-81	NW	RELEASE FOR CONSTRUCTION	006-	273000	SA
NO.	DATE	BY	DESCRIPTION	REV.	QTY	UNIT

**GLOBAL MARINE DEVELOPMENT INC.**  
 Morgan Road, Calif.

**MARINE SEISMIC SYSTEM (MSS)**  
**SLIPS ADAPTOR FOR STINGER**  
**DETAILS**

BY	DATE	SCALE	REVISIONS
H. WAGNER	1-14-81	HALF	
S. Dye	1-16-81	3/8"	
W. J. ...	1-19-81	006-	
...	...	273000	

NO.	REV.	DESCRIPTION
0		DATE
1		PURCHASE
2		CONSTRUCTION
3		CONSTRUCTION
4		CONSTRUCTION
5		CONSTRUCTION
6		CONSTRUCTION
7		CONSTRUCTION
8		CONSTRUCTION
9		CONSTRUCTION
10		CUSTOMER
11		WILLIAMS
12		FILE
13		WILSON
14		MITCHELL
15		FARNHAM
16		LIBRARY

APPROVED	DATE	BY	QTY	UNIT	TOTAL NET UNIT PRICE
AAA					
AAA					

3

2

6

5

USE EXIST. WIRE ROPE AND  
CLEVIS AND ATTACH TO  
TV GUIDE FRAME FOR  
TV CAMERA DEPLOYMENT

EXIST DAVIT ARM  
SEE REF 2

SEE DETAIL 9-2

SLOT FOR TV  
CABLE

MAIN DECK

TV CABLE TO MON TOR

0-0 REF

TWEEN DECK

0-0


DECK LEVEL END

EXIST GUIDE  
FRAME. SEE  
REF 2

LINK/CABLE TO  
LOWERING LINE

DECK LEVEL END

5





2-


3

2

1


LIST OF MATERIALS

QTY	NO.	QTY	DESCRIPTION	QTY



DETAIL 3-D

3/8" O.D.



BOTH HOLES CENTER LINES TO STRADDLE CENTER LINE OF SHIP

DETAIL 3-C

3/8" O.D.

GENERAL NOTES (UNLESS OTHERWISE NOTED)

1. ALL PLATES AND SHAPES TO BE ASTM A-80 OR EQUAL
2. ALL WELDING TO BE IN ACCORDANCE WITH AWS PROCEDURES
3. BREAK ALL SHARP EDGES AND REMOVE ALL BURRS
4. ALL WELDS TO BE 1/4" CONTINUOUS FILLET.


REFERENCE DRAWINGS

LEVINGTON SUPPLY CO


LT 54-54-18 DRILLWELL PULLEYS

LT 54-54-25 DRILLWELL PLUG

LT 54-54-44 2x4x4x1/2 PLOT LOG INSTALLATION & DETAILS



DETAIL  
: 07



ELEVATION 6.A  
1/1-02

ELEVATION 5.A  
1/1-02

6

5

4

4





6

5



4

D

C

B



A



6

5

4




DETAIL 3-C

D.001-A057

NO. REV'D.	REVISION	DATE	BY
1	ALTERATION	7-5-58	
	PURCHASING		
	CONSTRUCTION		
	ENGINEERING		
	WROD		
	ASS		
10	CUSTOMER		
1	WALLERSTEDT		
1	DYK		
1	F. HARRAN		
1	RITCHIE		
1	FARRAR		
2	LIBRARY		

APPROVED	DESIGNED OR REVISED	ALT. NO.	LETTER DATE	FILE NO.	TOTAL NET WT. MAT'L.
ASS.					TOTAL NET WT. EQUIP.
U.S.C.R.					TOTAL NET WEIGHT



LIST OF MATERIALS				
ORDER PART	ITEM	QTY.	DESCRIPTION	MATERIAL OR DWG. NO.
	1	2	1/2"-13 UNC 2A x 7" LG GALV. HEX BOLT	STEEL
	2	2	1/2 GALV. PLAIN WASHER	
	3	4	1/2"-13 UNC 2B NYLOC STOP NUT	
	4	2	1/2"-13 UNC 2A x 11" LG GALV. HEX BOLT	
	5	1	1.250 ± .001 OD x 1" ID x 1" LG BUSHING	316 S STL
	6	1	1/4 x 2" GALV. SCREW EYE BOLT (CROSBY G-275 OR EQUAL)	STEEL

**DETAIL 3-C**

1	3-20-81	NW	ADDED ITEM #6 (1/4" SCREW EYE BOLT)	006-923000	46
0	2-24-81	NW	RELEASE FOR CONSTRUCTION	006-323000	46
NO.	DATE	BY	DESCRIPTION	JOB NO.	APPR.

D-001-A035

NO. REQ'D.	NEXT ASSEMBLY
1	ALTERATION
250	DATE
	PURCHASING
	CONSTRUCTION
	ENGINEERING
	USCG
	ABS
10	CUSTOMER
1	WALLERSTEDT
1	DYE
1	BURKHARDT
1	MITCHELL
1	FARNHAM
2	LIBERTEI




THE DRAWING AND THE DESIGN IT ENTAILS ARE THE CONFIDENTIAL PROPERTY OF GLOBAL MARINE DEVELOPMENT, INC. AND MAY NOT BE REPRODUCED OR DISCLOSED TO OTHERS OR USED FOR MANUFACTURE OR OTHER PURPOSES WITHOUT THE WRITTEN CONSENT OF GLOBAL MARINE DEVELOPMENT, INC. THE DRAWING SHALL BE RETURNED TO GLOBAL MARINE DEVELOPMENT, INC. ON REQUEST.


**MARINE SEISMIC SYSTEM (MSS) RUNNING FAIRLEADER DETAILS**

APPROVED	EXAMINED OR REVIEWED	ALT. NO.	LETTER DATE	FILE REF. NO.	TOTAL NET WGT. MAT'L
					TOTAL NET WGT. EQUIP.
					TOTAL NET WEIGHT

DRW. H. WAGNER	DATE 2-15-81	SCALE HALF SIZE	TOLERANCES UNLESS OTHERWISE NOTED FRACTION - 1/16" ANGULAR - 1/2"
DRW. N. SLIDE	DATE 2-20-81	SCALE 1/2" = 1"	DESIGNATED DIMENSIONS
CHK. E. SHAMAM 20	DATE 2-24-81	JOB NO. 006-923000	DWG. NO. D-001-A035
APPR. [Signature]	DATE 2-24-81		SHEET 1 OF 1

SEE DETAIL 3-C






LIST OF MATERIALS				
CUSTOMER PART NO.	ITEM	QTY.	DESCRIPTION	MATERIAL OR DWG. NO.
	1	1	1/2" CLOSED SPELTER SOCKET (CROSBY G-417 OR EQUAL)	
	2	2	5/8" BOLT TYPE ANCHOR SHACKLE (CROSBY G-890 OR EQUAL)	
	3	1	4 STL SWIVEL (MILLER TYPE 2, MODEL G OR EQUAL)	
	4	1	1/2" x 4" WELDLESS RING (CROSBY S-648 OR EQUAL)	
	5	1	WEIGHT 2250# WET	
	6	6	3/4" ROPE THIMBLE GALVANIZED STEEL	
	7	1	RELEASE ACTUATOR (HELLE MODEL # 5207 OR EQUAL)	
	8	1	RUNNING FAIRLEADER	REF DWG #1
	9	1	COMMAND TRANSMITTER W/TRANSDUCER & 50 FT OF CABLE (HELLE MODEL 5148 OR EQUAL)	

GENERAL NOTES: (UNLESS OTHERWISE NOTED)  
 ▷ ITEM (9) MAYBE PLACED ABOARD GLDMAR CHALLENGER.

REFERENCE DRAWINGS:  
 1. D-001-A035 MARINE SEISMIC SYSTEM (MSS) RUNNING FAIRLEADER DETAILS



NO. REV'S	NEXT ASSEMBLY
0	ALTERATION
1-5	DATE
	PURCHASING
	CONSTRUCTION
	ENGINEERING
	USED
	AGE
10	CUSTOMER
1	WILLIAMS TEST
1	BY
1	BUCHANAN
1	ARCHER
1	FARHAM
2	LIBRARY

APPROVED	DESIGNED OR REVISED	ALT. NO.	LETTER DATE	PLG REF NO.	TOTAL NET WT. SHT'L	TOTAL NET WT. BOND	TOTAL NET WEIGHT

0	2-20-81	NW	RELEASE FOR CONSTRUCTION	006-001-A037
NO.	DATE	BY	DESCRIPTION	JOB AUTH. APPR.
			ALTERATIONS	



**GLOBAL MARINE DEVELOPMENT INC.**  
 Newport Beach, Calif.


THIS DRAWING AND THE DESIGN IT ENTAILS ARE THE CONFIDENTIAL PROPERTY OF GLOBAL MARINE DEVELOPMENT, INC. AND MAY NOT BE REPRODUCED OR DISCLOSED TO OTHERS OR USED FOR MANUFACTURE OR OTHER PURPOSES WITHOUT THE WRITTEN CONSENT OF GLOBAL MARINE DEVELOPMENT, INC. THE DRAWING SHALL BE RETURNED TO GLOBAL MARINE DEVELOPMENT, INC. AS REQUESTED.


**MARINE SEISMIC SYSTEM (MSS)  
 DUAL SHIP ENTANGLEMENT SYSTEM ASSEMBLY**

DATE	BY	SCALE	TOLERANCE UNLESS OTHERWISE NOTED
2-17-81	WAGNER	NONE	FRACTION - 1/32" ANGULAR - 1°
2-20-81	N. SLORE		MILLIMETER - 1.000 ( ) DENOTATED MILLIMETER DIMENSIONS
2-20-81	FARHAM		
2-20-81	WAGNER		
2-20-81	WAGNER		
		JOB AUTH. 006-001-A037	DWG. NO. D-001-A037
		525000	


6

5





**BLOCK WIZING DIAGRAM**




**NOTES:**

1. TEMPORARY INSTRUMENTATION CABLES TO TO STRUCTURE TO PREVENT PHYSICAL PAN OCCURRING DURING PROJECT OPERATION.
2. WIRE ONE EACH (36) HEAD-CHST SET INTO DR PILOT HOUSE 'E' CALL SOUND POWERED TELEPH FOR "HANDS FREE" COMMUNICATION TO WINCH & VAN

**REFERENCES:**

1. E-001-A012 (MSS) GLOMAR CHALLENGER ARRANGEMENT




2

1

3

2

1



WIRING DIAGRAM



**NOTES:**

1. TEMPORARY INSTRUMENTATION CABLES TO BE STRAPPED TO STRUCTURE TO PREVENT PHYSICAL DAMAGE FROM OCCURRING DURING PROJECT OPERATION.
2. WIRE ONE EACH (30) HEAD-CHEST SET INTO DRILLERS AND PILOT HOUSE "E" CALL SOUND POWERED TELEPHONE UNIT BOX FOR "HANDS FREE" COMMUNICATION TO WINCH & VAN CONSOLE AREAS.

**REFERENCES:**

1. E-001-A01Z (MSS) GLOMAR CHALLENGER INSTALLATION AIR ARRANGEMENT

- (100') (24)
- ENCL (22)
- WBY (25)
- LOAD CELL (23)
- E SPEED COUNTER (20)
- COIN BOX
- BY GEOTECH (70')
- CK, PLUG (17) (18) (36)
- IT
- PUSHBUTTON (19)



**LIST OF MATERIALS**

QTY	DESCRIPTION	MANUFACTURER
1	TRANSFORMER 30KVA 208/120V 480V 208/120V 480V	GEN ELECT
2		
3		
4	PLUG 4 POLE 4 WIRE 100A 240VAC	GEOTECH FIEN
5	ENCLOSURE 8"x6"x6" OIL TIGHT	HOFFMAN A-8066CN
6	INTERIOR PANEL FOR ITEM 5	HOFFMAN A-8066
7	AMMETER 4" DIAL AC 0-10A SCALE, FULL SCALE DEFLECTION	GEN ELECT 90-109 1M15MT
8	CURRENT XFMR 10/5 RATIO	WIPKEY ELECT PROD ZL7210
9	PUSHBUTTON 1/2" INCL CONTACT BLOCK, BLACK BUTTON	GEN ELECT CR294611111111
10	NAMEPLATE MARKED "TEST" EXTRA LARGE FOR PUSHBUTTON	GEN ELECT NP-161658A
11	TERMINAL BLOCK 2 POINT 50AMP	GEN ELECT LRT4001111111
12	RESISTOR 10 OHM 5WATT	
13	PUSHBUTTON 1/2" W/1/2" SPRING RETURN CONTACTS	BELJAMIN B499
14	BUZZER 115VAC, 60HZ	BELJAMIN BT97-115V
15	SOUND PWR TELEPHONE HANDSET	HOSE MC CANN A-590
16	SOUND PWR TELEPHONE HANDSET HOLDER	HOSE MC CANN A-251
17	JACK FOR SOUND PWR TELEPHONE	HOSE MC CANN A-590
18	PLUG FOR SOUND PWR TELEPHONE JACK	HOSE MC CANN A-529
19	WIRE LINE SPEED 4 STAGE COUNTER METER PANEL	SEA-MAC
20	WIRE LINE SPEED 4 FOOTAGE COUNTER	SEA-MAC
21	DIGITAL WEIGHT INDICATOR PANEL	MARTIN-DEKOR
22	TRANS-DUCER IN NEMA-1E ENCLOSURE	MARTIN-DEKOR H100361
23	TRANSITION LOAD CELL	MARTIN-DEKOR E1319-155
24	SIGNAL CABLE 450V 100 FT LONG	MARTIN-DEKOR PWC 204
25	HOSE 450V	MARTIN-DEKOR H134-2
26	3 COND #14AWG TYPE 30 EXT LEAD W/WRAPPED PLUG 25' LONG	
27	1 COND #14AWG INSULATED WIRE	
28	4 COND #2 AWG TYPE 90	GEOTECH FIB
29	2 COND #22 AWG TRIPLED SHIELDED PAIR	BELDEN 9446
30	490' D56A-4 CABLE	
31	20' T56A-14 CABLE	
32	150' F56A-50 CABLE	
33	30' MHOF-7 FLEX CABLE	
34	70' R6 B/U COAX	GEOTECH FIB
35	4 COND #22 AWG TRIPLED SHIELDED PAIR BELDEN #873	BELDEN 9446
36	SOUND PWR TELEPHONE HEAD-CHEST SET	HOSE MC CANN A-590


D

C

B


MAIN HIGH SEAS RADIC (EXIST)

DR WOODS + REEDS 175  
RACK TO VAN)






WIRE LINE


DIGITAL 1



DIGITAL REZ  
(LOCATED ON  
INSIDE VAN)




4



- NOTES:**
1. TEMPORARY INSTRUMENTATION CABLES TO STRUCTURE TO PREVENT PHYSICAL OCCURRING DURING PROJECT OPERATI
  2. WIRE ONE EACH (36) HEAD-CHEST SET IN PILOT HOUSE 'E' CALL SOUND POWERED TE FOR "HANDS FREE" COMMUNICATION TO WINCH

- REFERENCES:**
1. E-001-AD12 (MSS) GLOMAR CHALLENGER ARRANGEMENT



E	1-11-82	CHANGED PC#1 FROM 15 TO 30KVA, PC#4 FROM 30A TO 100A GEOTECH FUZZ, PC#28 FROM #8AWG TO #2AWG GEOTECH FUZZ, PC#31 FROM T-4 TO T-14, PC#32 FROM F-4 TO F-50 DELETED PC#2 DISK SW & PC#5 FUSES ADDED PC#38	00006 963000	RAB	APPROVED	DESIGNED OR REDESIGNED	ALT. NO.	LETTER DATE	FILE NO.	TOTAL
					ASB					TOTAL
	NO.	DATE BY	DESCRIPTION	JOB AUTH	APPR					TOTAL

4

3

2

5



**NOTES:**

1. TEMPORARY INSTRUMENTATION CABLES TO BE STRAPPED TO STRUCTURE TO PREVENT PHYSICAL DAMAGE FROM OCCURRING DURING PROJECT OPERATION.
2. WIRE ONE EACH (30) HEAD-CHEST SET INTO DRILLERS AND PILOT HOUSE 'E' CALL SOUND POWERED TELEPHONE JUNCT BOX FOR "HANDS FREE" COMMUNICATION TO WINCH & VAN CONSOLE AREAS.

**REFERENCES:**

1. E-001-A01Z (MSS) GLOMAR CHALLENGER INSTALLATION ARRANGEMENT

- (100') (24)
- WELL (22)
- BY (25)
- LOAD CELL (23)
- E SPEED & COUNTER (20)
- LOWN BOX
- BY GEOTECH (70')
- WELL PLUG (17) (18) (36)
- T
- PUSHBUTTON (13)



**DETAIL 2-A**  
GROUND DETECTION PANEL  
WIRING DIAGRAM & FRONT VIEW

15	1	SOUND PWR TELEPHONE HANDSET	HOSE MC CANN A-960
16	1	SOUND PWR TELEPHONE HANDSET HOLDER	HOSE MC CANN A-251
17	2	JACK FOR SOUND PWR TELEPHONE	HOSE MC CANN A-990
18	2	PLUG FOR SOUND PWR TELEPHONE JACK	HOSE MC CANN A-929
19	1	WIRE LINE SPEED & FTAGE COUNTER METER PANEL	SEA-MAC
20	1	WIRE LINE SPEED & FOOTAGE COUNTER	SEA-MAC
21	1	DIGITAL WEIGHT INDICATOR PANEL	MARTIN-DEKOR
22	1	TRANSDUCER IN NEMA-PL ENCLURE	MARTIN-DEKOR H10096A
23	1	TRANSION LOAD CELL	MARTIN-DEKOR E010-255
24	1	SIGNAL CABLE ASSY 100 FT LONG	MARTIN-DEKOR D100-200
25	1	HOSE ASSY	MARTIN-DEKOR A134-5
26	1	3 COND #14AWG TYPE 30 EXT CORD W/IMPED PLUG 55' LONG	
27	10'	1 COND #4AWG INSULATED WIRE	
28	20'	4 COND #2 AWG TYPE 30	GEOTECH FURN
29	170'	2 COND #22AWG TWISTED SHIELDED PAIR	DELLEN 9462
30	190'	D7GA-4 CABLE	
31	20'	T5GA-14 CABLE	
32	150'	F5GA-50 CABLE	
33	30'	MHOF-7 FLEX CABLE	
34	70'	R4B/U COAX	GEOTECH FURN
35	50'	4 COND #22AWG TWISTED SHIELDED PAIR DELLEN #675	GEOTECH FURN
36	2	SOUND PWR TELEPHONE HEAD-CHEST SET	HOSE MC CANN A-990
37	1	DIGITAL RECORDER (BCD INTERFAS)	HERLETT-PARKER E050
38	1	CIRCUIT BREAKER 100AMP-50MT 480VAC, 3 POLE	GEN ELECT TED-194090

ALTERATIONS CONTINUED AT BONE 3A

1/9/81	00006 323000	CHANGED PL#19 & 20 FROM MARTIN DEKOR TO SEA MAC, MOVED 3" FRAME FWD TO MEET LATEST DESIGN REQUIREMENTS, ADDED PL#37 DIGITAL CHART RECORDER TO INTERFACE WITH MARTIN-DEKOR & SEA-MAC EQUIPMENT.
0	00006 323000	INITIAL RELEASE

NO. REV.	REVISION
2	DATE
3	PURCHASING
4	CONSTRUCTION
5	ENGINEERING
6	WELDING
7	INS
8	APP
9	SYSTEMS
10	WARRANTY
11	OFF
12	CONTRACT
13	MANAGEMENT
14	PROGRAM
15	LIBRARY

**GLOBAL MARINE DEVELOPMENT INC.**  
Newport Beach, Calif.

**MARINE SEISMIC SYSTEM (MSS) GLOMAR CHALLENGER ELECTRICAL INSTALLATION**

REV. 006	DATE 11/10/80	SCALE 1/8" = 1'-0"	PROJECT NO. 00006
REV. 005	DATE 11/10/80	PROJECT NO. 140M ONLY	PROJECT NO. 00006
REV. 004	DATE 11/10/80	PROJECT NO. 00006	PROJECT NO. 00006
REV. 003	DATE 11/10/80	PROJECT NO. 00006	PROJECT NO. 00006
REV. 002	DATE 11/10/80	PROJECT NO. 00006	PROJECT NO. 00006
REV. 001	DATE 11/10/80	PROJECT NO. 00006	PROJECT NO. 00006

E-001-E001

30KVA, PL#4 FROM PL#28 FROM FURN PL#31 M F-1 TO F-50 C#5 FUSES	00006 323000	REV. 006	DATE 11/10/80
--	--------------	----------	---------------

APPROVED	DESIGNED OR APPROVED	ALT. NO.	LETTER DATE	FILE NO.	TOTAL NET WT. GALT.

6

5

D

HEAVE COMPENSATOR

H-5

J-1

F-13

F-14

C

15'

TMP


F-1

TMP

H-2

TMP


B



4

3

2



## LIST OF MATERIALS

ITEM NO.	QTY.	DESCRIPTION	GRADE
F-1	2	1/4" THD TEE-3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-2	6	1/4" x 3" LG THD NIPPLE SCH 80	ASTM A-105 GRADE-A-STL
F-3	2	1/4" THD COUPLING-3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-4	2	1/4" x 2" LG THD NIPPLE SCH 80	ASTM A-105 GRADE-A-STL
F-5	2	1/4" THD 90° ELBOW 3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-6	2	1/4" x 4" LG THD NIPPLE SCH 80	ASTM A-105 GRADE-A-STL
F-7	1	1" x 1/4" THD RED BUSHING 3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-8	1	1" THD PLUG-3000 <sup>#</sup>	
F-9	1	1" THD CROSS-3000 <sup>#</sup>	
F-10	3	1" x 2" LG THD NIPPLE SCH 80	ASTM A-105 GRADE-A-STL
F-11	1	2" x 1" THD RED BUSHING 3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-12	1	1" MALE THD/MALE JIC ST FLARE HOSE ADAPTOR SYNPLEX 3A09-16A16	STEEL
F-13	1	1" THD TEE-3000 <sup>#</sup>	ASTM A-105 GRADE-A-STL
F-14	1	1" x 6" LG THD NIPPLE SCH 80	ASTM A-105 GRADE-A-STL
G-1	1	GAUGE - 6" DIA 500-1500 PSI	
G-2	1	GAUGE - 6" DIA 500-2500 PSI	
G-3	1	REGULATOR - INLET PRESS 2360 PSI OUTLET PRESS FROM 500 PSI TO 1500 PSI 1/4" NPT	
H-1	1	1/4" SYNPLEX HOSE x 70 FT LG W/ MALE PIPE SWIVEL ENDS - TYPE 3133-04-140-140-840	
H-2	3	1/4" SYNPLEX HOSE x 18" LG W/ MALE PIPE SWIVEL ENDS TYPE 3133-04	
H-3	1	1" SYNPLEX HOSE x 10 FT LG W/ FEMALE SWIVEL ENDS - TYPE 3'00-16	
J-1	1	PIPE THREADED O-RING FLANGE 3000 PSI	
R-1	5FT	1/4" SCH 80 PIPE	ASTM A-105 GRADE-A-STL
V-1	1	1/4" THD IN-LINE RELIEF VALVE SET @ 1500 PSI	STEEL
V-2	2	1/4" BALL VALVE	
V-3	2	1" BALL VALVE	


## GENERAL NOTES: (UNLESS OTHERWISE NOTED)

1. REMOVE GAUGES WITH PRECISE TESTING.
2. ALL PIPING TO BE TESTED AT 2500 PSI.
3. GAUG RELIEF VALVE (V-1) DURING PRESSURE TESTING.

C

B

A



6

4

5

A



			ORANGE 3/4" DIA 500-1500 PSI	
G-2	1		GAUGE - 6" DIA 500-2500 PSI	
G-3	1		REGULATOR - INLET PRESS 2360 PSI OUTLET PRESS FROM 500 PSI TO 1500 PSI 1/4" NPT	
H-1	1		1/4" SYNIFLEX HOSE x 70 TT LG W/ MALE PIPE SWIVEL ENDS - TYPE 3188-04-140-140-240	
H-2	5		1/4" SYNIFLEX HOSE x 12' LG W/ MALE PIPE SWIVEL ENDS TYPE 3188-04	
H-3	1		1" SYNIFLEX HOSE x 10 FT LG W/ FEMALE SWIVEL ENDS - TYPE 2'00-16	
J-1	1		PIPE THREADED O-RING FLANGE 3000 PSI	
R-1	5FT		1/4" SCH 80 PIPE	ASTM A-53 (GRADE A-STEEL)
V-1	1		1/4" THD IN-LINE RELIEF VALVE SET @ 1500 PSI	STEEL
V-2	2		1/4" BALL VALVE	
V-3	2		1" BALL VALVE	

**GENERAL NOTES: (UNLESS OTHERWISE NOTED)**

1. REMOVE GAUGES WITH PRECURE TESTING.
2. ALL PIPING TO BE TESTED AT 2500 PSI.
3. GAG RELIEF VALVE (V-1) DURING PRESSURE TESTING.

E-001-AD12

NO. REQ'D	DESCRIPTION
0	ALTERATION
75W	DATE
	PURCHASING
	CONSTRUCTION
	ENGINEERING
	UNCS
	AMB
10	CUSTOMER
1	WALTERSTEDT
1	DIE
1	BUECHNER
1	MITCHELL
1	FARRHAM
2	LEDBETTER

0	12/08/87W	RELEASE FOR CONSTRUCTION	006	325000	006
A	12-1-80W	PRELIMINARY RELEASE	006	325000	006



**GLOBAL MARINE DEVELOPMENT INC.**  
Newport Beach, Calif.

THIS DRAWING AND THE DESIGN IT CONTAINS ARE THE CONFIDENTIAL PROPERTY OF GLOBAL MARINE DEVELOPMENT, INC. AND MAY NOT BE REPRODUCED OR DISCLOSED TO OTHERS OR USED FOR MANUFACTURE OR OTHER PURPOSES WITHOUT THE WRITTEN PERMISSION OF GLOBAL MARINE DEVELOPMENT, INC. AND DRAWING SHALL BE RETURNED TO GLOBAL MARINE DEVELOPMENT, INC. ON REQUEST.

**MARINE SEISMIC SYSTEM (MSS)  
HEAVE COMPENSATOR PIPING  
DIAGRAM**

APPROVED	EXAMINED OR REVIEWED	ALT. NO.	LETTER DATE	FILE REF. NO.	TOTAL NET WT. MAT'L	DATE	SCALE	TOLERANCE UNLESS OTHERWISE NOTED FRACTIONS - 1/32" ANGLES - 1/4" UNLESS NOTED - 1/8" DIA
AAA							NONE	
USCG								

BY: N. WAGNER	DATE: 12-1-80	SCALE: NONE	TOLERANCE UNLESS OTHERWISE NOTED FRACTIONS - 1/32" ANGLES - 1/4" UNLESS NOTED - 1/8" DIA
CHKD: W. H. S.	DATE: 12-1-80	JOB AUTH: 006	DWG. NO. E-001-AD12
APPD: P. H. S.	DATE: 12-1-80	JOB AUTH: 006	DWG. NO. E-001-AD12
CHKD: W. H. S.	DATE: 12-1-80	JOB AUTH: 006	DWG. NO. E-001-AD12

2

1

6