


AD A155 388


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
NOYES BROOK DAM (ME 0...U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 81

1/20

UNCLASSIFIED

FIG 13/13 NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A155 388

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER ME 00347	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Noyes Brook Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE September 1981
		13. NUMBER OF PAGES 80
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Saint John River Basin Limestone Maine Noyes Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The earthfill embankment is 1000 ft. long and 31 ft. high. The facility was found in good condition. It is small in size with a high hazard classification. No urgent or emergency actions are required for the dam based on this inspection.		

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY
 NEW ENGLAND DIVISION, CORPS OF ENGINEERS
 424 TRAPELO ROAD
 WALTHAM, MASSACHUSETTS 02254

REPLY TO
 ATTENTION OF:
 NEDED

SEP 23 1981

Honorable Joseph E. Brennan
 Governor of the State of Maine
 State Capitol
 Augusta, Maine 04330

Dear Governor Brennan:

Inclosed is a copy of the Noyes Brook Dam (ME-00347) Phase I Inspection Report, prepared under the National Program for Inspection of Non-Federal Dams. This report is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. I approve the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is vitally important.


Copies of this report have been forwarded to the Department of Agriculture and to the owner, Town of Limestone. Copies will be available to the public in thirty days.

I wish to thank you and the Department of Agriculture for your cooperation in in this program.

Sincerely,

C. E. EDGAR, III
 Colonel, Corps of Engineers
 Division Engineer

Incl
 As stated



Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/	23 211

NOYES BROOK DAM

ME 00347

ST. JOHN RIVER BASIN
LIMESTONE, MAINE

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

Identification No. : ME 00347
Name of Dam : Noyes Brook Dam
Town : Limestone
County & State : Aroostook, Maine
Stream : Noyes Brook
Date of Inspection : November 8, 1979


BRIEF ASSESSMENT

Noyes Brook dam is a ten year old submerged sediment storage pool and flood water retarding structure designed by the USDA Soil Conservation Service. The earth fill embankment is 1000 feet long and 31 feet high. The downstream slope, the crest and the upstream slope above the pool are grass covered. A reinforced concrete drop inlet principal spillway leads to a 30 inch diameter reinforced concrete pipe conduit under the dam that ends in a reinforced concrete impact basin. A grass lined earth cut emergency spillway is provided 950 feet north of the left abutment. The pool is maintained behind the dam at a normal elevation of 594 NGVD (approximate depth of 14 feet).

The embankment dam, principal spillway drop inlet, principal spillway impact basin and emergency spillway were found in good condition. In the embankment itself, there were no abnormal dips, sags or other evidence of distress. The reinforced concrete structures were sound with no evidence of deterioration. The grass cover on the embankment and emergency spillway was well developed. A point of seepage at the maximum section downstream toe was observed at 1.5 gal/sec. This seepage was free of suspended or transported solids.

Based on a maximum storage of 350 acre-feet and a height of 31 feet, Noyes Brook Dam falls within the small size classification. The dam's hazard classification has been established as high based on the potential for loss of more than a few lives in the event of a dam failure. The test flood used was the probable maximum flood. The test flood was estimated for the 2.85 square mile drainage area of rolling terrain using the "Preliminary Guidance for Estimating Maximum Probable Discharges in Phase I Safety Investigations", New England Division Corps of Engineers, March 1978. This yielded a peak inflow of 3900 cfs (1370 csm) and a peak routed outflow of 3470 cfs (about 11% reduction). The computed maximum reservoir level El. 608.9 was below the embankment crest El. 611.2 NGVD and no overtopping of the embankment would occur.


No urgent or emergency actions are required for Noyes Brook Dam based on this inspection. Remedial measures include monitoring the seepage at the toe of the dam, monitoring the project during periods of intense rainfall, developing a downstream warning system and conducting bi-annual technical inspections. These measures should be initiated within two years.


J.E. Giles, Jr., P.E.
Project Manager
Massachusetts PE No. 1643

This Phase I Inspection Report on Noyes Brook Dam (ME-00347) has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.



ARAMAST MAHTESIAN, MEMBER
Geotechnical Engineering Branch
Engineering Division




CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division



JOSEPH W. FINEGAN, JR., CHAIRMAN
Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of Phase I investigation: however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

REPORT



1. PROJECT INFORMATION	
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
c. Scope of Inspection Program	1-1
1.2 Description of Project	1-2
a. Location	1-2
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-3
e. Ownership	1-3
f. Operator	1-3
g. Purpose of Dam	1-3
h. Design and Construction History	1-3
i. Normal Operational Procedure	1-3

<u>Section</u>	<u>Page</u>
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1
3. VISUAL INSPECTION	
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-1
d. Reservoir Area	3-2
e. Downstream Channel	3-2
3.2 Evaluation	3-2
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	4-1
a. General	4-1
b. Description of any Warning System in Effect	4-1
4.2 Maintenance Procedures	4-1
a. General	4-1
b. Operating Facilities	4-1
4.3 Evaluation	4-1
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General	5-1
5.2 Design Data	5-1


<u>Section</u>	<u>Page</u>
5.3 Experience Data	5-1
5.4 Test Flood Analysis	5-1
5.5 Dam Failure Analysis	5-2
6. EVALUATION OF STRUCTURAL STABILITY	6-1
6.1 Visual Observation	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-1
6.4 Seismic Stability	6-1
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
7.4 Alternatives	7-2
<u>APPENDIXES</u>	
APPENDIX A - INSPECTION CHECKLIST	A-1
APPENDIX B - ENGINEERING DATA	B-1
APPENDIX C - PHOTOGRAPHS	C-1
APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1



OVERVIEW PHOTO



FROM: USGS LIMESTONE, ME
QUADRANGLE MAP



NOYES BROOK DAM LOCATION MAP

U.S. ARMY CORPS OF ENGINEERS
PHASE I INSPECTION PROGRAM

MAIN

DATE
CLIENT 100 PLATE
1345 72

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

NOYES BROOK DAM, LIMESTONE MAINE

SECTION I

PROJECT INFORMATION

1.1 General

- a. Authority - Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Chas. T. Main, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Maine. Authorization and notice to proceed were issued to Chas. T. Main, Inc. under a letter of November 6, 1979 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0011 has been assigned by the Corps of Engineers for this work.
- b. Purpose - The purposes of the inspection program are:
 - (1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
 - (2) To encourage and prepare the states to initiate effective dam safety programs for non-Federal dams.
 - (3) To update, verify and complete the National Inventory of Dams.
- c. Scope of Inspection Program - The scope of this Phase I inspection report includes:
 - (1) Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.

(2) A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.

(3) Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.

(4) An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgment on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.

1.2 Description of Project

- a. Location - The Noyes Brook Dam is located on Noyes Brook, one half mile above its confluence with Limestone Stream and 1.5 miles northeast of the Town of Limestone, Aroostook County, Maine. The dam location is included on U.S.G.S. 7.5 minute series Quadrangle, Limestone, Maine with approximate coordinates N46°55'50", W67°50'50".
- b. Description of Dam and Appurtenances - The project is a dual purpose recreation and floodwater retarding structure. It consists of three principal features: an earthfill dam, a principal spillway, and an emergency spillway. The dam is 1000 feet long, 31 feet high, and 14 feet wide at its crest. Material excavated from the emergency spillway channel was used for the fill in the dam. The fill materials are of glacial till origin with zoning limited to placing the more impervious material in the core and the more pervious material in the outside shells. The structure has a toe drain system with collector pipes and a central cutoff trench.

The principal spillway is a double 7'-6" wide ungated drop intake to a 30 inch diameter reinforced concrete pipe under the dam. The 30-inch pipe is provided with anti-seep collars and discharges into a reinforced concrete impact basin (energy dissipator). The dam has a 15" drain that discharges into the 30" conduit. The emergency spillway is an excavated, grass lined, earth channel approximately 950 feet from the left abutment. It is 226.4 feet wide at crest elevation of 607 feet with 2 horizontal to 1 vertical side slopes. The discharge from the emergency spillway is directed away from the downstream channel into Limestone Stream to the east (see drawing 2 of 18, page B-3).

Plans, profiles, and sections of the dam and its appurtenant structures are included in Appendix B. Photographs are shown in Appendix C.

- c. Size Classification - The maximum embankment height is 31 feet above the stream channel and the maximum storage is 350 acre feet at El. 611.2. This gives the dam a small size classification (less than 1000 ac.-ft and less than 40' high) according to the Recommended Guidelines for Safety Inspection of Dams.
- d. Hazard Classification - This facility is classified as a high hazard potential dam based on the potential for loss of more than a few lives in the event of a dam failure in six occupied dwellings 1200 to 4200 feet downstream of the dam.
- e. Ownership - The dam and associated works are owned by the Town of Limestone, Maine.
- f. Operators - The project is designed for unsupervised operation. No manual operations are required to pass a flood flow. The project is operated and maintained by the Town of Limestone, Maine. The responsible person is Mr. Thomas Stevens, Town Manager, Limestone, Maine 04750, Telephone (207) 325-3131.
- g. Purpose of Dam - The project is a floodwater retarding structure of standard USDA SCS design. The reservoir drain intake sluice gate is currently closed and the reservoir maintained at El. 594 NGVD for fish and recreation purposes.
- h. Design and Construction History - The project was designed by the USDA Soil Conservation Service and constructed by Hornbrook, Inc. in 1970.
- i. Normal Operating Procedures - The reservoir is normally maintained at El. 594. All flood flows are passed through the principal and emergency spillways which are designed for uncontrolled discharge. No other operating procedures are in evidence.

1.3 Pertinent Data

- a. Drainage Area - Noyes Brook Dam controls a drainage area of 2.85 square miles. The watershed is approximately 65 percent wooded and 35 percent agricultural. The slopes are gentle with one large swamp area upstream. The watershed ranges from Elev. 720 to Elev 580.
- b. Discharge at Damsite
 - (1) Outlet Works - A screw operated sluice gate and 15"Ø CMP provide the capability to drain the reservoir to El. 582.5 NGVD. This drain discharges into the base of the principle spillway riser.
 - (2) Maximum known flood - Unknown.
 - (3) Principal spillway capacity at top of dam - 155 cfs @ El. 611.2.

- (4) Principal spillway capacity at emergency spillway crest elevation - 143 cfs @ El. 607.
- (5) Gated spillway capacity at normal pond elevation - N/A.
- (6) Principal spillway capacity at test flood elevation - 148 cfs @ El. 608.9.
- (7) Emergency spillway capacity at test flood elev. - 3470 cfs @ El. 608.9.
- (8) Total project discharge at top of dam - 13,748 cfs @ El. 611.2.
- (9) Total project discharge at test flood elevation - 3,625 cfs @ El. 608.9.

c. Elevations (feet above NGVD)

(1) Streambed at toe of dam	580.0
(2) Bottom of cutoff	576.0
(3) Maximum tailwater	Not available
(4) Normal pool (Max. Depth = 14')	594.0
(5) Full flood control pool	607.0
(6) Spillway crest	
(a) Principal	594.0
(b) Emergency spillway crest	607.0
(7) Design surcharge (Original Design)	unknown
(8) Top of dam	611.2
(9) Test flood surcharge	608.9

d. Reservoir (Length in feet)

(1) Normal pool	1000
(2) Flood control pool	2800

(3)	Spillway crest pool	
(a)	Principal	1000
(b)	Emergency spillway crest pool	2800
(4)	Top of dam	3400
(5)	Test flood pool	3100
e.	<u>Storage (acre-feet)</u>	
(1)	Normal pool	94
(2)	Flood control pool	255
(3)	Spillway crest pool	255
(4)	Top of dam	350
(5)	Test flood pool	265
f.	<u>Reservoir Surface (acres)</u>	
(1)	Normal pool	4
(2)	Flood-control pool	33
(3)	Spillway crest	33
(4)	Test flood pool	38
(5)	Top of dam	45
g.	<u>Dam</u>	
(1)	Type	Earthfill
(2)	Length	1000 feet
(3)	Height	31 feet
(4)	Top Width	14 feet
(5)	Side Slopes	Upstream 3 Hor. to 1 Vert. Downstream 2.5 Hor. to 1 Vert.
(6)	Zoning	2 zones

- | | |
|---------------------|------------------------------------|
| (7) Impervious Core | Most impervious
toward the core |
| (8) Cutoff | 5' trench |
| (9) Grout curtain | None |
| (10) Other | None |

h. Diversion and Regulating Tunnel - None

i. Spillway (Principal)

- (1) Type - Reinforced concrete riser to 30" ϕ conduit
- (2) Length of weir - 15'
- (3) Crest elevation - El. 594 NGVD
- (4) Gates - Ungated
- (5) U/S Channel - N/A
- (6) D/S Channel - Natural
- (7) General - Reinforced Concrete Impact Basin at Outfall

Spillway (Emergency)

- (8) Weir crest - El. 607 NGVD
- (9) Length of weir - 226.4'
- (10) U/S Channel - Grass lined earth channel
- (11) D/S Channel - Grass lined earth channel
- (12) General - 2 Hor. to 1 Vert. side slopes

j. Regulating Outlets

- (1) Invert - El. 582.5 NGVD
- (2) Size - 15" ϕ CMP
- (3) Description - Sluice gate to drain reservoir
- (4) Control Mechanism - 15" ϕ Sluice gate w/screw operator
- (5) Other - None

SECTION 2
ENGINEERING DATA

2.1 Design

As built drawings of Noyes Brook Dam are on file at the GSA Federal Archives and Records Center, 380 Trapelo Road, Waltham, MA 02154 (617-223-2657). Design calculations and specifications were not available. The December 1964 Limestone Stream Watershed Work Plan indicates that:

"...hydrology and hydraulics analyses followed procedures given in the National Engineering Handbook of the Soil Conservation Service, Section 4, Supplement A, Hydrology (NEH 4A) and Section 5, Hydraulics (NEH 5)."

and for civil works:

"All designs are in accord with the latest Soil Conservation Service design criteria as set forth in Engineering Memoranda SCS-27, 31, 4D and 42; Technical Release No. 10; Section 3.21, Hydrology, Supplement A of the National Engineering Handbook; U.S. Weather Bureau Technical Paper No. 40; and other sources of recognized engineering material."

2.2 Construction

The Noyes Dam and appurtenances were constructed in 1970 by Hornbrook, Inc. No construction records or photographs were available to the inspection team. A set of "as built" construction prints was reviewed. Those pertinent to this report are included in Appendix B.

2.3 Operation

No formal operational procedures were available for review. The principal and emergency spillways are uncontrolled structures requiring no manual operations.

2.4 Evaluation

- a. Availability: A set of project design (SCS) drawings and a set of typical Soil Conservation Service Construction Specifications for nearby Durepo Brook Dam were reviewed.
- b. Adequacy: The evaluation was based on visual inspection, past performance history and engineering judgment and experience.
- c. Validity: The limited data available restrict evaluation of the Noyes Brook Dam and appurtenances to the visual inspection and

engineering judgment. The field inspection indicated that the external features of Noyes Brook Dam substantially agree with those shown on the available plans.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General - The field inspection was conducted by L. Seward and J. Jonas of Chas. T. Main, Inc. on 8 November 1979 and J.E. Giles, Jr., August 12, 1981. On the date of inspection, the Noyes Brook Dam and appurtenances were in good condition. No urgent or emergency actions are required at this time.

b. Dam

(1) Crest - The embankment crest was true to line with no abnormal dips, sags, cracks or other evidence of distress (Photos 2, 7 and 9). The as-built camber was observed and appears unchanged. At the left abutment, adjacent to Noyes Road, there is a low point which can be seen in the original design (see drawing number 2 of 18, page B-3; at station 13+00) and is apparent visually (Photos 7 & 8). It is understood from speaking with the local residents that during times of high water, there is a considerable flow (say 500-1000 cfs) that flows over Noyes Road at the left abutment. This flow runs down the road for a short distance and then turns back in towards the downstream channel. Wheel tracks were observed on the crest. The crest is grass covered with no pavement.

(2) Upstream slope - The upstream slope riprap appeared in good condition. The slope above the normal pool El. 594 has a well developed tight grass cover (Photo 1). There was no evidence of sloughing or erosion on the slope.

(3) Downstream slope - The downstream slope (Photo 7) has a well developed, tight grass cover. No significant gully action was observed on the slope. No slides or sags were observed.

(4) Downstream toe - The downstream toe is generally dry with no boils or seeps observed except at the toe drain (Photo 3). On the right side of the riprapped toe drain near sta. 25+00, a 1 1/2 gal/sec seep was issuing from the riprap. The flow carried no sediment or suspended fines (Photo 6).

(5) Underdrain system - Two 6-inch diameter toe drain collector pipes issue from the dam adjacent to the principal spillway outlet. These outlets both had minor clear flows.

(6) Instrumentation - No instrumentation was observed.

c. Appurtenant Structures

(1) Principal Spillway - The principal spillway intake (Photo 4) was observed from shore. The exposed concrete and trashrack steel appeared in good condition.

(2) Outlet works - The outlet impact basin (Photo 5) was found in good condition. All construction joints were tight. No spalling was observed. The reservoir drain inlet was submerged and could not be inspected. The outlet conduit could not be inspected. It was reported by the Project Operator (Limestone Town Manager) that the drain had not been recently operated.

(3) Emergency spillway - The emergency spillway was clear of debris and in good condition with a well developed grass cover.

d. Reservoir Area - No areas of potential or actual shoreline movement were observed.

e. Downstream Channel - The downstream channel (Photo 6) was clear with no evidence of erosion.

3.2 Evaluation - In general, the dam and appurtenances are in good condition. The toe seepage at the time of the inspection was within acceptable limits. The slopes are stable and the crest is in good shape. The concrete structures are sound. The low point at the left abutment is at approximate Elev. 608 which is one foot above the emergency spillway crest. Any water which flows over at this low point will flow down the road for a short way and then back towards the downstream channel. Erosion of the downstream toe is not considered a problem in this area. No urgent or emergency repairs are required.

SECTION 4

OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

- a. General: The principal and emergency spillways are uncontrolled crest structures. No manual operations are required to insure safe passage of a flood flow. No recent operation of the reservoir drain is reported.
- b. Description of Downstream Warning System: No warning system or emergency evacuation plans are in effect for this project.

4.2 Maintenance Procedures

- a. General: The Town of Limestone has an operation and maintenance agreement with the Soil Conservation Service. Each dam is inspected at least once annually and after every major storm. An inspection report is prepared and any required maintenance is then performed by the town.
- b. Operating Facilities: There are no manual operating facilities at this structure except for the reservoir drain gate on the principal spillway riser. No regular maintenance procedures for the project operating facilities are specified. Repairs are made as required.

4.3 Evaluation

The operating and maintenance procedures are limited for this project. The owner should establish procedures to inspect the structures regularly, to monitor the seepage at the toe of the dam, to keep the embankment free of brush and trees, and to monitor the project during periods of intense rainfall. The owner should arrange to have a technical inspection made on a bi-annual basis and establish a warning system to follow in the event of emergency conditions.

SECTION 5

EVALUATION OF HYDROLOGIC AND HYDRAULIC FEATURES

- 5.1 General - The watershed is 2.85 square miles of undeveloped rolling terrain. The dam is located on the Noyes Brook, about 0.5 miles upstream from the confluence with Limestone Stream. The earth embankment develops sufficient storage to reduce the Probable Maximum Flood (PMF) peak from 3900 cfs (1370 csm) to 3470 cfs (about 11% reduction).
- 5.2 Design Data - The dam was designed by the Soil Conservation Service, U.S. Department of Agriculture. The top of the dam elevation varies according to the as-built drawing (page B-3) from 611.7 feet at center to 611.2 feet at both abutments. This 0.5 foot variance, is the allowance for natural settlement at the center of the dam. The maximum height of the dam is 31.2 feet (capacity 350 ac. ft.) and is classified as a small dam. The principal spillway consists of a reinforced concrete riser, a gated reservoir drain, a principal spillway conduit with anti-seep collars and an energy dissipating structure at the outlet with a rip-rapped channel. The dam is equipped with a remote emergency spillway located approximately 950 feet north of the left abutment. The plans show that the emergency spillway channel bottom width is 226.4 feet which has a crest elevation of 607.0 feet. The plans indicate a channel depth at the crest of 9-12 feet, with channel side slopes of 2:1. The emergency spillway discharges away from the downstream channel (Noyes Brook) directing the flow into Limestone Stream to the east. At the left abutment of the dam there is a low spot (Station 18+00) which was designed to allow for water to flow over during the Design High Water (Elev. 608.8). This flow will then be directed over Noyes Road and back into the downstream channel.
- 5.3 Experience Data - There are no records of past floods or any overtopping of the dam.
- 5.4 Test Flood Analysis - Based upon "Preliminary Guidance for Estimating Maximum Probable Discharge", dated March 1978, the watershed classification (rolling), and our hydraulic computations, the test flood for this high hazard, small size dam is estimated to be equivalent to the PMF of 3900 cfs (1370 csm). The flood routing starting elevation was selected to be the recreation pool elevation (594 ft), and the inflow hydrograph peak was reduced by the volume between emergency spillway crest and principal spillway intake elevations. For this particular portion of Maine, the PMF runoff is assumed to be 13". The routed test flood outflow was determined in accordance with Corps of Engineers "Guidance for Estimating Effect of Surcharge Storage on Maximum Probable Discharges", and the hydraulic characteristics of the reservoir. The emergency spillway discharge was computed as open channel flow. The routed test flood outflow was determined as 3470 cfs, and corresponding water surface El. 608.9 ft. The top of the dam elevation is 611.2 ft and thus the dam

would not be overtopped. The emergency spillway capacity is more than 100 percent of the test flood. As a check, a second test flood routing was performed assuming weir control in the emergency spillway and the dam was not overtopped under these conditions.

- 5.5 Dam Failure Analysis - The volume in the reservoir corresponding to the water surface elevation 608.9 ft is 260 ac. - ft. which is considered at the time of dam failure. The impact of failure of the dam was assessed using the "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs" prepared by the Corps of Engineers. The breach discharge was estimated with the maximum water surface elevation during the test flood. The breach width was selected to be 35 percent of the length of the dam at mid-height. The discharge through the emergency spillway was not considered in the downstream prefailure flow since it is directed away from Noyes Brook and into Limestone Stream. An estimated flow of 1000 cfs was assumed for the downstream prefailure flow due to the low point at the left abutment and the principal spillway discharge. The total peak discharge during breach was estimated to be 84,200 cfs.

The results show that prior to dam failure there will be no flooding of the two houses located at Reach 4 (1200 feet downstream), about eight feet above the channel bed. Further downstream at Reach 14 (4200 feet downstream) the prefailure flow will cause some minor flooding of two houses located very near the channel bed but no flooding in the remaining four houses located some six to eight feet above the channel bed. The prefailure flow is assumed to be 1000 cfs. This results in a water depth of approximately four feet in the downstream channel through Reach 14 (4200 feet from the dam). In the event of a dam failure, the initial wave was calculated to reach a depth of 16.7 feet at Reach 4 where two houses will be impacted by about nine feet of water and a depth of 10.9 feet at Reach 14 where the four previously unflooded houses will be impacted by about four to six feet of water. In view of these results it is concluded that more than a few lives could be lost in the event of dam failure. Thus this dam constitutes a high hazard potential.

SECTION 6

EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observation

The visual inspection of November 8, 1979 revealed no dips, sags, depressions or other evidence of instability. Seepage of 1.5 gallons per second of clear water was observed at the toe of the downstream slope.

6.2 Design and Construction Data

Design calculations and construction records were not available for review in preparing this report. The construction drawings for the dam were reviewed. A typical construction specification for Durepo Brook Dam was reviewed as it was reported to be similar to the Noyes Brook specification. The Noyes Brook and Durepo Dam designs and specifications are according to SCS standard practice for floodwater retarding structures.

6.3 Post Construction Changes

No evidence of modification to the dam since construction was observed.

6.4 Seismic Stability

The dam is located in Seismic Zone No. 2 and, in accordance with recommended Phase I guidelines, does not warrant seismic analysis.

SECTION 7

ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

- a. Condition - The visual inspection indicates that Noyes Brook Dam is in good condition. The inspection revealed that there is a seepage of about 1.5 gallons per second at the downstream toe of the dam near Station 25+00.
- b. Adequacy of Information - The lack of in-depth engineering data did not allow for a definitive review. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data but is based primarily on visual inspection, past performance history and sound engineering judgment.
- c. Urgency - The recommendations and remedial measures presented below should be implemented by the owner within two years of receipt of this Phase I Inspection Report.

7.2 Recommendations - None

7.3 Remedial Measures The owner should:

- a. Monitor the seepage at the toe of the dam on at least a monthly basis. If any significant change in the flow volume or coloration is observed, engage a qualified registered professional engineer to determine its significance.
- b. Implement a monthly visual inspection program of the dam and appurtenances. Observations should be recorded in a maintenance log.
- c. Establish a system to monitor the project during periods of intense rainfall.
- d. Develop a downstream warning plan in the event of an emergency at the dam.
- e. Conduct bi-annual technical inspections of the project.
- f. Establish regular maintenance procedures at the project and continue to keep the embankments free of brush and trees.
- g. Remove the brush and trees from the downstream toe to a distance approximately 25' downstream.

h. Obtain and maintain a set of as-built drawings and technical investigation reports.

i. Insure the operability of the reservoir drain.

7.4 Alternatives

There are no practical alternatives to the recommendations of Sections 7.2 and 7.3.

APPENDIX A

FIELD INSPECTION CHECK LIST

30

INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT Noyes Brook Dam

DATE Nov. 8, 1979

TIME 12:00 Noon

WEATHER Fair - 40°F

U.S. ELEV. _____ U.S. _____ DN.S.

PARTY:

- | | |
|---|-----------|
| 1. <u>Lewis B. Seward - Hydrologist</u> | 6. _____ |
| 2. <u>Jan N. Jonas - Civil Engineer</u> | 7. _____ |
| 3. <u>Peerless J. Snow - Project Operator</u>
<u>(Town Manager, Limestone)</u> | 8. _____ |
| 4. <u>J.E. Giles, Jr. - Project Manager</u> | 9. _____ |
| 5. <u>August 12, 1981</u> | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
All of the project features were inspected by each of the party		
1. <u>members.</u>	_____	_____
2. _____	_____	_____
3. _____	_____	_____
4. _____	_____	_____
5. _____	_____	_____
6. _____	_____	_____
7. _____	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	611.2
Current Pool Elevation	594.0
Maximum Impoundment to Date	214 Ac./Ft.
Surface Cracks	None Visible
Pavement Condition	Riprap on u/s thick grass on d/s
Movement or Settlement of Crest	None noticable
Lateral Movement	None noticable
Vertical Alignment	No change noticed
Horizontal Alignment	No change noticed
Condition at Abutment and at Concrete Structures	Riprap at concrete struc.; undisturbed earthfill at abutment
Indications of Movement of Structural Items on Slopes	None
Trespassing on Slopes	Seeps at d/s rt. of outlet structure
Vegetation on Slopes	Thick grass
Sloughing or Erosion of Slopes or Abutments	No sloughing noticed
Rock Slope Protection - Riprap Failures	Riprap in good condition
Unusual Movement or Cracking at or near Toes	No cracking noticed
Unusual Embankment or Downstream Seepage	Concentrated outflow of about 1 1/2 gal./sec from riprap toe rt. side
Piping or Boils	None
Foundation Drainage Features	Outflow from both outlet structure
Toe Drains	Drain openings
Instrumentation System	None noticed

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. <u>Approach Channel</u> Slope Conditions Bottom Conditions Rock Slides or Falls Log Boom Debris Condition of Concrete Lining Drains or Weep Holes</p> <p>b. <u>Intake Structure</u> Condition of Concrete Stop Logs and Slots</p>	<p>None</p> <p>Concrete overflow with gate valve</p> <p>Good</p> <p>None</p>

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. <u>Concrete and Structural</u>	
General Condition	Very good
Condition of Joints	Tight
Spalling	None
Visible Reinforcing	None
Rusting or Staining of Concrete	None
Any Seepage or Efflorescence	None
Joint Alignment	Good alignment
Unusual Seepage or Leaks in Gate Chamber	Not applicable
Cracks	None
Rusting or Corrosion of Steel	None
b. <u>Mechanical and Electrical</u>	
Air Vents	None noticed
Float Wells	Not applicable
Crane Hoist	Not applicable
Elevator	Not applicable
Hydraulic System	Not applicable
Service Gates	Not applicable
Emergency Gates	Manually operated from top of struc.
Lightning Protection System	None
Emergency Power System	None
Wiring and Lighting System in Gate Chamber	None

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	
General Condition of Concrete	Good
Rust or Staining on Concrete	None
Spalling	"
Erosion or Cavitation	"
Cracking	"
Alignment of Monoliths	"
Alignment of Joints	"
Numbering of Monoliths	"

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Very good
Rust or Staining	None
Spalling	None
Erosion or Cavitation	None
Visible Reinforcing	None
Any Seepage or Efflorescence	None
Condition at Joints	Joints were tight
Drain Holes	Two circular openings at outlet, rip-
Channel	raped bed for seeping water at toe.
Loose Rock or Trees Overhanging Channel	Some small trees overhanging brook channel
Condition of Discharge Channel	Grassed banks with shrubs and small trees

INSPECTION CHECKLIST

PROJECT Noyes Brook Dam DATE Nov. 8, 1979
 PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
 DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p> <p>a. <u>Approach Channel</u> General Condition Loose Rock Overhanging Channel Trees Overhanging Channel Floor of Approach Channel</p> <p>b. <u>Weir and Training Walls</u> General Condition of Concrete Rust or Staining Spalling Any Visible Reinforcing Any Seepage or Efflorescence Drain Holes</p> <p>c. <u>Discharge Channel</u> General Condition Loose Rock Overhanging Channel Trees Overhanging Channel Floor of Channel Other Obstructions</p>	<p>None</p> <p>Not applicable - fields and meadows</p>

INSPECTION CHECKLIST


PROJECT Noyes Brook Dam DATE Nov. 8, 1979
PROJECT FEATURE Earthfill Dam NAME Lewis B. Seward
DISCIPLINE Hydro NAME Jan N. Jonas

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - SERVICE BRIDGE</u> a. <u>Super Structure</u> Bearings Anchor Bolts Bridge Seat Longitudinal Members Under Side of Deck Secondary Bracing Deck Drainage System Railings Expansion Joints Paint b. <u>Abutment & Piers</u> General Condition of Concrete Alignment of Abutment Approach to Bridge Condition of Seat & Backwall	Not applicable

APPENDIX B


ENGINEERING DATA

- Note: 1. All design records are in storage at the:
- National Archives and Records Service
GSA Federal Archives and Records Center
380 Trapelo Road, Waltham, Massachusetts
617-223-2657
2. No past inspection reports were available for review.
3. The following drawings are as built prints.



LIMESTONE STREAM WATERSHED PROJECT
 LIMESTONE QUARRY BORROW AREA
 LIMESTONE QUARRY
 PLAN OF STORAGE AND BORROW AREA
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

LEGEND
 PERMANENT ROAD
 TEMPORARY ROAD
 RAILROAD
 CONCRETE DAM
 DRAINAGE CANAL
 BORROW AREA
 QUARRY



LIMESTONE STREAM IMPROVEMENT PROJECT
 FLOOD WATER RETARDING DAM NO. 2
 MOVES AREA
 LIMESTONE STREAM
 SUBDIVISION OF WATER RESOURCES
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE





TABLE OF MATERIALS

ITEM	QUANTITY	UNIT	REMARKS
1. CONCRETE	1000	CU YD	FOR FOUNDATION
2. BRICK	10000	NO	COMMON
3. LUMBER	1000	LF	2x4
4. ROOFING	1000	SQ YD	ASPH/FLT
5. PAINT	100	GA	SEMI-GLOSS
6. GLASS	100	SQ FT	6x8
7. INSULATION	1000	CU YD	PERlite
8. PLASTER	1000	SQ YD	1/2" THICK
9. FINISH	1000	SQ YD	CONCRETE
10. FLOORING	1000	SQ YD	WOOD
11. ROOFING	1000	SQ YD	SHINGLE
12. PAINT	100	GA	FLAT
13. GLASS	100	SQ FT	4x6
14. INSULATION	1000	CU YD	Wool
15. PLASTER	1000	SQ YD	1/2" THICK
16. FINISH	1000	SQ YD	CONCRETE
17. FLOORING	1000	SQ YD	WOOD
18. ROOFING	1000	SQ YD	SHINGLE
19. PAINT	100	GA	FLAT
20. GLASS	100	SQ FT	4x6
21. INSULATION	1000	CU YD	Wool
22. PLASTER	1000	SQ YD	1/2" THICK
23. FINISH	1000	SQ YD	CONCRETE
24. FLOORING	1000	SQ YD	WOOD
25. ROOFING	1000	SQ YD	SHINGLE
26. PAINT	100	GA	FLAT
27. GLASS	100	SQ FT	4x6
28. INSULATION	1000	CU YD	Wool
29. PLASTER	1000	SQ YD	1/2" THICK
30. FINISH	1000	SQ YD	CONCRETE
31. FLOORING	1000	SQ YD	WOOD
32. ROOFING	1000	SQ YD	SHINGLE
33. PAINT	100	GA	FLAT
34. GLASS	100	SQ FT	4x6
35. INSULATION	1000	CU YD	Wool
36. PLASTER	1000	SQ YD	1/2" THICK
37. FINISH	1000	SQ YD	CONCRETE
38. FLOORING	1000	SQ YD	WOOD
39. ROOFING	1000	SQ YD	SHINGLE
40. PAINT	100	GA	FLAT
41. GLASS	100	SQ FT	4x6
42. INSULATION	1000	CU YD	Wool
43. PLASTER	1000	SQ YD	1/2" THICK
44. FINISH	1000	SQ YD	CONCRETE
45. FLOORING	1000	SQ YD	WOOD
46. ROOFING	1000	SQ YD	SHINGLE
47. PAINT	100	GA	FLAT
48. GLASS	100	SQ FT	4x6
49. INSULATION	1000	CU YD	Wool
50. PLASTER	1000	SQ YD	1/2" THICK
51. FINISH	1000	SQ YD	CONCRETE
52. FLOORING	1000	SQ YD	WOOD
53. ROOFING	1000	SQ YD	SHINGLE
54. PAINT	100	GA	FLAT
55. GLASS	100	SQ FT	4x6
56. INSULATION	1000	CU YD	Wool
57. PLASTER	1000	SQ YD	1/2" THICK
58. FINISH	1000	SQ YD	CONCRETE
59. FLOORING	1000	SQ YD	WOOD
60. ROOFING	1000	SQ YD	SHINGLE
61. PAINT	100	GA	FLAT
62. GLASS	100	SQ FT	4x6
63. INSULATION	1000	CU YD	Wool
64. PLASTER	1000	SQ YD	1/2" THICK
65. FINISH	1000	SQ YD	CONCRETE
66. FLOORING	1000	SQ YD	WOOD
67. ROOFING	1000	SQ YD	SHINGLE
68. PAINT	100	GA	FLAT
69. GLASS	100	SQ FT	4x6
70. INSULATION	1000	CU YD	Wool
71. PLASTER	1000	SQ YD	1/2" THICK
72. FINISH	1000	SQ YD	CONCRETE
73. FLOORING	1000	SQ YD	WOOD
74. ROOFING	1000	SQ YD	SHINGLE
75. PAINT	100	GA	FLAT
76. GLASS	100	SQ FT	4x6
77. INSULATION	1000	CU YD	Wool
78. PLASTER	1000	SQ YD	1/2" THICK
79. FINISH	1000	SQ YD	CONCRETE
80. FLOORING	1000	SQ YD	WOOD
81. ROOFING	1000	SQ YD	SHINGLE
82. PAINT	100	GA	FLAT
83. GLASS	100	SQ FT	4x6
84. INSULATION	1000	CU YD	Wool
85. PLASTER	1000	SQ YD	1/2" THICK
86. FINISH	1000	SQ YD	CONCRETE
87. FLOORING	1000	SQ YD	WOOD
88. ROOFING	1000	SQ YD	SHINGLE
89. PAINT	100	GA	FLAT
90. GLASS	100	SQ FT	4x6
91. INSULATION	1000	CU YD	Wool
92. PLASTER	1000	SQ YD	1/2" THICK
93. FINISH	1000	SQ YD	CONCRETE
94. FLOORING	1000	SQ YD	WOOD
95. ROOFING	1000	SQ YD	SHINGLE
96. PAINT	100	GA	FLAT
97. GLASS	100	SQ FT	4x6
98. INSULATION	1000	CU YD	Wool
99. PLASTER	1000	SQ YD	1/2" THICK
100. FINISH	1000	SQ YD	CONCRETE


LITTLE STREAM WATERSHED PROJECT
 WILLIAM SPILLMAN LEECH
 ARCHITECT
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE



Approved by: _____ Date: _____
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

DRAINAGE SYSTEM

NO.	DESCRIPTION	QUANTITY	UNIT	PRICE	TOTAL
1	Excavation	100	cu yd	1.00	100.00
2	Structure	1	unit	50.00	50.00
3	Material	200	cu yd	0.50	100.00
4	Gate	1	unit	20.00	20.00
5	Other	10	units	1.00	10.00
TOTAL					280.00



CONSTRUCTION DETAILS

1. Use the same concrete mix as for the dam.
 2. Use the same reinforcement as for the dam.
 3. Use the same formwork as for the dam.
 4. Use the same construction methods as for the dam.

ALTERNATE W TO SECTIONS

Station	Collar Location	Collar Elevation
100+00	Top of Spillway	100.00
100+10	Top of Spillway	100.00
100+20	Top of Spillway	100.00
100+30	Top of Spillway	100.00
100+40	Top of Spillway	100.00
100+50	Top of Spillway	100.00
100+60	Top of Spillway	100.00
100+70	Top of Spillway	100.00
100+80	Top of Spillway	100.00
100+90	Top of Spillway	100.00
101+00	Top of Spillway	100.00

ALTERNATE W TO SECTIONS


Station	Collar Location	Collar Elevation
100+00	Top of Spillway	100.00
100+10	Top of Spillway	100.00
100+20	Top of Spillway	100.00
100+30	Top of Spillway	100.00
100+40	Top of Spillway	100.00
100+50	Top of Spillway	100.00
100+60	Top of Spillway	100.00
100+70	Top of Spillway	100.00
100+80	Top of Spillway	100.00
100+90	Top of Spillway	100.00
101+00	Top of Spillway	100.00

ALBANY, N. Y. 12208
 U. S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

Item No.	Description	Quantity	Unit	Price	Total
101	Excavation for foundation	100	cu yd	1.50	150.00
102	Concrete foundation	100	sq ft	1.20	120.00
103	Reinforcing steel	100	lb	0.05	5.00
104	Formwork	100	sq ft	0.10	10.00
105	Foundation	100	sq ft	1.50	150.00
106	Excavation for foundation	100	cu yd	1.50	150.00
107	Concrete foundation	100	sq ft	1.20	120.00
108	Reinforcing steel	100	lb	0.05	5.00
109	Formwork	100	sq ft	0.10	10.00
110	Foundation	100	sq ft	1.50	150.00
111	Excavation for foundation	100	cu yd	1.50	150.00
112	Concrete foundation	100	sq ft	1.20	120.00
113	Reinforcing steel	100	lb	0.05	5.00
114	Formwork	100	sq ft	0.10	10.00
115	Foundation	100	sq ft	1.50	150.00
116	Excavation for foundation	100	cu yd	1.50	150.00
117	Concrete foundation	100	sq ft	1.20	120.00
118	Reinforcing steel	100	lb	0.05	5.00
119	Formwork	100	sq ft	0.10	10.00
120	Foundation	100	sq ft	1.50	150.00

LIMESTONE STREAM WATERBED PROJECT
 FLOOD WATER RETARDING DAM NO. 2
 NOYES BROOK
 LIMESTONE, MAINE
 1957
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE
 WASHINGTON, D.C.

APPENDIX C
PHOTOGRAPHS



LEGEND

① PHOTO LOCATION

**NOYES BROOK DAM
PHOTO LOCATION**

**U.S. ARMY CORPS OF ENGINEERS
PHASE I INSPECTION PROGRAM**

MAIN

DATE

CLIENT 100 PLATE
1345 72 3



Photo 1
Upstream Slope From
Right Abutment



Photo 2
Crest From
Right Abutment



Photo 3
Downstream Toe
Seepage Area
& Toe Drain Detail




Photo 4
Principal Spillway




Photo 5
Impact Basin &
Underdrain Outfalls



Photo 6
Downstream Channel



Photo 7

Crest of Dam

Toward left Abutment




Photo 8

View of Noyes Road

Looking Downstream at

Left Abutment of Dam



Photo 9

Downstream Slope from

Right Abutment




Photo 10


Emergency Spillway
from left embankment.
Noyes Brook Dam is
beyond the red house.



Photo 11

Emergency Spillway
viewed from left
embankment looking
downstream.

ESTIMATING EFFECT
ON MAXIMUM



STEP 1: Determine P
Curves.

STEP 2: a. Determine
"Qp1".

b. Determine
(STOR₁) In

c. Maximum l
England e

$$Q_{p2} =$$


STEP 3: a. Determining
"STOR₂"

b. Average
Determining
Resulting

DIX D

HAULIC COMPUTATIONS

"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_0 = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS 1/2 OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2} (\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING Q_{p2} (TRIAL).

D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

SURCHARGE STORAGE ROUTING SUPPLEMENT

STEP 3: a. Determine Surchage Height and
"STOR₂" To Pass "Q_{p2}"



b. Avg "STOR₁" and "STOR₂" and
Compute "Q_{p3}".

c. If Surchage Height for Q_{p3} and
"STOR_{AVG}" agree O.K. If Not:


STEP 4: a. Determine Surchage Height and
"STOR₃" To Pass "Q_{p3}"

b. Avg. "Old STOR_{AVG}" and "STOR₃"
and Compute "Q_{p4}"

c. Surchage Height for Q_{p4} and
"New STOR_{AVG}" should Agree
closely



LOCATION MAP



MAP SOURCE: US DI-GS FORT FAIRFIELD & VAN BUREN, MAINE QUADR. SHEETS.
Scale 1 = 62500

NOYES BROOK DAM DRAINAGE AREA MAP

U.S. ARMY CORPS OF ENGINEERS
PHASE I INSPECTION PROGRAM



MAIN

DATE

CLIENT 100 PLATE
1345 72 1

MAIN


Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 1 of 23
 Subject NOYES BROOK RESERVOIR By T. OTOVA Date 2-3-81
CURVE FITTING OF THE CAPA- Ctd. Rev.
CITY CURVE

I	X(I)	Y(I)
1	500	500.0000
2	510	510.0000
3	520	520.0000
SOURCE OF LOG		
TOTAL	2000.00	500
REG 1	1960.00	57.0
RESID 1	40.00	4
SQUARES =		0.983

YHAT = 564.049 + 0.958 LOG X

X(I)	Y(I)	YHAT	RESIDUALS
500.00	500.00	500.40	-0.40
510.00	510.00	511.49	-1.49
520.00	520.00	519.00	0.00

600
602
604
606
608
610
612
614
616
618
620



MAIN


Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 2 of 23
 Subject NOYES BROOK RESERVOIR By T. OZAWA⁰¹⁵ Date 2-3-81
CAPACITY CURVE Ckd. _____ Rev. _____

40.00	593.77	400.00	012.30
42.00	594.72	450.00	013.20
44.00	595.67	500.00	014.10
46.00	596.64	550.00	014.90
48.00	597.64	600.00	015.60
50.00	598.69	650.00	016.24
52.00	599.76	700.00	016.84
54.00	600.84	750.00	017.40
56.00	601.96	800.00	017.91
58.00	603.11	850.00	018.40
60.00	604.24	900.00	018.85
62.00	605.34	950.00	019.28
64.00	606.41	1000.00	019.71
66.00	607.45		
68.00	608.46		
70.00	609.44		
72.00	610.39		
74.00	611.31		

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 3 of 23
Subject NINES BRACK RESERVOIR By T. D. J. VA Date 2-3-81
AREA - CAPACITY CURVE Chd. _____ Rev. _____


AREA - CAPACITY CURVES



MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 4 of 23
 Subject NOYES BROOK RESERVOIR By T. OTOVA Date 2-3-81
EMERGENCY SPILLWAY RATING CURVE Ctd. _____ Rev. _____

EMERGENCY SPILLWAY RATING CURVE



Open Channel Formula: $Q = \frac{1.49 \times A \times R^{2/3} \times S^{1/2}}{m}$

$m = 0.03$ (assumed)

$S = 0.01$ (averaged from the drawing)

(Computations based on open channel flow as being more conservative than the broad crested weir approach.)

GRADE-AREA METHOD

No. OF CROSS-SEC. POINTS = 4

SLOPE = 01

ELEV.	AREA	DISCH.
607	0	0
608	1130.2	1130.2
609	3606.8	3606.8
610	7125.6	7125.6
611	11597.2	11597.2
611.2	13550.4	13550.4

M S ELEV.

DISCHARGE

607

0

608

1130.2

609

3606.8

610

7125.6

611

11597.2

611.2

13550.4

MAIN

Client CORPS OF ENGINEERS

Job No. 1345-072

Sheet 5 of 23


Subject NOYES BROOK RESERVOIR

By T. STUBB

Date 2-3-81

EMERGENCY SPILLWAY RATING CURVE

Chd. _____ Rev. _____



EMERGENCY SPILLWAY RATING CURVE

MAIN

Client CORPS OF ENGINEERS

Job No. 1345-072 Sheet 5^A of 23

Subject NOYES BROOK DAM

By T. OTOVA Date 2-3-81

PRINCIPAL SPILLWAY RATING TABLE

Chg. _____ Rev. _____

PRINCIPAL SPILLWAY

The formula used in these calculations is presented in the Bureau of Reclamation's DESIGN OF SMALL DAMS (1977) page 557, Figure B-10

$$Q = 2.5294 * (1 + K_e)^{-0.5} * D^{2.5} * H^{1.5} * \left[\frac{1.49}{n} \right]^{0.58} * L^{0.78} * D^{0.12}$$

Where:

- H = Head in feet
- K_e = Entrance loss coefficient
- D = Diameter of pipe in feet
- n = Mannings roughness coefficient
- L = Length of culvert in feet
- Q = Design discharge rate in cfs

- K_e = 2
- D = 2.5 (ft)
- n = .01
- L = 140 (ft)

ENTRANCE ELM = 594 (ft)
 OUTLET ELM = 581 (ft)

ELEVATION (ft) DISCHARGE (cfs)

600	80	140
600	10	141
600	54	142
600	9	143
600	26	144
600	33	145
600	33	146
600	33	147
600	33	148
600	33	149
600	33	150
600	33	151
600	33	152
600	33	153
600	33	154
600	33	155

MAIN

Client CORPS OF ENGINEERS Job No. 1345-07 Sheet 6 of 23
Subject NOYES BROOK RESERVOIR By T. J. T. V. ⁰¹⁵ Date 2-3-81
FLOOD ROUTING Ckd. _____ Rev. _____

Drainage Area = 2.85 sq. mi.

For 19" runoff and for rolling terrain the PMF curves yield $q_{PMF} = 2000 \text{ cfs/sq. mi.}$

Then,

$$Q_{PMF} = 2.85 \times 2000 = 5700 \text{ cfs.}$$

The Depth - Area - Duration curves for this part of MAINE show a 13" runoff.

The revised peak discharge,

$$Q_{PMF} = 5700 \times \frac{13}{19} = 3900 \text{ cfs.}$$

The test flood is selected to be 3900 cfs.

MAIN

Client CORPS OF ENGINEERS Job No. 1345-072 Sheet 7 of 23
 Subject NOYES BROOK RESERVOIR By T. OTOVA Date 2-3-81
FLOOD ROUTING Ckd. _____ Rev. _____

CALCULATIONS

S T E P 1

ESTIMATING
 EFFECT OF SURCHARGE STORAGE
 ON MAXIMUM PROBELE DISCHARGES

These calculations are performed according to the Corps of Engineers Guidelines

NOYES BROOK DAM

D R A I N A G E

DRAINAGE AREA
 $A = 2.25$ (sq mi.)

PEAK INFLOW
 $Q_{p1} = 3990$ (cfs)

PRINCIPAL SPILLWAY CREST ELEV.
 $ELV_1 = 594$ (ft.)

EMERGENCY SPILLWAY CREST ELEV.
 $ELV_2 = 607$ (ft.)

Emergency Spillway Rating Curve is defined as:

$$H = a * Q^b * c$$

$a = 0.0377588$
 $b = 2.55791$

The Capacity - Elv. curve is defined as:

$$Elv = m + n * Log(Volume)$$

$m = 552.349$
 $n = 0.353$

TOTAL PMP RANGE
 $= 13$ (in.)

Reduction of the Q_{p1} due to starting elevation at Principal Spillway crest elev.

Volume at 594 (ft.)

Volume1 = $Exp((ELV_1 - m)/n)$
 Volume1 = 41,137 (ac-ft)

Volume at 607 (ft.)

Volume2 = $Exp((ELV_2 - m)/n)$
 Volume2 = 206,485 (ac-ft)

Diff. of Volumes:

Diff. Volume = 165,347 (ac-ft)
 or
 Diff Volume: D = 1.08 (in.)

NEW $Q_{p1} = Q_{p1} * (1 - D/R)$
 NEW $Q_{p1} = 3573$ (cfs)

S T E P 2

Surcharge Height:

$H = a * Q_{p1}^b * c$
 $H = 1.98$ (ft.)

Surcharge Volume:

$ELV = ELV_1 + H$
 $ELV = 606.98$ (ft.)

Volume = 264,193 (ac-ft)

STOR1 = Volume - Volume2

STOR1 = 57,708 (ac-ft)

or
 STOR1 = 1.37 (in.)

MAIN

Client CORPS OF ENGINEERS
Subject NOYES BROOK RESERVOIR
FLOOD ROUTING

Job No. 1345-072 Sheet 8 of 23
By T. OTAVA Date 2-3-81
Ckd. _____ Rev. _____

Corresponding Discharges:

Qp2 = Qp1 * (1 - STOR1/R)
Qp3 = 3469 (cfs)

STEP 3

Surcharge Height:

H = a * Qp3 ^ b
H = 1.94 (ft.)

Surcharge Volume: STOR2:

ELV = ELU2 + H
ELV = 508.94 (ft.)

Volume = 262.736 (ac-ft.)

Q1+ Volume = Volume - Volume2

Q1+ Volume = 56.25 (ac-ft.)

STOR2 = .37 (in.)

OLD STOR. AVE. = (STOR1 + STOR2)

OLD STOR. AVE. = .37 (in.)

Qp3 = Qp1 * (1 - OLD STO. AVE. / R)

Qp3 = 3470 (cfs)

STEP 4

Surcharge Height:

H = a * Qp3 ^ b
H = 1.94 (ft.)

Q1+ Volume: STOR3:

EL1 = 513 - H2

EL1 = 508.94 (cfs)

Volume = ELV * (EL1 - EL2) / 2

Volume = 262.755 (ac-ft.)

Q1+ Q3 = Volume - Volume2

Q1+ Q3 = 56.169 (ac-ft.)

STOR3 = .37 (in.)

NEW STO. AVE. = (OLD STO. AVE. + STOR3)

STOR3 = .2

NEW STO. AVE. = .37 (in.)

Qp4 = Qp1 * (1 - NEW STO. AVE. / R)

Qp4 = 3471 (cfs)

Surcharge Height:

H4 = a * Qp4 ^ b
H4 = 1.94 (ft.)

EL2 = EL1 + H2

EL2 = 508.94 (ft.)

CHECKING:

E3 - EL2 = 0 (ft.)

RESULTS:

AVERAGED DISCHARGE = 3470 (cfs)

WATER SURFACE ELEV. = 508.94 (ft.)

SURCHARGE HEIGHT = 1.94 (ft.)

CREST ELEV. OF THE DAM:
Ec = 511.2 (ft.)

VOLUME AT DAM CREST ELEV.
Vc = 347.738 (ac-ft.)

VOLUME AT MAX. WATER SURFACE ELEV.

Vm = 262.759 (ac-ft.)

MAIN

Client CORPS OF ENGINEERS
 Subject NOYES BROOK DAM
FAILURE ANALYSES

Job No. 1345-072 Sheet 9 of 23
 By T. OTTUM⁰¹⁵ Date 2-2-81
 Ctd. _____ Rev. _____

NOYES BROOK DAM FAILURE ANALYSES

These calculations are performed according to the RULE OF THUMB procedures of the Corps of Engineers

The breach discharge:
 $Q_b = 3.17 * W_b * a * 0.5 * Y_o^{3/2}$

where

Y_o is the height of the breach (from river bed to the max. pool level)

W_b is 75% of the length of the dam or $W_b = .35 * L$

a is the acceleration of the area $a = 11.2 \text{ ft/sec}^2$

- $L = 165 \text{ ft}$
- $W_b = 210 \text{ ft}$
- $a = 11.2 \text{ ft/sec}^2$

From above equation:
 $Q_{b1} = 33137 \text{ (cfs)}$

The natural channel cross sections are simplified as triangular cross sections

The stage-discharge relationship becomes as:

$$Q = [1.058 * n * \tan(a) * S * C_{os(a)}^{2/3} / 6^{1/5}]^{3/8} \dots (I)$$

where:

- Q = Discharge (cfs)
- a = Side slope angle (deg)
- S = Channel slope


The cross section Area:

$$A = W^2 / \tan(a) \dots (II)$$

The Volume of the Reservoir

$$V = 358,759 \text{ (ac-ft)}$$

$$V = 11445762.04 \text{ (cub-ft)}$$



MAIN

Client CORPS OF ENGINEERS


Job No. 1345-072-015 Sheet 14 of 23

Subject NOYES BROOK DAM

By T.OTOVA Date 2-3-81

FAILURE ANALYSES

Chd. _____ Rev. _____



BREACH (5) CALCULATIONS

Test flood discharge:
 $Q^* = 1300$ (cfs)

$h_1 = 5$ (ass.)
 $S = 0.125$
 $C = 0.87$
 $L = 300$ (ft)

From Formula (I),

Prefailure height,

$h_1 = 4.6$ (ft)

From Formula (II),

$A_1 = 242$ (sq. ft.)

$Q = Q_{e1} + Q^*$

From Formula (I),

Total Height,
 $h = 19.2$ (ft)

From Formula (II),

Total Area,
 $A = 4240$ (sq-ft)

Residual Area,

$A_2 = A - A_1$
 $A_2 = 3998$ (sq-ft)

Residual Volume,

$M_1 = L \times A_2$

$M_1 = 1199506$ (cub-ft)

$Q_{e2} = Q_{e1} \times (1 - W_1)$

$Q_{e2} = 39794$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q^*$

$Q = 40794$ (cfs)

$h = 13$ (ft)

From Formula (II),

$A = 3910$ (sq-ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3668$ (sq-ft)

$M_2 = A_2 \times L$

$M_2 = 1100404$ (cub-ft)

$W_{ave} = (M_1 + M_2) \div M_1$

$W_{ave} = 1149955$ (cub-ft)

$Q_{e2} = Q_{e1} \times (1 - W_{ave} \div W_1)$

$Q_{e2} = 35987$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q^*$

$h_2 = 18.5$ (ft)

RESULTS

1. Prefailure Height = 4.6 (ft)

2. Postfailure Height = 18.5 (ft)

3. Breach Discharge = 35987 (cfs)

4. Breach Length = 300 (ft)

MAIN

Client CORPS OF ENGINEERS

Job No. _____

Sheet 15 of 23

Subject NOYES BROOK DAM


By T.OTOVA

Date 2-3-81

FAILURE ANALYSES

Chd. _____

Rev. _____



PRELIMINARY CALCULATIONS

Test flood discharge
 $Q_t = 1000$ (cfs)

$a = 5$ (deg.)
 $S = 0.143$
 $L = 300$ (ft)

From Formula (I),

Pre-failure height,

$h_1 = 4.4$ (ft)

From Formula (II),

$A_1 = 230$ (sq-ft)

$Q = Q_{e1} + Q_t$

From Formula (I),

Total Height,
 $h = 18$ (ft)

From Formula (II),

Total Area,
 $A = 3731$ (sq-ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3500$ (sq-ft)

Residual Volume,

$V_1 = L \times A_2$

$V_1 = 1050210$ (cub-ft)

$Q_{e2} = Q_{e1} \times (1 - V_1 / V_2)$

$Q_{e2} = 36318$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q_t$

$Q = 37318$ (cfs)

$h = 17$ (ft)

From Formula (II),

$A = 3477$ (sq-ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3247$ (sq-ft)

$V_2 = A_2 \times L$

$V_2 = 974189$ (cub-ft)

Wave = $(V_1 + V_2) / 2$

Wave = 1012199 (cub-ft)

$Q_{e2} = Q_{e1} \times (1 - \text{Wave} / V_2)$

$Q_{e2} = 36451$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q_t$

$h_2 = 17.4$ (ft)

RESULTS

1.) Pre-failure Height = 4.4 (ft)

2.) Post-failure Height = 17.4 (ft)

3.) Breach Discharge = 36451 (cfs)

4.) Breach Length = 300 ft

MAIN

Client _____ Job No. _____ Sheet 16 of 23
 Subject _____ By _____ Date 2-3-81
 Chd. _____ Rev. _____

REACH (7) CALCULATIONS

Test flood discharge:
 $Q_t = 1000$ (cfs)
 $s = 3.77$ (deg.)
 $Q = 0143$
 $n = 0.07$
 $L = 300$ (ft)

From Formula (I),
 Prefailure height,
 $h_1 = 4$ (ft)

From Formula (II),
 $A_1 = 247$ (sq-ft)

$Q = Q_{p1} + Q_t$

From Formula (I),
 Total Height,
 $h = 15.6$ (ft)

From Formula (II),
 Total Area,
 $A = 3739$ (sq-ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 3492$ (sq-ft)

Residual Volume:

$V_1 = L \times A_2$

$V_1 = 1047855$ (cub-ft)

$Q_{p2} = Q_{p1} * (1 - V_1 / V)$

$Q_{p2} = 33114$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$Q = 34114$ (cfs)

$h = 15$ (ft)

From Formula (II),

$A = 3487$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3240$ (ft)

$V_2 = A_2 * L$

$V_2 = 972000$ (cub-ft)

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 1009931$ (cub-ft)

$Q_{p2} = Q_{p1} * (1 - V_{ave} / V)$

$Q_{p2} = 33234$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$h_2 = 15.1$ (ft)

RESULTS

- 1.) Prefailure Height = 4 (ft)
- 2.) Postfailure Height = 15.1 (ft)
- 3.) Breach Discharge = 33234 (cfs)
- 4.) Reach Length = 300 (ft)

MAIN

Client _____ Job No. _____ Sheet 17 of 23
 Subject _____ By _____ Date 2-3-81
 Cht. _____ Rev. _____

PRELIMINARY CALCULATIONS

Test flood discharge:
 $Q_T = 1000$ (cfs)

$\theta = 3$ (deg)
 $S = .014$
 $n = .07$
 $L = 300$ (ft)

From Formula (I),

Pretailure height,

$h_1 = 3.7$ (ft)

From Formula (II),

$A_1 = 263$ (sq-ft)

$Q = Q_{P1} + Q_T$

From Formula (I),

Total Height,
 $h = 13.9$ (ft)

From Formula (II),

Total Area,
 $A = 3730$ (sq-ft)

Residual Area,

$A_2 = A - A_1$
 $A_2 = 3466$ (sq-ft)

Residual Volume,

$V_1 = L * A_2$

$V_1 = 1040043$ (cub-ft)

$Q_{P2} = Q_{P1} * (1 - V_1 / V_2)$

$Q_{P2} = 30214$ (cfs)

From Formula (I),

$Q = Q_{P2} + Q_T$

$Q = 31214$ (cfs)

$h = 13$ (ft)

From Formula (II),

$A = 3480$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3217$ (ft)

$V_2 = A_2 * L$

$V_2 = 965155$ (cub-ft)

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 1002599$ (cub-ft)

$Q_{P2} = Q_{P1} * (1 - V_{ave} / V_2)$

$Q_{P2} = 30323$ (cfs)

From Formula (I),

$Q = Q_{P2} + Q_T$

$h_2 = 13.5$ (ft)

RESULTS :

1.) Pretailure Height = 3.7 (ft)

2.) Postfailure Height = 13.5 (ft)

3.) Breach Discharge = 30323 (cfs)

4.) Reach Length = 300 (ft)

MAIN

Client _____ Job No. _____ Sheet 18 of 23
 Subject _____ By _____ Date 2-3-81
 Ckd. _____ Rev. _____

PRELIMINARY CALCULATIONS

Test flood discharge
 $Q_t = 1000 \text{ (cfs)}$

$a = 3.2 \text{ (cfs)}$
 $g = 0.135$
 $n = 0.07$
 $L = 300 \text{ (ft)}$

From Formula (I),

Pre-failure height,

$h_1 = 3.8 \text{ (ft)}$

From Formula (II),

$A_1 = 252 \text{ (sq-ft)}$

$Q = Q_{p1} + Q_t$

From Formula (I),

Total Height,
 $h = 13.9 \text{ (ft)}$

From Formula (II),

Total Area,
 $A = 3431 \text{ (sq-ft)}$

Residual Area,

$A_2 = A - A_1$
 $A_2 = 3218 \text{ (sq-ft)}$

Residual Volume,

$V_1 = L \times A_2$

$V_1 = 965529 \text{ (cub-ft)}$

$Q_{p2} = Q_{p1} \times C_1 = 17765 \text{ (cfs)}$

$Q_{p2} = 17765 \text{ (cfs)}$

From Formula (I),

$Q = Q_{p2} + Q_t$

$Q = 28765 \text{ (cfs)}$

$h = 13 \text{ (ft)}$

From Formula (II),

$A = 3002 \text{ (sq-ft)}$

Residual Area,

$A_2 = A - A_1$

$A_2 = 3002 \text{ (sq-ft)}$

$V_2 = A_2 \times L$

$V_2 = 900385 \text{ (cub-ft)}$

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 933957 \text{ (cub-ft)}$

$Q_{p1} = Q_{p1} \times C_1 = V_{ave} / h_1$

$Q_{p1} = 17765 \text{ (cfs)}$

From Formula (I),

$Q = Q_{p1} + Q_t$

$h_2 = 13.5 \text{ (ft)}$

RESULTS

1) Pre-failure Height = 3.8 ft

2) Post-failure Height = 13.5 ft

3) Breach Discharge = 17765 cfs

4) Reach Length = 300 ft

MAIN

Client _____ Job No. _____ Sheet 19 of 23
 Subject _____ By _____ Date 2-3-81
 Ctd. _____ Rev. _____

P E P O H (10) CALCULATIONS

Test flood discharge:
 $Q_t = 1000$ (cfs)

$a = 3.23$ (dee.)
 $b = .91$
 $c = .87$
 $L = 300$ (ft)

From Formula (I),
 Prefailure height:
 $h_1 = 4$ (ft)

From Formula (II),
 $A_1 = 293$ (sq-ft)

$Q = Q_{p1} + Q_t$

From Formula (I),
 Total Height,
 $h = 14.3$ (ft)

From Formula (II),
 Total Area,
 $A = 3657$ (sq-ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 3363$ (sq-ft)

Residual Volume,
 $V_1 = L \times A_2$
 $V_1 = 1009075$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - V_1 / V)$

$Q_{p2} = 25395$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$Q = 26395$ (cfs)

$h = 13$ (ft)

From Formula (II),

$A = 3421$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3127$ (ft)

$V_2 = A_2 \times L$

$V_2 = 938268$ (cub-ft)

$Wave = (V_1 + V_2) / E$

$Wave = 973672$ (cub-ft)

$Q_{p2} = Q_{p1} \times (1 - Wave / V)$

$Q_{p2} = 25481$ (cfs)

From Formula (I),

$Q = Q_{p2} + Q_t$

$h_2 = 13.8$ (ft)

RESULTS

- 1.) Prefailure Height = 4 (ft)
- 2.) Postfailure Height = 13.8 (ft)
- 3.) Breach Discharge = 25481 (cfs)
- 4.) Reach Length = 300 (ft)

MAIN

Client _____ Job No. _____ Sheet 20 of 23
 Subject _____ By _____ Date 2-7-81
 Ckd. _____ Rev. _____

P E A C H (11) CALCULATIONS

Test flood discharge:
 $Q_t = 1000$ (cfs)

$a = 2.55$ (dead)
 $g = .01$
 $s = .07$
 $L = 300$ (ft)

From Formula (I),
 Prefailure height,
 $h_1 = 3.7$ (ft)

From Formula (II),
 $A_1 = 311$ (sq ft.)

$Q = Q_{e1} + Q_t$

From Formula (I),
 Total Height,
 $h = 12.7$ (ft)

From Formula (II),
 Total Area,
 $A = 3534$ (sq-ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 3223$ (sq-ft)

Residual Volume,
 $V_1 = L * A_2$
 $V_1 = 967083$ (cub-ft)

$Q_{e2} = Q_{e1} * (1 - V_1 / V)$

$Q_{e2} = 23362$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q_t$

$Q = 24262$ (cfs)

$h = 12$ (ft)

From Formula (II),

$A = 3403$ (ft)

Residual Area,

$A_2 = A - A_1$

$A_2 = 3092$ (ft)

$V_2 = A_2 * L$

$V_2 = 927781$ (cub-ft)

$V_{ave} = (V_1 + V_2) / 2$

$V_{ave} = 962432$ (cub-ft)

$Q_{e2} = Q_{e1} * (1 - V_{ave} / V)$

$Q_{e2} = 23339$ (cfs)

From Formula (I),

$Q = Q_{e2} + Q_t$

$h_2 = 12.3$ (ft)

RESULTS :

- 1) Prefailure Height = 3.7 (ft)
- 2) Postfailure Height = 12.3 (ft)
- 3) Breach Discharge = 23339 (cfs)
- 4) Reach Length = 300 (ft)

MAIN

Client _____ Job No. _____ Sheet 21 of 23
Subject _____ By _____ Date 2-3-81
Ctd. _____ Rev. _____

PREBREACH (12) CALCULATIONS

Test Flood discharge:
 $Q_1 = 1000$ (cfs)
 $s = 2.35$ (deg)
 $n = .31$
 $k = .07$
 $L = 300$ (ft)

From Formula (I),
Prefailure height:
 $h_1 = 3.6$ (ft)

From Formula (II),
 $A_1 = 317$ (sq. ft.)

$Q = Q_1 + Q_2$
From Formula (I),
Total Height:
 $h = 11.9$ (ft)

From Formula (III),
Total Area:
 $A = 3482$ (sq-ft)
Residual Area:
 $A_2 = A - A_1$
 $A_2 = 3164$ (sq-ft)

Residual Volume:
 $U_1 = L \times A_2$
 $U_1 = 949200$ (cub-ft)

$Q_2 = Q_1 \times (1 - U_1)$
 $Q_2 = 31403$ (cfs)
From Formula (I),
 $Q = Q_2 + Q_1$
 $Q = 22403$ (cfs)

$h = 11$ (ft)
From Formula (III),
 $A = 3272$ (ft)

Residual Area:
 $A_2 = A - A_1$
 $A_2 = 2954$ (ft)

$U_2 = A_2 \times L$
 $U_2 = 886395$ (cub-ft)

$Wave = (U_1 + U_2) / 2$
 $Wave = 917878$ (cub-ft)

$Q_2 = Q_1 \times (1 - Wave / U_1)$
 $Q_2 = 21467$ (cfs)

From Formula (I),
 $Q = Q_2 + Q_1$
 $h_2 = 11.6$ (ft)

RESULTS

- 1) Prefailure Height = 3.6 (ft)
- 2) Postfailure Height = 11.6 (ft)
- 3) Breach Discharge = 21467 (cfs)
- 4) Breach Length = 300 (ft)

MAIN

Client _____ Job No. _____ Sheet 22 of 23
Subject _____ By _____ Date 2-3-81
Ckd. _____ Rev. _____

REACH (13) CALCULATIONS

Test flood discharge:
 $Q_1 = 1000$ (cfs)
 $s = 2.35$ (sec.)
 $z = .01$
 $z = .07$
 $L = 300$ (ft)

From Formula (I),
Pretailure height,
 $h_1 = 3.6$ (ft)
From Formula (II),
 $A_1 = 317$ (sq. ft)

$Q = Q_1 - Q_r$
From Formula (I),
Total Height,
 $h = 11.6$ (ft)

From Formula (II),
Total Area,
 $A = 3279$ (sq. ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 2961$ (sq. ft)

Residual Volume,
 $V_1 = L * A_2$
 $V_1 = 888500$ (cub. ft)

$Q_2 = Q_1 * (1 - W_1)$
 $Q_2 = 19801$ (cfs)
From Formula (I),
 $Q = Q_2 + Q_r$
 $Q = 30801$ (cfs)
 $h = 11$ (ft)

From Formula (II),
 $A = 3095$ (ft)

Residual Area,
 $A_2 = A - A_1$
 $A_2 = 2777$ (ft)

$W_2 = A_2 * L$
 $W_2 = 833250$ (cub. ft)

$W_{ave} = (W_1 + W_2) / 2$
 $W_{ave} = 868800$ (cub. ft)

$Q_2 = Q_1 * (1 - W_{ave} / V_1)$
 $Q_2 = 19852$ (cfs)

From Formula (I),
 $Q = Q_2 + Q_r$
 $h_2 = 11.2$ (ft)

RESULTS

- 1.) Pretailure Height = 3.6 (ft)
- 2.) Posttailure Height = 11.2 (ft)
- 3.) Breach Discharge = 19852 (cfs)
- 4.) Reach Length = 300 (ft)



MAIN

Client _____ Job No. _____ Sheet 23 of 23
Subject _____ By _____ Date 2-3-81
Ckd. _____ Rev. _____

PRE-FLOOD (14') CALCULATIONS

Test flood discharge:
 $Q_1 = 1000$ (cfs)

$a = 2.35$ (deg)
 $m = 91$
 $n = 37$
 $L = 300$ (ft)

From Formula (I):

Pre-failure height:

$h_1 = 3.6$ (ft)

From Formula (II):

$A_1 = 317$ (sq-ft)

$Q = Q_{p1} + Q_1$

From Formula (I):

Total height:

$h = 11.2$ (ft)

From Formula (II):

Total Area:

$A = 2181$ (sq-ft)

Residual Area:

$A_2 = A - A_1$

$A_2 = 2782$ (sq-ft)

Residual Volume:

$U_2 = A_2 * L$

$U_2 = 834988$ (cub-ft)

$Q_{p2} = Q_{p1} * (1 - U_1 / U_2)$

$Q_{p2} = 18404$ (cfs)

From Formula (I):

$Q = Q_{p2} + Q_1$

$Q = 19404$ (cfs)

$h = 10$ (ft)

From Formula (II):

$A = 2938$ (ft)

Residual Area:

$A_2 = A - A_1$

$A_2 = 2620$ (ft)

$U_2 = A_2 * L$

$U_2 = 786004$ (cub-ft)

$Wave = (U_1 + U_2) / 2$

$Wave = 810541$ (cub-ft)

$Q_{p2} = Q_{p1} * (1 - Wave / U_2)$

$Q_{p2} = 18447$ (cfs)

From Formula (I):

$Q = Q_{p2} + Q_1$

$h_2 = 10.9$ (ft)

RESULTS

1) Pre-failure Height = 3.6 (ft)

2) Post-failure Height = 10.9 (ft)


3) Breach Discharge = 18447 (cfs)


4) Reach Length = 300 (ft)

APPENDIX E


NATIONAL INVENTORY OF DAMS

NOTE
 Required Earth Fill to be obtained
 from Emergency Spillway Excavation





- LEGEND**
- PERMANENT POOL
 - DESIGN HIGH WATER
 - STREAM
 - BUILDING
 - ROAD
 - 600 CONTOUR
 - RAILROAD
 - CONSTRUCTION LIMIT
 - ▨ AREA TO BE CLEARED
 - ▩ WASTE DISPOSAL AREA
 - AREA TO BE CLEARED AND GRUBBED
- NOTE**
Permanent Pool Contour line is construction limit





LIMESTONE STREAM WATERSHED PROJECT
 FLOOD - WATER RETARDING DAM NO 2
 NOYES BROOK
 LIMESTONE, MAINE

PLAN OF STORAGE AND BORROW AREA
 U. S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE


Designed	F JAGELS	Date	3-68	Approved by	
Drawn	M ATLAS	Date	4-68	Title	
Checked	R A H	Date	1-68	Sheet	N. 2
				of 18	ME-503-P

SCS-313-C (9-64)






EARTH FILL REQUIREMENTS							
ZONE	MATERIAL	SOURCE	MAX ROCK SIZE	MAX LIFT THICKNESS	REQUIRED WATER CONTENT	COMPACTION	
						CLASS	DEFINITION
1	Materials or mixtures of materials from Emergency spillway excavation EX. including such clean gravels, sands as are represented by samples from the 3, 6 and 10-12' depths of TP-203	Emergency Spillway Excavation	6"	9"	Min water content = optimum of 100% standard density	A	95% of maximum density as determined by ASTM D-698 Method D
2	Materials or mixtures of materials from Emergency spillway excavation.	Emergency Spillway Excavation	6"	9"	Min water content = optimum of 100% standard density	A	95% of maximum density as determined by ASTM D-698 Method D

- Maximum lift thickness prior to Compaction
- NOTE
- 1 See sheets LZ and LR for Test Pits
 - 2 The foundation surface (See Middle Creek)
 - 3 For fill adjacent to structures, Max. Rock Size: 5'




OUTLET CHANNEL DIKE SECTION
Sta 3+87 - 5+37


OUTLET CHANNEL ROCK RIP RAP (Equipment Placed)
Sta 3+87 - 4+07




LIMESTONE STREAM WATERSHED PROJECT			
FLOOD-WATER RETARDING DAM NO 2			
NOYES BROOK			
LIMESTONE, MAINE			
FILL PLACEMENT & SPILLWAY EXCAV.			
U.S. DEPARTMENT OF AGRICULTURE			
SOIL CONSERVATION SERVICE			
Designed F. JAGELS	Date 3-60	Approved by 1-16	
Drawn M. ATLAS	4-60	1-16	
Checked M		Sheet 5 of 10	Drawing No. ME-503-P





SECTION B-B
Not to scale




SECTION C-C
Not to scale








PLAN OF DRAINAGE SYSTEM



SECTION E-E
Not to scale






CONSTRUCTION DETAILS

All materials used shall conform to the specifications of the U.S. Army Corps of Engineers, District of Columbia, and the U.S. Army Corps of Engineers, District of Columbia, and the U.S. Army Corps of Engineers, District of Columbia.

The construction shall be in accordance with the specifications and will be subject to inspection with conditions.




QUANTITY SUMMARY

300 4'-0" of 6" dia Perf CMP
 8'-0" of 6" dia Perf CMP
 12'-0" of 6" dia Non-Perf CMP
 2 3'-0" elbows
 2 metal end caps

DRAIN FILL GRADATION	
SIZE (No.)	PERCENTAGE
3"	100
1"	52-70
7/8"	10-22
3/4"	59-80
No. 4	43-71
No. 10	8-55
No. 20	1-39
No. 30	3-25
No. 50	7
No. 100	0-5

NOTE
 40% of the material used in the fill should be larger than 200.

SMALL ANIMAL GUARD DETAILS




Revised M. White, 3/69. Rev drawn by E. Snow 3/69

LIMESTONE STREAM WATERSHED PROJECT
 FLOOD-WATER RETARDING DAM NO 2
 NOYES BROOK
 LIMESTONE, MAINE
 DRAINAGE DETAILS


U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by R. A. HYATT	Date 9-68	Approved by	Title
Drawn by R. L. ALLEN	Date 9-68	Checked	Sheet No. 6 of 18
Drawing No. ME-503-P			

Reservoir Drain Inlet
See Sheet 15



RISER
See Sheets B to E



B
Berm

48.6

Center of Dam


90°

14' Top Width of Dam

E. Drain Trench


66° 22'

PLAN VIEW




ALTERNATE "A"

PROFILE ALONG C OF PRINCIPAL SPILLWAY



ALTERNATE "B"

PROFILE ALONG C OF PRINCIPAL SPILLWAY



CONSTRUCTION DETAILS:

- 1. 30" inside Dia. Reinf. Conc. Water Pipe - Spec 109
 - a. (7) 20'-0" Sections - 140'-0" (Alternate "A")
 - (1) Wall Fitting For 10" Wall
 - b. (9) 16'-0" Sections - 144'-0" (Alternate "B")
 - (1) Wall Fitting For 10" Wall

2. Load for A or B

Load = 19,425 lbs per lin ft based on O D of 30.8 ft

Min. 3 edge bearing strength for 0.01" crack (non-prestressed pipe) = 9,235 lbs per ft AWWA C-300

Min. 3 edge bearing strength for 0.001" crack (prestressed pipe) = 6,944 lbs per ft AWWA C-301

Max. Pressure Head 31 ft

Reinf. Conc. Impact Basin Class 4000 Conc.

ALTERNATE "A" 20' SECTIONS		
JOINT	DISTANCE FROM RISER	INVERT ELEV OF CONDUIT
J-1	0 33	581.25
J-2	20 33	581.06
J-3	40 33	580.86
J-4	60 33	580.67
J-5	80 33	580.48
J-6	100 33	580.29
J-7	120 33	580.09
J-8	140 33	579.90

COLLAR LOCATION		
Collar	Distance from Riser Wall	Invert of 30" Conduit
C-1	4 33	581.21
C-2	24 33	581.02
C-3	44 33	580.83
C-4	64 33	580.63
C-5	84 33	580.44


Gradient = 0.964285%

ALTERNATE "B" 16' SECTIONS		
JOINT	DISTANCE FROM RISER	INVERT ELEV OF CONDUIT
J-1	0 33	581.25
J-2	16 33	581.10
J-3	32 33	580.95
J-4	48 33	580.80
J-5	64 33	580.65
J-6	80 33	580.50
J-7	96 33	580.35
J-8	112 33	580.20
J-9	128 33	580.05
J-10	144 33	579.90

COLLAR LOCATION		
Collar	Distance from Riser	Invert of 30" Conduit
C-1	4 33	581.21
C-2	24 33	581.03
C-3	44 33	580.84
C-4	64 33	580.61
C-5	88 33	580.43

Gradient = 0.9375%

Note: Dimensions for pipe lengths are based on nominal lengths and do not include creep



LIMSTONE STREAM WATERSHED PROJECT
 FLOOD-WATER RETARDING DAM NO 2
 NOYES BROOK
 LIMSTONE, MAINE
 PRINCIPAL SPILLWAY DETAILS
U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DESIGNED BY M. P. WHITE	DATE 5/68	APPROVED BY E. F. SNOW	DATE 5/68
PROJECT NO. 7		DRAWING NO. ME-503-P	

TP-1. Abutment 4 Sta. 22+00, 30 ft. dia.

0 - 1.5 Topsoil. Silty gravel. (GM)
1.5 - 1.5 Sandy gravel. About 5% fines, 40% f. to c. sand, 5% f. to c. gravel, 1% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-2. Abutment 6 Sta. 22+00, 30 ft. dia.

0 - 1.5 Topsoil. Silty gravel. (GM)
1.5 - 11.5 Gravelly sand. Grey. About 2% fines, 40% f. to c. sand, 40% f. to c. gravel, 10% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Moderate dilatancy. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-3. Abutment 8 Sta. 22+00, 30 ft. dia.

0 - 1 Topsoil. Silty gravel. (GM)
1.0 - 1.0 Sandy gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-4. Abutment 10 Sta. 22+00, 30 ft. dia.

0 - 1 Topsoil. Silty gravel. (GM)
1.0 - 1.0 Sandy gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-5. Abutment 12 Sta. 22+00, 30 ft. dia.

0 - 1 Topsoil. Silty gravel. (GM)
1.0 - 1.0 Sandy gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-6. Abutment 14 Sta. 22+00, 30 ft. dia.

0 - 1.5 Silty gravel. (GM)
1.5 - 9.5 Silty gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-7. Abutment 16 Sta. 22+00, 30 ft. dia.

0 - 1 Topsoil. Silty gravel. (GM)
1.0 - 1.0 Gravelly sand. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-8. Abutment 18 Sta. 22+00, 30 ft. dia.

0 - 1 Topsoil. Silty gravel. (GM)
1.0 - 1.5 Sandy gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-9. Abutment 120' dia from E Sta. 10+00

0 - 1.5 Topsoil. (GM)
1.5 - 9.0 Silty gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-10. Abutment 120' dia from E Sta. 10+00

0 - 1 Topsoil. (GM)
1.0 - 1.0 Gravelly sand. Grey. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-11. Abutment 120' dia from E Sta. 19+50

0 - 1 Topsoil. (GM)
1.0 - 1.0 Sandy gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-12. Abutment 120' dia from E Sta. 21+00

0 - 1.5 Topsoil. (GM)
1.5 - 5.0 Silty gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-13. Abutment 120' dia from E Sta. 21+00

0 - 1.0 Topsoil. (GM)
1.0 - 9.5 Silty gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.0', 10'

TP-14. E Sta. 25+00 in Stream Valley

0 - 2 Peat and Muck. With cobbles. GWT at surface. (Pt)
2 - 11 Silty gravelly sand. With cobbles. Grey. About 15% fines, 40% f. to c. sand, 25% f. to c. gravel, 20% f. to c. cobbles, occasional boulders (1" max.). Thin (1"-2") layers of silt (ML). Wet. Loose. Moderately plastic. Rapid dilatancy. Very permeable. Outwash. The percent of sand and gravel vary 15-20%. (Sw)
11 - 12 Clayey gravelly sand. Grey. About 10% fines, 40% f. to c. sand, 25% f. to c. gravel, 5% cobbles, (6" max.). Wet. Very hard. Moderately plastic. No dilatancy. Slow permeability. Till. (GC-SC)

TP-15. E Sta. 26+50 in Stream Valley

0 - 4 Peat and Muck. Much on info master. GWT at surface. (Pt)
4 - 10 Gravelly silty gravelly sand and gravelly sand. Yellow brown. About 5% fines, 40% f. to c. sand, 30% f. to c. gravel, 10% cobbles, (6" max.). Wet. Loose. Thin (1"-2") silty layers are moderately plastic. Very permeable. Outwash. Sample 1-1, 0'-4', 10'

TP-16. E Sta. 26+50 in Stream

0 - 2 Peat and Muck. GWT at surface. (Pt)
2 - 5 Gravelly sand and gravel. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 15% cobbles, (6" max.). Wet. Loose. Slightly plastic. Rapid dilatancy. Very permeable. Outwash. Sample 1-1, 0'-2', 10'

TP-17. E Sta. 26+00 (Left bank of Stream)

0 - 2 Peat and Muck. GWT at surface. (Pt)
2 - 5 Silty gravel. Grey. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Slightly plastic. Rapid dilatancy. Very permeable. Outwash. Sample 1-1, 0'-2', 10'

TP-18. E Sta. 27+00

0 - 1 Peat and Muck. GWT at surface. (Pt)
1 - 5 Silty gravel. Grey. About 10% fines, 40% f. to c. sand, 40% f. to c. gravel, 10% cobbles, (6" max.). Wet. Hard. Slightly plastic. Rapid dilatancy. Very permeable. Outwash. Sample 1-1, 0'-1', 10'

TP-19. Abutment 25' dia from E Sta. 25+00

0 - 1.5 Fieldstone. (GM)
1.5 - 11.5 Gravelly sand. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles up to 6". Particles are a mixture of hard and soft, semi-banded. Moist. to wet. Loose. Non-plastic. Very permeable. Outwash. Hole stopped at 10' due to caving of sides. Sample 1-1, 0'-1.5', 10'

TP-20. Abutment 25' dia from E Sta. 26+00

0 - 1 Topsoil. (GM)
1 - 1.5 Gravelly silty sand. Yellow brown. About 10% fines, 40% f. to c. sand, 40% f. to c. gravel, 10% cobbles, (6" max.). Wet. Hard. Slightly plastic. Rapid dilatancy. Very permeable. Outwash. GWT at 0'. (Sw)

TP-21. Abutment 25' dia from E Sta. 26+00

0 - 1 Topsoil. (GM)
1 - 7 Gravelly sand. Yellow brown. About 5% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles, (6" max.). Wet. Loose. Non-plastic. Rapid dilatancy. Very permeable. Outwash. (Sw)
7 - 13 Boulderly sandy gravel. About 5% fines, 20% f. to c. sand, 30% f. to c. gravel, 45% cobbles and boulders up to 2". Moist. Loose. Non-plastic. Rapid dilatancy. Very permeable. Outwash. GWT at 7'. (GC)
at 13 Bedrock. Greyish lime shale. (Pt)

TP-22. Abutment 220' dia from E Sta. 26+10

0 - 2 Topsoil and slope wash. (GM)
2 - 9 Silty sandy gravel. Yellow brown. About 15% fines, 25% f. to c. sand, 50% f. to c. gravel, 10% cobbles. Moist. Hard. Moderately plastic. Moderate dilatancy. Moderately permeable. Outwash. GWT at 8'. (Sw)
9 - 12.5 Clayey gravel. Grey-brown. About 25% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles, occasional boulders to 2". Wet. Hard. Moderately plastic. Slow dilatancy. Slow permeability. Till. (GC)

Leg Valley

much organic matter. (Pt)
Silty gravelly sand and gravelly sand. (SM-SB)
0-1.5 ft. to m. sand, 30% f. to c. gravel, 10% cobbles, 5% boulders, etc. Loose. Thin beds are moderately plastic. Outwash. Sample 10-1, 6'-8".

Topsoil
0-1 (Pt)
1-7 (GP)
Clayey sandy gravel. Yellow brown. About 35% fines, 25% f. to sand, 35% f. to c. gravel, 5% cobbles, (1" max.). Damp. Hard. Moderately plastic. No dilatancy. Slow permeability. Till.
At 7 (SH)
Bedrock. Brittle shale. Breaks into sharp angular pieces up to 6".

bank of Stream
0-1 (Pt)
1-3 (GM)
3 (GC)
At 8 (SH)
Bedrock. Brittle shale.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

Topsoil
0-1 (Pt)
1-10.5 (GP)
Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable. Outwash. Sample 18-1, 4'.
Yellow-brown. About 5-10% f. to m. gravel, 50% f. to c. gravel, 10% cobbles, (6" max.). Moderately plastic. No dilatancy. Low permeability. Till. 3'-10', GC-SC.

TP-23 E. Abutment 5 Sta. 25+20 Edge of Road

0-1 (Pt) Topsoil.
1-13 (GP) Silty gravel or gravelly sand. Greyish-brown. About 10% fines, 40% m. sand, 40% f. to c. gravel, 10% cobbles, (6" max.). Damp. Loose. Non-plastic. Rapid dilatancy. Very permeable. Outwash. GWT at 10'. Sample 23-1, 5'-6", SP.

TP-24 E. Abutment 10' d.s. from E Sta. 26+90

0-1 (Pt) Topsoil.
1-7 (GC) Clayey sandy gravel. Yellow brown. About 35% fines, 25% f. to sand, 35% f. to c. gravel, 5% cobbles, (1" max.). Damp. Hard. Moderately plastic. No dilatancy. Slow permeability. Till.
At 7 (SH) Bedrock. Brittle shale. Breaks into sharp angular pieces up to 6".

TP-5 E. Abutment 125' d.s. from E Sta. 26+60

0-1 (Pt) Topsoil.
1-3 (GM) Silty gravel. Yellow brown. About 15% fines, 60% f. to m. sand, 45% f. to c. gravel. Damp. Loose. Slightly plastic. Moderate dilatancy. Moderately permeable. Outwash.
3 (GC) Clayey sand gravel. Yellow brown. About 35% fines, 20% f. to c. sand, 40% f. to c. gravel, 5% cobbles, occasional 1' boulders. Damp. Hard. Moderately plastic. No dilatancy. Low permeability. Till.
At 8 (SH) Bedrock. Brittle shale.

TP-101 E. Spvy. - Back side of pond on hill level

0-1 (Pt) Topsoil.
1-10.5 (GP) Gravelly sand. About 5-10% fines, 50% f. to m. sand, 35% f. to c. gravel, 5% cobbles. Damp. Loose. Rapid dilatancy. Non-plastic. Very permeable.

TP-102 In back field along Durepo Road

0-2 (Pt) Dry peat.
2-4 (GM) Silty sandy gravel. GWT at 4'.
4-8 (GP) Silty gravel. Loose. 10% fines, 30% f. to c. sand, 60% f. to c. gravel.
8-10 (GC) Clayey gravel. 40% fines, 60% gravel.

LIMESTONE STREAM WATERSHED PROJECT
FLOOD-WATER RETARDING DAM NO 2
NOYES BROOK
LIMESTONE, MAINE
TEST PITS
U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
INVESTIGATED BY ERINAKES DATE
BY L GERRY 2/68
ME-503-P

AD A155 388

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
HOYES BROOK DAM (ME O. I.) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 81

216

FIG 13/13 NB

UNCLASSIFIED



END
DATE
FBI
8-85
DTI



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

TR-201 So. Hwy. S Sta. 3200

- 0 - 1 **Fillstone** up to 1.5' (GM)
- 1 - 4 **Silty gravel.** Yellow brown. About 15% fines, 30% f. to c. sand, 45% f. to c. gravel, 10% cobbles. Dump. Moderately hard. Slightly plastic. Till. (GM)
- 4 - 10+ **Clayey gravel.** Yellow brown. About 25% fines, 35% f. to c. sand, 20% f. to c. gravel, 20% cobbles, occasional boulders to 1.5' max. Wet. Hard. Moderately plastic. Very slow dilatancy. Slow permeability. Till. GWT at 7'. (GC)

TR-202 So. Hwy. S Sta. 4210

- 0 - 1 **Unsettled.** (GM)
- 1 - 3 **Silty gravel.** Yellow brown. About 15% fines, 40% f. to c. sand, 40% f. to c. gravel, 5% cobbles to 5". Dry. Moderately hard. Slightly plastic. Moderately permeable. Till. Sample 202-1, 2'-3", GM. (GM-BM)
- 3 - 7 **Clayey bouldery gravel.** Gray brown. About 25% fines, 20% f. to c. sand, 25% f. to c. gravel, 30% cobbles, occasional boulders up to 1.5'. Dump. Extremely hard. Moderately plastic. No dilatancy. Slow permeability. Till (stratified cobbles). Sample 202-2, 4'-5", GC. (GC)
- 7 - 9.5 **Sandy gravel.** Gray. About 10% fines, 30% s. sand, 30% f. to c. gravel, 10% cobbles, (6" max.). Dump. Moderately hard. Slightly plastic. Moderately permeable. Outwash. Dry hole. Sample 202-3, 8'-9", GP. (GP)

TR-203 So. Hwy. S Sta. 3220


- 0 - 1 **Unsettled.** (GM)
- 1 - 3 **Silty sandy gravel.** Yellow brown. About 10% fines, 40% f. to c. sand, 40% f. to c. gravel, 10% cobbles, occasional boulders to 1". Dump. Loose. Slightly plastic. Moderately permeable. Outwash. Sample 203-1, 2'-3", GM. (GM)
- 3 - 6 **Clean gravelly sand.** Gray. No fines, About 60% s. to c. sand, 35% f. to c. gravel, 5% cobbles. Dump. Loose. Non-plastic. Very permeable. Outwash. Sample 203-2, 3'-4", SP. (SP)
- 6 - 10 **Clayey gravel.** Gray brown. About 30% fines, 30% f. to c. sand, 30% f. to c. gravel, 10% cobbles and boulders, 1 boulder up to 2.5". Dump. Very hard. Moderately plastic. Slow permeability. Till. Sample 203-3, 8'-10", GC. In-place density test taken at 8'. 152 lbs. per cubic foot at 10.7% moisture. (GC)
- 10 - 12+ **Clean gravelly sand.** About 60% s. to c. sand, 40% f. to c. gravel. Outwash. No GWT. (GP)

TR-204 So. Hwy. S Sta. 4220


- 0 - 1 **Unsettled.** (GM)
- 1 - 8 **Silty sandy gravel.** Yellow brown. About 15% fines, 35% f. to c. sand, 40% f. to c. gravel, 10% cobbles, occasional boulders up to 1". Dump. Moderately hard. Moderately plastic. Moderately permeable. Till. Sample 204-1, 4", GM. In place density test taken at 4'. 126 lbs per cubic foot at 12% moisture. (GM)
- 8 - 13 **Slighty sand.** Yellow brown. About 25% fines, 30% f. to c. sand, 35% f. to c. gravel, 10% cobbles and boulders up to 2" max. Moist. Hard. Moderately plastic. Low permeability. Till. GWT at 7'. (GC)

TR-205 Test hole in gravel pit. 135' S. So. Hwy. S Sta. 4224


- 0 - 5 **Silty gravel.** Yellow brown. About 10% fines, 40% f. to c. sand, 40% f. to c. gravel, 10% cobbles, occasional boulders to 1.5". Dry. Loose. Slightly plastic. Moderately permeable. Outwash. (GM)
- 5 - 20 **Silty gravel.** Brown-gray. About 25% fines, 10% cobbles, 25% f. to c. sand, 35% f. to c. gravel, occasional boulders to 1.5". Dump. Moderately hard. Moderately plastic. Moderate permeable. Till. (GM)




COMPACTION CURVE
FIELD SAMPLE NO. 202.1
LABORATORY CLASSIFICATION - G-M




COMPACTION CURVE
FIELD SAMPLE NO. 203.2
LABORATORY CLASSIFICATION -




COMPACTION CURVE
FIELD SAMPLE NO. 202.2
LABORATORY CLASSIFICATION - SC-SM



COMPACTION CURVE
FIELD SAMPLE NO. 203.3
LABORATORY CLASSIFICATION -



COMPACTION CURVE
FIELD SAMPLE NO. 202.3
LABORATORY CLASSIFICATION - G-M



COMPACTION CURVE
FIELD SAMPLE NO. 204.1
LABORATORY CLASSIFICATION -

LEGEND

TR-4 Test Pit (backhoe)
 GW Ground Water Table
 u.s. or d.s. Upstream or downstream
 No. Spwy. Emergency Spillway
 L. Abut. or R. Abut. Left Abutment or Right
 Abutment

(GC) Field Classification
 (GM) Lab classification

TEST PIT NUMBERING SYSTEM

1-99 Contour of Dam
 101-199 Survey Area
 201-299 Emergency Spillway

ROCK SYMBOLS

Sh Shale

UNIFIED SOIL CLASSIFICATION SYSTEM SYMBOLS

- GW Well graded gravels; gravel sand mixture
- GP Poorly graded gravels
- GM Silty gravels; gravel-sand-silt mixtures
- GC Clayey gravels; gravel-sand-clay mixtures
- GU Well graded sand; sand-gravel mixture
- SP Poorly graded sands
- SM Silty sands; sand-silt mixtures
- SC Clayey sand; sand-clay mixtures
- ML Silts; silty, v. fine sands; sandy or clayey silts
- CL Clays of low to medium plasticity; silty, sandy, or gravelly clays
- Pt Peat


NOTE: All descriptions and classifications based on visual observations and the Unified Soil Classification System.

All test pits are located on plans and profiles for the site.


Test pitting accomplished from 6/21/67 to 6/27/67. All test pits logged by G. Erinhart, Geologist.

All test pits were dug with a truck-mounted hydraulic backhoe, Hy-Line 380.


All test hole depths at in feet.



WATER CONTENT IN PERCENT OF DRY WEIGHT
COMPACTION CURVE
 FIELD SAMPLE NO. 203.2
 LABORATORY CLASSIFICATION - GM



WATER CONTENT IN PERCENT OF DRY WEIGHT
COMPACTION CURVE
 FIELD SAMPLE NO. 203.3
 LABORATORY CLASSIFICATION - GC-GM



WATER CONTENT IN PERCENT OF DRY WEIGHT
COMPACTION CURVE
 FIELD SAMPLE NO. 204.1
 LABORATORY CLASSIFICATION - GM

LIMESTONE STREAM WATERSHED PROJECT
FLOOD - WATER RETARDING DAM NO. 2
NOYES BROOK
LIMESTONE, MAINE
TEST PITS

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

INVESTIGATED BY _____ Date _____
 Approved by _____
 Checked by G. ERINHART 6-27
 Drawn by BERRY 2/68
 Title _____
 Project No. _____
 File No. _____
 ME-503-P



PART I - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for instructions.

FORM APPROVED
OMB NO. 43-39421

REQUIREMENTS CONTROL SYMBOL
DAEM-CWE-17

STATE	IDENTITY NUMBER				
1	2	3	4	5	6
MA	0	0	3	4	7

IDENTIFICATION	[2] [3] [4] [5] [6] [7] [8]					[9] NAME	[10] LATITUDE (North)	[11] LONGITUDE (West)	[12] REPORT DATE		
	DIVISION	STATE	COUNTY	CORNER EAST	CORNER WEST				STATE	COUNTY	TYPE OF DAM
0 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80	NE	MA	00	03	02	NOYES BROOK DAM	46	55	8	17	78

IDENTIFICATION (Continued)	[13] POPULAR NAME										[14] NAME OF IMPOUNDMENT																																																													
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79
0 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80	SAME										UNNAMED																																																													

LOCATION	[15] DIVISION	[16] STATE	[17] RIVER OR STREAM										[18] NEAREST DOWNSTREAM CITY - TOWN - VILLAGE										[19] DIST. FROM DAM (mi)	[20] POPULATION																																																
			8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27		28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76
0 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80	0	10	INDYES BROOK										LIMESTONE										1.5	04302																																																

STATISTICS	[21] TYPE OF DAM										[22] YEAR COMPLETED	[23] PURPOSES										[24] STRUCTURAL HEIGHT (ft)	[25] HYDRAULIC HEIGHT (ft)	[26] IMPOUNDING CAPACITIES				[27A] CORP'S ENGR. DIST.	[27B] CON.	[27C] FILL	[27D] REPAIRS	[27E] OTHER	[27F] VERIFICATION DATE			BLANK																																				
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79
0 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80	RE										1970	R, R										31	29	350				04	N	N	N	N	70																																							

REMARKS	[28] REMARKS																																																																															
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80							
0 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80																																																																																





PART II - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for instructions.

FORM APPROVED
GSA NO. 48-80421
REGULATORY CONTROL SYMBOL
DAMS-CBE-17

STATE	IDENTITY NUMBER
W	0004

STATISTICS	[29] [30] [31] [32]		[33]		[34]		[35]		[36]		[37] [38]		[39] [40]		[41] [42]		[43] [44]		[45]		
	D/S	HAZ	CREST LENGTH (ft)	SPILLWAY TYPE	WIDTH (ft)	MAXIMUM DISCHARGE (cfs)	VOLUME OF DAM (CY)	INSTALLED (MW)	PROPOSED (MW)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	BLANK	
	2	1	000	U	5	148															5

MISC DATA	[46] OWNER															[47] ENGINEERING BY															[48] CONSTRUCTION BY																													
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59
	TDMA OF LIMESTONE															SOIL CONSERVATION SERVICE															MORNING DOCK, INC.																													

MISC DATA (Continued)	[49] DESIGN															[50] CONSTRUCTION															[51] OPERATION															[52] MAINTENANCE														
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59
	NONE															NONE															NONE															NONE														

MISC DATA (Continued)	[53] INSPECTION BY															[54] INSPECTION DATE			[55] AUTHORITY FOR INSPECTION																																												
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	DAY	MO	YR	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59

REMARKS	[56] REMARKS																																																											
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59



**PART III - INVENTORY OF DAMS IN THE UNITED STATES
SUPPLEMENTARY DATA**

STATE	IDENTITY NUMBER
000000	
REC00043	

LOCATION	TOWN										NEED PERMIT NO	STATE NUMBER										FERC NO	USGS SHEET																
	1-10	11-20	21-30	31-40	41-50	51-60	61-70	71-80	81-90	91-00	1-10	11-20	21-30	31-40	41-50	51-60	61-70	71-80	81-90	91-00	1-10	11-20	21-30	31-40	41-50	51-60	61-70	71-80	81-90	91-00	1-10	11-20	21-30	31-40	41-50	51-60	61-70	71-80	81-90
NONE	/ / / / / / / / / / / /											/ / / / / / / / / / / /											/ / / / / / / / / / / /																

DRAINAGE CHARACTERISTICS	DRAINAGE AREA SQ MI	FLOW DATA			CREST ELEV MSL	ADJUT. ELEV MSL	USABLE STORAGE ACRES FEET		RESERVOIR AREA ACRES	FLASH BOARD HT FEET	OUTLET CONDUITS SIZE		INVERT ELEV MSL		
	1-2	3-4	5-6	7-8	9-10	11-12	13-14	15-16	17-18	19-20	21-22	23-24			
	3	/	/	/	64	72	/	/	4		1	30	WCA	58	25

POWER DATA	GENERATION UNITS				AVERAGE ANNUAL GENERATION KWH	LAST GEN YEAR	RETIRED YEAR	FORMER USE	CAPACITY FACTOR
	NO	INSTALLED CAP KW	NO	PLANNED CAP KW	1-10	11-12	13-14	15-16	17-18
	/	/	/	/	/	/	/	/	/

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

NED FORM 1 JAN 79 80(7257)



PART III - INVENTORY OF DAMS IN THE UNITED STATES
SUPPLEMENTARY DATA

A-1

A-2

A-3

A-4

LOCATION	TOWN																				NEE PERMIT NO.	STATE NUMBER	FERC NO.																													
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59

LIMESTON

B-1

B-2

B-3

B-4

B-5

B-6

B-7

B-8

B-9

DRAINAGE CHARACTERISTICS	DRAINAGE AREA SQ MI	FLOW DATA			CREST ELEV. M.S.L.	ABUT. ELEV. M.S.L.	USABLE STORAGE ACRE FEET	RESERVOIR AREA ACRES	FLASH BOARD HT FEET																																											
		MIN. C.F.S.	AVE. C.F.S.	MAX. C.F.S.																																																
8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60

C-1

C-2

C-3

C-4

C-5

C-6

C-7

POWER DATA	GENERATION UNITS						AVERAGE ANNUAL GENERATION K.W.H.	LAST GEN YEAR	RETIRED YEAR	FORMER USE	CAPACITY FACTOR																																									
	INSTALLED NO.	CAP K.W.	PLANNED NO.	CAP K.W.																																																
8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60

FORM
NED 1 JAN 1980 (TEST)

2

III - INVENTORY OF DAMS IN THE UNITED STATES
SUPPLEMENTARY DATA

STATE		IDENTITY NUMBER				
1	2	3	4	5	6	7
M	E	0	0	3	4	7

(A-2)		(A-3)		(A-4)		(A-5)																																																		
NED PERMIT NO.		STATE NUMBER		F.E.R.C. NO.		U.S.G.S SHEET																																																		
24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
L																				MESTONE, MAINE																				A																

(B-4)		(B-5)		(B-6)		(B-7)		(B-8)		(B-9)		(B-10)		(B-11)		(B-12)																																											
MAX. C.F.S.		CREST ELEV. M.S.L.		ABUT. ELEV. M.S.L.		USABLE STORAGE ACRE FEET		RESERVOIR AREA ACRES		FLASH BOARD HT FEET		OUTLET CONDUITS NO. SIZE		INVERT ELEV. M.S.L.																																													
24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80			
6																				1		2		74																				4		1		30		1		WCA		53		25		B	

(C-3)		(C-4)		(C-5)		(C-6)		(C-7)																																																
AVERAGE ANNUAL GENERATION K.W.H.		LAST GEN YEAR		RETIRED YEAR		FORMER USE		CAPACITY FACTOR																																																
24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
/																				/																				C																

24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
/																				/																				D																

24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
/																				/																				E																





PART I - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for instructions.

[2] [3] [4] [5] [6] [7] [8] [9]

IDENTIFICATION	DIVISION			STATE			COUNTY			CONGR DIST			NAME																																							
	8	9	10	11	12	13	14	15	16	17	18	19		20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58
	NEDEME			00			302						NOYES BROOK DAM																																							

[13]

IDENTIFICATION (Continued)	POPULAR NAME																																																											
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60							
	SAME																																										UNNAMED																	

[15] [16] [17] [18]


LOCATION	REGION		RIVER OR STREAM																	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE																																
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59
	0	1	NOYES BROOK																	LIMESTONE																																

[21] [22] [23] [24] [25] [26] [27]

STATISTICS	TYPE OF DAM																	YEAR COMPLETED	PURPOSES	STRUCTURAL HEIGHT (ft)	HYDRAULIC HEIGHT (ft)	IMPOUNDING CAPACITIES																														
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24					25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	MAXIMUM (acre - ft.)		NORMAL (acre - ft.)											
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59
	RE																	1970	C, R	31	29	350																														

[28]

REMARKS	REMARKS																																																											
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60							



S IN THE UNITED STATES
IC LAW 92-367)

instructions.

FORM APPROVED
OMB NO. 49-ND421
REQUIREMENTS CONTROL SYMBOL
DAEN-CWE-17

STATE		IDENTITY NUMBER				
1	2	3	4	5	6	7
M	E	0	0	3	4	7

[9]

[10]

[11]

[12]

NAME	LATITUDE (North)	LONGITUDE (West)	REPORT DATE		
			DAY	MO	YR
ROCK DAM	46	55	8	17	1981

[14]

NAME OF IMPOUNDMENT

UNNAMED																																																																							1
---------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---

[18]

[19]

[20]

NEAREST DOWNSTREAM
CITY - TOWN - VILLAGE

DIST.
FROM
DAM
(mi)

POPULATION

LIPRESTONE																																																																					1.5	10430
------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	-----	-------

[24]

[25]

[26]

[27]

[27A]

[27B]

[27C]

[27D]

[27E]

[27F]

STRUC- TURAL HEIGHT (ft)	HYDRAULIC HEIGHT (ft)	IMPOUNDING CAPACITIES		COMPS ENGR. DIST.	OWN.	FED. #	FRV/REG (27D)	SCS #	VERIFICATION DATE	BLANK															
		MAXIMUM (acre - ft.)	NORMAL (acre - ft.)							DA	MO	YR													
31	29	350	94		N	N	N	T																	

[28]

REMARKS

																																																																							4
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	---



PART II - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for instructions.

[29] [30] [31] [32] [33] [34] [35] [36] [37] [38] [39] [40]

STATISTICS	D/S HAZ	CREST LENGTH (ft)		SPILLWAY			VOLUME OF DAM (CY)		POWER CAPACITY								NAV																																					
				TYPE	WIDTH (ft)	MAXIMUM DISCHARGE (cfs)			INSTALLED (MW)	PROPOSED (MW)	NO	YE	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)																																							
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58			
	2	/	1	0	0	0	U	/	/	/	/	/	/	/	/	/	/	4	8																																			

[46] [47]

MISC. DATA	OWNER																		ENGINEERING BY																																						
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58						
	T	O	W	N	O	F	L	I	M	E	S	T	O	N	E	/	/	/	/	/	/	/	/	/	/	/	/	/	S	O	I	L	C	O	N	S	E	R	V	A	T	I	O	N	S	E	R	V	I	C	E	/	H	O			

[49] [50] [51]

MISC. DATA (Continued)	REGULATORY AGENCY																																																									
	DESIGN																			CONSTRUCTION																			OPERATION																			
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58							
	N	O	N	E	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/	/			

[53] [54]

MISC. DATA (Continued)	INSPECTION BY																																						INSPECTION DATE			AI														
																																							DAY	MO	YR															
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48		49	50	51	52	53	54	55	56	57	58				

[56]

REMARKS	REMARKS																																																									
	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58							

DAMS IN THE UNITED STATES PUBLIC LAW 92-367 for instructions.	FORM APPROVED OMB NO. 48-00421 REQUIREMENTS CONTROL SYMBOL DAEN-CWE-17	STATE	IDENTITY NUMBER					
		1 2 3 4 5 6 7	M	E	O	0	7	4

[35]	[36]	[37]	[38]	[39]	[40]	[41]	[42]	[43]	[44]	[45]																																							
POWER CAPACITY	NAVIGATION LOCKS											BLANK																																					
	INSTALLED (MW)	PROPOSED (MW)	SE	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)																																						
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
												5																																					

[47]	[48]																																																
ENGINEERING BY	CONSTRUCTION BY																																																
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
SOIL CONSERVATION SERVICE												HORN BROOK, INC.												6																									

[50]	[51]	[52]																																															
REGULATORY AGENCY																																																	
CONSTRUCTION	OPERATION	MAINTENANCE																																															
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
NONE												NONE												7																									

[54]	[55]																																																
INSPECTION DATE	AUTHORITY FOR INSPECTION																																																
DAY MO YR																																																	
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
																								8																									

[56]																																																	
REMARKS																																																	
31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80
																								9																									

END

DATE

FILMED

8 - 85

DT

