

TECHNICAL REPORT GL-87-14

0007

CHE

SEISMIC STABILITY EVALUATION OF FOLSOM DAM AND RESERVOIR PROJECT

Report 7 UPSTREAM RETAINING WALL

by

Harold J. Leeman, Jr., Mary E. Hynes Wipawi Vanadit-Ellis, Takashi Tsuchida

Geotechnical Laboratory

DEPARTMENT OF THE ARMY Waterways Experiment Station, Corps of Engineers PO Box 631, Vicksburg, Mississippi 39180-0631



and the second second

Approved For Public Release. Distribution Unlimited

original contains color plates: All DTIC reproductions will be in black and white"

88 9 26 066

Prepared for US Army Engineer District, Sacramento Sacramento, California 95814-4794 Destroy this report when no longer needed. Do not return it to the originator.

The findings in this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

•

i

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products.

		REPORT	DOCUMENTATIO	N PAGE			Form Approved OMB No. 0704-0188
a. REPORT SECURITY CLASSIFICATION Unclassified				1b. RESTRICTIVE MARKINGS Unclassified			
2a. SECURITY	CLASSIFICATION	AUTHORITY		3. DISTRIBUTION / AVAILABILITY OF REPORT			
26. DECLASSIFICATION / DOWNGRADING SCHEDULE				unlimited			
. PERFORMIN	G ORGANIZATI	ON REPORT NUMB	R(S)	5 MONITORING ORGANIZATION REPORT NUMBER(S)			
Technica	1 Report (G L-87- 14					
ia. NAME OF	PERFORMING C	RGANIZATION	66. OFFICE SYMBOL	7a NAME OF MO	ONITORING ORGA	NIZATIC	N .
USAEWES Geotechn	ical Labor	ratory	(if applicable) CEWES-GH				
C. ADDRESS (City, State, and	(Z:P Code)		75. ADDRESS (Cit	v. State and ZIP	Code)	
		·			,,		
PU Box 6 Vicksbur	31 0. MS 391	180-0631					
A. NAME OF	FUNDING / SPON	NSORING	85. OFFICE SYMBOL	9. PROCUREMENT	T INSTRUMENT ID	ENTIFIC	TION NUMBER
ORGANIZA	TION US Ar	rmy Sacramento	(If applicable)			-	
C. ADDRESS (C	ity State and	ZIF Code)	CESFR-ED				
650 Capi	tol Mall	,		PROGRAM	PROJECT	TASK	WORK UNIT
Sacramen	to, CA 95	5814-4794		ELEMENT NO.	NO.	NO.	ACCESSION NO
Leeman, a. TYPE OF F Report 7	Harold J., REPORT of a seri	Jr., Hynes, 13b TIME CO Les FROM 1	Mary E., Vanad OVERED 982 TO 1988	it-Ellis, Wig 14 Date of Repo July 198	p awi, and T a RT (Year, Month, B	suchic	la, Takashi 15 PAGE COUNT 103
Leeman, 3a. TYPE OF P Report 7 6. SUPPLEMEN Availabl VA 2216	Harold J., REPORT of a seri NTARY NOTATIC e from Nat 1.	Jr., Hynes, 13b TIME CC 13b TIME CC FROM 1 ON Clonal Techni	Mary E., Vanad OVERED 982 TO 1988 cal Information	it-Ellis, Wij 14 Date OF REPO July 1981 Service, 523	p awi, and T RT (Year, Month, B 85 Port Roya	suchic Dey) al Ros	da, Takashi 15 PAGE COUNT 103 ad, Springfield,
Leeman, 3a. TYPE OF I Report 7 6. SUPPLEMEN Availabl VA 2216 7.	Harold J., REPORT of a seri NTARY NOTATIC e from Nat 1. COSATI CC	Jr., Hynes, 13b Time Co FROM 1 ON 10nal Techni ODES	Mary E., Vanad SVERED 982 TO 1988 cal Information 18 SUBJECT TERMS (Dam safety	it-Ellis, Wij 14 Date OF REPO July 1981 Service, 522 Continue on reverse	pawi, and T RT (Year, Month, B B5 Port Roya e of necessary and	suchic Day) al Ros	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block number!
Leeman, Ja. TYPE OF I Report 7 6. SUPPLEMEN Availabl VA 2216 7 FIELD	Harold J., REPORT of a seri NTARY NOTATIC e from Nat 1. COSATI CC GROUP	Jr., Hynes, 13b Time Co FROM 1 ON Cional Techni ODES SUB-GROUP	Mary E., Vanad DVERED 982 TO 1988 cal Information 18 SUBJECT TERMS (Dam safety Earthquakes a	it-Ellis, Wij 14 DATE OF REPO July 1980 Service, 520 Continue on reverse nd hydraulic	pawi, and T RT (Year, Month, B B5 Port Roya e if necessary and structures	al Roa	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block numberi
Leeman, 3a TYPE OF I Report 7 6 SUPPLEMEN Availabl VA 2216 7 FIELD J. ABSTRACT	Harold J., REPORT of a seri UTARY NOTATIC e from Nat 1. COSATI CC GROUP	, Jr., Hynes, 13b TiME CC FROM 1 ON tional Techni ODES SUB-GROUP everse if necessary	Mary E., Vanad VERED 982 TO 1988 cal Information 18 SUBJECT TERMS (Dam safety Earthquakes a Folsom Dam (C and identify by block of	it-Ellis, Wij ¹⁴ DATE OF REPO July 1988 Service, 528 Continue on reverse nd hydraulic alif.) umber)	pawi, and Ti RT (Year, Month, B B5 Port Roya e If necessary and structures	suchic Dey) al Ros	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block numberi
Leeman, 3a TYPE OF 1 Report 7 6 SUPPLEMEN Availabl VA 2216 7 FIELD 9 ABSTRACT 1 9 ABSTRACT 1 10cated have been occurrin, The eval 1aborato Retainin envelopm during t	Harold J., REPORT of a seri ITARY NOTATIC e from Nat 1. COSATI CC GROUF (Continue on re e man-made on the Ame n evaluate g on the E uation pro ry investi g Wall B, en. fill. he design	Jr., Hynes, Isb TiME Co FROM 1 ON Clonal Techni ODES SUB-GROUP Everse if necessary e water retai prican River ed for their Cast Branch o Docess involve Igations, and a submerged It has been earthquake.	Mary E., Vanad VERED 982 TO 1988 cal Information 18 SUBJECT TERMS (Dam safety Earthquakes a Folsom Dam (C and identify by block not ning structures about 20 miles seismic safety f the Bear Moun d extensive rev analytical stu retaining wall concluded that	<pre>it-Ellis, Wij 14 DATE OF REPO July 1988 Service, 528 Continue on reverse nd hydraulic alif.) umber) at the Folse upstream of t in the event tains Fault 2 iew of constr dies. This n at the base of Retaining Wa </pre>	pawi, and T RT (Vear, Month, B B5 Port Roya structures of Dam and D the City of of a Magnit Zone at a di ruction reco report docum of the Right all B will p	Reserve Reserve Sacra tude of istance ords, ments t Wing perfor	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block number! roir Project, amento, Calif., 5.5 earthquake se of about 15 km field and studies of g Dam upstream rm satisfactorily
Leeman, Ja TYPE OF I Report 7 6 SUPPLEMEF Availabl VA 2216 7 FIELD 9 ABSTRACT I 10 Cated have bee occurrin, The eval laborato Retainin envelopm during ti DISTRIBUTIC 2 UNCLASSIN	Harold J., REPORT of a seri ITARY NOTATIC e from Nat 1. COSATI CC GROUF (Continue on re e man-made on the Amen n evaluate g on the E uation pro ry investi g Wall B, enc fill. he design DN / AVAILABILIT FIED/UNLIMITED	Jr., Hynes, Ib TiME Co. FROM 1 ON tional Techni ODES SUB-GROUP evene if necessary e water retai erican River ed for their Cast Branch o bcess involve Igations, and a submerged It has been earthquake. Ty OF ABSTRACT D SAME AS R	Mary E., Vanad VERED 982 TO 1988 cal Information 18 SUBJECT TERMS (Dam safety Earthquakes a Folsom Dam (C and identify by block of ning structures about 20 miles seismic safety f the Bear Mound d extensive rev analytical stu retaining wall concluded that	it-Ellis, Wij 14 Date OF REPO July 1988 Service, 528 Continue on reverse nd hydraulic alif.) umber) at the Folse upstream of to in the event tains Fault 2 iew of constr dies. This mat the base of Retaining Was 21 ABSTRACT SEC	pawi, and Ti RT (Vear, Month, B B5 Port Roy, a if necessary and structures om Dam and I the City of of a Magnii Zone at a di ruction reco report documon of the Right all B will ; UNITY CLASSIFIC Unclassifi	al Roa didentify Reserv Sacra tude (istanco ords, ments t Wing perfor	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block number; y by block number; y by block number; to fact a state of about 15 km field and studies of g Dam upstream rm satisfactorily
Leeman, a. TYPE OF I Report 7 5. SUPPLEMEF Availabl VA 2216 FIELD FIELD ABSTRACT I Iocated have bee occurrin, The eval laborato Retainin envelopm during t DISTRIBUTIC IZ UNCLASSII a. NAME OF	Harold J., REPORT of a seri STARY NOTATIC e from Nat 1. COSATI CC GROUP (Continue on re e man-made on the Ame n evaluate g on the E uation pro ry investi g Wall B, enc fill. he design DN (AVAILABILIT FIED/UNLIMITED RESPONSIBLE IM	Jr., Hynes, Isb TiME Co. FROM 1 ON FROM 1 ON FROM 1 ON FROM 1 ON FROM 1 ON FROM 1 FROM 1	Mary E., Vanad VERED 982 TO 1988 cal Information 18 SUBJECT TERMS (D Dam safety Earthquakes a Folsom Dam (C and identify by block no ning structures about 20 miles seismic safety f the Bear Mound d extensive rev analytical stur retaining wall concluded that	<pre>it-Ellis, Wig 14 DATE OF REPO July 1988 Service, 528 Continue on reverse nd hydraulic alif.) umber) at the Folse upstream of to in the event tains Fault 2 iew of consta dies. This is at the base of Retaining Wa 21 ABSTRACT SEC 22b TELEPHONE (# 22b TELEPHON</pre>	pawi, and Ti RT (Year, Month, B B5 Port Roya structures om Dam and I the City of of a Magnin Zone at a di ruction reco report docu of the Right all B will p Unclassifi Unclassifi Include Area Code	Reserv Sacra tude fi Istanco ords, ments Wing perfor	da, Takashi 15 PAGE COUNT 103 ad, Springfield, y by block number; y by block numb

1

Unclassified SECURITY CLASSIFICATION OF THIS PAGE

PREFACE

The US Army Engineer Waterways Experiment Station (WES) was authorized to conduct this study by the US Army Engineer District, Sacramento (SPK), by Intra-Army Order for Reimbursable Services Nos. SPKED-F-82-2, SPKED-F-82-11, SPKED-F-82-34, SPKED-F-83-15, SPKED-F-83-17, SPKED-F-84-14, and SPKED-D-85-12. This report is one in a series of reports which document the seismic stability evaluations of the man-made water retaining structures of the Folsom Dam and Reservoir Project, located on the American River in California. The Reports in this series are as follows:

Report	1:	Summary
Report	2:	Interface Zone
Report	3:	Concrete Gravity Dam
Report	4:	Mormon Island Auxiliary Dam - Phase I
Report	5:	Dike 5
Report	6:	Right and Left Wing Dams
Report	7:	Upstream Retaining Wall
Report	8:	Mormon Island Auxiliary Dam - Phase II

The work on these reports is a joint endeavor between SPK and WES. Messrs. John W. White and John S. Nickell, of Civil Design Section 'A', Civil Design Branch, Engineering Division (SPKED-D) at SPK were the overall SPK project coordinators. Messrs. Gil Avila and Matthew G. Allen, of the Soil Design Section, Geotechnical Branch, Engineering Division (SPKED-F) at SPK, made critical geotechnical contributions to field and laboratory investigations. Support was also provided by the South Pacific Division Laboratory. The WES Principal Investigator and Research Team Leader was Dr. Mary Ellen Hynes, of the Earthquake Engineering and Geophysics Division (EEGD), Geotechnical Laboratory (GL), WES. Primary Engineers on the WES team for the portion of the study documented in this report were MAJ Harold J. Leeman, Jr., on temporary assignment to WES from the US Military Academy, West Point, New York, Ms. Wipawi Vanadit-Ellis of the Soil Mechanics Division (SMD), GL, WES, and Mr. Takashi Tsuchida, on temporary assignment to WES from the Port and Harbour Research Institute, Yokosuka, Japan. Geophysical support was provided by Mr. Jose Llopis, EEGD. Additional engineering support was provided by Mr. David S. Sykora, EEGD, Mr. Ronald E. Wahl, EEGD, and

Mr. Richard S. Olsen, EEGD. Large-scale laboratory investigations were conducted by Mr. Robert T. Donaghe, SMD. Laboratory instrumentation services were provided by Mr. Thomas V. McEwen, of the Data Acquisition Section, Instrumentation Services Division, WES. Mr. W. L. Hanks, SMD, Mr. C. Schneider, SMD, Mr. B. L. Washington of the Engineering Geology and Rock Mechanics Division, EGRMD, GL, WES, Mr. M. H. Seid, EEGD, Mr. J. D. Myers, EEGD, Mr. H. Alderson, EEGD, and Mr. T. Cho, EEGD, assisted in preparation of figures. Key contributions also were made by Dr. Leslie F. Harder, Jr., of Sacramento, California; Professor Shobha Bhatia, Syracuse University; Professor Tarik Hadj-Hamou, Tulane University; and Professor David Elton, Auburn University.

Professors H. Bolton Seed, Anil K. Chopra and Bruce A. Bolt of the University of California, Berkeley; Professor Clarence R. Allen of the California Institute of Technology; and Professor Ralph B. Peck, Professor Emeritus of the University of Illinois, Urbana, served as Technical Specialists and provided valuable guidance during the course of the investigation.

Overall direction at WES was provided by Dr. A. G. Franklin, Chief, EEGD, and Dr. W. F. Marcuson III, Chief, GL.

COL Dwayne G. Lee, CE, is Commander and Director of WES. Dr. Robert W. Whalin is Technical Director.



"Original contains color plates: All DTIC reproductions will be in black and white"

CONTENTS

f

		Page
PREFACE		1
PART I:	INTRODUCTION	5
Genera	al	5
Projec	et History	6
Hydrol	logy and Pool Levels	6
Site (/
Seismi	ismological and geological investigations	8
Se	election of design ground motions	9
PART II: F	REVIEW OF CONSTRUCTION RECORDS	11
Genera	51	11
Descri	ption of Retaining Wall B	11
Founda	ation Conditions	11
Backfi	Ill Materials	12
Consti	ruction Sequence	13
Retair	ning Walls A and E	13
PART III: H	BACKFILL MATERIALS	15
Genera	11	15
Field	and Laboratory Investigations Performed for this Study	15
Liquei	action Susceptibility	1/
Residu	ial Strength	20
PART IV: S	STABILITY EVALUATION OF RETAINING WALL B	21
Genera	1	21
Yield	Acceleration Analyses	22
MC 117	DONODE-UKADE	22
Si	ummary of vield acceleration computations	26
Perman	nent Deformation Estimates	27
Ma	kdisi-Seed calculations	27
Sa	arma-Ambraseys calculations	29
Mc	odified Richards-Elms calculations	30
Post-1	Larthquake Stability Studies for Worst Case Scenarios	31
SLAUII		52
PART V: S	SUMMARY AND CONCLUSIONS	33
REFERENCES.		35
TABLES 1-4		
FIGURES 1-46		
APPENDIX A:	COMPUTER PROGRAM LISTINGS AND OUTPUT FOR YIELD	
	ACCELERATION COMPUTATIONS WITH THE MONONOBE-OKABE	
	PROCEDURE	AI

3

ı.

----7

SEISMIC STABILITY EVALUATION OF FOLSOM DAM AND RESERVOIR PROJECT Report 7: Upstream Retaining Wall

PART I: INTRODUCTION

General

1. This report is one of a series of reports that document the investigations and results of a seismic stability evaluation of the man-made water retaining structures at the Folsom Dam and Reservoir Project, located on the American River in Sacramento, Placer and El Dorado Counties, California, about 20 airline miles northeast of the City of Sacramento. This seismic safety evaluation was performed as a cooperative effort between the US Army Engineer Waterways Experiment Station (WES) and the US Army Englneer District, Sacramento (SPK). Professors H. Bolton Seed, Anil K. Chopra, and Bruce A. Bolt of the University of California, Berkeley, Professor Clarence R. Allen of the California Institute of Technology, and Professor Ralph B. Peck, Professor Emeritus of the University of Illinois, Urbana, served as Technical Specialists for the study. This report documents seismic stability studies of Retaining Wall B, a submerged retaining wall located at the base of the Right Wing Dam envelopment fill, at the contact between the Right Wing Dam and the Concrete Gravity Dam. A location map and plan of the project are shown in Figures 1 and 2.

2. Three retaining walls were constructed in the vicinity of the main dam in the wrap-around area parallel to the river. Downstream retaining walls were constructed on both the Right and Left wrap-around areas. Upstream, only the Right wrap-around area required a retaining wall, denoted Retaining Wall B in Figure 3. Failure of the downstream walls would not result in catastrophic loss of the reservoir. The upstream wall is of concern since the embankment shell is saturated and the intake ports for the powerhouse are located riverward of the wall, and could be blocked if the wall and embankment slid due to the design earthquake. The investigation was aimed at determining what movements the wall might experience during the design earthquake and whether such movements would threaten the integrity of the embankment. If excessive

5

<u>, 1</u> },

sliding were to occur, the freeboard could be lost and the reservoir contents could escape, leading to catastrophic failure of the dam.

3. Conservative estimates of earthquake-induced permanent displacements were made with Makdisi-Seed, Sarma-Ambraseys and modified Richards-Elms approaches. Yield accelerations were determined with Mononobe-Okabe and UTEXAS2 techniques. The estimates of earthquake-induced permanent displacement in Retaining Wall B and Right Wing envelopment fill are less than 10 ft. These Newmark sliding-block analyses indicate that some damage to the wall is expected but the deformations will be limited, and there will be no catastrophic loss of the reservoir.

Project History

4. The Folsom project was designed and built by the Corps of Engineers in the period 1948 to 1956, as authorized by the Flood Control Act of 1944 and the American River Basin Development Act of 1949. Upon completion of the project in May 1956, ownership of the Folsom Dam and Reservoir was transferred to the US Bureau of Reclamation for operation and maintenance. As an integral part of the Central Valley Project, the Folsom Project provides water supplies for irrigation, domestic, municipal, industrial and power production purposes as well as flood protection for the Sacramento Metropolitan area and extensive water related recreational facilities. Releases from the Folsom Reservoir are also used to provide water quality control for project diversions from the Sacramento-San Joaquin Delta, to maintain fish-runs in the American River below the dam, and to help maintain navigation along the lower reaches of the Sacramento River.

Hydrology and Pool Levels

5. Folsom Lake impounds the runoff from 1,875 square miles of rugged mountainous terrain. The reservoir has a storage capacity of 1 million acre-ft at gross pool and is contained by approximately 4.8 miles of man-made water-retaining structures that have a crest Elevation of 480.5 ft above sea level. These structures are the Right and Left Wing Dams, the Concrete

Gravity Dam, Mormon Island Auxiliary Dam, and 8 Saddle Dikes. At gross pool, Elevation 466 ft, there is 14.5 ft of freeboard. This pool level was selected for the safety evaluation, based on a review of current operational procedures and hydrologic records (obtained for a 29-year period, from 1956 to 1984) for the reservoir which shows that the pool typically reaches Elevation 466 ft about 10 percent of the time during the month of June, and considerably less than 10 percent of the time during the other months of the year. Under normal operating conditions, the pool is not allowed to exceed Elevation 466 ft. Hydrologic records show that emergency situations which would cause the pool to exceed Elevation 466 ft are rare events.

Site Geology

6. At the time of construction, the geology and engineering geology concerns at the site were carefully detailed by Kiersch and Treasher (1955). Their observations and the foundation reports from construction records are the sources for the summary of site geology provided in this section.

7. The Folsom Dam and Reservoir Project is located in the low, western-most foothills of the Sierra Nevada in central California, at the confluence of the North and South Forks of the American River. Relief ranges from a maximum of 1242 ft near Flagstaff Hill located between the upper arms of the reservoir, to 150 ft near the town of Folsom just downstream of the Concrete Gravity Dam. The North and South Forks entered the confluence in mature valleys up to 3 miles wide, but further downcutting resulted in a V-shaped inner valley 30 to 185 ft deep. Below the confluence, the inner canyon was flanked by a gently sloping mature valley approximately 1.5 miles wide bounded on the west and southeast by a series of low hills. The upper arms of the reservoir, the North and South Forks, are bounded on the north and east by low foothills.

8. A late Pliocene-Pleistocene course of the American River flowed through the Blue Ravine and joined the present American River channel downstream of the town of Folsom. The Blue Ravine was filled with late Pliocene-Pleistocene gravels, but with subsequent downcutting and headward erosion, the Blue Ravine was eventually isolated and drainage was diverted to the present American River Channel.

9. To important formations at the dam site are: a quartz diorite granite which forms the foundation at the Concrete Gravity Dam, Wing Dams, and Saddle Dikes 1 through 7; metamorphic rocks of the Amador group which underlie Saddle Dike 8 and the foundation at Mormon Island Auxiliary Dam; the Mehrten formation, a deposit of cobbles and gravels in a somewhat cemented clay matrix which caps the low hills that separate the saddle dikes and is part of the foundation at Dike 5; and the alluvium that fills the Blue Ravine at Mormon Island Auxiliary Dam.

10. Weathered granitic or metamorphic rock is present throughout the area. Figure 4 shows a geologic map of the project area. The Concrete Gravity Dam, the Wing Dams, the retaining walls, and Dikes 1 through 7 are founded on weathered quartz diorite granite. Between Dikes 7 and 8 there is a change in the bedrock. Dike 8 and Mormon Island Auxiliary Dam are underlain by metamorphic rocks of the Amador group. The Amador group consists of predominantly schiets with numerous dioritic and diobasic dikes.

Seismic Hazard Assessment

Seismological and geological investigations

11. Detailed geological and seismological investigations in the immediate vicinity of Folsom Reservoir were performed by Tierra Engineering, Incorporated to assess the potential for earthquakes in the vicinity, to estimate the magnitudes these earthquakes might have, and to assess the potential for ground rupture at any of the water-retaining structures (see Tierra Engineering, Inc., 1983, for comprehensive report). A 12-mile wide by 35-mile long study area centered on the Folsom Reservoir was extensively investigated using techniques such as areal imagery analysis, ground reconnaissance, geologic mapping, and detailed fault capability assessment. In addition, studies by others relevant to the geology and seismicity of the area around Folsom were also compiled. These additional literature sources include numerous geologic and seismologic studies published through the years, beginning with the "Gold Folios" published by the US Geological Survey in the 1890's, the engineering geology investigations for New Melones and the proposed Marysville and Auburn Dams, studies performed for the Rancho Seco Nuclear Power Plant as well as unpublished student theses and county planning studies.

12. It was determined that no capable faults underlie any of the water-retaining structures or the main body of the reservoir at the Folsom Project. The tectonic and seismicity studies also indicated that it is unlikely that Folsom Lake can induce major seismicity. Since the faults that underlie the water retaining structures at the Folsom Project were found to be noncapable, seismic fault displacement in the foundations of the water retaining structures is judged to be highly unlikely.

13. The closest capable fault is the East Branch of the Bear Mountains fault zone which has been found to be capable of generating a maximum magnitude M = 6.5 earthquake. The return period for this maximum earthquake is estimated to exceed 400 yrs (Tierra Eng. Inc., 1983). Determination that the East Branch of the Bear Mountains fault zone is a capable fault came from the Auburn Dam earthquake evaluation studies. The minimum distance between the East Branch of the Bear Mountains fault zone and Mormon Island Auxiliary Dam is 8 miles, and the minimum distance between this fault zone and the Concrete Gravity Dam is 9.5 miles. The focal depth of the earthquake is estimated to be 6 miles. This hypothetical maximum magnitude earthquake would cause more severe shaking at the project than earthquakes originating from other known potential cources.

Selection of design ground motions

14. The seismological and geological investigations summarized in the Tierra report were provided to Professors Bruce A. Bolt and H. B. Seed to determine appropriate ground motions for the seismic safety evaluation of the Folsom Dam Project. The fault zone of concern is the East Branch of the Bear Mountains fault zone located at a distance of about 15 kilometers from the site. This fault zone has an extensional tectonic setting and a seismic source mechanism that is normal dip-slip. The slip rate from historic geomorphic and geological evidence is very small, less than 10^{-3} centimeters per year with the most recent known displacement occurring between 10,000 and 500,000 years ago in the Pleistocene period.

15. Based on their studies of the horizontal ground accelerations recorded on an array of accelerometers normal to the Imperial Valley fault during the Imperial Valley earthquake of 1979, as well as recent studies of a large body of additional strong ground motion recordings, Bolt and Seed (1983) recommend the following design ground motions:

Peak horizontal ground acceleration = 0.35 g

Peak horizontal ground velocity = 20 cm/sec

Bracketed Duration (≥ 0.05 g) ≈ 16 sec

Because of the presence of granitic plutons at the site, it is expected that the earthquake accelerations might be relatively rich in high frequencies. Bolt and Seed (1983) provided 2 accelerograms that are representative of the design ground motions expected at the site as a result of a maximum magnitude M = 6.5 occurring on the East Branch of the Bear Mountains fault zone. The accelerograms are designated as follows (Bolt and Seed 1983):

> M6.5 - 15K - 83A. This accelerogram is representative of the 84-percentile level of ground motions that could be expected to occur at a rock outcrop as a result of a Magnitude 6-1/2 earthquake occurring 15 kms from the site. It has the following characteristics:

> > Peak acceleration = 0.35gPeak velocity ≈ 25 cm/sec Duration ≈ 16 sec.

M6.5 - 15K - 83B. This accelerogram is representative of the 84-percentile level of ground motions that could be expected to occur at a rock outcrop as a result of a Magnitude 6-1/2 earthquake occurring 15 kms from the site. It has the following characteristics:

> Peak acceleration = 0.35g Peak velocity ≅ 19.5 cm/sec Duration ≅ 15 sec

Figure 5 shows plots of acceleration as a function of time for the two design accelerograms and Figure 6 shows response spectra of the motions for damping ratios of 0, 2, 5, 10, and 20 percent damping.

PART II: REVIEW OF CONSTRUCTION RECORDS

General

16. Detailed construction records were kept to document the initial site reconnaissance, selection of borrow areas, foundation preparation and construction sequence for the dam. Pertinent information from these construction records are summarized in this chapter.

Description of Retaining Wall B

17. Retaining Wall B prevents the earthfill of the Right Wing Dam envelopment section from blocking the penstock and powerhouse inlets. During construction, Retaining Wall B also protected the diversion tunnel inlet channel. Plans and sections of the wall are shown in Figures 7, 8, and 9. The wall is 406 ft long and consists of 12 monoliths. The crest elevation varies between Elevation 310 and 350 ft and is controlled by the intersection of the wall with the designed slope of the earthfill envelopment. The elevation of the base of the wall varies between Elevation 270 and 290 ft. The elevation of the base of individual monoliths was adjusted according to the existing topography and the quality of the foundation rock. The maximum height of the wall is 82 ft, near wall axis Station 0+29, at the juncture of the wall with Monoliths 6 and 7 of the Concrete Gravity Dam. The minimum height of the wall is 27 ft at wall axis Station 4+35. The riverward face of the wall is battered at 1 (vertical) on 0.1 (horizontal). Monoliths shorter than 50 ft (Wall Monoliths 5, 6, 11, and 12) are battered at 1 (vertical) on 0.58 (horizontal) on the earthfill face. Monoliths taller than 50 ft have a backfill facing slope battered at 1 (vertical) on 0.65 (horizontal). A two-lane construction road exists at the base of the riverward face of the wall.

Foundation Conditions

18. The foundation rock is quartz diorite with varying degrees of weathering. Figures 10a and 10b show geologic plans and sections of the foundation. The degree of weathering is indicated in these figures. Several faults and shears were encountered in the foundation. The most significant are two parallel faults that strike northeast (roughly N 45-1/2 E) and dip northwest (roughly 45-1/2 NW), near wall axis Stations 1+65 and 2+17 (see Section A-A in Figure 10b). The fault near wall axis Station 1+65 contains a 0.3- to 8.0-ft wide zone of weathered, brecciated rock, and was exposed in the foundation for Wall Monoliths 1 through 4. The second fault, near wall axis Station 2+17, was exposed in the foundation for Wall Monoliths 5 and 6. No brecciated zone is present where the fault near wall axis Station 2+17 passes beneath the retaining wall. After excavation and cleanup was completed, the foundation rock exposure consisted of sharp, irregularly blasted surfaces, terminating at joint planes. Where the two northwest dipping faults crossed the foundation, V-shaped excavations were used to remove the soft, brecciated, and weathered rock. Between the heel of the Concrete Gravity Dam and wall axis Station 1+20, the brecciated fault zone is at maximum width. Loose material was hand-excavated and the breccia zone was cut vertically to minimize its adverse effect on the foundation. No springs or seeps were present in the mapped area. Eight inch diameter vitrified-clay pipe drains were installed normal to the wall axis and connected to vitrified clay pipe drains installed at the heel (rear face) of Retaining Wall B. The foundation was leveled with 1,811 cubic yards of grout and concrete to facilitate forming and placement of subsequent lifts.

Backfill Materials

19. The backfill behind Retaining Wall B is the Right Wing Dam envelopment fill. Sections of the Right Wing envelopment fill are shown in Figures 7, 8, and 11. The embankment consists of three zones: Zone A, a loose rockfill with considerable fines from excavation in the American River channel, Zone B, a gravel transition zone also from excavation in the American River channel, and Zone C, a well-compacted decomposed granite core from Borrow Area No. 2 shown in Figure 2. Gradations for Zones B and C are shown in Figures 12 and 13. The gradation of Zone A is only qualitatively described in construction records. Zone A was dumped in 12-ft lifts with no compaction required. Zone B was placed in 24-in. lifts, compacted with one complete coverage* of a D-8 Caterpillar tractor. Zone C was compacted in 12-in. lifts

^{*} It was estimated that one complete coverage is equivalent to three or four passes of the compaction equipment.

with 12 passes of a sheepsfoot roller or in 18-in. lifts with 6 passes of a pneumatic-tired roller. Construction photographs indicate that some compaction of the core in the envelopment area was also accomplished with fullyloaded dump trucks. Report 2 of this series provides more details of the construction of the envelopment areas.

20. The unit weight and shear strength characteristics of the embankment materials that were used in the original design are shown in Table 1. The Zone A rockfill was conservatively assumed to have the same characteristics as the Zone B gravel fill.

Construction Sequence

21. To better visualize the geometry of Retaining Wall B relative to the Concrete Gravity Dam, a series of construction photographs is provided. Figure 14 is a photograph of the completed wall (dated 16 April 1954) with Zone A backfill in place. Figures 15 through 23 show the chronological construction sequence of the wall and backfill placement operations. A key observation from the construction photographs is that a two-lane road exists along the base of the riverward face of the wall, as shown in Figures 14, 19, and 21. Therefore, it is apparent that the wall can displace at least 20 ft riverward without falling into the river channel. Displacements on the order of 10 to 20 ft are sufficient to block the 84-in. intake pipe in Monolith 7 of the Concrete Gravity Dam, but the penstocks would be only slightly obstructed (see Figure 9).

Retaining Walls A and E

22. Retaining Walls A and E provide support to the Right Wing and Left Wing envelopment areas, respectively. Retaining Wall A is 173 ft long and about 54 ft tall at maximum section. This is a combination gravity and cantilever structure connected to the Concrete Gravity Dam at Monolith 7. Retaining Wall E is 239 ft long and 60 ft tall at maximum section. This is a gravity type wall and adjoins the left edge of the flip bucket in Monolith 20. The surface of the backfill behind both walls, the downstream Right and Left envelopment shells, is sloped at 1 vertical to 2 horizontal at the contact with the Concrete Gravity Dam. Foundation conditions and preparation for both walls were similar to those for Retaining Wall B.

General

23. The backfill materials at Retaining Wall B are the upstream portion of the Right Wing Dam envelopment fill. The geometries of the backfill zones are shown in Figures 7 and 8, and a typical Right Wing Dam section in the envelopment area is shown in Figure 11. There are three material zones: Zone A, a loose, dumped rockfill with a considerable fines content, Zone B, a gravel transition zone, and Zone C, a compacted decomposed granite core. The material properties of the backfill and the behavior of the backfill during and after earthquake loading were determined in order to assess the adequacy of the wall and the seismic stability of the submerged envelopment fill. This part contains a summary of the results of field investigations and complementary laboratory tests (conducted as part of the seismic stability study) performed on the embankment materials to quantitatively determine material properties under static and cyclic loading conditions. Reports 4 and 6 of this series contain more detailed descriptions of the field and laboratory investigations conducted for this study and the analytical studies to determine dynamic response, liquefaction susceptibility, and seismically-induced residual excess pore pressures. The results of the analytical studies are briefly summarized in this part since they provide the basis for several parameter values selected to determine sliding resistance and permanent displacements.

Field and Laboratory Investigations Performed for this Study

24. Undisturbed sampling with a Denison sampler and SPT borings with trip hammer equipment were performed at 5-ft intervals at the centerline to sample core material, and near the downstream edge of the crest to sample filter and core material at two locations on the Right Wing Dam, near Stations 235 and 275. Figure 3 shows the locations of the field investigations. SPT borings are denoted SS and undisturbed borings are denoted US. Steel cased borings, shown as SCB in Figure 3, were drilled with Odex equipment in the downstream gravel shells. The Odex system consists of a downhole pneumatic hammer with an expanding bit that pulls a steel casing behind the bit.

When the casing is in place, the bit can be retracted and withdrawn through the casing. The steel casing used in these investigations had an inside diameter (ID) of 5 in. The Odex system was selected for installation of cased holes for subsurface geophysical testing because it did not require grouting of the gravels, the disturbance to the gravels was relatively minor, and several holes could be installed within a single work day. Unfortunately, this system does not provide satisfactory samples of the subsurface materials.

25. The US, SS, and SCB borings were drilled in pairs for geophysical crosshole testing. Test pits, shown as TP in Figure 3, were excavated in the downstream gravel shells at these locations to determine in situ densities and obtain disturbed samples for laboratory testing. Pairs of undisturbed and SPT borings were also drilled in core material at the interface area near Station 285, as shown in Figure 3.

26. Typically, the SPT blowcounts in the core material exceeded 40 blows per ft near Stations 235 and 275, and 30 blows per ft in the immediate vicinity of the end monolith of the Concrete Gravity Dam. The fines content averaged about 20 percent non-plastic fines near Station 235 and 275, and about 25 percent slightly plastic fines in the interface area. The core materials generally classified as a silty or clayey sand (SM, SC, SC-SM) according to the Unified Soils Classification System (USCS). Gradations from these recent field investigations are compared with record samples in Figure 24 for Stations 235 and 275, and Figure 25 for the interface area. The peak effective friction angle of the core material ranged from 35° to 45° (c' = 0), and the peak consolidated-undrained shear strength typically exceeded 6 TSF, based on the results of S and \overline{R} triaxial tests conducted over the stress range of interest. For the analyses in this study, peak effective stress strength parameters of $\phi' = 37^{\circ}$ and c' = 0, and peak consolidated-undrained strength parameters of $\phi = 30^{\circ}$ and c = 4 tsf were selected for the core material. Shear wave velocities in the core ranged from about 900 to 1,000 fps in the top 20 ft, to about 1,100 to 1,600 fps at depth. The average dry density from record samples of core material was 127 pcf, and the total unit weight was estimated to be 142 pcf.

27. Shear wave velocities in the shell ranged from 850 fps near the surface of the slope, to 1,350 fps at depth. Large-scale in situ density tests from 3 test pits in the gravel transition material showed an average dry density of 136 pcf. The buoyant unit weight is estimated to be 90 pcf. The

gravel transition material generally classified as a sandy, silty gravel, with an average fines content of 4 percent non-plastic fines and an average D_{50} of 1 in. Maximum particle sizes were typically less than 6 in. The range of gradations observed in these test pit samples is shown in Figure 26. The in situ relative density, D_r , of the Zone B gravel is estimated to be 60 to 70 percent. The average observed in the test pits was 63 percent.

28. The Zone B gravel was compacted according to the same specifications as the gravel shell in Zone 1 of Mormon Island Auxiliary Dam. Comparison of the range of gradations observed in test pits in both dams shows the materials are very similar. Becker Hammer blowcounts in the Mormon Island Auxiliary Dam shell were translated into equivalent SPT blowcounts (Harder 1986) and the average energy and overburden corrected blowcount, $(N_1)_{60}$, is estimated to be about 25 blows per ft. Based on large-scale triaxial tests on gravel specimens from Mormon Island Auxiliary Dam, the Zone B gravel in the Right Wing Dam is estimated to have an effective friction angle of 43° (c' = 0).

29. As part of the field work to assess the current conditions in the interface areas, the downstream Retaining Walls A and E were inspected in June, 1985. It was observed that some (but not all) weep holes in these walls were plugged. One or two holes in each wall were producing a minute amount of water. Mosses and algae at the base of the retaining walls below these moist weep holes indicated continuous moist conditions. The pool elevation at the time of the field visit was at or above Elevation 466 ft and it was observed that the seepage through the weepholes in the downstream retaining walls was minimal. In the line of reasoning that leads to the conclusion that Retaining Walls A and E are not critical to the satisfactory seismic performance of the interface areas, it is assumed that the downstream wrap-around shell materials are unsaturated and well-drained.

Liquefaction Susceptibility

30. The seismically-induced residual excess pore pressures developed in the envelopment fill behind the retaining wall were assumed to be similar to those developed in the upstream slope of the Right Wing Dam outside the envelopment area. As described in Report 6 of this series, the section selecced for analysis to represent both the Right and Left Wing Dams was the tallest

upstream section which occurs at Station 283 in the Right Wing embankment. The analysis section is shown in Figure 27. The elevation of the base of this upstream slope is 290 ft. The elevation of the base of the retaining wall varies between 270 ft and 290 ft. The slope of the envelopment fill varies between 1 (vertical) on 2 (horizontal) at the intersection with the Concrete Gravity Dam, to 1 (vertical) on 2.25 (horizontal) where the envelopment fill blends into the upstream slope of the Right Wing Dam.

31. The cyclic strengths of the shell and core materials were estimated with Seed's empirical approach (Seed et al. 1983, and Seed et al. 1984). The Zone A rockfill was assumed to have the same characteristics as the Zone B gravel transition. The average $(N_1)_{60}$ values of these materials were estimated to be 25 for the shell, Zones A and B, and 30 (plus) for the Zone C core. The fines contents average about 4 percent for the shell and 20 to 25 percent for the core.

32. Cyclic strengths were estimated from Seed's empirical chart shown in Figure 28 which shows a plot of cyclic strength versus corrected blowcount, $(N_1)_{60}$, for silty sands with different fines contents. The cyclic strength in Figure 28 is expressed as the cyclic stress ratio causing liquefaction (based on observations of liquefaction in the field), for a confining pressure of about 1 tsf and for earthquakes with M = 7.5. The blowcounts in this chart are corrected to an overburden pressure of 1 tsf and a 60 percent energy level, $(N_1)_{60}$. The cyclic stress ratios from this chart are interpreted to correspond to development of 100 percent residual excess pore pressure. Seed et al. (1983) has shown that for M = 6.5 events, the cyclic loading resistance is about 20 percent higher, for any value of $(N_1)_{60}$, than for M = 7.5 earthquakes.

33. The cyclic strength for the embankment shell was determined by entering the chart in Figure 28 at $(N_1)_{60} = 25$ and selecting the corresponding cyclic stress ratio from the curve for fines less than or equal to 5 percent, to obtain a cyclic stress ratio of 0.29. This chart value was then adjusted to correspond to a M = 6.5 event by the factor $K_M = 1.2$, to obtain a cyclic stress ratio of 0.35. The core materials have a value of $(N_1)_{60} = 30$ which exceeds the limits of the cyclic strength chart for silty sand with fines contents of about 20 to 25 percent. The asymtotic limit for this curve is $(N_1)_{60} \cong 23$. Consequently, the core materials are clearly not susceptible to liquefaction.

34. The ϵ bankment shells were further analyzed with finite element techniques. Initial static stresses in the analysis section were determined in static finite element analyses with the program FEADAM. The finite element mesh is shown in Figure 29, and the input properties are listed in Table 2. For each element, the vertical effective stress and initial horizontal shear stress were computed. The cyclic strength for each element is the cyclic stress ratio 0.35 adjusted by the factors K_{σ} , to account for the non-linear relationship between cyclic strength and overburden stress, and K_{α} , to account for the increase in cyclic strength with α defined as the ratio of initial horizontal shear stress to vertical effective stress. The factor K_{σ} is plotted in Figure 30 versus vertical effective stress. The factor K_{α} is plotted in Figure 31 versus initial shear stress ratio, α . The curves in Figures 30 and 31 were developed from large-scale cyclic triaxial tests on compacted specimens of gravel from test pits at Mormon Island Auxiliary Dam.

35. Dynamic shear stresses developed in the analysis section were computed with FLUSH, a two-dimensional, total stress, dynamic response finite element program, which solves the equations of motion in the frequency domain and accounts for non-linear soil behavior with an equivalent linear model. Of the two accelerograms provided for the analyses, Accelerogram B (denoted M6.5 - 15K - 83B in Part I) was selected for input to FLUSH since it resulted in slightly higher dynamic shear stresses in preliminary SHAKE analyses than Accelerogram A (denoted M6.5 - 15K - 83A in Part I). The accelerogram was input to the problem at the rock surface of an outcropping bedrock layer. The finite element mesh used in the FLUSH computations was the same as that used in the FEADAM computations. An average sand modulus degradation curve was used in the equivalent linear solution. Shear moduli for the section were estimated from the field geophysical measurements and the static stress analyses. Peak accelerations computed for several points in the section are shown in Figure 32.

36. The maximum horizontal dynamic shear stresses computed with FLUSH were multiplied by 0.65 to determine the average cyclic shear stress for each element. The available cyclic strength was compared to the earthquake-induced cyclic shear stress, and safety factors against liquefaction were computed for each element. Typically, the safety factors against liquefaction in the upstream shell exceeded 1.5. In the core, the safety factors were higher. Residual excess pore pressures of about 20 to 25 percent are expected to

develop in the upstream shell based on the relationship between residual excess pore pressure and factor of safety against liquefaction shown in Figure 33. This figure was developed from large-scale triaxial tests on gravels from Mormon Island Auxiliary Dam, as well as data on gravels from Evans (1987). No significant residual excess pore pressures are expected to develop in the core.

Residual Strength

37. To estimate stability of the retaining wall and backfill in worstcase scenarios, residual strength of the embankment shell material was estimated with Seed's empirical procedure (Seed 1986) which relates $(N_1)_{60}$ to residual (post-liquefaction) shear strength, S_{ur} . This relationship is shown in Figure 34. Since the average $(N_1)_{60}$ of the core exceeds a reasonable extrapolation of Seed's chart, worst-case post-earthquake strengths of the core were estimated from reduced laboratory strength values.

General

38. Because failure of the downstream walls ("A" and "E") would not result in catastrophic loss of the reservoir, detailed study of these walls was not performed. The upstream wall, Retaining Wall B, is of concern since the embankment shell is saturated and the intake ports for the powerhouse are located riverward of the wall, and could be blocked if the wall and embankment slid due to the design earthquake. The investigation was aimed at determining what movements the wall might experience during the design earthquake and whether such movements would threaten the integrity of the embankment.

39. The construction photograph dated 16 April 1954, Figure 14, shows the completed wall with Zone A backfill in place. It is evident that a twolane construction road exists at the base of the riverward face of the wall. Thus, the wall can undergo at least 20 ft of horizontal displacemen: without falling into the river channel.

40. However, horizontal displacements on the order of 20 ft or more, along with a deep-seated sliding failure surface through the embankment fill would seriously threaten the integrity of the envelopment area and reduce the crest elevation to the pool level. It is estimated that 10 ft of horizontal displacement could safely be tolerated since this corresponds roughly to a 5 ft reduction in crest height, leaving a freeboard of about 10 ft, and since a large volume of cohesionless material, Zone A and Zone B fills, are involved in the slide and would be available to fill cracks that developed.

41. A Newmark sliding block approach (Newmark 1965) was adopted to estimate the earthquake-induced permanent displacement of the wall and backfill. The Newmark approach for estimation of earthquake-induced permanent displacements involves determination of yield accelerations, estimation of embankment response and calculation of displacements. Yield acceleration is defined as the horizontal acceleration applied to the center of gravity of a sliding mass that results in a factor of safety against sliding of unity in a pseudo-static stability analysis. Two methods of stability analysis, Mononobe-Okabe (Seed and Whitman 1970) and UTEXAS2 (Wright 1985), and a range of material strengths were used to determine yield accelerations for Retaining Wall B. Vertical acceleration and possible hydrodynamic effects were expected

to be minimal, and with the concurrence of the Technical Specialists, were not included in the analyses.

42. The dynamic response of the embankment calculated with SEISCOE (a shear beam approach by Sarma 1979) and with FLUSH and the dynamic response of the Concrete Gravity Dam calculated with EADHI-84 were used to determine the earthquake-induced accelerations (loads) to be compared with the yield accelerations (available strength) in the backfill and retaining wall system. The earthquake-induced permanent displacements were then calculated with three different techniques, Makdisi-Seed (Makdisi and Seed 1979), Sarma-Ambraseys (Hynes-Griffin 1979, and Hynes-Griffin and Franklin 1984), and modified Richards-Elms (Whitman and Liao 1985). In addition to these analyses, an assessment of the post-earthquake stability of the wrap around was made with UTEXAS2 for a range of material strengths and geometries. A worst case scenario including a complete loss of Retaining Wall B and the Zone A material was included in these investigations.

ł

Yield Acceleration Analyses

43. Yield accelerations, k_y (the pseudo-static acceleration applied at the center of gravity of a sliding mass which will reduce the safety factor against sliding to one), were computed for two locations, Section A-A which represents the wall and backfill geometry at the contact with the Concrete Gravity Dam (the tallest wall section), and Section C-C, in the vicinity of Wall Station 2+00. These sections and locations are shown in Figure 7. For the two-dimensional stability analyses, Sections A-A and C-C were idealized as simple gravity retaining walls resting on a level rock surface. The idealized sections are shown in Figures 35 and 36. The friction angle at the base of the wall was conservatively estimated as 30 degrees. Mononobe-Okabe

44. Classically, seismically induced lateral earth pressures in dry granular media have been calculated with the Mononobe-Okabe approach. The complete form of the equation for the combined active and seismic force on the wall is:

$$P_{AE} = \frac{1}{2} \gamma H^2 (1 - k_v) \kappa_{AE}$$
(1)

Conventionally, k_v is ignored. Therefore, Equation 1 is simplified to the following form:

$$P_{AE} = \frac{1}{2} \gamma H^2 K_{AE}$$
(2)

where

$$K_{AE} = \frac{\cos^2 (\phi - \psi - \beta)}{\cos \psi \cos^2 \beta \cos (\psi + \beta + \delta) \left[1 + \sqrt{\frac{\sin (\phi + \delta) \sin (\phi - \psi - 1)}{\cos (1 - \beta) \cos (\psi + \beta + \delta)}}\right]^2}$$
(3)

The force P_{AE} is the combined static and dynamic force due to the earth wedge defined by the assumptions made in deriving the equation for K_{AE} . The equation for K_{AE} is subject to all of the limitations applicable to a Coulomb formulation. Definitions of terms are as follows:

(conventionally, k_v can be ignored and ψ equals $\tan^{-1}(k_h)$) ϕ_h = wall friction angle, it was assumed to be $\phi/2$

Because k_v can be ignored, from this point on the subscript, v or h, will be dropped, and the seismic coefficient will just be called k. (See Figure 37 for a visual representation of the variables).

45. Retaining Wall B is completely submerged and this fact was accounted for in the analysis. A homogeneous backfill with a total unit weight of 152 pcf was used in the Mononobe-Okabe calculations. The problem was solved as if the wall and backfill were not submerged. The procedure to compute the equivalent seismic coefficient, k_y^* , is discussed in the following paragraphs. Finally, k_y^* , was determined using the computer programs in Appendix A. Then the resulting yield acceleration, k_y^* , was multiplied by

the ratio of buoyant unit weight to total unit weight to determine k_y , the yield acceleration that accounts for the effect of submergence. In this way, horizontal loads are computed with the total unit weight of the backfill but effective or buoyant unit weight controls the vertical stresses and hence shear strength along the critical sliding surface. The ratio of buoyant unit weight to total unit weight is 0.6 for the rockfill and gravel transition backfill.

46. In the Mononobe-Okabe procedure, there is a condition that ψ , the arctan of the horizontal seismic coefficient, must be less than or equal to the friction angle, ϕ , minus the slope angle, i. Values larger than this correspond to a non-equilibrium condition, and backfill material would fail by ravelling and sliding until the slope angle i was reduced to the limiting value of $\phi - \psi$. Over the range of backfill strengths investigated, the condition that ψ be less than or equal to $\phi - i$ was maintained for all computed yield accelerations without changing the slope angle i.

47. Because of the uncertainties in dealing with a submerged retaining wall in a seismic environment (there have been no documented cases to verify the theoretical approach), two parameters were varied in the analyses and conservative conclusions were drawn from the results. The parameters varied were the pore pressure coefficient, reflected in the angle of internal friction utilized for the backfill, ϕ , and the wall inclination angle, β .

48. The backfill strengths were selected to correspond to excess pore pressure levels uniformly distributed throughout the backfill. With no excess pore pressure, $r_u = 0$, the effective friction angle of the Zone B gravel and that assumed for the Zone A rockfill is 43°, as presented earlier in Part III. It was estimated in the Wing Dam studies that the upstream shell of the Right Wing Dam may develop an average r_u about equal to or slightly less than 25 percent. The simple p-q diagram construction shown in Figure 38 was used to determine backfill friction angles of 43°, 37.9°, 33.1°, and 29.9° to correspond to excess pore pressure levels of 0 percent, 10 percent, 20 percent, and 25 percent, respectively. Yield accelerations were computed for these four excess pore pressure levels. The friction angle at the base of the wall, ϕ_b , was assumed to be 30 degrees. As mentioned in paragraph 18, the foundation rock exposure consisted of sharp, irregularly blasted surfaces. This foundation feature makes the selection of a 30 degree sliding friction angle

conservative. Two wall inclination angles were studied, the actual as-built value of 33 degrees and 0 degrees.

49. Short computer programs were developed to determine the values of $k_{_{\rm U}}$ for the various parameter values presented above. See Appendix A for a listing of the programs and detailed output. The computed yield accelerations are summarized in Figure 39 and Table 3. As expected, as excess pore pressures increase, the yield acceleration decreases. The most critical seismic coefficient leading to a safety factor of 1.0 against sliding was k = 0.025for Section A-A with a wall inclination angle of beta equal to 33 degrees and an excess pore pressure of 25 percent ($\phi = 29.9^\circ$). The corresponding failure surface is inclined at an angle of 34° which intercepts the core as shown in Figure 40a. The minimum yield acceleration computed for Section C-C was 0.034 for the excess pore pressure field of 25 percent. This failure surface is inclined at 34.5° and also intercepts the core, as shown in Figure 40b. The failure surface angle α is defined in Figure 35. Eccentricities of loads were also computed, and it was found that the resultants fell within the base of the wall. These calculations imply that sliding is more critical than overturning, however, it is recognized that the assumed friction at the base of the wall is quite conservative.

UTEXAS2 approach

50. As a check on the Mononobe-Okabe assumptions and calculations, the yield accelerations were also computed using UTEXAS2. The program has the capability to search for the most critical non-circular sliding surface, and was expected to provide a better estimate of the involvement of the core in the slide.

51. The UTEXAS2 program uses Spencer's procedure which satisfies all requirements for static equilibrium by assuming that all side forces have the same inclination. The trial and error solution involves successive assumptions for the factor of safety and side force inclination to search for the most critical shear surface.

52. For the two cross sections A-A and C-C, the seismic coefficient was varied until a factor of safety against sliding approximately equal to unity was determined. As in the Mononobe-Okabe calculations, the backfill strength parameters were $\phi = 43^{\circ}$, 37.9°, 33.1°, and 29.9° (c = 0) to correspond to r_{u} equal to 0, 10, 20, and 25 percent, respectively. Only values of β equal to 33° were investigated with UTEXAS2 for both cross sections.

53. Core strengths of $\phi = 37^{\circ}$ and 31.1° (c = 0) were used in the calculations. The resulting yield accelerations are shown in Table 4 with the Mononobe-Okabe results, and the critical failure surfaces for Sections A-A and C-C are shown in Figure 41. The corresponding minimum yield accelerations are 0.060 and 0.065, respectively for a core strength of $\phi = 31.1^{\circ}$, c = 0. The UTEXAS2 yield accelerations are fairly close to those obtained with the Mononobe-Okabe procedure for the range of strengths investigated, and the failure surfaces are in about the same locations. At low values of r_u , the yield accelerations are almost identical, and at higher values of r_u (values greater than 20 percent), the UTEXAS2 approach gives relatively higher results. In general, Section A-A has lower yield accelerations than Section C-C.

54. The strengths assumed for the core are conservative since the core is very densely compacted and has very high strength in consolidated-undrained loading. Figure 42 shows an R-strength envelope (total stress) with c = 4.06 tsf and $\phi = 30.6^{\circ}$ determined from laboratory tests on samples from Dike 5 which are representative of the core material, Zone C. Due to this high consolidated-undrained strength, it is unlikely that the core will undergo any Newmark-type deformation due to movement of the wall. A check on this assumption was made with a reduced undrained core strength of c = 4,000 psf and $\phi = 0$ for Section A-A. The shell strength corresponded to $r_u = 25$ percent. In this case, the yield acceleration was 0.073 and the critical failure surface, shown in Figure 41, did not involve the core.

Summary of yield acceleration computations

55. In summary, yield accelerations were calculated for two wall locations, Sections A-A and C-C, for a range of shell and core strengths by Mononobe-Okabe and UTEXAS2 procedures. A lower-bound estimate of the yield acceleration is 0.025g, based on Mononobe-Okabe calculations for Section A-A, with a residual excess pore pressure field of 25 percent ($\phi = 29.9^{\circ}$, c = 0) in the Zone A and Zone B shell materials. This failure surface is inclined at 34° and intercepts the core. A more representative, yet conservative UTEXAS2 analysis of Section A-A with a shell strength of $\phi = 29.9^{\circ}$ and c = 0, and a core strength of $\phi = 0$ and c = 4,000 psf (less than half the measured laboratory R-strength), resulted in a yield acceleration of 0.073g and a failure surface that does not intercept the core, but is confined to the upstream shell.

56. A degree of conservatism is called for in the analysis of Retaining Wall B due to a lack of well-documented case histories of submerged retaining walls subjected to seismic loading, variability in Newmark-type displacement calculations, and uncertainties in the material properties of the embankment fill, particularly Zone A, which construction records show is a rockfill with considerable fines dumped in 12-ft lifts. In view of these uncertainties, and to determine an upper bound for Newmark-type displacement of the wall and backfill, the displacement calculations were carried out with $k_y = 0.025g$, with the understanding that the actual displacements in the field should be less than the computed values.

Permanent Deformation Estimates

57. Earthquake-induced permanent displacements were estimated with three methods: Makdisi-Seed, Sarma-Ambraseys and modified Richards-Elms. The Makdisi-Seed and Sarma-Ambraseys methods explicitly include embankment amplification effects in the displacement calculations. The modified Richards-Elms approach is more approximate with regard to ground motion amplification, but due to the modifications developed by Whitman and Liao (1985) it quantitatively accounts for the many uncertainties in Newmark displacement calculations such as theoretical deficiencies in the sliding-block model, the random nature of earthquake ground motions, uncertainty in parameters characterizing the backfill, wall and foundation, and other, poorly understood deficiencies of the simple sliding block model. Each of these methods was applied to the retaining wall problem to estimate the range of earthquake-induced displacements consistent with the conservatively computed minimum yield acceleration of 0.025g. As discussed earlier, the wall and wrap-around backfill should be able to easily tolerate displacements of about 10 ft.

Makdisi-Seed calculations

58. The parameters needed for these calculations are:

- <u>a</u>. The yield acceleration, k_y (fixed at 0.025).
- b. The maximum crest acceleration, \ddot{u}_{max} .

- <u>c</u>. The maximum earthquake seismic coefficient, k (the maximum earthquake-induced acceleration averaged over the sliding surface boundary).
- <u>d</u>. The depth of the failure surface, y, relative to the total embankment height, h (only failure surfaces that extend over the full height of the embankment were considered, so y/h = 1.0).

The peak crest acceleration at the wrap-around is estimated to be somewhat greater than that calculated with FLUSH for the Wing Dams, but less than that calculated with EADHI-84 for the Concrete Gravity Dam. Figure 32 shows that the calculated \ddot{u}_{max} for the Wing Dams was 0.54g, which implies an amplification factor of the base ground motion of about 1.5. A peak crest acceleration of about 2.8g was estimated for the Concrete Gravity Dam, based on a single-mode approximation from the EADHI-84 results. Peak crest accelerations that ranged from 0.54 to 1.7g (the average of the embankment and gravity dam peak values) were considered in these displacement calculations. These values of \ddot{u}_{max} correspond to amplification factors that range from 1.5 to 5. Since the concrete dam is embedded in the embankment at the wrap-around, it is estimated that its dynamic response will be considerably reduced by the upstream and downstream fill. It is assumed that a good estimate for \ddot{u}_{max} at the wrap-around is lg.

59. The maximum earthquake seismic coefficient, k_{max} , is estimated from \ddot{u}_{max} and Figure 43, which shows a range of values for k_{max}/\ddot{u}_{max} (determined from numerous dynamic analyses) plotted versus y/h. For y/h = 1.0, the average value of k_{max}/\ddot{u}_{max} is 0.34 and the upper bound value is 0.47. Both of these values for k_{max}/\ddot{u}_{max} were used to estimate k_{max} for the various \ddot{u}_{max} values considered. The best estimate for k_{max} is 0.34 x (\ddot{u}_{max} = 1.0g) = 0.34. The upper bound estimate for k_{max} is 0.47 x (\ddot{u}_{max} = 1.7g) = 0.80.

60. Figure 44 shows a range of Newmark-type displacements determined for various values of k_y/k_{max} for Magnitude 6.5 earthquakes. For the best estimate of $k_{max} = 0.34$, the ratio k_y/k_{max} is equal to 0.025/0.34 = 0.07. The corresponding approximate displacement is 70 cm or 2.3 ft. For the upperbound estimate of $k_{max} = 0.80$, the lower-bound value of k_y/k_{max} is equal to 0.025/0.80 = 0.03. The corresponding upper-bound displacement is 7.2 ft. With the compounded conservatism of lower-bound yield acceleration and upperbound seismic coefficient and displacement values, it is expected from this application of the Makdisi-Seed procedure that movement along the failure surface will occur, but be limited to less than 7 ft.

Sarma-Ambraseys calculations

- 61. This procedure involves the following parameters:
 - <u>a</u>. The yield acceleration, k_v (fixed at 0.025).
 - b. The fundamental period of the system, T_{c} .
 - <u>c</u>. The amplification factor a , from which the maximum earthquake seismic coefficient (A, defined as the maximum embankment acceleration averaged over the sliding mass) is determined as $A = a \times peak$ bedrock acceleration.

<u>d</u>. The ratio y/h as defined above. For this case, y/h = 1.0. Values of amplification factor a were computed with SEISCOE for both earthquake records A and B for a range of fundamental periods, $T_0 = 0.1$ to 4 sec., and are shown in Figure 45 for several values of y/h. The maximum value of a from Figure 45 is 2.25 for y/h = 1.0, and occurs over the range $T_0 = 0.20$ to 0.25 sec. The fundamental period of the Wing Dam section computed with FLUSH was 0.83 sec. At $T_0 = 0.83$ sec, the amplification factor a is 1.0. The fundamental period of the concrete gravity dam, including foundation stiffness and the presence of the reservoir, is approximately 0.3 sec, and the corresponding amplification factor is approximately 1.75. The maximum value of a = 2.25 was used for the displacement calculations.

62. Newmark displacement charts were calculated for earthquake records A and B for several values of k_y/A , and are shown in Figure 46. For k_y = 0.025 and A = 2.25 × 0.35 = 0.79, k_y/A = 0.32. The corresponding chart displacement, U_c , is 91 cm (3 ft) for record A and 36 cm (1.2 ft) for record B. The field displacement, U_f is calculated as $\alpha \times a \times U_c$. The factor α is a term from the solution to the equations of motion for relative displacement of the sliding block (see Hynes-Griffin and Franklin, 1984), and is a function of the inclination of the sliding surface (34°) and the friction angle of the backfill (29.9°). The factor α is equal to $\cos(34° - 29.9°)/$ $\cos(29.9°) = 1.15$. The resulting field displacement for record A is $U_f = 1.15 \times 2.25 \times 91$ cm = 235 cm (7.7 ft), and for record B, $U_f = 1.15 \times 2.25 \times 36$ cm = 93 cm (3 ft). The Makdisi-Seed estimated displacements of 2.3 ft (best estimate) and 7.2 ft (maximum) are very similar to those calculated with the Sarma-Ambraseys approach.

Modified Richards-Elms calculations

63. The sliding-block method of analysis developed by Richards and Elms (1979) was modified by Whitman and Liao (1985) to quantitatively account for uncertainties in the input parameters and inadequacies in the model itself. These errors can be attributed to the uncertainty associated with ground motions, the uncertainties associated with resistance (unit weights of the backfill or the retaining wall, friction angles, or wall friction), due to model errors (assuming vertical acceleration is negligible, assuming that the slope failure angle is constant with time, or that the one-block model is accurate enough), or due to the effect of tilting (from Whitman and Liao, 1985). The Richards-Elms approach attempts to take these uncertainties into account when computing seismic induced displacements.

64. The basic equation proposed by Whitman and Liao is:

$$\mathbf{d}_{\mathbf{R}\mathbf{w}} = \mathbf{d}_{\mathbf{R}\mathbf{v}} \times \mathbf{R}_{2/1} \times \mathbf{Q} \times \mathbf{R}_{\phi} \times \mathbf{M}$$
(4)

where

- $d_{R_{W}}$ = predicted residual displacement
- d_{Rv} = mean (expected) residual displacement for a sliding block exposed to ground motion characterized by a small number of parameters (such as peak acceleration, A, and peak velocity, V)
- R_{2/1} = deterministic term accounting for a specific kinematic deficiency in the single sliding block model
 - Q = term accounting for the unpredictable details in the random nature of future earthquake shaking
 - R = term accounting for the uncertainty in the parameters characterizing the backfill, wall and foundation soil
 - M = term accounting for other, and as yet, poorly understood deficiencies of the simple sliding block model

65. Whitman and Liao (1985) recommend values for $R_{2/1}$, Q, R, and M to simplify Equation 4. Equation 4 can be rewritten to account for the probability of a computed displacement occurring. A 95 percent probability level corresponds to a factor of safety of 4 on the computed displacement, which means that the computed displacement for a 95 percent non-exceedance reliability is 4 times the best estimate value of displacement. The formula that relates the input parameters to displacement for a 95 percent probability of non-exceedance is:

$$\frac{k_y}{A_{max}} = 0.66 + \frac{1}{9.4} \ln \frac{V_{max}^2}{A_{max} g d_L}$$
(5)

where

 $g = 981 \text{ cm/sec}^2$

d_L = limiting value of displacement in cm for a 95 percent probability of non-exceedance

The parameters required to substitute into the equation above are:

- <u>a</u>. The yield acceleration, $k_y = 0.025$ from the Mononobe-Okabe calculations.
- b. The design ground motion parameters, $A_{max} = 0.35g$ and $V_{max} = 20 \text{ cm/sec}$.
- <u>c</u>. The degree of conservatism in the displacement calculations expressed as the probability that the wall displacement will not exceed the computed value. A 95 percent probability of non-exceedance was selected.

With these values and the Richards-Elms equation, the limiting value of displacement is computed to be 9.7 ft, and the best estimate for wall displacement is computed to be 2.4 ft. These values are quite similar to those computed with the Makdisi-Seed and Sarma-Ambraseys approaches, and are within tolerable limits.

Post-Earthquake Stability Studies for Worst Case Scenarios

66. A study was made of the consequences of complete wall failure by investigating two worst-case scenarios. In one case, the wall is assumed to have toppled, and the backfill slope is still approximately 1 vertical to 2 horizontal but the shell strength is reduced to a residual value of 1,800 psf (based on a reduced $(N_1)_{60}$ value of 19 for the envelopment shell from adjusted Becker data, and a corresponding residual strength from Seed (1986) shown in Figure 34). In this extreme case, the slope has a factor of safety of 1.12 against post-earthquake sliding. In the other case, the retaining wall and all of Zone A are assumed to be lost, leaving the gravel transition Zone B exposed at a slope of 1 vertical on 1.5 horizontal, with a residual strength of 1,800 psf. In this extreme case, the factor of safety against post-earthquake sliding was 1.07. Since the safety factors against liquefaction typically exceed 1.5 in the Right Wing Dam, the post-earthquake

stability of the wrap-around slope will be greater than that for the residual conditions listed above, and the deformations associated with development of soil strength will be considerably less than those needed for residual conditions.

67. The Newmark-type displacement analyses for the Wing Dams described in Report 6 of this series concluded that earthquake-induced deformations in the downstream shells would be less than 0.5 m. If Retaining Walls A and E were to fail due to earthquake loads, the deformed slope of the envelopment fill would be approximately 35°. Since this slope is significantly less than the friction angle of the fill, the deformed slope should be stable.

Stability Evaluation

68. The Makdisi-Seed, Sarma-Ambraseys and modified Richards-Elms approaches all gave earthquake-induced permanent displacement estimates of Retaining Wall B and Right Wing envelopment fill less than or equal to 5 ft for average estimates and less than 10 ft for upper-bound estimates. These Newmark sliding-block analyses indicate that some damage to the wall is expected but the deformations will be limited. Worst-case scenario investigations show the slopes will be stable even with total failure of Retaining Wall B. Catastrophic loss of the reservoir is not expected as a result of the damage to the upstream retaining wall and envelopment fill. It is concluded that failure of Retaining Walls A and E would not threaten the integrity of the envelopment area as long as the backfill is unsaturated.

PART V: SUMMARY AND CONCLUSIONS

69. There are many uncertainties associated with computing the displacements of a retaining wall in a seismic environment. These uncertainties have been compounded for Retaining Wall B because it is submerged, and there are no case studies to allow a comparison of computed displacements with actual field performances.

70. Therefore, a very conservative approach has been used in these analyses. Two procedures, Mononobe-Okabe and UTEXAS2, were used to compute the seismic coefficient, k_y . Within each procedure, conservative estimates of parameters were used. For example, reduced backfill strengths were used in both procedures. The minimum yield acceleration was computed with a reduced backfill strength of $\phi' = 29.9^{\circ}$, which corresponds to a uniform excess pore pressure field in the backfill of 25 percent. Several different parameter variations were investigated, and the most conservative combination was the basis for determining k_y . The final value of k_y used for displacement calculations was 0.025g.

71. With this value of k_y an estimate of the movement of the wall was performed using three different methods, Makdisi-Seed, Sarma-Ambraseys, and Richards-Elms. In each method an average value of displacement was computed, as well as, the worst possible displacement. The worst possible displacement, a slip of 9.7 ft along the failure angle with a vertical drop of 6.5 ft, was determined from the Richards-Elms method.

72. A vertical drop of 6.5 ft would case a noticeable slip in the interface area, even in the core of the Right Wing Dam. However, with a free-board of 15 ft a drop of 6.5 ft is an acceptable displacement. There should not be a breech in the dam, the reservoir will not be lost, and the intakes to the penstocks will not be completely blocked.

73. A case has also been made, that even if Retaining Wall B is completely removed from the site, the integrity of the interface will remain intact. With the loss of the Zone A shell, the Zone B shell at a slope of 1.5 to 1 has a factor of safety against sliding greater that 1.0. Therefore, the core of the dam will still be safe even if Retaining Wall B has been destroyed.

74. It is concluded that failure of Retaining Walls A and E would not threaten the integrity of the envelopment area as long as the backfill is
unsaturated. Periodic inspection and maintenance of the weep holes in these walls is recommended to assure backfill drainage.

REFERENCES

Allen, M. G. 1984. "Liquefaction Potential Investigation of Mormon Island Auxiliary Dam, Folsom Project, California", Soil Design Section, US Army Engineer District, Sacramento, CA.

Banerjee, N. G., Seed, H. B. and Chan, C. K. 1979. "Cyclic Behavior of Dense Coarse-Grained Materials in Relation to the Seismic Stability of Dams", Report No. EERC 79-13, Earthquake Engineering Research Center, University of California, Berkeley, CA.

Bhatia, S. 1986. "Dynamic Effective Stress Analysis, Folsom Project," WES Contract Report, Vicksburg, MS.

Bolt, B. A., and Seed, H. B. 1983. "Accelerogram Selection Report for Folsom Dam Project, California." Contract Report DACW 05-83-Q-0205, US Army Engineer District, Sacramento, CA.

Elms, D., and Richards, R. 1979. "Seismic Behavior of Gravity Retaining Walls." Journal of the Geotechnical Engineering Division, American Society of Engineers. Vol 105, No. GT4, pp 449-464.

Evans, M. 1987. "Undrained Cyclic Triaxial Testing of Gravels-The Effect of Membrane Compliance," PhD Thesis in Engineering, University of California, Berkeley, CA.

Hynes-Griffin, M. E. 1979. "Dynamic Analyses of Earth Embankments for Richard B. Russell Dam and Lake Project," Final report prepared for US Army Engineer District, Savannah, GA.

. 1987. "Seismic Stability Evaluation of Folsom Dam and Reservoir Project, Vol 1, Summary Report." Draft Technical Report GL-87-14, US Army Engineer Waterways Experiment Station, CE, Vicksburg, MS.

Hynes-Griffin, M. E., and Franklin, A. G. 1984. "Rationalizing the Seismic Coefficient Method." Miscellaneous Paper S-84-13, US Army Engineer Waterways Experiment Station, CE, Vicksburg, MS.

JSCE. 1977. "Earthquake Resistant Design for Civil Engineering Structures, Earth Structures and Foundations in Japan," Japan Society of Civil Engineers.

Kiersch, G. A., and Treasher, R. C. 1955. "Investigations, Areal and Engineering Geology - Folsom Dam Project, Central California," <u>Economic Geology</u>, Vol 50, No. 3, pp 271-310.

Liao, S., and Whitman, R., 1984. "Seismic Design of Gravity Retaining Walls," <u>Eighth World Conference on Earthquake Engineering</u>, July 21-28, 1984, San Francisco, CA. Vol III, pp 533-540.

Makdisi, F. I., and Seed, H. B. 1979. "Simplified Procedure for Estimating Dam and Embankment Earthquake-Induced Deformations." Journal of the Geotechnical Engineering Division, American Society of Civil Engineers. Vol 104, No. GT7, pp 849-867.

Newmark, N. M. 1965. "Effects of Earthquakes on Dams and Embankments," Geotechnique, Vol 15, No. 2, pp 139-160.

Roddy, R. Jr. 1955. "Stilling Basin and Retaining Walls, Folsom Project, Foundation Report, American River, California." US Army Corps of Engineers, Sacramento District, Sacramento, CA.

Sarma, S. K. 1979. "Response and Stability of Earth Dam. During Strong Earthquakes." Miscellaneous Paper GL-79-13, US Army Engineer Waterways Experiment Station, CE, Vicksburg, MS.

Seed, H. B. 1986. "Design Problems in Soil Liquefaction," UCB/EERC Report No. 86/02, University of California, Berkeley, CA.

Seed, H. B., Idriss, I. M., and Arango, I. 1983. "Evaluation of Liquefaction Potential Using Field Performance Data," Journal of the Geotechnical Engineering Division, American Society of Civil Engineers, Vol 109, No. GT3, pp 458-482.

Seed, H. B., Lee, K. L., Idriss, I. M., and Makdisi, F. 1973. "Analysis of the Slides in the San Fernando Dams during the Earthquake of February 9, 1971." Report No. EERC 73-2. Earthquake Engineering Research Center, University of California, Berkeley, CA.

Seed, H. B., Tokimatsu, K., Harder, L. F., and Chung, R. M. 1984. "The Influence of SPT Procedures in Soil Liquefaction Resistance Evaluations," UCB/EERC Report No. 84/15, University of California, Berkeley, CA.

Seed, H. B., and Whitman, R. V. 1970. "Design of Earth Retaining Structures for Dynamic Loads," <u>ASCE Specialty Conference, Lateral Stresses in the Ground</u> and Design of Earth Retaining Structures, pp 103-147.

Sykora, D. W., and Hynes-Griffin, M. E. 1987. "Seismic Stability Evaluation of Folsom Dam and Reservoir Project, Vol 2, Interface Report." Draft Technical Report GL-87-, US Army Engineer Waterways Experiment Station, CE, Vicksburg, MS.

Tierra Engineering Consultants, Inc., 1983. "Geologic and Seismologic Investigations of the Folsom, California Area." Contract Report DACW 05-82-C-0042, US Army Engineer District, Sacramento, CA.

Tsuchida, T. 1986. "Stability Analysis of Retaining Walls," working papers.

Whitman, R., and Liao, S. 1985. "Seismic Design of Gravity Retaining Walls," Miscellaneous Paper GL-85-1, US Army Engineer Waterways Experiment Station, CE, Vicksburg, MS.

Wright, S. G. 1985. "UTEXAS2 (University of Texas Analysis of Slopes -Version 2), A Computer Program for Slope Stability Calculations," US Army Engineer District, Ft. Worth Contract Report.

36

Design Values of Embankment Soil Properties in Wing Dams	from Construction Records
Design Val	
of	
Summary	

Table l

Ĩ

1

tive fon Permeability f) (ft/day)	-	1	0.5
Effec Cohes (ps	0	0	0
Effective Friction Angle (°)	40°	40°	35°
Saturated Unit Weight (pcf)	143.8	143.8	140.0
Moist Unit Weight (pcf)	133.0	133.0	134.0
Dry Unit Weight (pcf)	125.C	125.0	123.4*
Description	Rockfill Shell	Gravel Transition	Impervious Core
Zone	A	В	C

* At 95% Modified A.A.S.H.O. Density.

į.

Table 2 Hyperbolic Parameters Input to FEADAM for Static Analysis of Wing Dams

	Effective Unit	Young's	Modulus	Young's Modulue	Fallure	Bulk	Bulk Modulus	Effective	Effective	Change in ¢ Per Log Cycle Change	Static
Material Location	Weight (pcf)	Loading K (ksf)	Unloading K _{ur} (ksf)	Exponent	Ratio R _f	Modulus K _b	Exponent M	Cohesion Intercept C (ksf)	Friction Angle A (°)	in Confining Stress	Ratio
Saturated Shell	06	1,900	1,900	. 39	6.	1,287	.33	0	13	90	
Dry Shell	139	1,900	1,900	66.	6.	1.267	5 5		2 C V	, c	с. Л
Saturated Core	79.4	1,175	1,175	.15	69.	979	دد.	o c	0 F	5 0	C. 0
Dry Core	136	1,175	1,175	.15	.69	619	.43		رد ۲۶	5 0	0.43
Rock	150	10,000	10,000	1.0	6.	10,000	1.0	, v	in G	-	0.43
								v	201	2	

		Yield Acceler	ation, K _v	·	
			Excess Pore Pro	essure, r (2	()
	Cross Section	0	10	20	25
C A S	A-A	0.147	0.097	0.054	0.025
E 1	C-C	0.153	0.105	0.062	0.034
C A S	A-A	0.154	0.113	0.088	0.078
E 2	C-C	0.161	0.126	0.091	0.081

	Tab	le 3		
Yield Accelerations	Computed	with	Mononobe-Okabe	Approach

Residual Excess	Corresponding Effective Friction	YI)†		
Pore	Angle of	Sectio	on A-A	Secti	on C-C
r (%)	¢(°)	Mononobe- Okabe	UTEXAS2**	Mononobe- Okabe	UTEXAS2**
0	43.0	0.15	0.13	0.15	0.16
10	37.9	0.10	0.11	0.11	0.125
20	33.1	0.05	0.08	0.06	0.09
25	29.9	0.025	0.06	0.03	0.065

			Table 4				
Summary	of	Yield	Accelerations	for	Retaining	Wall	B

* For gravel shell, c = 0. ** Core strengths are c = 0, $\phi' = 31.1^{\circ}$. + $\phi_1 = 30^{\circ}$.

ŧ



Figure 1. Location of Folsom Dam and Reservoir Project



Plan of man-made retaining structures at Folsom Dam Project Figure 2.







Figure 4. Geologic map, parts of the Folsom and Auburn quadrangles





Figure 5. Acceleration histories used in the analysis

,





Figure 6. Response spectra of records A and B





•

















ŗ.





.



HYDROME TER

Grain size distribution for materials of Zone C and existing Figure 13. dam in Right Wing Dam (from construction records)



Figure 14. Construction photograph FOL 1818, dated 16 April 1954, showing construction of Right Wing Dam, concrete monoliths, and Retaining Wall B (completed)



Figure 15. Folsom Dam Photo FOL 1141 (25 June 1953) - excavation for Retaining Wall "B" looking downstream





Figure 17. Folsom Dam Photo FOL 1282 (28 August 1953) - upstream area in right abutment



Figure 18. Folsom Dam Photo FOL 1190 (22 September 1953) - right abutment at intersection of the Main Dam and Retaining Wall "B" (looking upstream)

1



Figure 19. Folsom Dam Photo FOL 1364 (15 October 1953) - Main Dam and RWD construction looking from left abutment



Figure 20. Folsom Dam Photo FOL 1377 (15 October 1953) - upstream area of RWD looking downstream during placement of fill



Figure 21. Folsom Dam Photo FOL 1387 (15 October 1953) - upstream area of RWD looking upstream during placement of fill



Figure 22. Folsom Dam Photo FOL 1502 (4 December 1953) - upstream area of RWD locking upstream during placement of fill



Figure 23. Folsom Dam Photo FOL 2065 (14 October 1954) - Left Wing Dam and MD with RWD in background shortly before completion of fill placement



Figure 24. Comparison of ranges of gradations of Zone C core material in Right Wing Dam observed during construction (record samples) and in 1982 field investigations (recent samples)



performed in 1984 (recent samples)



gravel at Right Wing Dam, Folsom Dam Project. Range is compared with two laboratory gradations Range of gradations observed in test shafts excavated in downstream embankment shell Figure 26.



ACTUAL SECTION



Figure 27. Cross-section views of Right Wing Dam, Sta 283



Figure 28. Relationships between stress ratio causing liquefaction and $\binom{N_1}{60}$ -values for silty sands and for M = 7-1/2 earthquakes (from Seed, Tokimatsu, Harder, and Chung 1984)
FINITE ELEMENT MESH FOR RIGHT WING DAM -

325 ELEMENTS 343 NODAL PUIN7S NOTE: ALL ELEMENTS BELOW HEAVY LINE ARE SUBMERGED.







Figure 30. Adjustment factor, K_{σ} , for change in cyclic stress ratio required to cause r_{u} = 100 with change in effective normal stress, determined from laboratory tests on Folsom gravels



Figure 31. Adjustment factor, K , for change in cyclic stress ratio required to cause r_{u} = 100 with change in initial shear stress ratio, α , determined from laboratory tests on Folsom gravels

ACCELERATIONS COMPUTED BY FLUSH



















Figure 35. Idealized section of Retaining Wa'll B, Section A-A







Figure 37. Definition of parameters for Mononobe-Okabe approach













CROSS SECTION C-C







(a)















Embankment Characteristics for Magnitude 6-1/2 Earthquake

<u>Case t</u>	Embankment Description	Height <u>(ft.</u>)	Base Acceleration	T ₀ ⁽¹⁾	(2) k max (g)	<u>Symbol</u>
1	Example Case - slope = 2:1 - k = 60	150	0.2 (Caltech record)	C.8	(a) 0.31 (b) 0.12	•
2	Example Case - slope = 2:1 - k _{2max} = 60	150	0.5 (Caltech record)	1.08	(a) 0.4 (b) 0.18	°D
3	Example Case - slope = 2:1 - k _{2max} = 80	150	0.5 (Lake Hughes record)	0.84	(a) 0.33 (b) 0.16	0 4
4	Example Case - slope = 2-1/2:1 - k _ = 60	150	C.5 (Caltech record)	0.95	(m) 0.49 (51.0.22	0 V
5	Example Case - slope = 2:1 - k = 60	75	C.5 (Caltech record)	0. 6	(a) 0.86 (b) 0.26	.

(1) T = + Calculated first natural period of the embankment.

(2) k + Maximum value of time history of: max (b) grant appeleration

(a) crest acceleration

average acceleration
 average acceleration for sluding mass extending through full height of - Number nt.





Figure 45. SEISCOE amplification factors from records A and B for embankments founded on rock



Figure 46. Sliding block analysis - computed permanent displacements for records A and B

APPENDIX A

COMPUTER PROGRAM LISTINGS AND OUTPUT FOR YIELD ACCELERATION COMPUTATIONS WITH THE MONONOBE-OKABE PROCEDURE

```
MONONOBE - OKABE
 .
    EARTH PRESSURE DURING EARTHQUAKE
Retaining Wall B (Section A-A)
RD=3.1416/1801 'converts
 .
                                'converts degrees to radians
      FI=43*RD
                                'angle of internal friction
                                buoyant unit weight of backfill
'total weight of backfill
'height of retaining wall
      soilwtb=89.6
      soilwtt=152
      H=80.4
      BETA=33*RD
                                'angle of inclination of back of wall to vertical
                                'angle of inclination of backfill
'angle of friction between backfill and wall
      i=26.5*RD
      delta=FT/2
                               'friction angle between bottom of wall and ground
      FIb=30*RD
input "to where (i.e. CON, LPT1, LPT2, PRN or DOS file name;";IO.name$
if io.name$="" then
      end if
      OPEN IO.name$ FOR OUTPUT AS #2
      OPEN IC.name$

PRINT #2, "

PRINT #2, "
                      Friction Angle (Degree) = ":FI/RD
Buoyant Weight of Backfill = ":soilwtb
                       Height of Retaining Wall
                                                          = ";H
                       Beta (Degree)
                                                          - ";BETA/RD
                                                          - ";1/PD
                       Inclination (Degree)
                                                          = ";delta/RD
                       Delta (Degree)
                                                          = ";FIb/RD
                      Fib (Degree)
      locate 12,35:print "working"
FOR kh= 0.0 TO 0.45 STEP .05
      psv= ATN(kh)
      alphamin= (FI-psy)/PD
IF i/RD>alphamin THEN i=RD*(alphamin-.1) finsures imax not violated
                                                          'wedge weight buoyant
      glb= .5*H*H*soilwtb
                      Q2=COS(BETA)*COS(BETA) 'used to compute failure
Q3=COS(1-BETA)*COS(psy) 'angle, alpha and the wedge
QLAST= -900001 'weight at failure
      QLAST= -900001
FOR J= 0 TO 50 STEP .1
        ALP= alphamin+J
      RAF=ALP*FD
      X1=SIN(RAP-i)
      X2=COS(BETA-RAP)*SIN(RAP-FI+psy)
     X3=COS(BETA+delta+FI-RAP)
     04 = X2/(X1 + X3)
     Q=Q1b+Q3+Q4/Q2
al= fi-psy-beta
                                    'constants used to compute
     a2= psy+beta+delta
a3= fi+delta
                                 'Kae
     a4= i-beta
a5= fi-psy-i
funcl= l+sgr( (sin(a])*sin(a5)) / (cos(a4)*cos(a2)) )
      func2= func1*func1
     Kae= ( cos(al)*cos(al) ) / ( cos(psy)*cos(beta)*cos(beta)*cos(a2)*func2
     WTb= 2229001
                                    'bouyant weight of retaining wall/soil mass
     AX= BETA+delta
                                    'constant used to compute components of Fae
     Paeb≕ q1b*kae
     FS= ( (WTb+Paeb*SIN(AX)) *TAN(FIb) ) / ( WIb*kh+Paeb*COS(AX) )
     IF Q < QLAST THEN
     PRINT #2, USING
                                "accel=+#,### Q(last) =+#####.#
                                                                          Angle=+###.# F
     if io.name$<>"CON" then
locate 12,35:print "accel=";kh
locate 13,35:print "FS=";FS
                                                       'if sending output to
'a printer, lets the
'user know that the
       end if
                                                       'program is functioning
     exit for
     end if
     QLAST= Q
       NEXT J
     NEXT kh
     END
```

Friction Angle (Degree) Buoyant Weight of Backfill Total Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Flb (Degree)	- 43 - 89.6 - 152 - 80.4 - 33 - 26.5 - 21.5 - 30	
accel=+0.000 Q(last) = +247.6 accel=+0.050 Q(last) = +282.5 accel=+0.100 Q(last) = +126.4 accel=+0.150 Q(last) = +384.8 accel=+0.200 Q(last) = +469.8 accel=+0.250 Q(last) = +617.1 accel=+0.350 Q(last) =+1053.9 accel=+0.350 Q(last) =+1171.8 accel=+0.400 Q(last) =+1320.1	Angle= +64.6 FS= +1.705 Angle= +59.8 FS= +1.491 Angle= +54.8 FS= +1.327 Angle= +49.3 FS= +1.327 Angle= +49.3 FS= +1.092 Angle= +27.8 FS= +1.001 Angle= +27.8 FS= +0.911 Angle= +22.5 FS= +0.887 Angle= +22.5 FS= +0.867	Kae= +0.855 Kae= +0.978 Kae= +1.136 Kae= +1.687 Kae= +1.687 Kae= +2.264 Kae= +3.967 Kae= +4.542 Kae= +5.288
Friction Angle (Degree) Buoyant Weight of Backfill Total Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) K	- 37.9 - 89.6 - 152 - 80.4 - 33 - 26.5 - 18.95 - 30	
accel=+0.000 Q(last) = +287. accel=+0.050 Q(last) = +331.6 accel=+0.100 Q(last) = +393.4 accel=+0.150 Q(last) = +492.6 accel=+0.200 Q(last) = +797.2 accel=+0.250 Q(last) = +851.0 accel=+0.300 Q(last) = +916.7 accel=+0.350 Q(last) = +993.0 accel=+0.400 Q(last) =+1084.5	Angle= +58.3 FS= +1.465 Angle= +58.3 FS= +1.295 Angle= +46.5 FS= +1.158 Angle= +39.4 FS= +1.040 Angle= +28.4 FS= +0.910 Angle= +25.7 FS= +0.881 Angle= +22.9 FS= +0.854 Angle= +20.2 FS= +0.831 Angle= +17.6 FS= +0.810	Kae= +0.991 Kae= +1.148 Kae= +1.372 Kae= +1.739 Kae= +2.863 Kae= +3.450 Kae= +3.849 Kae= +4.344
Friction Angle (Degree) Buoyant Weight of Backfill Total Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree) <u>k</u>	= 33.1 = 89.6 = 152 = 80.4 = 33 = 26.5 = 16.55 = 30	
accel=+0.000 Q(last) = +338.8 accel=+0.050 Q(last) = +406.5 accel=+0.100 Q(last) = +406.5 accel=+0.150 Q(last) = +543.6 accel=+0.200 Q(last) = +719.8 accel=+0.200 Q(last) = +759.2 accel=+0.300 Q(last) = +802.3 accel=+0.350 Q(last) = +805.6 accel=+0.400 Q(last) = +906.6	Angle= +50.6 $FS=$ +1.263 Angle= +43.3 $FS=$ +1.117 Angle= +33.7 $FS=$ +0.977 Angle= +26.7 $FS=$ +0.895 Angle= +23.8 $FS=$ +0.863 Angle= +21.0 $FS=$ +0.863 Angle= +18.2 $FS=$ +0.809 Angle= +15.5 $FS=$ +0.786 Angle= +12.9 $FS=$ +0.766	Eae= +1.170 Kae= +1.407 Kae= +1.696 Kae= +2.411 Kae= +2.585 Kae= +2.785 Kae= +3.020 Kae= +3.632
Friction Angle (Degree) Bucyant Weight of Backfill Total Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) Fib (Degree)	 29.9 89.6 152 80.4 33 26.5 14.95 30 	
accel=+0.000 Q(last) = +391.8 accel=+0.005 Q(last) = +400.2 accel=+0.010 Q(last) = +409.2 accel=+0.015 Q(last) = +409.2 accel=+0.025 Q(last) = +419.0 accel=+0.025 Q(last) = +441.1 accel=+0.030 Q(last) = +445.9 accel=+0.045 Q(last) = +468.4 accel=+0.045 Q(last) = +468.7 accel=+0.045 Q(last) = +504.7 accel=+0.050 Q(last) = +529.5	Angle= +43.5 $FS= +1.130$ Angle= +42.6 $FS= +1.130$ Angle= +42.6 $FS= +1.116$ Angle= +40.8 $FS= +1.086$ Angle= +39.9 $FS= +1.086$ Angle= +38.8 $FS= +1.071$ Angle= +38.8 $FS= +1.056$ Angle= +37.7 $FS= +1.040$ Angle= +36.6 $FS= +1.024$ Angle= +35.3 $FS= +1.008$ Angle= +34.0 $FS= +0.991$ Angle= +32.4 $FS= +0.972$	Kae= +1.353 Kae= +1.382 Kae= +1.413 Kae= +1.447 Kae= +1.484 Kae= +1.524 Kae= +1.659 Kae= +1.617 Kae= +1.677 Kae= +1.633

Α3

Friction) Buoyant Wei Total Weig Height of Beta (Deg Inclinatic Delta (Deg FIb (Degre	Angle (Dec eight of I ght of Bac Retaining ree) on (Degree gree) e)	gree) Backfill ckfill g Wall B)	- 27 - 89.6 - 152 - 80.4 - 33 - 26.5 - 13.5 - 30			
accel=+0.000	Q(last)	= +497.0	Angle≓	+32.6	FS= +0.985	Kae= +1.716
accel=+0.050	Q(last)	- +567.7	Angle=	+26.6	FS= +0.911	Kac= +1.965
acce1=+0.100	Q(last)	- +588.7	Angle=	+23.7	FS= +0.875	Kae= +2.053
acce1=+0.150	Q(last)	= +609.4	Angle=	+20.8	FS= +0.843	Kae= +2.152
accel=+0.200	Q(last)	■ +629.9 ■ +650 7	Angle=	+1/.9	FS= +0.813	Kae≠ +2.262 Kac= +2.387
accel=+0.250	Q(last)	= +670.7	Angle=	+12.1	FS= +0.767	$Kae = +2.5^{-1}$
accel=+0.300	Q(last)	= +695 6	Angle=	+9.6	FS= +0.740	Kae= +2.551
accel=+0.400	O(last)	= +721.5	Angle=	+7.0	FS= +0.720	Kae= +2.890
Friction A Buoyant Wei Total Weig Height of Beta (Degr Inclinatic Delta (Degre	ingle (Deg light of E ht of Eac Retaining ee) n (Degree ree) e)	gree) Backfill Skfill g Wall B)	 27.8 89.6 152 80.4 33 26.5 13.9 30 			
acce1=+0.000	Q(last)	- +452.6	Angle=	+36.7	FS= +1.033	Kae= +1.563
acce1=+0.005	Q(last)	= +468.4	Angle=	+35.3	FS= +1.015	Kae= +1.618
accel=+0.010	Q(last)	- +487.5	Angle=	+33.8	FS= +0.997	Kae= +1.684
accel=+0.020	O(last)	= +512.0	Angles	+ 2 Q Q	-5= +0.9/5	Kae= +1.765 Kae= +1.800
accel#+0.025	O(last)	= +562.7	Angle=	+29.9	FS= +0.938	Kacz +1 944
accel=+0.030	Q(last)	➡ +565.0	Angles	+28.6	ES= +0.934	Kacm +1.953
accel~+0.035	Q(last)	+ + 567.3	Angler	+28.3	FS= +0.930	Kae= +1.961
accel=+0.040	Q(last)	+569.5	Angle=	+28.0	FS= +0.926	Kae= +1.970
accel=+0 045						
accer=+0.045	Q(last)	- +571.8	Angle=	+27.7	FS= +0.922	Kae= +1.979

.

```
.
    MONONOBE - OKABE
    EARTH PRESSURE DURING EARTHQUAKE
Retaining Wall B (Section A-A)
RD=3.1416/1801 'converts
                                 'converts degrees to radians
'angle of internal friction
       FI=43*RD
                                 'buoyant unit weight of backfill
'total weight of backfill
       soilwtb=89.6
       soilwtt=152
                                 'height of retaining wall
       H=80.4
                                'and'e of inclination of back of wall to vertical
'angle of inclination of backfill
       BETA=0*RD
       1=26.5*RD
                                 'angle of friction between backfill and wall
       delta=FI/2
                                'friction angle between bottom of wall and ground
       FID=30*RD
      ----------
      input "to where (i.e. CON, LPT1, LPT2, PRN or DOS file name;";IO.name$
if io.name$="" then
                    io.name$="CON"
       elseif io.name$="L" or io.name$="1" then
                    io.name$="LPT2"
                 end if
      end if

OPEN IO.name$ FOR OUTPUT AS #2

PRINT #2, " Friction Angle (D

PRINT #2, " Buoyant Weight of

PRINT #2, " Height of Retaini

PRINT #2, " Beta (Degree)

PRINT #2, " Inclination (Degr

PRINT #2, " Delta (Degree)

PRINT #2, " FIb (Degree)

PRINT #2, ""
                       Friction Angle (Degree)
Buoyant Weight of Backfill
                                                             - ";FI/RD
                                                           = ";soilwtb
                        Height of Retaining Wall
                                                             - ";H
                        Beta (Degree)
Inclination (Degree)
                                                            - ";BETA/RD
                                                            - ":1/RD
                                                            ";delta/RD
                                                            = ";FIb/RD
      locate 12,35:print "working"
      FOR kh= 0.0 TO 0.45 STEP .05
      psv= ATN(kh)
      alphamin= (FI-psy)/RD
      IF i/RD>alphamin THEN i=RD*(alphamin-.1)
                                                           'insures imax not violated
      q1b= .5*H*H*soilwtb
                                                            'wedge weight buoyant
                                                                                      -----
      Q2=COS(BETA) *COS(BETA)
                                             'used to compute failure
                                                 'angle, alpha, and the wedge
'weight at failure
      03=00S(1-BETA)*COS(psy)
      QLAST= -900001
        FOR J= 0 TO 50 STEP .1
        ALP= alphamin+J
      RAP=ALP+RD
      X1=SIN(RAP-1)
      X2=COS(BETA-RAP)*SIN(PAP-FI+psy)
      X3=COS(BETA+de ta+FI-RAP)
     Q4=X2/(X1*X3)
     Q=Q1b*Q3*Q4/Q2
1 -----
         ------
                                                                 al= fi-psy-beta
                                    fronstants used to compute
                                   'Kae
     a2= psy+beta+delta
     a3= fi+delta
     a4= i-beta
a5= fi-psy-i
      funcl= 1 + sqr((sin(a3) + sin(a5)) / (cos(a4) + cos(a2)))
     func2= func1+func1
     Kae= (\cos(a1) * \cos(a1)) / (\cos(psy) * \cos(beta) * \cos(beta) * \cos(a2) * func2
     WTb- 2229001
                                     'bouyant weight of retaining wall/soil mass
     AX= BETA+delta
                                     'constant used to compute components of Pae
     Paeb= g1b*kae
     FS= ( (WTb+Paeb*SIN(AX)) *TAN(F. ) ) / ( WIb*kh+Paeb*COS(AX) )
                                                                              1
     IF Q < OLAST THEN
     PRINT #2, USING
                                 "accel=+#.### Q(last) =+#####.# Angle=+###.# F
     if io.name$<>"CON" then
locate 12,35:print "accel=";kh
locate 13,35:print "FS=";FS
                                                         'if sending output to
                                                         'a printer, lets the
'user know that the
       end if
                                                         'program is functioning
     exit for
     end if
     QLAST= Q
       NEXT J
     NEXT kh
```

END

Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	 ■ 43 ■ 89.6 ■ 80.4 ■ 0 ■ 26.5 ■ 21.5 ■ 30
accel=+0.000 Q(last) = +68.9 accel=+0.050 Q(last) = +81.3 accel=+0.100 Q(last) = +96.1 accel=+0.100 Q(last) = +114.4 accel=+0.200 Q(last) = +178.4 accel=+0.250 Q(last) = +174.5 accel=+0.300 Q(last) = +258.6 accel=+0.350 Q(last) = +275.7 accel=+0.400 Q(last) = +292.3	Angle= +59.8 FS= +4.362 Kae= +0.238 Angle= +56.7 FS= +2.857 Kae= +0.281 Angle= +53.2 FS= +2.096 Kae= +0.281 Angle= +49.2 FS= +1.630 Kae= +0.404 Angle= +44.5 FS= +1.309 Kae= +0.407 Angle= +38.5 FS= +1.059 Fae= +0.640 Angle= +28.5 FS= +0.811 Kae= +0.973 Angle= +25.9 FS= +0.737 Yae= +1.069 Angle= +23.3 FS= +0.675 Kae= +1.171
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	 ⇒ 37.9 ⇒ 89.6 ⇒ 80.4 ⇒ 5 ⇒ 18.95 ⇒ 30
accel=+0.000 Q(last) = +91.7 accel=+0.050 Q(last) = +108.6 accel=+0.100 Q(last) = +130.4 accel=+0.150 Q(last) = +162.1 accel=+0.200 Q(last) = +242.5 accel=+0.200 Q(last) = +257.2 accel=+0.300 Q(last) = +272.3 accel=+0.300 Q(last) = +286.5 accel=+0.400 Q(last) = +300.2	Angle= +54.8 10= +3.254 Fae= +0.317 Angle= +50.8 FS= +2.266 Fae= +0.376 Angle= +46.2 FS= +1.699 Fae= +0.455 Angle= +40.2 FS= +1.312 Kae= +0.457 Angle= +28.8 FS= +0.945 Fae= +0.871 Angle= +26.2 FS= +0.945 Fae= +0.944 Angle= +21.5 FS= +0.766 Fae= +1.025 Angle= +20.9 Fb= +0.764 Kae= +1.202
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FID (Degree)	■ 33.1 ■ 57.5 ■ 50.4 ■ 0 ■ 26.5 ■ 16.55 ■ 30
accel=+0.010 Q(last) = +121.8 accel=+0.010 Q(last) = +149.2 accel=+0.100 Q(last) = +195.0 accel=+0.100 Q(last) = +241.7 accel=+0.2.3 Q(last) = +255.0 accel=+0.25 Q(last) = +267.3 accel=+0.35 Q(last) = +267.3 accel=+0.355 Q(last) = +263.4 accel=+0.355 Q(last) = +293.4 accel=+0.405 Q(last) = +303.9	Andler +44.6 For +2.441 Faer 43.420 Angler +43.0 107 +1.249 Faer 40.513 Angler +34.4 For +1.263 Faer +0.683 Angler +21.1 For +0.999 Kaer +0.6853 Angler +21.6 For +0.802 Faer +0.985 Angler +21.6 For +0.802 Faer +0.988 Angler +18.4 For +0.730 Faer +1.061 Angler +16.3 For +0.670 Faer +1.137 Angler +13.8 For +0.619 Faer +1.217
Friction Angle (Degree) Buryant Weight of Backf'll Height of Fetaining Wall Deta (Degree) Inclination (Degree) Delta (Legree) Fib (Degree)	- 79.9 - 29.6 - 80.4 - 9 - 26.5 - 14.95 - 30
accel=+0.000 Q(last) = +151.4 accel=+0.050 C(last) = +203.6 accel=+0.100 Q(last, = +277.9 accel=+0.150 Q(last) = +264.0 accel=+0.200 Q(last) = +264.0 accel=+0.250 Q(last) = +275.7 accel=+0.300 Q(last) = +286.4 accel=+0.300 Q(last) = +296.4	$\Lambda::10 \rightarrow +42.8$ $ES \rightarrow +1.966$ $Ea \circ \mp +9.523$ $\Lambda::10 \rightarrow +32.8$ $ES \rightarrow +1.342$ $Ea \circ \mp +0.705$ $\Lambda::10 \rightarrow +26.9$ $EC \rightarrow +1.042$ $Ea \circ \mp +0.810$ $\Lambda::10 \rightarrow +24.1$ $ES \rightarrow +0.956$ $Ea \circ \mp +0.887$ $\Lambda::10 \rightarrow +21.3$ $ES \rightarrow +0.856$ $Ea \circ \mp +0.948$ $\Lambda::10 \rightarrow +21.3$ $ES \rightarrow +0.776$ $Ea \circ \mp +0.948$ $\Lambda::10 \rightarrow +11.9$ $ES \rightarrow +0.776$ $Ea \circ \mp +1.012$ $\Lambda::10 \rightarrow +11.2$ $ES \rightarrow +0.709$ $Ea \circ \mp +1.012$ $\Lambda::10 \rightarrow +10.2$ $ES \rightarrow +0.655$ $Ea \circ \mp +1.147$

Friction A Buoyant We Height of Beta (Degr Inclinatio Delta (Deg FIb (Degre	ngle (Degree) ight of Backfill Retaining Wall ee) n (Degree) ree) e)	 27.8 89.6 80.4 0 26.5 13.9 30 		
accel=+0.000 accel=+0.050 accel=+0.100 accel=+0.150 accel=+0.250 accel=+0.350 accel=+0.350 accel=+0.400	Q(last) = +182.2 Q(last) = +231.2 Q(last) = +244.5 Q(last) = +257.0 Q(last) = +268.6 Q(last) = +279.1 Q(last) = +288.5 Q(last) = +296.8 Q(last) = +304.0	Angle= +36.8 Angle= +27.7 Angle= +24.9 Angle= +22.1 Angle= +19.3 Angle= +16.6 Angle= +13.9 Angle= +11.2 Angle= +8.7	FS= +1.640 $FS= +1.198$ $FS= +1.047$ $FS= +0.930$ $FS= +0.837$ $FS= +0.760$ $FS= +0.697$ $FS= +0.643$ $FS= +0.597$	Kae= +0.629 Kae= +0.800 Kae= +0.853 Kae= +0.907 Kae= +0.965 Kae= +1.024 Kae= +1.086 Kae= +1.151 Kae= +1.218
Friction A Buoyant We Height of Beta (Degr Inclinatio Delta (Deg FIb (Degre	ngle (Degree) ight of Backfill Retaining Wall ee) n (Degree) ree) e)	 27 89.6 80.4 0 26.5 13.5 30 		
accel=+0.000 accel=+0.050 accel=+0.150 accel=+0.200 accel=+0.250 accel=+0.300 accel=+0.350 accel=+0.400	Q(last) = +202.4 Q(last) = +233.9 Q(last) = +246.9 Q(last) = +259.0 Q(last) = +270.2 Q(last) = +280.2 Q(last) = +289.2 Q(last) = +297.0 Q(last) = +303.7	Angle= +32.9 Angle= +26.9 Angle= +24.1 Angle= +21.3 Angle= +18.5 Angle= +15.8 Angle= +13.1 Angle= +10.5 Angle= +8.0	FS = +1.484 $FS = +1.181$ $FS = +1.035$ $FS = +0.921$ $FS = +0.692$ $FS = +0.692$ $FS = +0.639$ $FS = +0.594$	Kae= +0.699 Kae= +0.610 Kae= +0.861 Kae= +0.915 Kae= +0.970 Kae= +1.028 Kae= +1.088 Kae= +1.216

MONONOBE - OKABE . EARTH PRESSURE DURING EARTHQUAKE ÷ Retaining Wall B (Section C-C) RD=J.1416/1801 'converts degrees to radians 'angle of internal friction FI=43*RD soilwtb=89.6 'buoyant unit weight of backfill soilwtt=152 'total weight of backfill 'total weight of backfill 'height of retaining wall 'angle of inclination of back of wall to vertical 'angle of inclination of backfill 'angle of friction between backfill and wall 'friction angle between bottom of wall and ground H=55 BETA=33*RD i=25.5*RD delta=FI/2 FIb=30*RD input "to where (i.e. CON, LPT1, LPT2, PRN or DOS file name;";10.name\$
if io.name\$="" then io.name\$="CON" elseif io.name\$="L" or io.name\$="1" then io.name\$="LPT2" end if OPEN IO.name\$ FOR OUTPUT AS #2 OPEN IO.name\$ FOR OUTPUT AS \$2PRINT \$2, " Friction Angle (Degree)PRINT \$2, " Buoyant Weight of BackfillPRINT \$2, " Height of Retaining WallPRINT \$2, " Beta (Degree)PRINT \$2, " Inclination (Degree)PRINT \$2, " Delta (Degree)PRINT \$2, " FIb (Degree)PRINT \$2, " FIb (Degree)PRINT \$2, " FIb (Degree) = ";delta/RD locale 12,35:print "working" FOR kh= 0.0 TO 0.45 STEP .05 psy= ATN(kh) alphamin= (FI-psy)/RD IF i/RD>alphamin THEN i=RD*(alphamin-.1) 'insures imax not violated qlb= .5*H*H*soilwtb 'wedge weight buoyant -----QJ-COS (1-BETA) *COS (BETA) QJ-COS (1-BETA) *COS (psy) QLAST- -900001 Q2=COS (BETA) *COS (BETA) 'used to compute failure 'angle, alpha, and the wedge 'weight at failure FOR J= 0 TO 50 STEP .1 ALP= alphamin+J RAP=ALP*RD X1=SIN(RAP-1) X2=COS(BETA-RAP)*SIN(RAP-FI+psy) X3=COS(BETA+delta+FI-PAP) 04=X2/(X1+X3)Q=Q1b+Q3+Q4/Q2 1----al= fi-psy-beta 'constants used to compute a2= psy+beta+delta a3= fi+delta 'Kae a4= i-beta a5= fi-psy-i funcl= l+sqr((\$in(a3)*sin(a5)) / (cos(a4)*cos(a2)))
func2= funcl*func1 Kae= (cos(al)*cos(al)) / (cos(psy)*cos(beta)*cos(beta)*cos(a2)*func2 WTb= 219100! AX= BETA+delta 'bouyant weight of retaining wall/soil mass 'constant used to compute components of Pae Paeb= glb*kae FS= ((WTb+Paeb*SIN(AX)) *TAN(FIb)) / (WTb*kh+Paeb*COS(AX))) IF Q < QLAST THEN "accel=+#.### Q(last) =+#####.# en 'if sending output to ccel=";kh 'a printer, lets the S=";FS 'user know that the PRINT #2, USING ", if io.name\$<>"CON" then Angle=+###.# F locate 12,35:print "accel=";kh locate 13,35:print "FS=";FS end if 'program is functioning exit for end if QLAST= Q NEXT J NEXT kh END

84

,

Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	- 43 - 89.6 - 55 - 33 - 25.5 - 21.5 - 30	
accel=+0.000 Q(last) = +113.1 accel=+0.050 Q(last) = +128.5 accel=+0.100 Q(last) = +147.7 accel=+0.150 Q(last) = +172.7 accel=+0.200 Q(last) = +207.7 accel=+0.250 Q(last) = +264.0 accel=+0.300 Q(last) = +393.1 accel=+0.350 Q(last) = +548.4 accel=+0.400 Q(last) = +617.7	Angle= $+65.1$ $FS= +1.737$ Angle= $+60.5$ $FS= +1.516$ Angle= $+55.5$ $FS= +1.348$ Angle= $+50.2$ $FS= +1.216$ Angle= $+44.4$ $FS= +1.109$ Angle= $+38.1$ $FS= +1.018$ Angle= $+30.5$ $FS= +0.935$ Angle= $+25.1$ $FS= +0.888$ Angle= $+22.5$ $FS= +0.868$	Kae= +0.835 Kae= +0.951 Kae= +1.101 Kae= +1.303 Kae= +1.594 Kae= +2.069 Kae= +3.162 Kae= +4.542 Kae= +5.288
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	- 37.9 - 89.6 - 55 - 33 - 25.5 - 18.95 - 30	
accel=+0.000 Q(last) = +130.4 accel=+0.050 Q(last) = +149.7 accel=+0.150 Q(last) = +175.5 accel=+0.150 Q(last) = +214.5 accel=+0.200 Q(last) = +293.3 accel=+0.250 Q(last) = +398.2 accel=+0.300 Q(last) = +429.0 accel=+0.350 Q(last) = +464.7 accel=+0.400 Q(last) = +507.5	Angle= +59.0 FS= +1.495 Angle= +53.6 FS= +1.321 Angle= +47.7 FS= +1.181 Angle= +40.9 FS= +1.064 Angle= +32.5 FS= +0.954 Angle= +25.7 FS= +0.882 Angle= +22.9 FS= +0.855 Angle= +20.2 FS= +0.812 Angle= +17.6 FS= +0.811	Kae= +0.963 Kae= +1.107 Kae= +1.308 Kae= +2.251 Kae= +2.251 Kae= +3.450 Kae= +3.849 Kae= +4.344
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	 33.1 89.6 55 33 25.5 16.55 30 	
accel=+0.000 Q(last) = +152.4 accel=+0.050 Q(last) = +179.9 accel=+0.100 Q(last) = +227.3 accel=+0.150 Q(last) = +319.6 accel=+0.200 Q(last) = +336.9 accel=+0.250 Q(last) = +355.3 accel=+0.300 Q(last) = +375.4 accel=+0.350 Q(last) = +398.1 accel=+0.400 Q(last) = +424.3	Angle= +51.8 FS= +1.293 Angle= +44.9 FS= +1.146 Angle= +30.6 FS= +1.014 Angle= +26.7 FS= +0.898 Angle= +23.8 FS= +0.865 Angle= +21.0 FS= +0.836 Angle= +18.2 FS= +0.836 Angle= +15.5 FS= +0.787 Angle= +12.9 FS= +0.767	Kae= +1.125 Kae= +1.331 Kae= +1.694 Kae= +2.411 Kae= +2.585 Kae= +2.785 Kae= +3.020 Kae= +3.032 Kae= +3.632
Friction Angle (Degree) Bucyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) Flb (Degree)	- 29.9 - 89.6 - 55 - 33 - 25.5 - 14.95 - 30	
accel=+0.000 Q(last) = +173.6 accel=+0.050 Q(last) = +218.7 accel=+0.100 Q(last) = +218.8 accel=+0.150 Q(last) = +301.6 accel=+0.200 Q(last) = +314.6 accel=+0.250 Q(last) = +328.1 accel=+0.350 Q(last) = +342.6 accel=+0.350 Q(last) = +376.6	Angle= +45.4 FS= +1.164 Angle= +36.0 FS= +1.018 Angle= +26.5 FS= +0.903 Angle= +23.6 FS= +0.868 Angle= +20.7 FS= +0.837 Angle= +17.9 FS= +0.810 Angle= +15.1 FS= +0.784 Angle= +12.4 FS= +0.762 Angle= +9.8 FS= +0.741	Kae= +1.281 Kae= +1.617 Kae= +2.153 Kae= +2.275 Kae= +2.414 Kae= +2.756 Kae= +2.756 Kae= +3.223

Friction A Buoyant We Height of J Beta (Degre Inclination Delta (Degre FIb (Degree	ngle (Degree) ight of Backfill Retaining Wall ee) n (Degree) ree) e)	 27.8 89.6 55 33 25.5 13.9 30 		
accel=+0.000	O(last) = +194.7	Angle= +39.6	FS= +1.075	Kae= +1.437
accel=+0.005	O(last) = +199.6	Angle= +38.5	FS= +1.059	Kae= +1.473
accel=+0.010	O(last) = +205.1	Angle= +37.4	FS= +1.044	Kae= +1.513
acce1=+0.015	Q(last) = +211.2	Angle= +36.2	FS= +1.028	Kae= +1.559
accel=+0.020	O(last) = +218.2	Angle= +35.0	FS = +1.011	Kae= +1.611
acce1=+0.025	Q(last) = +226.4	Angle= +33.6	FS= +0.994	Kae= +1.672
acce1=+0.030	Q(last) = +236.6	Angle= +32.0	FS = +0.974	Kae= +1.748
acce1=+0.035	Q(last) = +250.6	Angle= +30.0	FS≈ +0.952	Kae= +1.852
acce1=+0.040	Q(last) = +282.2	Angle= +26.3	FS= +0.912	Kae= +2.086
acce1=+0.045	Q(last) = +267.6	Angle= +27.7	FS= +0.925	Kae= +1.979
acce1=+0.050	Q(last) = +268.7	Angle= +27.4	FS≈ +0.922	Kae= +1.987
accel=+0.055	Q(last) = +269.7	Angle= +27.2	FS= +0.918	Kae= +1.996
acce1=+0.060	Q(last) = +270.8	Angle= +26.8	FS≈ +0.914	Kae= +2.005
accel=+0.065	Q(last) = +271.8	Angle= +26.5	FS⇒ +0.910	Kae= +2.014
acce1=+0.070	Q(last) = +272.9	Angle= +25.2	FS≈ +0.906	Kae= +2.024
acce1=+0.075	Q(last) = +274.0	Angle= +25.9	13- +0.903	Kae= +2.033
acce1=+0.080	Q(last) = +275.0	Angle= +25.6	FS= +0.899	Kae= +2.042
accel=+0.085	Q(last) = +276.1	Angle= +25.3	FS= +0.895	Kae= +2.052
accel=+0.090	Q(last) = +277.1	Angle= +25.1	FS= +0.892	Kae= +2.061
accel=+0.095	Q(last) = +278.2	Angle= +24.8	FS= +0.888	Kae= +2.071

¢

. · .

```
MONONOBE - OKABE
EARTH PRESSURE DURING EARTHQUAKE
Retaining Wall B (Section C-C)
RD=3.1416/1801 'converts degrees to radians
FI=43*RD 'angle of internal friction
  soilwtb=89.6
                             'buoyant unit weight of backfill
                            'total weight of backfill
'height of retaining wall
'angle of inclination of back of wall to vertical
  soilwtt=152
  H=55
  BETA=0*RD
  i=25.5*RD
                            'angle of inclination of backfill
  delta=FI/2
                            'angle of friction between backfill and wall
                            'friction angle between bottom of wall and ground
  FIb=30*RD
        _____
  input "to where (i.e. CON, LPT1, LPT2, PRN or DOS file name;";IO.name$
if io.name$="" then
    io.name$="CON"
  elseif io.name$="L" or io.name$="1" then
    io.name$="LPT2"
  end if
  OPEN IO. name$ FOR OUTPUT AS #2
 OPEN 10.name:

PRINT #2, "

PRINT #2, "
                  Friction Angle (Degree)
Buoyant Weight of Backfill
                                                       = ":FI/RD
                                                       = ";soilwtb
= ";H
                   Height of Retaining Wall
                                                       = ";BETA/RD
= ";1/RD
                   Beta (Degree)
                   Inclination (Degree)
                                                       = ";delta/RD
                   Delta (Degree)
                                                       = ";FIb/RD
                  FIb (Degree)
 locate 12,35:print "working"
FOR kh= 0.0 TO 0.45 STEP .05
 psy= ATN(kh)
 alphamin= (FI-psy)/RD
 IF i/RD>alphamin THEN i=RD*(alphamin-.1) 'insures imax not violated
 qlb= .5*H*H*soilwtb
                                                       'wedge weight buoyant
                                                                                  ----
 Q2=COS(BETA) *COS(BETA)
Q3=COS(i-BETA) *COS(psy)
QLAST= -900001
                                             'used to compute failure
                                             'angle, alpha, and the wedge
'weight at failure
   FOR J= 0 TO 50 STEP .1
    ALP= alphamin+J
 PAP=ALP+RD
 X1=SIN(RAP-1)
 X2=COS (BETA-RAP) *SIN (PAP-FI+psy)
 X3=COS(BETA+delta+FI-RAP)
 Q4 = X2/(X1 + X3)
 0=016+03+04/02
 al= fi-psy-beta
                                'constants used to compute
 a2= psy+beta+delta
                                'Kae
 a3= fi+delta
 a4= i-beta
at i beca
a5= fi-pay-i
funcl= l+sqr( (sin(a3)*sin(a5)) / (cos(a4)*cos(a2)) )
 func2= func1*func1
 Kae= ( \cos(a1)*\cos(a1) ) / ( \cos(psy)*\cos(beta)*\cos(beta)*\cos(a2)*func2)
WTb= 219100!
                            'bouyant weight of retaining wall/soil mass
 AX= BETA+delta
                             'constant used to compute components of Pae
Paeb= glb*kae
FS= ( (WTb+Paeb*SIN(AX)) *TAN(FIb) ) / ( WTb*kh+Paeb*COS(AX) )
IF Q < QLAST THEN
                             "accel=+#.### Q(last) =+####.#
n 'if sending output to
cel=";kh 'a printer, lets the
=";FS 'user know that the
PRINT #2, USING
                                                                       Angle=+###.# F
if io.name$<>"CON" then
 locate 12,35:print "accel=";kh
locate 13,35:print "FS=";FS
   end if
                                             'program is functioning
 exit for
end if
QLAST= Q
NEXT J
NEXT kh
END
```

t

Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FID (Degree)	 43 89.6 55 0 25.5 21.5 30 	
accel=+0.000 Q(last) = +31.7 accel=+0.050 Q(last) = +37.3 accel=+0.100 Q(last) = +43.9 accel=+0.150 Q(last) = +51.9 accel=+0.200 Q(last) = +62.1 accel=+0.250 Q(last) = +76.4 accel=+0.300 Q(last) = +103.3 accel=+0.350 Q(last) = +129.0 accel=+0.400 Q(last) = +136.8	Angle= +60.1 FS= +4.521 Angle= +57.0 FS= +2.941 Angle= +53.7 FS= +2.152 Angle= +49.9 FS= +1.675 Angle= +45.4 FS= +1.349 Angle= +40.0 FS= +1.103 Angle= +21.1 FS= +0.882 Angle= +23.3 FS= +0.680	Kac= +0.234 Kac= +0.276 Kac= +0.327 Kac= +0.391 Kac= +0.476 Kac= +0.599 Kac= +0.831 Kac= +1.069 Kac= +1.171
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FID (Degree)	= 37.9 = 89.6 = 55 = 0 = 25.5 = 18.95 = 30	
accel=+0.000 Q(last) = +41.9 accel=+0.050 Q(last) = +49.4 accel=+0.100 Q(last) = +58.8 accel=+0.150 Q(last) = +71.6 accel=+0.200 Q(last) = +94.2 accel=+0.250 Q(last) = +120.4 accel=+0.350 Q(last) = +127.4 accel=+0.350 Q(last) = +134.1 accel=+0.400 Q(last) = +140.5	Angle= +55.2 $FS = +3.389$ Angle= +51.5 $FS = +2.350$ Angle= +47.1 $FS = +1.763$ Angle= +41.7 $FS = +1.373$ Angle= +33.8 $FS = +1.062$ Angle= +26.2 $FS = +0.856$ Angle= +20.9 $FS = +0.774$ Angle= +20.9 $FS = +0.706$ Angle= +18.4 $FS = +0.650$	Kae= +0.309 Kae= +0.365 Kae= +0.438 Kae= +0.540 Kae= +0.723 Kae= +0.944 Kae= +1.025 Kae= +1.111 Kae= +1.202
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	- 33.1 - 89.6 - 55 - 0 - 25.5 - 16.55 - 30	
accel=+0.000 Q(last) = +55.1 accel=+0.050 Q(last) = +66.2 accel=+0.100 Q(last) = +83.4 accel=+0.150 Q(last) = +113.1 accel=+0.200 Q(last) = +119.8 accel=+0.250 Q(last) = +126.0 accel=+0.300 Q(last) = +131.9 accel=+0.350 Q(last) = +137.3 accel=+0.400 Q(last) = +142.2	Angle= +49.4 FS= +2.565 Angle= +44.3 FS= +1.842 Angle= +37.2 FS= +1.367 Angle= +27.1 FS= +1.012 Angle= +24.3 FS= +0.901 Angle= +21.6 FS= +0.811 Angle= +18.9 FS= +0.738 Angle= +16.3 FS= +0.677 Angle= +13.8 FS= +0.625	Kae= +0.407 Kae= +0.490 Kae= +0.622 Kae= +0.853 Kae= +0.919 Kae= +0.988 Kae= +1.061 Kae= +1.137 Kae= +1.217
Friction Angle (Degree) Buoyant Weight of Backfill Height of Retaining Wall Beta (Degree) Inclination (Degree) Delta (Degree) FIb (Degree)	= 29.9 = 89.6 = 55 = 0 = 25.5 = 14.95 = 30	
Accel=+0.000 Q(last) = +67.6 Accel=+0.050 Q(last) = +85.5 Accel=+0.100 Q(last) = +111.3 Accel=+0.150 Q(last) = +117.6 Accel=+0.200 Q(last) = +123.5 Accel=+0.250 Q(last) = +129.0 Accel=+0.350 Q(last) = +138.5 Accel=+0.400 Q(last) = +142.5	Angle= +44.2 FS= +2.092 Angle= +36.4 FS= +1.485 Angle= +26.9 FS= +1.097 Angle= +24.1 FS= +0.969 Angle= +21.3 FS= +0.867 Angle= +18.6 FS= +0.785 Angle= +15.9 FS= +0.717 Angle= +13.2 FS= +0.660 Angle= +10.7 FS= +0.611	Kae= +0.499 Kae= +0.633 Kae= +0.830 Kae= +0.887 Kae= +0.948 Kae= +1.012 Kae= +1.078 Kae= +1.220

ſ

.

Friction A Buoyant We Height of Beta (Degr Inclinatio Delta (Deg FID (Degre	ngle (Degree) ight of Backfill Retaining Wall ee) n (Degree) ree) e)	= 27.8 = 89.6 = 55 = 0 = 25.5 = 13.9 = 30		
accel=+0.000	Q(last) = +79.2	Angle= +39.3	FS= +1.789	Kae= +0.584
accel=+0.050	Q(last) = +108.2	Angle= +27.7	FS= +1.218	Kae= +0.800
accel=+0.100	Q(last) = +114.4	Angle= $+24.9$	FS= +1.063	Kae= +0.853
accel=+0.150	Q(last) = +120.3	Angle= +22.1	FS= +0.943	Kae= +0.907
accel=+0.200	Q(last) = +125.7	Angle= +19.3	FS= +0.847	Kae = +0.965
accel=+0.250	Q(last) = +130.6	Angle= +16.6	FS= +0.769	Kae= +1.024
accel=+0.300	Q(last) = +135.0	Angle= +13.9	FS= +0.704	Kae= +1.086
accel=+0.350	Q(last) = +138.9	Angle = +11.2	FS= +0.650	Kae= +1.151
accel=+0.400	Q(last) = +142.3	Angle= +8.7	FS= +0.603	Kae= +1.218

.