U.S. ARMY TEST AND EVALUATION COMMAND TEST OPERATIONS PROCEDURE

Test Operations Procedure (TOP) 1-2-501 AD No.

30 June 1995

V

odes

Avail and / or

Special

Dist

19950621 014

RAIL IMPACT TESTING

Dorograph	1	Pag	<u>e</u>
raragraph	т.	SCOPE	1
	2.	FACILITIES AND INSTRUMENTATION.	1
	3.	REQUIRED TEST CONDITIONS.	3
	4.	TEST PROCEDURES	1.
	/ 1	Rail Impact Toat	4
			4
	4.2	Temperature Conditioning	5
	4.3	Failure Definition.	6
	5.	DATA REQUIRED	6
	6.	DATA PRESENTATION	7
	••		/
Appendix	Α.	REFERENCES	1

1. <u>SCOPE</u>.

a. This TOP describes the techniques for the acquisition and analysis of rail impact data and procedures for conducting a rail impact test. It is used to verify the structural integrity of the test item and the adequacy of the tiedown system and the tiedown procedures. This TOP is intended for vehicles and equipment that will be transported by rail; to determine the effect of normal railroad car impacts that occur during rail shipment.

b. This TOP is not intended for the separate testing of small, individually- packaged pieces of equipment that would normally be shipped (and tested) when mounted on a pallet. It does not cover vibration induced by railcar movement.

- 2. FACILITIES AND INSTRUMENTATION.
- 2.1 Facilities.

<u>Item</u>

Straight level section of railroad track minimum of 200 m with additional track to be able to reverse the test railcar for impacting in the opposite direction

Locomotive or Inclined Ramp

Requirement

To provide distance to accelerate the test item car to the desired velocity

To accelerate the railcar with the test item to the desired pre-impact velocity

Approved for public release; distribution unlimited.

<u>Item</u>

Requirement

To transport the test item into the

To act as anvil (buffer) car(s)

into which the test item car is

anvil (buffer) car(s)

impacted

Railcar equipped with standard draft gear couplers and a conventional underframe (without cushioning)

Railcar(s) (1 to 5) with total weight of 114,000Kg minimum, equipped with standard draft gear couplers and a conventional underframe (without cushioning)

Temperature conditioningTo provide the required temperaturesource of chamber (ifenvironment for the test item

2.2 <u>Instrumentation</u>.

required)

Devices for Measuring	Measurement Accuracy
Rail impact speed (timers)	<u>+</u> 0.08 km/hr
Distance between speed timers (measuring tape)	<u>+</u> 3 mm
Locomotive speed (speedometer)	<u>+</u> 0.16 km/hr
Coupler Force (strain gaged coupler)	<u>+</u> 2.2 kN (500 1b _f)
Initial Cable Tension (cable tensiometer)	<u>+</u> 90 N (20 1b _f)
Tiedown Bolt Torque (torque wrench)	<u>+</u> 5% of reading
Acceleration (accelerometers) (if required)	<u>+</u> 0.05 g
Strain (strain gages) (if required)	<u>+</u> 5 microstrain
Temperature (thermocouples) (if required)	<u>+</u> 2°C
Optical Instruments (video, movie, and still cameras)	As required

3. <u>REQUIRED TEST CONDITIONS</u>.

3.1 <u>Test Planning</u>.

a. Review previous test reports of similar test items.

b. Acquire Military Traffic Management Command (MTMC), Army Materiel Command (AMC) or U.S. Army Defense Ammunition Center and School (USADACS) approved blocking and tie-down instructions.

c. Check applicable equipment publications for special transportability requirements. This may include the basic vehicle weight plus additional payload weight for equipment, ammunition, etc.

d. Satisfy the requirements of MIL-STD-209^{1*} for the lifting and tie-down provisions of the test item.

3.2 <u>Test Preparation</u>.

a. Verify the calibration of all speed measuring devices (locomotive and impact speed) and instrumented coupler.

b. Note any existing damage to the test item or railcars including damage to chains, linkages, binders, or other load-securing devices.

c. Ensure that the personnel operating the locomotive or inclined ramp have been properly trained.

d. Ensure that all items are tested at their maximum gross weight (fully loaded) rating unless otherwise specified in the transportability requirements.

e. Ensure that blocking and tie-down are in accordance with Military Traffic Management Command (MTMC), Army Materiel Command (AMC) or U.S. Army Defense Ammunition Center and School (USADACS) approved procedures^a. Load, block, brace, and tie down the test item on the railcar in accordance with procedures approved by MTMC, USADSCS and procedures found in the test item's technical manual or AMC drawings. Torque nuts on wire rope clips to their correct value. Torque cable clamps to 61 J (45 lb-ft) for 0.95-cm (3/8-in.) wire rope cable, 88 J (65 lb-ft) for 1.3-cm (1/2-in.) and 129 J (95 lb-ft) for 1.6-cm (5/8-in.) wire rope cable.

f. Substitute (dummy) loads must be of equal weight, weight distribution, and size as the actual load that it is replacing.

g. Place speed indicator instrumentation, to determine the speed of the loaded railcar at impact, in position and calibrate prior to test operation.

*Superscript numbers/letters correspond to those in Appendix A, references.

Position the instrumented coupler for coupling on the impacted end of the stationary car(s) to measure coupler force during impact. Position additional transducers such as accelerometers (in three mutually perpendicular axes), strain gages, thermocouples, etc. at select locations on the test item and railcar deck, if required. Attach a calibrated speedometer to the locomotive and use as a speed indicator for the locomotive engineer.

h. Prior to rail impact testing, take characteristic photographs to document the tie-down procedures. In addition, video coverage may be provided for each impact test.

3.3 <u>Test Controls</u>.

a. Observe all safety procedures in accordance with the Safety Assessment Report (SAR), and facility safety regulations.

b. Conduct the test only when rails are dry to minimize variability due to sliding (acceptable conditions to be determined by rail impact test director, Military Traffic Management Command representative and locomotive engineer).

4. <u>TEST PROCEDURES</u>.

4.1 Rail Impact Test.

a. Accomplish the rail impact by securing the test item on a railcar and propelling the car, by means of a locomotive (or by inclined ramp), into one to five stationary anvil (buffer) cars. Measure actual impact speeds by determining the speed of the loaded railcar immediately prior to impact.

b. Position the stationary railcar(s) with their couplers compressed and their air and hand brakes set. Position the knuckles of the anvil and test cars for coupling.

c. Subject the moving railcar to impacts at speeds of 6.4 and 9.6 km/hr (4 and 6 mph) ± 5 % and 12.9 km/hr (8 mph) + 5 % / - 0 %. (If the speed is below 12.9 km/hr, repeat the impact.) Conduct the impact by accelerating the railcar to the desired speed using either a locomotive equipped with a speed-measuring device or inclined ramp. Release the railcar loaded with the test item approximately 15 m from the stationary anvil (buffer) railcars and allow to coast until it impacts.

d. Turn the railcar with the test item and repeat the test at 12.9 km/hr + 5 % / - 0 % for a total of four impacts.

e. At the conclusion of each impact, inspect the test item and its blocking and bracing for evidence of possible failure of the tie-down devices and transported test item for equipment damage. Take photographs of the extent of damage as needed. Once the test has started, there will be no

readjustment of the test item nor any reconditioning of the bracing, chock material, or tie-down cables. If the initial blocking and tie-down devices fail, repeat the entire test provided a revised method of securing is feasible and approved by MTMC, AMC or USADACS. At the completion of the test, examine the test item for any permanent displacement or damage and conduct a functional and operational checkout test. Conduct a visual examination of the test item and compare the results with the pretest data.

f. If the test item can be transported in more than one orientation (such as lengthwise and crosswise on the railcar), repeat the four impacts for each orientation.

g. Based on individual systems specifications, higher test speeds may be necessary in order to attain a higher level of confidence in the test item's ability to survive railcar impacting. Conduct the higher speed impacts after successful completion of the two 12.9-km/hr (8-mph) impacts listed above. Conduct these impacts at each higher speed once in each direction prior to proceeding to the next higher speed. Conduct a performance check to establish baseline data prior to proceeding to higher speeds.

4.2 <u>Temperature Conditioning</u>.

a. If the rail impact test is to be conducted at temperature extremes, prior to impacting:

(1) Secure the test item on the railcar and place the test item in the temperature chamber/enclosure and adjust the chamber air temperature to the test temperature. The temperature chamber/source should be located as close to the rail impact site as possible for best efficiency.

(2) Following temperature stabilization of the test item, maintain the storage temperature for a period as specified in the test plan before rail impact testing.

NOTE: Temperature stabilization is attained when the temperature of the operating part of the test item considered to have the longest thermal lag is changing no more than 2°C per hour.

(3) Disconnect the temperature conditioning chamber/source, if employed and perform the rail impact test as stated in paragraph 4.1.

If the test item is considered by itself in a temperature chamber rather than on the railcar, after the conditioned item is mounted on the railcar:

(1) Replace the test item in the temperature chamber and adjust chamber air temperature to the test temperature.

(2) Following temperature stabilization of the test item, maintain the storage temperature for a minimum of twice the amount of time that the

test item has been out of the temperature chamber.

(3) Perform the rail impact test as stated in paragraph 4.1.

b. If the test item remains outside the conditioning chamber for more than 15 minutes then reconditioning is required. If more impacts are required after 15 minutes, the test item shall be reconditioned for 30 minutes after the test item has stabilized at the required test temperature.

4.3 Failure Definition.

A test item shall be classified as not having survived the rail impact test and will be considered a failure if any item that is attached to or included as an integral part of the test item breaks free, loosens or shows any sign of permanent deformation beyond specification tolerances.

5. <u>DATA_REQUIRED</u>.

5.1 Rail Impact Test.

a. Documentation of the blocking and tie-down devices used to secure the test item (photos, drawings, materials list, etc.).

b. Description of existing damage on test item or railcars.

c. Description of the railcar including maximum coupler travel.

d. Description of test item including weight and dimensions and general location on test car.

e. Direction of the impact (define forward end of test item).

f. Impact speed.

g. Force imparted on the impacted coupler of the stationary railcars.

h. Results of examination and operational checkout tests.

i. If necessary, transducer measurements (i.e., acceleration, temperature, strain, etc.) of various locations on the test item and railcar.

j. Effects on the test item, blocking and tie-down devices including deficiencies, shortcomings, or limitations observed during rail impacting.

6. DATA PRESENTATION.

a. Prepare photographs and/or sketches of blocking and tie-down configuration.

b. Prepare graph of peak coupler force versus actual impact speed.

c. Prepare photographs of setup, instrumentation, and any damaged components.

d. If required, compile tables of peak acceleration levels and/or plots of time versus acceleration for each impact.

e. If required, present video documentation of actual impacts.

f. Prepare any pertinent graphs to represent other transducer measurements, if required (i.e., strain versus time, temperature recordings, etc.).

APPENDIX A. REFERENCES

1. MIL-STD-209H, Military Standard, Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment, 29 June 1991.

•

REFERENCES FOR INFORMATION ONLY

a. Association of American Railroads, "General Rules Governing the Loading of Commodities on Open Top Cars", updated yearly.

> Recommended changes of this publication should be forwarded to Commander, U.S. Army Test and Evaluation Command, ATTN: AMSTE-CT-T, Aberdeen Proving Ground, MD 21005-5055. Technical information may be obtained from the preparing activity: Commander, U.S. Army Aberdeen Test Center, ATTN: STEAC-AC-I, Aberdeen Proving Ground, MD 21005-5059. Additional copies are available from the Defense Technical Information Center, Cameron Station, Alexandria, VA 22304-6145. This document is identified by the accession number (AD No.) printed on the first page.

REPORT DOCI	JMENTATION P	eronenense er nære unerse konner andere er vangerner og verkener i helde. Neder som	Form Approved OMB No. 0704-0188
Public reporting burden for this collection of informatic pathering and maintaining the data needed, and compl ollection of information, including suggestions for red bayls Hidhway, Suite 1204, Arifington, VA 222024302; a	In is estimated to average 1 hour per eting and reviewing the collection of i ucing this burden, to Washington Hea and to the Office of Management and	response, including the time for re nformation Send comments rega dquarters Services, Directorate for Budget, Paperwork Reduction Proj	wewing instructions, searching existing data sour rding this burden estimate or any other aspect of 1 Information Operations and Reports, 1215 Jeffer ect (0704-0188), Washington, DC 20503.
AGENCY USE ONLY (Leave blank)	2. REPORT DATE 30 Jun 1995	3. REPORT TYPE AN	D DATES COVERED
TITLE AND SUBTITLE	ng na taning ng pangang ang pangang na kang na Na kang na kang	an a	5. FUNDING NUMBERS
Test Operations Procedure 1-2-501 Rail Impact Testi	(TOP) ng		WU A268445
. AUTHOR(S)	ganta rene padram na faranza da serena da	agan manan kan kan kan kan kan kan kan kan kan	
, PERFORMING ORGANIZATION NAME() AND ADDRESS(ES)	יינגע אינגע אינ אינגע אינגע אינ	8. PERFORMING ORGANIZATION
Commander			REPORT NUMBER
U.S. Army Aberdeen Test C	enter		TOP 1-2-501
Alin: Silac-AC-I Aberdeen Proving Ground,	MD 21005-5059		
SPONSORING / MONITORING AGENCY	NAME(S) AND ADDRESS(ES		10. SPONSORING / MONITORING AGENCY REPORT NUMBER
Commander U.S. Army Test and Evalua	tion Command		Same as Item 8
ATTN: AMSTE-CT-T Aberdeen Proving Ground,	MD 21005-5055		
1. SUPPLEMENTARY NOTES	an ann an an ann an aird a' channa mhar aird an an ann ann ann ann ann ann ann ann	<u></u>	איז
Defense Technical Informa	tion Center (DTIC)), AD NO: A	
DECTRIDUTION / AMANADUTTY CTAT	TACN'T	an a	12h DISTRIBUTION CODE
Approved for public relea	se;		
distribution unlimited.	,		
3. ABSTRACT (Maximum 200 words)	ਗ਼ਗ਼ਖ਼ਫ਼ਗ਼੶ਖ਼੶ਖ਼੶ਖ਼੶ੑੑਗ਼੶ਗ਼੶ਖ਼੶ਫ਼੶ਸ਼ਫ਼੶ਗ਼ਖ਼ਜ਼ਗ਼੶ਖ਼ਫ਼੶ਗ਼ਖ਼ਫ਼ਗ਼ਗ਼੶ਖ਼ਫ਼੶ਗ਼੶ਖ਼ੑਖ਼ <u>ਗ਼</u> ੶ਗ਼੶ਜ਼੶ਫ਼ਗ਼ਜ਼ਗ਼੶	na fra anna ann an an an an ann ann ann ann	an a
This TOP describes the te	chniques for the a	equisition and a model of the second se	analysis of rail impact
uata and procedures for e		impace coot.	
	DIIC LECTE UN 2 3 1995		
		DTIC	QUALITY INSPECTED 5
4. SUBJECT TERMS	₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩	ਗ਼ਖ਼ਖ਼੶ਲ਼ਫ਼ਗ਼ਖ਼ਫ਼ਖ਼ਖ਼੶ਖ਼ਫ਼ਲ਼ਗ਼ਫ਼ਖ਼ਫ਼ਗ਼੶ਖ਼ਖ਼੶ਫ਼ਗ਼੶ਫ਼ਖ਼੶ਫ਼ਖ਼੶ਫ਼ਖ਼੶ਫ਼ਖ਼੶ਖ਼ਫ਼ਖ਼ਖ਼ਖ਼ਫ਼ਖ਼ਖ਼ਫ਼ਖ਼ਖ਼ਫ਼ਖ਼ਖ਼ਫ਼ਖ਼ਖ਼ਖ਼ਖ਼ਖ਼ਖ਼ਖ਼ਖ਼	15. NUMBER OF PAGES
Rail impact Blocking Couplers Transportab	ility		16. PRICE CODE
Tie-downs Anvil car 7. SECURITY CLASSIFICATION 18. 5 CE REPORT 18. 5	ECURITY CLASSIFICATION	19. SECURITY CLASSIFI OF ABSTRACT	CATION 20. LIMITATION OF ABSTR
UNCLASSIFIED			SAR
SN 7540-01-280-5500	n an		Standard Form 298 (Rev. 2-8)

•