


AL/EQ-TR-1996-0040



**UNITED STATES AIR FORCE
ARMSTRONG LABORATORY**

**Demonstration of Radiofrequency Soil
Decontamination: Volume I**

Clifton F. Blanchard, Chesley R. Lyon,
and Laura H. Whitt

Halliburton NUS Environmental Corporation
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37830

October 1996

19970714 094

Approved for public release; distribution is unlimited.

Envionics Directorate
Environmental Risk
Management Division
139 Barnes Drive
Tyndall Air Force Base FL
32403-5323


NOTICES

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any employees, nor any of their contractors, subcontractors, or their employees, make any warranty, expressed or implied, or assume any legal liability or responsibility for the accuracy, completeness, or usefulness of any privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency, contractor, or subcontractor thereof. The views and opinions of the authors expressed herein do not necessarily state or reflect those of the United States Government or any agency, contractor, or subcontractor thereof.

When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely Government-related procurement, the United States Government incurs no responsibility or any obligation whatsoever. The fact that the Government may have formulated or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication, or otherwise in any manner construed, as licensing the holder or any other person or corporation; or as conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

This technical report has been reviewed by the Public Affairs Office (PA) and is releasable to the National Technical Information Service (NTIS) where it will be available to the general public, including foreign nationals.

This report has been reviewed and is approved for publication.


JEFFREY A. STINSON, Capt, USAF, BSC
Project Officer


ALLAN M. WEINER, Lt Col, USAF
Chief, Site Remediation Division

transl

DRAFT SF 298

| | | | | |
|---|---------------------------|--|--|----------------|
| 1. Report Date (dd-mm-yy) August 1996 | 2. Report Type Final | 3. Dates covered (from... to) June 1992 to December 1994 | | |
| Title & subtitle demonstration of Radio Frequency Soil Decontamination: Vol I, Technical Evaluation Report (Vol I of III) | | 5a. Contract or Grant # F33615-90-D-4011 | | |
| | | 5b. Program Element # 78008F | | |
| 6. Author(s) Clifton F. Blanchard, Chesley R. Lyon, and Laura H. Whitt | | 5c. Project # 3788 | | |
| | | 5d. Task # | | |
| | | 5e. Work Unit # 3073 | | |
| 7. Performing Organization Name & Address Halliburton NUS Environmental Corporation 800 Oak Ridge Turnpike Oak Ridge, Tennessee 37830 | | 8. Performing Organization Report # | | |
| 9. Sponsoring/Monitoring Agency Name & Address Armstrong Laboratory Environics Directorate Site Remediation Division 139 Barnes Drive, Suite 2 Tyndall Air Force Base, FL 32403-5323 | | 10. Monitor Acronym USAF | | |
| | | 11. Monitor Report # AL/EQ-TR-1996-0040 | | |
| 12. Distribution/Availability Statement Approved for public release. Distribution unlimited. | | | | |
| 13. Supplementary Notes | | | | |
| 14. Abstract The Air Force Armstrong Laboratory, Tyndall Air Force Base, Florida, has supported the research and development of Radio Frequency Soil Decontamination. Radio frequency soil decontamination is essentially a heat-assisted soil vapor extraction process. Site S-1 at Kelly Air Force Base, Texas, was selected for the demonstration of two patented techniques. The site is a former sump that collected spills and surface runoff from a waste petroleum, oils, and lubricants and solvent storage and transfer area. In 1993, a technique developed by the ITT Research Institute using an array of electrodes placed in the soil was demonstrated. In 1994, a technique developed by KAI Technologies, Inc. using a single applicator placed in a vertical borehole was demonstrated. Approximately 120 tons of soil were heated during each demonstration to a temperature of about 150 degrees Celsius. | | | | |
| 15. Subject Terms Radio Frequency Soil Heating, Soil Vapor Extraction | | | | |
| Security Classification of | | | 19. Limitation of Abstract | 20. # of Pages |
| 16. Report classified | 17. Abstract Unclassified | 18. This Page Unclassified | Unlimited | 137 |
| | | | 21. Responsible Person (Name and Telephone #) Capt Jeffrey A. Stinson (904) 283-6254 | |

PREFACE

This report was prepared by Halliburton NUS Environmental Corporation, 800 Oak Ridge Turnpike, Oak Ridge, TN 37830 under contract F33615-90-D-4011 for the Armstrong Laboratory Environics Directorate (AL/EQW) (formerly the Air Force Engineering and Services Center), Tyndall AFB, FL 32403-5323.

This final report summarizes the project's Phase I efforts for a field demonstration of the IIT Research Institute's (IITRI) tri-plate capacitor and the KAI Technologies, Inc.'s (KAI) antenna radio frequency heating (RFH) techniques for the enhancement of soil vapor extraction (SVE) for the in situ decontamination of soils.

The work was performed between June 1992 and December 1994. The AL/EQW technical project officers were Mr. Paul F. Carpenter (during the initial stage of the project) and Capt Jeffrey A. Stinson (during the latter stage of the project).

EXECUTIVE SUMMARY

The United States Air Force developed the Installation Restoration Program to assess past hazardous waste disposal and spill sites and prepare remedial actions consistent with the National Contingency Plan for those sites that pose a threat to human health or the environment. Within that program the Site Remediation Division of the Environics Directorate of the Air Force's Armstrong Laboratory at Tyndall AFB, Florida, has supported the research and development of Radio Frequency Soil Decontamination.

Armstrong Laboratory was sufficiently encouraged by the early test results in sandy soils at Tyndall AFB, Florida, and Volk Field, Wisconsin, to pursue larger-scale demonstrations in tight soils that are more difficult to treat. In September 1991, the Air Force Center for Environmental Excellence at Brooks AFB, Texas, contracted Halliburton NUS Environmental Corporation (now Brown & Root Environmental) to conduct pilot scale demonstrations of two different, patented, radio frequency heating techniques at Site S-1 at Kelly AFB, Texas.

The project was divided into three phases the Preplanning Phase, Phase I, and Phase II. The Preplanning Phase, completed in September 1992, included literature review, conceptual cost estimations, design plans and specifications preparation and review, and publication of a final report documenting the results. Phase I included two integrated pilot tests and the preparation of this final technical report evaluating the results of Phase I and the conceptual planning of Phase II. Phase II will include the complete planning and design of a full-scale commercial demonstration of radio frequency soil decontamination.

Radio frequency soil decontamination is essentially a heat-assisted vapor extraction process. Radio frequency energy applied to the soil causes polar molecules, including water and many organic compounds, to vibrate. This vibrational energy is lost as heat. The resulting rise in soil temperature vaporizes both water and contaminants, which may then be removed by application of a vacuum. Extracted vapors may be treated by a variety of methods, depending on the site and the nature of the contaminants. Vapors extracted during the demonstrations at Site S-1 were burned in a flare.

Two types of radio frequency soil heating were demonstrated at Site S-1 from January to August 1993 and 1994. In 1993, a technique developed by the IIT Research Institute that uses a series of exciter and ground electrodes placed in the soil was demonstrated. This technique was tested previously at Air Force sites. In 1994, a technique developed by KAI Technologies, Inc. which uses

an antenna-like device that may be placed in a vertical or horizontal borehole was demonstrated. Halliburton NUS Environmental Corporation provided site preparation services, the vapor extraction system, and supervised and coordinated all other aspects of the demonstrations.

Armstrong Laboratory, Kelly AFB, and the US Department of Energy have contributed funds and guidance for the work completed to date which includes the Preplanning Phase and Phase I. In addition, the Phase I demonstrations are part of the US Environmental Protection Agency's Superfund Innovative Technology Evaluation Program.

Halliburton NUS Environmental Corporation concludes that data gathered during the pilot demonstrations is invaluable to the development of radio frequency heating for the enhancement of soil vapor extraction and can be used to design a commercial scale system and implement remedial activities in accordance with United States Air Force procedures. From lessons learned during the Site S-1 demonstrations, criteria for technology implementation have become apparent that allow the selection of a site better suited to the unique physical and chemical phenomenon inherent in the process. To date only six field tests have been completed. These tests have addressed situations with a wide variance of soil and contaminant characteristics. A phased approach is recommended which would include more demonstrations to plug data gaps and define unknowns followed by commercial scale application. A smaller site with a simpler (more homogenous) soil and contaminant matrix, relative to Site S-1, would simplify the evaluation of results and better define technology applicability.

Table of Contents

| Section | Title | Page |
|---------|---|------|
| I. | INTRODUCTION | 1 |
| A. | BACKGROUND | 1 |
| B. | SITE HISTORY | 2 |
| C. | PROJECT BACKGROUND | 2 |
| II. | DEMONSTRATION OBJECTIVES | 4 |
| III. | SITE DESCRIPTION | 6 |
| A. | REGIONAL SETTING | 6 |
| 1. | Geography | 6 |
| 2. | Geology | 6 |
| 3. | Hydrology | 6 |
| B. | SITE S-1 | 7 |
| 1. | Location | 7 |
| 2. | Site History | 7 |
| 3. | Topography and Drainage | 7 |
| 4. | Geology | 7 |
| 5. | Hydrology | 9 |
| 6. | Levels and Extent of Contamination | 9 |
| IV | TECHNOLOGY DESCRIPTION | 13 |
| A. | PROCESS DESCRIPTION | 13 |
| B. | ENERGY REQUIREMENTS | 19 |
| V. | SYSTEM DESIGN AND INSTALLATION | 22 |
| A. | TREATABILITY OF S-1 SOIL FOR THE REMOVAL OF DIESEL RANGE ORGANICS | 22 |
| 1. | SOIL SAMPLE DESCRIPTION | 22 |
| 2. | Treatability Study Objectives and Approach | 22 |
| 3. | Experimental Apparatus | 25 |
| 4. | Experimental Procedure | 27 |
| 5. | Experimental Results and Conclusions | 28 |
| B. | HEATING SYSTEM DESIGN | 31 |
| 1. | Design Heated Volume | 31 |
| 2. | Estimate of Heating Time | 33 |
| 3. | System Design Overview | 33 |
| 4. | Electrode Array Design | 36 |
| 5. | RF Shield | 41 |
| 6. | Vapor and Gas Collection Lines | 41 |
| 7. | Temperature Instrumentation | 41 |
| VI. | DEMONSTRATION OPERATION | 51 |
| A. | SYSTEM START UP | 51 |
| B. | CHRONOLOGY OF EVENTS | 51 |

| | | |
|-------|---|-----|
| C. | DATA RECORDED AND PARAMETERS MONITORED | 52 |
| 1. | RF Power Delivery System: | 52 |
| 2. | Soil Temperature Data | 53 |
| 3. | Vapor Collection and Treatment System | 53 |
| VII. | DEMONSTRATION TEST DATA | 55 |
| A. | SOIL TEMPERATURE DATA | 55 |
| 1. | Summary | 55 |
| 2. | Excitor Row Temperatures | 59 |
| 3. | Ground Row Temperatures | 59 |
| 4. | Thermowell Temperatures | 59 |
| 5. | Temperature Outside the Array | 63 |
| 6. | Temperature During Cool Down | 63 |
| 7. | Spatial Temperature Distributions | 63 |
| B. | ANALYSIS OF SOIL FOR TOTAL PETROLEUM HYDROCARBONS | 68 |
| 1. | Pre-Demonstration Soil Samples | 68 |
| 2. | Post-Demonstration Soil Samples | 75 |
| 3. | Removal of TPH | 80 |
| C. | TRACER INJECTION EXPERIMENT | 86 |
| 1.. | Materials and Equipment | 86 |
| 2. | Procedure for Performing the Tracer Experiment | 87 |
| 3. | Trace Injection Results | 89 |
| D. | ELECTRICAL DATA | 91 |
| 1. | RF System Performance | 91 |
| 2. | RF Emissions Monitoring | 95 |
| VIII. | CONCLUSIONS | 100 |
| A. | TPH REMOVAL | 100 |
| B. | SOIL TEMPERATURE RISE | 101 |
| C. | OPERATION OF THE RF HEATING SYSTEM | 102 |
| IX. | RECOMMENDATIONS | 103 |
| X. | REFERENCES | 105 |

APPENDIXTITLE

| | | |
|---|--|-----|
| A | SUMMARY OF LOG BOOK ENTRIES FOR RF HEATING | 105 |
| B | SOIL TEMPERATURE DATA | 111 |
| C | ELECTRICAL DATA | 174 |
| D | OPERATING DATA | 198 |
| E | PARTICLE SIZE DISTRIBUTION | 213 |
| F | SOIL VAPOR ANALYTICAL SUMMARY | 218 |
| G | DEWATERING SYSTEM | 220 |
| H | SEMI VOLATILE ORGANICS | 226 |
| I | BASE/NEUTRAL/ACID EXTRACTABLES | 232 |
| J | TCLP ANALYSIS | 237 |
| K | COST SUMMARY | 246 |

List of Figures

| Figure | Title | Page |
|--------|--|------|
| 1 | Location Map for Site S-1 | 3 |
| 2 | Site S-1 | 8 |
| 3 | Artist's Illustration of the RF Process | 14 |
| 4 | Conceptual Block Diagram of the RF Process | 16 |
| 5 | Soil Permeability as a Function of Pore Saturation | 18 |
| 6 | Soil Treatability Experimental Set Up | 26 |
| 7 | Surface-Level Plan View of the Array | 32 |
| 8 | Conceptual Layout of the Demonstration System | 34 |
| 9 | Vertical Sections AA, BB, CC of Electrode Array | 36 |
| 10 | Transverse Section DD of the Array Near Soil Surface | 39 |
| 11 | Typical Section EE: Electrode Interconnection in Ground Rows A and C | 40 |
| 12 | RF Shield | 41 |
| 13 | Vapor Collection Manifold | 43 |
| 14 | Thermocouple Locations in Plane AA | 45 |
| 15 | Thermocouple Locations Plane BB | 46 |
| 16 | Thermocouple Locations in Plane CC | 47 |
| 17 | Typical Thermocouples Installation Within Electrodes | 48 |
| 18 | Surface-Level Plan View of the Array, Electrode and Thermowell Locations | 49 |
| 19 | Electrode Hole and Thermowell Layout | 56 |
| 20 | Average Temperature in the Array | 57 |
| 21 | Excitor Row Average Temperature | 60 |
| 22 | Ground Rows Average Temperature | 61 |
| 23 | Average Thermowell Temperature vs. Time | 62 |
| 24 | Outside Thermowell (TW7) Temperatures | 64 |
| 25 | Ground Rows Average Temperature (Since 12:00 hr., June 3, 1993) | 65 |
| 26 | Definition of Vertical Planes for Temperature Distribution | 66 |
| 27 | Transverse Temperature Distribution in Plane TRANS (Depth: 1 ft) | 67 |
| 28 | Transverse Temperature Distribution in Plane TRANS (Depth: 10-12 ft) | 69 |
| 29 | Transverse Temperature Distribution in Plane TRANS (Depth: 20-24 ft) | 70 |
| 30 | Pre and Post Demonstration TPH Concentration in Electrode Row A as a Function of Depth | 83 |
| 31 | Pre- and Post-Demonstration TPH Concentration in Electrode Row B as a Function of Depth | 84 |

List of Figures

| Figure | Title | Page |
|--------|---|------|
| 32 | Pre- and Post-Demonstration TPH Concentration in Electrode Row C as a Function of Depth | 85 |
| 33 | Gas Sampling Scheme for the Tracer Experiment | 88 |
| 34 | Input Power Level Vs Time | 92 |
| 35 | Cumulative RF Energy Vs Time | 93 |
| 36 | RF Power Source Utilization Vs. Time (Percent of Capacity) | 94 |
| 37 | Kelly AFB; Site S-1 Array Input Impedance Tracking | 96 |
| 38 | Kelly AFB; Site S-1 Array Input Impedance Tracking | 97 |

List of Figures

| Number | Title | Page |
|--------|---|------|
| B-1 | Surface-Level Plan View of the Array Showing Electrode and Thermowell Locations | B-2 |
| B-2 | Excitor Electrode B1 Temperature | B-32 |
| B-3 | Excitor Electrode B2 Temperature | B-33 |
| B-4 | Excitor Electrode B3 Temperature | B-34 |
| B-5 | Excitor Electrode B4 Temperature | B-35 |
| B-6 | Ground Row A Temperatures (1-ft Depth) | B-36 |
| B-7 | Ground Row A Temperatures (12-ft Depth) | B-37 |
| B-8 | Ground Row A Temperatures (24-ft Depth) | B-38 |
| B-9 | Ground Row A Temperatures (29-ft Depth) | B-39 |
| B-10 | Ground Row C Temperatures (1-ft Depth) | B-40 |
| B-11 | Ground Row C Temperatures (12-ft Depth) | B-41 |
| B-12 | Ground Row C Temperatures (24-ft Depth) | B-42 |
| B-13 | Ground Row C Temperatures (29-ft Depth) | B-43 |
| B-14 | Thermowell Temperature vs. Time (1-ft Depth) | B-44 |
| B-15 | Thermowell Temperature vs. Time (12-ft Depth) | B-45 |
| B-16 | Thermowell Temperature vs. Time (24-ft Depth) | B-46 |
| B-17 | Temperature Outside the Heated Array (Depth 12 ft) | B-47 |
| B-18 | Temperature Outside the Heated Array (Depth 24 ft) | B-48 |
| B-19 | Temperature Outside the Heated Array (Depth 29 ft) | B-49 |
| B-20 | Longitudinal Temperature Distribution in Plane LONG (Depth 1 ft) | B-50 |
| B-21 | Longitudinal Temperature Distribution in Plane LONG (Depth 10-12 ft) | B-51 |
| B-22 | Longitudinal Temperature Distribution in Plane LONG (Depth 20-24 ft) | B-52 |
| B-23 | Longitudinal Temperature Distribution in Plane LNGU (Depth 1 ft) | B-53 |
| B-24 | Longitudinal Temperature Distribution in Plane LNGU (Depth 12 ft) | B-54 |
| B-25 | Longitudinal Temperature Distribution in Plane LNGU (Depth 24 ft) | B-55 |
| B-26 | Transverse Temperature Distribution in Plane TRNV (Depth 1 ft) | B-56 |
| B-27 | Transverse Temperature Distribution in Plane TRNV (Depth 12 ft) | B-57 |
| B-28 | Transverse Temperature Distribution in Plane TRNV (Depth 24 ft) | B-58 |
| B-29 | Transverse Temperature Distribution in Plane TRNS (Depth 1 ft) | B-59 |
| B-30 | Transverse Temperature distribution in Plane TRNS (Depth 10-12 ft) | B-60 |

List of Tables

| Table | Title | Page |
|-------|---|------|
| 1 | Organic Compounds Detected in Soils, Site S-1, Kelly AFB, Texas | 11 |
| 2 | Boiling Point Reduction | 19 |
| 3 | Theoretical Energy Required to Heat Soil to 150°C | 21 |
| 4 | Field Screening and Lab. Analysis of Core Samples Obtained on 10-19-94, site S-1, Kelly AFB | 23 |
| 5 | Concentration ($\mu\text{g}/\text{kg}$) of Semi-Volatiles in Borings SB-16 to SB-18 | 24 |
| 6 | Soil Treatability Experimental Conditions and Results | 29 |
| 7 | Calculation of TPH Removal During Treatability Study | 30 |
| 8 | Electrode Array Dimensions--Designed vs. Implemented | 38 |
| 9 | Thermocouple Distribution Inside Electrodes | 42 |
| 10 | Chronology of Selected Events | 52 |
| 11 | Determination of Moisture in Pre-Demonstration Soil Samples | 71 |
| 12 | Determination of TPH in Pre-Demonstration Soil Samples | 72 |
| 13 | Determination of TPH in Pre-Demonstration Soil Samples--QA/QC Samples | 74 |
| 14 | Spike Recovery | 76 |
| 15 | Results of Duplicate Analysis | 77 |
| 16 | Post Demonstration Soil Analysis for TPH By California Method and Moisture by Weight Loss in Oven | 78 |
| 17 | Summary of TPH Analysis Done at IITRI, ppm | 81 |
| 18 | Results of Tracer Injection Experiment | 90 |
| 19 | RFI Safety Measurements Near/Far-Field | 99 |
| A-1 | Summary of Logbook Entries | A-2 |
| B-1 | Ground Electrodes and Outside Thermowell (TW7) Temperature (Recorded Manually) | B-3 |
| B-2 | Temperature in Thermowells (Outside Thermowell TW7 in Table B-1) | B-9 |
| B-3 | Temperature in Excitor Electrodes | B-17 |
| B-4 | Ground Electrode and Outside Thermowell Temperature (Recorded by Data Logger) | B-20 |
| C-1 | Operating Data -- Electrical | C-3 |

I. INTRODUCTION

The purpose of this document is to present the results of the in situ radio frequency heating soil decontamination experiment performed at Kelly Air Force Base, Site S-1, San Antonio, Texas. The heating portion of the experiment was performed from April 3, 1993 to June 3, 1993.

A number of different organizations were involved in this project. These were:

- HALLIBURTON NUS: USAF's prime contractor in charge of the demonstration project.
- IIT Research Institute: Subcontractor to HALLIBURTON NUS; technology developer and operator of the in situ heating system; analysis of soil for diesel range petroleum hydrocarbons.
- USEPA SITE Program Office: Technology evaluation and assessment including the analysis of soil samples for contaminant concentration.
- SAIC: USEPA's contractor for SITE program.

A. BACKGROUND

IIT Research Institute (IITRI) has been working with HQ AFCESA/RAVV, Tyndall Air Force Base for many years to develop the RF technology for in situ soil decontamination. The RF technology was originally conceived and developed for uniform heating of large volumes of earth formations for in situ fuel recovery. The technology was modified for soil decontamination purposes. IITRI had a number of contracts over the past years from U.S. Air Force, U.S. Environmental Protection Agency (EPA), and U.S. Department of Energy (DOE) to develop various aspects of the technology.

The radio frequency (RF) soil decontamination technology is based on in situ heating of soil through dissipation of electromagnetic energy in the RF band to volatilize the contaminants followed by collection and treatment of the effluent. The RF technology requires two major subsystems: the RF heating system and the effluent containment collection, and treatment (ECCT) system. The RF heating system includes the electrode array and the RF shield, RF power source, and matching network; the ECCT system includes the vapor barrier, vapor collection system, blower, and the vapor treatment system (VTS).

Energy is applied to the soil by energizing an array of electrodes placed in bore holes drilled through the contaminated soil. The electrodes are fabricated from copper and aluminum tubing or pipe. Selected electrodes are perforated and also connected to a vacuum system for the collection of the vaporized contaminants, water vapor and air. A vapor barrier and a RF shield is placed on top of the electrode array. The vapor barrier is needed to prevent emissions of the vaporized contaminants from the heated surface of the soil. The RF shield is needed to reduce RF emissions to low levels so that to avoid RF interference with other electronic systems and also to reduce RF emissions to safe levels.

B. SITE HISTORY

The demonstration experiment was conducted at Site S-1, located near the northern boundary of Kelly Air Force Base (AFB), Texas. This site was used as an intermediate storage area for wastes to be reclaimed off-base. The waste liquids were stored in storage tanks. Mixed solvents, carbon cleaning compounds, petroleum oils and lubricants (POL) were handled at the storage area. The soil is contaminated due to waste spills that occurred during waste transfer and storage tank overflow. The spilled material accumulated in a sump at the bottom of a nearby depression in the ground. The site was used from 1960 to 1973. It is reported that the depression was back filled with fill material after site operations were terminated. Figure 1 illustrates the general location of the site on Kelly AFB.

C. PROJECT BACKGROUND

Work was initiated by IITRI on this project on November 2, 1992. Prior to this, IITRI had completed a bench scale treatability study (Reference 2a) to determine the feasibility of the removal of diesel range TPH from Site S-1 soil. In the same project (Reference 2b), the design of a demonstration system based on 120 kW of input RF power was made. Subsequently, the design was revised in this project for an input power level of 40 kW in order to allow the demonstration to be done with IITRI's RF power source.




Figure 1. Location map for Site S-1.

II. DEMONSTRATION OBJECTIVES

The main objectives of the field demonstration test were the following:

- Obtain a greater than 90 percent removal efficiency from the soil for the following four semi-volatile organic compounds: 2-methynaphthalene, naphthalene, 2,4,6-trichlorophenol, and 2-methylphenol
- Obtain greater than 95 percent removal efficiency from the soil for the following four volatile organic compounds: benzene, toluene, ethylbenzene, and chlorobenzene
- Obtain greater than 90 percent removal of the diesel range total petroleum hydrocarbons (TPH).
- Measure the removal of three ring PAHs, bis(2-ethylhexyl)phthalate and other semi-volatiles found at the site.

It was planned to heat the soil to an average temperature of 150° C. This treatment temperature was selected based on the results of a laboratory treatability study in which the removal of diesel range organics from samples of site S-1 soil was studied.

The RF in situ soil decontamination process was tested by heating a soil volume of dimensions: 17.5 ft long, 10 ft wide and 20 ft deep. In the original design the depth of the heated zone was 24 ft, but this was changed during system installation. The change was necessary because ground water table was shallower than expected.

This project was accomplished by performing the following 13 tasks:

| | | |
|----------|---------------------------------------|----------|
| Task 1: | Scale Down Design and Document | (C06770) |
| Task 2: | Revise Work Plan and Schedule | (C06773) |
| Task 3: | Review Health and Safety Plan | (C06774) |
| Task 4: | Review of Sampling and Analysis Plan | (C06775) |
| Task 5: | Assist in Obtaining Permits | (C06771) |
| Task 6: | Procurement and Equipment Fabrication | (C06772) |
| Task 7: | System Installation | (C06776) |
| Task 8: | Start up and Shakedown of System | (C06778) |
| Task 9: | Perform Demonstration and Cool Down | (C06779) |
| Task 10: | Decontamination and Demobilization | (C06786) |

Task 11: Review Data, Cost Analysis and Write (C06781)
Final Report
Task 12: Attend Meetings (C06782)
Task 13: Analyze Pre-Demonstration Soil Samples (C06784)

III. SITE DESCRIPTION¹

A. REGIONAL SETTING

1. Geography

Kelly AFB lies in the western portion of the Gulf Coastal Plain, a gently undulating prairie with elevations ranging from 450 feet to approximately 700 feet above the National Geodetic Vertical Datum (NGVD). The plain slopes to the Southeast toward the Gulf of Mexico. Elevations at Kelly AFB vary from 730 to 620 feet above NGVD. Lower elevations lie along Leon Creek at the southern boundary of the base.

The San Antonio area lies within two distinct physiographic regions, the Edwards Plateau section of the Great Plains Province and the western Gulf Coastal Plain. The southwest-northeast trending Balcones Escarpment divides the two regions. The plateau serves as a recharge area for surface waters flowing to aquifers and streams extending through the San Antonio area.

2. Geology

The region surrounding Kelly AFB is underlain by Quaternary alluvium over a thick stratigraphic sequence of Cretaceous sediments. The alluvium consists of mixtures of clay, silt, and gravel. These deposits are typically 10 to 35 feet thick. The Cretaceous unit is the Navarro Group clay. The Navarro Group clay and other limestone and shale units form a thick sequence between the alluvium and the underlying Edwards Group limestone.

3. Hydrology

Surface Drainage

Surface runoff at Site S-1 drains eastward to Apache Creek, approximately 2.5 miles away. Apache Creek flows into San Pedro Creek, which in turn flows into the San Antonio River.

Groundwater

Kelly AFB lies above two groundwater aquifers. The uppermost aquifer lies within the lower strata of the Quaternary alluvium. Although this aquifer is capable of providing potable

¹Material in this Section is taken from Preplanning Report for the Demonstration of Radio Frequency Soil Decontamination -- Site S-1, HALLIBURTON NUS, USAF Contract No. F33615-90-D-4011, Delivery Order No. 0007, November 1993.

water, the quality and quantity are variable and questionable. The second aquifer is contained within the Edwards Group and is separated from the first aquifer by the Navarro Clay. The Texas Legislature established the Edwards Aquifer Underground Water District in 1959 to provide for the systematic planning and protection of groundwater in this aquifer. The EPA designated the Edwards a sole source aquifer in 1975 (40 CFR 149).

B. SITE S-1

1. Location

Site S-1 lies in the northern part of Kelly AFB, immediately south of Growdon Drive, north of West Thompson Drive, and west of a railroad spur near Building 1592.

2. Site History

Site S-1 served as an interim storage area for wastes to be reclaimed off base from the early 1960s to 1973. The western two-thirds of the site served as a temporary storage for electrical transformers and scrap metal. Liquid wastes, including mixed solvents and POLs were stored in above-ground tanks. Any spillage that occurred during storage, loading, and unloading flowed into a low area near the tanks. The site was later regraded after the abandonment and removal of the tanks.

Investigators observed a circular depression on old aerial photographs and investigated it as a possible dump site. No landfill material was found, and the depression area and a sump located within the depression were leveled with fill material. This waste oil sump is shown Figure 2 as a northwest - southeast trending region covering an area of approximately 40 by 150 feet. Further drilling has revealed a northwest-southeast-trending extension of the sump on the northeast side of the site.

3. Topography and Drainage

Site S-1 is generally flat, with surface elevations ranging from 690 to 691 feet above NGVD. Gravel covers the area over the former sump, but grass covers most of the remainder of the site. Rainfall at the site is likely to pool on the surface because of the slight topographic relief and low infiltration rates.

4. Geology

The alluvial material at Site S-1 consists of an upper layer of dark brown to black clay typically 7 feet thick overlying either a reddish brown silty clay or a clayey gravel, sand/gravel unit. The reddish brown silty clay lies in the southeast corner of the




Figure 2. Site S-1.

site and is usually 7 to 10 feet thick. The coarse-grained unit underlying the remainder of the site consists of surrounded to subangular limestone and chert.

Results from two grain size analyses of the sand and gravel unit collected from a boring adjacent to Site S-1 (APO2) show that the alluvial aquifer is approximately 40% sand, 40% gravel, and 20% fine-grained material. These results as well as other geotechnical samples collected at Kelly AFB demonstrate a significant variability in the porosity and permeability of the alluvium.

Much of the alluvium was removed and replaced by fill material in the former depression area. The fill material is dark brown to black gravelly clay with occasional zones of sand and silt covering an area approximately 150 by 300 feet. The depth ranges from 0 feet at the edge of the sump to 25 feet at its center. Large limestone and chert gravels up to 3 inches in diameter inhibited recovery during drilling throughout most of the unit.

The regional aquitard, the Navarro Group clay, lies 28 to 33 feet below the former depression area. Under Site S-1, the Navarro clay is a mottled, orange-brown to gray, stiff, plastic clay with crude laminae. A few borings have revealed silty horizons within the clay.

5. Hydrology

Water level measurements recorded between mid-1989 and late-1990 indicate that the direction of groundwater flow is towards the northeast. The water table beneath the site ranged from 25 to 30 feet below the surface, with a saturated aquifer thickness of 3 to 6 ft. The maximum water level fluctuation observed in the vicinity of Site S-1 was 3.25 ft. Northeast of the site, water level measurements made on April 30, 1992 indicated that groundwater gradient was 0.016 ft/ft, much higher than the 0.003 ft/ft gradient found immediately downgradient of the site. A local high are in the Navarro clay in combination with a groundwater mound effect appears to be the cause for the steep gradient across the sump.

6. Levels and Extent of Contamination

Soils

Site S-1 analytical results show significant contamination in the location of the former sump. The contamination consists of polychlorinated biphenyls (PCBs) in surface soils ($9,000 \mu\text{g}/\text{kg}$) and volatile organic compounds (VOCs) and semivolatile organics in the subsurface. The compound groups most prevalent in the subsurface are halogenated benzenes, methyl phenols, phthalates, and polynuclear aromatic hydrocarbons (PAHs).

Compounds with the highest concentrations in the soil are 1,2-dichlorobenzene (1,200,000 $\mu\text{g}/\text{kg}$) and 1,4-dichlorobenzene (720,000 $\mu\text{g}/\text{kg}$). Table 1 shows the maximum concentration of each VOC and semivolatile compound detected by fixed-base or field laboratory analysis.

Horizontally, the contamination at Site S-1 is largely confined to a 110 by 120-foot area surrounding the sump. Vertically, most of the organic contamination in the soil lies in a 10 to 15-foot thick horizon 17 to 33 feet below the surface in boring S1B10 and S1B11. Although surface staining is evident in aerial photographs, little contamination is found above a depth of 10 feet. Another zone of contamination, isolated from the lower unit, was detected in boring S1B08 at a depth of approximately 12 feet. The lower extent of the contamination in this isolated area could not be determined because of poor sample recovery.

Table 1. Organic Compounds Detected in Soils, Site S-1, Kelly AFB, Texas

| Volatile Organics | Chemical Formula | Molecular Weight | Boiling Point at 1 atm., (°C) | Specific Gravity | Temperature at which Vapor Pressure is 1 mm Hg (°C) | Vapor Pressure at 20°C (mm Hg) | Maximum Concentration (µg/kg) |
|--------------------------|---|------------------|-------------------------------|------------------|---|--------------------------------|-------------------------------|
| 1,2-Dichlorobenzene | C ₆ HCl ₂ | 147.01 | 180 | 1.3048 | 20 | 1 | 5,100 |
| 1,4-Dichlorobenzene | C ₆ H ₄ Cl ₂ | 147.01 | 174 | 1.2975 | <50 | 0.6 | 5,100 |
| 1,3-Dichlorobenzene | C ₆ H ₃ Cl ₂ | 147.01 | 173 | 1.2884 | 12.1 | 2 (25 deg) | 1,800 |
| Styrene | C ₈ H ₈ | 104.2 | 145 | 0.9060 | -7 | 5 | 1,100 |
| Ethylbenzene | C ₈ H ₁₀ | 106.2 | 136 | 0.8670 | -9.8 | 7.1 | 2,700 |
| Chlorobenzene | C ₆ H ₅ Cl | 112.6 | 132 | 1.1058 | -13 | 9 | 3,200 |
| 2-Hexanone | C ₆ H ₁₂ O | 100.2 | 128 | 0.8113 | 7.7 | 2 | 32 |
| Tetrachloroethene | C ₂ Cl ₄ | 165.8 | 121 | 1.6227 | -20.6 | 14 | 4 |
| Toluene | C ₇ H ₈ | 92.2 | 111 | 0.8669 | -26.7 | 22 | 6,800 |
| Trichloroethene | C ₂ HCl ₃ | 131.4 | 87 | 1.4642 | -43.8 | 57.8 | 12 |
| Benzene | C ₆ H ₆ | 78.1 | 80 | 0.8787 | -36.7 | 76 | 1,200 |
| 2-Butanone | C ₄ H ₈ O | 72.1 | 80 | 0.8054 | -48.3 | 77.5 | 53 |
| 1,1,1-Trichloroethane | C ₂ H ₃ Cl ₃ | 133.4 | 74 | 1.3390 | -52 | 100 | 24 |
| Vinyl Acetate | C ₄ H ₆ O ₂ | 86.1 | 72 | 0.9317 | -48 | 83 | 4 |
| Chloroform | CHCl ₃ | 119.4 | 62 | 1.4832 | -58 | 160 | 17 |
| Trans-1,2-Dichloroethene | C ₂ H ₂ Cl ₂ | 96.9 | 48 | 1.2565 | -65.4 | 265 | 200 |
| Methylene Chloride | CH ₂ Cl ₂ | 86.9 | 40 | 1.3266 | -70 | 348.9 | 130 |

Table 1. Organic Compounds Detected in Soils, Site S-1, Kelly AFB, Texas (Continued)

| Semi-Volatile Organics/PCBs | Chemical Formula | Molecular Weight | Boiling Point at 1 atm., (°C) | Specific Gravity | Temperature at which Vapor pressure is 1 mm Hg (°C) | Vapor Pressure at 20°C (mm Hg) | Maximum Concentration (µg/kg) |
|-----------------------------|---|------------------|-------------------------------|------------------|---|--------------------------------|-------------------------------|
| Aroclor-1260 | Varies | =370 | 385 - 420 | 1.5660 | | 6E-5 (25 deg) | 6,700 |
| Benzoperylene | C ₂₂ H ₁₂ | 276.3 | >500 | | | 1.0E-10 (25 deg) | 230 |
| Indeno-(1,2,3)-Pyrene | C ₂₂ H ₁₂ | 276.3 | 536 | | | 1.0E-10 (25 deg) | 190 |
| Dibenzo Anthracene | C ₂₂ H ₁₄ | 278.4 | 524 | 1.2820 | | 1.00E-10 | 160 |
| Benzo Pyrene | C ₂₀ H ₁₂ | 252.3 | 495 | 1.3510 | | 5.00E-07 | 390 |
| Benzo Fluoranthene | C ₂₀ H ₁₂ | 252.3 | 480 | | | 5.00E-07 | 700 |
| Chrysene | C ₁₈ H ₁₂ | 228.3 | 448 | 1.2740 | | 6.30E-07 | 580 |
| Benzo Anthracene | C ₁₈ H ₁₂ | 282.3 | 439 | 1.2740 | | 2.00E-09 | 520 |
| Pyrene | C ₁₆ H ₁₀ | 202.3 | 393 | 1.2710 | | 2.5E-6 (25 deg) | 940 |
| Fluoranthene | C ₁₆ H ₁₀ | 202.3 | 375 | 1.2520 | | 5.00E-06 | 9,000 |
| Anthracene | C ₁₄ H ₁₀ | 178.2 | 340 | 1.2830 | 145 | 2.00E-04 | 130 |
| Pentanthrene | C ₁₄ O ₁₀ | 178.2 | 340 | 0.9800 | 118.2 | 2.10E-04 | 920 |
| Acena Phthylene | C ₁₂ H ₁₂ | 152.2 | 265 | 0.8988 | | 2.90E-02 | 20 |
| 2,4,6-Trichlorophenol | C ₆ H ₄ Cl ₃ O | 197.5 | 246 | 1.4900 | 76.5 | 1.7E-2 (25 deg) | 100,000 |
| 2-Methylnaphthalene | C ₁₁ H ₁₀ | 142 | 241 | 1.0058 | | | 12,000 |
| Di-n-Octyl Phthalate | C ₂₄ H ₃₈ O ₄ | 390.6 | 220 | 0.9900 | | 1.4E-4 (25 deg) | 2,800 |
| Naphthalene | C ₁₀ H ₈ | 128.2 | 218 | 1.0253 | 52.6 | 5.40E-02 | 10,000 |
| Bis(2-Ethylhexyl)-Phthalate | C ₂₄ H ₃₈ O ₄ | 390.6 | 218 | 0.9843 | | 2.00E-07 | 57,000 |
| 2,4-Dimethylphenol | C ₈ H ₁₀ O | 122.2 | 212 | 0.9650 | 51.8 | 6.20E-02 | 2,400 |
| 2,6-Dimethylphenol | C ₈ H ₁₀ O | 122.2 | 203 | 0.8600 | 58 | | 2,200 |
| 2-Methyphenol | C ₇ H ₈ O | 108.1 | 191 | 1.0273 | 38.2 | 0.3 (25 deg) | 8,100 |
| Phenol | C ₆ H ₆ O | 94.11 | 182 | 1.0722 | 40.1 | 0.2 | 3,200 |

IV TECHNOLOGY DESCRIPTION

A. PROCESS DESCRIPTION

In situ radio frequency (RF) heating and soil decontamination is a two-step process. These steps are: heating of soil to the treatment temperature, and recovery and treatment of the volatilized contaminants. Once the soil temperature is elevated above 40° to 50° C, these two steps work simultaneously.

In situ heating is accomplished by energizing an array of electrodes emplaced in bore holes drilled through the soil. The electrode array is supplied with electromagnetic (EM) energy in the RF band, typically between 2 and 13 MHz. The actual operating frequency is selected from the available ISM band frequencies in the above range. Typically three rows of electrodes are utilized. The two outer rows are called the guard electrodes and they serve to confine the energy to a well defined volume of the soil. The center row is called the excitor row. Figure 3 is an illustration of the in situ RF heating process depicting the electrode rows and the vapor collection system.

In RF heating, mechanism of heat generation is similar to that of the microwave oven. Electrical energy is dissipated volumetrically and converted to thermal energy due the absorption of EM energy by moisture and soil. The primary mechanism of energy absorption is the rotational and vibrational displacement and physical distortion of dipoles induced in polar molecules. The dielectric properties of soil determine the amount of RF power that can be dissipated in the soil. These properties are the relative dielectric constant (ϵ_r) and the loss tangent. The loss tangent, $\tan(\delta)$ is defined as $\sigma / (\omega \epsilon_0 \epsilon_r)$ where σ is the apparent conductivity, ω is the frequency of the applied electric field, radians/sec, and ϵ_0 is the permittivity of free space, and it equals 8.85×10^{-12} farads/meter. All the dielectric properties are a function of soil temperature, the frequency of the applied field and the composition of the major components. The amount of RF power dissipated in the soil is directly related to the frequency of the applied electric field, square of the amplitude, the relative dielectric constant and the loss tangent.

Due to its volumetric nature, the process does not depend upon conductive transport of thermal energy, even though thermal conduction does occur. With an appropriate array design and operating strategy, it is theoretically possible to obtain uniform heating of the soil volume enclosed within the two outer rows of the excitor array.

IN SITU Radio Frequency Soil Decontamination Process




Figure 3. Artist's Illustration of the RF Process.

As the soil heats up, the soil moisture and the organic contaminants begin to vaporize and they will eventually boil depending upon the final temperature and their boiling points. The vaporized and boiled materials are removed from the soil matrix by applying a vacuum to gas collection points. These points are vented electrodes placed in the array used to heat the soil. The preferred location of the gas collection electrodes is in the middle of the electrode array. This is the best location because the temperature rises first and reaches a higher level in the central row of electrodes. Collection of hot vapors from the central electrode row at high operating temperatures is however, technically challenging, because collection piping must be non-metallic and poses suitable dielectric insulating properties so as to prevent arcing and radiation of RF energy.

Vapors may also be collected from the surface of the heated zone as well as from the two outer rows of the electrode array. Collection from the two outer rows poses less electrical design challenges because metallic piping may be used here. Gases and vapors produced in the soil volume will also rise directly to the surface due to diffusion, and buoyancy. These may be collected at the surface by means of horizontal perforated gas collection lines placed on the surface of the soil. Depending upon their positioning these lines may be made from metal.

A vapor containment barrier is needed to prevent emissions from the heated soil surface. Typically this barrier must possess high temperature operating characteristics, be impermeable to organic vapors, and must be a suitable dielectric insulator. An elastomeric material like silicon rubber sheets can be used.

Figure 4 is a conceptual block diagram depicting the RF process. Electrical energy from the utility grid is converted to the high frequency electromagnetic energy by a RF power source. This source can be a modified radio transmitter, an amplifier or an oscillator. RF power sources can be trailer mounted for easy transportation to the waste sites. The output of the RF power source is conveyed to a matching network which optimizes the transfer of power between the source and the load. The load comprises of the electrode array along with the soil.

The recovered gas stream may need treatment prior to discharge to the environment. The type of treatment and clean-up required depends on the nature, concentration and total amount of contaminants present in the gas stream. Any proven technology for the clean up of the vent gas stream may be used, provided it can be built in transportable trailer mounted modules. Several options for gas treatment are available:

- Open release of dilute streams of hydrocarbons




Figure 4. Conceptual Block Diagram of the RF Process

- Cooling, condensation, carbon treatment
- Incineration
- Catalytic incineration
- Appropriate combination of above

During the in situ heating of soil several different phenomena occur which help in the vaporization and recovery of the contaminants. First, there is the development of effective permeability to gas flow in the soil matrix. Second there is the increased sweep of air and steam through the treatment zone and third, there is the possibility of steam distillation reducing the boiling point of a multi-phase mixture of organic and aqueous phases.

The effective permeability to air flow increases as the soil water is removed by evaporation and boiling, the vacated pore space becomes available for the flow of steam, vapors and air.

As the permeability to gas flow increases, a sweep of air or steam can be easily established in the soil to help facilitate the removal of organic vapors which are in the soil pore space. The air flow is induced in the soil by the application of vacuum. The steam flow is created by the applied vacuum and boiling of native soil moisture present in the heated volume and of any new water entering the heated zone from the surrounding soil. For some combinations of soil types and contaminants the effect of steam flow may be more beneficial in the removal of the contaminants from the soil matrix than an equivalent flow rate of air.

Figure 5 is a graph depicting the increased permeability to the flow of nitrogen gas in a small sample of clayey soil packed inside a cylindrical device for measuring permeability. The figure illustrates that as the pore saturation of water is reduced, the permeability to air flow increases. It does not matter how the water is removed from the soil pores. Data for two operating modes is presented. In the first, the soil moisture is removed at elevated temperature by heating the core. In the second operating mode, the soil moisture was removed by a nitrogen sweep through the core which was maintained at room temperature. The first operating mode is of course faster in obtaining the permeability change.

Steam distillation of organic liquids such as benzene, xylene, etc. occurs when a mixture of the organic liquid and water is brought to a boil under condition where two or more liquid phases co-exists. Under these conditions, the mixture boils at a lower temperature than that of either of the two phases when present alone. The mixture boils when the partial pressure of all the vapor phase components above the mixture equals 760mm Hg or the prevailing atmospheric pressure. In a multi-liquid-phase mixture, each liquid phase exerts its own vapor pressure, which contributes




Figure 5. Soil Permeability as a Function of Pore Saturation

TABLE 2. BOILING POINT REDUCTION
(Steam Distillation Conditions)

| Contaminant | Normal B.P., °C | Mixture B.P., °C | Steam/ Contaminant lb/lb |
|------------------------|-----------------------|------------------------|--------------------------------|
| 1,1,1 Tricholoroethane | 74.1 | 64.4 | 0.04 |
| Benzene | 80.1 | 68.3 | 0.09 |
| Toluene | 110.6 | 83.9 | 0.24 |
| Tetrachloroethylene | 120.8 | 87.7 | 0.19 |
| Bromoform | 150.0 | 94.3 | 0.31 |
| Hexachloroethane | 186.0 | 98.7 | 1.57 |
| Pentadecane | 270.5 | 99.95 | 30.10 |

each liquid phase exerts its own vapor pressure, which contributes to the total pressure above the liquid surface. Due to this reason the mixture boils at a temperature less than that of either of the liquid phases present. Table 2 lists the pure component and the mixture boiling points when several common environmental contaminants are subjected to steam distillation conditions.

B. ENERGY REQUIREMENTS

The theoretical amount of thermal energy required to heat soil depends upon the following factors:

- Initial soil temperature
- Final treatment temperature
- Initial Soil moisture content
- Initial hydrocarbon content
- Thermal properties of moist and dry soil

The actual amount of thermal energy needed for the heating of soil depends upon the factors listed above and heat loss. Heat loss from the heated volume can occur in the following ways:

- conduction from the heated soil surface
- conduction from the sides and bottom of the heated block of soil
- heating of any air flowing through the hot zone
- convection and radiation from the heated surface

system and gets converted to steam represents an additional heat load, the economic penalty may be offset by the beneficial aspects of steam sweep on the removal of the contaminants from the soil. In any event, the rate of water intrusion has to be limited to reasonable level such that the power source can provide the necessary extra energy, otherwise the entire volume will not reach the desired temperature or else experience a temperature drop.

In a prior study (Reference 1) the heat loss from the first three mechanism listed above was estimated for heating of large blocks of soil to a depth of 20 ft. In this study approximately 1 acre of soil was heated at the same time using a large RF power source with heating time ranging from 0.25 to 0.5 year. Under such conditions it was estimated that the actual energy required can be 25 percent higher due to heat loss, than the theoretical amount needed.

The additional energy required due to water intrusion was not considered because it is a site specific variable and water intrusion may be controlled by other means. On the other hand it is almost impractical to reduce heat losses due to conduction while operating under in situ conditions.

Table 3 gives an estimate of the theoretical amount of thermal energy needed for heating up one ton of soil to a temperature of 150° C. The following assumptions were made: the soil contains 10 to 20 percent initial moisture, initial contaminant concentration of 1%, average contaminant latent heat of vaporization of 200 Btu/lb; and no water intrusion. Table 3 shows that when the soil contains 10 percent water, 60 percent of the theoretical energy is required to boil the water. When the soil contains 20 percent initial water, 75 percent of the theoretical energy is required to boil the water. The energy needed to heat the soil after accounting for the conductive heat losses may be estimated from Table 3 by adding 25 percent to the amounts shown. Thus the thermal energy needed is in the range of 120 to 190 kWh/ton of soil heated. The amount of RF energy required to heat the soil is also equal to the above estimate due to extremely low losses for RF transmission and 100 percent conversion from RF to thermal energy.

The amount of AC power needed from the utility to heat the soil is a function of the RF power requirements and the AC to RF conversion efficiency of the RF power source. The conversion efficiency ranges from 45 to 65 percent depending upon the type and design of the RF power source. Older, tube-based RF transmitters like IITRI's 40 kW unit, have a conversion efficiency of about 45 percent. Modern tube units have an efficiency ranging from 60 to

TABLE 3. THEORETICAL ENERGY REQUIRED TO HEAT SOIL TO 150° C

| | Soil Moisture, % | | | |
|--|------------------|---------|---------|---------|
| | 10% | | 20% | |
| | Btu/ton | kWh/ton | Btu/ton | kWh/ton |
| Sensible heat required to reach 100° C | 88,200 | 25.84 | 88,200 | 25.84 |
| Heat Required to boil water | 194,000 | 56.84 | 388,000 | 113.68 |
| Heat required to boil contaminants | 4,000 | 1.17 | 4,000 | 1.17 |
| Heat required to raise temperature from 100° to 150° C | 40,050 | 11.73 | 35,550 | 10.42 |
| Total Heat Required | 326,250 | 95.58 | 515,750 | 151.11 |

design of the RF power source. Older, tube-based RF transmitters like IITRI's 40 kW unit, have a conversion efficiency of about 45 percent. Modern tube units have an efficiency ranging from 60 to 65 percent. Future solid state units are projected to have conversion efficiency in the range of 70 to 75 percent.

The above discussion does not allow for the AC power requirements of the vapor treatment system. These requirements are estimated to be low, of the order of 10 percent of that needed for heating soil.

V. SYSTEM DESIGN AND INSTALLATION

The system as designed and implemented in the field at Site S-1 is described in this section. The purpose of this design was to heat soil to an average temperature of 150°C in order to meet the objectives listed in Section 2. The temperature of 150°C was selected based on the removal of diesel range organics observed during the soil treatability study done by IITRI in a prior project (Reference 2). The results of the treatability study are also summarized below.

A. TREATABILITY OF S-1 SOIL FOR THE REMOVAL OF DIESEL RANGE ORGANICS

1. SOIL SAMPLE DESCRIPTION

Three new bore holes were made by HALLIBURTON NUS on October 19, 1991, at the southeastern corner of site S-1. Two of these bore holes were on the center line of the pit while one was outside. Continuous coring was done during the drilling of these bore holes by means of a hollow stem auger drill. Table 4 summarizes the core recoveries, field OVA readings, HALLIBURTON NUS' analysis for TPH from selected core intervals, etc. Soil needed for the treatability study was selected from the samples sent to IITRI. In Table 4 the core sample used for each of the five experiments is also indicated by means of the experiment number.

Table 5 provides a list of other contaminants found in the new borings. As the data in Tables 4 and 5 show, TPH with a concentration of up to 980 ppm is by far the most abundant contaminant present in the soil samples analyzed for this study. Other contaminants listed in Table 5 are present at levels which are approximately one thousandth the concentration of TPH. The results from the samples obtained from SB-16 show that the concentrations are considerably lower 5 to 6 ft outside the original estimated location of the sump boundary. Thus SB-16 may indeed be outside the original boundary and also outside the zone of current contamination. The field demonstration should be performed in the southern edge of the sump, near the location of borings SB-17 and SB-18.

2. Treatability Study Objectives and Approach

Soil treatability experiments were performed to determine the required treatment conditions for the removal of petroleum hydrocarbons found in soils obtained from borings made in Site S-1, Kelly AFB. The main focus of the study was to determine the

TABLE 4. FIELD SCREENING AND LAB. ANALYSIS OF CORE SAMPLES OBTAINED
ON 10/19/91, SITE S-1, KELLY AFB
(All results in ppm)

| Depth Interval | SB-17 | | | | SB-18 | | | | SB-16 | | | |
|----------------|---------|---------|---------|--------------|---------|-----------|----------|--------------|---------|---------|---------|--------------|
| | TPH ppm | Moist % | OVA ppm | Reco very ft | TPH ppm | Moist % | OVA ppm | Reco very ft | TPH ppm | Moist % | OVA ppm | Reco very ft |
| 2-7 | 400 | 20.3 | 40-700 | 4.5 <20 | 19.5 | 300-700 | 4 Exp5 | <20 | 12.2 | 30-80 | 1.9 | |
| 7-12 | NA | NA | 20 | 1 <20 | 24.7 | 100-1000+ | 4.6 Exp4 | <20 | 9.2 | 5-80 | 4.5 | |
| 12-17 | NA | NA | 10-40 | 1.0 <20 | 26.7 | 300-1000+ | 5 Exp2 | NA | NA | 0 | 0.8 | |
| 17-22 | 980 | 8.5 | 200-300 | 2.0 Exp1 | NA | 200-300 | 1.5 Exp3 | NA | NA | 15 | 0.4 | |
| 22-27 | NA | NA | 40 | 0.8 110 | 15.7 | 500-700 | 2.5 | - | - | - | 0.0 | |
| 27-32 | - | - | - | 0.0 NA | NA | 700 | 2 | NA | NA | 0-2 | 0.8 | |
| 32-37 | - | - | - | 0.0 <20 | 22.1 | 10-100 | 3 | - | - | - | 0.0 | |

TPH: Total petroleum hydrocarbons as analyzed by HALLIBURTON NUS.
OVA: Field measurement for hydrocarbons
NA: Not Analyzed
-: No Sample Recovery

TABLE 5. CONCENTRATION ($\mu\text{g}/\text{kg}$) OF SEMI-VOLATILES IN
BORINGS SB-16 TO SB-18

| Chemical Name | SB-16 | SB-17 | SB-18 | | |
|----------------------------|-------|-------|-------|--------|--------|
| | 2-7' | 2-7' | 2-7' | 22-27' | 32-37' |
| 1,2,4-trichlorobenzene | | | | 190 | |
| 1,2-dichlorobenzene | | | | 3600 | 230 |
| 1,3-dichlorobenzene | | 200 | | 1600 | |
| 1,4-dichlorobenzene | | 1100 | | 9300 | |
| 2-methylnaphthalene | | 2300 | | 4400 | |
| Benzo(a)anthracene | 170 | | | | |
| Benzo(b)fluoranthene | 260 | | | | |
| bis(2-ethylhexyl)phthalate | | 13000 | 640 | 1800 | |
| Di-n-butylphthalate | | 200 | 250 | | |
| Fluoranthene | 430 | 300 | | | |
| Naphthalene | | 140 | | | |
| Phenanthrene | | 200 | | | |
| Pyrene | 350 | | | | |
| Solids, wt % | 87.8 | 79.7 | 80.5 | 84.3 | 77.7 |

Blank cells indicate the contaminant was below its quantitation limit

In SB-16, 7-12 ft all were below quantitation limit

In SB-17, 17-22 ft all were below quantitation limit

In SB-18, 7-12, and 12-17 all were below quantitation limit

temperature and time conditions necessary to remove at least 90 percent of the total petroleum hydrocarbons (TPH) as analyzed by the California DHS method (Reference 3) for TPH.

The analytical method allows for determination of TPH as gasoline or as diesel. In this study the TPH was reported as diesel to determine the condition necessary for the removal of higher boiling components represented by diesel. Most of the hydrocarbons in diesel contain nine to 21 carbon atoms. They are primarily straight and branched chain alkanes, alkyl benzenes and PAH. The boiling point range of the straight chain alkanes is in the range of 150°-376°C; the lowest boiling branched chain alkane in diesel boils at 306°C; the alkyl benzenes boil in the range of 80° to 255°C, and the PAHs boil in the range of 218°C to greater than 500°C. Thus most of the diesel components can be classified as semi-volatiles. Based on previous treatability studies performed by IITRI on clayey soils it is anticipated that lower boiling volatile organics would have even better removal efficiency under the same conditions that give greater than 90 percent removal for diesel range TPH.

The laboratory approach to the treatability study attempts to simulate the temperature and gas flow conditions that occur in situ. This approach was developed at IITRI over the last five years and was used to develop conditions for the successful field experiment at Volk ANGB (Reference 4). The treatability experiments were performed by packing the clayey soils of Site S-1 into a 1.5-in. diameter pipe. The soil column was heated with externally wrapped heating tapes. Gas flow was simulated by injecting at a controlled rate either nitrogen or superheated steam at the base of the soil column.

Under in situ conditions, as soil is heated and the native moisture is removed from the soil pores, the effective permeability to gas flow increases. Thus a gas and steam sweeping action is established in the heated zone due to the vacuum imposed for the collection of the contaminant gases, vapors and steam. The gas and steam sweep thus established helps to increase the rate of contaminant removal from the soil matrix. In the laboratory this sweeping action is simulated by injection of nitrogen, air or steam at the base of the soil column.

3. Experimental Apparatus

The treatability experiments were performed by heating a column of soil packed into a 1.5-in. diameter stainless steel pipe. The soil inside the pipe was heated by means of heating tapes wound around the pipe. Thermocouples were used to measure the temperature of the soil inside the pipe. The experimental set up is illustrated in Figure 6. The hot gases and vapors formed upon




Figure 6. Soil Treatability Experimental Set Up

heating the soil pass through a heated vapor tube into a water cooled condenser. The outlet of the condenser is connected to a chilled condensate receiver wherein all the liquids formed in the condenser are collected. The uncondensed gases leaving the condensate receiver were passed through a wet test meter.

The soil column was equipped with an injection port at the bottom through which a selected gas (air or nitrogen) or superheated steam was introduced into the soil column to simulate the gas sweep established in the soil upon in situ heating and collection of the produced gases and vapors. The volume of uncondensed gas leaving the chilled condensate receiver was measured by means of a wet test meter as shown in Figure 2. When nitrogen or air was injected at the base of the column it was assumed that the uncondensed gas leaving the receiver was 100% v/v air or nitrogen. Superheated steam was made by pumping deionized water at a controlled rate through a heat traced tubing. The amount of water pumped through the soil column was determined by weighing the water reservoir.

4. Experimental Procedure

The cleaned stainless steel reactor was packed with soil core samples sent to IITRI by HALLIBURTON NUS. Only core samples obtained from the two bore holes made inside the pit were used in the treatability study. In all experiments soil obtained from a single core interval (5 ft length of core) was packed into the reactor. As the reactor was being packed, soil samples were taken for TPH analysis and transferred to a clean glass jar. In some cases, the collected soil sample was split into two portions, one of which was spiked with a solution of known concentration of diesel in carbon disulfide. The jar was sealed with a teflon lined cap and refrigerated pending analysis.

After packing the reactor with soil, the column was connected to the vapor condenser, the wet test meter and the gas injection system as shown in Figure 6. The experiment was begun by heating the column of soil while passing nitrogen or air through the column. During this phase of the experiment native water present in the soil was recovered along with the condensed contaminant vapors in the chilled receiver. Once the recovery of the native soil moisture had ceased (determined by visual observation in the glass condenser) then the nitrogen or air flow was stopped, and the condensate receiver was replaced with a new one. Steam injection was now begun. The temperature of steam entering the base of the soil column was measured and adjusted to match the average temperature of the soil in the column.

Once the final soil temperature was attained, the soil was maintained at the temperature for a period of 100 to 380 hours (the

soak period). During the soaking period the flow of sweep gas was maintained at a constant rate.

At the end of the soaking period steam injection was terminated and nitrogen was re-injected at the base of the column. The purpose of nitrogen injection was to remove all residual steam from the column. The experiment was then terminated and the soil was allowed to cool down to room temperature. During this period the reactor was kept vented to the condenser and the condensate recovery system.

Once the soil had cooled to room temperature, the reactor was opened and the soil was transferred to a clean 1-gallon glass jar. The jar was sealed and tumbled on a roller table for a period of 20 min. A sample of the treated soil was obtained from the gallon jar and transferred to a sample jar. In some experiments two samples were obtained, one of which was spiked with a solution of known concentration of diesel in carbon disulfide.

5. Experimental Results and Conclusions

Five soil treatability experiments were performed. The experimental conditions and TPH concentration in soil are shown in Table 6. The TPH removal calculation is summarized in Table 7. Detailed information regarding each experiment along with temperature profiles are provided in Reference 2. The data shown in Tables 6 and 7 are based on TPH analysis performed by IITRI.

The data in Table 6 indicate that in 2 of the 5 experiments the soil did not have significant amount of TPH contamination as compared to the other samples from the site. Results from the other three experiments show that TPH can be reduced to the range of 60 to 230 ppm depending upon the treatment condition. Thus increasing treatment temperature from 113° to 150°C has a significant effect on the final concentration of the soil. Due to the long residence time in the field, the actual removal of the TPH under field conditions is expected to be even higher than that seen in the laboratory.

The results of Experiments 1 to 3 indicate that with the specific combination of contaminants and the soil matrix there is no effect of the type of sweep gas (steam/nitrogen versus nitrogen alone) on the residual concentration of the TPH. In Experiment 2 a low percent removal was attained due to the low initial concentration of the TPH in the soil. Table 7 is a summary of the removal calculations which take into account the change in soil moisture upon heating.

The calculations summarized in Table 7 are based on a mass balance for TPH and moisture. The basis for performing the mass

TABLE 6. SOIL TREATABILITY EXPERIMENTAL CONDITIONS AND RESULTS

| Expt. No. | Soak Temperature C | Soak Time hr | Nitrogen/ Air Sweep | Water Injection g/min | TPH Concentration ppm | |
|--------------|--------------------------|--------------------|---------------------------|-----------------------------|--------------------------|-------|
| | | | | | Initial | Final |
| 1 | 113 | 122 | Nitrogen | 4.6 | 3124 | 227.7 |
| 2 | 150 | 118 | Nitrogen | 5.2 | 1.98 | 70 |
| | | | | | 1.98 | 59.1 |
| 3 | 151 | 102 | Nitrogen | 0.0 | 2740 | 94 |
| 4 | 153 | 112 | Air | 0.0 | 59.9 | 11.5 |
| 5 | 112 | 388 | Nitrogen | 0.5 | 18.2 | 13 |

Expt 1: soil from boring SB-17, 17-22 ft depth
 Expt 2: soil from boring SB-18, 12-17 ft depth. Three different treated samples were analyzed. First line provides the results of the first sample and the second line gives the average of the other two.

Expt 3: soil from boring SB-18, 17-22 ft depth
 Expt 4: soil from boring SB-18, 7-12 ft depth
 Expt 5: soil from boring SB-18, 2-7 ft depth

TABLE 7. CALCULATION OF TPH REMOVAL DURING TREATABILITY STUDY
 (Basis: 100 gm of Initial Soil)

| Expt. No. | IN INITIAL SOIL | | IN FINAL SOIL | | TPH REMOVED μg | PERCENT REMOVAL % |
|--------------|--------------------|---------------|--------------------|---------------|----------------------|-------------------------|
| | TPH Conc. μg/gm | Moisture % | TPH Conc. μg/gm | Moisture % | | |
| 1 | 3124.0 | 9.1% | 227.7 | 0.1% | 291747.8 | 93.4 |
| 2 | 198.0 | 26.8% | 70.0 | 0.0% | 14677.0 | 74.1 |
| 2 | 198.0 | 26.8% | 59.1 | 0.0% | 15474.8 | 78.2 |
| 3 | 2740.0 | 15.1% | 94.0 | 0.0% | 266044.4 | 97.1 |
| 4 | 59.9 | 23.4% | 11.5 | 0.0% | 5109.2 | 85.3 |
| 5 | 18.2 | 16.6% | 13.0 | 2.8% | 704.3 | 38.7 |

Expt 1. Initial Soil average of two analysis: 3371, and 2877
 $\mu\text{g/gm}$

Expt 2. Three different treated soil samples were analyzed. First line provides the results of the first sample. The second line gives the average results of the other two samples.

Expt 3. Initial Soil analyzed two ways: by dilution for low level calibration: 2270 $\mu\text{g/gm}$ and by hi level calibration curve and no dilution: 2740 $\mu\text{g/gm}$. Use hi level result.

balance was 100 gm of initial soil. Consider, as an example, 100 gm of initial soil used in Experiment 1. The soil contains 312,400 μ g of TPH, 9.1 gm of moisture, and 90.59 gm of solids. The 90.59 gm of solids (considered as inert) remain unchanged upon heating, but the moisture content reduces to 0.1% and the TPH concentration reduces to 227.7 μ g/gm. Thus, in the final soil, solids represent 99.88% of the total residual mass. The residual mass of final soil is 90.70 gm. Thus the amount of TPH present in 90.7 gm of final soil is 20,652 μ g. The amount of TPH removed from the initial soil is $(312,400 - 20,652) = 291,748 \mu\text{g}$. Therefore, the removal of TPH, expressed as a percentage of initial TPH present in 100 gm of soil is $(291,748/312,400) * 100 = 93.4$ percent.

B. HEATING SYSTEM DESIGN

1. Design Heated Volume

The volume of the soil heated by the RF process is determined by the dimensions and geometry of the electrode array because the soil between the two outer electrode rows is heated. For this demonstration the size of the heated volume was limited by the size of the available RF power source, which was 40 kW. The soil was heated by installing an array of electrodes in the soil. The electrodes were installed in vertical bore holes drilled in three parallel rows. Figure 7 is a plan view of the electrode array implemented for the demonstration at Site S-1. The length of the two outer rows of electrodes (Rows A and C) is 17.5 ft and length of the Excitor row (Row B) is 7.5 ft. The depth of the two outer rows was 29 ft while the depth of the Excitor row was 20 ft. The heated volume will be determined by the geometry of the electrode array. As discussed above, the two outer rows are both longer and deeper than the central row. This was done to contain the fringing RF fields that emanate from the ends of the excitor row. Thus the volume that is expected to be heated is larger than the length and depth of the excitor row but less than the depth and length of the two outer rows. The width of the heated zone is equal to the separation of the two outer rows, that is 10 ft.

The length expected to be heated is equal to the length of the excitor row plus 66 percent of the row separation at each end. This gives an effective heated length of $(7.5+0.66*5*2)=14.1$ ft. Similarly, the expected depth of the heated zone is equal to the depth of the excitor row plus 66 percent of the row separation below the tips of the excitor electrodes. This gives a heated depth of $(20+0.66*5)=23.3$ ft. This gives a heated zone volume of approximately 3,285 cu. ft or 122 cu. yd.




Figure 7. Surface-Level Plan View of the Array (Electrode Locations Shown by •).

Thus the volume that the electrode array was expected to heat has a dimensions of:

Width: 10 ft
Length: 14.1 ft
Depth: 23.3 ft

2. Estimate of Heating Time

Previously, the energy required to heat one ton of soil was estimated as a function of soil moisture content. The RF energy varied between 120 to 190 kW-hr/ton of soil when the soil moisture varied between 10 to 20 percent. The soil moisture content at site S-1 varied between 9 to 26 percent. The heating time for the soil may be estimated by using the higher value for energy requirement corresponding to a moisture content of 20 percent.

The weight of the soil volume which is expected to be heated is approximately 165 tons. Thus the energy required is 31,350 kW-hr. If the RF power source works continuously at the rated output of 40 kW, it will take 33 days to heat the soil to the desired temperature of 150°C. But because the source will not operate at its rated capacity nor will it work continuously, the actual time required will be longer than 33 days.

A practical operating rate of the power source might be in the range of 70 to 80 percent of its rated capacity, or 28 to 32 kW. It was planned to shut down the RF power source three times every 24 hours to take temperature measurements. Each shut down was expected to last 30 to 60 mins. Thus power feed interruptions of 1.5 to 3 hrs in every 24-hr period were planned. Thus the energy output per day from the power source after accounting for planned interruptions and operating rate is 590 to 720 kW-hr/day. Thus a practical heating time for the soil treatment zone would be 44 to 54 days.

3. System Design Overview

Implementation of the RF technology for soil remediation requires two major subsystems; the RF heating system, and the effluent containment, collection, and treatment (ECCT) system. The RF heating system's purpose is to heat the soil to the required temperature range in the most efficient manner possible. The main components of the RF heating system are the RF power source, the coaxial transmission line, the matching network, the electrode array, the RF shield and RF chokes. The purpose of the ECCT system is to collect and treat the effluents generated during decontamination of soil in an environmentally benign and efficient manner.

A conceptual layout of the RF system configuration is shown in Figure 8. This figure shows all the major components of the heating system and how they are configured in the overall system. The electrode array determines the size of the volume heated by the process. The electrode array had three rows of vertically emplaced electrodes. The width of the array was 10 ft, length 17.5 ft and depth of 20 to 29 ft. The depth of the central row of electrodes was 20 ft while that of the outer rows was 29 ft. A RF shield was placed over the electrode array to mitigate RF radiation from the heated zone. The RF power was generated by the RF power source and conveyed over a co-axial cable to the array through two matching networks and a RF choke. The purpose of the matching networks was to optimize power transfer from the source to the array. These networks contain active and/or passive inductive and capacitive components which were adjusted during heating to optimize power transfer.

A vapor barrier is shown in the plan view. The purpose of the vapor barrier is to help control fugitive emissions from the site and to control the infiltration of air into the heated zone from the surface. The upper surface of the vapor barrier was covered with a thermal insulation blanket to minimize heat loss.

Gas collection lines leave the array and convey the hot gases to an on site vapor treatment system. Hot gases comprise of air, steam and vaporized contaminants present in the soil. Gases are collected from four places by means of application of a vacuum: the two outer rows of electrodes and from two horizontal perforated lines placed on the surface below the vapor barrier. A RF choke is used on the gas pipeline leaving the system to prevent the conduction of RF currents along the surface of the pipeline.

The temperature of the soil was measured by means of thermocouples mounted inside the electrodes and by periodically inserting fiber optic temperature measurement probes into thermowells. The thermocouple cables leaving the two outer rows of electrodes were connected to a data logger. The thermocouples in the excitor row and the fiber optic thermometer in the thermowells were read after shutting down the RF power.

The vapor treatment system utilized in this demonstration consisted of a propane flare in which the entire collected gas stream was burnt. The vacuum required for the collection and transport of the gases was provided by means of compressed air ejectors. The motive air used for the operation of the ejectors was mixed with the collected gases.




Figure 8. Conceptual Layout of the Demonstration System.

4. Electrode Array Design

Figure 7 (Page 32) is the surface level plan view of the electrode array. It shows the three rows of electrodes and their spacing. The three vertical sections AA, BB and CC of the array are displayed in Figure 9. In this figure the dotted lines show the electrodes in the two ground rows of electrodes, A1,C1,...,A8,C8. The depth of these electrodes was 29 ft. All of these electrodes except the ones at the four corners were perforated and connected to the gas collection system. The bottoms of these electrodes were capped. All the electrodes in the two ground rows were made from 2-in. diameter schedule 40 aluminum pipe. At the top the perforated ground electrodes were connected with each other within a row to form a gas collection manifold. Thermocouples were placed inside selected electrodes to obtain temperature data.

The excitor electrode of Section BB are illustrated by the solid lines in Figure 9. There were four excitor electrodes. The two outer electrodes were 3 in. dia. Type K copper tube and the two inner electrodes were 2 in. diameter type K copper tube. The depth of these electrodes was 20 ft. The tops of these electrodes were connected together by means of copper tube and Tees. A single RF feed line of 3 in. diameter was provided to the excitor electrode manifold. At the bottom of the excitor electrodes a brass sphere was welded to the electrode in order to increase the surface area of the tips of the electrodes in order to reduce the current density concentration at the tips. The sphere at the bottom of electrodes B1 and B4 had a diameter of 5.5 in. The sphere at the bottom of electrodes B2 and B3 had a diameter of 4.5 in. None of these electrodes were used for gas collection.

All the boreholes were drilled by means of hollow stem augers which were required to obtain undisturbed core samples of the soil while drilling for the electrode bore holes. As a result the ID of the bore hole was considerably larger than the OD of the electrodes. The annular gap had to be backfilled with either native material or else another material having similar clay, silt and sand levels. The soil borings obtained from the site contained large pieces of gravel mixed with plastic clay which was difficult to re-insert in the annular space between the electrode and the borehole. So the bore holes were backfilled with a mixture of clay and red "ball park sand". The clay was obtained from a materials yard and the sand was obtained from a local sand pit. The mixture was four volumes of the sand to one volume of the clay.

Figure 9 illustrates the outline of the RF shield which was made from corrugated aluminum sheeting curved to form a semi-circular cylinder of diameter 9 ft. The shield is described in another section later.




Figure 9. Vertical Sections , BB, CC of Electrode Array.

TABLE 8. ELECTRODE ARRAY DIMENSIONS--DESIGNED VS. IMPLEMENTED

| Dimension | Planned | Implemented |
|----------------------------------|---------|-------------|
| Depth of outer rows, ft | 29 | 29 |
| Depth of center row, ft | 24 | 20 |
| Length of the outer rows, ft | 17.5 | 17.5 |
| Length of the center row, ft | 7.5 | 7.5 |
| Separation of two outer rows, ft | 10 | 10 |

The design of the electrode array was changed in the field after the bore holes were drilled and the water table was discovered to be shallower than anticipated. The original design of the array required the excitor electrodes to be 24 ft deep. But the depth of the electrodes was reduced when the shallow water table was discovered. Table 8 compares the original dimensions of the array to that actually implemented.

Figure 10 illustrates a typical Section DD of the array. This figure shows the construction of the array near the surface. The drawing illustrates the locations of: the horizontal gas collection line place on the surface, the pea gravel fill, the contaminated soil overpack, the aluminum bus bar connecting the outer electrodes, the extended ground plane wire mesh, the vapor barrier, the thermal insulation and the bentonite-filled trench to make a seal between the soil surface and the vapor barrier.

Figure 11 illustrates a typical section EE. This view illustrates the interconnection of any two adjacent gas-collecting electrodes in the two outer rows. The tops of most of the electrodes in the ground row were connected to the branch leg of a Tee. The straight runs of the Tees were interconnected by means of short pieces of flexible silicone rubber hose clamped to pipe nipples threaded into the Tee.

A short piece of aluminum angle was also welded to each Tee. These were welded such that they bent towards the outside of the array. The electric bus bar was bolted to each of these angles to




Figure 10. Transverse Section DD of the Array Near Soil Surface.




Figure 11. Typical Section EE: Electrode Interconnection in Ground Rows A and C.

provide the current path from electrode to electrode. The bus bar was made from a strip of aluminum sheeting 2.5 ft long, and 3 in. wide.

5. RF Shield

Figure 12 illustrates the RF shield. The RF shield consisted of a semi-circular cylinder lying on its side. It was made by screwing together in the field pre-curved sheets of corrugated aluminum. The finished length of the shield was approximately 22 ft; 9 ft diameter. The ends of the cylinder were made from aluminum sheet. The height of the shield was 4.5 ft. Means of continuously venting the interior of the shield were provided. The vented air was passed through activated carbon drums.

6. Vapor and Gas Collection Lines

Figure 13 illustrates the network of pipes used to collect hot gases from the soil surface and at depth. The main gas line was split into four legs, each with its own ball valve and a vacuum gauge. The gases were collected from two perforated horizontal surface gas collection lines as well as from each of the two outer electrode rows. The surface gas collection lines were made from aluminum pipe. All lines were heat traced once they left the heated soil area. The ball valves were provided to adjust the vacuum level in each leg of the collection system.

7. Temperature Instrumentation

The soil temperature was measured by means of thermocouples attached to the inner walls of selected thermocouples and by inserting fiber optic thermometers into thermowells installed in bore holes located between the electrode rows.

Table 9 gives the distribution of the electrodes which were installed inside the electrodes. In both the ground row electrodes the thermocouples were installed at a depth of 1, 12, 24, and 29 ft. In the excitor row the thermocouples were installed at a depth of 1, 10, 20 ft.

In the original design the location of the thermocouples was selected to provide temperature data at four horizons of interest below the soil surface. These horizons were: the 1-ft depth, the mid point of the excitor electrodes, the tips of the excitor electrodes and the tips of the ground electrodes. However, during field installation of the electrode array the design of the excitor electrodes had to be changed because a shallow water table was encountered, contrary to expectations. At this time it was not possible to change the location of the thermocouples already




Figure 12. RF Shield (Stage #1 matcher enclosed under arch)




Figure 13. Vapor Collection Manifold.

TABLE 9. THERMOCOUPLE DISTRIBUTION INSIDE ELECTRODES

| | Ground Row A | Ground Row B | Excitor Row C |
|-------------------------|---------------|----------------|---------------|
| No. of Thermocouples | 11 | 16 | 12 |
| Electrodes with T/Cs | A2,A3,A4 | C1,C2,C3,C4,C6 | B1,B2,B3,B4 |
| Total No. of Electrodes | 8 | 8 | 4 |
| Depths of T/Cs, ft | 1, 12, 24, 29 | 1, 12, 24, 29 | 1, 10, 20 |

installed in the ground electrodes. Thus the four temperature measurement horizons are not true horizontal planes as is evident from Table 9.

The location of the thermocouples in the array is presented graphically in Figures 14 through 16. The thermocouple location is marked with a X. Figure 17 illustrates the method of thermocouple attachment to the electrode wall. All thermocouples were Type K with a 1/16 in. SS 304 sheath. The junctions were ungrounded. The sheaths on these thermocouples were long enough so that the transition from sheath to wire occurred above ground. The thermocouple wires were run inside conduit to minimize RF pick up. A separate conduit was not necessary. For the excitor electrodes the thermocouple sheaths were run inside the tubular RF bus supplying power to the center row. For the two ground rows the thermocouples were run inside the vapor collection conduit attached to the tops of the ground electrodes.

All the thermocouples from the ground electrodes were connected at the surface to a data logger through a multiplexer. Data was recorded by the data logger once every 4 hours. The data were available for inspection on a PC screen which was refreshed every 2 min. The measurement of temperature in the excitor row required the RF power to be switched off. Then the thermocouple wires were plugged into a hand held thermometer and the temperature of the 12 measurement points in the excitor electrodes was manually entered into the project log book. These readings were taken once every 8 to 12 hours.

Temperature of the soil in the region between the electrodes was taken by inserting a fiber optic probe into thermowells placed




Figure 14. Thermocouple Locations in Plane AA.




Figure 15. Thermocouple Locations Plane BB.




Figure 16. Thermocouple Locations in Plane CC.





Figure 17. Typical Thermocouple Installation Within Electrode.

Figure 18. Surface-Level Plan View of the Array. Electrode (●) and Thermowell (▲) Locations.



in bore holes. Figure 18 shows the locations of the seven thermowells marked TW1 through TW7. In each thermowell location a bundle of teflon tubes sealed at the bottom was placed in a borehole. The tubes in the bundle were of different lengths so that the temperature could be measured as a function of depth. In TW1 through TW6 there were six tubes in each bundle. These tubes were installed such that their bottoms terminated at depths of 1, 12, 24, 29, 31 and 34 ft below the heated surface. These depths were selected to correspond to the depths of thermocouples in the electrodes. These thermowells had two additional depths of 31 and 34 ft. to investigate what effect if any there was below the electrode array. Thermowell TW7 had three tubes installed at depths of 12, 24 and 29 ft. Thermowell TW7 was installed approximately 3 ft outside the array directly opposite electrode C4. The temperature at the bottom of each tube was measured by inserting the fiber optic probe in each tube one at a time. The bottoms of each plugged tube was filled with a small amount of silicone oil to help facilitate temperature equilibration between the thermowell and the fiber optic probe. The fiber optic temperature measurements of all the thermowells were made and recorded once every 24 hours. However, four probes were left in selected thermowells and these could be measured whenever desired. Measurements taken by fiber optic probes do not require shutting down of the RF power.

VI. DEMONSTRATION OPERATION

A. SYSTEM START UP

The RF heating system was turned on at Noon on April 3, 1993. Prior to this time, the vapor collection system had been operational for several days, collecting gases and vapors from the soil volume which was at ambient temperature. Initially power to the array was applied at low levels in the range of 0-5 kW. During this time the system was stabilized and measurements of radiated E (electric) and H (magnetic) fields were made in the vicinity of the demonstration system. The purpose of these measurements was to ensure that there were no unsafe levels of radiated fields. Another set of measurements was made at the low input power level for assessing near and far field radio frequency interference (RFI).

The input power was gradually increased over the next two days until on April 5, 55 hours after start up, the input power reached the rated capacity of power source. After attaining the rated power operation, additional measurements were made to assure that there was no radio frequency interference as a result of the demonstration project. RFI measurements were made near the test site, and at distances of 0.5 and 1 mile from the array.

The safety measurements were made at least three times every day during the course of the demonstration.

B. CHRONOLOGY OF EVENTS

Table 10 summarizes the highlights of the demonstration experiment. A detailed summary of events culled from the project log books is presented in Appendix A. The central volume of soil between electrodes (A3,C3,C6,A6) reached an average temperature of 100°C in the period April 22 to April 24, 1993. The average temperature in this zone reached the target temperature of 150°C by May 15, 1993. However, on May 18, 1993, RF power matching difficulties were encountered which were to stay with us for the remaining duration of the experiment. As it will be discussed in Section 7, these were due to extreme hot spots located in the excitor row which caused melting of the copper electrodes. As the temperature data will show, no substantial increase in temperature of the heated zone occurred after the matching difficulties started.

Attempt to continue heating of the soil after May 18 were made in the hope of maximizing the volume of soil inside the array which gets heated to 150°C. The heating experiment was terminated on June 3, at Noon.

Table 10. Chronology of Selected Events

| Date | Event |
|--------------------|---|
| 4/3/93 | Started Heating |
| 4/6/93 | Excitor Row reaches 99° C |
| 4/19/93 | Excitor Row reaches 100° C |
| 4/22 to 4/24/93 | Central volume defined by (A3,C3,C6,A6) reaches an average temp. of 100° C |
| 5/6 to 5/11/93 | Temperature at measurement point B2A started increasing faster than the other points. 253° C on 5/6; 740° C on 5/11 |
| 5/15/93 | Central volume defined by (A3,C3,C6,A6) reaches an average temp. of 150° C |
| 5/18/93 | RF power matching difficulties start |
| 5/30/93 | Tracer injection experiment was performed |
| 6/3/93 | Heating was terminated |

C. DATA RECORDED AND PARAMETERS MONITORED

1. RF Power Delivery System:

During the course of the demonstration project the following measurements were made regarding the operation of the RF system:

- Forward and reflected power at the array (upstream of the Stage 1 matcher)
- Net input power was calculated by difference of the forward and reflected power
- Vector voltmeter reading: V_a , V_b and phase angle
- Forward and reflected power as measured at the output of the RF power source

The above measurements were recorded in the project log book at least once every 2 to 3 hours of operation

The following parameters were monitored by the operators:

- Settings on the RF power amplifier
- Reflected and forward power as measured at the power

- source with suitable adjustments to the Stage 2 matching network to maintain zero reflected power
- Monitoring of the vector voltmeter readings

The above parameters were monitored on a semi-continuous basis. All the necessary gauges and controls were arrayed at the operator's work bench.

Once in every 8 hour shift, the operator would survey the RF equipment with a portable E and H field probe to assure that any radiation from the equipment was at safe levels.

2. Soil Temperature Data

The following measurements were made once in 24 hours:

- Measurement of the thermowell temperature by manually inserting fiber optic probes into each thermowell. There were six thermowell locations inside the electrode array each containing 6 thermowells. One thermowell was outside the array and its temperature was monitored by the data logger.

The following measurements were made once every 8 to 12 hours:

- Measurement of the temperature from the 12 thermocouples installed in the excitor electrode row. These measurements were made during shift changes after shutting down the RF power input to the soil.

The following measurements were made once every 4 hours:

- The thermocouples in the two outer row of electrode, the ground rows, were logged automatically by the data logger once every four hours. This included the measurement of thermowell TW7 temperatures also. In addition, the operator manually wrote down the temperature readings from the PC display once every 2 to 3 hours.

In addition to the above measurements, the ground row temperatures were monitored on a semi-continuous basis from the PC display where the data was updated every 2 minutes.

3. Vapor Collection and Treatment System

This system was operated and maintained by HALLIBURTON NUS personnel. However, the following data were also recorded by IITRI personnel:

- Vacuum level in each of the four legs of the gas

collection system

- Total flow rate exiting the ejectors and entering the flare
- Flow rate and pressure of compressed air supplied to the ejector system
- Vacuum at the inlet of the ejectors
- Temperature of the heat traced vapor collection lines

VII. DEMONSTRATION TEST DATA

A. SOIL TEMPERATURE DATA

1. Summary

As mentioned in Section 6, in situ heating of the soil was begun on April 3, 1993. Power was initially applied to soil at 16:40 hours. The center row of electrodes reached a temperature of 99°C by April 6 and it reached 150°C by April 19. Figure 19 illustrates the electrode array showing the location of the electrodes and thermowells. Thermocouples were attached to the inner walls of many electrodes to measure temperature as explained in detail in Section 5.

Figure 20 illustrates the average soil temperature within two zones of the electrode array. These zones are referred to as Volume I and Volume II. Volume I is the soil contained within the two outer electrode rows and the center row of electrodes, defined by electrodes (A3, C3, C6, A6). As Figure 20 shows, the average soil temperature in Volume I exceeded 150°C for a number of days. In fact the average in this zone peaked at approximately 280°C. The reason for the high average temperature in this volume was the presence of extreme hot spots that developed along the center row of electrodes which melted the copper tube used for the fabrication of the electrodes. Melting point of copper is 1083°C. As will be shown later, there were large temperature non-uniformities in the transverse direction. For example, while the temperature in the center row reached copper's melting point, the temperature in the two ground rows did not exceed 110°C.

It is estimated that the region defined as Volume I is approximately 56 cu. yd. It should be noted that due to the large temperature range within this zone, every temperature measuring point was not at 150°C. It is estimated that 34 cu. yd. of soil was heated such that every measurement point within it achieved and maintained 150°C for long period (>100 hours) of time.

Figure 19 illustrates a second region of soil called Volume II. This area of the array is outside the central row of electrodes and it is bounded by electrodes (A1,C1,C2,A2). It was anticipated that the energy dissipation in this area would be reduced, and, as anticipated, the average temperature of Volume II was less, in the range of 60° to 70°C. It is estimated that Volume II is 18.5 cu. yd. However, due to symmetry considerations, there is another volume of similar size at the opposite end of the array (bounded by electrodes A7,C7,C8,A8) which probably experienced a similar temperature history. There were no temperature measurement points in the opposite end of the array. Thus total volume where

**Figure 19. Electrode Hole and Thermowell Layout
(Plan)**





Figure 20
 AVERAGE TEMPERATURE IN THE ARRAY, C
 (In Volume I and II)



Average Temperature, C

the average temperature was in the range of 60°C to 70°C is estimated to be 37 cu. yd.

There is an intermediate temperature region between Volumes I and II where the average temperature was in the range of 70° to 150°C. It was estimated that the volume of soil where every measurement point equalled or exceeded 100°C is 93 cu. yd. This was estimated by the data presented in the spatial temperature distribution plots presented in a later section herein and in Appendix B.

As mentioned above, there was clear evidence that the copper electrodes in the central row melted due to very high temperatures achieved in this row. Copper melts at 1083°C. Evidence of fused electrodes was recovered during post demonstration demobilization activities from each of the four electrode bore holes B1 to B4. An examination of the complete temperature data presented in Appendix B shows that the melting point of copper was first exceeded at the bottom of electrode B2, as measured by thermocouple B2C. This occurred sometime between May 19 and May 20. The other two measurement points in electrode B2 exceeded the melting point of copper between May 25 and May 26. During the same time, temperature point B3B and B1C also reached or exceeded the melting point of copper. It should be noted that of the 12 temperature measuring points within the center row, only five points reached the melting point of copper and one other fell just short of it by 20°C.

The evidence obtained from the field indicated that every excitor electrode melted. Each of the locations of these electrodes was redrilled with a hollow stem auger. From each hole, electrode pieces were recovered. However, no hole yielded an amount of copper sufficient to account for all the material in an electrode. Due to this it is likely that nearly complete melting of all four electrodes took place. From each hole, nearly intact top section of the electrode was recovered. These varied in length from 6 in. to 24 in.

It is also possible that the thermocouples lost their accuracy once the temperature exceeded 899°C, which is the continuous-duty temperature rating of the thermocouples used in this field experiment. This rating is imposed by the design of the SS 304 sheath used with the Type K, Chromel-Alumel thermocouples used in the field. The chromel alumel thermocouple itself may be used with high temperature sheaths, for measuring temperatures up to 1260°C. SS304 melts in a temperature range of 1400 to 1454°C so it is unlikely that a total failure of the thermocouple sheath occurred.

One possible reason for the overheating of the electrodes in the center row of electrodes was the close proximity of the

electrode tips to the water table. This is a possible reason because RF fields will hunt out and concentrate towards water or other polar fluid if present in the vicinity.

The actual depth to water table inside the heated volume during the course of heating is unknown. However, during site preparation activities, four dewatering wells were installed at the four corners of the array area, outside the perimeter of the vapor barrier. There was a water table monitoring point inside the array. One of the electrode bore holes was used for this purpose until it became necessary to remove the piezometer in order to complete the array. The dewatering wells were operated continuously (barring brief shut downs for maintenance and one power failure) in an attempt to keep the water level depressed.

Water level measurements were made in the central piezometer in the period February 2, 1993 to February 11, 1993. Water level was in the range of 22.47 ft to 23.84 ft below ground surface. In the above mentioned time period water table levels decreased by approximately 1 to 1.5 ft. Dewatering wells were operational during this period.

2. Excitor Row Temperatures

Figure 21 illustrates the average temperature in the excitor (Center row) row of electrodes as a function of time and depth. The temperature was measured in each electrode at three depths-- 1 ft, 10 and at the bottom, at approximately 19.5 ft (shown as 20 ft in the Figures). Complete temperature data of the excitor electrodes is presented in Appendix B along with additional graphs.

3. Ground Row Temperatures

Figure 22 illustrates the average temperature of the thermocouples inserted in ground row electrodes. The data is presented as a function of time and depth of insertion. The graph also shows the average of those thermocouples measurement points which were opposite the excitor electrodes B1 to B4. As the graph shows, the average temperature of the ground row measurement points did not exceed 100°C. Although the average was maintained in the temperature range of 85 to 90°C for long period of time. There was one measurement point in electrode A4 which exceeded 100°C. Complete data tables and additional graphs of temperature for the ground electrodes are presented in Appendix B.

4. Thermowell Temperatures

Figure 23 illustrates the average temperature as measured in the six thermowells located inside the array. There was a seventh thermowell located outside the array, opposite electrode C4.

Excitor Row Average Temperature

Figure 21





Figure 22
Ground Rows Average Temperature



Temperature, C

Average Thermowell Temperature vs. Time

Figure 23




Figure 19 illustrates the thermowell locations. A detail description of the thermowells was presented in Section 5. As the data show, the average thermocouple temperature at a depth of 1-ft reached 140°C towards the end of the demonstration. Similarly the average at the 12 foot level reached 130 to 140°C range. The 24-foot level reached approximately 50°C. During the course of the test, attempts were made to make measurements at a depth of 20 ft in a thermowell which was inserted to a depth of 24 ft. These data show that the average temperature at the 20 ft level reached almost 130°C. It should be noted that these averages include measurements made in TW1 which is on the edge of the array and it consistently showed temperatures much less than the other thermocouples. TW3 was the other thermowell inside the array to exhibit lower temperatures.

Additional temperature data from the thermowells is presented in Appendix B.

5. Temperature Outside the Array

There was one thermowell, TW7, which was placed in a bore hole three feet outside Ground Row C. This hole was located opposite electrode C4. This thermowell had measurement points at depths of 12, 24, and 29 ft. The data is presented as a function of time and depth in Figure 24. At a depth of 12 ft, a maximum temperature of approximately 65°C was achieved. At a depth of 24 ft. the temperature was on the range of 35 to 40°C at the time of shut down. Appendix B illustrates curves in which the temperature in TW7 is compared with the temperature inside the nearest electrode, C4.

6. Temperature During Cool Down

Figure 25 illustrates the average temperature of the two ground rows as a function of depth and time during cool down. As the curves show, the soil cooling rate was quite small despite the continued operation of the vacuum extraction system.

7. Spatial Temperature Distributions

The spatial temperature distribution in five different vertical planes intersecting the electrode array was plotted. Figure 26 defines the locations of the five vertical planes. These were labelled: LONG, LNGU, TRANS, TRNS, and TRNV. The first two are longitudinal vertical planes aligned with the length of the array. The other three are transverse vertical planes, aligned with the width of the array. For illustrative purposes, the spatial distribution as a function of time for plane TRANS is presented here. The remaining distributions are presented in Appendix B.

Figure 24
OUTSIDE THERMOWELL (TW7) TEMPERATURES
(All Depths)




Figure 25
Ground Rows Average Temperature
(Since 12:00hr, June 3, 1993)




Figure 26. Definition of Vertical Planes for Temperature Distribution (Plan)




Figure 27. Transverse Temperature Distribution in Plane TRANS
 (Depth: 1 ft)




Figure 27 illustrates the spatial temperature distribution in transverse plane labelled TRANS. This is the central plane running perpendicular to the length of the array and it intersects all three rows. Figure 27 shows the temperature profile at a depth of 1 ft. As indicated earlier, ground row temperature at C4 did not exceed 100°C. Temperature at A4 did exceed 100°C towards the end of the experiment. The data shown in this and other spatial distribution figures were selected at approximately one week intervals, after the first day of operation. It should be noted that after 1085 hours, operating difficulties were noted relating to the stability of the electrical match between the load impedance and the impedance of the power source. Temperature at many measurement points decreased after this time, even though attempts were made to continue power input to the soil.

Figure 28 illustrates the transverse temperature distribution at a depth of 10 to 12 ft. B2 was the only measurement point at a depth of 10 ft; all others were at 12 ft. This figure shows the high temperature attained by thermocouple B2B at 1250 hours after start of the demonstration. Figure 29 illustrates the transverse temperature distribution in a depth range of 20 to 24 ft. It should be noted that in this figure, the only measurement point at 20 ft was that in electrode B2, all others were at 24 ft.

B. ANALYSIS OF SOIL FOR TOTAL PETROLEUM HYDROCARBONS

Soil samples obtained from the field by HALLIBURTON NUS were handed over to SAIC, USEPA's contractor for analysis. However, IITRI also performed analysis on the samples using the California DHS method for the analysis of Total Petroleum Hydrocarbons (TPH) expressed as diesel range organics. This was done so that the results may be compared with the results of the Bench scale studies done by IITRI.


The soil samples were shipped to IITRI in coolers after SAIC had finished its analyses of the soil sample. Thus there was a long storage period for these samples, much more than the customary 14 days allowed by many QA/QC procedures. Storage in IITRI was in the original jars which were kept in a refrigerator.

1. Pre-Demonstration Soil Samples

The soil was analyzed by means of methylene chloride extraction followed by extract concentration and analysis of the concentrate by a GC/FID. A solution of diesel in methylene chloride was used to prepare a multi-point calibration curve for the instrument.

Tables 11, 12, and 13 summarize the results of Soil moisture determination, TPH analysis and QA/QC sample analysis,

Figure 28. Transverse Temperature Distribution in Plane TRANS
(Depth: 10-12 ft)






TABLE 11. DETERMINATION OF MOISTURE IN PRE-DEMONSTRATION SOIL SAMPLES

| Reference No. | Sample Hole Location | Sample Depth Code | Depth Interval ft | Percent Water | Comment |
|---------------|----------------------|-------------------|-------------------|---------------|---------------------------|
| 1 | EA01 | U0406 | 4-6 | 22.0% | |
| 2 | EA01 | U0406 | 4-6 | 20.4% | Duplicate of No. 1 above |
| 3 | EA02 | U1214 | 12-14 | 26.5% | |
| 4 | EA03 | U0204 | 2-4 | 19.9% | |
| 5 | EA03 | U1618 | 16-18 | 15.9% | |
| 6 | EA04 | U0002 | 0-2 | 17.2% | |
| 7 | EA04 | U2022 | 20-22 | 11.0% | |
| 8 | EA05 | U2224 | 22-24 | 10.7% | |
| 9 | EA07 | U0810 | 8-10 | 20.7% | |
| 10 | EA07 | U1214 | 12-14 | 26.4% | |
| 11 | EA08 | U1416 | 14-16 | 23.6% | |
| 12 | EA08 | U2830 | 28-30 | 10.1% | |
| 13 | EB01 | U0002 | 0-2 | 21.1% | |
| 14 | EB01 | U1214 | 12-14 | 27.1% | |
| 15 | EB02 | U0406 | 4-6 | 21.5% | |
| 16 | EB02 | U0810 | 8-10 | 20.3% | |
| 17 | EB03 | U0204 | 2-4 | 16.2% | |
| 18 | EB03 | U0204 | 2-4 | 18.9% | Duplicate of No. 17 above |
| 19 | EB03 | U1012 | 10-12 | 19.3% | |
| 20 | EB04 | U1416 | 14-16 | 21.0% | |
| 21 | EB04 | U2022 | 20-22 | 16.8% | |
| 22 | EC02 | U0608 | 6-8 | 22.9% | |
| 23 | EC02 | U2022 | 20-22 | 8.9% | |
| 24 | EC03 | U0002 | 0-2 | 22.0% | |
| 25 | EC03 | U1820 | 18-20 | 24.2% | |
| 26 | EC03 | U2224 | 22-24 | 9.0% | |
| 27 | EC03 | U2224 | 22-24 | 9.9% | Duplicate of No. 26 above |
| 28 | EC05 | U1012 | 10-12 | 11.0% | |
| 29 | EC05 | U1012 | 10-12 | 11.5% | Duplicate of No. 28 above |
| 30 | EC06 | U0204 | 2-4 | 18.2% | |
| 31 | EC06 | U1820 | 18-20 | 20.6% | |
| 32 | EC07 | U0406 | 4-6 | 16.0% | |
| 33 | EC07 | U0406 | 4-6 | 20.0% | Duplicate of No. 32 above |
| 34 | EC08 | U0406 | 4-6 | 20.0% | |
| 35 | EC08 | U0406 | 4-6 | 16.4% | Duplicate of No. 34 above |
| 36 | EC08 | U1416 | 14-16 | 19.7% | |
| 37 | EC08 | U2224 | 22-24 | 9.8% | |
| 38 | TW01 | U1416 | 14-16 | 22.0% | |
| 39 | TW02 | U0406 | 4-6 | 19.6% | |
| 40 | TW02 | U1416 | 14-16 | 25.7% | |
| 41 | TW02 | U1416 | 14-16 | 23.4% | Duplicate of No. 40 above |

TABLE 12. DETERMINATION OF TPH IN PRE-DEMONSTRATION SOIL SAMPLES

| Reference No. | Sample Hole Location | Depth Interval ft. | Gas Chromatograph | | TPH Conc. In soil ppm dry basis | TPH Conc. In soil ppm dry basis | No. of Peaks in Diesel Range | Was Extract Diluted? Yes/No | Comments |
|---------------|----------------------|--------------------|-------------------|------------------|---------------------------------|---------------------------------|------------------------------|-----------------------------|----------|
| | | | Sample Depth Code | Sample Batch No. | | | | | |
| 1 | EA01 | U0106 | 4-6 | MC-23 | 6 | 47 | 61 | 31 | N |
| 3 | EA02 | U1214 | 12-14 | MC-28 | 7 | 240 | 326 | 43 | N |
| 4 | EA03 | U0204 | 2-4 | MC-35 | 8 | 30 | 37 | N | |
| 5 | EA03 | U1618 | 16-18 | MC-4 spike dl | 3 | 6935 | 8317 | 58 | |
| 5 | EA03 | U1618 | 16-18 | MC-4 dl | 3 | 6935 | 8120 | 55 | |
| 6 | EA04 | U0002 | 0-2 | MC-27 | 7 | 13 | 15 | 39 | |
| 7 | EA04 | U2022 | 20-22 | MC-20 | 6 | 2443 | 2716 | 67 | |
| 7 | EA04 | U2022 | 20-22 | MC-20RE | 6 | 2226 | 2727 | 60 | |
| 7 | EA04 | U2022 | 20-22 | MC-38 | 6 | 2318 | 2605 | 88 | |
| 8 | EA05 | U2224 | 22-24 | MC-7 dl | 2 | 2954 | 2800 | 85 | |
| 9 | EA07 | U0810 | 8-10 | MC-31 | 7 | 78 | 96 | 28 | |
| 10 | EA07 | U1214 | 12-14 | MC-14 | 5 | 21 | 29 | 32 | |
| 10 | EA07 | U1214 | 12-14 | MC-14RE | 6 | 12 | 17 | 30 | |
| 10 | EA07 | U1214 | 12-14 | MC-14RE | 7 | N.D. | N.D. | 32 | |
| 11 | EA08 | U1416 | 14-16 | MC-34 | 6 | 27 | 35 | 40 | |
| 12 | EA08 | U2830 | 28-30 | MC-29 | 7 | 413 | 460 | 82 | |
| 13 | EB01 | U0002 | 0-2 | MC-37 | 8 | 329 | 417 | 36 | |
| 14 | EB01 | U1214 | 12-14 | MC-8 | 3 | 39 | 53 | 58 | |
| 15 | EB02 | U0408 | 4-6 | MC-6 | 1 | 65 | 82 | 87 | |
| 15 | EB02 | U0408 | 4-6 | MC39 | 9 | 171 | 218 | 45 | |
| 16 | EB02 | U0810 | 8-10 | MC-26 | 7 | 187 | 234 | 25 | |
| 17 | EB03 | U0204 | 2-4 | MC-1 | 3 | N.D. | N.D. | 28 | |
| 19 | EB03 | U1012 | 10-12 | MC-24 | 6 | 3027 | 3751 | 42 | |
| 20 | EB04 | U1416 | 14-16 | MC-15 | 5 | 821 | 1030 | 54 | |
| 21 | EB04 | U2022 | 20-22 | MC-18 | 5 | 1049 | 1260 | 49 | |
| 21 | EB04 | U2022 | 20-22 | MC-18 | 6 | 1049 | 1261 | 56 | |
| 21 | EB04 | U2022 | 20-22 | MC-40 | 6 | 1490 | 1791 | 60 | |

N.D.: None Detected

Shaded Results: In these the TPH area response was less than or equal to Average method blank area + three times standard deviation of the blanks

RE: Extract re injected, Duplicate: duplicate extraction/injection; dl: extract was diluted

TABLE 12. DETERMINATION OF TPH IN PRE-DEMONSTRATION SOIL SAMPLES

| Reference No. | Sample Hole Location | Sample Depth Code | Depth Interval ft. | Gas Chromatograph | | TPH Conc. In soil ppm | TPH Conc. In soil ppm | No. of Peaks in Diesel Range | Was Extract Diluted? Yes/No | Comments |
|---------------|----------------------|-------------------|--------------------|-------------------|-----------------|-----------------------|-----------------------|------------------------------|-----------------------------|--------------------------------|
| | | | | Sample Batch No. | No. re-injected | | | | | |
| 22 | EC02 | U0008 | 0-8 | MC-2 | 1 | 351 | 455 | 64 | N | |
| 22 | EC02 | U0008 | 6-8 | MC-2RE | 2 | 341 | 443 | 61 | N | |
| 23 | EC02 | U2022 | 20-22 | MC-32 | 8 | 2597 | 2852 | 58 | N | |
| 24 | EC03 | U0002 | 0-2 | MC-12 | 4 | 34 | 44 | 39 | N | MC-2 re-injected |
| 25 | EC03 | U1820 | 18-20 | MC-21 | 6 | 5499 | 7257 | 50 | N | |
| 25 | EC03 | U1820 | 18-20 | MC-21 DIL | 7 | 9239 | 12194 | 55 | Y | |
| 26 | EC03 | U2224 | 22-24 | MC-5 | 2 | 4287 | 4710 | 69 | Y | |
| 26 | EC03 | U2224 | 22-24 | MC-5 DUP. | 2 | 3964 | 4400 | 58 | Y | MC-5 duplicated |
| 26 | EC03 | U2224 | 22-24 | MC-5 DUP. | 2 | 4003 | 4443 | 58 | Y | Re-injection of MC-5 duplicate |
| 28 | EC05 | U1012 | 10-12 | MC-3 | 3 | 865 | 972 | 50 | N | |
| 28 | EC05 | U1012 | 10-12 | MC-3D2 | 3 | 966 | 1110 | 61 | Y | MC-3 diluted, X 22.2 |
| 28 | EC05 | U1012 | 10-12 | MC-3 dW | 3 | 862 | 960 | 62 | Y | MC-3 diluted, X 7.41 |
| 29 | EC05 | U1012 | 10-12 | MC-25 | 6 | 463 | 523 | 38 | N | MC-3 duplicate |
| 30 | EC06 | U0204 | 2-4 | MC-30 | 7 | 68 | 83 | 36 | N | |
| 31 | EC06 | U1820 | 18-20 | MC-33 | 8 | 3126 | 3936 | 55 | N | |
| 31 | EC06 | U1820 | 18-20 | MC-33RE | 9 | 3148 | 3905 | 67 | N | |
| 31 | EC06 | U1820 | 18-20 | MC-33dW | 10 | 3228 | 4066 | 54 | Y | MC-33 re-injected |
| 32 | EC07 | U0408 | 4-6 | MC-16 | 5 | 26 | 31 | 35 | N | MC-33 diluted |
| 34 | EC08 | U0408 | 4-6 | MC-16 | 5 | 20 | 25 | 31 | N | |
| 36 | EC08 | U1416 | 14-16 | MC-9 | 3 | N.D. | N.D. | 41 | N | |
| 36 | EC08 | U1416 | 14-16 | MC-17 | 6 | 52 | 65 | 44 | N | Duplicate of MC-9 |
| 37 | EC08 | U2224 | 22-24 | MC-10 | 4 | 1945 | 2156 | 52 | N | |
| 38 | TW01 | U1416 | 14-16 | MC-22 | 6 | 504 | 646 | 58 | N | |
| 39 | TW02 | U0408 | 4-6 | MC-11 | 4 | 31 | 39 | 35 | N | |
| 40 | TW02 | U1416 | 14-16 | MC-36 | 6 | 426 | 573 | 49 | N | |

N.D.: None Detected

Shaded Result: In these the TPH area response was less than or equal to
Average method blank area + three times standard deviation of the blanks

RE: Extract re-injected, Duplicate: duplicate extraction/injection; dil: extract was diluted

TABLE 13. DETERMINATION OF TPH IN PRE-DEMONSTRATION SOIL SAMPLES
QA/QC SAMPLES

| Gas Chromatograph Sample Batch No. | TPH Conc. In sample mg/ml As Analyzed | TPH Conc. In sample mg/ml Actual | Error % | Comments |
|------------------------------------|---------------------------------------|----------------------------------|---------|---|
| KQA-1 | 3 | 4.33 | 4.12 | 5.1% QA/QC Control Sample for Checking of GC |
| KQA-2 | 3 | 2.18 | 2.13 | 2.6% QA/QC Control Sample for Checking of GC |
| MCMB-2 | 3 | N.D. | 0 | Method Blank (TPH Area: 14,151) |
| MC-13 | 4 | 0.04 | 0 | Method Blank (TPH Area: 18,033) |
| KQA-3 | 4 | 5.78 | 5.52 | QA/QC Control Sample for Checking of GC |
| KQA-4 | 4 | 2.95 | 2.76 | QA/QC Control Sample for Checking of GC |
| KQA-4 | 5 | 2.84 | 2.76 | QA/QC Control Sample for Checking of GC |
| KQA-3 | 6 | 5.60 | 5.52 | QA/QC Control Sample for Checking of GC |
| KQA-4 | 6 | 2.81 | 2.76 | QA/QC Control Sample for Checking of GC |
| KQA-F | 7 | 1.91 | 1.93 | -1.0% QA/QC Control Sample for Checking of GC |
| KQA-3 | 7 | 5.78 | 5.52 | 4.7% QA/QC Control Sample for Checking of GC |
| KQA-F | 9 | 1.94 | 1.93 | 0.3% QA/QC Control Sample for Checking of GC |
| KQA-3 | 9 | 5.62 | 5.52 | 1.9% QA/QC Control Sample for Checking of GC |
| MC-43 | 10 | 0.33 | 0 | Method Blank with spike: 1 ml. of 7.638 mg/ml |
| MC-41 | 10 | 0.04 | R | Method Blank, no spike (TPH Area: 20,020) |
| MC-42 | 10 | 0.25 | R | Method Blank with spike: 1 ml. of 1.92 mg/ml |

N.D.: None Detected

R: Spike recovery calculation made separately in Table 14

respectively. Thirty four different samples were analyzed. The results show that the soil concentration varies from less than 35 ppm to 9200 ppm (as received). On a dry basis the concentration ranges from less than 44 to 12,200 ppm. In a number of samples it was observed that there were compounds present, outside the diesel window, towards the higher boiling end. These have not been included in the reported results. There were eight samples in which the concentration (as received) was in the range of 12 to 34 ppm. In these eight samples, the TPH area count is within 3 standard deviations of the area count of the method blanks.

Table 14 is a summary of the spiked sample analyses. Two types of spiked samples were analyzed. First, the soil as received from the field was spiked with a known amount of TPH. Then the spiked soil was extracted and the extract analyzed on the GC/FID. The results were compared (through a mass balance on TPH) with the results of the unspiked field soil to determine the percent recovery. The percent recovery ranged between 200 and 320 percent. It should be noted that the TPH concentration reported in Table 12 has not been corrected by the recovery efficiency.

In the second type of spiking experiment, a method blank was spiked with a known amount of TPH (Table 14). The recovery was calculated by a mass balance on TPH. The mass balance was done by a comparison of TPH mass in unspiked method blank versus the spiked method blank. The recovery of TPH from spiking of the method blanks was in the range of 103 to 130 percent.

Table 15 is a summary of sample duplicates. Four samples were extracted and analyzed in duplicate. The relative percentage difference (RPD) ranges from 2.5 to 100 percent. The low concentration sample gave the 100 percent RPD. In four cases, the prepared extract was injected twice into the GC/FID to test the reproducibility of the instrument. The RPD was in the range of 0.4 to 1.5 percent. In one case, a low concentration (less than 21 ppm) sample was injected three times which yielded a relative standard deviation of 96 percent.

2. Post-Demonstration Soil Samples

The post demonstration soil samples were analyzed in a similar manner as the pre-demonstration soil samples. Even these samples had a long storage period as mentioned earlier.

Twenty one post-demonstration soil samples were analyzed by the California DHS method. The result of these analyses are presented in Table 16. The concentrations of soil moisture and TPH are presented in the table.

TABLE 14. SPIKE RECOVERY

RECOVERY OF TPH SPIKES FROM SOIL

| Ref. No. | Sample Nos. | TPH Conc. in Soil as Received ppm | Amount Spiked Equivalent, ppm | Total TPH Conc. in Spiked Soil ppm | Spike Recovery % |
|-------------|------------------------|--|----------------------------------|--|------------------------|
| 5 | MC-4 MC-4 spike,dil | 6835 | 50 | 6995 | 320 |
| 15 | MC-6 MC-39 | 65 | 46.2 | 171 | 229 |
| 21 | MC-18 MC-40 | 1049 | 218 | 1490 | 202 |

RECOVERY OF TPH SPIKE FROM METHOD BLANKS

| | Total TPH mg | Recovery % |
|------------------------------|-----------------|---------------|
| Unspiked Method Blank: | 0.4 | --- |
| Method Blank + 1.92 mg spike | 2.5 | 130 |
| Method Blank + 7.64 mg spike | 8.25 | 103 |

TABLE 15. RESULTS OF DUPLICATE ANALYSIS

RESULTS OF DUPLICATE EXTRACTIONS/GC ANALYSIS

| Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm |
|------------------|------------------------------|---------------|------------------------------|----------------|------------------------------|---------------|------------------------------|
| MC-5 MC-5dup | 4287 3984 | MC-25 MC-3 | 463 908 | MC-20 MC-38 | 2435 2318 | MC-9 MC-17 | 0 52 |
| Average R.P.D | 4136 3.7% | | 686 32.0% | | 2377 2.5% | | 26 100.0% |

RESULTS OF DUPLICATE GC INJECTIONS

| Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm | Sample No. | TPH Conc. as received ppm |
|------------------|------------------------------|----------------|------------------------------|----------------------|------------------------------|------------------|------------------------------|-----------------------------|------------------------------|
| MC-20 MC-20RE | 2443 2426 | MC-2 MC-2RE | 351 341 | MC-5DUP MC-5DUPRE | 3984 4003 | MC-33 MC-33RE | 3126 3148 | MC-14 MC-14RE MC-14RE | 21 12 0 |
| Average R.P.D | 2434.5 0.4% | | 346 1.5% | | 3983.5 0.5% | | 3137 0.4% | | 11 |

TABLE 16. POST DEMONSTRATION SOIL ANALYSIS FOR TPH BY CALIFORNIA METHOD AND MOISTURE BY WEIGHT LOSS IN OVEN
(Preliminary Results Subject to Review and Correction)

| Sample No. | Sample Depth ft | Percent Water | Gas Chromatograph File No. | Date Injected | Regression Reference | No. of Was Extract mg/ml as received | No. of Was Extract Diluted? Yes/No | Comments |
|-------------|-----------------|---------------|----------------------------|---------------|----------------------|--------------------------------------|------------------------------------|----------|
| EA01A U0008 | 0-8 | 5.0% | F120 | Final20 | 05/06/94 NSMSTR01 | 0.91 | 128 | 134 |
| EA02A U1410 | 14-16 | 10.7% | F116 | Final21 | 05/06/94 NSMSTR01 | 1.99 | 300 | 443 |
| EA02A U1410 | 14-16 | 23.4% | F138 | Final143 | 05/20/94 NSMSTR03 | 50.19 | 6766 | 8838 |
| EA02A U1410 | 14-16 | 23.4% | F138DL | Final182 | 05/25/94 NSCAL09 | 51.08 | 6885 | 8993 |
| EA03A U1820 | 18-20 | 6.1% | F86 | Final19 | 05/06/94 NSMSTR01 | 15.45 | 2497 | 2600 |
| EA03A U1820 | 18-20 | 6.1% | F86DL | Final27 | 05/09/94 NSCAL04 | 10.03 | 1622 | 1727 |
| EA03A U1820 | 18-20 | 6.1% | F86DL | Final156 | 05/21/94 NSMSTR03 | 15.48 | 2502 | 2605 |
| EA04A U0002 | 0-2 | 0.5% | F84 | Final40 | 05/10/94 NSCAL05 | 0.07 | 10 | 11 |
| EA04A U0002 | 0-2 | 0.5% | F84DUP | Final105 | 05/27/94 NSCAL10 | 0.09 | 14 | 15 |
| EA04A U2022 | 20-22 | 0.4% | F159 | Final23 | 05/06/94 NSMSTR01 | 5.31 | 594 | 597 |
| EA04A U2022 | 20-22 | 0.4% | F159S | Final22 | 05/09/94 NSMSTR01 | 0.79 | 1213 | 1218 |
| EA04A U2022 | 20-22 | 0.4% | F159SDII | Final155 | 05/21/94 NSMSTR03 | 10.01 | 1241 | 1246 |
| EA05A U2223 | 22-23 | 1.9% | F121 | Final42 | 05/10/94 NSCAL05 | 14.76 | 1753 | 1766 |
| EA05A U2223 | 22-23 | 1.6% | F121DL | Final51 | 05/11/94 NSCAL06 | 5.56 | 690 | 672 |
| EA05A U2223 | 22-23 | 1.6% | F121DLI | Final157 | 05/21/94 NSMSTR03 | 0.79 | 1182 | 1184 |
| EA08A U1820 | 18-20 | 3.0% | F175 | Final43 | 05/10/94 NSCAL05 | 2.28 | 279 | 288 |
| EA07A U0810 | 8-10 | 0.3% | F177 | Final41 | 05/10/94 NSCAL05 | 0.20 | 26 | 26 |
| EA07A U1214 | 12-14 | 3.0% | F178 | Final50 | 05/11/94 NSCAL06 | 0.82 | 123 | 127 |
| EA08A U1410 | 14-16 | 0.7% | F155 | Final39 | 05/10/94 NSCAL05 | 2.03 | 440 | 442 |
| EB01A U0002 | 0-2 | 0.5% | F13 | Final52 | 05/11/94 NSCAL06 | 0.04 | 5 | 5 |
| EB01A U0002 | 0-2 | 0.5% | F13Rex | Final145 | 05/20/94 NSMSTR03 | 0.36 | 43 | 43 |
| EB01A U1618 | 16-18 | 0.3% | F107 | Final53 | 05/11/94 NSCAL06 | 0.24 | 29 | 29 |
| EB01A U1618 | 16-18 | 0.3% | F107Rex | Final163 | 05/22/94 NSMSTR03 | 0.41 | 71 | 71 |
| EB02A U0406 | 4-6 | 0.2% | F12 | Final58 | 05/11/94 NSCAL06 | 0.05 | 7 | 7 |
| EB03A U0204 | 2-4 | 0.4% | F39 | Final61 | 05/11/94 NSCAL06 | 0.13 | 16 | 16 |
| EB03A U0204 | 2-4 | 0.4% | F39Rex | Final144 | 05/20/94 NSMSTR03 | 0.44 | 61 | 61 |
| EB03A U0204 | 2-4 | 0.4% | F131-1 | Final148 | 05/20/94 NSMSTR03 | 0.40 | 48 | 48 |
| EB03A U0204 | 2-4 | 0.4% | F131-2 | Final149 | 05/21/94 NSMSTR03 | 3.01 | 348 | 350 |
| EB03A U1012 | 10-12 | 2.8% | F73 | Final56 | 05/11/94 NSCAL06 | 0.03 | 4 | 4 |
| EB04A U1618 | 14-16 | 3.9% | F34 | Final75 | 05/12/94 NSCAL07 | 0.73 | 107 | 112 |
| EB04A U2022 | 20-22 | 7.9% | F8 | Final60 | 05/11/94 NSCAL06 | 2.09 | 273 | 297 |
| EB04A U2022 | 20-22 | 7.9% | F8DUP | Final201 | 05/27/94 NSCAL10 | 2.21 | 290 | 315 |

Re: Duplicate Extraction of soil. Dup: duplicate injection; Dil: extract diluted

3. Removal of TPH

A comparison of the post test and pretest concentration of DRO was done. This is summarized in the attached Table 17. Figure 19 (Page 56) is a plan view of the electrode array which helps to elucidate the various comparisons made in Table 17. Table 17 summarizes the average concentration of DRO TPH as a function of heated soil zones. There are four zones based upon which the comparison was made.

The first zone is the entire heated volume to a depth of less than or equal to 24 ft; in this zone the average concentration in the defined volume was calculated by considering all valid analytical results.

The second zone is defined by the area enclosed by the four corner electrodes A1, C1, C8, A8 and a depth less than or equal to 20 ft. Only valid analytical results for samples which were obtained from this volume were averaged.

The third zone is defined by the area enclosed by the central electrodes A3, C3, C6, A6 and a depth less than or equal to 24 ft.

The fourth zone is defined by the area bounded by the central electrodes A3, C3, C6, A6 and a depth less than or equal to 20 ft. As Table 17 illustrates, the highest removal was obtained in the central zone to a depth of 24 ft or less. In this zone the removal of DRO TPH was 67 to 69 percent. As the volume is enlarged to include the entire surface area (defined by A1,C1,C8,A8) the removal drops to 23 to 29 percent to a depth of 24 ft or less. A review of the soil samples taken from the lateral Volume II indicates that in this region the concentration of the soil may have increased. A similar increase may have occurred in the corresponding volume at the opposite end of the array. This cannot be definitely concluded due to lack of paired before and after samples of soil from this region of the array.

The above data are presented in terms of two depth ranges because the central row of electrodes, the excitor row had a depth of 20 ft and the two outer rows had a depth of 29 ft. The central row was originally designed for a depth of 24 ft. Its depth was decreased in the field because a shallow water table was encountered in the depth interval of 19 to 24 ft. A corresponding depth reduction of the two outer rows was not done due to time and logistics constraints. The heated depth extends below the bottom of the excitor electrodes. This heating is caused by electric fields fringing below the central row of electrodes. It is estimated that fringing fields could extend the heating effect by an additional depth equal to 50 to 60 percent of row separation (that is 2.5 to 3 ft more).

TABLE 17. SUMMARY OF TPH ANALYSIS DONE AT IITRI, PPM

| Volume | Pre-Demonstration | | | | Post-Demonstration | | | |
|---|-------------------|-----------|------|--------|--------------------|-----------|------|--------|
| | n | \bar{x} | s | R.S.D. | n | \bar{x} | s | R.S.D. |
| Total, for all depths $\leq 24'$ | 33 | 1518 | 2636 | 174 | 33 | 1077 | 2131 | 198 |
| For volume defined by (A1, C1, C8, A8), Depth $\leq 20'$ | 26 | 1280 | 2866 | 224 | 28 | 984 | 2261 | 230 |
| For volume defined by (A1, C1, C2, A2), Depth $\leq 24'$ (Volume III) | 7 | 706 | 975 | 138 | 8 | 2405 | 3495 | 145 |
| For volume defined by (A1, C1, C2, A2), Depth $\leq 20'$ | 6 | 348 | 257 | 74 | 7 | 2348 | 3771 | 161 |
| For volume defined by (A3, C3, C6, A6), depths $\leq 24'$ | 18 | 2347 | 3300 | 141 | 17 | 730 | 1467 | 201 |
| For volume defined by (A3, C3, C6, A6), depths $\leq 20'$ | 14 | 2208 | 3707 | 168 | 14 | 717 | 1610 | 225 |

The data were presented in terms of two areal zones because the maximum temperature rise was confined to the central zone as defined by electrodes A3, C3, C6, A6.

A graphical comparison of the soil concentrations before and after the demonstration experiment was made. The data for samples obtained from ground row A is shown in Figure 30. A two-dimensional pattern is revealed regarding the distribution of sampling points. This pattern may have biased the results for the following reasons:

- It is known that the concentration of TPH increased with depth, and that it was higher in the depth interval of 12 to 25 ft. As the figure shows, deep samples were taken below the 20 ft zone (below the bottoms of the excitor electrodes).
- There were no samples taken in the middle of the heated zone, that is, the zone defined by Electrodes A3 to A6 and depth interval of 2 to 20 ft. This was the area of highest temperature increase in Ground Row A.
- Samples taken at depth may be confounded by the presence of the water table for depths larger than 24 ft.

Based on the comparison of the post test and pre-test average concentration, there was no removal of TPH in the vertical plane defined by ground row A. The average pre-test concentration in this plane was 1340 ppm and the post test average was 1478 ppm.

Figure 31 illustrates the distribution of contaminant concentration in the vertical plane represented by the excitor row electrodes. This plane includes the two thermowells TW1 and TW2. The location of sampling points are such that no obvious pattern can be discerned from Figure 31, which is the desired random distribution of the sampling points. The average pre-test concentration of TPH in this plane was 809 ppm. The average post test concentration was 710 ppm if all the data are included. There is one post test sample which seems to increase the post test average from 127 ppm to 710 ppm. This is the sample in TW1 from the depth interval of 14 to 16 ft. The analyzed concentration is in excess of three standard deviations of the average of the remaining samples.

Figure 32 illustrates the concentration profile for TPH in the vertical plane represented by ground row C. The distribution of sampling point locations does not reveal any pattern, which was the desired outcome. The average concentration of all the pre-test samples was 2271 ppm. The average of all the post-test samples was 1079 ppm, which represents a concentration decrease of




Figure 30. Pre and Post Demonstration TPH Concentration in Electrode Row A as a Function of Depth




Figure 31. Pre- and Post-Demonstration TPH Concentration in Electrode Row B as a Function of Depth

• Outside 3 standard deviations of the average of all the other post-test samples in this plane

Ground
Electrode
Bottoms

TW: Thermowell




Figure 32. Pre- and Post-Demonstration TPH Concentration in Electrode Row C as a Function of Depth

approximately 53 percent. If the samples taken below the depth of 20 ft are removed then concentration decrease is approximately 63 percent.

C. TRACER INJECTION EXPERIMENT

Towards the end of the heating portion of the demonstration a tracer experiment was done to show that soil fluids were moving into the heated zone. The tracer experiment was performed on May 30, 1993 between 9:00 and 15:30 hrs. The results of the tracer experiment are summarized here along with a description of the procedures.

Halon 2402, dibromotetrafluoroethane, was used as a chemical tracer. The tracer was injected outside the heated array, in cool soil at a depth of 7 feet. The injection point was located on a center line approximately 9 ft from the western edge of the array. The distance from the center of the array was approximately 14 ft. The soil temperature at the injection point was 32.3°C. The tracer was injected into a 0.25-in. O.D. copper tubing which was placed in a bore hole at the time of system installation. After introduction into the copper tube the tube opening was closed to prevent the escape of the tracer. The raw gases leaving the heated zone were sampled and analyzed for the presence of Halon 2402. A gas chromatograph equipped with an electron capture detector was used for the analysis. The purpose of the tracer experiment was to prove that the tracer moves into the heated zone. Thus only qualitative analysis was performed.

1. Materials and Equipment

Halon 2402 is a liquid at ambient temperature, boiling at 47.3°C. The liquid density is 135 lb/cu. ft. at 70° F. The vapor specific gravity is 8.97 (Air =1).

A Packard gas chromatograph, Model 427 equipped with a Nickel -63 electron capture detector was used for the analysis of Halon 2402. A stainless steel column, 1/8 in O.D. packed with 80/100 mesh Porapak Q was used for separation. The column was purchased from Altech. The GC operating conditions were: Injector temperature 220°C; oven temperature 220°C; detector temperature 230°C; carrier gas zero grade nitrogen supplied at a head pressure of 60 psig which gives a flow rate of approximately 20 ml/min.

Gas tight syringes were used to inject the gas sample into the GC. The retention time of Halon 2402 was in the range of 1.6 to 1.65 minutes. It was found by injecting the gas from the head space of a vial containing pure Halon 2402.

After the injection of the halon tracer into the soil the raw gases leaving the soil were sampled and analyzed for the presence of Halon 2402. The sampling system is illustrated in Figure 1 and the procedure is described below.

2. Procedure for Performing the Tracer Experiment

The overall procedure for performing the tracer experiment has four part:

- Set up of GC and confirmation of Halon 2402 peak elution time.
- Set up of a raw gas sampling train
- Collection of preliminary and background data and information prior to tracer injection
- Collection of gas samples and their analysis after tracer injection

Set Up of GC and Determination of Elution Time

The ECD GC was set up and several injections were made to determine the elution time of the Halon tracer. The base line was verified to be clean after the tracer peak had eluted. When injecting room air the chromatogram showed a response for air and then had a clean baseline. The sensitivity of the detector should was set in the medium range, about 3 to 4. The retention time of Halon 2402 was in the range of 1.6 to 1.65 minutes.

Gas Sampling Equipment and Procedure

Figure 33 illustrates the method of setting up the gas sampling train. The gas sample point for the tracer study was the same point on the ejector system where Halliburton personnel had been taking samples for volatile and semi-volatile analysis. But existing tygon tubing was replaced with 0.25 in. O.D. teflon tubing. The sample was conveyed to a glass flask in which any water droplets in the line were separated. The outlet port of the flask was connected to a diaphragm pump. A Thomas pump was used. This pump has a teflon-lined rubber diaphragm. This is a positive displacement pump and will generate high pressure if the outlet is blocked or restricted.

The outlet of the pump was connected to valve V1. The line leaving V1 was connected to a Tee. Valve V2 was connected to the branch leg of the Tee. The run-leg of the Tee was connected to teflon tubing which was connected to the glass gas sampling bottle by means of a short length of tygon tubing.




Figure 33. Gas Sampling Scheme for the Tracer Experiment

The line leaving from the branch leg of the Tee was connected to Valve V2. The line leaving valve V2 was submerged in 10 in. of water. This line was made from tygon hose. The purpose of this line was to allow the filling of the gas sample bottle under pressure of 10 in. of water.

The gas sample train was started and used in the following manner:

First the pressure was set as follows:

- With valve V1 open, valve V2 was cracked open. Stop cock C1 was closed. Pump was turned on. Valve V2 was adjusted so that the air just bubbled out of the submerged tubing.

Gas was sampled as follows:

- With the pump running as above, stop cocks C1 and C2 were turned on.

- Gas was flushed through the gas sample bottle for about 3 min. Then stop cock C2 was closed followed by stop cock C1. Pump was switched off. The sample bottle was labelled with date and time.

Sampling the Gas Bottle for GC Injection

A rubber septa was attached on one outlet end of the filled gas sample bottle. The stop cock at the same end was opened. The gas was sampled with the syringe needle inserted through the septa. After removing sample the stop cock was closed.

Collection of background information prior to tracer injection:

- Insert a thermocouple into the tracer injection well (0.25 in tubing) and measure the temperature and the depth of the hole. CAUTION: RF power must be switched off while inserting and using the thermocouple.
- Before injecting the trace the following operating conditions were recorded:
 - * All the RF power input parameters
 - * All the data from the vapor collection system.

Injection of tracer

A 5 ml. syringe was filled with the liquid tracer and it was injected into the copper tracer injection tubing inserted in the ground. The time and date were recorded. The copper injection tubing was capped.

Immediately after the injection of the tracer a gas sample was taken. New gas samples were taken after every 15 minutes until 120 minutes had elapsed.

Prior to reuse, the gas sample bottles were thoroughly flushed out and cleaned. The cleanliness of the sample bottle was verified by analyzing a sample taken from the bottle after it had been flushed.

3. Trace Injection Results

The results of the gas samples analyzed for the presence of the tracer gas in the raw gas stream collected from the heated soil zone are presented in Table 18.

TABLE 18. RESULTS OF TRACER INJECTION EXPERIMENT

| Tracer Injection Time | Sample No. | G.C. Run No. | Sampling Time | Elapsed Time | Sample | | Response per ml. sample | Normalized Area |
|-----------------------------|---------------|-----------------|---------------|-----------------|--------|-----------|----------------------------|--------------------|
| | | | | | Start | Finish | | |
| 5/30/93 9:04 | * | 17 | 09:07 | 09:10 | 4.5 | 0.05 | 1,442,000 | 28,840,000 |
| | 3 | 18 | 09:32 | 09:35 | 29.5 | 0.1 | 1,128,900 | 22,570,000 |
| | 4 | 19 | 09:59 | 10:02 | 56.5 | 0.1 | 797,460 | 7,974,600 |
| | 5 | 20 | 10:23 | 10:26 | 80.5 | 0.1 | 567,310 | 5,673,100 |
| | 6 | 21 | Estimated | 110 | 0.1 | 707,970 | 7,079,700 | |
| | 7 | 22 | 11:32 | 11:35 | 149.5 | 0.1 | 1,575,500 | 15,755,000 |
| | 8 | 24 | 12:02 | 12:05 | 179.5 | 0.1 | 880,460 | 8,804,600 |
| | 9 | 25 | 12:32 | 12:35 | 209.5 | 0.1 | 799,350 | 7,993,500 |
| | 10 | 26 | | | | 1,359,100 | | 13,591,000 |
| 5/30/93 13:00 | 11 | 27 | 13:11 | 13:14 | 12.5 | 0.1 | 0 | 0 |
| | 11 | 28 | 13:11 | 13:14 | 12.5 | 0.1 | 1,356,300 | 13,563,000 |
| | 12 | 29 | 13:25 | 13:28 | 26.5 | 0.2 | 1,276,800 | 6,384,000 |
| | 13 | 30 | 13:50 | 13:53 | 51.5 | 0.2 | 0 | 0 |
| | 14 | 31 | 14:12 | 14:15 | 73.5 | 0.2 | 626,480 | 3,132,400 |
| | 15 | 32 | 14:42 | 14:45 | 103.5 | 0.2 | 110,760,000 | 553,800,000 |
| | 15 | 33 | 14:42 | 14:45 | 103.5 | 0.2 | 159,270,000 | 796,350,000 |
| | 16 | 37 | 15:06 | 15:09 | 127.5 | 0.2 | 8,217,600 | 41,088,000 |

* Blank sample comprising of the atmospheric air at the site

Halon 2402 was first injected into the injection well at 09:00 hrs on May 30, 1993. Approximately 5 ml. of the tracer was injected. The first sample of raw gas from the vapor collection system was obtained between 09:07 and 09:10 hrs. Additional samples were obtained every 15 to 20 minutes. A sample of the gas was injected into the GC/ECD and the peak elution time and peak area were noted. The data are summarized in Table 18. As shown by the results of samples 3 through 10 the presence of tracer in the raw gas stream could not be conclusively proven although it appears that sample 7 had increased levels of the tracer.

One reason that the tracer response was so low is that we had injected insufficient amount of the tracer and it was getting diluted by the air and gases flowing into the vapor collection system. Thus another larger injection of the tracer was made later the same day at 13:00 hrs four hours after the first injection. Twenty five ml. of the liquid tracer was injected. A large increase in the GC response was observed for sample number 15 which was taken approximately 104 minutes after the second tracer injection.

These results show that the liquid tracer injected outside of the heated zone migrated inside and was collected by the vapor collection system. Because of the way the experiment was done, it is not possible to rule out the fact that the observed increase of the tracer concentration in the gas samples may have been due to the first tracer injection and not the second. If this is indeed the case, then the tracer could have taken as long as 5 hr and 40 minutes to be collected by the vapor collection system.

D. ELECTRICAL DATA

1. RF System Performance

The operational performance of the RF heating system used for the Kelly AFB demonstration test was evaluated by monitoring the RF power delivered and absorbed by the array, by tracking the electrode array's input impedance and by continuously adjusting the matching network to achieve the most efficient energy delivery between the source and the array. Figures 34, 35, and 36 illustrate the applied or input RF power to the array, the cumulative RF energy delivered, and the effective RF power source utilization, respectively, as function of time.

Both the forward and reflected RF power at the output of the RF power source were continuously monitored throughout the test. Additionally, the forward and reflected RF power was monitored at the input to the stage 1 matching network, adjacent to the array. By periodically adjusting the variable components of the stage 2 matching network, the reflected power to the RF power source was

INPUT POWER LEVEL VS. TIME

Figure 34




Figure 35

CUMULATIVE RF ENERGY vs. TIME





Figure 36

RF POWER SOURCE UTILIZATION VS. TIME (Percent of Capacity)



minimized or maintained at zero. Finally, by recording the measurements obtained from the IITRI designed in-line impedance meter, changes in trends in the input impedance to the electrode array were tracked as a function of time. By monitoring the trends in this impedance, a qualitative assessment of the performance of the RF heating system was performed.

During the operation of the test it was determined that the use of the single RF frequency of 6.78 MHz would be sufficient. All subsequent RF data is for a fundamental applied frequency of 6.78 MHz. Figure 37 illustrates a calculated Smith chart representation of the array's input impedance as would be measured at the soil surface, if possible, as a function of time for the first 33 days of the demonstration test. During this period of the test, the track of the array's input impedance appears, for the most part, as would be expected for the RF heating of this specific triplate array. Figure 38 shows a calculated Smith chart representation of the array's input impedance at the soil surface for the final month of the test. The erratic pattern indicates that major impedance variations were occurring within the triplate array throughout the majority of the final two to three weeks of the heating.

2. RF Emissions Monitoring

Near and far-field electromagnetic field measurements were made at and around the test area. Near-field refers to the immediate vicinity of the test site (within ~15 feet of the array); far-field refers to locations 100 to 1600 meters from the test site. All far-field locations were selected in consultation with Kelly AFB communication personnel. The purpose of these measurements was to ensure that any radiated RF power levels were below permissible FCC and Air Force standards, that no interference was generated with base communications, and that no personnel safety problem areas existed.

These measurements were made in two different phases. The first phase or series of measurements were conducted before the initiation of the actual test by applying low RF power levels (~5 kW) to the electrode array and monitoring both near and far-field radio frequency interference (RFI) electric field intensity values in order to identify any potential problem areas. The second series of measurements were conducted during the test. These near and far-field RFI measurements were made while full power was being applied to the electrode array. Ambient field levels were measured by momentarily turning the RF source off to the electrode array at each measurement point or location.

Figure 8, previously illustrated an overview of the Kelly AFB; Site S-1 demonstration test layout. RFI safety measurements were

Kelly AFB; Site S-1 Array Input Impedance Tracking




Figure 37. Kelly AFB; Site S-1.

Kelly AFB; Site S-1 Array Input Impedance Tracking




Figure 38. Kelly AFB; Site S-1.

conducted periodically during the test throughout the area shown in the figure. These safety measurements consisted of recording the RF power density as measured by a hand held RF field strength or exposure probe. The maximum measured RF power density was found just below the 6 $\frac{1}{2}$ inch coax RF choke. The maximum value recorded at full power (40 kW applied to the array) was 0.16 mW/cm² which is less than 1% of the maximum permissible exposure limit (19.6 mW/cm² at 6.78 MHz) as identified by IEEE C95.1-1991 (Reference 5). There were no measurable RF power densities within the area except in the proximity of conducting materials. The average RF power density measured within 6 inches of the coaxial transmission lines was 4 μ W/cm². This represents 0.02% of the permissible limit.

Table 19 contains the maximum measured electric field strengths for both near and far-field RFI safety measurements. Also illustrated in this table are the appropriate limits identified by the Institute of Electrical and Electronic Engineers (IEEE) and accepted by the American National Standards Institute (ANSI) and the National Institute of Occupational Safety and Health (NIOSH) for near-field continuous exposure to electric fields at this frequency of operation. The maximum measured electric field strength of 40 mV/m at a distance of 10 meters is more than three orders of magnitude below the minimum of these two ratings. In addition, no electromagnetic interference was experienced by any of the air base communication staff throughout the duration of the demonstration.

No out-of-band electric field strengths were measurable at frequencies that were not, themselves, ISM band frequencies. Out-of-band refers to measurements at frequencies other than the operating or fundamental frequency directly generated as part of its operation (harmonics, spurious radiation, etc.).

The fact that all RFI measurements, near and far-field met personnel safety limits and were within permissible standards, indicates that more than sufficient efforts were employed during the design, fabrication and installation of this demonstration test to insure adequate site personnel safety and not pose any interference to the surrounding community.

TABLE 19. RFI SAFETY MEASUREMENTS NEAR/FAR-FIELD
(APPLIED FREQUENCY = 6.78 MHz, APPLIED POWER = 40 KW)

| Distance from Array (meters) | Electric Field Strength (millivolts/meter) | Personnel Safety Continuous Exposure Electric Field Strength Standards (Volts/meter) | |
|---------------------------------------|---|--|-------|
| | | IEEE/ANSI | NIOSH |
| 10 | 40.0 | 121.5 | 192. |
| 100 | 1.30 | | |
| 400 | 0.071 | | |
| 800 | 0.126 | | |
| 1600 | 0.016 | | |

VIII. CONCLUSIONS

A. TPH REMOVAL

In the central row of electrodes, the excitor Row B, high removal of TPH was observed due to the high temperature achieved in this row. The residual concentration of TPH in this row was in the range of 4 to 112 ppm. Higher concentrations were observed below the tips of the excitor electrodes (305 ppm) and towards the edges of the row where the temperature was lower. Thus, in thermowell TW2 the concentration range was 48 to 417 ppm and in TW1 it was 263 to 6543 ppm. The high reading in TW1 is probably an outlier as explained in Section VII. The average temperature in the excitor row ranged from 125°C to 650°C (Figure 21). The average temperature in this row was in the range of 125 to 150°C from 200 to approximately 700 hours of elapsed time. After 700 hours, the temperatures at the tips of the excitor electrodes shot up and so did the average.

The results of the Bench Scale Treatability study (Reference 2a) had shown that treatment at a temperature of 150°C with a residence time of 100 hours was sufficient to reduce the TPH concentration to 60 to 90 ppm. The percent removal depends upon the initial concentration of soil and it ranged from 75 to 97 percent in the laboratory studies. Thus, the residual concentrations observed in Row B were consistent with the results of the treatability study.

Comparison of the initial and final concentrations of samples obtained from Row B indicate that there was a 84 percent reduction of TPH concentration. We have omitted the outlier in this calculation. If all the data points are considered, including the outlier, then the reduction in TPH concentration is only 12 percent.

The residual concentration of TPH in ground Row C was in the range of 5 to 5700 ppm. There were 12 post demonstration soil samples. Of these 2 were in the depth range of 20 to 24 ft which is below the tips of the excitor electrodes and they may have also been very close to, if not below the water table surface. These two samples had a concentration of 2800 to 2840 ppm. The average temperature in ground rows A and C at a depth of 24 foot did not exceed 45 to 50 °C (Figure 22). Thus the above results are not surprising considering the sample locations and the temperature history.

There were another two samples, in the depth range of 18 to 20 ft, with residual TPH concentration in the range of 1100 to 5700 ppm. There are no temperature data in the depth range of 18 to 20 ft. But by interpolating between data of depth ranges 12 and

24 ft, one can see that the temperature in the depth range of 18 to 20 ft was in the range of 45° to 70°C.

The remaining 8 samples of Ground Row C were from the depth range of 0 to 16 ft. with a residual TPH concentration in the range of 5 to 210 ppm with an average of 64 ppm. The initial concentration of these 8 locations was in the range of 25 to 896 ppm with an average of 221 ppm. Thus, the percentage removal in the 0 to 18 ft depth interval of Row C was 70 percent. If all the samples of Row C are considered in the calculations of initial and residual average concentrations then the following results are obtained: Initial average concentration: 2271 ppm, and final average concentration: 1079 ppm for a reduction of 52.5 percent.

The concentration data for ground Row A is more difficult to interpret because of the way the sampling points happen to fall in relation to the water table, and the extent of the heated zone. It was pointed out earlier that most of the samples were taken from area where the temperature rise was inadequate or else they were taken close to the water table. The average concentration of all the 11 pre-demonstration soil samples in Row A was 1340 ppm. The average of all 10 post-demonstration soil samples was 1478, indicating either that the TPH was not removed or it increased slightly. In both Rows A and C the hottest soil region was opposite electrodes in positions 3 to 6, that is A3 to A6, etc. In Row A, there were only 3 post demonstration samples from these electrodes, of which two were in the depth interval of 18 to 20 ft. where the temperature rise was inadequate to remove TPH. In Row A there were 7 post-demonstration samples taken from locations which were either too deep or else were in the fringe area where the temperature rise was insufficient.

The results of the soil sample analysis when considered in relation to the sample location and the temperature history support the conclusion that where ever the soil was heated to a temperature range of 150°C, low residual concentration of TPH was obtained.

B. SOIL TEMPERATURE RISE

As illustrated by the data presented in the figures of Section VII it is clear that the central row of electrodes were abnormally overheated whereas there was severe under heating of zones further removed from the central row of electrodes. The design goal was to heat 122 cu. yd. to a temperature of 150°C. The results show the following:

- Volume of soil where every measurement point exceeded 100°C for long (>100 hr) periods of time was estimated to be 90 cu. yd.

- volume of soil where the average temperature was $>150^{\circ}\text{C}$ was estimated to be 56 cu. yd. But volume within which every measurement point exceeded 150°C was 34 cu. yd.
- Volume of soil where the average temperature was in the range of 60° to 70°C was 37 cu. yd.

These results indicate that the desired volume of soil did not reach the temperature objective of 150°C . The main reason for this was the melting of electrode due to their close proximity to the water table.

The high temperature to which the soil was heated may have contributed to some oxidation of contaminants present in the soil. IITRI has no data to prove or disprove this hypothesis, but it is a reasonable one to make.

C. OPERATION OF THE RF HEATING SYSTEM

After May 18, 1993, sustained operation of the RF power source became difficult. The analysis of data and information now available show clearly that this was due to the high temperature achieved in the central row which led to the melting of the electrodes. Prior to this time the RF system performed quite well considering that the RF power source was 40 to 45 years old and it exhibited signs of age as evidenced by frequent short circuiting due to insulation failure and rectifier problems. However, the matching networks and instrumentation all performed as expected.

It is probable that the electrodes melted due to their close proximity to the water table. But depth of water table below the heated zone is not known in the time period that the demonstration was performed. Due to the design of the array, it was not possible to monitor the water table location. However, water table depth was monitored prior to completion of the electrode array. These data indicate that the water table was 2.5 ft to 3.5 ft below the tips of the excitor electrode in February 1993. The water table level was controlled by means of four dewatering wells that pumped continuously during system installation and operation. It is known that the pumps were able to reduce the water table depth by 1 to 1.5 ft during the nine days ending February 11, 1993.

The measurements of radiated power levels indicated that there were no RFI problems. Safety measurements made in the immediate vicinity of the RF equipment indicated safe levels of E and H fields.

IX. RECOMMENDATIONS

In light of the results of the field demonstration the following recommendations are made:

- Develop, through engineering analysis, sound and reliable criteria which dictate the proximity of the electrode tips and the water table
- For sites which have a shallow water table, means of measuring, while heating, the depth of the water table below the electrode array must be incorporated in the design of the array.
- A review of the impedance data plotted on Smith charts indicates that there were clues developing prior to May 18, 1993, which may have been indicative of the problems which we were to experience in the future. An engineering analysis should be done to catalogue such clues so that the system operating personnel can be alert to the possible mal-operation of the system.
- An analysis of the radiation measurements from the heated zone indicate that the RF shield may have been over designed. Future demonstrations should evaluate other simpler alternatives for the shield design.
- Temperature of the thermowells was measured by means of fiber optic probes. These probes were found to work reliably at temperatures below 200°C. However, for higher temperatures the probes failed due to material failure. Alternative probes should be sought.
- The RF system does not lend itself to an elegant and economical way of measuring temperature of the soil between the two outer rows of electrodes. Due to this reason, thermocouples were inserted inside the excitor electrodes and thermowells were installed. Thermocouples inside the excitor electrodes were read by switching off the RF power. The reason is that no electrical conductor may leave the heated area when the RF power is on. Recent developments in fiber optic tele-metering should be investigated to develop a continuous temperature logging system for both soil and electrode temperatures.
- Means of recovering hot gases and vapors from the excitor electrode row or other central area of the array should be developed. When hot vapors are collected from the

ground rows, they cool and some fraction of these may condense there, depending upon the local temperature and the dew point.

X. REFERENCES

1. Cost Study of In Situ RF Heating for Treatment of Hazardous Substances. IITRI Project No. C06558 Final Report. Rockwell International Sub-contract No. N256045ZKX, Prime Contract No. 68-03-3014. August 1982
- 2a. Dev, H., Bajzek, T., and Bridges, J. Bench Scale Treatability Study and Soil Dielectric Property Measurements. Halliburton NUS Environmental Corporation, Sub-contract No. 91-D-4011I-1018, IITRI Report No. C06754. June 1992
- 2b. Dev, H., Bajzek, T., and Bridges, J. Radio Frequency Soil Decontamination Demonstration Project, Site S-1, Kelly AFB; Demonstration System Design. Halliburton NUS Environmental Corporation, Sub-contract No. 91-D-4011I-1018, IITRI Report No. C06754. July 1992
3. Recommended DHS Analytical Methods, Appendix D: Analytical Procedures in Leaking Underground Fuel Tank Field Manual: Guidelines for Site Assessment, Clean Up and Underground Storage Tank Closure, October 1989. State of California Leaking Underground Fuel Tank Task Force, State Water Resources Control Board.
4. Dev H., et al. In Situ Decontamination by Radio Frequency Heating -- Field Test. IIT Research Institute. Final Report C06666/C06676. USAF HQ AFESC/RDV, Tyndall AFB. ESL report number ESL-TR-88-62. NTIS Number ADA221186.
5. IEEE C95.1-1991, IEEE Standard for Safety levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz, IEEE Standards Coordinating Committee 28, Non-Ionizing Radiation Hazards, April 27, 1992.

Appendix A

SUMMARY OF LOG BOOK ENTRIES FOR RF HEATING

Appendix A

SUMMARY OF LOG BOOK ENTRIES FOR RF HEATING

Table A-1 summarizes the high lights of the log book entries made by the shift operators during the in situ RF heating experiment. These entries pertain to the operation of the RF power source and the thermal data logging system. It should be noted that the experiment was performed with a 40 kW power source which is at least 45 years old and is prone to breakdowns related to age.

TABLE A-1. SUMMARY OF LOGBOOK ENTRIES

| Date | Time | Logbook | | Individual | Summary of Logbook Entry |
|----------|-------|----------|------|------------|--|
| | | Number | Page | | |
| 04-04-93 | 21:00 | 30583 | 4 | Bajzek | Recorded warming of the exciter row thermocouple jacks in the plexiglass housing. Estimated temperature 40°C. |
| 04-05-93 | 17:55 | 30583 | 5 | Suchanek | Heard loud noises from the power source FR7-6. |
| 04-06-93 | 13:10 | 30583 | 6 | Jones | Start full power RFI measurements. |
| 04-08-93 | 02:42 | 30583 | 8 | Suchanek | RF wave form has modulation. Rectifier tube changed. |
| 04-09-93 | 00:25 | 30583 | 9 | Suchanek | Lost power. Sam called. Down for 75 minutes. |
| 04-10-93 | | 30583 | 10 | | Thermocouple connectors for excitor T/C are hot. Tried shielding with Teflon. Plug for B1A is turning black. |
| 04-10-93 | 15:00 | 30583 | 10 | | Teflon does not help reduce heating of T/C plugs. Teflon removed. |
| 04-11-93 | 23:00 | 30583 | 11 | Jones | FRJ-T has been down for 4 hours. Switching interlock system to the new power source. Sparking observed at the rear of the third cabinet of FR7-6. Teflon shield applied. |
| 04-14-93 | | 30583 | 13 | Jones | Match is moving more rapidly than before. |
| 04-14-93 | 14:50 | 30583 | 13 | Jones | Reflected power moved up to 500 watts in a period of 10 minutes. |
| 04-17-93 | 17:09 | 30583 | 17 | Tumarkin | Arcing under rectifier sockets. Short in C1585 air type capacitor. |
| | | 2875 (D) | 12 | Kunstmanas | |
| 04-18-93 | 00:05 | 30583 | 16 | Kunstmanas | HNUS equipment lost power. Power (RF) off. Waited 1-hr. after HNUS power was restored before powering up with RF. |
| 04-18-93 | 06:40 | 30583 | 16 | Kunstmanas | Arcing in transmitter. Shut down. |
| 04-20-93 | 19:51 | 30583 | 19 | Kunstmanas | Problems with transmitter. |
| 04-21-93 | 11:26 | 30583 | 20 | | Arcing in the transmitter. |
| 04-22-93 | 08:10 | 30583 | 20 | | Arcing in the transmitter. |
| 04-22-93 | 1:28 | 30583 | 20 | | Transmitter was shut down because power dropped "radically" 35 to 31 kW then to 20 kW. |
| 04-23-93 | 20:29 | 30583 | 22 | | Transmitter tripped off. Circuit breaker tripped. Interlock light on. Breaker reset. Could not find open interlock switch. At 9:08 p.m. light off on its own. |
| 04-24-93 | 01:00 | 30583 | 22 | | Interlock opened somewhere. Bypassed. Resume power input to array. |

TABLE A-1. SUMMARY OF LOGBOOK ENTRIES

| Date | Time | Logbook | | Individual | Summary of Logbook Entry | |
|----------|-------|---------|------|-------------------|--|--|
| | | Number | Page | | | |
| 04-24-93 | 20:56 | 30583 | 23 | | Arcing in transmitter. Shutdown. Restarted. Sam investigated. | |
| 04-25-93 | 02:40 | 30583 | 23 | Suchanek | Over-voltage trip. Shut down. Could not restart. PA motorized switch banged with screwdriver handle. Restarted OK. | |
| 04-25-93 | 09:35 | 30583 | 24 | Tumarkin | Shut down to repair the motor driven PA high-voltage breaker. | |
| 04-26-93 | 00:10 | 30583 | 24 | | Tripped rectified tube was replaced. Down for 80 minutes. | |
| 04-26-93 | 15:25 | 30583 | 24 | | Wait-hour meter on HNUS transformer was repaired. Reads 0000. | |
| 04-27-93 | 15:45 | 30583 | 25 | | Read wait hour meter: 1,737.5 kW hr. ≈ 71.41 kW. | |
| 04-28-93 | 11:05 | 30585 | 1 | | Wave form is "wavy". High voltage rectifier tube out. | |
| 04-29-93 | 02:20 | 30585 | 1 | | Arcing in transmitter, rear of 3rd cabinet. | |
| 04-29-93 | 08:20 | 30585 | 2 | | Hard rain. Ponding of water. | |
| 04-30-93 | | 30585 | 3 | | Fog. Lots of moisture in air. | |
| 04-30-93 | | 30583 | 3 | | Shutdown for changes to matching network. Removed bullet capacitor. Change internal capacitor. | |
| 05-01-93 | 03:30 | 30585 | 3 | Suchanek | Waveform has a ripple. Replaced 2 rectifier tubes. Down for 3 hrs. | |
| 05-01-93 | 05:15 | 30585 | 3 | | Rich reported that excitor T/C connector for B1A crumbled. | |
| 05-01-93 | 10:10 | 30585 | 4 | Tumarkin | Tested new transmitter into dummy load. | |
| 05-01-93 | 16:50 | 30585 | 4 | Tumarkin Jones | Restarted after shut down. T/C wiring was removed and pulled back from the plexi-glass housing. Now the exciter electrode T/C wing has been wound and tied to the center conductor inside the dog house. | |
| 05-01-93 | 17:45 | 30585 | 4 | Jones | Transmitter tripped. Small amount of smoke. | |
| 05-02-93 | 11:15 | 30585 | 5 | | Power down from 11:15 to 00:15 a.m. | |
| 05-03-93 | 07:40 | 30585 | 5 | | Excitor T/C plugs were replaced. | |
| 05-05-93 | 04:05 | 30585 | 6 | Dev | Very heavy rain. Rained all day till about 6 p.m. 6° rainfall at San Antonio airport. | |
| 05-06-93 | | | | | During morning excitor T/C measurement B2A was 253°C. Vapor barrier temperature near TWI bundle was 120°C. | |
| 05-06-93 | 23:06 | 30585 | 7 | | One T/C in excitor row, B2A, over 300°C. | |

TABLE A-1. SUMMARY OF LOGBOOK ENTRIES

| Date | Time | Logbook Number | Page | Individual | Summary of Logbook Entry |
|----------|-------|----------------|------|------------|--|
| 05-08-93 | 07:00 | 30585 | 8 | Tumarkin | Transmitter down for 3 hrs., 45 minutes. |
| 05-09-93 | 15:15 | 30585 | 8 | Dev | Temperature of vapor barrier was measured. $T = 119^\circ\text{C}$ under thermal insulation blanket 18' north of electrode B2. $T = 72^\circ\text{C}$ on exposed vapor barrier at B2. (Thermal blanket on top of B2 removed at some prior time.) |
| 05-10-93 | 15:20 | 30585 | 9 | | Vapor barrier temperature above B2 - 78°C . 1' north of B2, under blanket 120°C . |
| 05-11-93 | 07:20 | 30585 | 9 | | Vapor barrier temperature about the same as the measurement shown in line above. |
| 05-11-93 | 15:25 | 30585 | 10 | D2877 | B2A was 741.5°C @ 15:25. |
| 05-11-93 | 15:30 | 30585 | 9 | | Vapor barrier temperature above B2 : 78°C 1' foot north: 128°C ; 2 ft. north 100°C . |
| 05-11-93 | 16:30 | 30585 | 10 | Asc | Power down. Power down for ≈ 12 hrs. Resume power to soil at 03:55 hrs. 05-12-93. |
| 05-12-93 | 03:55 | 30585 | 10 | Asc | Power on. |
| 05-12-93 | 23:00 | 30585 | 10 | | Vapor barrier temperature 60°C (exposed surface), 125°C under blanket, 2 ft. north. |
| 05-13-93 | 15:20 | 30585 | 11 | | Vapor barrier temperature 50°C on exposed surface. 120°C under blanket 2 ft. north |
| 05-13-93 | 23:07 | 30585 | 11 | | Vapor barrier, exposed surface 59°C . 2 ft. north, under blanket 119°C . Power tripped. Resume at 01:40. Ran at 10 kW prior to 1:40, while waiting for Sam. |
| 05-18-93 | 11:15 | 30585 | 14 | | High winds; very heavy rain; power in trailer is flickering. |
| 05-18-93 | 17:05 | 30585 | 14 | | Reflected power meter moving up and down. Matching network adjusted many times for match. |
| 05-18-93 | 18:00 | 30585 | 14 | | Reflected power meter moving up and down. Matching network adjusted many times for match. |
| 05-19-93 | 19:00 | 30585 | 15 | Suchanek | Transmitter shut down. Reflected power increased to 4 kW. Called Sam. |
| 05-20-93 | 06:25 | D2877 | 17 | | Running at 35 kW. Constant adjustment of match for the last 4 hours. |
| 05-20-93 | 18:30 | 30585 | 15 | Suchanek | B2C had no reading at 22:51 hrs. 5-19, B3C unstable. |
| 05-20-93 | 20:00 | 30585 | 15 | | B2C, 5/20, 0708 was 1330°C |
| 05-20-93 | 21:15 | 30585 | 15 | | Many adjustments necessary to match. ~ every 5 minutes. |
| 05-20-93 | 23:45 | | | Stable | Reflected power jumped to 1 kW. Decreased power to 10 kW. |

TABLE A-1. SUMMARY OF LOGBOOK ENTRIES

| Date | Time | Logbook | | Individual | Summary of Logbook Entry |
|----------|--------|---------|------|------------|---|
| | | Number | Page | | |
| 05-21-93 | 01:10 | 30585 | 15 | Dev | Reduced power to 10 kW from 20. Reflected power 0 to 1 kW. Phase angle fluctuations. |
| 05-21-93 | 05:30 | 30585 | 15 | Dev | Power increased to 15 kW. |
| 05-21-93 | 13:15 | 30585 | 16 | Tumarkin | Match is very unstable. Power at 15 kW. |
| 05-21-93 | | 30585 | 16 | | Reference to restarting power time? |
| 05-22-93 | ~06:50 | 30585 | 16 | Kunstmanas | Spent the whole shift gradually bringing power up to 39 kW. |
| 05-22-93 | 17:20 | 30585 | 16 | | Thunderstorm, heavy, but short duration. |
| 05-23-93 | 05:30 | 30585 | 17 | | Heavy rain for about 30 minutes. |
| 05-23-93 | 07:30 | 30585 | 17 | | Heavy rain. Dog house an island. Radio reports 7" of rain. |
| 05-23-93 | 20:00 | 30585 | 17 | | Large increase in reflected power, up to 3.8 kW refl. matched to zero. Large change in vector voltmeter readings. Rain ends at 18:00 hrs. |
| 05-24-93 | 17:30 | 30585 | 17 | | Power decreased to 20 kW. Reflected power fluctuating. |
| 05-24-93 | 22:15 | 30585 | 18 | Sabao | Stable at 20 kW so tried to increase power up to 25. Became unstable. Backed off to 20 kW. |
| 05-25-93 | | 30585 | 18 | | While at 21 kW reached the limit on capacitor C1. Backed down to 15 kW. |
| 05-26-93 | 09:50 | 30585 | 18 | | Do not increase power beyond 7 kW per Dev. |
| 05-28-93 | | 30585 | 19 | | New instructions from Dev |
| 05-28-93 | | 30585 | 19 | | New instructions from Dev |
| 05-28-93 | | 30585 | 19 | | Transmitter down form 16:10 to 18:40 hr. |
| 05-29-93 | 00:55 | 30585 | 19 | | Reflected power jumped to 2 kW. Then 40 kW circuit breaker tripped. Restarted; rematched; stable. |
| 05-30-93 | | 30585 | 20 | | B4C - no reading. 5-29-93. 13:00 hrs. |
| 06-03-93 | 11:00 | 30585 | 20 | | Very hard rain. Very windy. No entries in logbook C30585 for 6-1-93 or 6-2-93. |
| 06-03-93 | 12:00 | 30585 | 20 | | Safety measurements were made prior to shut down. RF power off. |

APPENDIX B

SOIL TEMPERATURE DATA

Appendix B

SOIL TEMPERATURE DATA

This appendix contains four tables which have temperature data obtained during the field demonstration:

Table B-1 has temperature data from the two outer rows of electrodes and the outside thermowell TW7.

Table B-2 has temperature data from all the thermowells which were inside the heated zone.

Table B-3 has temperature data measured by thermocouples installed inside the four center row electrodes, the excitor electrodes.

Table B-4 has the temperature data from the data logger. These temperatures were measured in the ground row electrodes and the outside thermowell TW7

The physical location of all the temperature measurement points can be found by referring to the attached Figure B-1, which is a plan view of the electrode array showing the electrode and thermowell numbering system. The temperature measurement point have a number designation composed of two parts: the first part is the number of the electrode or the thermowell. The second part is the depth code. A typical measurement point designation in the excitor row is of the type B1A, B3C, B4B etc. B1A refers to a measurement point in the B1 electrode at a depth 1-ft, which has a depth code of A. B3C means electrode B3 at a depth of 19 ft which has a depth code of C. Similar numbering system is used for temperature measurement points in the two ground rows and the thermowells. The following table defines the depth codes.

| <u>Depth Code Letter</u> | <u>Ground Rows A & C</u> | <u>Excitor Row B</u> | <u>Thermowells</u> |
|------------------------------|----------------------------------|--------------------------|--------------------|
| A | 1 ft | 1 ft | 1 ft |
| B | 12 ft | 10 ft | 12 ft |
| C | 24 ft | 19 ft | 24 ft |
| D | 29 ft | ----- | 29 ft |
| E | ----- | ----- | 31 ft |
| F | ----- | ----- | 34 ft |

Figure B-1
ELECTRODE HOLE AND THERMOWELL LAYOUT
 (Plan)




Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually)

| Elapsed Time Maximum Temp. | Date | Time | A2A 1-ft | A3A 1-ft | A4A 1-ft | C2A 1-FT | C3A 1-ft | C4A 1-FT | A2B 12-ft | A3B 12-ft | A4B 12-ft | C2B 12-ft | C3B 12-ft | C4B 12-ft | C6B 12-ft | A3C 24-h |
|----------------------------------|-----------------------|------|-------------|-------------|-------------|-------------|-------------|-------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|-------------|
| | | | 79 | 86 | 112 | 82 | 98 | 92 | 84 | 85 | 96 | 68 | 84 | 99 | 96 | 42 |
| 04/03/93 16:40 0.00 | 04/03/93 17:00 0.33 | 17.9 | 16.2 | 18.1 | 18.2 | 18.5 | 18.8 | 19.5 | 19.8 | 19.1 | 19.0 | 19.8 | 19.8 | 21.0 | 21.7 | 21.8 |
| 04/04/93 17:10 24.50 | 04/04/93 19:00 50.33 | 19.7 | 21.0 | 22.7 | 19.6 | 21.6 | 23.3 | 19.4 | 19.6 | 18.9 | 18.9 | 19.7 | 19.7 | 20.9 | 21.8 | 21.9 |
| 04/05/93 17:30 72.83 | 04/06/93 17:30 101.50 | 23.9 | 25.9 | 32.4 | 22.8 | 27.6 | 32.7 | 19.4 | 19.8 | 19.3 | 19.0 | 19.2 | 19.9 | 19.9 | 20.9 | 21.8 |
| 04/07/93 22:10 124.67 | 04/08/93 03:45 227.08 | 27.8 | 30.5 | 40.4 | 25.7 | 32.5 | 37.4 | 19.6 | 20.1 | 19.9 | 20.1 | 19.3 | 20.3 | 20.4 | 21.3 | 21.8 |
| 04/09/93 21:40 149.00 | 04/10/93 17:45 189.06 | 35.6 | 41.4 | 54.1 | 33.3 | 49.9 | 54.3 | 19.9 | 20.4 | 21.6 | 22.0 | 19.3 | 20.7 | 21.2 | 22.1 | 22.2 |
| 04/11/93 16:10 193.50 | 04/12/93 16:51 218.18 | 39.2 | 47.7 | 60.7 | 37.7 | 50.9 | 56.8 | 21.8 | 24.1 | 27.0 | 19.7 | 21.6 | 26.6 | 30.2 | 26.9 | 22.5 |
| 04/13/93 03:45 227.08 | 04/14/93 05:55 253.25 | 42.7 | 50.5 | 62.5 | 40.3 | 54.0 | 58.9 | 23.0 | 26.4 | 30.7 | 20.2 | 23.2 | 29.7 | 35.0 | 29.7 | 22.8 |
| 04/15/93 07:00 278.33 | 04/16/93 08:45 304.08 | 42.7 | 53.2 | 65.3 | 42.0 | 57.2 | 61.6 | 24.3 | 28.8 | 34.7 | 20.9 | 24.9 | 33.1 | 39.2 | 32.8 | 22.7 |
| 04/17/93 08:29 327.82 | 04/18/93 07:48 351.13 | 43.3 | 54.3 | 68.9 | 42.6 | 58.5 | 62.7 | 24.6 | 29.8 | 38.6 | 21.4 | 25.3 | 34.5 | 40.9 | 33.8 | 22.6 |
| 04/19/93 06:40 374.00 | 04/20/93 08:48 400.10 | 44.9 | 57.1 | 68.3 | 44.3 | 61.2 | 64.4 | 26.5 | 32.9 | 41.8 | 21.0 | 24.6 | 26.6 | 36.6 | 22.8 | 22.4 |
| 04/21/93 09:00 424.33 | 04/22/93 09:18 446.63 | 45.9 | 59.3 | 69.1 | 45.5 | 62.6 | 65.4 | 28.7 | 36.3 | 46.9 | 23.0 | 29.6 | 32.6 | 42.7 | 30.9 | 23.1 |
| 04/23/93 08:00 471.33 | 04/24/93 09:15 496.58 | 47.0 | 60.0 | 69.5 | 46.9 | 64.0 | 63.6 | 31.0 | 40.4 | 52.9 | 24.4 | 32.6 | 47.1 | 56.1 | 42.5 | 24.1 |
| 04/25/93 08:42 518.03 | 04/26/93 07:15 542.58 | 47.3 | 60.4 | 68.6 | 47.0 | 63.5 | 64.7 | 33.2 | 43.8 | 57.4 | 25.3 | 35.0 | 51.7 | 61.6 | 45.3 | 24.1 |
| 04/27/93 11:05 570.42 | 04/28/93 08:00 591.33 | 51.5 | 63.5 | 74.5 | 54.8 | 70.3 | 70.5 | 47.0 | 55.5 | 61.0 | 26.6 | 37.0 | 56.2 | 66.4 | 49.2 | 24.3 |
| 04/29/93 08:20 615.67 | 04/30/93 09:00 640.33 | 48.4 | 61.9 | 70.7 | 48.6 | 65.2 | 66.3 | 37.7 | 50.4 | 65.0 | 27.9 | 39.4 | 60.0 | 73.0 | 23.9 | 24.6 |
| 05/01/93 11:36 666.93 | 05/02/93 09:20 688.67 | 54.2 | 63.4 | 72.2 | 50.3 | 66.7 | 67.2 | 40.2 | 54.1 | 69.3 | 29.4 | 42.3 | 64.3 | 70.6 | 52.5 | 24.8 |
| 05/03/93 12:21 715.68 | 05/04/93 09:15 743.32 | 54.2 | 63.6 | 70.1 | 50.1 | 63.9 | 73.0 | 43.1 | 57.6 | 72.9 | 31.2 | 45.2 | 68.4 | 81.5 | 53.8 | 24.1 |
| 05/05/93 07:09 758.46 | 05/06/93 08:12 783.53 | 57.4 | 68.0 | 81.4 | 60.9 | 76.4 | 76.4 | 55.2 | 71.6 | 84.8 | 39.7 | 58.1 | 81.6 | 93.1 | 64.8 | 25.8 |
| 05/07/93 21:05 820.42 | 05/08/93 18:12 841.53 | 59.4 | 66.9 | 83.3 | 63.3 | 81.3 | 82.0 | 57.8 | 75.0 | 87.2 | 41.7 | 60.7 | 85.4 | 95.3 | 66.6 | 25.6 |
| 05/09/93 06:04 853.40 | 05/10/93 10:11 881.52 | 61.4 | 67.4 | 78.1 | 67.1 | 83.1 | 83.1 | 62.0 | 72.4 | 85.7 | 50.1 | 63.7 | 86.1 | 96.1 | 57.8 | 26.0 |
| 05/10/93 08:30 893.30 | | 61.8 | 67.9 | 91.0 | 65.6 | 90.5 | 93.7 | 60.0 | 77.2 | 88.2 | 43.5 | 62.2 | 90.1 | 96.2 | 67.2 | 26.5 |
| | | 62.0 | 73.3 | 90.5 | 68.1 | 89.0 | 95.5 | 71.4 | 86.6 | 96.6 | 50.3 | 60.5 | 95.0 | 97.4 | 62.4 | 26.2 |
| | | 63.0 | 70.4 | 95.5 | 68.1 | 96.1 | 95.5 | 62.4 | 79.4 | 89.7 | 45.4 | 56.0 | 95.5 | 96.3 | 69.6 | 26.2 |
| | | 63.6 | 71.3 | 96.2 | 68.8 | 94.7 | 81.5 | 64.6 | 82.3 | 92.8 | 47.2 | 67.6 | 95.5 | 97.5 | 70.6 | 26.5 |
| | | 63.6 | 70.1 | 82.9 | 69.3 | 88.4 | 76.1 | 66.0 | 84.1 | 92.6 | 48.7 | 68.6 | 88.7 | 90.0 | 64.9 | 27.6 |
| | | 63.6 | 70.8 | 79 | 75.7 | 94.2 | 86.4 | 76.3 | 82.9 | 94.5 | 50.6 | 69.7 | 83.6 | 85.1 | 76.0 | 27.5 |
| | | 64.2 | 76.8 | 84.2 | 76.4 | 92.5 | 90.5 | 67.5 | 85.7 | 90.0 | 51.1 | 69.3 | 90.2 | 97.9 | 66.2 | 26.5 |
| | | 65.2 | 84.5 | 93.0 | 71.2 | 91.9 | 90.7 | 70.2 | 89.2 | 92.1 | 52.8 | 71.3 | 92.1 | 93.2 | 91.2 | 26.3 |
| | | 67.3 | 85.8 | 83.8 | 72.8 | 94.1 | 83.2 | 71.7 | 90.4 | 92.4 | 53.8 | 72.7 | 95.5 | 97.5 | 70.1 | 26.8 |
| | | 68.9 | 82.1 | 83.6 | 75.9 | 94.1 | 85.7 | 73.8 | 91.6 | 92.4 | 55.3 | 74.1 | 94.6 | 95.8 | 71.6 | 27.5 |
| | | 70.8 | 79 | 86.7 | 80.3 | 94.6 | 90.8 | 79.8 | 93.8 | 94.9 | 60.4 | 78.5 | 94.2 | 95.0 | 74.0 | 27.0 |
| | | 72.0 | 77.5 | 85.8 | 77.7 | 94.1 | 93.0 | 94.4 | 77.4 | 94.7 | 59.0 | 78.5 | 94.2 | 95.0 | 73.1 | 27.6 |
| | | 73.5 | 79.6 | 86.7 | 80.3 | 94.6 | 90.8 | 79.8 | 93.8 | 94.9 | 60.4 | 78.5 | 94.2 | 95.0 | 74.0 | 27.0 |
| | | 74.4 | 80.9 | 87.6 | 81.0 | 95.3 | 91.0 | 94.8 | 94.8 | 95.3 | 60.9 | 78.5 | 94.2 | 95.0 | 75.0 | 27.0 |

Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually) [Continued]

| Date | Time | Elapsed Time | A2A | A3A | A4A | C2A | C3A | C4A | A2B | A3B | C1B | C2B | C3B | C4B | C6B | A2C | A3C |
|----------|-------|---------------|------|------|-------|------|------|------|------|------|-------|------|-------|-------|-------|------|------|
| | | Maximum Temp. | 1-h | 1-h | 1-h | 1-ft | 1-h | 1-ft | 12-h | 12-h | 12-ft | 12-h | 12-ft | 12-ft | 12-ft | 24-h | 24-h |
| 05/11/93 | 09:14 | 904.57 | 79 | 86 | 112 | 62 | 96 | 92 | 84 | 95 | 95.1 | 61.7 | 79.3 | 94.5 | 92.6 | 73.1 | 31.3 |
| 05/12/93 | 12:24 | 931.73 | 75.2 | 80.9 | 87.3 | 81.5 | 95.0 | 91.5 | 80.8 | 93.5 | 95.1 | 62.1 | 79.4 | 92.0 | 88.3 | 74.5 | 33.9 |
| 05/13/93 | 09:30 | 952.83 | 75.3 | 83.0 | 86.4 | 74.2 | 92.3 | 87.7 | 79.9 | 92.1 | 92.1 | 63.2 | 94.6 | 92.2 | 78.9 | 32.6 | 34.7 |
| 05/14/93 | 04:00 | 971.33 | 76.3 | 82.4 | 86.6 | 76.2 | 95.0 | 88.5 | 80.6 | 93.8 | 94.5 | 94.1 | 86.8 | 75.2 | 71.2 | 35.3 | 35.3 |
| 05/15/93 | 09:21 | 1000.68 | 77.4 | 84.0 | 88.3 | 78.0 | 94.1 | 88.9 | 81.8 | 94.2 | 94.1 | 84.0 | 81.7 | 82.3 | 75.4 | 33.2 | 36.1 |
| 05/16/93 | 15:43 | 1031.05 | 78.2 | 84.6 | 89.0 | 77.6 | 95.0 | 95.0 | 89.0 | 92.3 | 95.5 | 94.7 | 92.9 | 92.7 | 94.4 | 34.1 | 37.0 |
| 05/17/93 | 23:27 | 1062.76 | 79.3 | 85.8 | 90.0 | 80.3 | 95.4 | 89.9 | 83.2 | 94.7 | 95.7 | 85.5 | 82.7 | 83.9 | 81.2 | 34.1 | 38.4 |
| 05/18/93 | 09:50 | 1073.17 | 76.8 | 85.5 | 89.4 | 79.1 | 97.9 | 84.4 | 84.4 | 95.0 | 96.2 | 87.3 | 94.6 | 93.7 | 90.6 | 35.6 | 38.9 |
| 05/19/93 | 01:53 | 1089.22 | 77.7 | 83.5 | 87.3 | 78.0 | 93.5 | 87.3 | 83.0 | 93.2 | 94.2 | 87.8 | 84.1 | 93.6 | 91.2 | 84.5 | 39.4 |
| 05/19/93 | 23:58 | 1111.30 | 75.9 | 82.2 | 85.6 | 76.3 | 92.9 | 84.1 | 81.6 | 91.6 | 92.2 | 87.9 | 81.2 | 93.1 | 89.0 | 79.0 | 40.1 |
| 05/20/93 | 23:24 | 1134.73 | 72.2 | 80.1 | 83.8 | 73.3 | 90.2 | 81.9 | 79.6 | 85.3 | 90.6 | 87.9 | 87.7 | 86.1 | 78.8 | 37.8 | 40.6 |
| 05/22/93 | 22:00 | 1161.33 | 72.1 | 87.1 | 91.1 | 67.3 | 92.2 | 81.1 | 78.1 | 88.9 | 90.5 | 87.1 | 81.2 | 87.7 | 75.9 | 38.8 | 41.9 |
| 05/23/93 | 10:46 | 1194.13 | 71.4 | 78.5 | 80.7 | 70.2 | 90.7 | 81.8 | 77.7 | 88.9 | 88.7 | 67.6 | 78.6 | 91.4 | 85.4 | 75.5 | 42.4 |
| 05/24/93 | 11:54 | 1219.23 | 71.4 | 80.2 | 79.6 | 69.7 | 88.9 | 80.7 | 78.0 | 85.6 | 87.1 | 67.8 | 79.5 | 69.2 | 86.1 | 70.5 | 42.6 |
| 05/24/93 | 19:10 | 1226.50 | 71.0 | 79.8 | 81.1 | 70.4 | 88.8 | 81.0 | 77.4 | 85.8 | 86.1 | 67.8 | 79.7 | 69.4 | 86.2 | 70.1 | 42.9 |
| 05/25/93 | 21:30 | 1252.83 | 69.1 | 77.0 | 82.4 | 68.1 | 87.1 | 80.5 | 75.9 | 85.4 | 82.6 | 67.7 | 78.6 | 88.1 | 72.5 | 40.5 | 43.6 |
| 05/26/93 | 19:20 | 1274.67 | 68.5 | 74.3 | 83.4 | 64.6 | 85.4 | 79.3 | 74.0 | 83.7 | 80.0 | 66.6 | 77.6 | 88.6 | 82.9 | 71.3 | 40.4 |
| 05/27/93 | 09:12 | 1288.53 | 65.6 | 73.7 | 84.5 | 63.1 | 84.6 | 77.9 | 73.7 | 80.2 | 78.7 | 66.7 | 77.3 | 85.9 | 82.6 | 67.6 | 40.7 |
| 05/28/93 | 09:19 | 1312.65 | 63.7 | 72.6 | 89.3 | 60.9 | 83.7 | 77.5 | 72.7 | 82.5 | 77.6 | 66.1 | 76.4 | 85.1 | 81.6 | 71.2 | 41.2 |
| 05/29/93 | 05:48 | 1333.13 | 62.6 | 71.4 | 83.8 | 60.9 | 81.9 | 77.3 | 72.1 | 81.8 | 76.7 | 65.6 | 76.3 | 83.3 | 83.1 | 79.0 | 41.5 |
| 05/30/93 | 09:30 | 1360.83 | 61.8 | 70.8 | 98.7 | 60.8 | 81.3 | 77.0 | 71.3 | 81.4 | 75.9 | 65.0 | 75.6 | 83.1 | 83.3 | 73.4 | 41.9 |
| 05/31/93 | 11:10 | 1387.00 | 62.0 | 70.3 | 103.0 | 61.5 | 80.3 | 76.1 | 70.5 | 80.7 | 76.4 | 64.2 | 74.6 | 82.2 | 83.1 | 77.4 | 41.6 |
| 06/01/93 | 09:25 | 1408.75 | 61.2 | 70.8 | 106.0 | 61.1 | 79.7 | 75.3 | 70.1 | 80.3 | 76.4 | 64.1 | 74.3 | 81.0 | 82.0 | 67.8 | 45.0 |
| 06/02/93 | 08:00 | 1431.33 | 62.9 | 72.2 | 110.2 | 63.3 | 78.6 | 77.3 | 70.0 | 80.5 | 78.1 | 63.8 | 74.0 | 81.3 | 82.7 | 70.5 | 42.2 |
| 06/03/93 | 09:27 | 1456.76 | 62.7 | 73.0 | 112.0 | 63.0 | 78.0 | 77.3 | 69.8 | 80.5 | 81.0 | 63.7 | 73.4 | 80.7 | 83.5 | 73 | 45.3 |
| 06/03/93 | 12:00 | 1459.33 | 62.4 | 73 | 112.1 | 62.5 | 77.4 | 76.3 | 69.3 | 80.3 | 63 | 63 | 79.8 | 80.2 | 81.2 | 72.6 | 41.7 |

Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually) [Continued]

| Date | Time | Elapsed Time | AAC | C1C | C2C | C3C | C4C | A3D | C4D | C6D | TW7B | TW7C | TW7D | |
|--------------------|-------|--------------|------|------|------|------|------|------|------|------|------|------|------|------|
| | | | 24-h | 24-h | 24-h | 24-h | 24-h | 29-h | 29-h | 29-h | 29-h | 12-h | 24-h | 29-h |
| Maximum Temp. ---> | 49 | 49 | 49 | 52 | 49 | 52 | 49 | 32 | 34 | 32 | 30 | 32 | 30 | 30 |
| 04/03/93 | 16:40 | 0:00 | | | | | | | | | | | | |
| 04/03/93 | 17:00 | 0:33 | 21.9 | 21.5 | 21.6 | 21.7 | 21.6 | 21.9 | 21.9 | 21.9 | 21.9 | 21.8 | 21.9 | 21.9 |
| 04/04/93 | 17:10 | 24.50 | 21.9 | 21.4 | 21.5 | 21.6 | 21.6 | 21.9 | 21.8 | 21.8 | 21.8 | 21.6 | 21.8 | 21.8 |
| 04/05/93 | 19:00 | 50.33 | 21.6 | 21.5 | 21.4 | 21.4 | 21.5 | 21.7 | 21.7 | 21.6 | 21.5 | 21.5 | 21.7 | 21.7 |
| 04/06/93 | 17:30 | 72.63 | 22.3 | 21.6 | 21.6 | 21.8 | 21.6 | 21.9 | 21.9 | 21.9 | 21.8 | 21.9 | 21.9 | 21.9 |
| 04/07/93 | 22:10 | 101.50 | 22.2 | 21.5 | 21.4 | 21.6 | 21.6 | 21.8 | 21.8 | 21.7 | 21.6 | 21.8 | 21.8 | 21.8 |
| 04/08/93 | 21:20 | 124.67 | 22.2 | 21.6 | 21.6 | 21.6 | 21.6 | 21.7 | 21.8 | 21.8 | 21.6 | 21.5 | 21.6 | 21.6 |
| 04/09/93 | 21:40 | 149.00 | 22.4 | 21.6 | 21.6 | 21.7 | 21.6 | 21.8 | 21.8 | 21.7 | 21.7 | 21.6 | 21.6 | 21.6 |
| 04/10/93 | 17:45 | 169.06 | 22.7 | 21.5 | 21.7 | 21.7 | 21.6 | 22.0 | 21.8 | 21.8 | 21.6 | 21.4 | 21.6 | 21.6 |
| 04/11/93 | 16:10 | 193.50 | 23.0 | 21.7 | 21.9 | 22.1 | 22.5 | 21.9 | 21.8 | 21.7 | 21.6 | 21.5 | 21.7 | 20.1 |
| 04/12/93 | 16:51 | 216.18 | 23.3 | 21.8 | 22.2 | 22.4 | 22.8 | 21.8 | 21.8 | 21.7 | 21.6 | 21.6 | 21.7 | 20.7 |
| 04/13/93 | 03:45 | 227.08 | 23.4 | 21.9 | 22.4 | 22.6 | 23.2 | 21.8 | 22.0 | 21.9 | 21.9 | 21.8 | 21.9 | 21.6 |
| 04/14/93 | 05:55 | 253.25 | 23.6 | 22.0 | 22.6 | 23.2 | 23.6 | 21.9 | 22.1 | 21.9 | 22.0 | 21.9 | 21.9 | 21.7 |
| 04/15/93 | 07:00 | 278.33 | 24.0 | 22.1 | 22.8 | 23.4 | 24.0 | 24.0 | 21.9 | 22.1 | 21.9 | 21.8 | 23.0 | 21.6 |
| 04/16/93 | 06:45 | 304.08 | 24.6 | 22.3 | 23.4 | 24.2 | 24.7 | 24.7 | 22.1 | 22.2 | 22.2 | 21.9 | 24.2 | 22.7 |
| 04/17/93 | 08:29 | 322.82 | 24.6 | 22.3 | 23.3 | 24.2 | 24.7 | 22.0 | 22.1 | 22.0 | 22.0 | 21.8 | 25.5 | 22.4 |
| 04/18/93 | 07:46 | 351.13 | 25.1 | 22.5 | 23.5 | 24.5 | 25.2 | 22.1 | 22.3 | 22.1 | 22.0 | 22.0 | 22.6 | 21.5 |
| 04/19/93 | 06:40 | 377.00 | 25.4 | 22.8 | 23.9 | 24.9 | 25.6 | 22.2 | 22.4 | 22.0 | 22.1 | 22.1 | 28.6 | 21.7 |
| 04/20/93 | 06:46 | 400.10 | 25.7 | 22.9 | 24.2 | 25.3 | 26.3 | 22.5 | 22.5 | 22.1 | 22.3 | 22.1 | 30.4 | 22.1 |
| 04/21/93 | 09:00 | 422.33 | 26.2 | 23.3 | 24.8 | 26.1 | 27.0 | 22.3 | 22.6 | 22.4 | 22.2 | 22.1 | 32.4 | 21.8 |
| 04/22/93 | 09:16 | 446.63 | 26.7 | 23.4 | 25.2 | 26.8 | 28.0 | 22.5 | 22.7 | 22.4 | 22.6 | 22.3 | 34.2 | 23.7 |
| 04/23/93 | 08:00 | 471.33 | 27.1 | 23.8 | 25.8 | 27.4 | 28.7 | 22.6 | 22.9 | 22.5 | 22.7 | 22.3 | 36.2 | 24.0 |
| 04/24/93 | 09:15 | 496.56 | 27.4 | 24.0 | 26.0 | 27.9 | 29.6 | 22.6 | 22.6 | 22.6 | 22.6 | 22.6 | 38.0 | 24.3 |
| 04/25/93 | 08:42 | 518.03 | 27.6 | 24.3 | 26.3 | 28.4 | 30.2 | 22.7 | 23.1 | 22.6 | 22.6 | 22.7 | 39.8 | 24.6 |
| 04/26/93 | 07:15 | 542.59 | 28.4 | 24.8 | 27.1 | 29.4 | 31.6 | 22.9 | 22.9 | 22.7 | 23.1 | 22.9 | 41.8 | 25.1 |
| 04/27/93 | 11:05 | 570.42 | 29.1 | 25.0 | 27.7 | 30.3 | 32.9 | 22.9 | 23.4 | 22.7 | 23.1 | 22.9 | 43.7 | 25.7 |
| 04/28/93 | 08:00 | 591.33 | 29.6 | 25.5 | 27.1 | 29.8 | 31.3 | 23.0 | 23.4 | 22.9 | 23.3 | 23.3 | 45.4 | 26.1 |
| 04/29/93 | 09:20 | 615.67 | 30.0 | 26.1 | 29.2 | 32.6 | 35.2 | 23.1 | 23.6 | 23.3 | 23.3 | 23.3 | 47.1 | 26.1 |
| 04/30/93 | 09:00 | 640.33 | 30.7 | 26.4 | 30.6 | 33.7 | 36.5 | 23.1 | 23.7 | 23.3 | 23.5 | 23.1 | 48.8 | 26.6 |
| 05/01/93 | 11:36 | 666.93 | 31.1 | 26.8 | 31.4 | 34.3 | 37.1 | 23.2 | 23.8 | 23.3 | 23.8 | 23.5 | 49.6 | 28.6 |
| 05/02/93 | 09:20 | 688.67 | 31.9 | 27.7 | 31.6 | 35.2 | 37.7 | 23.7 | 24.3 | 24.5 | 24.3 | 23.8 | 50.6 | 29.8 |
| 05/03/93 | 12:21 | 715.68 | 32.1 | 27.7 | 31.8 | 35.1 | 37.0 | 23.6 | 24.3 | 24.5 | 24.4 | 24.4 | 50.5 | 29.2 |
| 05/04/93 | 15:59 | 749.32 | 32.7 | 28.6 | 32.6 | 35.6 | 37.2 | 24.2 | 24.9 | 24.4 | 25.0 | 25.1 | 51.4 | 29.9 |
| 05/05/93 | 07:09 | 758.48 | 33.0 | 28.8 | 32.9 | 35.7 | 37.1 | 24.2 | 25.0 | 25.1 | 25.2 | 25.0 | 52.2 | 29.8 |
| 05/06/93 | 08:12 | 783.53 | 33.6 | 29.4 | 34.1 | 36.0 | 37.2 | 24.5 | 25.3 | 25.4 | 25.5 | 25.3 | 53.1 | 30.3 |
| 05/07/93 | 21:05 | 820.42 | 34.1 | 30.0 | 36.9 | 36.2 | 37.3 | 24.8 | 25.6 | 25.0 | 25.7 | 25.7 | 54.3 | 30.3 |
| 05/08/93 | 10:12 | 841.53 | 34.3 | 30.2 | 36.4 | 36.3 | 37.2 | 24.8 | 25.7 | 25.2 | 25.7 | 25.8 | 54.6 | 30.3 |
| 05/09/93 | 06:04 | 853.40 | 34.9 | 30.4 | 36.6 | 36.1 | 37.6 | 25.0 | 25.9 | 25.3 | 25.7 | 25.9 | 55.1 | 30.7 |
| 05/10/93 | 10:11 | 881.52 | 35.7 | 30.6 | 35.9 | 37.3 | 37.9 | 25.0 | 25.9 | 25.4 | 26.1 | 25.9 | 55.7 | 30.8 |
| 05/11/93 | ? | 893.30 | 35.8 | 30.9 | 35.7 | 37.0 | 37.9 | 25.1 | 25.9 | 25.4 | 26.2 | 25.8 | 56.2 | 30.5 |

Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually) [Continued]

| Date | Time | Elapsed Time | A1C 24-ft | C1C 24-ft | C2C 24-ft | C3C 24-ft | C4C 24-ft | A3D 29-ft | A4D 29-ft | C2D 29-ft | C3D 29-ft | C4D 29-ft | TW7B 12-ft | TW7C 24-ft | TW7D 29-ft |
|----------|-------|---------------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|---------------|
| 05/11/93 | 09:14 | 90:57 | 36.6 | 31.0 | 36.2 | 49 | 52 | 49 | 32 | 34 | 32 | 33 | 30 | 62 | 39 |
| | | Maximum Temp. ----> | 49 | 42 | 49 | 24-ft | 24-ft | 24-ft | 29-ft | 29-ft | 29-ft | 30 | 32 | 30 | 28 |
| 05/12/93 | 12:24 | 931.73 | 36.6 | 30.9 | 35.6 | 37.9 | 36.6 | 25.2 | 26.1 | 25.7 | 26.4 | 26.0 | 25.9 | 56.3 | 31.1 |
| 05/13/93 | 09:30 | 932.83 | 37.6 | 31.6 | 36.4 | 38.6 | 39.6 | 25.6 | 26.6 | 26.3 | 26.4 | 26.4 | 26.3 | 57.5 | 31.6 |
| 05/14/93 | 04:00 | 971.33 | 38.4 | 32.2 | 36.7 | 39.0 | 40.2 | 26.1 | 27.2 | 26.3 | 26.8 | 26.8 | 27.2 | 58.2 | 31.8 |
| 05/15/93 | 09:21 | 1000.68 | 39.6 | 32.3 | 37.0 | 39.9 | 41.0 | 26.2 | 27.4 | 26.5 | 27.2 | 26.9 | 27.0 | 58.7 | 32.0 |
| 05/16/93 | 15:43 | 1031.05 | 40.9 | 32.7 | 37.4 | 40.9 | 42.2 | 26.3 | 27.7 | 26.3 | 27.2 | 27.5 | 27.5 | 59.6 | 32.6 |
| 05/17/93 | 23:27 | 1062.78 | 42.6 | 33.9 | 38.7 | 42.9 | 44.5 | 26.9 | 28.4 | 26.9 | 28.4 | 28.0 | 28.3 | 61.0 | 33.4 |
| 05/18/93 | 09:50 | 1073.17 | 43.3 | 33.6 | 39.3 | 43.4 | 45.1 | 27.1 | 28.5 | 27.2 | 28.1 | 28.1 | 28.1 | 61.0 | 33.7 |
| 05/19/93 | 01:53 | 1089.22 | 43.6 | 34.5 | 39.6 | 44.1 | 46.0 | 27.4 | 28.7 | 27.2 | 28.3 | 28.2 | 28.2 | 61.6 | 33.8 |
| 05/19/93 | 23:58 | 1111.30 | 44.7 | 35.1 | 40.6 | 45.1 | 46.9 | 27.6 | 29.1 | 27.5 | 28.4 | 28.5 | 28.2 | 61.8 | 34.3 |
| 05/20/93 | 23:24 | 1134.73 | 45.0 | 35.5 | 41.2 | 46.0 | 47.4 | 27.9 | 29.5 | 27.8 | 28.7 | 28.9 | 28.4 | 61.8 | 34.9 |
| 05/22/93 | 22:00 | 1161.33 | 46.1 | 36.6 | 42.9 | 47.4 | 48.4 | 28.6 | 30.3 | 28.4 | 29.4 | 29.6 | 29.6 | 62.0 | 35.4 |
| 05/23/93 | 10:46 | 1194.13 | 46.6 | 37.1 | 43.1 | 47.9 | 48.6 | 28.7 | 30.3 | 28.5 | 29.6 | 29.7 | 28.9 | 61.7 | 37.5 |
| 05/24/93 | 11:54 | 1219.23 | 47.1 | 37.7 | 45.8 | 48.9 | 48.8 | 28.8 | 30.6 | 28.6 | 29.6 | 29.8 | 28.9 | 61.1 | 37.4 |
| 05/24/93 | 19:10 | 1226.50 | 47.1 | 37.8 | 47.4 | 49.1 | 48.9 | 29.1 | 30.8 | 28.9 | 29.9 | 30.0 | 29.3 | 61.0 | 37.2 |
| 05/25/93 | 21:30 | 1252.83 | 47.4 | 38.6 | 48.0 | 50.3 | 49.0 | 29.5 | 31.3 | 29.3 | 30.4 | 30.4 | 29.6 | 60.8 | 37.3 |
| 05/26/93 | 19:20 | 1274.67 | 47.3 | 39.1 | 48.1 | 49.5 | 49.9 | 29.6 | 31.3 | 29.4 | 30.5 | 30.4 | 29.5 | 60.2 | 37.2 |
| 05/27/93 | 09:12 | 1288.53 | 47.6 | 39.8 | 48.5 | 51.3 | 49.0 | 29.8 | 31.6 | 29.8 | 30.5 | 30.5 | 29.3 | 60.0 | 37.6 |
| 05/28/93 | 09:19 | 1312.65 | 48.0 | 40.4 | 48.4 | 51.6 | 49.1 | 30.2 | 32.0 | 31.2 | 30.7 | 30.7 | 29.6 | 59.7 | 37.8 |
| 05/29/93 | 05:48 | 1333.13 | 48.0 | 41.2 | 48.3 | 51.6 | 49.1 | 30.5 | 32.3 | 30.4 | 31.4 | 31.0 | 30.2 | 59.6 | 37.8 |
| 05/30/93 | 09:30 | 1360.83 | 48.4 | 41.8 | 48.3 | 51.9 | 49.3 | 30.8 | 32.8 | 30.8 | 31.9 | 31.3 | 30.2 | 59.4 | 38.4 |
| 05/31/93 | 11:40 | 1387.00 | 48.2 | 41.9 | 48.1 | 51.3 | 48.6 | 31.1 | 32.9 | 31.0 | 32.0 | 31.4 | 30.2 | 58.4 | 38.3 |
| 06/01/93 | 09:25 | 1408.75 | 48.2 | 42.2 | 48.2 | 51.2 | 48.6 | 31.3 | 33.1 | 31.2 | 32.1 | 31.2 | 30.4 | 58.4 | 38.3 |
| 06/02/93 | 08:00 | 1431.33 | 48.4 | 42.4 | 48.4 | 51.1 | 48.8 | 31.8 | 33.7 | 31.7 | 32.5 | 31.8 | 30.4 | 58.7 | 38.7 |
| 06/03/93 | 09:27 | 1456.78 | 48.6 | 42.3 | 48.3 | 51.1 | 48.8 | 32.2 | 33.9 | 32.2 | 33 | 32 | 30.3 | 58.3 | 38.9 |
| 06/03/93 | 12:00 | 1459.33 | 48.1 | 41.8 | 47.6 | 50.4 | 48.2 | 31.8 | 33.6 | 31.6 | 32.7 | 31.7 | 30.2 | 58 | 38.5 |

Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually) [Continued]

| Date | Time | Elapsed Time | 1-foot | Average Temperatures | | | Grand Average |
|----------|-------|--------------|--------|----------------------|------|------|---------------|
| | | | | 67 | 68 | 47 | |
| 04/03/93 | 16:40 | 0.00 | 16.3 | 19.7 | 21.7 | 20.1 | 20.0 |
| 04/03/93 | 17:00 | 0.33 | 16.3 | 19.6 | 21.7 | 21.2 | 20.8 |
| 04/04/93 | 17:10 | 24.50 | 21.3 | 19.6 | 21.7 | 23.5 | 22.6 |
| 04/05/93 | 19:00 | 50.33 | 27.6 | 19.7 | 21.6 | 25.5 | 24.2 |
| 04/06/93 | 17:30 | 72.03 | 32.4 | 20.0 | 21.9 | 27.6 | 26.1 |
| 04/07/93 | 22:10 | 101.50 | 36.3 | 20.6 | 21.6 | 29.9 | 27.6 |
| 04/08/93 | 21:20 | 124.67 | 42.9 | 21.6 | 21.9 | 22.0 | 29.4 |
| 04/09/93 | 21:40 | 149.00 | 46.5 | 23.1 | 22.1 | 33.6 | 30.7 |
| 04/10/93 | 17:45 | 169.08 | 48.6 | 24.7 | 22.4 | 36.0 | 32.5 |
| 04/11/93 | 18:10 | 193.50 | 51.2 | 27.2 | 22.6 | 36.3 | 34.2 |
| 04/12/93 | 18:51 | 218.16 | 53.7 | 29.6 | 22.6 | 39.3 | 35.0 |
| 04/13/93 | 03:45 | 227.06 | 56.7 | 30.9 | 22.6 | 41.6 | 36.8 |
| 04/14/93 | 05:55 | 250.25 | 58.7 | 34.0 | 23.1 | 43.8 | 38.6 |
| 04/15/93 | 07:00 | 276.33 | 58.1 | 37.3 | 23.8 | 45.8 | 40.2 |
| 04/16/93 | 08:45 | 301.06 | 58.5 | 40.9 | 23.8 | 42.4 | 40.4 |
| 04/17/93 | 08:29 | 322.82 | 57.5 | 44.2 | 23.8 | 48.9 | 43.7 |
| 04/18/93 | 07:48 | 351.13 | 58.6 | 47.2 | 24.2 | 51.0 | 44.6 |
| 04/19/93 | 08:40 | 374.00 | 60.2 | 50.4 | 24.5 | 53.1 | 46.3 |
| 04/20/93 | 08:46 | 400.10 | 61.6 | 53.8 | 24.7 | 54.5 | 47.7 |
| 04/21/93 | 09:00 | 424.33 | 62.1 | 56.7 | 25.2 | 56.0 | 49.1 |
| 04/22/93 | 09:16 | 448.63 | 62.6 | 59.3 | 25.7 | 57.6 | 50.5 |
| 04/23/93 | 08:00 | 471.33 | 64.2 | 61.6 | 26.2 | 59.4 | 52.2 |
| 04/24/93 | 09:15 | 496.58 | 65.6 | 64.4 | 26.6 | 60.7 | 53.5 |
| 04/25/93 | 08:42 | 518.03 | 67.4 | 66.3 | 27.0 | 62.8 | 55.5 |
| 04/26/93 | 07:15 | 542.58 | 70.4 | 68.6 | 27.7 | 63.1 | 57.5 |
| 04/27/93 | 11:05 | 570.42 | 73.2 | 71.2 | 28.4 | 67.1 | 60.9 |
| 04/28/93 | 08:00 | 591.33 | 76.8 | 73.1 | 29.0 | 67.3 | 59.4 |
| 04/29/93 | 08:20 | 615.67 | 79.7 | 75.6 | 29.8 | 69.7 | 61.6 |
| 04/30/93 | 09:00 | 640.33 | 77.7 | 75.7 | 30.5 | 68.4 | 61.2 |
| 05/01/93 | 11:36 | 666.93 | 75.1 | 75.5 | 31.1 | 66.9 | 60.6 |
| 05/02/93 | 09:20 | 688.67 | 71.6 | 74.9 | 31.8 | 59.4 | 58.8 |
| 05/03/93 | 12:21 | 715.68 | 74.7 | 76.0 | 31.7 | 67.1 | 65.5 |
| 05/04/93 | 15:59 | 743.32 | 79.4 | 76.6 | 32.4 | 70.1 | 63.4 |
| 05/05/93 | 07:09 | 758.48 | 81.2 | 79.9 | 32.6 | 71.1 | 64.5 |
| 05/06/93 | 08:12 | 783.53 | 81.7 | 80.5 | 33.1 | 71.1 | 65.0 |
| 05/07/93 | 21:05 | 820.42 | 82.4 | 82.0 | 33.8 | 71.8 | 66.1 |
| 05/08/93 | 16:12 | 841.53 | 81.4 | 81.4 | 33.9 | 70.8 | 65.5 |
| 05/09/93 | 06:04 | 853.40 | 82.7 | 82.7 | 34.1 | 71.9 | 66.5 |
| 05/10/93 | 10:11 | 881.52 | 84.3 | 83.1 | 34.5 | 72.4 | 67.2 |
| 05/10/93 | - | 893.30 | 85.1 | 83.4 | 34.6 | 72.9 | 67.6 |

Table B-1 Ground Electrodes and Outside Thermowell (TW7)
Temperature (Recorded Manually) [Continued]

| Date | Time | Elapsed Time | Maximum Temp. | Average Temperatures | | | | | Grand Average |
|----------|-------|-----------------|---------------|----------------------|---------|---------|----------------------------|----|------------------|
| | | | | 1-foot | 12-foot | 24-foot | Opposite Electrods, All | | |
| 05/11/93 | 09:14 | 90:57 | 65.2 | 63.0 | 35.0 | 73.1 | 68.0 | 72 | |
| 05/12/93 | 12:24 | 931.73 | 61.5 | 62.6 | 35.1 | 71.4 | 66.4 | | |
| 05/13/93 | 09:30 | 952.83 | 64.4 | 64.9 | 35.9 | 73.7 | 68.4 | | |
| 05/14/93 | 04:00 | 971.33 | 64.4 | 64.0 | 36.4 | 73.0 | 68.2 | | |
| 05/15/93 | 09:21 | 1000.66 | 65.3 | 65.0 | 37.0 | 74.1 | 69.1 | | |
| 05/16/93 | 15:43 | 1031.05 | 65.7 | 66.4 | 37.9 | 75.3 | 70.0 | | |
| 05/17/93 | 23:27 | 1062.78 | 66.6 | 67.7 | 39.5 | 76.7 | 71.4 | | |
| 05/18/93 | 09:50 | 1073.17 | 66.7 | 66.2 | 39.9 | 77.2 | 71.7 | | |
| 05/19/93 | 01:53 | 1069.22 | 64.6 | 66.5 | 40.5 | 75.5 | 70.6 | | |
| 05/19/93 | 23:58 | 1111.30 | 62.6 | 84.5 | 41.4 | 74.4 | 69.6 | | |
| 05/20/93 | 23:24 | 1131.73 | 60.3 | 62.3 | 41.9 | 72.6 | 68.2 | | |
| 05/22/93 | 22:00 | 1161.33 | 76.5 | 62.5 | 43.2 | 73.1 | 68.2 | | |
| 05/23/93 | 10:48 | 1194.13 | 76.9 | 61.7 | 43.4 | 72.9 | 68.1 | | |
| 05/24/93 | 11:54 | 1219.23 | 76.4 | 60.5 | 44.4 | 72.0 | 67.8 | | |
| 05/24/93 | 19:10 | 1226.50 | 76.7 | 80.3 | 44.7 | 72.0 | 68.0 | | |
| 05/25/93 | 21:30 | 1252.63 | 77.4 | 79.4 | 45.4 | 71.5 | 67.5 | | |
| 05/26/93 | 19:20 | 1274.67 | 75.6 | 77.9 | 45.4 | 70.6 | 66.4 | | |
| 05/27/93 | 09:12 | 1288.53 | 74.9 | 76.6 | 45.9 | 69.6 | 65.9 | | |
| 05/28/93 | 09:19 | 1312.65 | 74.7 | 76.7 | 46.2 | 70.4 | 65.9 | | |
| 05/29/93 | 05:46 | 1333.13 | 74.7 | 77.2 | 46.3 | 70.9 | 68.2 | | |
| 05/30/93 | 09:30 | 1360.83 | 75.1 | 76.1 | 46.6 | 70.7 | 66.0 | | |
| 05/31/93 | 11:40 | 1387.00 | 75.5 | 76.1 | 46.4 | 71.0 | 66.0 | | |
| 06/01/93 | 09:25 | 1408.75 | 75.7 | 74.6 | 46.5 | 70.2 | 65.5 | | |
| 06/02/93 | 08:00 | 1431.33 | 77.5 | 75.1 | 46.7 | 71.2 | 66.3 | | |
| 06/03/93 | 09:27 | 1456.78 | 77.7 | 75.7 | 46.7 | 71.0 | 66.6 | | |
| 06/03/93 | 12:00 | 1459.33 | 77.3 | 74.9 | 46.1 | 71.1 | 66.0 | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1)

| | Date | Time | Elapsed | TW1A 1-ft | TW2A 1-ft | TW3A 1-ft | TW4A 1-ft | TW5A 1-ft | TW6A 1-ft | TW7A 1-ft | TW8B 12-ft | TW9B 12-ft | TW10B 12-ft | TW11B 12-ft | TW12B 20-ft | TW13B 20-ft | TW14B 20-ft |
|---------------|-------|--------|---------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|----------------|----------------|----------------|----------------|----------------|
| Maximum Temp. | | | Maximum Temp. | 103.1 | 129 | 104.7 | 195.1 | 243 | 180.6 | ERR | 93.7 | 126 | 110.6 | 187.5 | 201.3 | 206.2 | ERR |
| 04/03/93 | 16:40 | 0.00 | | | | | | | | | | | | | | | |
| 04/03/93 | 20:05 | 3.42 | | | | | | | | | | | | | | | |
| 04/03/93 | 20:45 | 4.08 | | | | | | | | | | | | | | | |
| 04/03/93 | 19:00 | 2.33 | | 17.9 | | | | | | | | | | | | | |
| 04/04/93 | 16:00 | 23.33 | | | | 34.7 | | | | | | | | | | | |
| 04/05/93 | 19:30 | 50.83 | | | | | 75.0 | | | | | | | | | | |
| 04/06/93 | 16:00 | 71.33 | | | | | | 65.0 | | | | | | | | | |
| 04/07/93 | 19:00 | 96.33 | | | | | | | 67.0 | | | | | | | | |
| 04/08/93 | 19:15 | 122.58 | | | | | | | | 71.8 | | | | | | | |
| 04/09/93 | 20:00 | 147.33 | | | | | | | | | 89.3 | | | | | | |
| 04/10/93 | 19:55 | 171.25 | | | | | | | | | | 90.9 | | | | | |
| 04/11/93 | 20:45 | 220.08 | | | | | | | | | | | 93.5 | | | | |
| 04/13/93 | 20:00 | 243.33 | | | | | | | | | | | | 96.5 | | | |
| 04/14/93 | 20:25 | 267.75 | | | | | | | | | | | | | 97.0 | | |
| 04/15/93 | 21:00 | 292.33 | | | | | | | | | | | | | | 97.0 | |
| 04/16/93 | 14:45 | 310.06 | | | | | | | | | | | | | | | 97.7 |
| 04/17/93 | 23:20 | 342.67 | | | | | | | | | | | | | | | 98.6 |
| 04/18/93 | 19:14 | 362.57 | | | | | | | | | | | | | | | 98.6 |
| 04/19/93 | 16:40 | 366.00 | | | | | | | | | | | | | | | 99.5 |
| 04/20/93 | 16:50 | 410.17 | | | | | | | | | | | | | | | 101.9 |
| 04/21/93 | 18:53 | 434.22 | | | | | | | | | | | | | | | 102.7 |
| 04/22/93 | 19:14 | 458.57 | | | | | | | | | | | | | | | 104.1 |
| 04/23/93 | 21:25 | 484.75 | | | | | | | | | | | | | | | 104.9 |
| 04/24/93 | 20:00 | 507.33 | | | | | | | | | | | | | | | 105.6 |
| 04/25/93 | 20:50 | 532.17 | | | | | | | | | | | | | | | 106.4 |
| 04/26/93 | 20:30 | 555.83 | | | | | | | | | | | | | | | 107.2 |
| 04/27/93 | 20:55 | 580.25 | | | | | | | | | | | | | | | 108.0 |
| 04/28/93 | 18:35 | 601.92 | | | | | | | | | | | | | | | 108.8 |
| 04/29/93 | 18:35 | 724.00 | | | | | | | | | | | | | | | 111.3 |
| 04/30/93 | 20:00 | 651.33 | | | | | | | | | | | | | | | 111.8 |
| 05/01/93 | 20:30 | 675.83 | | | | | | | | | | | | | | | 114.6 |
| 05/02/93 | 20:35 | 699.92 | | | | | | | | | | | | | | | 115.5 |
| 05/03/93 | 20:40 | 724.00 | | | | | | | | | | | | | | | 115.8 |
| 05/04/93 | 19:08 | 746.47 | | | | | | | | | | | | | | | 116.8 |
| 05/05/93 | 22:30 | 773.83 | | | | | | | | | | | | | | | 117.3 |
| 05/06/93 | 21:00 | 796.33 | | | | | | | | | | | | | | | 118.9 |
| 05/07/93 | 21:44 | 821.07 | | | | | | | | | | | | | | | 120.0 |
| 05/08/93 | 20:04 | 833.40 | | | | | | | | | | | | | | | 124.0 |
| 05/09/93 | 21:07 | 868.45 | | | | | | | | | | | | | | | 126.8 |
| 05/10/93 | | 891.75 | | | | | | | | | | | | | | | 137.2 |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Elapsed Time | TW1A 1-hr | TW2A 1-hr | TW3A 1-hr | TW4A 1-hr | TW5A 1-hr | TW6A 1-hr | TW7A 1-hr | TW1B 12-hr | TW2B 12-hr | TW3B 12-hr | TW4B 12-hr | TW5B 12-hr | TW6B 12-hr | TW7B 12-hr | TW1-20 20-hr | TW2-20 20-hr | TW3-20 20-hr |
|----------|-------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|-----------------|-----------------|-----------------|
| 05/11/93 | 20:10 | 915.50 | 103.1 | 104.0 | 103.8 | 104.7 | 195.1 | 243 | 180.6 | 89.4 | 104.8 | 102.2 | 110.6 | 167.5 | 201.3 | 206.2 | 88.6 | 117.4 | 87.4 |
| 05/11/93 | 20:00 | 939.33 | 100.0 | 104.4 | 104.1 | 104.1 | 139.2 | 164.0 | 152.4 | 151.4 | 89.5 | 104.3 | 103.7 | 133.4 | 143.4 | 141.4 | 143.2 | | |
| 05/12/93 | 20:17 | 963.62 | 102.1 | 119.8 | 104.3 | 141.0 | 141.0 | 164.2 | 151.9 | 91.3 | 106.2 | 105.1 | 137.0 | 150.2 | 147.5 | | | | |
| 05/13/93 | 20:20 | 987.67 | 101.7 | 128.2 | 104.7 | 141.6 | 141.6 | 164.0 | 151.0 | 92.3 | 105.9 | 104.6 | 139.1 | 154.2 | 151.4 | | | | |
| 05/14/93 | 21:00 | 1012.33 | 102.9 | 129.0 | 104.4 | 142.4 | 163.4 | 150.0 | 93.7 | 115.7 | 104.9 | 140.9 | 158.6 | 155.9 | | | | | |
| 05/15/93 | 20:50 | 1036.17 | 98.6 | 125.9 | 100.0 | 138.6 | 158.0 | 147.3 | 90.3 | 112.8 | 100.5 | 131.4 | 156.8 | 154.2 | | | | | |
| 05/16/93 | 20:22 | 1059.70 | 98.1 | 128.2 | 99.5 | 129.6 | 158.7 | 148.0 | 90.6 | 113.7 | 101.6 | 133.0 | 158.6 | 155.5 | | | | | |
| 05/17/93 | 21:30 | 1084.63 | 96.5 | 125.4 | 99.6 | 138.1 | 158.1 | 147.6 | 90.1 | 113.9 | 103.7 | 130.7 | 159.3 | 156.5 | | | | | |
| 05/18/93 | 20:00 | 1107.33 | 91.1 | 121.9 | 99.8 | 135.0 | 155.2 | 145.4 | 89.9 | 115.4 | 110.6 | 126.1 | 160.8 | 157.9 | | | | | |
| 05/19/93 | 22:05 | 1133.42 | 83.0 | 115.1 | 95.2 | 125.5 | 148.4 | 140.3 | 86.1 | 114.6 | 98.7 | 140.4 | 161.6 | 158.9 | | | | | |
| 05/20/93 | 21:10 | 1156.50 | 78.4 | 109.9 | 90.0 | 122.6 | 144.3 | 137.8 | 84.6 | 114.6 | 98.7 | 142.6 | 168.6 | 165.6 | | | | | |
| 05/21/93 | 12:55 | 1172.25 | 77.4 | 88.2 | 82.3 | 121.3 | 136.7 | 136.7 | 86.6 | 143.5 | 98.6 | 171.1 | 157.6 | 157.6 | | | | | |
| 05/22/93 | 21:25 | 1204.75 | 68.2 | 112.2 | 84.0 | 125.6 | 153.6 | 111.5 | 65.7 | 99.5 | 98.8 | 146.6 | 187.4 | 184.0 | | | | | |
| 05/23/93 | 08:00 | 1215.33 | 72.1 | 97.9 | 86.6 | 126.0 | 140.5 | 138.9 | 66.4 | 105.4 | 99.4 | 146.2 | 194.0 | 189.6 | | | | | |
| 05/24/93 | 20:10 | 1227.50 | 71.1 | 100.3 | 89.5 | 129.6 | 157.6 | 126.9 | 66.2 | 115.4 | 100.6 | 152.0 | 201.3 | 195.3 | | | | | |
| 05/25/93 | 19:00 | 1250.33 | 70.4 | 102.1 | 90.9 | 134.7 | 151.9 | 146.7 | 65.7 | 122.4 | 101.9 | 157.9 | | | | | | | |
| 05/26/93 | 20:25 | 1275.75 | 70.3 | 102.3 | 93.0 | 141.8 | 140.6 | 140.5 | 65.7 | 126.0 | 103.7 | 165.9 | | | | | | | |
| 05/27/93 | 12:11 | 1291.52 | 64.7 | 101.6 | 87.6 | 157.6 | 145.1 | 148.0 | 81.9 | 124.8 | 101.0 | 150.6 | | | | | | | |
| 05/28/93 | 03:00 | 1306.33 | 64.0 | 103.0 | 67.7 | 144.1 | 152.6 | 151.0 | 62.0 | 129.0 | 101.0 | 160.0 | | | | | | | |
| 05/29/93 | 20:20 | 1323.67 | 64.7 | 101.2 | 91.6 | 178.6 | 156.5 | 139.4 | 61.3 | 125.3 | 101.0 | 167.5 | | | | | | | |
| 05/30/93 | 03:30 | 1330.83 | | | | | | | | | | | | | | | | | |
| 05/29/93 | 15:00 | 1342.33 | | | | | | | | | | | | | | | | | |
| 05/29/93 | 19:50 | 1347.17 | 62.4 | 101.6 | 93.6 | 193.3 | 175.9 | 165.8 | 60.3 | 124.3 | | | | | | | | | |
| 05/30/93 | 19:26 | 1370.80 | 62.3 | 101.4 | 96.6 | 195.1 | 191.0 | 174.9 | 60.3 | 123.9 | 101.5 | | | | | | | | |
| 05/31/93 | 19:30 | 1394.83 | 63.7 | 103.1 | 98.5 | 175.4 | 243.0 | 180.1 | 76.8 | 121.1 | 100.6 | | | | | | | | |
| 06/01/93 | 03:40 | 1403.00 | 64.4 | 102.5 | 97.5 | 170.6 | 237.8 | 180.6 | 79.3 | 120.4 | 100.4 | | | | | | | | |
| 06/01/93 | 19:00 | 1418.33 | 65.0 | 107.5 | 96.3 | 168.9 | 227.1 | 180.0 | 78.2 | 119.8 | 99.4 | | | | | | | | |
| 06/02/93 | 19:00 | 1442.33 | 68.3 | 102.6 | 96.3 | 162.6 | 218.6 | 178.6 | 77.5 | 116.8 | 98.3 | | | | | | | | |
| 06/03/93 | 12:30 | 1459.83 | 69.6 | 101.1 | 95.1 | 156.6 | 214.0 | 176.8 | 76.3 | 115.5 | 96.4 | | | | | | | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Elapsed Time | TW4-20 | TW5-20 | TW6-20 | TW1C | TW2C | TW3C | TW4C | TW5C | TW6C | Average Temperatures | TW7C | TW1D | TW2D |
|----------|-------|--------------------|--------|--------|--------|-------|-------|-------|-------|-------|-------|----------------------|---------|-------|-------|
| | | Maximum Temp. ---> | 20-ft | 20-ft | 20-ft | 24-ft | 24-ft | 24-ft | 24-ft | 24-ft | 24-ft | 24-Foot | 20-foot | 24-Ft | 29-ft |
| 04/03/93 | 16:40 | 0:00 | | | | | | | | | | | | | |
| 04/03/93 | | 20:05 | 3.42 | | | | | | | | | | | | |
| 04/03/93 | | 20:45 | 4.08 | | | | | | | | | | | | |
| 04/03/93 | | 19:00 | 2.33 | | | | | | | | | | | | |
| 04/03/93 | | 16:00 | 23.33 | | | | | | | | | | | | |
| 04/04/93 | | 19:30 | 50.63 | | | | | | | | | | | | |
| 04/06/93 | | 16:00 | 71.33 | | | | | | | | | | | | |
| 04/07/93 | | 19:00 | 96.33 | | | | | | | | | | | | |
| 04/08/93 | | 19:15 | 122.58 | | | | | | | | | | | | |
| 04/09/93 | | 20:00 | 147.33 | | | | | | | | | | | | |
| 04/10/93 | | 19:55 | 171.25 | | | | | | | | | | | | |
| 04/12/93 | | 20:45 | 220.08 | | | | | | | | | | | | |
| 04/13/93 | | 20:00 | 243.33 | | | | | | | | | | | | |
| 04/14/93 | | 20:25 | 207.75 | | | | | | | | | | | | |
| 04/15/93 | | 21:00 | 292.33 | | | | | | | | | | | | |
| 04/16/93 | | 14:45 | 310.08 | | | | | | | | | | | | |
| 04/17/93 | | 23:20 | 342.67 | | | | | | | | | | | | |
| 04/18/93 | | 19:14 | 362.57 | | | | | | | | | | | | |
| 04/19/93 | | 18:40 | 386.00 | | | | | | | | | | | | |
| 04/20/93 | | 18:50 | 410.17 | | | | | | | | | | | | |
| 04/21/93 | | 18:53 | 434.22 | | | | | | | | | | | | |
| 04/22/93 | | 19:14 | 458.57 | | | | | | | | | | | | |
| 04/23/93 | | 21:25 | 484.75 | | | | | | | | | | | | |
| 04/24/93 | | 20:00 | 507.33 | | | | | | | | | | | | |
| 04/25/93 | | 20:50 | 532.17 | | | | | | | | | | | | |
| 04/26/93 | | 20:30 | 555.83 | | | | | | | | | | | | |
| 04/27/93 | | 20:55 | 580.25 | | | | | | | | | | | | |
| 04/28/93 | | 16:35 | 601.92 | | | | | | | | | | | | |
| 04/29/93 | | 18:35 | 625.92 | | | | | | | | | | | | |
| 04/30/93 | | 20:00 | 651.33 | | | | | | | | | | | | |
| 05/01/93 | | 20:30 | 675.83 | | | | | | | | | | | | |
| 05/02/93 | | 20:35 | 699.92 | | | | | | | | | | | | |
| 05/03/93 | | 20:40 | 724.00 | | | | | | | | | | | | |
| 05/04/93 | | 19:08 | 746.47 | | | | | | | | | | | | |
| 05/05/93 | | 22:30 | 773.83 | | | | | | | | | | | | |
| 05/06/93 | | 21:00 | 796.33 | | | | | | | | | | | | |
| 05/07/93 | | 21:44 | 821.07 | | | | | | | | | | | | |
| 05/08/93 | | 20:04 | 843.40 | | | | | | | | | | | | |
| 05/09/93 | | 21:07 | 868.45 | | | | | | | | | | | | |
| 05/10/93 | | | 891.75 | | | | | | | | | | | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Elapsed Time | TW4-20 20-ft | TW5-20 20-ft | TW6-20 20-ft | TW7C 24-ft | TW2C 24-ft | TW3C 24-ft | TW4C 42.3 | TW5C 46.4 | TW6C 55.0 | Average Temperatures | TW7C 24-ft | TW1D 24-ft | TW2D 29-ft | |
|--------------------|-------|--------------|-----------------|-----------------|-----------------|---------------|---------------|---------------|--------------|--------------|--------------|----------------------|---------------|---------------|---------------|------|
| Maximum Temp. ---> | | | 196.5 | 233.7 | 204.6 | 63.3 | 60.4 | 90.2 | 90.1 | 68 | 65.4 | 144 | 142 | 133 | 59 | ERR |
| 05/11/93 | 20:10 | 915.50 | | | | | | | | | | | | | | 29.5 |
| 05/12/93 | 20:00 | 939.33 | | | | | | | | | | | | | | 37.5 |
| 05/13/93 | 20:17 | 963.62 | | | | | | | | | | | | | | 37.6 |
| 05/14/93 | 20:20 | 987.67 | | | | | | | | | | | | | | 37.6 |
| 05/15/93 | 21:00 | 1012.33 | | | | | | | | | | | | | | 32.6 |
| 05/16/93 | 20:50 | 1036.17 | | | | | | | | | | | | | | 32.6 |
| 05/17/93 | 20:22 | 1059.70 | 96.7 | 104 | 91.6 | 36.3 | 48.6 | 44.3 | 52.4 | 61.4 | 55.0 | 128 | 119 | 47 | 28.3 | |
| 05/18/93 | 21:30 | 1084.83 | 90.6 | 129.7 | 103.6 | 37.7 | 47.4 | 45.8 | 56.7 | 66.1 | 59.7 | 127 | 120 | 48 | 30.4 | |
| 05/19/93 | 20:00 | 1107.33 | 97.8 | 137.4 | 113.8 | 38.4 | 48.4 | 47.1 | 58.4 | 68.0 | 61.9 | 131 | 123 | 49 | 31.0 | |
| 05/20/93 | 22:05 | 1133.42 | 93.5 | 163.4 | 119.5 | 37.9 | 46.3 | 46.3 | 58.0 | 68.6 | 61.4 | 132 | 125 | 51 | 29.7 | |
| 05/21/93 | 21:10 | 1158.50 | 95.9 | 176.1 | 128.3 | 38.2 | 48.5 | 47.7 | 58.6 | 68.7 | 62.0 | 128 | 125 | 49 | 28.3 | |
| 05/22/93 | 12:55 | 1172.25 | 89.7 | 90.2 | 90.2 | 38.8 | 47.1 | 59.0 | 62.5 | 62.5 | 108 | 126 | 84 | 51 | 52 | |
| 05/23/93 | 21:25 | 1204.75 | 126.4 | 233.7 | 175.7 | 39.4 | 51.6 | 50.0 | 62.6 | 66.9 | 63.3 | 126 | 90 | 52 | 52 | |
| 05/24/93 | 08:00 | 1215.33 | 147.2 | 201.6 | 148.7 | 40.0 | 53.3 | 50.2 | 63.3 | 67.6 | 63.5 | 125 | 127 | 98 | 54 | |
| 05/25/93 | 20:10 | 1227.50 | 146.7 | 165.7 | 165.7 | 41.9 | 56.1 | 52.8 | 65.6 | 65.4 | 119 | 127 | 99 | 54 | 54 | |
| 05/26/93 | 19:00 | 1250.33 | 106.2 | 44.2 | 44.2 | 50.2 | 56.3 | 68.5 | 67.7 | 62.0 | 114 | 129 | 102 | 54 | 54 | |
| 05/27/93 | 20:25 | 1275.75 | 196.5 | 204.6 | 46.1 | 60.4 | 58.5 | 69.6 | 67.7 | 62.5 | 108 | 125 | 125 | 52 | 52 | |
| 05/28/93 | 12:11 | 1291.52 | | | 44.3 | 54.5 | 56.6 | | | | | 110 | 137 | 133 | 56 | 56 |
| 05/29/93 | 03:00 | 1306.33 | | | | 63.3 | 59.5 | 57.3 | 65.0 | | | 113 | 142 | 116 | 56 | 56 |
| 05/29/93 | 20:20 | 1323.67 | | | | | | | | | | 116 | 134 | 110 | 55 | 55 |
| 05/29/93 | 03:30 | 1330.83 | | | | | | | | | | 117 | 132 | 117 | 55 | 55 |
| 05/29/93 | 15:00 | 1342.33 | | | | | | | | | | 117 | 133 | 115 | 59 | 59 |
| 05/29/93 | 19:50 | 1347.17 | | | | | | | | | | 117 | 132 | 138 | 59 | 59 |
| 05/30/93 | 19:28 | 1370.80 | | | | | | | | | | 136 | 136 | 136 | 30.5 | 30.5 |
| 05/31/93 | 19:30 | 1394.83 | | | | | | | | | | 45.2 | | | 33.5 | 33.5 |
| 06/01/93 | 03:40 | 1403.00 | | | | | | | | | | | | | | |
| 06/01/93 | 19:00 | 1418.33 | | | | | | | | | | | | | | |
| 06/02/93 | 19:00 | 1442.33 | | | | | | | | | | | | | | |
| 06/03/93 | 12:30 | 1459.83 | | | | | | | | | | | | | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Elapsed Time | TW3D | TW4D | TW5D | TW6D | TW7D | TW1E | TW2E | TW3E | TW4E | TW5E | TW6E | TW7E | TW1F | TW2F | TW3F | TW4F |
|----------|-------|----------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|
| | | Maximum Temp. - - -> | 29-# | 29-# | 29-# | 29-# | 29-# | 31-# | 31-# | 31-# | 31-# | 31-# | 31-# | 31-# | 31-# | 34-# | 34-# | 34-# |
| | | | 50.5 | 37.7 | 36.2 | 39.1 | ERR | 28.1 | 21.0 | 23 | 21.0 | 23 | 21.0 | 23.2 | ERR | 26.5 | ERR | 27.6 |
| 04/03/93 | 16:40 | 0.00 | | | | | | | | | | | | | | | | |
| 04/03/93 | 20:05 | 3.42 | | | | | | | | | | | | | | | | |
| 04/03/93 | 20:45 | 4.08 | | | | | | | | | | | | | | | | |
| 04/03/93 | 19:00 | 2.33 | | | | | | | | | | | | | | | | 21.1 |
| 04/04/93 | 16:00 | 23.33 | | | | | | | | | | | | | | | | |
| 04/05/93 | 19:30 | 50.83 | | | | | | | | | | | | | | | | |
| 04/06/93 | 16:00 | 71.33 | | | | | | | | | | | | | | | | |
| 04/07/93 | 19:00 | 98.33 | | | | | | | | | | | | | | | | |
| 04/08/93 | 19:15 | 122.58 | | | | | | | | | | | | | | | | |
| 04/09/93 | 20:00 | 147.33 | | | | | | | | | | | | | | | | |
| 04/10/93 | 19:55 | 171.25 | | | | | | | | | | | | | | | | |
| 04/11/93 | 20:45 | 220.08 | | | | | | | | | | | | | | | | |
| 04/12/93 | 20:00 | 243.33 | | | | | | | | | | | | | | | | |
| 04/13/93 | 20:25 | 267.75 | | | | | | | | | | | | | | | | |
| 04/14/93 | 21:00 | 292.33 | | | | | | | | | | | | | | | | |
| 04/15/93 | 14:45 | 310.08 | | | | | | | | | | | | | | | | |
| 04/16/93 | 23:20 | 342.67 | | | | | | | | | | | | | | | | |
| 04/17/93 | 19:14 | 362.57 | | | | | | | | | | | | | | | | |
| 04/18/93 | 18:40 | 386.00 | | | | | | | | | | | | | | | | |
| 04/19/93 | 18:50 | 410.17 | | | | | | | | | | | | | | | | |
| 04/20/93 | 18:53 | 434.22 | | | | | | | | | | | | | | | | |
| 04/21/93 | 19:14 | 458.57 | | | | | | | | | | | | | | | | |
| 04/22/93 | 21:25 | 484.75 | | | | | | | | | | | | | | | | |
| 04/23/93 | 20:00 | 507.33 | | | | | | | | | | | | | | | | |
| 04/24/93 | 20:50 | 532.17 | | | | | | | | | | | | | | | | |
| 04/25/93 | 20:30 | 555.63 | | | | | | | | | | | | | | | | |
| 04/26/93 | 20:55 | 580.25 | | | | | | | | | | | | | | | | |
| 04/27/93 | 18:35 | 601.92 | | | | | | | | | | | | | | | | |
| 04/28/93 | 18:35 | 625.92 | | | | | | | | | | | | | | | | |
| 04/29/93 | 20:00 | 651.33 | | | | | | | | | | | | | | | | |
| 04/30/93 | 20:30 | 675.63 | | | | | | | | | | | | | | | | |
| 05/01/93 | 20:35 | 699.92 | | | | | | | | | | | | | | | | |
| 05/02/93 | 20:40 | 724.00 | | | | | | | | | | | | | | | | |
| 05/03/93 | 19:08 | 746.47 | | | | | | | | | | | | | | | | |
| 05/04/93 | 22:30 | 773.63 | | | | | | | | | | | | | | | | |
| 05/05/93 | 21:00 | 796.33 | | | | | | | | | | | | | | | | |
| 05/06/93 | 21:44 | 821.07 | | | | | | | | | | | | | | | | |
| 05/07/93 | 20:04 | 843.40 | | | | | | | | | | | | | | | | |
| 05/08/93 | 21:07 | 868.45 | | | | | | | | | | | | | | | | |
| 05/09/93 | ? | 891.75 | | | | | | | | | | | | | | | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Elapsed Time | Time | TW3D 29-f | TW4D 29-f | TW5D 29-f | TW6D 29-f | TW1E 31-f | TW2E 31-f | TW3E 31-f | TW4E 31-f | TW5F 31-f | TW6E 31-f | TW1F 31-f | TW2F 31-f | TW3F 31-f | TW4F 31-f |
|---------------|-----------------|---------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|--------------|
| Maximum Temp. | | | 80.5 | 37.7 | 36.2 | 39.1 | 39.1 | 31.8 | 23 | 21.8 | 23 | 23.2 | 23.2 | 28.5 | 28.5 | 34-f |
| 05/11/93 | 20:10 | 015.50 | 29.6 | 31.4 | 32.1 | 31.3 | | | | | | | | | | |
| 05/12/93 | 20:00 | 039.33 | 29.9 | 31.9 | 32.5 | 31.8 | | | | | | | | | | |
| 05/13/93 | 20:17 | 063.62 | 30.4 | 32.3 | 33.3 | 32.3 | | | | | | | | | | |
| 05/14/93 | 20:20 | 087.67 | 31.0 | 32.8 | 33.8 | 32.7 | | | | | | | | | | |
| 05/15/93 | 21:00 | 1012.33 | 31.3 | 33.2 | 33.2 | 37.7 | | | | | | | | | | |
| 05/16/93 | 20:50 | 1036.17 | 28.4 | 33.3 | 32.3 | 33.2 | | | | | | | | | | |
| 05/17/93 | 20:22 | 1059.70 | | | | | | | | | | | | | | |
| 05/18/93 | 21:30 | 1084.83 | | | | | | | | | | | | | | |
| 05/19/93 | 20:00 | 1107.33 | 29.5 | 35.6 | 35.6 | 37.0 | | | | | | | | | | |
| 05/20/93 | 22:05 | 1133.42 | 30.5 | 37.7 | 36.2 | 39.1 | | | | | | | | | | |
| 05/21/93 | 21:10 | 1156.50 | | | | | | | | | | | | | | |
| 05/22/93 | 12:55 | 1172.25 | | | | | | | | | | | | | | |
| 05/23/93 | 21:25 | 1204.75 | | | | | | | | | | | | | | |
| 05/24/93 | 08:00 | 1215.33 | | | | | | | | | | | | | | |
| 05/24/93 | 20:10 | 1227.50 | | | | | | | | | | | | | | |
| 05/25/93 | 19:00 | 1250.33 | | | | | | | | | | | | | | |
| 05/26/93 | 20:25 | 1275.75 | | | | | | | | | | | | | | |
| 05/27/93 | 12:11 | 1291.52 | | | | | | | | | | | | | | |
| 05/28/93 | 03:00 | 1306.33 | | | | | | | | | | | | | | |
| 05/28/93 | 20:20 | 1323.67 | | | | | | | | | | | | | | |
| 05/29/93 | 03:30 | 1330.83 | | | | | | | | | | | | | | |
| 05/29/93 | 15:00 | 1342.33 | | | | | | | | | | | | | | |
| 05/29/93 | 19:50 | 1347.17 | | | | | | | | | | | | | | |
| 05/30/93 | 19:28 | 1370.60 | | | | | | | | | | | | | | |
| 05/31/93 | 19:30 | 1394.63 | | | | | | | | | | | | | | |
| 06/01/93 | 03:40 | 1403.00 | | | | | | | | | | | | | | |
| 06/01/93 | 19:00 | 1418.33 | | | | | | | | | | | | | | |
| 06/02/93 | 19:00 | 1442.33 | | | | | | | | | | | | | | |
| 06/03/93 | 12:30 | 1459.63 | | | | | | | | | | | | | | |

Table B-2 Temperature in Thermowells (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Elapsed | TW5F | | | TW6F | | |
|----------|-------|---------|---------------|------|------|------|------|------|
| | | | Maximum Temp. | Time | 34-# | 34-# | 34-# | 34-# |
| | | | ERR | ERR | ERR | ERR | ERR | ERR |
| 04/03/93 | 16:40 | 0.00 | | | | | | |
| 04/03/93 | 20:05 | 3.42 | | | | | | |
| 04/03/93 | 20:45 | 4.08 | | | | | | |
| 04/03/93 | 19:00 | 2.33 | | | | | | |
| 04/04/93 | 16:00 | 23.33 | | | | | | |
| 04/05/93 | 19:30 | 50.63 | | | | | | |
| 04/06/93 | 16:00 | 71.33 | | | | | | |
| 04/07/93 | 19:00 | 98.33 | | | | | | |
| 04/08/93 | 19:15 | 122.58 | | | | | | |
| 04/09/93 | 20:00 | 147.33 | | | | | | |
| 04/10/93 | 19:55 | 171.25 | | | | | | |
| 04/11/93 | 20:45 | 220.08 | | | | | | |
| 04/13/93 | 20:00 | 243.33 | | | | | | |
| 04/14/93 | 20:25 | 267.75 | | | | | | |
| 04/15/93 | 21:00 | 292.33 | | | | | | |
| 04/16/93 | 14:45 | 310.08 | | | | | | |
| 04/17/93 | 23:20 | 342.67 | | | | | | |
| 04/18/93 | 19:14 | 362.57 | | | | | | |
| 04/19/93 | 16:40 | 386.00 | | | | | | |
| 04/20/93 | 16:50 | 410.17 | | | | | | |
| 04/21/93 | 16:53 | 434.22 | | | | | | |
| 04/22/93 | 19:14 | 458.57 | | | | | | |
| 04/23/93 | 21:25 | 484.75 | | | | | | |
| 04/24/93 | 20:00 | 507.33 | | | | | | |
| 04/25/93 | 20:50 | 532.17 | | | | | | |
| 04/26/93 | 20:30 | 555.83 | | | | | | |
| 04/27/93 | 20:55 | 580.25 | | | | | | |
| 04/28/93 | 16:35 | 601.92 | | | | | | |
| 04/29/93 | 18:35 | 625.92 | | | | | | |
| 04/30/93 | 20:00 | 651.33 | | | | | | |
| 05/01/93 | 20:30 | 675.83 | | | | | | |
| 05/02/93 | 20:35 | 699.92 | | | | | | |
| 05/03/93 | 20:40 | 724.00 | | | | | | |
| 05/04/93 | 19:08 | 746.47 | | | | | | |
| 05/05/93 | 22:30 | 773.83 | | | | | | |
| 05/06/93 | 21:00 | 796.33 | | | | | | |
| 05/07/93 | 21:44 | 821.07 | | | | | | |
| 05/08/93 | 20:04 | 843.40 | | | | | | |
| 05/09/93 | 21:07 | 868.45 | | | | | | |
| 05/10/93 | | 891.75 | | | | | | |

Table B-2 Temperature in Thermowell^s (Outside Thermowell TW7
in Table B-1) [Continued]

| Date | Time | Time | TW5F 34-# ERR | TW6F 34-# ERR | TW7F 34-# ERR |
|-------------------------------|-------|---------|---------------------|---------------------|---------------------|
| Elapsed Maximum Temp. ---> | | | | | |
| 05/11/93 | 20:10 | 915.50 | | | |
| 05/12/93 | 20:00 | 939.33 | | | |
| 05/13/93 | 20:17 | 963.62 | | | |
| 05/14/93 | 20:20 | 961.67 | | | |
| 05/15/93 | 21:00 | 1012.33 | | | |
| 05/16/93 | 20:50 | 1036.17 | | | |
| 05/17/93 | 20:22 | 1059.70 | | | |
| 05/18/93 | 21:30 | 1084.63 | | | |
| 05/19/93 | 20:00 | 1107.33 | | | |
| 05/20/93 | 22:05 | 1133.42 | | | |
| 05/21/93 | 21:10 | 1156.50 | | | |
| 05/22/93 | 12:55 | 1172.25 | | | |
| 05/23/93 | 21:23 | 1204.75 | | | |
| 05/24/93 | 08:00 | 1215.33 | | | |
| 05/24/93 | 20:10 | 1227.50 | | | |
| 05/25/93 | 19:00 | 1250.33 | | | |
| 05/26/93 | 20:25 | 1275.75 | | | |
| 05/27/93 | 12:11 | 1291.52 | | | |
| 05/28/93 | 03:00 | 1306.33 | | | |
| 05/28/93 | 20:20 | 1323.67 | | | |
| 05/29/93 | 03:30 | 1330.63 | | | |
| 05/29/93 | 15:00 | 1342.33 | | | |
| 05/29/93 | 19:50 | 1347.17 | | | |
| 05/30/93 | 19:20 | 1370.60 | | | |
| 05/31/93 | 19:30 | 1394.63 | | | |
| 06/01/93 | 03:40 | 1403.00 | | | |
| 06/01/93 | 19:00 | 1416.33 | | | |
| 06/02/93 | 19:00 | 1442.33 | | | |
| 06/03/93 | 12:30 | 1459.83 | | | |

Table B-3 Temperature in Excitor Electrodes (Continued)

| Date | Time | Elapsed Time | B1A | B2A | B3A | B4A | B1B | B2B | B3B | B4B | B1C | B2C | B3C | B4C | B1D | B2D | B3D | B4D | Average Temperature | Overall |
|---------------|-------|--------------|--------|--------|-------|-------|--------|--------|--------|--------|--------|--------|-------|-------|-----|-----|-----|-----|---------------------|---------|
| | | Time | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-R | 1-Foot | 20-Foot |
| Maximum Temp. | -- | --> | B1A | B2A | B3A | B4A | B1B | B2B | B3B | B4B | B1C | B2C | B3C | B4C | B1D | B2D | B3D | B4D | 10-Foot | 20-Foot |
| 05/09/93 | 23:10 | 070:50 | 164.4 | 365.8 | 159.1 | 177.4 | 176.9 | 158.1 | 195.3 | 177.4 | 219.2 | 201.2 | 246 | 168.6 | 222 | 177 | 208 | 202 | 202 | |
| 05/10/93 | 07:10 | 070:50 | 162.9 | 396.3 | 157.4 | 178.9 | 162.9 | 160 | 196.2 | 177.6 | 220.5 | 203.1 | 246.9 | 168.6 | 224 | 174 | 210 | 203 | 203 | |
| 05/11/93 | 07:15 | 902.58 | 162.1 | 472.6 | 156.6 | 175.5 | 173.1 | 164.8 | 198 | 178.8 | 221.9 | 204.5 | 247.8 | 171.4 | 242 | 179 | 211 | 211 | 211 | |
| 05/12/93 | 07:00 | 926.33 | 156.1 | 512.6 | 152.9 | 186.9 | 167.5 | 167.5 | 194.4 | 175.6 | 208.1 | 192.1 | 227.6 | 160.8 | 247 | 175 | 197 | 207 | 207 | |
| 05/13/93 | 07:08 | 950.47 | 161.4 | 695.7 | 155.4 | 170.9 | 170.9 | 171.3 | 181.3 | 200.6 | 179.8 | 209.4 | 237.4 | 244 | 171 | 343 | 184 | 215 | 247 | |
| 05/14/93 | 07:00 | 974.33 | 158.7 | 658.6 | 154.7 | 169.5 | 174.7 | 192.6 | 200.6 | 180.2 | 207.6 | 262.9 | 236.3 | 170.6 | 335 | 187 | 219 | 247 | 247 | |
| 05/15/93 | 07:14 | 998.57 | 159.8 | 671.2 | 156.8 | 170.9 | 177.5 | 206.4 | 204.6 | 182.6 | 212.9 | 353.1 | 243.8 | 178.2 | 340 | 193 | 260 | 247 | 260 | |
| 05/16/93 | 07:33 | 1022.88 | 161.2 | 660.6 | 156.6 | 170.7 | 178.2 | 208.3 | 212.1 | 183.8 | 216.9 | 375.5 | 257.6 | 180.1 | 337 | 195 | 356 | 297 | 297 | |
| 05/17/93 | 23:00 | 1062.33 | 167.2 | 659.9 | 158 | 169 | 179.5 | 194.4 | 230.4 | 186.4 | 227.9 | 526.1 | 421.9 | 192.6 | 339 | 198 | 343 | 293 | 293 | |
| 05/18/93 | 23:30 | 1086.83 | 158.6 | 679.6 | 154.9 | 160.6 | 167.9 | 195.7 | 256.1 | 188.1 | 226.7 | 445.2 | 650.9 | 201.1 | 288 | 202 | 431 | 307 | 307 | |
| 05/19/93 | 22:50 | 1110.17 | 156 | 651.6 | 158.4 | 155.5 | 158.7 | 210.8 | 325.6 | 203.6 | 223.7 | 530.0 | 223.7 | 224 | 225 | 224 | 224 | 249 | 249 | |
| 05/20/93 | 07:08 | 1116.47 | 152.3 | 614.8 | 154 | 153.8 | 153.8 | 223.6 | 376.6 | 202.2 | 216.9 | 133.0 | 216.9 | 268 | 239 | 774 | 774 | 358 | 358 | |
| 05/20/93 | 17:25 | 1126.75 | 147.5 | 494.5 | 148.6 | 145.1 | 147.3 | 208.8 | 277.7 | 195.8 | 211.6 | 237 | 234 | 207 | 224 | 221 | 221 | 221 | 221 | |
| 05/21/93 | 23:03 | 1158.42 | 157.3 | 636.5 | 147 | 142.5 | 145.2 | 323.3 | 596.8 | 209.5 | 215.7 | 834.5 | 230.6 | 271 | 319 | 427 | 331 | 331 | 331 | |
| 05/22/93 | 22:35 | 1181.92 | 164.7 | 660.2 | 154 | 147.3 | 158.6 | 620 | 976.3 | 254 | 230.8 | 719.4 | 978.3 | 334.2 | 552 | 568 | 485 | 515 | 515 | |
| 05/23/93 | 07:03 | 1206.42 | 171.4 | 963.4 | 163.5 | 152.2 | 172.4 | 984.4 | 862.4 | 275.8 | 244.2 | 650.2 | 891.2 | 399.5 | 568 | 598 | 598 | 598 | 598 | |
| 05/24/93 | 22:35 | 1230.25 | 183.1 | 647.8 | 168.8 | 148.3 | 213.1 | 880.1 | 572.1 | 273.8 | 895.7 | 847.6 | 551.2 | 314.3 | 465 | 652 | 491 | 491 | 491 | |
| 05/25/93 | 23:00 | 1254.47 | 212.6 | 912.9 | 186.7 | 150.5 | 329.7 | 796.3 | 840.6 | 284.7 | 1069.8 | 647.2 | 839 | 346.6 | 563 | 776 | 568 | 568 | 568 | |
| 05/26/93 | 07:10 | 1286.6 | 1150.0 | 208.0 | 152.0 | 498.5 | 1304.0 | 1119.0 | 284.7 | 1170.0 | 861.9 | 555.0 | 295.1 | 437 | 802 | 721 | 653 | 653 | 653 | |
| 05/27/93 | 22:35 | 1306.35 | 227.4 | 1055.2 | 208.1 | 151.5 | 517.6 | 1174.0 | 1238.0 | 282.5 | 1028.0 | 995.0 | 567.0 | 275.7 | 411 | 803 | 701 | 638 | 638 | |
| 05/28/93 | 07:03 | 1310.43 | 244.9 | 695.2 | 219.8 | 156.9 | 725.4 | 993.3 | 1260.0 | 290.4 | 997.2 | 950.0 | 474.7 | 330.5 | 379 | 822 | 630 | 630 | 630 | |
| 05/29/93 | 07:15 | 1334.58 | 433.2 | 928.0 | 232.5 | 165.3 | 219.5 | 856.9 | 1220.0 | 308.1 | 885.2 | 806.7 | 483.0 | 578.8 | 651 | 440 | 686 | 593 | 593 | |
| 05/30/93 | 07:20 | 1358.67 | 298.1 | 229.3 | 169.3 | 166.3 | 229.3 | 166.3 | 302.6 | 302.6 | 468.6 | 419.5 | 873.6 | 232 | 235 | 594 | 368 | 368 | 368 | |
| 05/31/93 | 07:10 | 1382.50 | 238.1 | 223.7 | 178.4 | 155.0 | 1120.0 | 155.0 | 388.6 | 363.1 | 405.8 | 637.9 | 213 | 272 | 502 | 355 | 355 | 355 | 355 | |
| 06/01/93 | 05:00 | 1404.33 | 251.1 | 695.7 | 218.3 | 181.8 | 155.0 | 1120.0 | 605.6 | 996.0 | 326.2 | 356.9 | 609.0 | 387 | 627 | 583 | 527 | 527 | 527 | |
| 06/02/93 | 05:50 | 1429.17 | 219.8 | 330.1 | 241.1 | 154.9 | 121.6 | 464.2 | 1008.1 | 347.7 | 324.6 | 1021.1 | 284 | 673 | 471 | 334 | 334 | 334 | 334 | |
| 06/03/93 | 12:07 | 1459.45 | 246.0 | | | | | | | | | | | | | | | 376 | 271 | |

Table B-4 Ground Electrode and Outside Thermowell Temperatures
 (Recorded by Data Logger) [Continued]

| Date | Time | A2A | A2B | A2C | A3A | A3B | A3C | A3D | A4A | A4B | A4C | A4D | TW7A | TW7B | TW7C | C4D | C4B | C4C | C4D | C4E |
|------------------|-------|-------|------|------|------|------|------|-------|------|------|------|------|------|------|------|------|------|------|------|------|
| Maximum Temp. -- | 70.5 | 84.2 | 42.3 | 80.3 | 85.9 | 45.4 | 32.0 | 112.2 | 66.6 | 48.7 | 33.9 | 62.0 | 38.7 | 27.7 | 30.9 | 68.4 | 42.0 | 82.0 | 48.7 | 31.0 |
| Minimum Temp. -- | 70.5 | 84.2 | 42.3 | 80.3 | 85.9 | 45.4 | 32.0 | 112.2 | 66.6 | 48.7 | 33.9 | 62.0 | 38.7 | 27.7 | 30.9 | 68.4 | 42.0 | 82.0 | 48.7 | 31.0 |
| 04/08/93 | 20.00 | 123.3 | 39.3 | 20.5 | 22.2 | 41.1 | 21.0 | 22.3 | 53.7 | 22.0 | 22.3 | 21.8 | 19.5 | 21.5 | 21.7 | 21.8 | 19.4 | 21.7 | 21.7 | 21.7 |
| 04/08/93 | 00.00 | 127.3 | 35.0 | 20.5 | 22.3 | 42.0 | 21.0 | 22.5 | 54.0 | 22.5 | 22.6 | 22.0 | 19.6 | 21.7 | 21.8 | 21.8 | 19.4 | 21.7 | 21.7 | 21.6 |
| 04/08/93 | 04.00 | 131.3 | 38.0 | 20.5 | 22.1 | 42.3 | 22.0 | 22.3 | 55.1 | 22.7 | 22.5 | 21.8 | 19.4 | 21.6 | 21.7 | 21.8 | 19.4 | 21.7 | 21.7 | 21.6 |
| 04/08/93 | 08.00 | 135.3 | 36.2 | 20.6 | 22.2 | 43.0 | 22.5 | 22.5 | 55.8 | 23.3 | 22.7 | 21.8 | 19.5 | 21.8 | 21.8 | 21.8 | 19.4 | 21.8 | 22.0 | 21.6 |
| 04/08/93 | 12.00 | 139.3 | 36.4 | 20.6 | 21.9 | 43.0 | 22.4 | 22.4 | 56.1 | 23.7 | 22.6 | 21.7 | 19.2 | 21.8 | 21.4 | 21.4 | 19.3 | 21.7 | 21.7 | 24.4 |
| 04/08/93 | 16.00 | 143.3 | 36.8 | 20.6 | 21.8 | 43.0 | 22.5 | 22.3 | 56.9 | 23.8 | 22.4 | 21.7 | 19.2 | 21.5 | 21.5 | 21.5 | 19.1 | 21.2 | 21.6 | 25.3 |
| 04/08/93 | 20.00 | 147.3 | 37.4 | 21.0 | 22.3 | 44.8 | 22.6 | 22.3 | 57.4 | 24.0 | 22.4 | 21.9 | 19.5 | 21.5 | 21.7 | 21.6 | 19.5 | 21.7 | 21.5 | 24.9 |
| 04/08/93 | 00.00 | 151.3 | 38.2 | 21.3 | 22.4 | 45.7 | 23.1 | 22.6 | 58.6 | 24.7 | 22.6 | 21.9 | 19.7 | 21.5 | 21.8 | 21.8 | 19.7 | 21.7 | 21.7 | 25.4 |
| 04/10/93 | 04.00 | 155.3 | 38.2 | 21.3 | 22.3 | 46.1 | 23.3 | 22.6 | 59.2 | 25.2 | 22.7 | 21.9 | 19.6 | 21.6 | 21.6 | 21.6 | 19.6 | 21.6 | 21.6 | 25.7 |
| 04/10/93 | 08.00 | 159.3 | 38.3 | 21.4 | 22.2 | 46.5 | 23.5 | 22.6 | 59.6 | 25.6 | 22.7 | 21.8 | 19.6 | 21.6 | 21.5 | 21.5 | 19.5 | 21.7 | 21.5 | 25.9 |
| 04/10/93 | 12.00 | 163.3 | 38.6 | 21.5 | 22.0 | 46.6 | 24.1 | 22.8 | 59.4 | 26.8 | 23.1 | 21.9 | 19.4 | 22.0 | 21.8 | 21.8 | 19.4 | 22.0 | 21.8 | 26.1 |
| 04/10/93 | 16.00 | 167.3 | 38.8 | 21.5 | 22.0 | 47.1 | 24.0 | 22.5 | 59.7 | 27.1 | 22.8 | 20.7 | 19.5 | 21.5 | 21.5 | 21.5 | 19.5 | 21.5 | 21.4 | 26.6 |
| 04/10/93 | 20.00 | 171.3 | 39.6 | 22.0 | 22.5 | 48.4 | 24.4 | 22.6 | 61.1 | 27.2 | 22.7 | 21.9 | 19.9 | 21.4 | 21.5 | 21.5 | 19.9 | 21.7 | 22.0 | 27.5 |
| 04/11/93 | 04.00 | 175.3 | 40.0 | 22.1 | 22.4 | 48.0 | 22.7 | 21.8 | 62.0 | 27.9 | 22.8 | 21.0 | 20.0 | 21.5 | 19.8 | 19.8 | 21.3 | 21.6 | 22.2 | 21.5 |
| 04/11/93 | 08.00 | 179.3 | 40.3 | 22.3 | 22.5 | 49.8 | 25.1 | 22.7 | 62.4 | 28.5 | 22.9 | 21.6 | 20.6 | 21.6 | 21.2 | 22.2 | 21.6 | 21.7 | 22.5 | 21.8 |
| 04/11/93 | 12.00 | 183.3 | 40.4 | 22.3 | 22.2 | 49.8 | 25.5 | 22.8 | 62.6 | 29.2 | 23.0 | 21.7 | 19.8 | 21.7 | 21.6 | 22.0 | 21.9 | 21.9 | 22.5 | 21.6 |
| 04/11/93 | 16.00 | 187.3 | 40.7 | 22.7 | 22.2 | 50.1 | 26.0 | 22.0 | 62.8 | 30.0 | 23.2 | 21.8 | 19.8 | 22.0 | 21.7 | 21.8 | 21.8 | 22.0 | 22.2 | 21.6 |
| 04/11/93 | 20.00 | 191.3 | 40.6 | 22.6 | 22.5 | 49.4 | 24.4 | 22.6 | 61.1 | 27.2 | 22.7 | 21.9 | 19.9 | 21.4 | 21.5 | 21.5 | 19.9 | 21.7 | 22.0 | 27.5 |
| 04/11/93 | 04.00 | 195.3 | 41.4 | 23.3 | 22.8 | 50.8 | 22.8 | 22.0 | 62.6 | 30.8 | 22.0 | 21.6 | 21.5 | 21.6 | 21.6 | 21.6 | 20.5 | 22.0 | 21.6 | 28.4 |
| 04/11/93 | 08.00 | 199.3 | 41.6 | 23.3 | 22.7 | 51.0 | 27.1 | 22.0 | 62.7 | 31.9 | 23.0 | 20.8 | 21.9 | 21.9 | 20.7 | 20.7 | 21.9 | 21.7 | 22.0 | 30.5 |
| 04/12/93 | 00.00 | 203.3 | 41.8 | 23.5 | 22.6 | 51.8 | 27.3 | 22.9 | 63.2 | 32.4 | 23.2 | 21.9 | 20.5 | 21.7 | 21.7 | 21.8 | 21.8 | 21.8 | 21.7 | 31.0 |
| 04/12/93 | 04.00 | 207.3 | 41.9 | 23.7 | 22.5 | 51.9 | 27.8 | 23.0 | 63.8 | 33.2 | 23.2 | 21.8 | 20.8 | 21.6 | 21.7 | 21.7 | 21.8 | 22.0 | 21.9 | 31.5 |
| 04/12/93 | 08.00 | 211.3 | 42.0 | 24.0 | 22.7 | 52.1 | 28.2 | 23.1 | 63.9 | 33.5 | 22.1 | 20.6 | 22.0 | 21.2 | 21.1 | 21.2 | 21.1 | 21.0 | 22.0 | 31.7 |
| 04/12/93 | 12.00 | 215.3 | 42.3 | 24.0 | 22.4 | 52.5 | 28.5 | 22.9 | 64.7 | 34.3 | 23.2 | 21.8 | 20.4 | 21.5 | 21.5 | 21.5 | 21.4 | 21.7 | 22.2 | 31.0 |
| 04/12/93 | 16.00 | 219.3 | 42.0 | 24.7 | 23.0 | 53.5 | 28.9 | 23.2 | 65.0 | 35.0 | 23.4 | 22.1 | 21.0 | 21.8 | 21.6 | 22.1 | 22.4 | 21.9 | 22.7 | 33.0 |
| 04/12/93 | 20.00 | 223.3 | 42.8 | 24.8 | 22.9 | 54.0 | 29.5 | 23.2 | 66.4 | 36.0 | 23.5 | 22.1 | 21.1 | 22.0 | 21.3 | 22.0 | 22.5 | 22.0 | 22.7 | 35.1 |
| 04/12/93 | 00.00 | 227.3 | 43.4 | 24.9 | 22.8 | 54.4 | 29.9 | 23.1 | 67.0 | 36.7 | 23.4 | 22.1 | 21.2 | 22.1 | 21.4 | 22.7 | 22.5 | 21.9 | 22.8 | 35.8 |
| 04/12/93 | 04.00 | 231.3 | 43.5 | 25.1 | 22.8 | 54.8 | 30.4 | 23.2 | 67.4 | 37.5 | 23.5 | 22.1 | 21.3 | 22.1 | 21.5 | 22.9 | 22.7 | 22.0 | 23.2 | 34.1 |
| 04/12/93 | 08.00 | 235.3 | 43.6 | 25.3 | 22.5 | 54.6 | 30.6 | 23.2 | 68.0 | 38.1 | 23.5 | 21.8 | 21.0 | 21.8 | 21.3 | 22.6 | 22.4 | 21.6 | 23.3 | 34.4 |
| 04/12/93 | 12.00 | 239.3 | 44.1 | 25.8 | 22.9 | 55.0 | 31.1 | 23.3 | 69.0 | 38.2 | 23.7 | 22.0 | 21.8 | 21.9 | 21.7 | 22.0 | 22.5 | 22.0 | 23.3 | 35.1 |
| 04/12/93 | 16.00 | 243.3 | 44.6 | 26.0 | 23.0 | 56.2 | 31.6 | 23.4 | 69.5 | 39.7 | 23.9 | 22.1 | 21.8 | 22.0 | 21.6 | 22.7 | 22.7 | 22.0 | 23.5 | 35.7 |
| 04/12/93 | 20.00 | 247.3 | 44.7 | 26.2 | 23.0 | 56.5 | 32.3 | 23.4 | 69.0 | 40.5 | 23.8 | 22.2 | 21.9 | 22.2 | 21.7 | 22.0 | 22.7 | 22.0 | 23.5 | 35.7 |

Table B-4 Ground Electrode and Outside Thermowell Temperatures
(Recorded by Data Logger) [Continued]

| Date | Time | Elapsed Time | A2A | A2B | A2C | A3A | A3B | A3C | A4D | A4A | A4B | A4C | A4D | TW7B | TW7D | C8D | C1B | C1C | C2A | C2B | C2C | C2D | C3A | C3B | C3C | C3D | C4A | C4B | C4C | C4D | C6B | | |
|----------|-------|--------------|------|------|------|------|------|------|------|-------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|
| 06/01/93 | 04:00 | 1403.3 | 62.0 | 70.6 | 42.3 | 71.4 | 80.5 | 45.2 | 31.6 | 104.3 | 76.4 | 48.4 | 33.4 | 58.9 | 38.6 | 27.3 | 30.5 | 64.4 | 42.6 | 62.1 | 74.9 | 48.4 | 31.4 | 40.2 | 62.4 | 51.4 | 32.3 | 76.2 | 83.1 | 48.9 | 31.7 | 69.3 | |
| 06/01/93 | 06:00 | 1407.3 | 61.7 | 70.8 | 42.3 | 71.3 | 80.3 | 45.4 | 31.8 | 108.5 | 76.7 | 48.7 | 33.4 | 58.6 | 38.7 | 27.5 | 30.3 | 64.5 | 42.6 | 61.7 | 74.6 | 48.7 | 31.7 | 40.3 | 62.2 | 51.6 | 32.5 | 75.0 | 83.0 | 49.0 | 31.7 | 65.8 | |
| 06/01/93 | 12:00 | 1411.3 | 61.4 | 69.8 | 41.6 | 70.5 | 80.2 | 44.9 | 31.4 | 108.7 | 76.0 | 48.2 | 33.2 | 58.3 | 38.4 | 27.3 | 30.2 | 63.8 | 41.9 | 61.0 | 73.9 | 48.1 | 31.2 | 39.3 | 61.3 | 51.2 | 32.2 | 75.6 | 80.4 | 48.6 | 31.5 | 65.7 | |
| 06/01/93 | 16:00 | 1415.3 | 62.1 | 69.7 | 41.7 | 71.4 | 80.4 | 45.0 | 31.6 | 107.6 | 77.2 | 48.2 | 33.5 | 58.3 | 38.5 | 27.5 | 30.3 | 63.6 | 41.9 | 62.2 | 73.0 | 48.0 | 31.3 | 39.0 | 60.9 | 50.9 | 32.3 | 76.8 | 82.8 | 48.7 | 31.6 | 69.3 | |
| 06/01/93 | 20:00 | 1419.3 | 62.3 | 69.6 | 42.1 | 71.6 | 80.2 | 44.8 | 31.6 | 106.5 | 76.6 | 47.9 | 33.3 | 58.4 | 38.0 | 27.3 | 30.3 | 63.8 | 42.2 | 63.0 | 74.3 | 48.0 | 31.3 | 39.6 | 61.3 | 50.6 | 32.2 | 78.6 | 82.3 | 48.2 | 31.4 | 69.4 | |
| 06/02/93 | 00:00 | 1423.3 | 63.0 | 70.2 | 42.3 | 72.2 | 80.5 | 45.2 | 31.8 | 109.3 | 77.7 | 48.3 | 33.6 | 58.6 | 38.6 | 27.5 | 30.4 | 64.0 | 42.5 | 63.4 | 74.4 | 48.4 | 31.5 | 39.5 | 61.0 | 51.1 | 32.4 | 77.0 | 82.6 | 48.7 | 31.7 | 67.6 | |
| 06/02/93 | 04:00 | 1427.3 | 62.8 | 70.2 | 42.3 | 72.3 | 80.4 | 45.1 | 31.8 | 108.8 | 77.6 | 48.4 | 33.7 | 58.7 | 38.6 | 27.5 | 30.5 | 63.9 | 42.4 | 63.2 | 74.3 | 48.3 | 31.6 | 39.9 | 61.4 | 51.0 | 32.5 | 77.2 | 82.6 | 48.7 | 31.7 | 69.5 | |
| 06/02/93 | 08:00 | 1431.3 | 62.9 | 70.0 | 42.2 | 72.2 | 80.5 | 45.3 | 31.8 | 110.2 | 76.1 | 48.4 | 33.7 | 58.7 | 38.7 | 27.7 | 30.4 | 63.8 | 42.4 | 63.3 | 74.0 | 48.4 | 31.7 | 39.8 | 61.3 | 51.1 | 32.5 | 77.3 | 82.7 | 48.8 | 31.8 | 70.5 | |
| 06/02/93 | 12:00 | 1435.3 | 62.7 | 69.5 | 41.7 | 72.6 | 80.0 | 44.9 | 31.7 | 110.2 | 77.9 | 48.1 | 33.5 | 58.1 | 38.4 | 27.5 | 30.1 | 63.5 | 41.9 | 62.8 | 73.4 | 48.2 | 31.6 | 39.6 | 60.8 | 50.8 | 32.5 | 77.0 | 82.0 | 48.4 | 31.6 | 69.9 | |
| 06/02/93 | 16:00 | 1439.3 | 62.5 | 69.1 | 41.8 | 73.7 | 79.8 | 44.7 | 31.6 | 110.4 | 77.7 | 47.9 | 33.5 | 57.9 | 38.3 | 27.3 | 30.0 | 63.1 | 41.6 | 63.0 | 73.1 | 47.6 | 31.3 | 39.7 | 60.5 | 50.4 | 32.3 | 77.0 | 81.6 | 48.2 | 31.5 | 70.2 | |
| 06/02/93 | 20:00 | 1443.3 | 62.6 | 69.6 | 42.2 | 74.4 | 80.0 | 44.8 | 31.8 | 111.3 | 78.4 | 47.9 | 33.7 | 58.3 | 38.0 | 27.4 | 30.4 | 63.4 | 42.2 | 63.2 | 73.0 | 47.8 | 31.6 | 39.8 | 61.1 | 50.3 | 32.4 | 77.2 | 82.6 | 48.0 | 31.6 | 73.3 | |
| 06/03/93 | 00:00 | 1447.3 | 62.6 | 69.8 | 42.2 | 72.8 | 80.2 | 45.1 | 32.0 | 111.9 | 79.8 | 48.2 | 33.8 | 58.5 | 38.5 | 27.6 | 30.5 | 63.5 | 42.3 | 63.2 | 73.6 | 48.0 | 31.7 | 39.7 | 61.0 | 50.6 | 32.5 | 77.7 | 82.6 | 48.4 | 31.6 | 73.4 | |
| 06/03/93 | 04:00 | 1451.3 | 62.4 | 69.7 | 42.3 | 73.1 | 80.2 | 45.1 | 32.0 | 112.2 | 80.3 | 48.3 | 33.9 | 58.6 | 38.6 | 27.7 | 30.5 | 63.5 | 42.3 | 63.0 | 73.9 | 47.9 | 31.8 | 39.8 | 60.9 | 50.6 | 32.6 | 77.8 | 83.0 | 48.5 | 31.6 | 73.3 | |
| 06/03/93 | 08:00 | 1455.3 | 62.3 | 69.8 | 42.1 | 73.1 | 80.2 | 45.1 | 32.0 | 111.3 | 80.7 | 48.3 | 33.8 | 58.4 | 38.6 | 27.7 | 30.3 | 63.5 | 42.2 | 62.7 | 73.6 | 47.8 | 31.9 | 39.8 | 60.6 | 50.7 | 32.7 | 77.2 | 82.6 | 48.5 | 31.6 | 72.7 | |
| 06/03/93 | 12:00 | 1459.3 | 62.4 | 69.2 | 41.7 | 73.0 | 79.8 | 44.8 | 31.9 | 112.1 | 80.3 | 48.1 | 33.8 | 58.0 | 38.1 | 27.5 | 30.2 | 63.0 | 41.8 | 62.5 | 72.9 | 47.6 | 31.8 | 39.8 | 77.4 | 80.2 | 50.4 | 32.7 | 76.3 | 81.2 | 48.2 | 31.7 | 72.6 |

Figure B-2
Excitor Electrode B1 Temperature




Figure B-3
Excitor Electrode B2 Temperature




Figure B-4
Excitor Electrode B3 Temperature




Figure B-5
Excitor Electrode B4 Temperature






Figure B-6
 GROUND ROW A (EAST ROW) TEMPERATURES
 (1-ft Depth)




GROUND ROW A (EAST ROW) TEMPERATURES
 (12-ft Depth)



GROUND ROW A (EAST ROW) TEMPERATURES
(24-ft Depth)

Figure B-8



Temperature, C

GROUND ROW A (EAST ROW) TEMPERATURES
(29-ft Depth)





Figure B-10

GROUND ROW C (WEST ROW) TEMPERATURES
(1-ft Depth)



GROUND ROW C (WEST ROW) TEMPERATURES
(12-ft Depth)

Figure B-11




Figure B-12
GROUND ROW C (WEST ROW) TEMPERATURES
(24-ft Depth)




Figure B-13
 GROUND ROW C (WEST ROW) TEMPERATURES
 (29-ft Depth)




Figure B-14
 Thermowell Temperature vs. Time
 (1-foot depth)





Figure B-15
Thermowell Temperature vs. Time
(12-foot depth)



Temperature, C

Figure B-16
Thermowell Temperature vs. Time
(24-foot depth)




Figure B-17
 Temperature Outside the Heated Array
 (Depth of 12 ft)




Figure B-18
Temperature Outside the Heated Array
(Depth of 24 ft)




Figure B-19
 Temperature Outside the Heated Array
 (Depth of 29 ft, Near Ambient Temp.)






Figure B-20. Longitudinal Temperature Distribution in Plane LONG
(Depth: 1 ft)



**Figure B-21. Longitudinal Temperature Distribution in Plane LONG
(Depth: 10-12 ft)**



**Figure B-22. Longitudinal Temperature Distribution in Plane LONG
(Depth: 20-24 ft)**




Figure B-23. Longitudinal Temperature Distribution in Plane LNGU





Figure B-24. Longitudinal Temperature Distribution in Plane LNGU



**Figure B-25. Longitudinal Temperature Distribution in Plane LNGU
(Depth: 24 ft)**




Figure B-26. Transverse Temperature Distribution in Plane TRNV




Figure B-27. Transverse Temperature Distribution in Plane TRNV




Figure B-28. Transverse Temperature Distribution in Plane TRNV






Figure B-29. Transverse Temperature Distribution in Plane TRNS
 (Depth: 1 ft)



**Figure B-30. Transverse Temperature Distribution in Plane TRNS
(Depth: 10-12 ft)**



APPENDIX C
ELECTRICAL DATA

APPENDIX C

ELECTRICAL DATA

The electrical data and logbook entries regarding the performance of the RF power source and other observations concerning the load are summarized in this memo. Detailed information is available in the log-books. There are two tables entitled: Operating Data -- Electrical and Summary of Log Book Entries.

The table entitled Operating Data -- Electrical provides the electrical operating data for the heating experiment. The following data are tabulated:

- Date and Time
- Forward and Reflected power as measured at the array
- Net input power obtained as the difference of the forward and reflected power measured at the array
- Elapsed time in hours from the beginning of the experiment
- Equivalent days of operation at 40-kW.
- Elapsed calendar days of operation
- Power source utilization factor, percent; found by dividing equivalent days at 40-kW by the calendar days.
- VSWR estimated by equation (1) below. Also see Note 1 below.
- Vector Voltmeter readings, Va and Vb in mV.
- Magnitude of impedance calculated from equation (2) below
- Phase angle as measured by the vector voltmeter
- Magnitude of real and imaginary portions of the impedance as calculated by Equations (3a) and (3b) below.

$$VSWR = \frac{1 + \sqrt{\frac{Ref1}{Forward}}}{1 - \sqrt{\frac{Ref1}{Forward}}} \quad (1)$$

$$Z, \text{ ohms} = 31.98 \left(\frac{Va}{Vb} \right) \quad (2)$$

$$Z_{real} = Z \cos \left(\frac{\pi}{180} (-\phi) \right) \quad (3a)$$

$$Z_{img} = Z \sin \left(\frac{\pi}{180} (-\phi) \right) \quad (3b)$$

where:

Refl: Reflected power measured at array
Forward: Forward power measured at array
 ϕ : phase angle measured by Vector voltmeter
Va, Vb: Vector voltmeter readings, mV

NOTE 1: On May 22, it was observed that there was a large discrepancy between the net input power as measured at the array versus that measured at the power source. This is marked on page 22 of the table containing electrical data (between two horizontal lines). From this point onwards, the forward and reflected data tabulated in this table is from measurements made at the power source. Due to this reason, subsequent VSWR calculations are 1 or very close to 1 unless there was significant reflected power at the power source.

Table C-1 Operating Data -- Electrical

| DATE | Power at Array | | Input Power in kW | Equiv. Time hours | Elapsed Days at 40 kW | Source Utilization % | Vector Voltmeter | | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|---------------|----------------------|----------------------|--------------------------|-------------------------|------------------|----------|-------|--------------|--------|-------------|
| | TIME hr mi | Forw. Ref. | | | | | Vb mV | Va mV | | | | |
| 03-Apr | 16 40 | 10.5 | 4.5 | 6.00 | 0.0 | 0.0 | 4.8 | 13.0 | 9.2 | 45.2 | -70.5 | 15.1 |
| 03-Apr | 20 4 | 10.6 | 4.5 | 6.10 | 3.4 | 0.1 | 15 | 4.7 | 13.0 | 9.2 | 45.2 | -70.7 |
| 03-Apr | 20 5 | 0.0 | 0.0 | 0.00 | 3.4 | 0.0 | 15 | ERR | ERR | ERR | ERR | ERR |
| 03-Apr | 22 45 | 0.0 | 0.0 | 0.00 | 6.1 | 0.0 | 8 | ERR | ERR | ERR | ERR | ERR |
| 03-Apr | 22 46 | 9.9 | 4.2 | 5.70 | 6.1 | 0.0 | 8 | 4.7 | 12.5 | 8.9 | 44.9 | -70.2 |
| 04-Apr | 2 50 | 10.0 | 4.4 | 5.60 | 10.2 | 0.0 | 11 | 4.9 | ERR | ERR | ERR | ERR |
| 04-Apr | 2 51 | 0.0 | 0.0 | 0.00 | 10.2 | 0.0 | 11 | ERR | ERR | ERR | ERR | ERR |
| 04-Apr | 3 10 | 0.0 | 0.0 | 0.00 | 10.5 | 0.0 | 10 | 0.4 | ERR | ERR | ERR | ERR |
| 04-Apr | 3 11 | 10.0 | 4.4 | 5.60 | 10.5 | 0.0 | 10 | 0.4 | ERR | ERR | ERR | ERR |
| 04-Apr | 8 39 | 11.0 | 4.6 | 6.40 | 16.0 | 0.1 | 12 | 4.7 | 12.6 | 9.3 | 43.3 | -71.9 |
| 04-Apr | 8 40 | 0.0 | 0.0 | 0.00 | 16.0 | 0.1 | 12 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 8 54 | 0.0 | 0.0 | 0.00 | 16.2 | 0.1 | 12 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 8 55 | 19.1 | 8.2 | 10.90 | 16.3 | 0.1 | 12 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 10 29 | 19.8 | 9.0 | 10.80 | 17.8 | 0.1 | 13 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 10 30 | 0.0 | 0.0 | 0.00 | 17.8 | 0.1 | 13 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 10 39 | 0.0 | 0.0 | 0.00 | 18.0 | 0.1 | 13 | 0.7 | ERR | ERR | ERR | ERR |
| 04-Apr | 10 40 | 20.0 | 9.0 | 11.00 | 18.0 | 0.1 | 13 | 0.8 | ERR | ERR | ERR | ERR |
| 04-Apr | 14 29 | 19.8 | 8.8 | 11.00 | 21.8 | 0.1 | 13 | 0.9 | ERR | ERR | ERR | ERR |
| 04-Apr | 14 30 | 0.0 | 0.0 | 0.00 | 21.8 | 0.1 | 13 | 0.9 | ERR | ERR | ERR | ERR |
| 04-Apr | 14 44 | 0.0 | 0.0 | 0.00 | 22.1 | 0.1 | 15 | 0.9 | ERR | ERR | ERR | ERR |
| 04-Apr | 14 45 | 20.0 | 9.0 | 11.00 | 22.1 | 0.1 | 15 | 0.9 | ERR | ERR | ERR | ERR |
| 04-Apr | 15 29 | 20.0 | 9.0 | 11.00 | 22.8 | 0.2 | 16 | 5.1 | ERR | ERR | ERR | ERR |
| 04-Apr | 15 30 | 41.5 | 19.0 | 22.50 | 22.8 | 0.2 | 16 | 5.2 | 25.7 | 18.8 | 43.7 | -71.8 |
| 04-Apr | 16 59 | 43.0 | 19.0 | 24.00 | 24.3 | 0.2 | 18 | 5.0 | ERR | ERR | ERR | ERR |
| 04-Apr | 17 0 | 0.0 | 0.0 | 0.00 | 24.3 | 0.2 | 18 | 1.0 | ERR | 25.8 | 18.9 | 43.7 |
| 04-Apr | 17 5 | 0.0 | 0.0 | 0.00 | 24.4 | 0.2 | 18 | 1.0 | ERR | ERR | -71.6 | ERR |
| 04-Apr | 17 6 | 43.0 | 19.0 | 24.00 | 24.4 | 0.2 | 18 | 5.0 | ERR | ERR | 13.8 | 41.4 |
| 04-Apr | 18 59 | 41.0 | 17.5 | 23.50 | 26.3 | 0.2 | 21 | 4.8 | 25.6 | 18.2 | 45.0 | -70.4 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Input Power in kW | Elapsed Time hours | Equiv. Days at 40kW | Source Days Utilization % | Vector Voltmeter Va mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------------|----------------|-------|-------|-------------------|--------------------|---------------------|---------------------------|------------------------|-------|--------------|--------|-------------|
| | TIME hr mi | Forw. | Refl. | | | | | | | | | |
| 05-Apr 08 59 | 33.0 | 10.8 | 22.20 | 40.3 | 0.5 | 1.7 | 32 | 3.7 | ERR | 45.6 | -68.8 | ERR |
| 05-Apr 09 00 | 0.0 | 0.0 | 0.00 | 40.3 | 0.5 | 1.7 | 32 | 22.1 | ERR | 45.6 | 16.5 | 42.5 |
| 05-Apr 09 09 | 0.0 | 0.0 | 0.00 | 40.5 | 0.5 | 1.7 | 32 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 09 10 | 33.0 | 10.8 | 22.20 | 40.5 | 0.5 | 1.7 | 32 | 3.7 | ERR | ERR | ERR | ERR |
| 05-Apr 10 05 | 33.0 | 10.8 | 22.20 | 41.4 | 0.6 | 1.7 | 33 | 3.7 | ERR | ERR | ERR | ERR |
| 05-Apr 10 15 | 49.0 | 15.0 | 34.00 | 41.6 | 0.6 | 1.7 | 33 | 3.5 | 27.5 | 18.5 | 47.5 | -67.6 |
| 05-Apr 10 59 | 49.0 | 15.0 | 34.00 | 42.3 | 0.6 | 1.8 | 34 | 3.5 | ERR | ERR | ERR | ERR |
| 05-Apr 11 00 | 0.0 | 0.0 | 0.00 | 42.3 | 0.6 | 1.8 | 34 | ERR | 27.6 | 18.3 | 48.2 | -67.1 |
| 05-Apr 11 21 | 0.0 | 0.0 | 0.00 | 42.7 | 0.6 | 1.8 | 34 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 11 22 | 52.0 | 16.2 | 35.80 | 42.7 | 0.6 | 1.8 | 34 | 3.5 | 27.8 | 18.7 | 47.5 | 67.9 |
| 05-Apr 12 59 | 50.0 | 14.0 | 36.00 | 44.3 | 0.7 | 1.8 | 36 | 3.2 | ERR | ERR | ERR | ERR |
| 05-Apr 13 00 | 0.0 | 0.0 | 0.00 | 44.3 | 0.7 | 1.8 | 36 | ERR | 27.2 | 17.8 | 48.9 | -66.1 |
| 05-Apr 13 9 | 0.0 | 0.0 | 0.00 | 44.5 | 0.7 | 1.9 | 36 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 13 10 | 50.0 | 14.0 | 36.00 | 44.5 | 0.7 | 1.9 | 36 | 3.2 | ERR | ERR | ERR | ERR |
| 05-Apr 14 59 | 44.8 | 11.9 | 32.90 | 46.3 | 0.7 | 1.9 | 38 | 3.1 | ERR | ERR | ERR | ERR |
| 05-Apr 15 00 | 0.0 | 0.0 | 0.00 | 46.3 | 0.7 | 1.9 | 38 | ERR | 26.2 | 17.2 | 48.7 | -63.0 |
| 05-Apr 15 9 | 0.0 | 0.0 | 0.00 | 46.5 | 0.7 | 1.9 | 37 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 15 10 | 44.8 | 11.9 | 32.90 | 46.5 | 0.7 | 1.9 | 37 | 3.1 | ERR | ERR | ERR | ERR |
| 05-Apr 15 59 | 44.8 | 11.9 | 32.90 | 47.3 | 0.8 | 2.0 | 38 | 3.1 | ERR | ERR | ERR | ERR |
| 05-Apr 16 0 | 0.0 | 0.0 | 0.00 | 47.3 | 0.8 | 2.0 | 38 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 16 19 | 0.0 | 0.0 | 0.00 | 47.7 | 0.8 | 2.0 | 38 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 16 20 | 46.0 | 12.0 | 34.00 | 47.7 | 0.8 | 2.0 | 38 | 3.1 | 26.0 | 17.5 | 47.5 | -63.3 |
| 05-Apr 17 59 | 46.0 | 12.0 | 34.00 | 49.3 | 0.8 | 2.1 | 40 | 3.1 | ERR | ERR | ERR | ERR |
| 05-Apr 18 0 | 0.0 | 0.0 | 0.00 | 49.3 | 0.8 | 2.1 | 40 | ERR | 24.9 | 15.7 | 50.7 | -52.6 |
| 05-Apr 18 5 | 0.0 | 0.0 | 0.00 | 49.4 | 0.8 | 2.1 | 39 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr 18 6 | 42.0 | 8.5 | 33.50 | 49.4 | 0.8 | 2.1 | 39 | 2.6 | ERR | ERR | ERR | ERR |
| 05-Apr 19 59 | 42.0 | 8.5 | 33.50 | 51.3 | 0.9 | 2.1 | 41 | 2.6 | ERR | ERR | ERR | ERR |
| 05-Apr 20 0 | 0.0 | 0.0 | 0.00 | 51.3 | 0.9 | 2.1 | 41 | ERR | ERR | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Input Power | Equiv. | Elapsed Days at 40 kW | Source | Vector Voltmeter | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|-------|-------|-------------|--------|-----------------------|--------|-------------------|-------------------|--------------|--------|-------------|
| | TIME hr mi | FORW. | REFL. | Time hours | Days | Utilization % | VSWR | V _a mV | V _b mV | ERR | ERR | ERR |
| 05-Apr | 20 5 | 0.0 | 0.0 | 51.4 | 0.9 | 2.1 | 41 | ERR | ERR | ERR | ERR | ERR |
| 05-Apr | 20 6 | 42.0 | 8.5 | 33.50 | 51.4 | 0.9 | 2.1 | 41 | 2.6 | ERR | ERR | ERR |
| 05-Apr | 21 59 | 42.0 | 8.5 | 33.50 | 53.3 | 0.9 | 2.2 | 43 | 2.6 | ERR | ERR | ERR |
| 05-Apr | 22 0 | 0.0 | 0.0 | 0.00 | 53.3 | 0.9 | 2.2 | 43 | ERR | ERR | ERR | ERR |
| 05-Apr | 22 49 | 0.0 | 0.0 | 0.00 | 54.2 | 0.9 | 2.3 | 42 | 2.6 | 28.6 | 18.2 | -52.7 |
| 05-Apr | 22 50 | 52.0 | 10.0 | 42.00 | 54.2 | 0.9 | 2.3 | 42 | 2.6 | 28.6 | 18.0 | 50.3 |
| 05-Apr | 23 59 | 52.0 | 10.0 | 42.00 | 55.3 | 1.0 | 2.3 | 43 | 2.6 | 28.7 | 18.0 | 51.0 |
| 06-Apr | 0 0 | 0.0 | 0.0 | 0.00 | 55.3 | 1.0 | 2.3 | 43 | ERR | ERR | ERR | ERR |
| 06-Apr | 0 15 | 0.0 | 0.0 | 0.00 | 55.6 | 1.0 | 2.3 | 43 | ERR | ERR | ERR | ERR |
| 06-Apr | 0 16 | 52.0 | 10.0 | 42.00 | 55.6 | 1.0 | 2.3 | 43 | 2.6 | ERR | ERR | ERR |
| 06-Apr | 1 59 | 52.0 | 10.0 | 42.00 | 57.3 | 1.1 | 2.4 | 45 | 2.6 | ERR | ERR | ERR |
| 06-Apr | 2 0 | 0.0 | 0.0 | 0.00 | 57.3 | 1.1 | 2.4 | 45 | ERR | 28.6 | 17.7 | -52.0 |
| 06-Apr | 2 10 | 0.0 | 0.0 | 0.00 | 57.5 | 1.1 | 2.4 | 45 | ERR | ERR | 51.7 | 31.8 |
| 06-Apr | 2 11 | 52.0 | 10.0 | 42.00 | 57.5 | 1.1 | 2.4 | 45 | 2.6 | ERR | ERR | ERR |
| 06-Apr | 3 59 | 50.0 | 9.0 | 41.00 | 59.3 | 1.1 | 2.5 | 47 | 2.5 | ERR | ERR | ERR |
| 06-Apr | 4 0 | 0.0 | 0.0 | 0.00 | 59.3 | 1.2 | 2.5 | 47 | ERR | 27.8 | 17.5 | -50.5 |
| 06-Apr | 4 15 | 0.0 | 0.0 | 0.00 | 59.6 | 1.2 | 2.5 | 46 | ERR | ERR | ERR | 32.3 |
| 06-Apr | 4 16 | 50.0 | 9.0 | 41.00 | 59.6 | 1.2 | 2.5 | 46 | 2.6 | ERR | ERR | ERR |
| 06-Apr | 5 59 | 50.0 | 8.2 | 41.80 | 61.3 | 1.2 | 2.6 | 48 | 2.4 | ERR | ERR | ERR |
| 06-Apr | 6 0 | 0.0 | 0.0 | 0.00 | 61.3 | 1.2 | 2.6 | 48 | ERR | 27.5 | 17.5 | 50.8 |
| 06-Apr | 6 15 | 0.0 | 0.0 | 0.00 | 61.6 | 1.2 | 2.6 | 48 | ERR | ERR | ERR | 39.2 |
| 06-Apr | 6 16 | 50.0 | 8.2 | 41.80 | 61.6 | 1.2 | 2.6 | 48 | 2.4 | ERR | ERR | ERR |
| 06-Apr | 7 59 | 48.0 | 8.2 | 39.80 | 63.3 | 1.3 | 2.6 | 49 | 2.4 | ERR | ERR | ERR |
| 06-Apr | 8 0 | 0.0 | 0.0 | 0.00 | 63.3 | 1.3 | 2.6 | 49 | ERR | 26.5 | 17.3 | -49.2 |
| 06-Apr | 8 10 | 0.0 | 0.0 | 0.00 | 63.5 | 1.3 | 2.6 | 49 | ERR | ERR | ERR | 32.8 |
| 06-Apr | 8 11 | 48.0 | 8.2 | 39.80 | 63.5 | 1.3 | 2.6 | 49 | 2.4 | ERR | ERR | ERR |
| 06-Apr | 9 59 | 48.0 | 7.2 | 40.80 | 65.3 | 1.4 | 2.7 | 51 | 2.3 | ERR | ERR | ERR |
| 06-Apr | 10 0 | 0.0 | 0.0 | 0.00 | 65.3 | 1.4 | 2.7 | 51 | ERR | 25.7 | 17.0 | 48.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array in kW | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days Utilization % | Source | Vector Voltmeter | Z | | |
|--------|---------------|-------------------------|-------------------------|--------------------------|----------------------------|----------------------------------|--------|------------------|----------------------|----------------------|----------|
| | | | | | | | | | V _a mV | V _b mV | Z ohm |
| | | | | | | | | | ERR | ERR | ERR |
| 06-Apr | 10 8 | 0.0 | 0.0 | 0.00 | 65.5 | 1.4 | 2.7 | 50 | ERR | ERR | ERR |
| 06-Apr | 10 9 | 48.0 | 7.2 | 40.80 | 65.5 | 1.4 | 2.7 | 50 | 2.3 | ERR | ERR |
| 06-Apr | 11 59 | 46.5 | 6.5 | 40.00 | 67.3 | 1.5 | 2.8 | 52 | 2.2 | ERR | ERR |
| 06-Apr | 12 0 | 0.0 | 0.0 | 0.00 | 67.3 | 1.5 | 2.8 | 52 | ERR | 25.5 | 50.3 |
| 06-Apr | 12 9 | 0.0 | 0.0 | 0.00 | 67.5 | 1.5 | 2.8 | 52 | ERR | ERR | -45.4 |
| 06-Apr | 12 10 | 46.5 | 6.5 | 40.00 | 67.5 | 1.5 | 2.8 | 52 | 2.2 | ERR | ERR |
| 06-Apr | 14 39 | 46.5 | 6.5 | 40.00 | 70.0 | 1.6 | 2.9 | 53 | 2.2 | ERR | ERR |
| 06-Apr | 14 40 | 0.0 | 0.0 | 0.00 | 70.0 | 1.6 | 2.9 | 53 | ERR | ERR | ERR |
| 06-Apr | 14 50 | 0.0 | 0.0 | 0.00 | 70.2 | 1.6 | 2.9 | 53 | ERR | ERR | ERR |
| 06-Apr | 14 51 | 46.0 | 6.8 | 39.20 | 70.2 | 1.6 | 2.9 | 53 | 2.2 | 24.3 | 16.5 |
| 06-Apr | 15 30 | 45.0 | 6.5 | 38.50 | 70.8 | 1.6 | 3.0 | 54 | 2.2 | 25.3 | 16.3 |
| 06-Apr | 17 59 | 45.0 | 6.5 | 38.50 | 73.3 | 1.7 | 3.1 | 55 | 2.2 | ERR | ERR |
| 06-Apr | 18 0 | 0.0 | 0.0 | 0.00 | 73.3 | 1.7 | 3.1 | 55 | ERR | ERR | ERR |
| 06-Apr | 18 5 | 0.0 | 0.0 | 0.00 | 73.4 | 1.7 | 3.1 | 55 | ERR | ERR | ERR |
| 06-Apr | 18 6 | 45.0 | 6.5 | 38.50 | 73.4 | 1.7 | 3.1 | 55 | 2.2 | ERR | ERR |
| 06-Apr | 21 59 | 45.0 | 6.5 | 38.50 | 77.3 | 1.8 | 3.2 | 57 | 2.2 | 25.2 | 16.4 |
| 06-Apr | 22 0 | 0.0 | 0.0 | 0.00 | 77.3 | 1.8 | 3.2 | 57 | ERR | ERR | ERR |
| 06-Apr | 22 5 | 0.0 | 0.0 | 0.00 | 77.4 | 1.8 | 3.2 | 57 | ERR | ERR | ERR |
| 06-Apr | 22 6 | 45.0 | 6.5 | 38.50 | 77.4 | 1.8 | 3.2 | 57 | 2.2 | ERR | ERR |
| 06-Apr | 1 59 | 45.0 | 6.5 | 38.50 | 81.3 | 2.0 | 3.4 | 59 | 2.2 | ERR | ERR |
| 07-Apr | 2 0 | 0.0 | 0.0 | 0.00 | 81.3 | 2.0 | 3.4 | 59 | ERR | 25.2 | 16.6 |
| 07-Apr | 2 10 | 0.0 | 0.0 | 0.00 | 81.5 | 2.0 | 3.4 | 59 | 2.2 | ERR | ERR |
| 07-Apr | 2 11 | 46.0 | 6.5 | 39.50 | 81.5 | 2.0 | 3.4 | 59 | 2.2 | ERR | ERR |
| 07-Apr | 5 59 | 46.0 | 6.4 | 39.60 | 85.3 | 2.2 | 3.6 | 61 | 2.2 | 48.5 | -44.5 |
| 07-Apr | 6 0 | 0.0 | 0.0 | 0.00 | 85.3 | 2.2 | 3.6 | 61 | ERR | 25.0 | 16.7 |
| 07-Apr | 6 7 | 0.0 | 0.0 | 0.00 | 85.5 | 2.2 | 3.6 | 60 | ERR | ERR | ERR |
| 07-Apr | 6 8 | 46.0 | 6.5 | 39.50 | 85.5 | 2.2 | 3.6 | 60 | 2.2 | ERR | ERR |
| 07-Apr | 8 29 | 46.0 | 6.6 | 39.40 | 87.8 | 2.3 | 3.7 | 61 | 2.2 | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days at 40 kW | Source Days Utilization % | Vector Voltmeter Va mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|----------------------|-----------------|-----------------------|----------------------------|---------------------------------|------------------------------|----------|-----------------|-----------|----------------|
| | TIME hr mi | Input Power in kW | Refil. Forw. | | | | | | | | |
| 07-Apr | 8 30 | 0.0 | 0.0 | 87.8 | 2.3 | 3.7 | 61 | ERR | ERR | ERR | ERR |
| 07-Apr | 8 36 | 0.0 | 0.0 | 87.9 | 2.3 | 3.7 | 61 | ERR | ERR | ERR | ERR |
| 07-Apr | 8 37 | 46.0 | 6.6 | 39.40 | 88.0 | 2.3 | 3.7 | 61 | 2.2 | 24.7 | 16.7 |
| 07-Apr | 13 4 | 46.0 | 6.6 | 39.40 | 92.4 | 2.4 | 3.9 | 63 | 2.2 | ERR | ERR |
| 07-Apr | 13 5 | 0.0 | 0.0 | 92.4 | 2.4 | 3.9 | 63 | ERR | ERR | ERR | ERR |
| 07-Apr | 13 14 | 0.0 | 0.0 | 92.6 | 2.4 | 3.9 | 63 | ERR | ERR | ERR | ERR |
| 07-Apr | 13 15 | 48.2 | 7.5 | 40.70 | 92.6 | 2.4 | 3.9 | 63 | 2.3 | 25.7 | 16.8 |
| 07-Apr | 14 35 | 47.2 | 7.5 | 39.70 | 93.9 | 2.5 | 3.9 | 64 | 2.3 | 25.4 | 16.5 |
| 07-Apr | 16 59 | 45.0 | 7.5 | 37.50 | 96.3 | 2.6 | 4.0 | 64 | 2.4 | ERR | ERR |
| 07-Apr | 17 0 | 0.0 | 0.0 | 96.3 | 2.6 | 4.0 | 64 | ERR | ERR | ERR | ERR |
| 07-Apr | 17 7 | 0.0 | 0.0 | 96.5 | 2.6 | 4.0 | 64 | ERR | 25.4 | 16.4 | 49.5 |
| 07-Apr | 17 8 | 45.0 | 7.5 | 37.50 | 96.5 | 2.6 | 4.0 | 64 | 2.4 | ERR | ERR |
| 07-Apr | 19 15 | 45.9 | 7.2 | 38.70 | 98.6 | 2.7 | 4.1 | 65 | 2.3 | 25.6 | 16.2 |
| 07-Apr | 21 52 | 46.2 | 7.0 | 39.20 | 101.2 | 2.8 | 4.2 | 66 | 2.3 | 25.9 | 16.2 |
| 07-Apr | 21 57 | 46.2 | 7.0 | 39.20 | 101.3 | 2.8 | 4.2 | 66 | 2.3 | ERR | ERR |
| 07-Apr | 21 58 | 0.0 | 0.0 | 101.3 | 2.8 | 4.2 | 66 | ERR | ERR | ERR | ERR |
| 07-Apr | 22 2 | 0.0 | 0.0 | 101.4 | 2.8 | 4.2 | 66 | ERR | ERR | ERR | ERR |
| 07-Apr | 22 3 | 46.2 | 7.0 | 39.20 | 101.4 | 2.8 | 4.2 | 66 | 2.3 | 26.0 | 16.2 |
| 08-Apr | 2 44 | 46.2 | 7.0 | 39.20 | 106.1 | 3.0 | 4.4 | 67 | 2.3 | ERR | ERR |
| 08-Apr | 2 45 | 0.0 | 0.0 | 106.1 | 3.0 | 4.4 | 67 | ERR | ERR | ERR | ERR |
| 08-Apr | 3 29 | 0.0 | 0.0 | 106.8 | 3.0 | 4.5 | 67 | ERR | ERR | ERR | ERR |
| 08-Apr | 3 30 | 46.0 | 6.5 | 39.50 | 106.8 | 3.0 | 4.5 | 67 | 2.2 | ERR | ERR |
| 08-Apr | 5 59 | 46.0 | 6.5 | 39.50 | 109.3 | 3.1 | 4.6 | 68 | 2.2 | ERR | ERR |
| 08-Apr | 6 0 | 0.0 | 0.0 | 109.3 | 3.1 | 4.6 | 68 | ERR | ERR | ERR | ERR |
| 08-Apr | 6 7 | 0.0 | 0.0 | 109.5 | 3.1 | 4.6 | 67 | ERR | 28.0 | 15.5 | 57.8 |
| 08-Apr | 6 8 | 46.0 | 6.5 | 39.50 | 109.5 | 3.1 | 4.6 | 67 | 2.2 | ERR | ERR |
| 08-Apr | 8 10 | 46.4 | 6.9 | 39.50 | 111.5 | 3.2 | 4.6 | 68 | 2.3 | 27.3 | 15.5 |
| 08-Apr | 11 0 | 47.0 | 7.0 | 40.00 | 114.3 | 3.3 | 4.8 | 69 | 2.3 | 27.1 | 15.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array in kW | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Source Days Utilization % | Vector Voltmeter Vb mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|---------------|-------------------------|-------------------------|--------------------------|----------------------------|--|------------------------------|----------|-----------------|-----------|----------------|
| | | | | | | | | | | | |
| 08-Apr | 11 26 | 47.0 | 7.0 | 40.00 | 114.8 | 3.3 | 4.8 | 69 | 2.3 | ERR | ERR |
| 08-Apr | 11 27 | 0.0 | 0.0 | 0.00 | 114.8 | 3.3 | 4.8 | 69 | ERR | ERR | ERR |
| 08-Apr | 11 41 | 0.0 | 0.0 | 0.00 | 115.0 | 3.3 | 4.8 | 69 | ERR | ERR | ERR |
| 08-Apr | 11 42 | 44.2 | 7.0 | 37.20 | 115.0 | 3.3 | 4.8 | 69 | 2.3 | 26.8 | 15.0 |
| 08-Apr | 13 30 | 46.5 | 7.0 | 39.50 | 116.8 | 3.4 | 4.9 | 69 | 2.3 | 27.3 | 15.2 |
| 08-Apr | 14 25 | 46.0 | 7.0 | 39.00 | 117.8 | 3.4 | 4.9 | 69 | 2.3 | 27.3 | 15.1 |
| 08-Apr | 15 44 | 46.0 | 7.0 | 39.00 | 119.1 | 3.5 | 5.0 | 70 | 2.3 | ERR | ERR |
| 08-Apr | 15 45 | 0.0 | 0.0 | 0.00 | 119.1 | 3.5 | 5.0 | 70 | ERR | ERR | ERR |
| 08-Apr | 15 59 | 0.0 | 0.0 | 0.00 | 119.3 | 3.5 | 5.0 | 70 | ERR | ERR | ERR |
| 08-Apr | 16 0 | 45.0 | 7.2 | 37.80 | 119.3 | 3.5 | 5.0 | 70 | 2.3 | 27.6 | 15.2 |
| 08-Apr | 18 59 | 45.0 | 7.2 | 37.80 | 122.3 | 3.6 | 5.1 | 70 | 2.3 | ERR | ERR |
| 08-Apr | 19 0 | 0 | 0 | 0 | 122.3 | 3.5 | 5.1 | 69 | ERR | ERR | ERR |
| 08-Apr | 19 4 | 0 | 0 | 0 | 122.4 | 3.5 | 5.1 | 69 | ERR | ERR | ERR |
| 08-Apr | 19 5 | 45.0 | 7.0 | 38.00 | 122.4 | 3.6 | 5.1 | 70 | 2.3 | 27.6 | 15.0 |
| 09-Apr | 0 29 | 45.0 | 7.0 | 38.00 | 127.8 | 3.8 | 5.3 | 71 | 2.3 | ERR | ERR |
| 09-Apr | 0 30 | 0.0 | 0.0 | 0.00 | 127.8 | 3.7 | 5.3 | 69 | ERR | ERR | ERR |
| 09-Apr | 2 0 | 0.0 | 0.0 | 0.00 | 129.3 | 3.5 | 5.4 | 65 | ERR | ERR | ERR |
| 09-Apr | 2 1 | 48.0 | 7.0 | 41.00 | 129.4 | 3.7 | 5.4 | 68 | 2.2 | 28.7 | 15.2 |
| 09-Apr | 4 0 | 48.0 | 7.0 | 41.00 | 131.3 | 3.9 | 5.5 | 72 | 2.2 | 60.4 | -47.8 |
| 09-Apr | 4 1 | 0.0 | 0.0 | 0.00 | 131.4 | 3.9 | 5.5 | 71 | ERR | ERR | ERR |
| 09-Apr | 4 6 | 0.0 | 0.0 | 0.00 | 131.4 | 3.7 | 5.5 | 67 | ERR | ERR | ERR |
| 09-Apr | 4 7 | 48.0 | 7.0 | 41.00 | 131.5 | 3.6 | 5.5 | 65 | ERR | ERR | ERR |
| 09-Apr | 9 0 | 50.0 | 7.0 | 43.00 | 136.3 | 4.2 | 5.7 | 73 | 2.2 | 28.0 | 14.7 |
| 09-Apr | 10 55 | 48.0 | 7.0 | 41.00 | 138.3 | 4.3 | 5.8 | 74 | 2.2 | 27.5 | 14.4 |
| 09-Apr | 13 43 | 48.0 | 7.0 | 41.00 | 141.1 | 4.4 | 5.9 | 74 | 2.2 | ERR | ERR |
| 09-Apr | 10 44 | 0.0 | 0.0 | 0.00 | 138.1 | 4.3 | 5.8 | 75 | ERR | 27.8 | 14.4 |
| 09-Apr | 10 53 | 0.0 | 0.0 | 0.00 | 138.2 | 4.3 | 5.8 | 75 | ERR | 61.7 | -48.4 |
| 09-Apr | 10 55 | 48.0 | 7.0 | 41.00 | 138.3 | 4.3 | 5.8 | 75 | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days at 40 kW | Source Utilization % | VSWR | Vector Voltmeter Va mV | Vb mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|----------------|------------------------|-----------------------|----------------------------|--------------------------|----------------------------|------|------------------------------|----------|----------|-----------------|-----------|----------------|
| | TIME hr mi | in kW Forw. | Power in kW Ref. | | | | | | | | | | | |
| 09-Apr | 14 14 | 48.0 | 7.0 | 41.00 | 141.6 | 4.4 | 5.9 | 74 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 14 15 | 0.0 | 0.0 | 0.00 | 141.6 | 4.3 | 5.9 | 73 | ERR | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 14 29 | 0.0 | 0.0 | 0.00 | 141.8 | 4.4 | 5.9 | 74 | ERR | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 14 30 | 48.0 | 6.9 | 41.10 | 141.8 | 4.3 | 5.9 | 73 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 17 33 | 46.5 | 6.8 | 39.70 | 144.9 | 4.5 | 6.0 | 74 | 2.2 | 27.4 | 14.4 | 60.9 | -48.4 | 40.4 |
| 09-Apr | 18 29 | 46.5 | 6.8 | 39.70 | 145.8 | 4.5 | 6.1 | 74 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 18 30 | 0.0 | 0.0 | 0.00 | 145.8 | 4.5 | 6.1 | 74 | ERR | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 18 34 | 0.0 | 0.0 | 0.00 | 145.9 | 4.5 | 6.1 | 74 | ERR | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 18 35 | 46.5 | 6.8 | 39.70 | 145.9 | 4.5 | 6.1 | 74 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 09-Apr | 21 7 | 46.2 | 6.2 | 40.00 | 148.5 | 4.6 | 6.2 | 74 | 2.2 | 28.1 | 14.5 | 62.0 | -47.7 | 41.7 |
| 09-Apr | 23 0 | 46.2 | 6.2 | 40.00 | 150.3 | 4.7 | 6.3 | 75 | 2.2 | 28.4 | 14.5 | 62.6 | -45.4 | 44.0 |
| 10-Apr | 1 30 | 46.0 | 6.2 | 39.80 | 152.8 | 4.8 | 6.4 | 75 | 2.2 | 28.5 | 14.5 | 62.9 | -44.6 | 44.1 |
| 10-Apr | 3 0 | 46.0 | 6.2 | 39.80 | 154.3 | 4.8 | 6.4 | 75 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 3 1 | 0.0 | 0.0 | 0.00 | 154.4 | 4.8 | 6.4 | 75 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 3 11 | 0.0 | 0.0 | 0.00 | 154.5 | 4.8 | 6.4 | 75 | 2.2 | 28.8 | 14.7 | 62.7 | -40.0 | 48.0 |
| 10-Apr | 3 12 | 46.0 | 6.2 | 39.80 | 154.5 | 4.8 | 6.4 | 75 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 5 0 | 46.0 | 6.0 | 40.00 | 156.3 | 4.9 | 6.5 | 76 | 2.1 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 10 5 | 49.5 | 6.5 | 43.00 | 161.4 | 5.2 | 6.7 | 77 | 2.1 | 28.3 | 15.0 | 60.3 | -42.1 | 44.8 |
| 10-Apr | 11 39 | 49.5 | 6.5 | 43.00 | 163.0 | 5.2 | 6.8 | 77 | 2.1 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 11 40 | 0.0 | 0.0 | 0.00 | 163.0 | 5.2 | 6.8 | 77 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 11 54 | 0.0 | 0.0 | 0.00 | 163.2 | 5.2 | 6.8 | 77 | 2.1 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 11 55 | 49.0 | 6.5 | 42.50 | 163.3 | 5.2 | 6.8 | 77 | 2.1 | 28.4 | 14.0 | 64.9 | -42.4 | 47.9 |
| 10-Apr | 14 20 | 48.0 | 6.5 | 41.50 | 165.7 | 5.3 | 6.9 | 77 | 2.2 | 28.3 | 14.7 | 61.6 | -42.0 | 45.8 |
| 10-Apr | 15 38 | 48.0 | 6.5 | 41.50 | 167.0 | 5.4 | 7.0 | 78 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 15 39 | 0.0 | 0.0 | 0.00 | 167.0 | 5.4 | 7.0 | 78 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 15 44 | 0.0 | 0.0 | 0.00 | 167.1 | 5.4 | 7.0 | 78 | 2.2 | 28.0 | 14.5 | 61.8 | -42.1 | 45.8 |
| 10-Apr | 15 45 | 48.0 | 6.5 | 41.50 | 167.1 | 5.4 | 7.0 | 78 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 10-Apr | 17 36 | 47.0 | 6.5 | 40.50 | 168.9 | 5.5 | 7.0 | 78 | 2.2 | 28.0 | 14.5 | 61.8 | -42.1 | 45.8 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Source % | Vector Voltmeter | | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|-------------|-------------------|--------------------|----------------------|----------|------------------|-------|-------|--------------|--------|-------------|
| | TIME hr mi | Forw. Refl. | | | | | VSWR | Va mV | | | | |
| 10-Apr | 19 23 | 47.0 | 6.2 | 40.80 | 170.7 | 5.6 | 7.1 | 78 | 2.1 | 28.6 | 14.4 | 63.5 |
| 10-Apr | 20 32 | 46.5 | 6.2 | 40.30 | 171.9 | 5.6 | 7.2 | 78 | 2.2 | ERR | ERR | 45.4 |
| 10-Apr | 20 33 | 0.0 | 0.0 | 0.00 | 171.9 | 5.6 | 7.2 | 78 | 2.2 | ERR | ERR | 44.4 |
| 10-Apr | 20 37 | 0.0 | 0.0 | 0.00 | 172.0 | 5.6 | 7.2 | 78 | 2.2 | ERR | ERR | ERR |
| 10-Apr | 20 38 | 46.5 | 6.2 | 40.30 | 172.0 | 5.6 | 7.2 | 78 | 2.2 | ERR | ERR | ERR |
| 10-Apr | 22 13 | 46.5 | 6.2 | 40.30 | 173.6 | 5.7 | 7.2 | 78 | 2.2 | 64.9 | -42.6 | 47.7 |
| 11-Apr | 0 0 | 47.0 | 6.2 | 40.80 | 175.3 | 5.7 | 7.3 | 79 | 2.1 | 29.1 | 14.3 | 65.1 |
| 11-Apr | 0 9 | 46.0 | 5.9 | 40.10 | 175.5 | 5.8 | 7.3 | 79 | 2.1 | ERR | ERR | 48.7 |
| 11-Apr | 0 10 | 0.0 | 0.0 | 0.00 | 175.5 | 5.8 | 7.3 | 79 | 2.1 | ERR | ERR | 43.2 |
| 11-Apr | 0 14 | 0.0 | 0.0 | 0.00 | 175.6 | 5.8 | 7.3 | 79 | 2.1 | ERR | ERR | ERR |
| 11-Apr | 0 15 | 46.0 | 5.9 | 40.10 | 175.6 | 5.8 | 7.3 | 79 | 2.1 | ERR | ERR | 43.9 |
| 11-Apr | 2 0 | 47.0 | 5.8 | 41.20 | 177.3 | 5.8 | 7.4 | 78 | 2.1 | 29.4 | 14.4 | 65.3 |
| 11-Apr | 3 0 | 48.0 | 5.8 | 42.20 | 178.3 | 5.8 | 7.4 | 79 | 2.1 | 29.5 | 14.4 | 65.5 |
| 11-Apr | 4 0 | 48.0 | 6.0 | 42.00 | 179.3 | 5.9 | 7.5 | 79 | 2.1 | 29.6 | 14.4 | 65.7 |
| 11-Apr | 5 0 | 48.0 | 6.2 | 41.80 | 180.3 | 5.9 | 7.5 | 79 | 2.1 | 29.6 | 14.3 | 66.2 |
| 11-Apr | 5 54 | 48.0 | 6.2 | 41.80 | 181.2 | 6.0 | 7.6 | 79 | 2.1 | ERR | ERR | 48.1 |
| 11-Apr | 5 55 | 0.0 | 0.0 | 0.00 | 181.3 | 6.0 | 7.6 | 79 | 2.1 | ERR | ERR | 45.5 |
| 11-Apr | 5 59 | 0.0 | 0.0 | 0.00 | 181.3 | 6.0 | 7.6 | 79 | 2.1 | ERR | ERR | 43.4 |
| 11-Apr | 6 0 | 48.0 | 6.2 | 41.80 | 181.3 | 6.0 | 7.6 | 79 | 2.1 | 29.8 | 14.4 | 66.2 |
| 11-Apr | 9 53 | 48.0 | 6.2 | 41.80 | 185.2 | 6.1 | 7.7 | 79 | 2.1 | 29.7 | 13.7 | 69.3 |
| 11-Apr | 11 30 | 49.0 | 6.5 | 42.50 | 186.8 | 6.2 | 7.8 | 80 | 2.1 | 29.3 | 13.5 | 69.4 |
| 11-Apr | 12 36 | 49.0 | 6.5 | 42.50 | 187.9 | 6.3 | 7.8 | 80 | 2.1 | ERR | ERR | 52.1 |
| 11-Apr | 12 37 | 0.0 | 0.0 | 0.00 | 188.0 | 6.3 | 7.8 | 80 | 2.1 | ERR | ERR | 45.3 |
| 11-Apr | 16 13 | 0.0 | 0.0 | 0.00 | 191.6 | 6.3 | 8.0 | 78 | 2.1 | ERR | ERR | 46.0 |
| 11-Apr | 16 14 | 47.8 | 6.0 | 41.80 | 191.6 | 6.3 | 8.0 | 78 | 2.1 | ERR | ERR | 45.9 |
| 11-Apr | 16 39 | 47.8 | 6.0 | 41.80 | 192.0 | 6.3 | 8.0 | 78 | 2.1 | 28.3 | 13.3 | 68.0 |
| 11-Apr | 19 43 | 47.8 | 6.0 | 41.80 | 195.1 | 6.4 | 8.1 | 79 | 2.1 | ERR | ERR | 50.8 |
| 11-Apr | 19 44 | 0.0 | 0.0 | 0.00 | 195.1 | 6.4 | 8.1 | 79 | 2.1 | ERR | ERR | 45.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array in kW | Input Power in kW | Equiv. Power in kW | Elapsed Time hours | Days at 40 kW | Source Utilization % | VSWR | Vector Voltmeter Va mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|---------------|-------------------------|----------------------|--------------------------|--------------------------|------------------|----------------------------|------|------------------------------|----------|-----------------|-----------|----------------|
| | | | | | | | | | | | | ERR | ERR |
| 11-Apr | 19 33 | 47.5 | 6.1 | 41.40 | 194.9 | 6.4 | 8.1 | 79 | 2.1 | ERR | ERR | ERR | ERR |
| 11-Apr | 21 59 | 47.5 | 6.1 | 41.40 | 197.3 | 6.5 | 8.2 | 79 | 2.1 | ERR | ERR | ERR | ERR |
| 11-Apr | 22 0 | 0.0 | 0.0 | 0.00 | 197.3 | 6.5 | 8.2 | 79 | ERR | ERR | ERR | ERR | ERR |
| 11-Apr | 22 10 | 0.0 | 0.0 | 0.00 | 197.5 | 6.5 | 8.2 | 78 | ERR | ERR | ERR | ERR | ERR |
| 11-Apr | 22 11 | 47.5 | 6.1 | 41.40 | 197.5 | 6.5 | 8.2 | 78 | 2.1 | ERR | ERR | ERR | ERR |
| 11-Apr | 22 20 | 47.5 | 6.1 | 41.40 | 197.7 | 6.5 | 8.2 | 78 | 2.1 | ERR | ERR | ERR | ERR |
| 11-Apr | 22 11 | 0.0 | 0.0 | 0.00 | 197.5 | 6.5 | 8.2 | 78 | ERR | ERR | ERR | ERR | ERR |
| 11-Apr | 22 43 | 0.0 | 0.0 | 0.00 | 198.1 | 6.5 | 8.3 | 78 | ERR | ERR | ERR | ERR | ERR |
| 11-Apr | 22 44 | 47.8 | 6.0 | 41.80 | 198.1 | 6.5 | 8.3 | 78 | 2.1 | ERR | ERR | ERR | ERR |
| 11-Apr | 23 10 | 47.8 | 6.0 | 41.80 | 198.5 | 6.5 | 8.3 | 78 | 2.1 | 29.6 | 13.2 | 71.7 | -40.8 |
| 12-Apr | 0 30 | 47.8 | 6.0 | 41.80 | 199.8 | 6.5 | 8.3 | 79 | 2.1 | 29.7 | 13.3 | 13.3 | -41.4 |
| 12-Apr | 1 40 | 48.0 | 6.2 | 41.80 | 201.0 | 6.6 | 8.4 | 79 | 2.1 | 29.7 | 13.4 | 70.9 | -41.9 |
| 12-Apr | 3 0 | 48.0 | 6.2 | 41.80 | 202.3 | 6.6 | 8.4 | 79 | 2.1 | 29.7 | 13.3 | 71.4 | -42.2 |
| 12-Apr | 4 0 | 48.0 | 6.2 | 41.80 | 203.3 | 6.7 | 8.5 | 79 | 2.1 | 29.7 | 13.2 | 72.0 | -42.1 |
| 12-Apr | 4 19 | 48.0 | 6.2 | 41.80 | 203.7 | 6.7 | 8.5 | 79 | 2.1 | ERR | ERR | ERR | ERR |
| 12-Apr | 4 20 | 0.0 | 0.0 | 0.00 | 203.7 | 6.7 | 8.5 | 79 | ERR | ERR | ERR | ERR | ERR |
| 12-Apr | 4 27 | 0.0 | 0.0 | 0.00 | 203.8 | 6.7 | 8.5 | 79 | ERR | ERR | ERR | ERR | ERR |
| 12-Apr | 4 28 | 48.0 | 6.2 | 41.80 | 203.8 | 6.7 | 8.5 | 79 | 2.1 | ERR | ERR | ERR | ERR |
| 12-Apr | 5 0 | 48.0 | 6.2 | 41.80 | 204.3 | 6.7 | 8.5 | 79 | 2.1 | 30.0 | 13.3 | 72.1 | -41.1 |
| 12-Apr | 6 0 | 48.0 | 6.2 | 41.80 | 205.3 | 6.8 | 8.6 | 79 | 2.1 | 29.9 | 13.1 | 73.0 | -41.0 |
| 12-Apr | 7 0 | 46.0 | 6.0 | 40.00 | 206.3 | 6.8 | 8.6 | 79 | 2.1 | 29.5 | 13.0 | 72.6 | -42.2 |
| 12-Apr | 8 0 | 48.0 | 6.2 | 41.80 | 207.3 | 6.9 | 8.6 | 79 | 2.1 | 29.8 | 13.2 | 72.2 | -42.0 |
| 12-Apr | 9 25 | 48.0 | 6.2 | 41.80 | 208.8 | 6.9 | 8.7 | 80 | 2.1 | 30.0 | 12.9 | 74.4 | -40.9 |
| 12-Apr | 9 32 | 48.0 | 6.2 | 41.80 | 208.9 | 6.9 | 8.7 | 80 | 2.1 | ERR | ERR | ERR | ERR |
| 12-Apr | 9 33 | 0.0 | 0.0 | 0.00 | 208.9 | 6.9 | 8.7 | 80 | ERR | ERR | ERR | ERR | ERR |
| 12-Apr | 10 29 | 0.0 | 0.0 | 0.00 | 209.8 | 6.9 | 8.7 | 79 | 2.1 | 30.0 | 13.1 | 73.2 | -40.2 |
| 12-Apr | 10 30 | 48.0 | 6.2 | 41.80 | 209.8 | 6.9 | 8.7 | 79 | 2.1 | ERR | ERR | ERR | ERR |
| 12-Apr | 13 14 | 47.5 | 6.0 | 41.50 | 212.6 | 7.0 | 8.9 | 80 | 2.1 | ERR | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days | Source Utilization % | Vector Voltmeter | | | Angle degree | Z Real | Z Imaginary |
|--------|----------------|----------------|------------------------|--------------------------|----------------|----------------------------|------------------|----------------------|----------------------|-----------------|-----------|----------------|
| | TIME hr mi | in kW Forw. | Power in kW Ref. | | | | VSWR | V _a mV | V _b mV | ohm | | |
| 12-Apr | 13 15 | 0.0 | 0.0 | 0.00 | 212.6 | 7.0 | 8.9 | 80 | ERR | ERR | ERR | ERR |
| 12-Apr | 13 27 | 0.0 | 0.0 | 0.00 | 212.8 | 7.0 | 8.9 | 79 | ERR | ERR | ERR | ERR |
| 12-Apr | 13 28 | 47.5 | 6.0 | 41.50 | 212.8 | 7.0 | 8.9 | 79 | 2.1 | 29.3 | 13.0 | -39.0 |
| 12-Apr | 15 47 | 47.5 | 6.2 | 41.30 | 215.1 | 7.1 | 9.0 | 80 | 2.1 | 29.1 | 12.9 | -39.5 |
| 12-Apr | 18 10 | 46.5 | 6.2 | 40.30 | 217.5 | 7.2 | 9.1 | 80 | 2.2 | 29.5 | 12.8 | -39.6 |
| 12-Apr | 19 42 | 46.0 | 6.0 | 40.00 | 219.0 | 7.3 | 9.1 | 80 | 2.1 | ERR | ERR | ERR |
| 12-Apr | 19 43 | 0.0 | 0.0 | 0.00 | 219.1 | 7.3 | 9.1 | 80 | ERR | ERR | ERR | ERR |
| 12-Apr | 19 46 | 0.0 | 0.0 | 0.00 | 219.1 | 7.3 | 9.1 | 80 | ERR | ERR | ERR | ERR |
| 12-Apr | 19 47 | 47.0 | 6.2 | 40.80 | 219.1 | 7.3 | 9.1 | 80 | 2.1 | 30.2 | 12.8 | 75.5 |
| 12-Apr | 22 0 | 47.0 | 6.2 | 40.80 | 221.3 | 7.4 | 9.2 | 80 | 2.1 | 30.5 | 12.8 | -40.0 |
| 12-Apr | 23 47 | 48.0 | 6.5 | 41.50 | 223.1 | 7.5 | 9.3 | 80 | 2.2 | 30.5 | 12.8 | -39.8 |
| 13-Apr | 2 0 | 48.0 | 6.2 | 41.80 | 225.3 | 7.6 | 9.4 | 81 | 2.1 | 30.5 | 12.8 | 76.2 |
| 13-Apr | 4 0 | 48.0 | 6.2 | 41.80 | 227.3 | 7.7 | 9.5 | 81 | 2.1 | 30.5 | 12.8 | -39.9 |
| 13-Apr | 5 59 | 48.0 | 6.2 | 41.80 | 229.3 | 7.7 | 9.6 | 81 | 2.1 | 30.5 | 12.7 | 76.8 |
| 13-Apr | 6 0 | 0.0 | 0.0 | 0.00 | 229.3 | 7.6 | 9.6 | 79 | ERR | ERR | ERR | ERR |
| 13-Apr | 6 5 | 0.0 | 0.0 | 0.00 | 229.4 | 7.6 | 9.6 | 80 | ERR | ERR | ERR | ERR |
| 13-Apr | 6 6 | 48.0 | 6.2 | 41.80 | 229.4 | 7.8 | 9.6 | 81 | 2.1 | 30.5 | 12.7 | 76.8 |
| 13-Apr | 6 10 | 48.0 | 6.2 | 41.80 | 229.5 | 7.8 | 9.6 | 81 | 2.1 | 30.0 | 12.2 | -39.5 |
| 13-Apr | 14 4 | 48.0 | 6.5 | 41.50 | 237.4 | 8.1 | 9.9 | 82 | 2.2 | 30.5 | 12.2 | 78.6 |
| 13-Apr | 14 5 | 0.0 | 0.0 | 0.00 | 237.4 | 8.1 | 9.9 | 82 | ERR | ERR | ERR | ERR |
| 13-Apr | 14 11 | 0.0 | 0.0 | 0.00 | 237.5 | 8.1 | 9.9 | 82 | ERR | ERR | ERR | ERR |
| 13-Apr | 14 12 | 48.0 | 6.5 | 41.50 | 237.5 | 8.1 | 9.9 | 82 | 2.2 | 30.5 | 12.3 | -39.6 |
| 13-Apr | 16 2 | 47.0 | 6.5 | 40.50 | 239.4 | 8.2 | 10.0 | 82 | 2.2 | 30.5 | 12.1 | 79.3 |
| 13-Apr | 20 52 | 46.5 | 6.5 | 40.00 | 244.2 | 8.4 | 10.2 | 82 | 2.2 | 30.5 | 12.1 | 80.6 |
| 13-Apr | 20 53 | 0.0 | 0.0 | 0.00 | 244.2 | 8.4 | 10.2 | 82 | ERR | ERR | ERR | ERR |
| 13-Apr | 20 57 | 0.0 | 0.0 | 0.00 | 244.3 | 8.4 | 10.2 | 82 | ERR | ERR | ERR | ERR |
| 13-Apr | 20 58 | 46.5 | 6.5 | 40.00 | 244.3 | 8.4 | 10.2 | 82 | 2.2 | 30.8 | 12.0 | 82.1 |
| 14-Apr | 0 0 | 46.5 | 6.5 | 40.00 | 247.3 | 8.4 | 10.3 | 82 | 2.2 | 30.8 | 12.0 | -38.3 |
| | | | | | | | | | | | | 64.4 |
| | | | | | | | | | | | | 50.9 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days at 40 kW | Source Utilization % | VSWR | Vector Voltmeter Va mV | Vb mV | Z ohm | Angle degree | $\frac{Z}{\sqrt{2}}$ Real Imaginary |
|--------|----------------|-------|------|----------------------|-----------------------|----------------------------|--------------------------|----------------------------|------|------------------------------|----------|----------|-----------------|---|
| | TIME hr mi | Forw. | Ref. | | | | | | | | | | | |
| 14-Apr | 2 0 | 46.5 | 6.5 | 40.00 | 249.3 | 8.6 | 10.4 | 83 | 2.2 | 31.0 | 12.0 | 82.6 | -38.2 | 64.9 |
| 14-Apr | 2 1 | 0.0 | 0.0 | 0.00 | 249.4 | 8.5 | 10.4 | 82 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 2 8 | 0.0 | 0.0 | 0.00 | 249.5 | 8.6 | 10.4 | 83 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 2 9 | 46.5 | 6.5 | 40.00 | 249.5 | 8.5 | 10.4 | 82 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 4 59 | 46.5 | 6.5 | 40.00 | 252.3 | 8.7 | 10.5 | 82 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 5 0 | 0.0 | 0.0 | 0.00 | 252.3 | 8.5 | 10.5 | 81 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 5 6 | 0.0 | 0.0 | 0.00 | 252.4 | 8.7 | 10.5 | 82 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 5 7 | 46.5 | 6.5 | 40.00 | 252.5 | 8.6 | 10.5 | 81 | 2.2 | 30.9 | 12.0 | 82.3 | -37.4 | 65.4 |
| 14-Apr | 9 49 | 47.0 | 6.3 | 40.70 | 257.2 | 8.8 | 10.7 | 82 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 9 50 | 0.0 | 0.0 | 0.00 | 257.2 | 8.7 | 10.7 | 81 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 9 57 | 0.0 | 0.0 | 0.00 | 257.3 | 8.8 | 10.7 | 82 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 9 58 | 47.0 | 6.3 | 40.70 | 257.3 | 8.7 | 10.7 | 81 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 19 20 | 47.0 | 6.3 | 40.70 | 266.7 | 9.0 | 11.1 | 81 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 19 21 | 0.0 | 0.0 | 0.00 | 266.7 | 8.9 | 11.1 | 80 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 19 25 | 0.0 | 0.0 | 0.00 | 266.8 | 9.0 | 11.1 | 81 | ERR | ERR | ERR | ERR | ERR | ERR |
| 14-Apr | 19 26 | 47.0 | 6.3 | 40.70 | 266.8 | 8.9 | 11.1 | 80 | 2.2 | 32.2 | 12.0 | 85.8 | -35.6 | 69.8 |
| 15-Apr | 0 0 | 48.0 | 7.0 | 41.00 | 271.3 | 9.1 | 11.3 | 80 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 3 59 | 48.0 | 7.0 | 41.00 | 275.3 | 9.4 | 11.5 | 82 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 4 0 | 0.0 | 0.0 | 0.00 | 275.3 | 9.1 | 11.5 | 80 | ERR | 32.1 | 12.0 | 85.5 | -35.4 | 69.7 |
| 15-Apr | 4 4 | 0.0 | 0.0 | 0.00 | 275.4 | 9.4 | 11.5 | 82 | ERR | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 4 5 | 48.0 | 7.0 | 41.00 | 275.4 | 9.1 | 11.5 | 80 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 10 15 | 52.0 | 7.3 | 44.70 | 281.6 | 9.6 | 11.7 | 82 | 2.2 | 32.0 | 11.5 | 89.0 | -36.3 | 71.7 |
| 15-Apr | 11 2 | 52.0 | 7.3 | 44.70 | 282.4 | 9.5 | 11.8 | 80 | 2.2 | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 11 3 | 0.0 | 0.0 | 0.00 | 282.4 | 9.6 | 11.8 | 81 | ERR | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 11 10 | 0.0 | 0.0 | 0.00 | 282.5 | 9.5 | 11.8 | 80 | ERR | ERR | ERR | ERR | ERR | ERR |
| 15-Apr | 11 11 | 50.0 | 7.3 | 42.70 | 282.5 | 9.6 | 11.8 | 81 | 2.2 | 32.0 | 11.4 | 89.8 | -35.6 | 73.0 |
| 15-Apr | 20 18 | 49.0 | 7.4 | 41.60 | 291.6 | 9.7 | 12.2 | 79 | 2.3 | 32.1 | 11.2 | 91.7 | -34.9 | 75.2 |
| 15-Apr | 20 19 | 0.0 | 0.0 | 0.00 | 291.7 | 9.8 | 12.2 | 81 | ERR | ERR | ERR | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days at Source Utilization % | Vector Voltmeter Va mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|----------------|---------------|-----------------------|----------------------------|---|------------------------------|----------|-----------------|-----------|----------------|
| | TIME hr mi | Input in.kW | Ref. Forw. | | | | | | | | |
| 15-Apr | 20 22 | 0.0 | 0.0 | 291.7 | 9.7 | 12.2 | 79 | ERR | ERR | ERR | ERR |
| 15-Apr | 20 23 | 49.0 | 7.4 | 41.60 | 291.7 | 9.8 | 61 | 2.3 | 92.0 | -34.7 | 75.6 |
| 15-Apr | 21 40 | 49.0 | 7.4 | 41.60 | 293.0 | 9.7 | 79 | 2.3 | 32.5 | 11.3 | 52.4 |
| 16-Apr | 0 0 | 48.0 | 7.5 | 40.50 | 295.3 | 9.9 | 81 | 2.3 | 33.0 | 11.7 | 51.3 |
| 16-Apr | 2 0 | 48.5 | 7.5 | 41.00 | 297.3 | 9.9 | 80 | 2.3 | 33.2 | 11.7 | 51.5 |
| 16-Apr | 4 0 | 48.0 | 7.5 | 40.50 | 299.3 | 10.1 | 81 | 2.3 | 33.2 | 11.7 | 51.0 |
| 16-Apr | 6 0 | 50.0 | 7.5 | 42.50 | 301.3 | 10.1 | 80 | 2.3 | 33.3 | 11.7 | 51.3 |
| 16-Apr | 7 10 | 49.5 | 7.6 | 41.90 | 302.5 | 10.3 | 81 | 2.3 | 33.8 | 11.5 | 52.6 |
| 16-Apr | 10 0 | 51.5 | 7.9 | 43.60 | 305.3 | 10.2 | 80 | 2.3 | 94.0 | -34.0 | 77.9 |
| 16-Apr | 13 3 | 0.0 | 0.0 | 308.4 | 10.4 | 12.8 | 81 | ERR | ERR | ERR | ERR |
| 16-Apr | 13 14 | 0.0 | 0.0 | 308.6 | 10.3 | 12.9 | 80 | ERR | ERR | ERR | ERR |
| 16-Apr | 13 15 | 50.0 | 8.0 | 42.00 | 308.6 | 10.4 | 12.9 | 81 | 2.3 | 33.0 | 11.0 |
| 16-Apr | 19 4 | 0.0 | 0.0 | 314.4 | 10.3 | 13.1 | 79 | ERR | ERR | ERR | ERR |
| 16-Apr | 19 13 | 0.0 | 0.0 | 314.6 | 10.5 | 13.1 | 80 | ERR | ERR | ERR | ERR |
| 16-Apr | 19 14 | 51.0 | 8.1 | 42.90 | 314.6 | 10.3 | 13.1 | 79 | 2.3 | 33.9 | 11.2 |
| 16-Apr | 21 35 | 50.0 | 8.0 | 42.00 | 316.9 | 10.6 | 13.2 | 80 | 2.3 | 34.0 | 11.0 |
| 16-Apr | 23 2 | 0.0 | 0.0 | 318.4 | 10.4 | 13.3 | 78 | ERR | ERR | ERR | ERR |
| 17-Apr | 0 14 | 0.0 | 0.0 | 319.6 | 10.6 | 13.3 | 80 | ERR | ERR | ERR | ERR |
| 17-Apr | 0 15 | 50.0 | 8.5 | 41.50 | 319.6 | 10.4 | 13.3 | 78 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 2 0 | 50.0 | 8.5 | 41.50 | 321.3 | 10.7 | 13.4 | 80 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 8 20 | 52.0 | 8.8 | 43.20 | 327.7 | 10.8 | 13.7 | 79 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 14 20 | 52.5 | 9.0 | 43.50 | 333.7 | 11.2 | 13.9 | 81 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 16 5 | 52.0 | 9.0 | 43.00 | 335.4 | 11.1 | 14.0 | 80 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 17 4 | 52.0 | 9.0 | 43.00 | 336.4 | 11.3 | 14.0 | 81 | 2.4 | 33.2 | 11.7 |
| 17-Apr | 17 5 | 0.0 | 0.0 | 336.4 | 11.1 | 14.0 | 80 | ERR | ERR | ERR | ERR |
| 17-Apr | 21 39 | 0.0 | 0.0 | 341.0 | 11.4 | 14.2 | 80 | ERR | ERR | ERR | ERR |
| 17-Apr | 21 40 | 52.0 | 9.0 | 43.00 | 341.0 | 11.2 | 14.2 | 79 | 2.4 | 35.0 | 11.1 |
| 18-Apr | 0 5 | 52.0 | 9.0 | 43.00 | 343.4 | 11.5 | 14.3 | 80 | 2.4 | 35.0 | 11.0 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array in kW | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Source Utilization % | Vector Voltmeter V _a mV | Vector Voltmeter V _b mV | Z ohm | Z Real Imaginary | |
|--------|---------------|-------------------------|----------------------|-----------------------|----------------------------|----------------------------|--|--|----------|---------------------|-----------------|
| | | | | | | | | | | VSWR | Angle degree |
| 18-Apr | 0 6 | 0.0 | 0.0 | 343.4 | 11.3 | 14.3 | 79 | ERR | ERR | ERR | ERR |
| 18-Apr | 1 38 | 0.0 | 0.0 | 345.0 | 11.5 | 14.4 | 80 | ERR | ERR | ERR | ERR |
| 18-Apr | 1 39 | 52.0 | 9.0 | 43.00 | 345.0 | 11.3 | 14.4 | 79 | 2.4 | 35.0 | 11.0 |
| 18-Apr | 10 10 | 52.5 | 9.5 | 43.00 | 353.5 | 11.7 | 14.7 | 80 | 2.5 | 35.0 | 11.1 |
| 18-Apr | 12 25 | 54.0 | 9.9 | 44.10 | 355.8 | 11.8 | 14.8 | 80 | 2.5 | 34.6 | 11.2 |
| 18-Apr | 20 1 | 53.0 | 10.0 | 43.00 | 363.4 | 12.2 | 15.1 | 80 | 2.5 | 35.5 | 11.0 |
| 18-Apr | 22 36 | 52.0 | 10.0 | 42.00 | 365.9 | 12.3 | 15.2 | 81 | 2.6 | 36.0 | 11.0 |
| 19-Apr | 1 20 | 52.0 | 10.0 | 42.00 | 368.7 | 12.4 | 15.4 | 81 | 2.6 | 36.0 | 11.0 |
| 19-Apr | 6 30 | 54.0 | 10.0 | 44.00 | 373.8 | 12.6 | 15.6 | 81 | 2.5 | 36.0 | 11.0 |
| 19-Apr | 13 15 | 56.0 | 11.0 | 45.00 | 380.6 | 12.9 | 15.9 | 82 | 2.6 | 35.9 | 10.4 |
| 19-Apr | 13 16 | 0.0 | 0.0 | 380.6 | 12.8 | 15.9 | 81 | ERR | ERR | ERR | ERR |
| 19-Apr | 14 34 | 0.0 | 0.0 | 381.9 | 13.0 | 15.9 | 81 | ERR | ERR | ERR | ERR |
| 19-Apr | 14 35 | 54.0 | 11.0 | 43.00 | 381.9 | 12.8 | 15.9 | 81 | 2.6 | 35.5 | 10.4 |
| 19-Apr | 18 23 | 55.0 | 11.0 | 44.00 | 385.7 | 13.0 | 16.1 | 81 | 2.6 | 35.5 | 10.4 |
| 19-Apr | 19 13 | 55.0 | 11.0 | 44.00 | 386.6 | 13.0 | 16.1 | 81 | 2.6 | 35.5 | 10.4 |
| 19-Apr | 19 14 | 0.0 | 0.0 | 386.6 | 13.1 | 16.1 | 81 | ERR | ERR | ERR | ERR |
| 19-Apr | 19 25 | 0.0 | 0.0 | 386.8 | 13.0 | 16.1 | 81 | ERR | ERR | ERR | ERR |
| 19-Apr | 19 26 | 55.0 | 11.2 | 43.80 | 386.8 | 13.1 | 16.1 | 81 | 2.6 | 36.1 | 10.4 |
| 19-Apr | 22 27 | 54.0 | 11.2 | 42.80 | 389.8 | 13.1 | 16.2 | 81 | 2.7 | 37.1 | 10.4 |
| 20-Apr | 8 30 | 56.0 | 12.0 | 44.00 | 399.8 | 13.7 | 16.7 | 82 | 2.7 | 37.5 | 10.0 |
| 20-Apr | 13 34 | 57.0 | 12.3 | 44.70 | 404.9 | 13.8 | 16.9 | 82 | 2.7 | 37.5 | 10.0 |
| 20-Apr | 13 35 | 0.0 | 0.0 | 404.9 | 13.8 | 16.9 | 82 | ERR | ERR | ERR | ERR |
| 20-Apr | 13 44 | 0.0 | 0.0 | 405.1 | 13.8 | 16.9 | 82 | ERR | ERR | ERR | ERR |
| 20-Apr | 13 45 | 57.0 | 12.5 | 44.50 | 405.1 | 13.8 | 16.9 | 82 | 2.8 | 37.9 | 11.1 |
| 20-Apr | 19 50 | 56.0 | 12.8 | 43.20 | 411.2 | 13.9 | 17.1 | 81 | 2.8 | 38.3 | 11.0 |
| 20-Apr | 19 51 | 0.0 | 0.0 | 411.2 | 13.9 | 17.1 | 81 | ERR | ERR | ERR | ERR |
| 20-Apr | 20 29 | 0.0 | 0.0 | 411.8 | 13.9 | 17.2 | 81 | ERR | ERR | ERR | ERR |
| 20-Apr | 20 30 | 57.0 | 13.0 | 44.00 | 411.8 | 13.9 | 17.2 | 81 | 2.8 | 38.5 | 11.0 |
| | | | | | | | | | | -31.9 | -31.9 |
| | | | | | | | | | | 95.0 | 95.0 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array in kW | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days Utilization % | Source VSWR | Vector Voltmeter Va mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|---------------|-------------------------|----------------------|-----------------------|-------------------------|-------------------------------|----------------|------------------------------|----------|-----------------|-----------|----------------|
| | | | | | | | | | | | ERR | ERR |
| 20-Apr | 21 39 | 57.0 | 13.0 | 44.00 | 413.0 | 14.0 | 17.2 | 81 | 2.8 | ERR | ERR | ERR |
| 20-Apr | 21 40 | 0.0 | 0.0 | 0.00 | 413.0 | 14.0 | 17.2 | 81 | ERR | ERR | ERR | ERR |
| 21-Apr | 0 54 | 0.0 | 0.0 | 0.00 | 416.2 | 14.0 | 17.3 | 81 | ERR | ERR | ERR | 67.6 |
| 21-Apr | 0 55 | 58.0 | 13.0 | 45.00 | 416.3 | 14.1 | 17.3 | 81 | 2.8 | 39.1 | 10.0 | -32.7 |
| 21-Apr | 6 0 | 58.6 | 13.0 | 45.60 | 421.3 | 14.2 | 17.6 | 81 | 2.8 | 39.0 | 11.0 | -38.1 |
| 21-Apr | 11 19 | 58.0 | 13.0 | 45.00 | 426.7 | 14.5 | 17.8 | 82 | 2.8 | ERR | ERR | ERR |
| 21-Apr | 11 20 | 0.0 | 0.0 | 0.00 | 426.7 | 14.3 | 17.8 | 80 | ERR | ERR | ERR | ERR |
| 21-Apr | 16 29 | 0.0 | 0.0 | 0.00 | 431.8 | 14.7 | 18.0 | 81 | ERR | ERR | ERR | ERR |
| 21-Apr | 16 30 | 56.0 | 13.0 | 43.00 | 431.8 | 14.4 | 18.0 | 80 | 2.9 | 38.1 | 9.7 | -38.5 |
| 21-Apr | 19 43 | 57.5 | 13.5 | 44.00 | 435.1 | 14.7 | 18.1 | 81 | 2.9 | 39.0 | 9.9 | -38.8 |
| 21-Apr | 19 59 | 57.5 | 13.5 | 44.00 | 435.3 | 14.6 | 18.1 | 80 | 2.9 | ERR | ERR | ERR |
| 21-Apr | 20 0 | 0.0 | 0.0 | 0.00 | 435.3 | 14.7 | 18.1 | 81 | ERR | ERR | ERR | ERR |
| 21-Apr | 23 59 | 0.0 | 0.0 | 0.00 | 439.3 | 14.7 | 18.3 | 80 | ERR | ERR | ERR | ERR |
| 21-Apr | 0 0 | 60.0 | 14.0 | 46.00 | 415.3 | 14.3 | 17.3 | 82 | 2.9 | 40.0 | 10.0 | -38.5 |
| 22-Apr | 9 15 | 56.0 | 13.5 | 42.50 | 448.6 | 14.9 | 18.7 | 80 | 2.9 | 38.0 | 9.6 | 100.1 |
| 22-Apr | 10 40 | 55.0 | 13.4 | 41.60 | 450.0 | 15.8 | 18.8 | 84 | 2.9 | 37.5 | 9.4 | 127.9 |
| 22-Apr | 13 27 | 55.0 | 13.4 | 41.60 | 452.8 | 15.1 | 18.9 | 80 | 2.9 | 38.0 | 9.6 | -40.7 |
| 22-Apr | 13 28 | 0.0 | 0.0 | 0.00 | 452.8 | 15.9 | 18.9 | 84 | ERR | ERR | ERR | ERR |
| 22-Apr | 18 9 | 0.0 | 0.0 | 0.00 | 457.5 | 15.2 | 19.1 | 79 | ERR | ERR | ERR | ERR |
| 22-Apr | 18 10 | 60.0 | 15.0 | 45.00 | 457.5 | 16.0 | 19.1 | 84 | 3.0 | 39.5 | 9.7 | -38.5 |
| 23-Apr | 1 30 | 60.0 | 15.0 | 45.00 | 464.8 | 15.3 | 19.4 | 79 | 3.0 | 41.0 | 10.0 | 127.6 |
| 23-Apr | 9 40 | 65.0 | 16.6 | 48.40 | 473.0 | 16.8 | 19.7 | 85 | 3.0 | 40.0 | 10.0 | -41.0 |
| 23-Apr | 12 19 | 65.0 | 16.6 | 48.40 | 475.7 | 15.9 | 19.8 | 80 | 3.0 | ERR | ERR | ERR |
| 23-Apr | 12 20 | 0.0 | 0.0 | 0.00 | 475.7 | 16.8 | 19.8 | 85 | ERR | ERR | ERR | ERR |
| 23-Apr | 13 19 | 0.0 | 0.0 | 0.00 | 476.7 | 15.9 | 19.9 | 80 | ERR | ERR | ERR | ERR |
| 23-Apr | 13 20 | 61.0 | 16.0 | 45.00 | 476.7 | 16.9 | 19.9 | 85 | 3.1 | 39.5 | 9.6 | -42.7 |
| 24-Apr | 0 10 | 64.0 | 17.5 | 46.50 | 487.5 | 16.1 | 20.3 | 79 | 3.2 | 41.9 | 10.0 | 131.6 |
| 24-Apr | 0 59 | 64.0 | 17.5 | 46.50 | 488.3 | 17.4 | 20.3 | 86 | 3.2 | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME | | Power at Array in kW | Input Power Ref. in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Source Days Utilization % | VSWR | Vector Voltmeter | | Angle degree | Z Real | Z Imaginary |
|--------|------|----|-------------------------|------------------------------|--------------------------|-------------------------------|---|------|----------------------|----------------------|-----------------|-----------|----------------|
| | hr | mi | | | | | | | V _b mV | V _a mV | | | |
| 24-Apr | 1 | 0 | 0.0 | 0.0 | 488.3 | 16.2 | 20.3 | 79 | ERR | ERR | ERR | ERR | ERR |
| 24-Apr | 1 | 54 | 0.0 | 0.0 | 489.2 | 17.4 | 20.4 | 86 | ERR | ERR | ERR | ERR | ERR |
| 24-Apr | 1 | 55 | 64.0 | 17.5 | 46.50 | 489.3 | 16.2 | 20.4 | 79 | 3.2 | ERR | ERR | ERR |
| 24-Apr | 13 | 4 | 64.0 | 17.9 | 46.10 | 500.4 | 17.7 | 20.9 | 85 | 3.2 | ERR | ERR | ERR |
| 24-Apr | 13 | 5 | 0.0 | 0.0 | 500.4 | 16.5 | 20.9 | 79 | ERR | ERR | ERR | ERR | ERR |
| 24-Apr | 13 | 29 | 0.0 | 0.0 | 500.8 | 17.7 | 20.9 | 85 | ERR | ERR | ERR | ERR | ERR |
| 24-Apr | 13 | 30 | 66.0 | 18.5 | 47.50 | 500.8 | 16.5 | 20.9 | 79 | 3.3 | 134.4 | -46.1 | 96.9 |
| 24-Apr | 22 | 34 | 64.0 | 18.2 | 45.80 | 509.9 | 17.9 | 21.2 | 84 | 3.3 | 42.0 | 9.8 | 137.1 |
| 25-Apr | 2 | 39 | 64.0 | 18.5 | 45.50 | 514.0 | 17.1 | 21.4 | 80 | 3.3 | ERR | ERR | ERR |
| 25-Apr | 2 | 40 | 0.0 | 0.0 | 514.0 | 18.0 | 21.4 | 84 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 2 | 49 | 0.0 | 0.0 | 514.2 | 17.1 | 21.4 | 80 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 2 | 50 | 62.0 | 18.5 | 43.50 | 514.2 | 18.0 | 21.4 | 84 | 3.4 | ERR | ERR | ERR |
| 25-Apr | 9 | 34 | 64.0 | 19.0 | 45.00 | 520.9 | 17.3 | 21.7 | 80 | 3.4 | 41.8 | 9.9 | 135.0 |
| 25-Apr | 9 | 35 | 0.0 | 0.0 | 520.9 | 18.2 | 21.7 | 84 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 11 | 54 | 0.0 | 0.0 | 523.2 | 17.3 | 21.8 | 79 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 11 | 55 | 65.0 | 19.1 | 45.90 | 523.3 | 18.2 | 21.8 | 84 | 3.4 | 41.9 | 10.0 | 134.0 |
| 25-Apr | 20 | 44 | 65.0 | 19.2 | 45.80 | 532.1 | 17.5 | 22.2 | 79 | 3.4 | 41.0 | 10.0 | 131.1 |
| 25-Apr | 20 | 45 | 0.0 | 0.0 | 532.1 | 18.5 | 22.2 | 83 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 21 | 33 | 0.0 | 0.0 | 532.9 | 17.5 | 22.2 | 79 | ERR | ERR | ERR | ERR | ERR |
| 25-Apr | 21 | 34 | 65.0 | 19.2 | 45.80 | 532.9 | 18.5 | 22.2 | 83 | 3.4 | ERR | ERR | ERR |
| 26-Apr | 0 | 9 | 66.0 | 20.0 | 46.00 | 535.5 | 17.6 | 22.3 | 79 | 3.4 | ERR | ERR | ERR |
| 26-Apr | 0 | 10 | 0.0 | 0.0 | 535.5 | 18.5 | 22.3 | 83 | ERR | ERR | ERR | ERR | ERR |
| 26-Apr | 1 | 29 | 0.0 | 0.0 | 536.8 | 17.6 | 22.4 | 79 | ERR | ERR | ERR | ERR | ERR |
| 26-Apr | 1 | 30 | 66.0 | 20.0 | 46.00 | 536.8 | 18.6 | 22.4 | 83 | 3.4 | ERR | ERR | ERR |
| 26-Apr | 12 | 55 | 69.0 | 21.0 | 48.00 | 548.3 | 17.9 | 22.8 | 78 | 3.5 | 43.5 | 14.1 | 98.7 |
| 26-Apr | 14 | 11 | 69.0 | 21.0 | 48.00 | 549.5 | 19.2 | 22.9 | 84 | 3.5 | ERR | ERR | -39.5 |
| 26-Apr | 14 | 12 | 0.0 | 0.0 | 549.5 | 18.0 | 22.9 | 78 | ERR | ERR | ERR | ERR | 62.8 |
| 26-Apr | 14 | 21 | 0.0 | 0.0 | 549.7 | 19.2 | 22.9 | 84 | ERR | ERR | ERR | ERR | 76.1 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days at 40 kW | Source Utilization % | VSWR | Vector Voltmeter | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|-------------------------|---------------|--------------------------|----------------------------|----------------------------|------|------------------|----------|-----------------|-----------|----------------|
| | TIME hr mi | Input Power in kW | Ref. Forw. | | | | | | | | | |
| 26-Apr | 14 22 | 67.0 | 21.0 | 46.00 | 549.7 | 18.0 | 22.9 | 78 | 3.5 | 42.5 | 14.2 | 95.7 |
| 26-Apr | 20 0 | 67.0 | 21.0 | 46.00 | 555.3 | 19.3 | 23.1 | 84 | 3.5 | 42.8 | 13.7 | 99.9 |
| 26-Apr | 20 1 | 0.0 | 0.0 | 0.00 | 555.4 | 18.1 | 23.1 | 78 | ERR | ERR | ERR | -40.4 |
| 26-Apr | 21 4 | 0.0 | 0.0 | 0.00 | 556.4 | 19.4 | 23.2 | 83 | ERR | ERR | ERR | ERR |
| 26-Apr | 21 5 | 67.0 | 21.0 | 46.00 | 556.4 | 18.1 | 23.2 | 78 | 3.5 | ERR | ERR | ERR |
| 26-Apr | 21 45 | 68.0 | 22.0 | 46.00 | 557.1 | 19.4 | 23.2 | 83 | 3.6 | 42.8 | 13.5 | 101.4 |
| 27-Apr | 3 0 | 67.0 | 22.0 | 45.00 | 562.3 | 18.4 | 23.4 | 79 | 3.7 | 44.0 | 14.0 | 100.5 |
| 27-Apr | 12 30 | 70.0 | 23.6 | 46.40 | 571.8 | 20.1 | 23.8 | 84 | 3.8 | 45.5 | 10.5 | 138.6 |
| 27-Apr | 14 29 | 70.0 | 23.6 | 46.40 | 573.8 | 18.9 | 23.9 | 79 | 3.8 | ERR | ERR | ERR |
| 27-Apr | 14 30 | 0.0 | 0.0 | 0.00 | 573.8 | 20.1 | 23.9 | 84 | ERR | ERR | ERR | ERR |
| 27-Apr | 14 39 | 0.0 | 0.0 | 0.00 | 574.0 | 19.0 | 23.9 | 79 | ERR | ERR | ERR | ERR |
| 27-Apr | 14 40 | 70.0 | 29.0 | 41.00 | 574.0 | 20.1 | 23.9 | 84 | 4.6 | 45.1 | 10.5 | 137.4 |
| 27-Apr | 20 25 | 70.0 | 29.0 | 41.00 | 579.8 | 19.1 | 24.2 | 79 | 4.6 | 45.0 | 10.5 | 137.1 |
| 28-Apr | 6 35 | 72.0 | 29.5 | 42.50 | 589.9 | 20.8 | 24.6 | 85 | 4.6 | 45.6 | 10.5 | 138.9 |
| 28-Apr | 11 4 | 72.0 | 29.5 | 42.50 | 594.4 | 19.7 | 24.8 | 80 | 4.6 | ERR | ERR | ERR |
| 28-Apr | 11 5 | 0.0 | 0.0 | 0.00 | 594.4 | 20.9 | 24.8 | 84 | ERR | ERR | ERR | ERR |
| 28-Apr | 11 54 | 0.0 | 0.0 | 0.00 | 595.2 | 19.7 | 24.8 | 80 | ERR | ERR | ERR | ERR |
| 28-Apr | 11 55 | 72.0 | 29.5 | 42.50 | 595.3 | 20.9 | 24.8 | 84 | 4.6 | ERR | ERR | ERR |
| 28-Apr | 22 35 | 76.0 | 32.0 | 44.00 | 605.9 | 20.0 | 25.2 | 79 | 4.7 | 46.3 | 10.9 | 135.8 |
| 29-Apr | 1 0 | 75.0 | 32.5 | 42.50 | 608.3 | 21.5 | 25.3 | 85 | 4.9 | 46.2 | 11.0 | 134.3 |
| 29-Apr | 14 30 | 77.0 | 33.0 | 44.00 | 621.8 | 20.7 | 25.9 | 80 | 4.8 | 46.4 | 11.1 | 133.7 |
| 29-Apr | 18 30 | 80.0 | 35.0 | 45.00 | 625.8 | 22.3 | 26.1 | 86 | 4.9 | 48.0 | 11.6 | 132.3 |
| 30-Apr | 0 35 | 80.0 | 35.0 | 45.00 | 631.9 | 21.2 | 26.3 | 80 | 4.9 | 48.0 | 11.9 | 129.0 |
| 30-Apr | 7 50 | 83.0 | 36.1 | 46.90 | 639.2 | 23.0 | 26.6 | 86 | 4.9 | 48.4 | 12.4 | 124.8 |
| 30-Apr | 10 59 | 83.0 | 36.1 | 46.90 | 642.3 | 21.7 | 26.8 | 81 | 4.9 | ERR | ERR | ERR |
| 30-Apr | 11 0 | 0.0 | 0.0 | 0.00 | 642.3 | 23.0 | 26.8 | 86 | ERR | ERR | ERR | ERR |
| 30-Apr | 13 34 | 0.0 | 0.0 | 0.00 | 644.9 | 21.7 | 26.9 | 81 | ERR | ERR | ERR | ERR |
| 30-Apr | 13 35 | 37.0 | 0.4 | 36.60 | 644.9 | 23.1 | 26.9 | 86 | 1.2 | 21.0 | 14.5 | 46.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days Utilization % | Source VSWR | Vector Voltmeter Va mV | Z ohm | Angle degree | $\frac{Z}{R}$ Real | $\frac{Z}{I}$ Imaginary |
|--------|----------------|-------|-------|-------------------|--------------------|----------------------|----------------------------|-------------|------------------------|-------|--------------|--------------------|-------------------------|
| | TIME hr mi | Forw. | Rell. | | | | | | | | | | |
| 30-Apr | 21 30 | 38.0 | 0.3 | 37.70 | 652.8 | 21.9 | 27.2 | 80 | 1.2 | 20.5 | 46.8 | 0.2 | 46.8 |
| 1-May | 1 0 | 37.0 | 0.3 | 36.70 | 656.3 | 23.5 | 27.3 | 86 | 1.2 | 20.0 | 45.7 | 0.2 | 45.7 |
| 1-May | 7 50 | 40.0 | 0.4 | 39.60 | 663.2 | 22.3 | 27.6 | 81 | 1.2 | 20.0 | 44.5 | 0.8 | 44.1 |
| 1-May | 10 49 | 40.0 | 0.4 | 39.60 | 666.2 | 23.9 | 27.8 | 86 | 1.2 | 20.0 | 44.1 | 0.8 | 44.1 |
| 1-May | 10 50 | 0.0 | 0.0 | 0.00 | 666.2 | 22.4 | 27.8 | 81 | ERR | ERR | ERR | ERR | ERR |
| 1-May | 11 9 | 0.0 | 0.0 | 0.00 | 666.5 | 23.9 | 27.8 | 86 | ERR | ERR | ERR | ERR | ERR |
| 1-May | 11 10 | 39.0 | 0.6 | 38.40 | 666.5 | 22.4 | 27.8 | 81 | 1.3 | 19.6 | 42.9 | 1.0 | 42.9 |
| 1-May | 14 29 | 39.0 | 0.6 | 38.40 | 669.8 | 24.0 | 27.9 | 86 | 1.3 | 19.4 | 42.8 | 1.0 | 42.8 |
| 1-May | 14 30 | 0.0 | 0.0 | 0.00 | 669.8 | 22.4 | 27.9 | 80 | ERR | ERR | ERR | ERR | ERR |
| 1-May | 16 49 | 0.0 | 0.0 | 0.00 | 672.2 | 24.0 | 28.0 | 86 | ERR | ERR | ERR | ERR | ERR |
| 1-May | 16 50 | 40.0 | 5.0 | 35.00 | 672.2 | 22.5 | 28.0 | 80 | 2.1 | 20.2 | 15.9 | 30.0 | 35.2 |
| 2-May | 12 0 | 39.0 | 4.8 | 34.20 | 691.3 | 24.4 | 28.8 | 85 | 2.1 | 19.4 | 36.9 | 29.8 | 32.0 |
| 2-May | 21 47 | 43.0 | 5.8 | 37.20 | 701.1 | 23.6 | 29.2 | 81 | 2.2 | 20.2 | 19.2 | 33.6 | 71.8 |
| 3-May | 0 14 | 43.0 | 5.8 | 37.20 | 703.6 | 24.8 | 29.3 | 85 | 2.2 | ERR | ERR | ERR | ERR |
| 3-May | 0 15 | 0.0 | 0.0 | 0.00 | 703.6 | 23.6 | 29.3 | 81 | ERR | ERR | ERR | ERR | ERR |
| 3-May | 0 54 | 0.0 | 0.0 | 0.00 | 704.2 | 24.8 | 29.3 | 85 | ERR | ERR | ERR | ERR | ERR |
| 3-May | 0 55 | 44.0 | 6.0 | 38.00 | 704.3 | 23.6 | 29.3 | 81 | 2.2 | ERR | ERR | ERR | ERR |
| 3-May | 8 20 | 44.0 | 6.5 | 37.50 | 711.7 | 25.0 | 29.7 | 84 | 2.2 | 20.4 | 18.8 | 34.7 | 35.0 |
| 3-May | 15 4 | 44.0 | 6.3 | 37.75 | 718.4 | 24.2 | 29.9 | 81 | 2.2 | ERR | ERR | ERR | ERR |
| 3-May | 15 5 | 0.0 | 0.0 | 0.00 | 718.4 | 25.1 | 29.9 | 84 | ERR | ERR | ERR | ERR | ERR |
| 3-May | 15 19 | 0.0 | 0.0 | 0.00 | 718.7 | 24.2 | 29.9 | 81 | ERR | ERR | ERR | ERR | ERR |
| 3-May | 15 20 | 41.0 | 6.6 | 34.40 | 718.7 | 25.1 | 29.9 | 84 | 2.3 | 19.6 | 18.3 | 34.3 | 35.6 |
| 4-May | 6 59 | 42.0 | 6.5 | 35.50 | 734.3 | 24.5 | 30.6 | 80 | 2.3 | ERR | ERR | ERR | ERR |
| 4-May | 7 0 | 0.0 | 0.0 | 0.00 | 734.3 | 25.4 | 30.6 | 83 | ERR | ERR | ERR | ERR | ERR |
| 4-May | 7 34 | 0.0 | 0.0 | 0.00 | 734.9 | 24.5 | 30.6 | 80 | ERR | ERR | ERR | ERR | ERR |
| 4-May | 7 35 | 43.6 | 7.0 | 36.60 | 734.9 | 25.4 | 30.6 | 83 | 2.3 | 20.6 | 18.2 | 36.2 | 36.4 |
| 4-May | 18 18 | 44.0 | 7.7 | 36.30 | 745.6 | 24.7 | 31.1 | 80 | 2.4 | 20.9 | 18.5 | 36.1 | 29.1 |
| 4-May | 23 35 | 45.0 | 8.4 | 36.60 | 750.9 | 26.0 | 31.3 | 83 | 2.5 | 21.2 | 18.7 | 36.3 | 29.2 |
| | | | | | | | | | | | | 41.1 | 27.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array | | Input Power in kW | Elapsed Time hours | Equiv. Days at 40 kW | Elapsed Days at 40 kW | Source Utilization % | Vector Voltmeter | Z ohm | Angle degree | $\frac{Z}{R}$ Real | Z Imaginary |
|--------|---------------|----------------|------|----------------------|-----------------------|----------------------------|--------------------------|-------------------------|------------------|----------|-----------------|-----------------------|----------------|
| | | in kW | Ref. | | | | | | | | | | |
| 5-May | 11 5 | 48.0 | 8.9 | 39.10 | 762.4 | 25.4 | 31.8 | 80 | 2.5 | 21.0 | 19.0 | 35.3 | 45.0 |
| 5-May | 17 58 | 46.0 | 9.5 | 36.50 | 769.3 | 26.7 | 32.1 | 83 | 2.7 | 21.0 | 19.0 | 35.3 | 44.0 |
| 6-May | 1 30 | 47.0 | 10.8 | 36.20 | 776.8 | 25.9 | 32.4 | 80 | 2.8 | 21.2 | 20.2 | 33.6 | 47.0 |
| 6-May | 6 6 | 46.5 | 11.0 | 35.50 | 783.4 | 27.2 | 32.6 | 83 | 2.9 | 21.6 | 20.0 | 34.5 | 49.5 |
| 6-May | 22 37 | 48.0 | 12.6 | 35.40 | 798.0 | 26.7 | 33.2 | 80 | 3.1 | 21.9 | 20.6 | 34.0 | 47.0 |
| 7-May | 1 30 | 48.5 | 13.0 | 35.50 | 800.8 | 27.9 | 33.4 | 84 | 3.1 | 21.9 | 20.5 | 34.2 | 47.5 |
| 7-May | 7 6 | 48.5 | 13.0 | 35.50 | 806.4 | 27.0 | 33.6 | 80 | 3.1 | ERR | ERR | ERR | ERR |
| 7-May | 7 7 | 0.0 | 0.0 | 0.00 | 806.5 | 28.0 | 33.6 | 83 | ERR | ERR | ERR | ERR | ERR |
| 7-May | 7 29 | 0.0 | 0.0 | 0.00 | 806.8 | 27.0 | 33.6 | 80 | ERR | ERR | ERR | ERR | ERR |
| 7-May | 7 30 | 53.5 | 13.3 | 40.20 | 806.8 | 28.0 | 33.6 | 83 | 3.0 | 21.8 | 20.5 | 34.0 | 43.0 |
| 7-May | 20 28 | 53.0 | 14.0 | 39.00 | 819.8 | 27.3 | 34.2 | 80 | 3.1 | 21.7 | 21.0 | 33.0 | 42.0 |
| 8-May | 2 30 | 55.0 | 14.9 | 40.10 | 825.8 | 28.8 | 34.4 | 84 | 3.2 | 22.3 | 21.9 | 32.6 | 43.0 |
| 8-May | 6 59 | 55.0 | 15.0 | 40.00 | 830.3 | 27.7 | 34.6 | 80 | 3.2 | ERR | ERR | ERR | ERR |
| 8-May | 7 0 | 0.0 | 0.0 | 0.00 | 830.3 | 28.9 | 34.6 | 84 | ERR | ERR | ERR | ERR | ERR |
| 8-May | 10 44 | 0.0 | 0.0 | 0.00 | 834.1 | 27.8 | 34.8 | 80 | ERR | ERR | ERR | ERR | ERR |
| 8-May | 10 45 | 56.5 | 16.1 | 40.40 | 834.1 | 29.0 | 34.8 | 83 | 3.3 | 22.6 | 21.5 | 33.6 | 51.5 |
| 8-May | 14 54 | 56.5 | 16.1 | 40.40 | 838.2 | 27.9 | 34.9 | 80 | 3.3 | ERR | ERR | ERR | ERR |
| 8-May | 14 55 | 0.0 | 0.0 | 0.00 | 838.3 | 29.1 | 34.9 | 83 | ERR | ERR | ERR | ERR | ERR |
| 8-May | 15 36 | 0.0 | 0.0 | 0.00 | 838.9 | 27.9 | 35.0 | 80 | ERR | ERR | ERR | ERR | ERR |
| 8-May | 15 37 | 55.0 | 16.0 | 39.00 | 839.0 | 29.1 | 35.0 | 83 | 3.3 | 22.5 | 21.5 | 33.5 | 52.0 |
| 9-May | 0 10 | 56.0 | 16.5 | 39.50 | 847.5 | 28.1 | 35.3 | 80 | 3.4 | 22.8 | 21.8 | 33.4 | 52.0 |
| 9-May | 6 24 | 57.0 | 17.0 | 40.00 | 853.7 | 29.7 | 35.6 | 83 | 3.4 | 23.2 | 22.1 | 33.6 | 52.3 |
| 9-May | 21 50 | 56.4 | 18.0 | 38.40 | 869.2 | 29.0 | 36.2 | 80 | 3.6 | 22.8 | 22.7 | 32.1 | 55.2 |
| 10-May | 1 5 | 58.0 | 19.0 | 39.00 | 872.4 | 30.5 | 36.4 | 84 | 3.7 | 23.3 | 23.2 | 32.1 | 55.7 |
| 10-May | 21 56 | 59.9 | 20.0 | 39.90 | 893.3 | 29.9 | 37.2 | 80 | 3.7 | 23.7 | 26.0 | 29.2 | 57.3 |
| 11-May | 0 30 | 62.0 | 21.0 | 41.00 | 895.8 | 31.4 | 37.3 | 84 | 3.8 | 24.3 | 26.5 | 29.3 | 56.9 |
| 11-May | 8 0 | 63.0 | 21.9 | 41.10 | 903.3 | 30.4 | 37.6 | 81 | 3.9 | 24.4 | 23.6 | 33.1 | 57.6 |
| 11-May | 16 0 | 54.5 | 18.7 | 35.80 | 911.3 | 32.0 | 38.0 | 84 | 3.8 | 23.9 | 23.8 | 32.1 | 53.3 |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | Elapsed Time in hours | Equiv. Power in kW | Elapsed Days at 40 kW | Source Utilization % | VSWR | Vector Voltmeter mV | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|---------------|--------------------------|--------------------------|--------------------------|----------------------------|------|------------------------|----------|-----------------|-----------|----------------|
| | TIME hr mi | Ref: Forw: | | | | | | | | | | |
| 11-May | 16 29 | 54.5 | 18.7 | 35.80 | 911.8 | 30.7 | 81 | 3.8 | ERR | ERR | 15.6 | ERR |
| 11-May | 16 30 | 0.0 | 0.0 | 0.00 | 911.8 | 32.1 | 84 | ERR | ERR | ERR | 18.1 | -29.1 |
| 12-May | 3 55 | 64.0 | 24.5 | 39.50 | 923.3 | 31.2 | 85 | 4.2 | 25.6 | 24.8 | 56.0 | -26.9 |
| 12-May | 12 18 | 59.0 | 20.5 | 38.50 | 931.6 | 32.5 | 84 | 3.9 | 23.1 | 22.8 | 53.9 | -26.2 |
| 12-May | 19 55 | 55.5 | 19.0 | 36.50 | 939.3 | 31.8 | 81 | 3.8 | 22.3 | 22.0 | 52.9 | -25.9 |
| 13-May | 2 0 | 56.5 | 17.5 | 39.00 | 945.3 | 33.0 | 84 | 3.5 | 22.5 | 22.2 | 51.9 | -22.9 |
| 13-May | 13 20 | 52.5 | 12.5 | 40.00 | 956.7 | 32.5 | 82 | 2.9 | 20.6 | 21.1 | 47.1 | -23.2 |
| 13-May | 21 55 | 51.5 | 14.0 | 37.50 | 965.3 | 33.8 | 40.2 | 84 | 3.2 | 20.7 | 31.5 | -23.7 |
| 14-May | 4 0 | 54.0 | 15.0 | 39.00 | 971.3 | 33.1 | 40.5 | 82 | 3.2 | 21.4 | 31.5 | -23.7 |
| 14-May | 15 55 | 51.5 | 14.3 | 37.20 | 983.3 | 34.5 | 41.0 | 84 | 3.2 | 20.4 | 31.1 | -22.6 |
| 14-May | 21 55 | 52.5 | 14.3 | 38.20 | 989.3 | 33.8 | 41.2 | 82 | 3.2 | 20.8 | 31.4 | -22.6 |
| 15-May | 0 37 | 52.2 | 13.0 | 39.20 | 992.0 | 34.8 | 41.3 | 84 | 3.0 | 21.2 | 31.5 | -23.1 |
| 15-May | 6 40 | 52.2 | 14.5 | 37.70 | 998.0 | 34.2 | 41.6 | 82 | 3.2 | 21.1 | 31.2 | -22.8 |
| 15-May | 8 30 | 56.0 | 15.2 | 40.80 | 999.8 | 35.2 | 41.7 | 84 | 3.2 | 20.6 | 30.6 | -22.0 |
| 15-May | 11 44 | 56.0 | 15.2 | 40.80 | 1003.1 | 34.4 | 41.8 | 82 | 3.2 | 20.8 | 46.0 | -21.8 |
| 15-May | 11 45 | 0.0 | 0.0 | 0.00 | 1003.1 | 35.2 | 41.8 | ERR | ERR | ERR | 47.2 | -21.4 |
| 15-May | 12 4 | 0.0 | 0.0 | 0.00 | 1003.4 | 34.4 | 41.8 | 82 | 3.2 | 20.9 | 46.9 | -21.3 |
| 15-May | 12 5 | 54.0 | 15.1 | 38.90 | 1003.4 | 35.3 | 41.8 | 84 | 3.2 | 20.5 | 30.6 | -21.3 |
| 15-May | 21 43 | 52.0 | 15.0 | 37.00 | 1013.1 | 34.6 | 42.2 | 82 | 3.3 | 20.4 | 21.3 | -22.4 |
| 16-May | 1 5 | 53.0 | 15.2 | 37.80 | 1016.4 | 35.8 | 42.4 | 84 | 3.3 | 20.9 | 30.8 | -22.5 |
| 16-May | 4 2 | 53.0 | 15.2 | 37.80 | 1019.4 | 34.8 | 42.5 | 82 | 3.3 | 20.2 | 30.9 | -21.3 |
| 16-May | 9 55 | 48.0 | 9.4 | 38.60 | 1025.3 | 36.1 | 42.7 | 85 | 2.6 | 18.1 | 29.8 | -17.8 |
| 16-May | 20 2 | 46.0 | 8.5 | 37.50 | 1035.4 | 35.4 | 43.1 | 82 | 2.5 | 18.0 | 29.8 | -16.9 |
| 16-May | 21 40 | 46.0 | 8.5 | 37.50 | 1037.0 | 36.6 | 43.2 | 85 | 2.5 | 18.1 | 30.0 | -16.8 |
| 17-May | 0 28 | 46.0 | 8.3 | 37.70 | 1039.8 | 35.6 | 43.3 | 82 | 2.5 | 18.2 | 30.2 | -16.9 |
| 17-May | 8 40 | 46.2 | 7.4 | 38.80 | 1048.0 | 37.0 | 43.7 | 85 | 2.3 | 18.0 | 30.3 | -15.1 |
| 17-May | 12 0 | 0.0 | 0.0 | 0.00 | 1051.3 | 35.8 | 43.8 | 82 | ERR | ERR | 34.0 | ERR |
| 17-May | 12 34 | 0.0 | 0.0 | 0.00 | 1051.9 | 37.1 | 43.8 | 85 | ERR | ERR | 30.0 | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | Power at Array | | | Elapsed Time hours | Equiv. Days at 40 kW | Source % | Vector Voltmeter | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|----------------|-------|------|--------------------|----------------------|----------|------------------|-------|--------------|--------|-------------|
| | TIME hr mi | in kW | Fwd. | | | | | | | | |
| 17-May | 12 35 | 45.6 | 7.9 | 37.70 | 1051.9 | 35.8 | 43.8 | 82 | 2.4 | ERR | ERR |
| 17-May | 15 5 | 0.0 | 0.0 | 0.00 | 1054.4 | 37.1 | 43.9 | 84 | ERR | ERR | ERR |
| 17-May | 15 34 | 0.0 | 0.0 | 0.00 | 1054.9 | 35.9 | 44.0 | 82 | ERR | ERR | ERR |
| 17-May | 15 35 | 45.0 | 7.5 | 37.50 | 1054.9 | 37.1 | 44.0 | 84 | 2.4 | ERR | ERR |
| 17-May | 21 0 | 44.0 | 7.5 | 36.50 | 1060.3 | 36.0 | 44.2 | 81 | 2.4 | 17.3 | 29.4 |
| 18-May | 4 35 | 44.0 | 6.5 | 37.50 | 1067.9 | 37.6 | 44.5 | 85 | 2.2 | 16.6 | 28.7 |
| 18-May | 6 0 | 44.0 | 6.0 | 38.00 | 1069.3 | 36.4 | 44.6 | 82 | 2.2 | 16.8 | 29.0 |
| 18-May | 8 45 | 45.5 | 6.5 | 39.00 | 1072.1 | 37.8 | 44.7 | 85 | 2.2 | 16.9 | 28.7 |
| 18-May | 13 30 | 43.0 | 4.9 | 38.10 | 1076.8 | 36.7 | 44.9 | 82 | 2.0 | 17.0 | 18.1 |
| 18-May | 16 0 | 41.8 | 4.0 | 37.80 | 1079.3 | 38.1 | 45.0 | 85 | 1.9 | 16.9 | 17.2 |
| 18-May | 23 40 | 18.0 | 2.5 | 15.50 | 1087.0 | 36.9 | 45.3 | 82 | 2.2 | 20.4 | 7.5 |
| 18-May | 23 55 | 0.0 | 0.0 | 0.00 | 1087.3 | 38.2 | 45.3 | 84 | ERR | ERR | ERR |
| 19-May | 1 15 | 0.0 | 0.0 | 0.00 | 1088.6 | 36.9 | 45.4 | 81 | ERR | ERR | ERR |
| 19-May | 1 15 | 21.0 | 0.7 | 20.30 | 1088.6 | 38.2 | 45.4 | 84 | 1.4 | ERR | ERR |
| 19-May | 5 58 | 21.5 | 0.8 | 20.70 | 1093.3 | 37.0 | 45.6 | 81 | 1.5 | 20.3 | 8.0 |
| 19-May | 7 55 | 22.0 | 0.8 | 21.20 | 1095.3 | 38.4 | 45.6 | 84 | 1.5 | 20.0 | 7.8 |
| 19-May | 10 0 | 35.5 | 2.0 | 33.50 | 1097.3 | 37.1 | 45.7 | 81 | 1.6 | 25.1 | 9.4 |
| 19-May | 11 11 | 34.0 | 0.8 | 33.20 | 1098.5 | 38.5 | 45.8 | 84 | 1.4 | 23.4 | 9.9 |
| 19-May | 14 13 | 33.0 | 0.7 | 32.30 | 1101.6 | 37.3 | 45.9 | 81 | 1.3 | 22.3 | 10.0 |
| 19-May | 14 23 | 38.0 | 0.8 | 37.20 | 1101.7 | 38.6 | 45.9 | 84 | 1.3 | 24.0 | 10.8 |
| 19-May | 15 23 | 36.5 | 0.5 | 36.00 | 1102.7 | 37.3 | 45.9 | 81 | 1.3 | 23.0 | 11.4 |
| 19-May | 17 0 | 38.0 | 0.8 | 37.20 | 1104.3 | 38.7 | 46.0 | 84 | 1.3 | 24.0 | 10.0 |
| 19-May | 19 0 | 38.0 | 2.5 | 35.50 | 1106.3 | 37.4 | 46.1 | 81 | 1.7 | 25.0 | 11.8 |
| 19-May | 20 0 | 42.5 | 6.5 | 36.00 | 1107.3 | 38.8 | 46.1 | 84 | 2.3 | 26.5 | 13.3 |
| 19-May | 23 55 | 33.0 | 3.0 | 30.00 | 1111.3 | 37.6 | 46.3 | 81 | 1.9 | 21.5 | 12.7 |
| 20-May | 4 22 | 26.0 | 6.0 | 20.00 | 1115.7 | 39.1 | 46.5 | 84 | 2.8 | 22.0 | 10.5 |
| 20-May | 5 49 | 7.0 | 0.0 | 7.00 | 1117.2 | 37.7 | 46.5 | 81 | 1.0 | 23.0 | 5.7 |
| 20-May | 6 25 | 0.0 | 0.0 | 0.00 | 1117.8 | 39.1 | 46.6 | 84 | ERR | ERR | ERR |

Table C-1 Operating Data -- Electrical (Continued)

| DATE | TIME hr mi | Power at Array | | Elapsed Time hours | Days at 40 kW | Equiv. Source % | Vector Voltmeter | | Z ohm | Angle degree | Z Real | Z Imaginary |
|--------|---------------|----------------|----------------|--------------------------|------------------|-----------------------|------------------|----------------------|----------------------|-----------------|-----------|----------------|
| | | in kW | Power in kW | | | | Vswr | V _a mV | V _b mV | | | |
| 20-May | 7 30 | 31.0 | 15.0 | 16.00 | 1118.8 | 37.7 | 46.6 | 81 | 5.6 | 29.0 | 9.0 | 103.0 |
| 20-May | 7 31 | 0.0 | 0.0 | 0.00 | 1118.9 | 39.1 | 46.6 | 84 | ERR | ERR | ERR | ERR |
| 20-May | 18 29 | 0.0 | 0.0 | 0.00 | 1129.8 | 37.8 | 47.1 | 80 | ERR | ERR | ERR | ERR |
| 20-May | 18 30 | 12.0 | 2.0 | 10.00 | 1129.8 | 39.1 | 47.1 | 83 | 2.4 | 16.0 | 5.5 | 93.0 |
| 20-May | 18 53 | 24.0 | 3.6 | 20.40 | 1130.2 | 37.8 | 47.1 | 80 | 2.3 | 22.3 | 7.9 | 90.3 |
| 21-May | 0 25 | 22.5 | 3.0 | 19.50 | 1135.8 | 39.2 | 47.3 | 83 | 2.2 | 21.7 | 8.4 | 82.6 |
| 21-May | 1 18 | 10.0 | 0.0 | 10.00 | 1136.6 | 37.9 | 47.4 | 80 | 1.0 | 11.5 | 6.0 | 61.3 |
| 21-May | 3 31 | 11.0 | 1.1 | 9.90 | 1138.9 | 39.3 | 47.5 | 83 | 1.9 | 15.5 | 5.6 | 88.5 |
| 21-May | 5 23 | 11.0 | 1.0 | 10.00 | 1140.7 | 38.0 | 47.5 | 80 | 1.9 | 14.7 | 6.0 | 78.4 |
| 21-May | 5 30 | 16.0 | 1.5 | 14.50 | 1140.8 | 39.3 | 47.5 | 83 | 1.9 | 17.6 | 7.2 | 78.2 |
| 21-May | 8 15 | 23.0 | 2.1 | 20.90 | 1143.6 | 38.0 | 47.6 | 80 | 1.9 | 20.4 | 8.4 | 77.7 |
| 21-May | 8 55 | 10.0 | 0.0 | 10.00 | 1144.3 | 39.3 | 47.7 | 83 | 1.0 | 11.3 | 6.6 | 54.8 |
| 21-May | 9 28 | 17.0 | 1.9 | 15.10 | 1144.8 | 38.0 | 47.7 | 80 | 2.0 | 18.0 | 10.0 | 57.6 |
| 21-May | 13 15 | 16.0 | 0.3 | 15.70 | 1148.6 | 39.4 | 47.9 | 82 | 1.3 | 13.0 | 8.6 | 48.3 |
| 21-May | 23 6 | 22.0 | 2.5 | 19.50 | 1158.4 | 38.3 | 48.3 | 79 | 2.0 | 17.1 | 11.0 | 49.7 |
| 22-May | 0 49 | 32 | 7.3 | 24.70 | 1160.2 | 39.6 | 48.3 | 82 | 2.8 | 29.5 | 5.9 | 159.9 |
| 22-May | 1 57 | 46.0 | 16.0 | 30.00 | 1161.3 | 38.4 | 48.4 | 79 | 3.9 | 38.0 | 6.0 | 202.5 |
| 22-May | 4 18 | 66.0 | 22.0 | 44.00 | 1163.6 | 39.8 | 48.5 | 82 | 3.7 | 45.0 | 8.0 | 179.9 |
| 22-May | 7 40 | 35.0 | 0.0 | 35.00 | 1167.0 | 38.6 | 48.6 | 79 | 1.0 | 48.0 | 8.2 | 187.2 |
| 22-May | 12 20 | 30.0 | 0.0 | 30.00 | 1171.7 | 40.1 | 48.8 | 82 | 1.0 | 46.0 | 9.7 | 151.7 |
| 22-May | 16 25 | 35.0 | 0.0 | 35.00 | 1175.8 | 38.9 | 49.0 | 79 | 1.0 | 49.5 | 8.4 | 188.2 |
| 22-May | 21 24 | 35.0 | 0.1 | 34.90 | 1180.7 | 40.4 | 49.2 | 82 | 1.1 | 51.8 | 8.3 | 199.6 |
| 22-May | 23 29 | 38.0 | 0.1 | 37.90 | 1182.8 | 39.1 | 49.3 | 79 | 1.1 | 51.0 | 8.6 | 189.6 |
| 23-May | 1 14 | 39.8 | 0.1 | 39.70 | 1184.6 | 40.5 | 49.4 | 82 | 1.1 | 54.2 | 8.8 | 197.0 |
| 23-May | 5 29 | 37.0 | 0.1 | 36.90 | 1188.8 | 39.4 | 49.5 | 79 | 1.1 | 51.0 | 8.0 | 203.9 |
| 23-May | 20 8 | 36.0 | 0.0 | 36.00 | 1203.5 | 41.3 | 50.1 | 82 | 1.0 | 46.1 | 10.4 | 141.8 |
| 24-May | 6 0 | 10.0 | 0.1 | 9.90 | 1213.3 | 40.0 | 50.6 | 79 | 1.2 | ERR | ERR | ERR |
| 24-May | 6 43 | 15.0 | 0.0 | 15.00 | 1214.1 | 41.6 | 50.6 | 82 | 1.0 | 8.1 | 13.0 | 19.9 |

APPENDIX D

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|--------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| 4/3/93 | 15:30 | 70 | 66 | 90 | 12 | 17 | 170 | 0.4 | 65 | | 100 |
| | 16:35 | | | | | | | | | | |
| | 18:25 | 70 | 66 | 90 | 13 | 17 | 170 | 0.6 | 65 | | 100 |
| | 20:25 | 70 | 66 | 85 | 13 | 16 | 170 | 0.5 | 65 | | 100 |
| | 23:10 | 70 | 66 | 85 | 13 | 18 | 170 | 0.4 | 68 | | 100 |
| 4/4/93 | 1:30 | 70 | 66 | 88 | 13 | 18 | 180 | 0.6 | 60 | | 110 |
| | 4:30 | 70 | 66 | 87 | 13 | 18 | 180 | 0.6 | 60 | | 110 |
| | 6:25 | 70 | 66 | 86 | 13 | 18 | 180 | 0.5 | 60 | | 110 |
| | 9:27 | 70 | 67 | 85 | 13 | 18 | 180 | 0.5 | 66 | | 110 |
| | 11:45 | 70 | 68 | 90 | 13 | 18 | 180 | 0.5 | 66 | | 110 |
| | 14:30 | 70 | 67 | 91 | 13 | 17 | 180 | 0.5 | 80 | | 110 |
| | 16:30 | 70 | 66 | 90 | 13 | 18 | 180 | 0.6 | 80 | | 110 |
| | 18:40 | 70 | 68 | 90 | 13 | 17 | 180 | 0.5 | 80 | | 110 |
| | 20:30 | 70 | 67 | 90 | 12 | 16 | 180 | 0.4 | 65 | | 110 |
| | 22:30 | 70 | 67 | 88 | 12 | 17 | 180 | 0.5 | 65 | | 110 |
| 4/5/93 | 0:32 | 70 | 67 | 88 | 12 | 16 | 180 | 0.6 | 70 | | 110 |
| | 2:25 | 70 | 67 | 91 | 12 | 16 | 180 | 0.7 | 70 | | 110 |
| | 4:29 | 70 | 67 | 90 | 12 | 16 | 180 | 0.7 | 67 | | 110 |
| | 6:27 | 70 | 67 | 90 | 11 | 16 | 180 | 0.7 | 67 | | 110 |
| | 8:30 | 70 | 67 | 93 | 11 | 16 | 180 | 0.5 | 70 | | 110 |
| | 10:30 | 65 | | | | 16 | | | | | |
| | 11:40 | 75 | 78 | 105 | 11 | 16 | 190 | 0.6 | 90 | 56 | 115 |
| | 13:35 | 70 | 78 | 107 | 11 | 16 | 190 | 0.5 | 90 | 70 | 120 |
| | 15:40 | 70 | 79 | 115 | 10 | 15 | 190 | 0.5 | 110 | 72 | 120 |
| | 17:30 | 65 | 79 | 120 | 10 | 15 | 190 | 0.5 | 100 | 74 | 125 |
| | 19:30 | 65 | 79 | 120 | 10 | 15 | 190 | 0.4 | 90 | | 125 |
| | 23:30 | 70 | 78 | 111 | 10 | 15 | 190 | 0.6 | 81 | | 120 |
| 4/6/93 | 1:30 | 70 | 78 | 111 | 10 | 15 | 180 | 0.6 | 84 | | 110 |
| | 3:30 | 70 | 78 | 112 | 10 | 14 | 190 | 0.6 | 84 | | 120 |
| | 5:30 | 70 | 78 | 113 | 10 | 14 | 190 | 0.5 | 85 | | 120 |
| | 7:30 | 70 | 78 | 115 | 10 | 14 | 180 | 0.5 | 90 | 56 | 110 |
| | 9:35 | 70 | 78 | 115 | 10 | 15 | 180 | 0.6 | 90 | 70 | 110 |
| | 11:30 | 70 | 78 | 116 | 10 | 15 | 180 | 0.5 | 90 | 72 | 110 |
| | 13:28 | 71 | 79 | 120 | 11 | 14 | 179 | 0.5 | 91 | 74 | 108 |
| | 16:00 | 71 | 78 | 120 | 10 | 14 | 180 | 0.4 | 90 | 74 | 109 |
| | 18:00 | 70 | 79 | 120 | 10 | 14 | 180 | 0.5 | 90 | 70 | 110 |
| | 20:00 | 70 | 78 | 120 | 9 | 14 | 180 | 0.5 | 90 | 68 | 110 |
| | 22:00 | 70 | 79 | 119 | 9 | 14 | 190 | 0.5 | 85 | 68 | 120 |
| 4/7/93 | 0:01 | 70 | 78 | 119 | 9 | 14 | 180 | 0.6 | 91 | 67 | 110 |
| | 1:55 | 70 | 78 | 119 | 9 | 14 | 180 | 0.6 | 91 | 67 | 110 |
| | 4:00 | 70 | 78 | 119 | 8 | 14 | 190 | 0.5 | 94 | 67 | 120 |
| | 6:05 | 70 | 78 | 120 | 9 | 14 | 180 | 0.5 | 94 | 66 | 110 |
| | 8:00 | 70 | 79 | 121 | 9 | 14 | 180 | 0.5 | 100 | 70 | 110 |
| | 10:00 | 70 | 78 | 121 | 9 | 14 | 180 | 0.6 | 100 | 72 | 110 |
| | 12:02 | 69 | 78 | 120 | 10 | 14 | 180 | 0.5 | 100 | 62 | 111 |
| | 13:55 | 70 | 78 | 130 | 12 | 17 | 190 | 0.6 | 110 | 80 | 120 |
| | 15:55 | 70 | 78 | 139 | 12 | 17 | 190 | 0.6 | 115 | 82 | 120 |
| | 18:00 | 70 | 78 | 140 | 12 | 17 | 180 | 0.5 | 110 | 74 | 110 |
| | 20:00 | 70 | 78 | 135 | 12 | 16 | 190 | 0.5 | 110 | 65 | 120 |
| | 22:00 | 69 | 79 | 135 | 12 | 16 | 185 | 0.6 | 110 | 64 | 116 |
| 4/8/94 | 0:02 | 70 | 78 | 134 | 12 | 16 | 190 | 0.5 | 100 | 62 | 120 |
| | 2:00 | 70 | 78 | 133 | 12 | 16 | 190 | 0.5 | 105 | 62 | 120 |
| | 4:00 | 70 | 78 | 131 | 12 | 15 | 190 | 0.5 | 104 | 63 | 120 |
| | 6:00 | 70 | 77 | 129 | 12 | 16 | 180 | 0.5 | 103 | 62 | 110 |
| | 8:00 | 70 | 78 | 129 | 12 | 15 | 190 | 0.6 | 103 | 62 | 120 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 10:00 | 70 | 78 | 130 | 12 | 16 | 190 | 0.6 | 105 | 74 | 120 |
| | 12:00 | 65 | 78 | 137 | 12 | 16 | 190 | 0.6 | 110 | 82 | 125 |
| | 14:00 | 65 | 78 | 140 | 12 | 16 | 190 | 0.6 | 110 | 86 | 125 |
| | 16:00 | 70 | 78 | 140 | 12 | 16 | 190 | 0.6 | 115 | 82 | 120 |
| | 18:00 | 70 | 78 | 140 | 11 | 17 | 190 | 0.5 | 110 | 70 | 120 |
| | 20:00 | 70 | 78 | 138 | 11 | 15 | 190 | 0.5 | 115 | 68 | 120 |
| | 22:00 | 70 | 78 | 140 | 12 | 17 | 190 | 0.6 | 110 | 62 | 120 |
| 4/9/94 | 0:01 | 70 | 78 | 135 | 11 | 15 | 190 | 0.6 | 107 | 56 | 120 |
| | 2:00 | 70 | 78 | 132 | 11 | 15 | 180 | 0.6 | 104 | 53 | 110 |
| | 4:00 | 70 | 78 | 131 | 11 | 15 | 190 | 0.6 | 104 | 50 | 120 |
| | 6:00 | 70 | 78 | 131 | 11 | 15 | 190 | 0.6 | 105 | 48 | 120 |
| | 8:00 | 70 | 78 | 131 | 11 | 15 | 190 | 0.6 | 105 | 72 | 120 |
| | 10:00 | 70 | 78 | 130 | 11 | 15 | 190 | 0.5 | 110 | | 120 |
| | 12:05 | 70 | 78 | 135 | 11 | 15 | 190 | 0.5 | 110 | | 120 |
| | 14:00 | 70 | 78 | 142 | 12 | 16 | 195 | 0.4 | 120 | 95 | 125 |
| | 16:00 | 70 | 78 | 145 | 12 | 16 | 195 | 0.4 | 118 | | 125 |
| | 18:00 | 70 | 78 | 146 | 11 | 16 | 195 | 0.4 | 118 | | 125 |
| | 20:00 | 70 | 78 | 147 | 11 | 16 | 190 | 0.4 | 118 | 78 | 120 |
| | 22:00 | 75 | 78 | 145 | 11 | 16 | 190 | 0.4 | 115 | 70 | 115 |
| 4/10/94 | 0:01 | 75 | 78 | 145 | 11 | 15 | 190 | 0.5 | 113 | 57 | 115 |
| | 2:00 | 75 | 78 | 142 | 11 | 15 | 180 | 0.5 | 113 | 52 | 105 |
| | 4:04 | 75 | 78 | 139 | 11 | 15 | 180 | 0.5 | 113 | 49 | 105 |
| | 6:00 | 75 | 78 | 139 | 11 | 15 | 193 | 0.5 | 113 | 48 | 118 |
| | 8:00 | 70 | 78 | 139 | 11 | 15 | 195 | 0.4 | 120 | 70 | 125 |
| | 10:00 | 70 | 78 | 140 | 11 | 15 | 195 | 0.4 | 125 | | 125 |
| | 12:00 | 70 | 78 | 143 | 11 | 15 | 195 | 0.4 | 125 | | 125 |
| | 14:00 | 70 | 78 | 147 | 11 | 15 | 195 | 0.4 | 130 | | 125 |
| | 16:00 | 70 | 78 | 150 | 11 | 15 | 195 | 0.4 | 125 | 88 | 125 |
| | 18:00 | 70 | 78 | 151 | 11 | 15 | 195 | 0.4 | 121 | | 125 |
| | 20:00 | 70 | 78 | 151 | 11 | 15 | 195 | 0.4 | 120 | | 125 |
| | 22:00 | 70 | 78 | 149 | 11 | 15 | 190 | 0.4 | 115 | | 120 |
| 4/11/93 | 0:01 | 70 | 78 | 145 | 11 | 15 | 180 | 0.5 | 117 | 68 | 110 |
| | 2:00 | 70 | 78 | 143 | 11 | 15 | 180 | 0.5 | 117 | 68 | 110 |
| | 4:00 | 70 | 78 | 143 | 11 | 15 | 180 | 0.4 | 117 | 64 | 110 |
| | 6:00 | 70 | 78 | 144 | 10 | 15 | 180 | 0.4 | 120 | 62 | 110 |
| | 8:00 | 70 | 78 | 145 | 10 | 15 | 190 | 0.4 | 120 | 59 | 120 |
| | 10:00 | 70 | 78 | 146 | 10 | 15 | 190 | 0.4 | 125 | 72 | 120 |
| | 12:00 | 70 | 78 | 150 | 10 | 15 | 190 | 0.4 | 130 | 76 | 120 |
| | 14:00 | 70 | 78 | 155 | 11 | 15 | 190 | 0.4 | 130 | | 120 |
| | 16:00 | 70 | 78 | 154 | 12 | 15 | 190 | 0.5 | 130 | | 120 |
| | 18:00 | 69 | 78 | 155 | 12 | 15 | 195 | 0.4 | 125 | 82 | 126 |
| | 20:00 | 66 | 78 | 145 | 10 | 15 | 195 | 0.4 | 115 | 78 | 129 |
| | 22:00 | 68 | 77 | 145 | 11 | 15 | 190 | 0.5 | 120 | 76 | 122 |
| 4/12/93 | 0:01 | 64 | 77 | 142 | 11 | 15 | 180 | 0.4 | 111 | 69 | 116 |
| | 2:00 | 63 | 78 | 142 | 11 | 15 | 180 | 0.4 | 113 | 68 | 117 |
| | 4:00 | 65 | 78 | 143 | 11 | 15 | 180 | 0.4 | 115 | 68 | 115 |
| | 6:00 | 65 | 78 | 144 | 10 | 15 | 185 | 0.4 | 115 | 67 | 120 |
| | 8:00 | 65 | 78 | 145 | 10 | 15 | 190 | 0.4 | 120 | | 125 |
| | 10:00 | 65 | 78 | 145 | 10 | 15 | 190 | 0.3 | 125 | | 125 |
| | 12:00 | 65 | 78 | 145 | 10 | 15 | 190 | 0.4 | 125 | 78 | 125 |
| | 14:00 | | | | | | | | | | |
| | 16:00 | 71 | 89 | 155 | 10 | 14 | 197 | 0.4 | 125 | 88 | 126 |
| | 18:00 | 71 | 88 | 155 | 11 | 14 | 195 | 0.4 | 120 | 82 | 124 |
| | 20:00 | 71 | 88 | 150 | 10 | 14 | 195 | 0.4 | 120 | 78 | 124 |
| | 22:00 | 70 | 88 | 145 | 10 | 14 | 200 | 0.4 | 120 | 72 | 130 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| 4/13/93 | 0:01 | 70 | 88 | 146 | 10 | 14 | 190 | 0.4 | 116 | 70 | 120 |
| | 2:00 | 75 | 88 | 146 | 10 | 14 | 190 | 0.4 | 118 | 70 | 115 |
| | 4:00 | 75 | 88 | 147 | 10 | 14 | 190 | 0.4 | 120 | 70 | 115 |
| | 6:00 | 75 | 88 | 147 | 10 | 14 | 190 | 0.4 | 120 | 70 | 115 |
| | 8:00 | 75 | 88 | 147 | 10 | 14 | 195 | 0.4 | 125 | | 120 |
| | 10:00 | 75 | 88 | 148 | 10 | 14 | 195 | 0.4 | 120 | | 120 |
| | 12:00 | 75 | 88 | 148 | 10 | 14 | 195 | 0.4 | 120 | | 120 |
| | 14:00 | 80 | 88 | 150 | 10 | 14 | 195 | 0.4 | 125 | | 115 |
| | 16:00 | 80 | 88 | 150 | 10 | 14 | 195 | 0.4 | 120 | | 115 |
| | 18:00 | 80 | 89 | 150 | 11 | 14 | 195 | 0.4 | 118 | 78 | 115 |
| | 20:00 | 78 | 87 | 150 | 10 | 14 | 195 | 0.4 | 120 | 72 | 117 |
| | 22:00 | 80 | 86 | 150 | 10 | 14 | 200 | 0.4 | 120 | 70 | 120 |
| 4/14/93 | 0:01 | 78 | 87 | 148 | 9 | 14 | 190 | 0.4 | 118 | 70 | 112 |
| | 2:00 | 78 | 86 | 149 | 10 | 14 | 190 | 0.4 | 120 | 70 | 112 |
| | 4:00 | 78 | 87 | 148 | 9 | 13 | 190 | 0.4 | 118 | 69 | 112 |
| | 6:00 | 78 | 88 | 149 | 9 | 13 | 190 | 0.4 | 120 | 68 | 112 |
| | 8:00 | 70 | 88 | 149 | 9 | 13 | 190 | 0.4 | 120 | | 120 |
| | 10:00 | 75 | 88 | 150 | 10 | 13 | 190 | 0.4 | 120 | | 115 |
| | 12:00 | 75 | 88 | 150 | 10 | 14 | 190 | 0.4 | 125 | | 115 |
| | 14:00 | 75 | 90 | 150 | 10 | 14 | 195 | 0.4 | 125 | | 120 |
| | 16:00 | 75 | 89 | 150 | 10 | 14 | 196 | 0.4 | 124 | 86 | 121 |
| | 18:00 | 80 | 89 | 150 | 9 | 13 | 197 | 0.4 | 125 | 76 | 117 |
| | 20:00 | 80 | 89 | 151 | 10 | 14 | 195 | 0.4 | 125 | 60 | 115 |
| | 22:00 | 75 | 89 | 145 | 10 | 14 | 200 | 0.4 | 115 | 53 | 125 |
| 4/15/93 | 0:01 | 75 | 88 | 145 | 9 | 13 | 195 | 0.4 | 112 | 49 | 120 |
| | 2:00 | 75 | 88 | 145 | 9 | 13 | 195 | 0.4 | 112 | 49 | 120 |
| | 4:00 | 75 | 89 | 144 | 9 | 13 | 195 | 0.4 | 113 | 48 | 120 |
| | 6:00 | 70 | 90 | 144 | 9 | 13 | 200 | 0.4 | 114 | 45 | 130 |
| | 8:00 | 75 | 90 | 145 | 9 | 13 | 200 | 0.4 | 115 | | 125 |
| | 10:00 | 75 | 89 | 146 | 9 | 13 | 200 | 0.4 | 115 | | 125 |
| | 12:00 | 75 | 90 | 150 | 9 | 13 | 200 | 0.4 | 117 | | 125 |
| | 14:00 | 75 | 90 | 152 | 9 | 13 | 200 | 0.4 | 120 | | 125 |
| | 16:00 | 70 | 90 | 156 | 9 | 13 | 200 | 0.4 | 120 | 86 | 130 |
| | 18:00 | 70 | 90 | 155 | 9 | 13 | 200 | 0.4 | 120 | 75 | 130 |
| | 20:00 | 75 | 90 | 155 | 9 | 13 | 200 | 0.4 | 120 | 72 | 125 |
| | 22:00 | 75 | 90 | 155 | 9 | 13 | 200 | 0.4 | 120 | 60 | 125 |
| 4/16/93 | 0:01 | 80 | 90 | 145 | 9 | 13 | 200 | 0.4 | 115 | 58 | 120 |
| | 2:00 | 80 | 89 | 145 | 9 | 13 | 200 | 0.4 | 114 | 53 | 120 |
| | 4:00 | 80 | 89 | 144 | 9 | 13 | 200 | 0.4 | 115 | 50 | 120 |
| | 6:00 | 80 | 89 | 144 | 9 | 13 | 200 | 0.4 | 114 | 49 | 120 |
| | 8:00 | 80 | 89 | 145 | 9 | 13 | 200 | 0.4 | 115 | 64 | 120 |
| | 10:00 | 80 | 89 | 146 | 9 | 13 | 200 | 0.4 | 115 | | 120 |
| | 12:00 | 80 | 90 | 150 | 9 | 13 | 200 | 0.4 | 120 | 78 | 120 |
| | 14:00 | 80 | 90 | 150 | 9 | 13 | 200 | 0.4 | 120 | | 120 |
| | 16:00 | 80 | 89 | 150 | 8 | 13 | 200 | 0.4 | 120 | 80 | 120 |
| | 18:00 | 80 | 89 | 150 | 8 | 12 | 200 | 0.4 | 120 | 72 | 120 |
| | 20:00 | 75 | 88 | 145 | 8 | 12 | 200 | 0.4 | 115 | 66 | 125 |
| | 22:00 | 75 | 89 | 145 | 8 | 12 | 200 | 0.4 | 115 | 60 | 125 |
| 4/17/93 | 0:01 | 70 | 88 | 143 | 8 | 12 | 200 | 0.4 | 110 | 60 | 130 |
| | 2:00 | 75 | 87 | 140 | 8 | 12 | 195 | 0.4 | 110 | 58 | 120 |
| | 4:00 | 75 | 87 | 142 | 8 | 12 | 195 | 0.4 | 110 | 58 | 120 |
| | 6:00 | 70 | 87 | 142 | 8 | 12 | 195 | 0.5 | 111 | 59 | 125 |
| | 8:00 | 70 | 88 | 142 | 8 | 12 | 195 | 0.4 | 112 | 65 | 125 |
| | 10:00 | 70 | 8 | 146 | 8 | 13 | 195 | 0.5 | 115 | | 125 |
| | 12:00 | 70 | 88 | 144 | 8 | 15 | 195 | 0.4 | 115 | | 125 |

IITRI OPERATING DATA

| | | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| Date | Time | | | | | | | | | | |
| | 14:00 | 70 | 88 | 146 | 8 | 16 | 200 | 0.4 | 120 | 88 | 130 |
| | 16:00 | 70 | 89 | 150 | 8 | 16 | 200 | 0.4 | 120 | 88 | 130 |
| | 18:00 | 70 | 88 | 150 | 9 | 16 | 200 | 0.4 | 125 | 89 | 130 |
| | 20:00 | 75 | 88 | 143 | 8 | 16 | 200 | 0.4 | 120 | 69 | 125 |
| | 22:00 | 75 | 87 | 135 | 8 | 16 | 200 | 0.4 | 105 | 68 | 125 |
| 4/18/93 | 0:01 | | | | | | | | | | |
| | 1:10 | 75 | 87 | 133 | 8 | 16 | 200 | 0.4 | 104 | 64 | 125 |
| | 2:00 | 75 | 87 | 137 | 8 | 16 | 200 | 0.4 | 105 | 63 | 125 |
| | 4:00 | 75 | 88 | 137 | 8 | 16 | 200 | 0.4 | 106 | 61 | 125 |
| | 6:00 | 70 | 88 | 138 | 8 | 16 | 200 | 0.4 | 108 | 62 | 130 |
| | 8:00 | 70 | 88 | 140 | 8 | 16 | 200 | 0.4 | 110 | 65 | 130 |
| | 10:00 | 70 | 88 | 141 | 8 | 16 | 200 | 0.4 | 111 | 68 | 130 |
| | 12:00 | 70 | 88 | 146 | 8 | 16 | 200 | 0.4 | 116 | 75 | 130 |
| | 14:00 | 70 | 88 | 147 | 8 | 16 | 200 | 0.4 | 120 | 92 | 130 |
| | 16:00 | 70 | 89 | 150 | 8 | 16 | 200 | 0.4 | 120 | 92 | 130 |
| | 18:00 | 70 | 88 | 150 | 8 | 16 | 200 | 0.4 | 120 | 88 | 130 |
| | 20:00 | 70 | 89 | 150 | 8 | 16 | 200 | 0.4 | 120 | 80 | 130 |
| | 22:00 | 70 | 86 | 140 | 8 | 115 | 200 | 0.4 | 110 | 75 | 130 |
| 4/19/93 | 0:01 | 70 | 87 | 139 | 8 | 15 | 195 | 0.4 | 110 | 66 | 125 |
| | 2:00 | 70 | 87 | 139 | 8 | 15 | 195 | 0.4 | 110 | 66 | 125 |
| | 4:00 | 70 | 87 | 139 | 8 | 15 | 200 | 0.4 | 110 | 66 | 130 |
| | 6:00 | 65 | 87 | 139 | 8 | 15 | 200 | 0.4 | 111 | 66 | 135 |
| | 8:00 | 65 | 88 | 142 | 8 | 15 | 200 | 0.4 | 111 | | 135 |
| | 10:00 | 65 | 89 | 145 | 8 | 15 | 200 | 0.4 | 113 | | 135 |
| | 12:00 | 70 | 88 | 149 | 8 | 15 | 200 | 0.4 | 120 | | 130 |
| | 14:00 | 70 | 88 | 151 | 8 | 15 | 200 | 0.4 | 120 | | 130 |
| | 16:00 | 70 | 88 | 150 | 8 | 15 | 200 | 0.4 | 120 | 88 | 130 |
| | 18:00 | 70 | 88 | 150 | 8 | 15 | 200 | 0.4 | 118 | 85 | 130 |
| | 20:00 | 70 | 87 | 149 | 8 | 15 | 200 | 0.4 | 115 | 82 | 130 |
| | 22:00 | 70 | 88 | 144 | 8 | 15 | 200 | 0.4 | 110 | 70 | 130 |
| 4/20/93 | 0:01 | 65 | 86 | 142 | 8 | 15 | 195 | 0.4 | 110 | 69 | 130 |
| | 2:00 | 65 | 87 | 143 | 8 | 15 | 200 | 0.4 | 113 | 70 | 135 |
| | 4:00 | 60 | 87 | 144 | 8 | 15 | 200 | 0.4 | 114 | 70 | 140 |
| | 6:00 | 60 | 87 | 144 | 8 | 15 | 200 | 0.4 | 114 | 68 | 140 |
| | 8:00 | 60 | 88 | 145 | 8 | 15 | 200 | 0.4 | 115 | 70 | 140 |
| | 10:00 | 60 | 88 | 145 | 8 | 15 | 200 | 0.4 | 115 | 70 | 140 |
| | 12:00 | 60 | 88 | 145 | 8 | 15 | 200 | 0.4 | 115 | 72 | 140 |
| | 14:00 | 60 | 88 | 145 | 8 | 15 | 200 | 0.4 | 115 | 78 | 140 |
| | 16:00 | 60 | 89 | 139 | 8 | 15 | 200 | 0.4 | 115 | 78 | 140 |
| | 18:00 | 60 | 88 | 140 | 8 | 15 | 200 | 0.4 | 115 | 74 | 140 |
| | 20:00 | 80 | 89 | 145 | 8 | 15 | 200 | 0.4 | 120 | 70 | 120 |
| | 22:00 | 80 | 89 | 140 | 8 | 15 | 200 | 0.4 | 110 | 62 | 120 |
| 4/21/93 | 0:01 | 80 | 89 | 138 | 8 | 15 | 200 | 0.4 | 107 | 60 | 120 |
| | 2:00 | 80 | 88 | 135 | 8 | 15 | 200 | 0.4 | 105 | 57 | 120 |
| | 4:00 | 80 | 88 | 135 | 8 | 15 | 200 | 0.4 | 106 | 54 | 120 |
| | 6:00 | 78 | 88 | 135 | 8 | 15 | 200 | 0.4 | 106 | 54 | 122 |
| | 8:00 | 79 | 88 | 135 | 8 | 15 | 200 | 0.4 | 108 | 57 | 121 |
| | 10:00 | 80 | 89 | 137 | 8 | 15 | 200 | 0.4 | 111 | 60 | 120 |
| | 12:00 | 75 | 89 | 143 | 8 | 15 | 200 | 0.4 | 115 | 75 | 125 |
| | 14:00 | 75 | 89 | 142 | 8 | 16 | 200 | 0.4 | 111 | 75 | 125 |
| | 16:00 | 65 | 90 | 145 | 8 | 16 | 200 | 0.4 | 110 | 76 | 135 |
| | 18:00 | 65 | 90 | 145 | 8 | 16 | 200 | 0.4 | 110 | 74 | 135 |
| | 20:00 | 65 | 90 | 145 | 8 | 16 | 200 | 0.4 | 110 | 72 | 135 |
| | 22:00 | 65 | 90 | 145 | 8 | 15 | 200 | 0.4 | 107 | | 135 |
| 4/22/94 | 0:01 | 90 | 88 | 136 | 8 | 15 | 200 | 0.4 | 104 | 59 | 110 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 2:00 | 90 | 89 | 137 | 8 | 15 | 200 | 0.4 | 106 | 54 | 110 |
| | 4:00 | 90 | 89 | 137 | 8 | 15 | 200 | 0.4 | 106 | 50 | 110 |
| | 6:00 | 90 | 88 | 137 | 8 | 15 | 200 | 0.4 | 106 | 50 | 110 |
| | 8:00 | 90 | 88 | 137 | 8 | 15 | 200 | 0.4 | 110 | 60 | 110 |
| | 10:00 | 90 | 88 | 139 | 8 | 15 | 200 | 0.4 | 115 | 70 | 110 |
| | 12:00 | 85 | 88 | 145 | 8 | 15 | 200 | 0.4 | 115 | 72 | 115 |
| | 14:00 | 70 | 87 | 145 | 8 | 16 | 200 | 0.4 | 115 | 75 | 130 |
| | 16:00 | 75 | 87 | 143 | 8 | 16 | 200 | 0.4 | 115 | 75 | 125 |
| | 18:00 | 70 | 87 | 142 | 8 | 16 | 200 | 0.4 | 115 | 75 | 130 |
| | 20:00 | 80 | 88 | 142 | 8 | 16 | 200 | 0.4 | 115 | 70 | 115 |
| | 22:00 | 85 | 86 | 142 | 8 | 16 | 200 | 0.4 | 110 | 67 | 115 |
| | 24:00 | 85 | 86 | 140 | 8 | 16 | 200 | 0.4 | 110 | 60 | 110 |
| 4/23/93 | 2:00 | 90 | 84 | 135 | 8 | 15 | 200 | 0.4 | 110 | 58 | 110 |
| | 4:00 | 90 | 84 | 135 | 8 | 15 | 200 | 0.4 | 105 | 56 | 110 |
| | 6:00 | 90 | 84 | 134 | 8 | 15 | 200 | 0.4 | 105 | 66 | 110 |
| | 8:00 | 90 | 84 | 137 | 8 | 15 | 200 | 0.4 | 110 | 75 | 115 |
| | 10:00 | 85 | 84 | 142 | 8 | 15 | 200 | 0.4 | 115 | 81 | 125 |
| | 12:00 | 75 | 85 | 146 | 8 | 15 | 200 | 0.4 | 115 | 85 | 125 |
| | 14:00 | 75 | 84 | 145 | 8 | 15 | 200 | 0.4 | 115 | 86 | 115 |
| | 16:00 | 85 | 85 | 146 | 8 | 15 | 200 | 0.4 | 114 | 86 | 105 |
| | 18:00 | 85 | 84 | 146 | 8 | 15 | 190 | 0.4 | 112 | 78 | 110 |
| | 20:00 | 80 | 84 | 143 | 8 | 15 | 190 | 0.4 | 108 | 72 | 115 |
| | 22:00 | 80 | 84 | 138 | 8 | 15 | 195 | 0.4 | 102 | 72 | 115 |
| | 24:00 | 85 | 84 | 140 | 8 | 15 | 200 | 0.4 | 100 | 70 | 115 |
| 4/24/93 | 2:00 | 85 | 84 | 140 | 8 | 15 | 200 | 0.4 | 100 | 70 | 115 |
| | 4:00 | 85 | 84 | 142 | 8 | 15 | 200 | 0.4 | 100 | 67 | 115 |
| | 6:00 | 85 | 84 | 140 | 8 | 15 | 200 | 0.4 | 100 | 66 | 115 |
| | 8:00 | 85 | 84 | 142 | 8 | 15 | 200 | 0.4 | 105 | 70 | 115 |
| | 10:00 | 80 | 84 | 142 | 8 | 15 | 200 | 0.4 | 110 | 74 | 120 |
| | 12:00 | 80 | 84 | 143 | 8 | 15 | 200 | 0.4 | 110 | 80 | 120 |
| | 14:00 | 80 | 84 | 145 | 8 | 15 | 200 | 0.4 | 110 | 80 | 110 |
| | 16:08 | 80 | 85 | 149 | 7 | 15 | 190 | 0.4 | 117 | 80 | 115 |
| | 18:00 | 85 | 85 | 150 | 7 | 15 | 200 | 0.4 | 114 | 75 | 120 |
| | 20:00 | 80 | 84 | 145 | 7 | 15 | 200 | 0.4 | 109 | 72 | 120 |
| | 22:00 | 80 | 84 | 139 | 7 | 15 | 200 | 0.4 | 105 | 72 | 120 |
| | 24:00 | 80 | 84 | 140 | 7 | 15 | 200 | 0.4 | 100 | 72 | 120 |
| 4/25/93 | 2:00 | 75 | 84 | 142 | 7 | 15 | 200 | 0.4 | 100 | 71 | 125 |
| | 4:00 | 70 | 84 | 143 | 8 | 15 | 200 | 0.4 | 100 | 72 | 130 |
| | 6:00 | 70 | 84 | 145 | 7 | 15 | 200 | 0.4 | 100 | 72 | 130 |
| | 8:00 | 70 | 84 | 145 | 8 | 15 | 200 | 0.4 | 110 | 70 | 130 |
| | 10:00 | 70 | 83 | 147 | 8 | 15 | 200 | 0.4 | 110 | 74 | 130 |
| | 12:00 | 65 | 84 | 146 | 8 | 16 | 200 | 0.4 | 115 | 83 | 135 |
| | 14:00 | 70 | 84 | 148 | 8 | 16 | 200 | 0.4 | 120 | 85 | 130 |
| | 16:00 | 70 | 85 | 151 | 8 | 16 | 190 | 0.4 | 121 | 88 | 120 |
| | 18:00 | 75 | 85 | 151 | 8 | 15 | 190 | 0.4 | 117 | 85 | 115 |
| | 20:00 | 70 | 84 | 147 | 8 | 15 | 200 | 0.4 | 111 | 80 | 130 |
| | 22:00 | 70 | 85 | 141 | 8 | 15 | 200 | 0.4 | 105 | 75 | 130 |
| | 24:00 | 70 | 86 | 140 | 8 | 15 | 200 | 0.4 | 105 | 74 | 130 |
| 4/26/93 | 2:00 | 70 | 86 | 141 | 8 | 15 | 200 | 0.4 | 105 | 72 | 130 |
| | 4:00 | 70 | 86 | 140 | 8 | 15 | 200 | 0.4 | 105 | 71 | 130 |
| | 6:00 | 70 | 86 | 140 | 8 | 15 | 200 | 0.4 | 105 | | 130 |
| | 8:00 | 70 | 87 | 141 | 8 | 15 | 200 | 0.4 | 108 | 73 | 130 |
| | 10:00 | 70 | 85 | 145 | 7.5 | 15 | 200 | 0.4 | 115 | 78 | 130 |
| | 12:00 | 70 | 86 | 145 | 7.5 | 15 | 200 | 0.4 | 115 | 83 | 130 |
| | 14:00 | 65 | 87 | 150 | 7.5 | 15 | 200 | 0.4 | 118 | 90 | 135 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 16:00 | 70 | 87 | 153 | 8 | 15 | 200 | 0.4 | 117 | 80 | 130 |
| | 18:00 | 70 | 87 | 153 | 8 | 15 | 200 | 0.4 | 110 | 80 | 130 |
| | 20:00 | 80 | 86 | 149 | 8 | 15 | 200 | 0.4 | 111 | 76 | 120 |
| | 22:00 | 75 | 86 | 142 | 8 | 15 | 200 | 0.4 | 106 | 71 | 125 |
| | 24:00 | 70 | 84 | 142 | 7.5 | 15 | 200 | 0.4 | 105 | 66 | 130 |
| 4/27/93 | 2:00 | 70 | 84 | 141 | 7.5 | 15 | 200 | 0.4 | 105 | 64 | 130 |
| | 4:00 | 8 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 105 | 60 | 192 |
| | 6:00 | 75 | 86 | 145 | 7.5 | 15 | 200 | 0.4 | 103 | 60 | 125 |
| | 8:00 | 75 | 85 | 141 | 7.5 | 15 | 200 | 0.4 | 110 | 62 | 125 |
| | 10:00 | 75 | 85 | 14 | 7.5 | 15 | 200 | 0.4 | 110 | 70 | 125 |
| | 12:00 | 75 | 85 | 147 | 7.5 | 15 | 200 | 0.4 | 115 | 72 | 125 |
| | 14:00 | 75 | 85 | 145 | 7.5 | 15 | 200 | 0.4 | 115 | 76 | 125 |
| | 16:00 | 75 | 85 | 146 | 7.5 | 15 | 200 | 0.4 | 115 | 76 | 125 |
| | 18:00 | 71 | 85 | 148 | 7.5 | 15 | 200 | 0.4 | 111 | 72 | 129 |
| | 20:00 | 70 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 105 | 68 | 130 |
| | 22:00 | 75 | 84 | 140 | 7.5 | 15 | 200 | 0.4 | 105 | 68 | 125 |
| | 24:00 | 75 | 84 | 143 | 7.5 | 15 | 200 | 0.4 | 105 | 66 | 125 |
| 4/28/93 | 2:00 | 75 | 84 | 143 | 7.5 | 15 | 200 | 0.4 | 105 | 65 | 125 |
| | 4:00 | 75 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 104 | 64 | 125 |
| | 6:00 | 75 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 107 | 64 | 125 |
| | 8:00 | 75 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 111 | 65 | 125 |
| | 10:00 | 70 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 111 | 70 | 130 |
| | 12:00 | 70 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 109 | 72 | 130 |
| | 14:00 | 70 | 84 | 145 | 7.5 | 15 | 200 | 0.4 | 110 | 76 | 130 |
| | 16:00 | 70 | 84 | 147 | 7.5 | 15 | 200 | 0.4 | 112 | 71 | 130 |
| | 18:00 | 70 | 84 | 148 | 7.5 | 15 | 200 | 0.4 | 112 | 72 | 130 |
| | 20:00 | 70 | 84 | 148 | 7.5 | 15 | 200 | 0.4 | 111 | 71 | 130 |
| | 22:00 | 70 | 84 | 147 | 7.5 | 15 | 200 | 0.4 | 110 | 70 | 130 |
| | 24:00 | 70 | 84 | 147 | 7.5 | 15 | 200 | 0.4 | 108 | 70 | 130 |
| 4/29/93 | 2:00 | 70 | 84 | 148 | 7.5 | 15 | 200 | 0.4 | 107 | 68 | 130 |
| | 4:00 | 70 | 84 | 149 | 7.5 | 15 | 200 | 0.4 | 105 | 67 | 130 |
| | 6:00 | 70 | 85 | 150 | 7.5 | 15 | 200 | 0.4 | 105 | 66 | 130 |
| | 8:00 | 69 | 85 | 145 | 7.5 | 15 | 200 | 0.4 | 108 | 70 | 131 |
| | 10:00 | 70 | 84 | 155 | 7.5 | 15 | 200 | 0.4 | 140 | 72 | 130 |
| | 12:00 | 70 | 84 | 160 | 7.5 | 15 | 200 | 0.4 | 145 | 68 | 130 |
| | 14:00 | 70 | 85 | 170 | 8.5 | 16 | 200 | 0.4 | 140 | 68 | 130 |
| | 16:00 | 70 | 84 | 167 | 8.5 | 16 | 200 | 0.4 | 135 | 62 | 130 |
| | 18:00 | 70 | 84 | 166 | 8.5 | 16 | 195 | 0.4 | 135 | 63 | 125 |
| | 20:00 | 70 | 85 | 165 | 8.5 | 16 | 200 | 0.4 | 135 | 63 | 130 |
| | 22:00 | 70 | 85 | 164 | 8.5 | 16 | 200 | 0.4 | 137 | 62 | 130 |
| | 24:00 | 70 | 86 | 165 | 8.5 | 16 | 200 | 0.4 | 140 | 62 | 130 |
| 4/30/93 | 2:00 | 70 | 85 | 165 | 8.5 | 16 | 200 | 0.4 | 140 | 61 | 130 |
| | 4:00 | 70 | 85 | 163 | 8.5 | 16 | 200 | 0.4 | 139 | 60 | 130 |
| | 6:00 | 70 | 85 | 165 | 8.5 | 16 | 200 | 0.4 | 140 | 60 | 130 |
| | 8:00 | 70 | 85 | 160 | 8.5 | 16 | 200 | 0.4 | 135 | 58 | 130 |
| | 10:00 | 70 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 140 | 70 | 130 |
| | 12:00 | 65 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 135 | 69 | 135 |
| | 14:00 | 68 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 130 | 68 | 132 |
| | 16:00 | 70 | 85 | 160 | 8.5 | 16 | 200 | 0.4 | 135 | 72 | 130 |
| | 18:00 | 67 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 133 | 66 | 133 |
| | 20:00 | 63 | 84 | 159 | 8.5 | 16 | 200 | 0.4 | 135 | 64 | 137 |
| | 22:00 | 63 | 84 | 158 | 8.5 | 16 | 200 | 0.4 | 132 | 63 | 137 |
| | 24:00 | 65 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 134 | 62 | 135 |
| 5/1/93 | 2:00 | 65 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 135 | 61 | 135 |
| | 4:00 | 65 | 84 | 160 | 8.5 | 16 | 200 | 0.4 | 140 | 62 | 135 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|--------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 6:00 | 60 | 84 | 160 | 9 | 16 | 200 | 0.4 | 140 | 62 | 140 |
| | 8:00 | 60 | 84 | 156 | 8.5 | 16 | 200 | 0.4 | 130 | 63 | 140 |
| | 10:00 | 60 | 84 | 155 | 8.5 | 16 | 200 | 0.4 | 130 | 64 | 140 |
| | 12:00 | 60 | 84 | 160 | 8.5 | 16.5 | 200 | 0.4 | 131 | 73 | 140 |
| | 14:00 | 60 | 84 | 161 | 8.5 | 16 | 200 | 0.4 | 135 | 78 | 140 |
| | 16:00 | 60 | 84 | 163 | 8.5 | 16.5 | 200 | 0.4 | 135 | 82 | 140 |
| | 18:00 | 63 | 84 | 163 | 8.5 | 16 | 200 | 0.4 | 130 | 80 | 137 |
| | 20:00 | 63 | 84 | 158 | 8.5 | 16 | 200 | 0.4 | 125 | 77 | 137 |
| | 22:00 | 60 | 84 | 155 | 8 | 16 | 200 | 0.4 | 110 | 74 | 140 |
| | 24:00 | 60 | 84 | 153 | 8 | 16 | 200 | 0.4 | 110 | 70 | 140 |
| 5/2/93 | 2:00 | 60 | 84 | 152 | 8 | 16 | 200 | 0.4 | 109 | 70 | 140 |
| | 4:00 | 60 | 84 | 150 | 8.5 | 16 | 200 | 0.4 | 109 | 60 | 140 |
| | 6:00 | 60 | 84 | 149 | 8.5 | 16 | 200 | 0.4 | 109 | 60 | 140 |
| | 8:00 | 60 | 85 | 149 | 8.5 | 16 | 200 | 0.4 | 110 | 57 | 140 |
| | 10:00 | 60 | 85 | 149 | 8.5 | 16 | 200 | 0.4 | 115 | 68 | 140 |
| | 12:00 | 60 | 85 | 148 | 8.5 | 16 | 200 | 0.4 | 115 | 68 | 140 |
| | 14:00 | 63 | 84 | 150 | 8.5 | 16 | 200 | 0.4 | 120 | 74 | 137 |
| | 16:00 | 60 | 86 | 153 | 8.5 | 16 | 200 | 0.4 | 125 | 76 | 140 |
| | 18:00 | 60 | 86 | 155 | 8.5 | 16 | 200 | 0.4 | 120 | 74 | 140 |
| | 20:00 | 60 | 87 | 155 | 8.5 | 16 | 200 | 0.4 | 120 | 70 | 140 |
| | 22:00 | 60 | 85 | 150 | 8.5 | 16 | 200 | 0.4 | 120 | 70 | 140 |
| | 24:00 | 60 | 82 | 150 | 8.5 | 16 | 200 | 0.4 | 120 | 60 | 140 |
| 5/3/93 | 2:00 | 60 | 85 | 151 | 8.5 | 16 | 200 | 0.4 | 121 | 60 | 140 |
| | 4:00 | 60 | 85 | 150 | 8 | 16 | 200 | 0.4 | 120 | 59 | 140 |
| | 6:00 | 60 | 85 | 151 | 8 | 16 | 200 | 0.4 | 120 | 58 | 140 |
| | 8:00 | 60 | 85 | 150 | 8 | 16 | 200 | 0.4 | 120 | 62 | 140 |
| | 10:00 | 60 | 88 | 155 | 8 | 16 | 200 | 0.4 | 120 | 76 | 140 |
| | 12:00 | 60 | 89 | 160 | 8 | 16 | 200 | 0.4 | 125 | 80 | 140 |
| | 14:00 | 60 | 89 | 160 | 8 | 16 | 200 | 0.4 | 130 | 82 | 140 |
| | 16:00 | 80 | 90 | 163 | 8 | 16 | 200 | 0.4 | 130 | 82 | 120 |
| | 18:00 | 75 | 90 | 163 | 8 | 16 | 200 | 0.4 | 130 | 82 | 125 |
| | 20:00 | 80 | 89 | 160 | 8 | 15 | 200 | 0.4 | 125 | 76 | 120 |
| | 22:00 | 80 | 88 | 158 | 8 | 15 | 200 | 0.4 | 124 | 74 | 120 |
| | 24:00 | 80 | 86 | 150 | 8 | 15 | 200 | 0.4 | 125 | 64 | 120 |
| 5/4/93 | 2:00 | 80 | 87 | 152 | 8 | 15 | 200 | 0.4 | 125 | 64 | 120 |
| | 4:00 | 87 | 88 | 154 | 8 | 15 | 200 | 0.4 | 122 | 64 | 113 |
| | 6:00 | 86 | 87 | 155 | 8 | 15 | 200 | 0.4 | 128 | 64 | 114 |
| | 8:00 | 85 | 87 | 155 | 8 | 15 | 200 | 0.4 | 120 | 66 | 115 |
| | 10:00 | 85 | 87 | 155 | 8 | 15 | 200 | 0.4 | 120 | 67 | 115 |
| | 12:00 | 85 | 87 | 155 | 8 | 15 | 200 | 0.4 | 120 | 69 | 115 |
| | 14:00 | 85 | 87 | 157 | 8 | 16 | 200 | 0.4 | 125 | 73 | 115 |
| | 16:00 | 85 | 88 | 160 | 8 | 15.5 | 200 | 0.4 | 130 | 76 | 115 |
| | 18:00 | 84 | 88 | 160 | 8 | 16 | 200 | 0.4 | 130 | 78 | 116 |
| | 20:00 | 85 | 87 | 160 | 8 | 16 | 200 | 0.4 | 125 | 76 | 115 |
| | 22:00 | 85 | 86 | 155 | 8 | 16 | 200 | 0.4 | 125 | 75 | 115 |
| | 24:00 | 85 | 87 | 157 | 8 | 16 | 200 | 0.4 | 126 | 74 | 115 |
| 5/5/93 | 2:00 | 85 | 87 | 156 | 8 | 16 | 200 | 0.4 | 125 | 70 | 115 |
| | 4:00 | 85 | 87 | 155 | 8 | 16 | 200 | 0.4 | 130 | 66 | 115 |
| | 6:00 | 85 | 86 | 155 | 8 | 16 | 200 | 0.4 | 125 | 60 | 115 |
| | 8:00 | 85 | 87 | 155 | 8 | 15 | 200 | 0.4 | 125 | 60 | 115 |
| | 10:00 | 85 | 87 | 155 | 8 | 15 | 200 | 0.4 | 125 | 60 | 115 |
| | 12:00 | 90 | 87 | 157 | 8.5 | 16 | 200 | 0.4 | 130 | 63 | 110 |
| | 14:00 | 89 | 87 | 157 | 8.5 | 16 | 200 | 0.4 | 135 | 60 | 111 |
| | 16:00 | 89 | 87 | 157 | 8.5 | 16 | 200 | 0.4 | 137 | 60 | 111 |
| | 18:00 | 89 | 88 | 157 | 8.5 | 16 | 200 | 0.4 | 135 | 60 | 111 |

IITRI OPERATING DATA

| | | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| Date | Time | | | | | | | | | | |
| | 20:00 | 89 | 88 | 157 | 8.5 | 16 | 200 | 0.4 | 135 | 60 | 111 |
| | 22:00 | 88 | 87 | 155 | 8.5 | 16 | 200 | 0.4 | 130 | | 112 |
| | 24:00 | 88 | 87 | 156 | 8 | 16 | 200 | 0.4 | 130 | 60 | 112 |
| 5/6/93 | 2:00 | 88 | 86 | 155 | 8 | 16 | 200 | 0.4 | 127 | 59 | 112 |
| | 4:00 | 88 | 85 | 155 | 8 | 16 | 200 | 0.4 | 130 | 59 | 112 |
| | 6:00 | 87 | 86 | 160 | 8 | 16 | 200 | 0.4 | 135 | 60 | 113 |
| | 8:00 | 90 | 86 | 158 | 8 | 16 | 200 | 0.4 | 130 | 63 | 110 |
| | 10:00 | 85 | 87 | 161 | 8 | 15 | 200 | 0.4 | 130 | 68 | 115 |
| | 12:00 | 85 | 88 | 165 | 8 | 15 | 200 | 0.4 | 135 | 75 | 115 |
| | 14:00 | 90 | 87 | 164 | 8.5 | 16 | 200 | 0.4 | 135 | 77 | 110 |
| | 16:00 | 90 | 87 | 165 | 8 | 16 | 200 | 0.4 | 137 | 80 | 110 |
| | 18:00 | 90 | 87 | 164 | 8 | 16 | 200 | 0.4 | 137 | 80 | 110 |
| | 20:00 | 87 | 87 | 162 | 8 | 16 | 200 | 0.4 | 130 | 78 | 113 |
| | 22:00 | 87 | 87 | 162 | 8 | 16 | 200 | 0.4 | 130 | 78 | 113 |
| | 24:00 | 87 | 87 | 161 | 8 | 16 | 200 | 0.4 | 130 | 70 | 113 |
| 5/7/93 | 2:00 | 85 | 87 | 160 | 8 | 16 | 200 | 0.4 | 130 | 68 | 115 |
| | 4:00 | 85 | 86 | 160 | 8 | 16 | 200 | 0.4 | 130 | 68 | 115 |
| | 6:00 | 85 | 86 | 161 | 8 | 16 | 200 | 0.4 | 132 | 68 | 115 |
| | 8:00 | 85 | 86 | 160 | 8 | 16 | 200 | 0.4 | 132 | 69 | 115 |
| | 10:00 | 80 | 86 | 160 | 8 | 16 | 200 | 0.4 | 130 | 70 | 120 |
| | 12:00 | 75 | 86 | 162 | 8 | 16 | 200 | 0.4 | 127 | 79 | 125 |
| | 14:00 | 75 | 86 | 162 | 8 | 16 | 200 | 0.5 | 126 | 77 | 125 |
| | 16:00 | 75 | 86 | 162 | 8 | 15 | 200 | 0.5 | 125 | 69 | 125 |
| | 18:00 | 80 | 84 | 160 | 8 | 15 | 200 | 0.5 | 125 | 65 | 120 |
| | 20:00 | 80 | 86 | 160 | 8 | 15 | 200 | 0.4 | 125 | 65 | 120 |
| | 22:00 | 85 | 86 | 160 | 8 | 15 | 200 | 0.4 | 125 | 64 | 115 |
| | 24:00 | 85 | 86 | 160 | 8 | 15 | 200 | 0.4 | 130 | 62 | 115 |
| 5/8/93 | 2:00 | 85 | 87 | 160 | 8 | 15 | 200 | 0.4 | 125 | 62 | 115 |
| | 4:00 | 85 | 86 | 161 | 8 | 15 | 200 | 0.4 | 130 | 62 | 115 |
| | 6:00 | 85 | 86 | 158 | 8 | 15 | 200 | 0.4 | 130 | 62 | 115 |
| | 8:00 | 85 | 86 | 158 | 8 | 15 | 200 | 0.4 | 130 | 62 | 115 |
| | 10:00 | | 86 | 156 | 8 | 15 | 200 | 0.4 | 124 | 64 | 115 |
| | 12:00 | | 86 | 157 | 8 | 15 | 200 | 0.5 | 124 | 68 | 200 |
| | 14:00 | | 86 | 159 | 8 | 15 | 200 | 0.5 | 123 | 71 | 200 |
| | 16:00 | | 86 | 160 | 8 | 15 | 200 | 0.5 | 123 | 73 | 200 |
| | 18:00 | | 86 | 159 | 8 | 15 | 200 | 0.5 | 125 | 71 | 200 |
| | 20:00 | | 86 | 159 | 8 | 15 | 200 | 0.4 | 125 | 69 | 200 |
| | 22:00 | | 86 | 160 | 8 | 15 | 200 | 0.4 | 122 | 67 | 200 |
| | 24:00 | | 86 | 160 | 8 | 15 | 200 | 0.4 | 125 | 67 | 200 |
| 5/9/93 | 2:00 | | 86 | 160 | 8 | 15 | 200 | 0.4 | 130 | 66 | 200 |
| | 4:00 | | 86 | 157 | 8 | 15 | 200 | 0.4 | 130 | 64 | 200 |
| | 6:00 | | 86 | 155 | 8 | 15 | 200 | 0.4 | 130 | 64 | 200 |
| | 8:00 | | 86 | 157 | 8 | 15 | 200 | 0.4 | 130 | 64 | 200 |
| | 10:00 | | 86 | 157 | 8 | 15 | 200 | 0.4 | 121 | 65 | 200 |
| | 12:00 | | 86 | 159 | 8 | 15 | 200 | 0.4 | 122 | 68 | 200 |
| | 14:00 | | 87 | 163 | 8 | 16 | 200 | 0.4 | 124 | 70 | 200 |
| | 16:00 | | 87 | 164 | 8 | 16 | 200 | 0.4 | 127 | 74 | 200 |
| | 18:00 | | 87 | 164 | 8 | 16 | 200 | 0.4 | 127 | 77 | 200 |
| | 20:00 | | 87 | 163 | 8 | 16 | 200 | 0.4 | 127 | 77 | 200 |
| | 22:00 | | 87 | 159 | 8 | 16 | 200 | 0.4 | 125 | 73 | 200 |
| | 24:00 | | 86 | 155 | 8 | 15 | 200 | 0.4 | 110 | 65 | 200 |
| 5/10/93 | 2:00 | | 87 | 155 | 8 | 15 | 200 | 0.4 | 115 | 58 | 200 |
| | 4:00 | | 87 | 155 | 8 | 15 | 200 | 0.4 | 120 | 56 | 200 |
| | 6:00 | | 86 | 152 | 8 | 15 | 200 | 0.4 | 120 | 56 | 200 |
| | 8:00 | | 87 | 154 | 8 | 15 | 200 | 0.4 | 120 | 57 | 200 |

IITRI OPERATING DATA

| | | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| Date | Time | | | | | | | | | | |
| | 10:00 | | 88 | 156 | 8 | 15 | 210 | 0.4 | 121 | 64 | 210 |
| | 12:00 | 80 | 88 | 159 | 8 | 15 | 210 | 0.4 | 123 | 68 | 130 |
| | 14:00 | 85 | 89 | 163 | 8 | 15 | 210 | 0.4 | 125 | 71 | 125 |
| | 16:00 | 85 | 89 | 163 | 8 | 15 | 210 | 0.4 | 125 | 72 | 125 |
| | 18:00 | 80 | 90 | 165 | 8 | 15 | 210 | 0.4 | 127 | 74 | 130 |
| | 20:00 | 80 | 90 | 165 | 8 | 15 | 205 | 0.4 | 127 | 70 | 125 |
| | 22:00 | 80 | 88 | 160 | 8 | 15 | 205 | 0.4 | 127 | 68 | 125 |
| | 24:00 | 80 | 88 | 159 | 8 | 15 | 205 | 0.4 | 125 | 50 | 125 |
| 5/11/93 | 2:00 | 80 | 88 | 160 | 8 | 15 | 210 | 0.4 | 125 | 50 | 130 |
| | 4:00 | 82 | 88 | 160 | 8 | 15 | 210 | 0.4 | 125 | 52 | 128 |
| | 6:00 | 80 | 88 | 155 | 8 | 15 | 210 | 0.4 | 120 | 54 | 130 |
| | 8:40 | 75 | 87 | 156 | 8 | 15 | 210 | 0.4 | 120 | 65 | 135 |
| | 10:00 | 75 | 88 | 158 | 8 | 15 | 210 | 0.4 | 121 | 72 | 135 |
| | 12:00 | 75 | 88 | 160 | 8 | 15 | 210 | 0.4 | 123 | 79 | 135 |
| | 14:00 | 80 | 89 | 162 | 7 | 15 | 210 | 0.4 | 124 | 82 | 130 |
| | 16:00 | 60 | 90 | 162 | 7 | 15 | 210 | 0.4 | 125 | 84 | 150 |
| | 18:00 | 70 | 90 | 162 | 7 | 15 | 200 | 0.4 | 125 | 84 | 130 |
| | 20:00 | 80 | 90 | 163 | 7 | 15 | 200 | 0.4 | 125 | 78 | 120 |
| | 22:00 | 80 | 88 | 161 | 7 | 15 | 200 | 0.4 | 123 | 70 | 120 |
| | 24:00 | | | | | | | | | | |
| 5/12/93 | 2:00 | 80 | 87 | 159 | 7 | 15 | 200 | 0.4 | 122 | 64 | 120 |
| | 4:00 | 80 | 87 | 152 | 7.5 | 15 | 205 | 0.4 | 110 | 64 | 125 |
| | 6:00 | 81 | 87 | 155 | 7.5 | 15 | 205 | 0.4 | 115 | 65 | 124 |
| | 8:00 | 80 | 88 | 153 | 8 | 15 | 210 | 0.4 | 115 | 69 | 130 |
| | 12:45 | 80 | 89 | 160 | 8 | 15 | 210 | 0.4 | 118 | 82 | 130 |
| | 14:00 | 80 | 89 | 161 | 8 | 15 | 210 | 0.4 | 118 | 80 | 130 |
| | 16:00 | 75 | 90 | 160 | 7 | 15 | 210 | 0.4 | 120 | 81 | 135 |
| | 18:00 | 75 | 90 | 162 | 8 | 15 | 210 | 0.4 | 120 | 78 | 135 |
| | 20:00 | 80 | 88 | 160 | 8 | 15 | 210 | 0.4 | 120 | 76 | 130 |
| | 22:00 | 80 | 88 | 155 | 8 | 15 | 210 | 0.4 | 120 | 72 | 130 |
| | 24:00 | 80 | 88 | 154 | 8 | 15 | 210 | 0.4 | 122 | 70 | 130 |
| 5/13/93 | 2:00 | 80 | 88 | 155 | 7.5 | 15 | 210 | 0.4 | 120 | 62 | 130 |
| | 4:00 | 80 | 87 | 154 | 7.5 | 15 | 210 | 0.4 | 119 | 56 | 130 |
| | 6:00 | 80 | 87 | 155 | 7.5 | 15 | 210 | 0.4 | 120 | 56 | 130 |
| | 8:00 | 80 | 86 | 153 | 8 | 15 | 210 | 0.4 | 116 | 66 | 130 |
| | 10:00 | 75 | 84 | 158 | 8 | 15 | 210 | 0.4 | 119 | 78 | 135 |
| | 12:00 | 75 | 84 | 162 | 8 | 15 | 210 | 0.4 | 121 | 82 | 135 |
| | 14:00 | 75 | 85 | 165 | 8 | 15 | 210 | 0.4 | 121 | 80 | 135 |
| | 16:00 | 75 | 88 | 166 | 8 | 15 | 210 | 0.4 | 125 | 84 | 135 |
| | 18:00 | 70 | 88 | 166 | 8 | 15 | 210 | 0.4 | 125 | 84 | 140 |
| | 20:00 | 80 | 88 | 165 | 8 | 15 | 210 | 0.4 | 125 | 76 | 130 |
| | 22:00 | 80 | 87 | 163 | 8 | 15 | 210 | 0.4 | 120 | 70 | 130 |
| | 24:00 | 80 | 83 | 159 | 7.5 | 15 | 210 | 0.4 | 120 | 64 | 130 |
| 5/14/93 | 2:00 | 80 | 84 | 160 | 7.5 | 15 | 210 | 0.4 | 120 | 63 | 130 |
| | 4:00 | 80 | 84 | 155 | 7.5 | 15 | 205 | 0.4 | 115 | 62 | 125 |
| | 6:00 | 80 | 84 | 155 | 7.5 | 15 | 205 | 0.4 | 115 | 58 | 125 |
| | 8:00 | 80 | 84 | 155 | 7 | 15 | 210 | 0.4 | 116 | 73 | 130 |
| | 10:00 | 85 | 84 | 158 | 7 | 15 | 210 | 0.4 | 120 | 77 | 125 |
| | 12:00 | 80 | 86 | 164 | 8 | 15 | 210 | 0.4 | 121 | 86 | 130 |
| | 14:00 | 70 | 86 | 165 | 8 | 15 | 210 | 0.4 | 126 | 89 | 140 |
| | 16:00 | 70 | 87 | 165 | 8 | 15 | 210 | 0.4 | 128 | 89 | 140 |
| | 18:00 | 65 | 86 | 165 | 8 | 15 | 210 | 0.4 | 130 | 85 | 145 |
| | 20:00 | 80 | 85 | 163 | 8 | 15 | 210 | 0.4 | 125 | 80 | 130 |
| | 22:00 | 80 | 84 | 160 | 8 | 15 | 210 | 0.4 | 120 | 74 | 130 |
| | 24:00 | 90 | 84 | 157 | 8 | 15 | 210 | 0.4 | 110 | 69 | 120 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| 5/15/93 | 2:00 | 90 | 84 | 156 | 8 | 15 | 210 | 0.4 | 110 | 64 | 120 |
| | 4:00 | 90 | 84 | 156 | 8 | 15 | 210 | 0.4 | 110 | 62 | 120 |
| | 6:00 | 90 | 84 | 156 | 8 | 15 | 210 | 0.4 | 110 | 60 | 120 |
| | 8:00 | 80 | 84 | 156 | 7 | 15 | 210 | 0.4 | 117 | 77 | 130 |
| | 10:00 | 75 | 85 | 160 | 7 | 15 | 210 | 0.4 | 120 | 87 | 135 |
| | 12:00 | 80 | 85 | 165 | 7 | 15 | 210 | 0.4 | 122 | 88 | 130 |
| | 14:00 | 80 | 86 | 165 | 7 | 15 | 210 | 0.4 | 127 | 91 | 130 |
| | 16:00 | 80 | 86 | 165 | 7 | 15 | 210 | 0.4 | 129 | 89 | 130 |
| | 18:00 | 70 | 87 | 165 | 7 | 15 | 210 | 0.4 | 130 | 88 | 140 |
| | 20:00 | 70 | 86 | 165 | 7 | 15 | 210 | 0.4 | 127 | 80 | 140 |
| | 22:00 | 85 | 84 | 155 | 7 | 15 | 210 | 0.4 | 125 | 76 | 125 |
| | 24:00 | 80 | 84 | 155 | 7 | 15 | 210 | 0.4 | 115 | 72 | 130 |
| 5/16/93 | 2:00 | 85 | 84 | 154 | 7 | 15 | 210 | 0.4 | 115 | 68 | 125 |
| | 4:00 | 85 | 84 | 155 | 7 | 15 | 210 | 0.4 | 115 | 65 | 125 |
| | 6:00 | 85 | 83 | 155 | 7 | 15 | 210 | 0.4 | 115 | 63 | 125 |
| | 8:00 | 80 | 83 | 155 | 7 | 15 | 210 | 0.4 | 115 | 68 | 130 |
| | 10:00 | 80 | 84 | 157 | 7 | 15 | 210 | 0.4 | 119 | 76 | 130 |
| | 12:00 | 80 | 85 | 161 | 7 | 15 | 210 | 0.4 | 121 | 83 | 130 |
| | 14:00 | 85 | 86 | 163 | 7 | 15 | 210 | 0.4 | 125 | 86 | 125 |
| | 16:00 | 85 | 86 | 165 | 7 | 15 | 210 | 0.4 | 125 | 88 | 125 |
| | 18:00 | 80 | 86 | 165 | 7 | 15 | 210 | 0.4 | 125 | 88 | 130 |
| | 20:00 | 80 | 84 | 160 | 7 | 15 | 210 | 0.4 | 120 | 80 | 130 |
| | 22:00 | 80 | 84 | 157 | 7 | 15 | 210 | 0.4 | 120 | 76 | 130 |
| | 24:00 | 80 | 84 | 155 | 7 | 15 | 210 | 0.4 | 120 | 70 | 130 |
| 5/17/93 | 2:00 | 80 | 85 | 158 | 7 | 15 | 210 | 0.4 | 120 | 68 | 130 |
| | 4:00 | 80 | 84 | 155 | 7 | 15 | 210 | 0.4 | 115 | 68 | 130 |
| | 6:00 | 80 | 84 | 154 | 7 | 15 | 210 | 0.4 | 118 | 70 | 130 |
| | 8:00 | 80 | 84 | 154 | 7 | 15 | 210 | 0.4 | 115 | 70 | 130 |
| | 10:00 | 80 | 85 | 155 | 7 | 15 | 210 | 0.4 | 118 | 73 | 130 |
| | 12:00 | 80 | 86 | 161 | 7 | 15 | 210 | 0.4 | 120 | 80 | 130 |
| | 14:00 | 85 | 88 | 165 | 7 | 15 | 210 | 0.4 | | | 125 |
| | 16:00 | 80 | 86 | 159 | 7 | 15 | 210 | 0.4 | 122 | 88 | 130 |
| | 18:00 | 80 | 87 | 160 | 7 | 15 | 210 | 0.4 | 125 | 85 | 130 |
| | 20:00 | 80 | 88 | 160 | 7 | 15 | 210 | 0.4 | 123 | 82 | 130 |
| | 22:00 | 83 | 84 | 155 | 7 | 15 | 210 | 0.4 | 120 | 76 | 127 |
| | 24:00 | 80 | 84 | 154 | 7 | 15 | 210 | 0.4 | 115 | 73 | 130 |
| 5/18/93 | 2:00 | 80 | 84 | 156 | 7 | 15 | 210 | 0.4 | 117 | 72 | 130 |
| | 4:00 | 80 | 83 | 154 | 7 | 14 | 210 | 0.4 | 113 | 64 | 130 |
| | 6:00 | 80 | 84 | 154 | 7 | 15 | 210 | 0.4 | 115 | 63 | 130 |
| | 8:00 | 80 | 84 | 157 | 7 | 15 | 210 | 0.4 | 120 | 67 | 130 |
| | 10:00 | 85 | 84 | 160 | 7 | 15 | 210 | 0.4 | 120 | 65 | 125 |
| | 12:00 | 80 | 84 | 150 | 7 | 15 | 210 | 0.4 | 115 | 65 | 130 |
| | 14:00 | 80 | 85 | 155 | 7 | 15 | 210 | 0.4 | 120 | 78 | 130 |
| | 16:00 | 80 | 85 | 155 | 7 | 15 | 210 | 0.4 | 120 | 82 | 130 |
| | 18:00 | 80 | 86 | 165 | 7 | 15 | 210 | 0.4 | 125 | 80 | 130 |
| | 20:00 | 80 | 86 | 161 | 7 | 15 | 210 | 0.4 | 120 | 76 | 130 |
| | 22:00 | 80 | 86 | 160 | 7 | 15 | 210 | 0.4 | 115 | 76 | 130 |
| | 24:00 | 80 | 85 | 155 | 7 | 15 | 210 | 0.4 | 115 | 65 | 130 |
| 5/19/93 | 2:00 | 80 | 84 | 150 | 7 | 15 | 210 | 0.4 | 113 | 62 | 130 |
| | 4:00 | 80 | 84 | 150 | 7 | 15 | 210 | 0.4 | 111 | 60 | 130 |
| | 6:00 | 80 | 85 | 149 | 7 | 15 | 210 | 0.4 | 110 | 57 | 130 |
| | 8:00 | 80 | 85 | 150 | 7 | 15 | 210 | 0.4 | 115 | 70 | 130 |
| | 10:00 | 80 | 56 | 150 | 7 | 15 | 180 | 0.4 | 115 | 70 | 100 |
| | 12:00 | 80 | 46 | 155 | 7 | 14 | 160 | 0.4 | 120 | 70 | 80 |
| | 14:00 | 80 | 46 | 160 | 7 | 15 | 160 | 0.4 | 120 | 76 | 80 |

IITRI OPERATING DATA

| | | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| Date | Time | | | | | | | | | | |
| | 16:00 | 55 | 45 | 160 | 7 | 14 | 160 | 0.4 | 115 | 74 | 105 |
| | 18:00 | 60 | 46 | 160 | 7 | 14 | 160 | 0.4 | 125 | 74 | 100 |
| | 20:00 | 60 | 46 | 155 | 7 | 15 | 160 | 0.4 | 120 | 70 | 100 |
| | 22:00 | 60 | 45 | 152 | 7 | 14 | 160 | 0.4 | 110 | 64 | 100 |
| | 24:00 | 65 | 46 | 151 | 7 | 14 | 160 | 0.4 | 114 | 59 | 95 |
| 5/20/93 | 2:00 | 65 | 46 | 149 | 7 | 14 | 160 | 0.4 | 114 | 55 | 95 |
| | 4:00 | 70 | 46 | 148 | 7 | 14 | 160 | 0.4 | 112 | 53 | 90 |
| | 6:00 | 65 | 46 | 147 | 7 | 14 | 160 | 0.4 | 112 | 52 | 95 |
| | 8:00 | 60 | 46 | 148 | 7 | 14 | 155 | 0.4 | 110 | 60 | 95 |
| | 10:00 | 60 | 45 | 150 | 7 | 14 | 155 | 0.4 | 110 | 63 | 95 |
| | 12:00 | 60 | 46 | 152 | 7 | 14 | 157 | 0.4 | 115 | 70 | 97 |
| | 14:00 | 55 | 46 | 155 | 7 | 14 | 160 | 0.4 | 115 | 76 | 105 |
| | 16:00 | 55 | 46 | 154 | 7 | 14 | 160 | 0.4 | 115 | 76 | 105 |
| | 18:00 | 56 | 46 | 155 | 7 | 14 | 160 | 0.4 | 115 | 69 | 100 |
| | 20:00 | 60 | 46 | 152 | 7 | 14 | 160 | 0.4 | 110 | 66 | 105 |
| | 22:00 | 55 | 44 | 148 | 7 | 14 | 160 | 0.4 | 110 | 61 | 105 |
| | 24:00 | 55 | 44 | 144 | 7 | 14 | 160 | 0.4 | 108 | 61 | 105 |
| 5/21/93 | 2:00 | 55 | 44 | 144 | 7 | 13 | 160 | 0.4 | 108 | 58 | 105 |
| | 4:00 | 55 | 44 | 144 | 7 | 13 | 160 | 0.4 | 108 | 54 | 105 |
| | 6:00 | 55 | 44 | 144 | 7 | 14 | 160 | 0.4 | 107 | 53 | 105 |
| | 8:00 | 55 | 44 | 144 | 7 | 14 | 160 | 0.4 | 106 | 56 | 105 |
| | 10:00 | 55 | 44 | 145 | 7 | 14 | 160 | 0.4 | 110 | 69 | 105 |
| | 12:00 | 55 | 44 | 148 | 7 | 14 | 160 | 0.4 | 112 | 76 | 105 |
| | 14:00 | 55 | 45 | 151 | 7 | 15 | 160 | 0.4 | 115 | 76 | 105 |
| | 16:00 | 60 | 46 | 152 | 7 | 15 | 160 | 0.4 | 115 | 76 | 100 |
| | 18:00 | 60 | 46 | 150 | 7 | 14 | 160 | 0.4 | 115 | 74 | 105 |
| | 20:00 | 55 | 46 | 147 | 7 | 14 | 160 | 0.4 | 115 | 61 | 105 |
| | 22:00 | 55 | 46 | 145 | 7 | 14 | 160 | 0.4 | 104 | 61 | 100 |
| | 24:00 | 60 | 45 | 142 | 7 | 13 | 160 | 0.4 | 105 | 60 | 100 |
| 5/22/93 | 2:00 | 60 | 45 | 142 | 7 | 13 | 160 | 0.4 | 105 | 60 | 100 |
| | 4:00 | 60 | 45 | 142 | 7 | 13 | 160 | 0.4 | 105 | 60 | 100 |
| | 6:00 | 60 | 46 | 142 | 7 | 13 | 160 | 0.4 | 105 | 62 | 100 |
| | 8:00 | 60 | 46 | 144 | 7 | 13 | 160 | 0.4 | 105 | 62 | 100 |
| | 10:00 | 60 | 46 | 145 | 7 | 13 | 160 | 0.4 | 110 | 68 | 100 |
| | 12:00 | 60 | 46 | 145 | 7 | 13 | 160 | 0.4 | 112 | 69 | 100 |
| | 14:00 | 60 | 46 | 147 | 7 | 13 | 160 | 0.4 | 110 | 65 | 90 |
| | 16:00 | 60 | 46 | 145 | 7 | 14 | 150 | 0.4 | 110 | 65 | 100 |
| | 18:00 | 60 | 49 | 145 | 8 | 15 | 160 | 0.4 | 110 | 61 | 100 |
| | 20:00 | 60 | 50 | 150 | 8 | 14 | 160 | 0.5 | 110 | 62 | 100 |
| | 22:00 | 60 | 49 | 150 | 8 | 15 | 160 | 0.5 | 120 | 62 | 105 |
| | 24:00 | 55 | 48 | 149 | 8 | 14 | 160 | 0.5 | 119 | 63 | 105 |
| 5/23/93 | 2:00 | 60 | 48 | 149 | 8 | 14 | 160 | 0.4 | 120 | 63 | 100 |
| | 4:00 | 60 | 48 | 151 | 8 | 14 | 160 | 0.4 | 120 | 63 | 100 |
| | 6:19 | 55 | 48 | 147 | 8 | 14 | 160 | 0.4 | 119 | 54 | 105 |
| | 8:15 | 60 | 48 | 145 | 8 | 14 | 160 | 0.4 | 120 | 54 | 100 |
| | 10:00 | 60 | 48 | 150 | 8 | 14 | 160 | 0.4 | 125 | 57 | 100 |
| | 12:00 | 60 | 48 | 150 | 8 | 14 | 160 | 0.4 | 120 | 57 | 100 |
| | 14:00 | 60 | 48 | 146 | 8 | 14 | 160 | 0.4 | 120 | 57 | 100 |
| | 16:00 | 60 | 48 | 145 | 8 | 14 | 160 | 0.4 | 121 | 57 | 100 |
| | 18:00 | 60 | 48 | 152 | 8 | 14 | 160 | 0.4 | 125 | 56 | 100 |
| | 20:00 | 55 | 49 | 155 | 8 | 14 | 170 | 0.4 | 125 | 60 | 115 |
| | 22:00 | 55 | 50 | 155 | 8 | 14 | 165 | 0.4 | 125 | 60 | 110 |
| | 24:00 | 55 | 48 | 154 | 8 | 14 | 170 | 0.4 | 122 | 57 | 115 |
| 5/24/93 | 2:00 | 60 | 48 | 153 | 8 | 14 | 170 | 0.4 | 122 | 55 | 110 |
| | 4:00 | 60 | 48 | 152 | 8 | 14 | 170 | 0.4 | 120 | 54 | 110 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 6:00 | 60 | 48 | 152 | 8 | 14 | 170 | 0.4 | 120 | 54 | 110 |
| | 8:00 | 60 | 48 | 152 | 8 | 14 | 170 | 0.4 | 120 | 60 | 110 |
| | 10:00 | 60 | 46 | 155 | 8 | 14 | 180 | 0.4 | 125 | 65 | 120 |
| | 12:00 | 80 | 92 | 157 | 8 | 15 | 210 | 0.4 | 125 | 68 | 130 |
| | 14:00 | 75 | 90 | 157 | 8 | 15 | 210 | 0.4 | 125 | | 135 |
| | 16:00 | 75 | 90 | 158 | 8 | 15 | 210 | 0.4 | 120 | 70 | 135 |
| | 18:00 | 78 | 91 | 158 | 8 | 15 | 211 | 0.4 | 120 | 68 | 133 |
| | 20:00 | 75 | 92 | 155 | 8 | 15 | 210 | 0.4 | 116 | 67 | 135 |
| | 22:00 | 80 | 91 | 154 | 8 | 15 | 210 | 0.4 | 120 | 62 | 130 |
| | 24:00 | 75 | 92 | 153 | 8 | 15 | 220 | 0.4 | 115 | 60 | 145 |
| 5/25/93 | 2:00 | 80 | 93 | 153 | 8 | 15 | 230 | 0.4 | 115 | 56 | 150 |
| | 4:00 | 80 | 93 | 151 | 8 | 15 | 230 | 0.4 | 114 | 55 | 150 |
| | 6:00 | 80 | 93 | 151 | 8 | 15 | 230 | 0.4 | 114 | 54 | 150 |
| | 8:00 | 80 | 92 | 152 | 8 | 15 | 230 | 0.4 | 115 | 66 | 150 |
| | 10:00 | 75 | 92 | 154 | 8 | 15 | 230 | 0.4 | 120 | 68 | 155 |
| | 12:00 | 80 | 92 | 155 | 8 | 15 | 230 | 0.4 | 122 | 70 | 150 |
| | 14:00 | 80 | 94 | 155 | 8 | 15 | 220 | 0.4 | 120 | 74 | 140 |
| | 16:00 | 80 | 85 | 156 | 8 | 15 | 210 | 0.4 | 120 | 75 | 130 |
| | 18:00 | 80 | 84 | 154 | 8 | 15 | 210 | 0.4 | 120 | 76 | 130 |
| | 20:00 | 80 | 84 | 153 | 8 | 15 | 210 | 0.4 | 115 | 70 | 130 |
| | 22:00 | 75 | 84 | 150 | 8 | 15 | 210 | 0.4 | 115 | 66 | 135 |
| | 24:00 | 75 | 84 | 149 | 8 | 15 | 220 | 0.4 | 113 | 62 | 145 |
| 5/26/93 | 2:00 | 75 | 84 | 149 | 8 | 15 | 220 | 0.4 | 113 | 61 | 145 |
| | 4:00 | 75 | 84 | 15 | 8 | 15 | 220 | 0.4 | 114 | 60 | 145 |
| | 6:00 | 75 | 84 | 149 | 8 | 15 | 220 | 0.4 | 113 | 60 | 145 |
| | 8:00 | 75 | 86 | 150 | 8 | 15 | 220 | 0.4 | 115 | 65 | 145 |
| | 10:00 | 75 | 86 | 151 | 8 | 15 | 220 | 0.4 | 115 | 68 | 145 |
| | 12:00 | 75 | 86 | 151 | 8 | 16 | 220 | 0.4 | 117 | 70 | 145 |
| | 14:00 | 75 | 86 | 155 | 8 | 16 | 220 | 0.4 | 117 | 72 | 145 |
| | 16:00 | 75 | 86 | 155 | 8 | 16 | 220 | 0.4 | 116 | 74 | 145 |
| | 18:00 | 75 | 86 | 152 | 8 | 16 | 220 | 0.4 | 115 | 72 | 145 |
| | 20:00 | 70 | 86 | 150 | 8 | 16 | 220 | 0.4 | 115 | 68 | 150 |
| | 22:00 | 75 | 86 | 150 | 8 | 16 | 220 | 0.4 | 113 | | 145 |
| | 24:00 | 75 | 84 | 148 | 8 | 15 | 220 | 0.4 | 111 | 63 | 145 |
| 5/27/93 | 2:00 | 75 | 84 | 148 | 8 | 15 | 220 | 0.4 | 110 | 61 | 145 |
| | 4:00 | 75 | 85 | 147 | 8 | 15 | 220 | 0.4 | 110 | 59 | 145 |
| | 6:00 | 75 | 86 | 147 | 8 | 15 | 220 | 0.4 | 110 | 59 | 145 |
| | 8:00 | 75 | 86 | 150 | 8 | 15 | 220 | 0.4 | 112 | 62 | 145 |
| | 10:00 | 75 | 86 | 150 | 8 | 15 | 220 | 0.4 | 115 | 64 | 145 |
| | 12:00 | 75 | 87 | 155 | 8 | 16 | 220 | 0.4 | 115 | 66 | 145 |
| | 14:00 | 75 | 87 | 155 | 8 | 16 | 220 | 0.4 | 120 | | 145 |
| | 16:00 | 75 | 88 | 154 | 8 | 16 | 220 | 0.4 | 118 | 76 | 145 |
| | 18:00 | 72 | 88 | 156 | 8 | 16 | 220 | 0.4 | 118 | 75 | 148 |
| | 20:00 | 75 | 85 | 150 | 8 | 15 | 215 | 0.4 | 110 | 72 | 140 |
| | 22:00 | 75 | 84 | 150 | 8 | 15 | 220 | 0.4 | 112 | 65 | 145 |
| | 24:00 | 75 | 85 | 147 | 8 | 15 | 220 | 0.4 | 108 | 63 | 145 |
| 5/28/93 | 2:00 | 75 | 86 | 147 | 8 | 15 | 220 | 0.4 | 107 | 61 | 145 |
| | 4:00 | 75 | 85 | 147 | 8 | 15 | 220 | 0.4 | 106 | 61 | 145 |
| | 6:00 | 75 | 85 | 147 | 8 | 15 | 220 | 0.4 | 106 | 60 | 145 |
| | 8:00 | 70 | 85 | 148 | 8 | 15 | 210 | 0.4 | 105 | 60 | 140 |
| | 10:00 | 70 | 85 | 150 | 8 | 15 | 210 | 0.4 | 108 | 67 | 140 |
| | 12:00 | 75 | 87 | 156 | 8 | 16 | 215 | 0.4 | 115 | 72 | 140 |
| | 14:00 | 75 | 86 | 159 | 8 | 16 | 210 | 0.4 | 118 | 76 | 135 |
| | 16:00 | 75 | 86 | 150 | 8 | 15 | 210 | 0.4 | 112 | 78 | 135 |
| | 18:00 | 75 | 85 | 150 | 8 | 15 | 210 | 0.4 | 111 | 78 | 135 |

IITRI OPERATING DATA

| | | Inset Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|-------------------------------|----------------------------|----------------------|--------------------------|-------------------------|---------------------------------|----------------------------------|-------------------------------|---------------------|-------------------------|
| Date | Time | | | | | | | | | | |
| 5/29/93 | 20:00 | 75 | 86 | 150 | 8 | 16 | 220 | 0.5 | 115 | 72 | 145 |
| | 22:00 | 70 | 86 | 150 | 8 | 15 | 220 | 0.4 | 115 | 70 | 150 |
| | 24:00 | 75 | 86 | 150 | 8 | 15 | 220 | 0.4 | 113 | 60 | 145 |
| | 2:00 | 75 | 86 | 150 | 8 | 15 | 220 | 0.4 | 110 | 60 | 145 |
| | 4:00 | 75 | 85 | 150 | 8 | 15 | 220 | 0.4 | 108 | 60 | 145 |
| | 6:00 | 75 | 84 | 150 | 8 | 15 | 220 | 0.4 | 108 | 60 | 145 |
| | 8:00 | 75 | 84 | 150 | 8 | 15 | 220 | 0.4 | 108 | 62 | 145 |
| | 10:00 | 75 | 85 | 155 | 8 | 16 | 215 | 0.5 | 110 | 69 | 140 |
| | 12:00 | 75 | 86 | 157 | 8 | 16 | 220 | 0.4 | 112 | 72 | 145 |
| | 14:00 | 70 | 86 | 160 | 8 | 16 | 220 | 0.4 | 120 | 74 | 150 |
| | 16:00 | 75 | 86 | 160 | 8 | 16 | 220 | 0.4 | 120 | 80 | 145 |
| | 18:00 | 75 | 86 | 160 | 8 | 16 | 220 | 0.4 | 122 | 76 | 145 |
| | 20:00 | 75 | 86 | 157 | 8 | 15.5 | 220 | 0.5 | 120 | 80 | 145 |
| | 22:00 | 70 | 84 | 155 | 8 | 15 | 220 | 0.4 | 118 | 74 | 145 |
| | 24:00 | 75 | 84 | 154 | 8 | 15 | 220 | 0.4 | 118 | 74 | 145 |
| 5/30/93 | 2:00 | 75 | 84 | 152 | 8 | 15 | 220 | 0.4 | 115 | 72 | 145 |
| | 4:00 | 75 | 82 | 152 | 8 | 15 | 220 | 0.4 | 113 | 68 | 145 |
| | 6:00 | 75 | 84 | 150 | 8 | 15 | 220 | 0.4 | 110 | 64 | 145 |
| | 8:00 | 75 | 84 | 150 | 8 | 15 | 220 | 0.4 | 110 | 65 | 145 |
| | 10:00 | 75 | 86 | 155 | 8 | 16 | 220 | 0.4 | 110 | 67 | 145 |
| | 12:00 | 75 | 86 | 158 | 8 | 16 | 220 | 0.4 | 114 | 70 | 145 |
| | 14:00 | 75 | 87 | 165 | 8 | 16 | 220 | 0.4 | 130 | 77 | 145 |
| | 16:00 | 75 | 86 | 165 | 8 | 16 | 220 | 0.4 | 135 | 82 | 145 |
| | 18:00 | 75 | 86 | 165 | 8 | 16 | 220 | 0.4 | 135 | 76 | 145 |
| | 20:00 | 75 | 84 | 160 | 8 | 16 | 220 | 0.4 | 120 | 72 | 145 |
| | 22:00 | 75 | 84 | 160 | 8 | 16 | 220 | 0.4 | 120 | 70 | 145 |
| | 24:00 | 75 | 84 | 158 | 8 | 16 | 220 | 0.4 | 120 | 68 | 145 |
| 5/31/93 | 2:00 | 75 | 86 | 155 | 8 | 16 | 220 | 0.4 | 115 | 65 | 145 |
| | 4:00 | 75 | 86 | 152 | 8 | 16 | 220 | 0.4 | 113 | 60 | 145 |
| | 6:00 | 75 | 86 | 150 | 8 | 16 | 220 | 0.4 | 110 | 60 | 145 |
| | 8:00 | 75 | 86 | 155 | 8 | 16 | 220 | 0.4 | 110 | 64 | 145 |
| | 10:00 | 75 | 87 | 160 | 8 | 16 | 220 | 0.4 | 110 | 74 | 145 |
| | 12:00 | 60 | 46 | 164 | 8 | 16 | 185 | 0.4 | 125 | 82 | 125 |
| | 14:00 | 60 | 46 | 165 | 8 | 16 | 190 | 0.4 | 130 | 83 | 130 |
| | 16:00 | 60 | 46 | 165 | 8 | 16 | 190 | 0.4 | 130 | 85 | 130 |
| | 18:00 | 60 | 46 | 164 | 8 | 16 | 190 | 0.4 | 130 | 82 | 130 |
| | 20:00 | 60 | 45 | 161 | 8 | 16 | 190 | 0.4 | 115 | 76 | 130 |
| | 22:00 | 60 | 46 | 161 | 8 | 16 | 190 | 0.4 | 117 | 68 | 130 |
| | 24:00 | 60 | 46 | 155 | 8 | 16 | 190 | 0.4 | 115 | 66 | 130 |
| 6/1/93 | 2:00 | 60 | 46 | 155 | 8 | 16 | 185 | 0.4 | 113 | 64 | 125 |
| | 4:00 | 60 | 46 | 155 | 8 | 16 | 190 | 0.4 | 110 | 62 | 130 |
| | 6:00 | 60 | 46 | 150 | 7 | 16 | 190 | 0.4 | 105 | 60 | 130 |
| | 8:00 | 60 | 46 | 151 | 7 | 16 | 190 | 0.4 | 110 | 64 | 130 |
| | 10:00 | 60 | 44 | 159 | 7 | 16 | 190 | 0.4 | 115 | 72 | 130 |
| | 12:00 | 60 | 44 | 160 | 8 | 16 | 190 | 0.4 | 118 | 76 | 130 |
| | 14:00 | 70 | 44 | 165 | 8 | 15 | 190 | 0.4 | 125 | 76 | 120 |
| | 16:00 | 70 | 46 | 165 | 8 | 15 | 180 | 0.5 | 124 | 78 | 110 |
| | 18:00 | 70 | 44 | 164 | 8 | 15 | 180 | 0.5 | 117 | 76 | 110 |
| | 20:00 | 70 | 44 | 160 | 7 | 14 | 170 | 0.5 | 113 | 73 | 100 |
| | 22:00 | 60 | 44 | 158 | 7 | 14 | 170 | 0.5 | 112 | 69 | 110 |
| | 24:00 | 60 | 44 | 155 | 7 | 15 | 170 | 0.5 | 112 | 67 | 110 |
| 6/2/93 | 2:00 | 60 | 45 | 154 | 7 | 15 | 170 | 0.4 | 110 | 65 | 110 |
| | 4:00 | 70 | 44 | 152 | 7 | 15 | 170 | 0.4 | 108 | 62 | 100 |
| | 6:00 | 70 | 44 | 152 | 7 | 15 | 170 | 0.4 | 105 | 60 | 100 |
| | 8:00 | 70 | 44 | 154 | 7 | 15 | 185 | 0.4 | 110 | 62 | 115 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|-------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| | 10:00 | 70 | 44 | 155 | 7 | 15 | 190 | 0.4 | 110 | 74 | 120 |
| | 12:00 | 70 | 45 | 160 | 7.5 | 15 | 190 | 0.4 | 120 | 80 | 120 |
| | 14:00 | 70 | 45 | 163 | 7.5 | 15 | 190 | 0.4 | 130 | | 120 |
| | 16:00 | 70 | 45 | 164 | 7 | 15 | 180 | 0.5 | 130 | 83 | 110 |
| | 18:00 | 70 | 45 | 164 | 7 | 14 | 180 | 0.5 | 125 | 84 | 110 |
| | 20:00 | 70 | 45 | 162 | 7 | 14 | 180 | 0.4 | 114 | 79 | 110 |
| | 22:00 | 70 | 44 | 137 | 7 | 14 | 180 | 0.4 | 110 | 73 | 110 |
| | 24:00 | 70 | 44 | 155 | 7 | 14 | 180 | 0.4 | 110 | 70 | 110 |
| 6/3/93 | 2:00 | 70 | 44 | 153 | 7 | 14 | 180 | 0.4 | 110 | 68 | 110 |
| | 4:00 | 70 | 44 | 151 | 7 | 14 | 180 | 0.4 | 108 | 66 | 110 |
| | 6:00 | 70 | 45 | 150 | 7 | 14 | 170 | 0.4 | 105 | 64 | 100 |
| | 8:00 | 70 | 45 | 155 | 7 | 14 | 180 | 0.4 | 105 | 68 | 110 |
| | 10:00 | 70 | 45 | 155 | 7 | 14 | 185 | 0.4 | 110 | 72 | 115 |
| | 12:00 | 70 | 44 | 162 | 7 | 15 | 200 | 0.4 | 128 | 80 | 130 |
| | 14:00 | 70 | 44 | 165 | 7 | 15 | 200 | 0.4 | 130 | 84 | 130 |
| | 16:00 | 75 | 86 | 165 | 8 | 16 | 210 | 0.4 | 132 | 85 | 135 |
| 6/4/93 | 8:00 | 70 | 88 | 155 | 8 | 15 | 240 | 0.4 | 100 | 69 | 170 |
| | 9:00 | 70 | 88 | 153 | 8 | 15 | 240 | 0.4 | 105 | 73 | 170 |
| 6/5/93 | 9:00 | 70 | 88 | 145 | 8 | 15 | 240 | 0.4 | 100 | 72 | 170 |
| 6/6/93 | 8:30 | 70 | 88 | 145 | 8 | 15 | 240 | 0.4 | 100 | 71 | 170 |
| 6/7/93 | 9:26 | 70 | 88 | 145 | 8 | 16 | 240 | 0.4 | 103 | 69 | 170 |
| 6/8/93 | 9:00 | 70 | 84 | 144 | 8 | 15 | 240 | 0.4 | 100 | 70 | 170 |
| 6/9/93 | 8:45 | 70 | 84 | 144 | 7.5 | 15 | 240 | 0.4 | 100 | 74 | 170 |
| 6/10/93 | 8:51 | 70 | 84 | 141 | 7.5 | 15 | 240 | 0.4 | 100 | 70 | 170 |
| 6/11/93 | 8:10 | 70 | 84 | 143 | 7 | 15 | 240 | 0.4 | 96 | 76 | 170 |
| 6/12/93 | 8:05 | 70 | 84 | 143 | 7.5 | 15 | 240 | 0.4 | 97 | 74 | 170 |
| 6/13/93 | 8:00 | 70 | 84 | 147 | 7.5 | 16 | 240 | 0.4 | 99 | 74 | 170 |
| 6/14/93 | 7:25 | 70 | 84 | 144 | 7.5 | 16 | 240 | 0.4 | 95 | 71 | 170 |
| 6/15/93 | 7:35 | 70 | 85 | 145 | 8 | 16 | 240 | 0.4 | 105 | 72 | 170 |
| 6/16/93 | 9:45 | 70 | 87 | 156 | 7.5 | 16 | 250 | 0.3 | 112 | 82 | 180 |
| 6/17/93 | 9:00 | 70 | 86 | 148 | 7.5 | 16 | 240 | 0.4 | 96 | 73 | 170 |
| 6/18/93 | 9:10 | 76 | 84 | 142 | 7.5 | 16 | 230 | 0.4 | 98 | 73 | 154 |
| 6/19/93 | 10:41 | 70 | 84 | 144 | 7.5 | 16 | 240 | 0.4 | 100 | 78 | 170 |
| 6/20/93 | 9:05 | 70 | 84 | 141 | 7.5 | 16 | 220 | 0.5 | 92 | 72 | 150 |
| 6/21/93 | 8:05 | 70 | 84 | 141 | 7.5 | 16 | 230 | 0.5 | 93 | 74 | 160 |
| 6/22/93 | 7:10 | 70 | 84 | 142 | 7.5 | 16 | 230 | 0.5 | 95 | 73 | 160 |
| 6/23/93 | 8:15 | 70 | 84 | 140 | 7.5 | 16 | 220 | 0.4 | 98 | 75 | 150 |
| 6/24/93 | 7:35 | 70 | 84 | 140 | 7.5 | 16 | 230 | 0.5 | 94 | 74 | 160 |
| 6/25/93 | 7:25 | 70 | 84 | 138 | 7.5 | 16 | 230 | 0.5 | 90 | 77 | 160 |
| 6/26/93 | 7:35 | 70 | 84 | 138 | 7.5 | 16 | 230 | 0.4 | 91 | 69 | 160 |
| 6/27/93 | 9:35 | 70 | 84 | 140 | 7.5 | 16 | 230 | 0.4 | 100 | 80 | 160 |
| 6/28/93 | 7:35 | 70 | 84 | 137 | 7.5 | 16 | 230 | 0.4 | 94 | 76 | 160 |
| 6/29/93 | 7:25 | 70 | 84 | 138 | 7.5 | 16 | 230 | 0.4 | 93 | 79 | 160 |
| 6/30/93 | 8:15 | 50 | 42 | 136 | 6.5 | 13 | 150 | 0.6 | 96 | 80 | 100 |
| 7/1/93 | 8:10 | 60 | 44 | 135 | 7 | 15 | 170 | 0.5 | 98 | 80 | 110 |
| 7/2/93 | 7:12 | 60 | 44 | 136 | 7 | 15 | 170 | 0.4 | 98 | 79 | 110 |
| 7/3/93 | 11:15 | 60 | 44 | 145 | 7 | 15 | 170 | 0.5 | 102 | 90 | 110 |
| 7/4/93 | 11:20 | 60 | 42 | 140 | 7 | 15 | 170 | 0.4 | 99 | 80 | 110 |
| 7/5/93 | 10:10 | 55 | 44 | 137 | 14 | 20 | 170 | 0.4 | 100 | 85 | 115 |
| 7/6/93 | 8:10 | 60 | 44 | 140 | 13 | 19 | 170 | 0.5 | 99 | 75 | 110 |
| 7/7/93 | 8:00 | 55 | 42 | 135 | 13 | 20 | 170 | 0.4 | 99 | 75 | 115 |
| 7/8/93 | 8:10 | 55 | 44 | 135 | 13 | 19 | 170 | 0.4 | 99 | 80 | 115 |
| 7/9/93 | 6:30 | 55 | 44 | 135 | 13 | 19 | 170 | 0.4 | 99 | 77 | 115 |
| 7/10/93 | 9:45 | 55 | 44 | 135 | 13 | 20 | 170 | 0.4 | 99 | 90 | 115 |
| 7/11/93 | 11:30 | 55 | 44 | 135 | 13 | 20 | 170 | 0.4 | 99 | 95 | 115 |

IITRI OPERATING DATA

| Date | Time | Inlet Air Flow (CFM) | Inlet Air Pres (psi) | Vapor Temp (F) | Suction (in Water) | Discharge (in Water) | Mixed Vapor Flow (CFM) | Mixed Vapor Press (psi) | Mixed Vapor Temp (F) | Ambient Temp (F) | Vapor Flow (SCFM) |
|---------|------|----------------------|----------------------|----------------|--------------------|----------------------|------------------------|-------------------------|----------------------|------------------|-------------------|
| 7/12/93 | 8:00 | 55 | 44 | 135 | 13 | 19 | 170 | 0.4 | 99 | 85 | 115 |
| 7/13/93 | 7:45 | | | 80 | | | | | 78 | | |
| 7/14/93 | 8:14 | | | 79 | | | | | 76 | | |
| 7/15/93 | 6:25 | | | 78 | | | | | 79 | | |
| 7/16/93 | 8:00 | | | 79 | | | | | 79 | | |
| 7/17/93 | 8:00 | | | 81 | | | | | 79 | | |
| 7/21/93 | 8:10 | 30 | 0.3 | 127 | 5 | 4 | 100 | 0.4 | 94 | | 70 |
| 7/22/93 | 8:15 | 30 | 3 | 129 | 4 | 4 | 95 | 0.4 | 93 | | 65 |
| 7/23/93 | 7:45 | 30 | 3.5 | 126 | 4 | 4 | 95 | 0.4 | 90 | | 65 |
| 7/24/93 | 9:10 | 30 | 5 | 128 | 4 | 4 | 95 | 0.4 | 96 | | 65 |
| 7/25/93 | 9:15 | 30 | 4 | 127 | 4 | 4 | 75 | 0.4 | 97 | | 45 |
| 7/26/93 | 8:30 | 30 | 6 | 125 | 4 | 4 | 75 | 0.4 | 89 | | 45 |
| 7/27/93 | 7:55 | 30 | 6 | 126 | 4 | 4 | 75 | 0.4 | 90 | | 45 |
| 7/28/93 | 7:45 | 30 | 6 | 122 | 4 | 4 | 75 | 0.4 | 90 | | 45 |
| 7/29/93 | 8:00 | 30 | 6 | 131 | 4 | 4 | 60 | 0.4 | 94 | | 30 |
| 7/30/93 | 8:05 | 30 | 8 | 131 | 4 | 4 | 75 | 0.4 | 93 | | 45 |
| 7/31/93 | 9:30 | 30 | 8 | 132 | 4 | 4 | 75 | 0.4 | 95 | | 45 |
| 8/1/93 | 9:13 | 30 | 7 | 131 | 4 | 4 | 70 | 0.4 | 94 | | 40 |
| 8/2/93 | 7:55 | 30 | 7 | 128 | 4 | 4 | 75 | 0.4 | 89 | 78 | 45 |

APPENDIX E



May 27, 1993

Mr. Cliff Blanchard
Halliburton NUS Environmental Corporation
800 Oak Ridge Turnpike
Jackson Plaza, C-200
Oak Ridge, Tennessee 37830

RE: EPA Contract No. 68-CO-0048, WA 0-44
SAIC Project No. 01-0832-07-2249-014

Dear Mr. Blanchard:

Please find the enclosed four tables summarizing grain size distribution within the test plot. ASTM D422 was the procedure used for mechanical sieving, and specific gravity tests were conducted following procedure ASTM D845-83.

Tables 1-3 show the particle size distribution summary along the three plan-view cross sections A1-A8, TW1-B4, and C1-C8, respectively. Table 4 presents particle size data on selected samples which further subdivide the fines into silt and clay percentages, and present specific gravities. As a convenience, the particle sizes shown in Tables 1-3 are listed in order of descending percentage of the total, the dominant size listed first.

If you have any questions regarding this information, please do not hesitate to call me at (513) 723-2600, extension 2610.

Sincerely,

SCIENCE APPLICATIONS INTERNATIONAL CORPORATION


Jim Rawe
Work Assignment Manager

Encls.

b3.blnchr4.itr

TABLE 1. PARTICLE SIZE DISTRIBUTION - CROSS SECTION A1-A8

| Particle Size Distribution by Soil Boring (% by weight) ^a | | | | | | | | |
|--|----|-----------------------------------|----|-----------------------------------|-----------------------------------|----------------------------------|-----------------------------------|----|
| Sample Interval Depth BLS (ft) | A1 | A2 | A3 | A4 | A5 | A6 | A7 | A8 |
| 0 - 2 | | | | S-50 ^b G-32 F-18 | | | | |
| 2 - 4 | | | | G-45 ^d S-36 F-19 | | | | |
| 4 - 6 | | S-48 ^c G-28 F-24 | | | | | | |
| 6 - 8 | | | | | | | | |
| 8 - 10 | | | | | | S-57 ^b G-43 | | |
| 10 - 12 | | | | | | | | |
| 12 - 14 | | S-49 ^c F-32 G-19 | | | | S-72 ^c G-20 F-8 | | |
| 14 - 16 | | | | | | | F-49 ^b G-26 S-25 | |
| 16 - 18 | | S-53 ^c F-33 G-14 | | | | | | |
| 18 - 20 | | | | | | G-74 ^b S-19 F-7 | | |
| 20 - 22 | | | | | G-63 ^b F-21 S-16 | | | |
| 22 - 24 | | | | | | G-78 ^b S-19 F-3 | | |
| 24 - 26 | | | | | | | | |
| 26 - 28 | | | | | | | | |
| 28 - 30 | | | | | | | G-58 ^b S-25 F-17 | |
| 30 - 32 | | | | | | | | |
| 32 - 34 | | | | | | | | |
| 34 - 36 | | | | | | | | |

Notes:^a Percentages have been rounded to whole numbers^b Results are from one test^c Results are the average of two tests, one from a sample sleeve and the other from a bagged sample

— Approximate start of gravel zone.

— Navarro Clay

G = Gravel

S = Sand

F = Fines (silt and clay)

TABLE 2. PARTICLE SIZE DISTRIBUTION - CROSS SECTION TW1-B4

| Particle Size Distribution by Soil Bonding (% by weight) ^a | | | | | | |
|---|-----------------------------------|------------------------------------|-----------------------------------|----------------------------------|-----------------------------------|-----------------------------------|
| Sample Interval Depth BLS (ft) | TW1 | TW2 | B1 | B2 | B3 | B4 |
| 0 - 2 | | | S-39 ^d F-36 G-35 | | | |
| 2 - 4 | | | | | S-40 ^b G-38 F-22 | |
| 4 - 6 | F-29 G-34 S-27 | F-41 S-30 G-29 | | F-56 ^b S-38 G-6 | | |
| 6 - 8 | | | | | | |
| 8 - 10 | | | | G-67 ^b S-25 F-8 | | |
| 10 - 12 | | | | | G-50 ^b S-26 F-24 | |
| 12 - 14 | | | S-54 ^c F-27 G-19 | F-78 ^a S-18 G-4 | | |
| 14 - 16 | S-51 ^b F-35 G-14 | F-41 ^b S-33 G-19 | | | | S-51 ^b F-27 G-22 |
| 16 - 18 | | | | | | |
| 18 - 20 | | | | | | |
| 20 - 22 | | | | | G-37 ^b F-35 S-28 | |
| 22 - 24 | | | | | | G-86 ^b F-10 S-4 |
| 24 - 26 | | G-92 ^b S-6 F-2 | | | | |
| 26 - 28 | | | G-93 ^b S-6 F-1 | | | |
| 28 - 30 | | | | | | |
| 30 - 32 | | | | | | |
| 32 - 34 | | | | | | |
| 34 - 36 | | F-75 ^{b,e} S-17 G-8 | | | | |

Notes:

- a. Percentages have been rounded to whole numbers
- b. Results are from one test
- c. Results are the average of two tests, one from a sample sleeve and the other from a bagged sample.
- d. Results are the average of samples from two separate sleeves and one bag sample.
- e. The 75% includes 51% silt and clay and 24% of unaccountable solids that did not settle out of suspension during hydrometer testing.

— Approximate start of gravel zone.
 G = Navarro Clay
 S = Gravel
 F = Sand
 F = Fines (silt and clay)

TABLE 3. PARTICLE SIZE DISTRIBUTION - CROSS SECTION C1-C8

| Particle Size Distribution by Soil Boring (% by weight) ^a | | | | | | | | |
|--|----|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|-----------------------------------|----|
| Sample Interval Depth BLS (ft) | C1 | C2 | C3 | TW7 | C5 | C6 | C7 | C8 |
| 0 - 2 | | | F-49 ^c G-30 S-21 | | | | | |
| 2 - 4 | | | | | S-46 ^b F-27 G-27 | | | |
| 4 - 6 | | | | G-40 ^b S-34 F-26 | | S-45 ^c G-32 F-23 | G-48 ^c S-34 F-18 | |
| 6 - 8 | | S-47 ^c F-28 G-25 | | | | | | |
| 8 - 10 | | | | | | S-43 ^b G-43 F-14 | | |
| 10 - 12 | | | | G-41 ^b S-34 F-25 | | | | |
| 12 - 14 | | | | | | | | |
| 14 - 16 | | | G-42 ^b S-36 F-22 | | | S-44 ^c G-30 F-26 | | |
| 16 - 18 | | | | | | | | |
| 18 - 20 | | | S-60 ^c F-36 G-4 | | G-64 ^b S-22 F-14 | | | |
| 20 - 22 | | | | | | | | |
| 22 - 24 | | | G-79 ^b S-15 F-6 | | | | G-86 ^b S-10 F-4 | |
| 24 - 26 | | | | G-72 ^b S-19 F-9 | | G-64 ^b S-24 F-12 | | |
| 26 - 28 | | | | | | | | |
| 28 - 30 | | | | | | | | |
| 30 - 32 | | | | | | | | |
| 32 - 34 | | | | | | | | |
| 34 - 36 | | | | | | | | |

Notes:

- ^a Percentages have been rounded to whole numbers
^b Results are from one test
^c Results are the average of two tests, one from a sample sleeve and the other from a bagged sample

— Approximate start of gravel zone.
 Navarro Clay
 G = Gravel
 S = Sand
 F = Silt clay

TABLE 4. Particle Size Distribution and Specific Gravities of Selected Tests Samples

| Boring No. | Sample Interval - BLS (ft.) | PARTICLE SIZE (% by weight)* | | | | Specific Gravity |
|------------|-----------------------------|------------------------------|-----------------|---------------------|-----------------|------------------|
| | | Gravel | Sand | Slit | Clay | |
| A3 | 2-4 | 45 | 36 | | 19 | 2.51 |
| A4 | 20-22 | 74 | 17 | 5 | 4 | 2.55 |
| A8 | 14-16 | 26 | 25 | 31 | 18 | 2.43 |
| B1 | 0-2 | 48 | 30 | 13 | 9 | 2.42 |
| B2 | 12-14 | 34 ^b | 17 ^b | 20 ^b | 29 ^b | 2.32 |
| B3 | 10-12 | 50 | 26 | 11 | 13 | 2.41 |
| B4 | 20-22 | 37 | 28 | 17 | 18 | 2.53 |
| C3 | 0-2 | 30 | 21 | 22 | 27 | 2.52 |
| C3 | 22-24 | 79 | 15 | 3 | 3 | 2.62 |
| C5 | 10-12 | 41 | 34 | 15 | 10 | 2.54 |
| TW1 | 4-6 | 34 | 26 | 24 | 16 | 2.49 |
| TW2 | 4-6 | 29 | 30 | 24 | 17 | 2.51 |
| TW2 | 14-16 | 19 | 33 | 26 | 22 | 2.24 |
| TW3 | 35-36 | 8 | 17 | 75 includ. colloids | | 2.34 |

a Percentages have been rounded off to whole numbers and are adjusted where rounding off did not result in a sum of 100%.

b Percentages are the average of one sleeve sample and one bagged sample.

APPENDIX F

Table A.7 - Soil Vapor Analytical Summary
IITRI Demonstration

| Chemical (mg/m ³) | TPH | Benzene | Chloro- Benzene | Ethyl benzene | Toluene | Xylene total | Vinyl Chloride | PCE | Acetone | 2- Butanone | Vinyl Acetate |
|----------------------------------|--------|---------|--------------------|------------------|---------|-----------------|-------------------|------|---------|----------------|------------------|
| Date | | | | | | | | | | | |
| 3/30/93 | 190.00 | 1.15 | 5.00 | 0.14 | 0.39 | 0.20 | 0.23 | | | | 2.90 |
| 3/30/93 | 220.00 | 0.37 | 4.80 | 0.09 | 0.79 | 0.14 | 0.29 | | | | 5.50 |
| 3/31/93 | 250.00 | 2.80 | | 0.18 | | 0.19 | 0.10 | 0.02 | | | 2.50 |
| 4/1/93 | 2.50 | 0.04 | 2.80 | 0.02 | | 0.10 | 0.01 | | | | 0.02 |
| 4/2/93 | 1.00 | 2.20 | 8.50 | 0.29 | 0.55 | 0.38 | 0.04 | 1.20 | 0.26 | | 1.80 |
| 4/3/93 | 210.00 | 0.65 | 7.00 | 0.22 | 0.50 | 0.02 | 0.02 | 0.60 | 0.13 | | 1.90 |
| 4/3/93 | | 0.93 | 8.00 | 0.22 | 0.46 | 0.21 | 0.01 | 0.61 | | | 4.10 |
| 4/4/93 | 100.00 | 0.98 | 7.30 | 0.22 | 0.61 | 0.30 | 0.02 | 0.98 | | | 2.70 |
| 4/4/93 | 220.00 | 1.10 | 3.00 | 0.24 | 0.70 | 0.22 | 0.02 | 1.20 | | | 2.10 |
| 4/5/93 | 1.00 | | 4.20 | 0.15 | 0.28 | 0.19 | 0.02 | 0.60 | 0.13 | | 0.90 |
| 4/5/93 | | 0.02 | 2.90 | 0.02 | 0.02 | 0.05 | | 0.02 | 0.04 | | |
| 4/6/93 | 5.00 | | 0.05 | | | | | | | | |
| 4/6/93 | | 0.04 | 1.50 | | 0.01 | 0.10 | | 0.02 | 0.04 | | |
| 4/7/93 | 15.00 | 0.40 | 0.66 | | 0.01 | | | | | | 0.24 |
| 4/8/93 | 1.80 | 0.03 | 1.50 | | | 0.10 | | | | 0.08 | 0.31 |
| 4/8/93 | 0.60 | 0.16 | 0.85 | | 0.02 | | | | | | 0.09 |
| 4/9/93 | 6.10 | 0.07 | 3.60 | 0.04 | 0.03 | 0.05 | | 0.10 | | | 0.02 |
| 4/9/93 | | 0.75 | 14.00 | 0.35 | 0.04 | 0.60 | | 0.29 | | | 5.00 |
| 4/10/93 | 1.10 | 0.01 | 0.09 | | | | | | 0.07 | | 0.01 |
| 4/10/93 | | 0.11 | 0.55 | | 0.02 | | | | | 0.26 | 0.13 |
| 4/11/93 | 34.00 | 0.90 | 0.08 | 0.09 | | | | 0.08 | | 0.02 | 3.30 |
| 4/12/93 | 1.30 | 0.07 | | | | | | | | 0.47 | 0.18 |
| 4/12/93 | | 0.33 | 7.50 | | 0.05 | 0.21 | | 0.07 | 7.50 | 1.70 | 0.46 |
| 4/13/93 | 11.00 | 0.42 | 2.40 | | 0.05 | | | 0.03 | | 4.00 | 1.10 |
| 4/14/93 | 0.01 | | | | | | | | | | |
| 4/14/93 | 0.13 | | | | | | | | | | |
| 4/15/93 | 0.02 | | | | | | | | | | |
| 4/16/93 | 0.06 | | | | | | | | | | |
| 4/16/93 | | | | | 0.04 | | | | | | |
| 4/17/93 | 0.16 | | | | | 0.03 | 0.02 | | | | |
| 4/18/93 | | | | | | 0.01 | | | | | |
| 4/18/93 | 0.02 | | | | | 0.02 | 0.01 | | | | |
| 4/19/93 | 0.05 | | | | | | | 0.02 | | | |
| 4/19/93 | | | | | | 0.01 | 0.01 | | 0.07 | | |
| 4/20/93 | 0.08 | 0.01 | | | | 0.02 | 0.01 | | 0.02 | | |
| 4/20/93 | | | | | | 0.01 | | | | | |
| 4/21/93 | 0.09 | | | | | | | | | | |
| 4/22/93 | 0.09 | | | | | | | | | | |
| 4/23/93 | 0.02 | | | | | | | | | | |
| 4/24/93 | 0.08 | | | | | | | | | | |
| 4/25/93 | 0.80 | | | | | | | | | | 0.01 |
| 4/26/93 | 0.09 | | | | | | | | | | |
| 4/26/93 | | | | | | 0.01 | 0.01 | | | | |
| 4/27/93 | 0.10 | | | | | | | | | | |
| 4/28/93 | 0.14 | | | | | | | | | | |
| 4/29/93 | 0.05 | | | | | | | | | | |
| 4/30/93 | 0.12 | 0.01 | | | | 0.05 | | | | | |
| 5/1/93 | 0.11 | | | | | 0.01 | | | | | |
| 5/2/93 | 0.07 | | | | | | | | | | |
| 5/3/93 | 0.02 | 0.01 | | | | 0.03 | 0.02 | | | | |
| 5/3/93 | 0.04 | 0.16 | 0.05 | 0.02 | 0.11 | | | | | | |
| 5/4/93 | | 0.01 | | | | 0.01 | 0.01 | | | | |
| 5/6/93 | 6.30 | 0.16 | 0.08 | | 0.12 | 0.02 | | 0.06 | | | |
| 5/7/93 | | 0.05 | | | | 0.04 | | | 0.47 | | |
| 5/7/93 | 2.70 | 0.64 | 8.30 | 0.39 | 0.74 | 0.60 | 0.64 | 0.39 | 2.40 | 1.70 | |

**Table A.7. - Soil Vapor Analytical Summary
IITRI Demonstration**

| Chemical (mg/m3) | TPH | Benzene | Chloro-Benzene | Ethyl benzene | Toluene | Xylene total | Vinyl Chloride | PCE | Acetone | 2-Butanone | Vinyl Acetate |
|---------------------|-------|---------|----------------|---------------|---------|--------------|----------------|------|---------|------------|---------------|
| 5/8/93 | 0.02 | | 0.01 | | | | | | 0.36 | | |
| 5/9/93 | 7.00 | | | | | | | | | | |
| 5/9/93 | 0.04 | | 0.03 | | 0.01 | | | | | | |
| 5/10/93 | 0.91 | 0.08 | 0.09 | 0.05 | 0.09 | | | | | 0.01 | |
| 5/11/93 | 7.10 | | | | | | | | | | |
| 5/11/93 | 4.90 | | | | | | | | | | |
| 5/12/93 | 45.00 | 0.19 | 0.12 | | 0.07 | | | 0.01 | 32.00 | | 0.50 |
| 5/14/93 | 98.00 | 3.20 | 3.60 | | 2.30 | | | | | 13.00 | |
| 5/15/93 | 10.00 | 0.69 | | | 0.21 | | | | 20.00 | | 0.78 |
| 5/16/93 | 0.72 | 0.05 | | | 0.02 | | | | 4.60 | | 0.09 |
| 5/17/93 | 10.00 | 0.44 | | | 0.20 | | | | | | 0.62 |
| 5/18/93 | 57.00 | 2.70 | 0.50 | 0.31 | 1.10 | 0.04 | 21.00 | | 4.80 | 0.10 | 1.60 |
| 5/20/93 | 0.12 | 0.01 | | | | | | | | | 0.01 |
| 5/21/93 | 0.18 | | | | 0.03 | 0.02 | | 0.01 | 0.01 | 0.01 | |
| 5/22/93 | 0.13 | 0.03 | 0.07 | 0.01 | 0.01 | | | | 26.00 | 0.47 | 0.11 |
| 5/23/93 | 0.12 | | | | | | | | | | |
| 5/24/93 | 93.00 | 3.90 | 0.05 | 0.05 | 3.40 | 0.17 | | 0.06 | 19.00 | 0.07 | 0.09 |
| 5/25/93 | 0.35 | 0.02 | 0.01 | | 0.02 | 0.01 | | | 0.01 | | |
| 5/26/93 | 2.00 | 0.25 | 0.06 | 0.02 | 0.24 | 0.11 | | | | 0.03 | 0.10 |
| 5/27/93 | 87.00 | 2.30 | 0.60 | 0.10 | 2.40 | 0.30 | | 0.08 | | | 0.75 |
| 5/28/93 | 0.58 | 0.05 | 0.01 | | 0.02 | | | | 0.01 | 0.01 | |
| 5/29/93 | 0.12 | | 0.01 | | | | | | 0.01 | | |
| 6/1/93 | 0.34 | | 0.01 | | 0.02 | | | | | 0.01 | |
| 6/2/93 | 0.10 | | | | | | | | 0.06 | | |
| 6/3/93 | 0.17 | 0.01 | 0.14 | | 0.03 | | 0.01 | | 0.07 | 0.02 | |
| 6/4/93 | 0.02 | 0.02 | 0.03 | | 0.01 | | | 0.03 | 0.07 | 0.03 | |
| 6/5/93 | 0.12 | 0.01 | 0.03 | 0.08 | 0.04 | 0.05 | | | | 0.01 | |
| 6/6/93 | 4.20 | 0.37 | | | 0.01 | | | | 0.90 | 0.09 | 0.27 |
| 6/7/93 | 0.02 | | 0.01 | | | | | | 0.01 | | |
| 6/8/93 | 0.09 | | | 0.06 | 0.19 | 0.02 | | | | | |
| 6/9/93 | 0.06 | | | | | | | | | 0.02 | 0.05 |
| 6/10/93 | ND | | | | | | | | | 0.22 | 0.06 |
| 6/12/93 | ND | | | | 0.19 | | | | | 0.13 | |
| 6/14/93 | ND | | | | 0.02 | | | | 0.22 | 0.30 | 0.26 |
| 6/16/93 | 0.04 | | | | | | | | 0.05 | 0.26 | 0.01 |
| 6/18/93 | 0.56 | | | | | | | | | 0.05 | 0.39 |
| 6/20/93 | 0.19 | | | | | | | | | 0.02 | |
| 6/22/93 | 0.28 | | | | | | | | | | |



APPENDIX G

DEWATERING SYSTEM


I. INTRODUCTION

The IITRI demonstration began in January 1993 with site preparation and the installation of a dewatering system around the demonstration area at Site S-1. The dewatering system was necessary to keep groundwater levels 5 feet below the bottom tip of the excitor electrodes. Initial water levels in January 1993 indicated the water table at approximately 22.4 feet below the surface. The top of the water table needed to be drawn down to a depth of approximately 24 feet or more below the surface. The dewatering system consisted of four dewatering wells six inches in diameter. One existing well (S1PW04) and three newly installed wells (DW01, DW02, and DW03) were used (Figure G .-1).

II. INSTALLATION

Installation of the three new dewatering wells was completed on January 28, 1993. DW01 was drilled to a depth of 42.5 feet and set at 39.8 feet. DW02 was drilled to a depth of 40 feet and set at 38 feet. DW03 was drilled to a depth of 35 feet and set at 35 feet. These dewatering wells were installed in a 14-inch diameter borehole with 20 feet of PVC screen 6 inches in diameter and a sump at the bottom. A sandpack was added and a bentonite seal was installed above the sandpack. Well S1PW04 had been installed in 1991 during a previous investigation to a depth of 38.9 feet with 14.5 feet of 6-inch diameter PVC screen. All dewatering wells were developed by using a surge block and a pump to remove suspended solids.

After well development the dewatering system was installed. The dewatering system consisted of ejectors in the wells, air lines from the electric air compressor and control panel located in a shed adjacent to the site office trailer, water lines leading from the wells to a "Frac" or storage tank located along the east side of the demonstration site. The dewatering system was installed during the end of January and the first part of February (see Figure 2).






FIGURE A.8.-2
DEWATERING SYSTEM SCHEMATIC
IITRI DEMONSTRATION
SITE S-1, KELLY AFB

III. OPERATION

Dewatering began on February 2, 1993, using wells DW03 and S1PW04. Wells DW01 and DW02 came on line a few days later and the pumping levels were adjusted to match recharge in the wells. The dewatering system was turned off on February 13, 1993, to allow the aquifer to recharge to equilibrium before a test was performed to see how quickly and to what depth the water table could be lowered. Table G.-1 illustrates the results of the dewatering system during this test. When the dewatering system was turned off the water level at temporary well PW03 was 24.5 below the surface and rose to 22.6 feet below the surface before the system was turned on again on February 15. The dewatering system was able to lower the water table in the demonstration area 1.9 feet in twenty-four hours. PW03 was installed on January 28, 1993, to collect water levels in the demonstration area to determine the effectiveness of the dewatering system in lowering the water table. PW03 was abandoned on February 22, 1993, prior to the IITRI demonstration startup. From the results of the test it was concluded that the dewatering system would be able to keep the water table lowered 5 feet below the excitor electrodes. Water levels from PW03 and wells adjacent to the demonstration site are provided in Table A.8.-1.

Water removed by the dewatering system was collected in a holding tank at the site and transported to the Kelly AFB EPCF for treatment. Initially the water was collected in a tanker truck and transported to the EPCF in the tanker truck. Beginning in April 1993 the water was collected in a frac tank then transferred to a tanker truck for transport to the EPCF.

IV. CONCLUSIONS

Volumes of water, average pumping rates, rainfall, and water transport data during the period of the IITRI demonstration are provided in Table G.-2. Average pumping rates ranged from 0.79 gpm to 3.79 gpm during the demonstration. Variations in pumping rates can be attributed to various factors including precipitation, evaporation, recharge of the aquifer, and the nearby pond at the fuel tank farm to the east of the demonstration site. The dewatering system was able to draw the water table at the demonstration site down to a level of approximately 24.5 feet during a pump test in February 1993. The goal was to be able to draw the water table down to approximately 5 feet below the bottom of the exciter electrodes which was at a depth of approximately 20 feet. Actual water levels during the demonstration may have been even lower due to the continual dewatering over a longer period of time.

TABLE G.-1
WATER LEVELS
SITE S-1, KELLY AFB

| Date | Time | Well Number | | | | | | | | |
|---------|----------|-------------|-------|-------|-------|-------|-------|-------|-------|-------|
| | | PW03 | PW04 | DW01 | DW02 | DW03 | TW09 | TW10 | TW11 | TW12 |
| 1/30/93 | 2:15 PM | | | 23.74 | 22.4 | 23.17 | | | | |
| 2/2/93 | 7:30 AM | 22.47 | 24.63 | 23.80 | 22.58 | 23.28 | 24.39 | 23.80 | 23.66 | 23.92 |
| 2/2/93 | 9:15 AM | 22.75 | 35.35 | | 25.97 | | | 23.85 | 23.83 | |
| 2/2/93 | 12:30 PM | 23.47 | 32.83 | | 25.78 | | | 23.85 | 23.85 | |
| 2/2/93 | 1:20 PM | 23.11 | | | | | | | | |
| 2/2/93 | 3:20 PM | 23.45 | | | | | | | | |
| 2/3/93 | 6:43 PM | 23.78 | 34.99 | 29.78 | 28.27 | 24.17 | 24.43 | 23.95 | 24.07 | 26.28 |
| 2/3/93 | 1:15 PM | | 34.89 | | 27.8 | | | 23.95 | 24.14 | 26.21 |
| 2/3/93 | 6:30 PM | 22.41 | 33.55 | | 27.78 | | | 23.88 | 24.23 | 26.14 |
| 2/4/93 | 7:30 AM | 23.7 | | 30.02 | 27.75 | | | 23.96 | 24.4 | 26.09 |
| 2/4/93 | 12:40 PM | 22.9 | 34.95 | 29.91 | 27.69 | 24.18 | 24.49 | 23.97 | 24.35 | 26.11 |
| 2/4/93 | 4:00 PM | 23.84 | | 29.74 | 28.02 | | | 24 | 24.54 | 26.08 |
| 2/7/93 | 1:30 PM | 23.44 | | | | | | 23.92 | 24.24 | 25.76 |
| 2/7/93 | 5:38 PM | 23.47 | | | | | | | | |
| 2/8/93 | 6:46 AM | 23.6 | | | | | | | | |
| 2/8/93 | 1:10 PM | 23.35 | | | | | | | | |
| 2/8/93 | 6:14 PM | 23.46 | | | | | | 24.67 | 25.39 | |
| 2/9/93 | 8:08 AM | 22.85 | | | | | 24.1 | 24.45 | 24.21 | |
| 2/9/93 | 10:50 AM | 22.98 | | | | | 24.13 | 24.22 | 24.67 | |
| 2/9/93 | 12:50 PM | 23.12 | | | | | | 24.28 | 25 | |
| 2/9/93 | 4:35 PM | 23.46 | | | | | | 24.14 | 25.73 | |
| 2/10/93 | 8:35 AM | 20.59 | | | | | 24.16 | 24.22 | 24.12 | |
| 2/10/93 | 1:55 AM | 22.08 | | | | | 24.1 | 24.27 | 25.52 | |
| 2/11/93 | 8:10 AM | 23.26 | | | 23.73 | | 24.13 | 24.23 | 25.69 | |
| 2/11/93 | 1:00 PM | 23.47 | | | 25.64 | | 24.15 | 24.25 | 25.67 | |
| 2/12/93 | 2:00 PM | 24.8 | | | | | | 24.3 | 26.8 | |
| 2/13/93 | 7:30 AM | 24.5 | | | | | | | | |
| 2/13/93 | 1:00 PM | 24.5 | | | | | | | 25.96 | |
| 2/15/93 | 8:30 AM | 22.6 | | | | | | | | |
| 2/16/93 | 8:30 AM | 24.4 | | | | | | | | |
| 2/16/93 | 2:00 PM | 24.6 | | | | | | | | |
| 2/18/93 | 7:30 AM | 24.71 | | | | | | | | |
| 2/19/93 | 7:55 AM | 24.68 | | | | | | | | |

Table G -2
Dewatering Data Summary
IITRI Demonstration
Site S-1, Kelly AFB, TX

| Item | Date | Quantity (gal) | Days | Gallons per day | Rainfall (in) | Average gpm |
|---------------|---------|-------------------|------------|--------------------|------------------|----------------|
| March | | | | | 2.21 | |
| Start-up | 4/3/94 | 0 | | | 0.19 | |
| Water Hauling | 4/12/93 | 16,000 | 9 | | 0.25 | 1.23 |
| Water Hauling | 4/19/93 | 16,000 | 7 | | 0 | 1.59 |
| Water Hauling | 4/28/93 | 16,000 | 9 | | 0 | 1.23 |
| April | | 48,000 | 25 | 1920 | 0.44 | 1.33 |
| Water Hauling | 5/5/93 | 8,000 | 7 | | 3.91 | 0.79 |
| Water Hauling | 5/8/93 | 16,000 | 3 | | 0 | 3.70 |
| Water Hauling | 5/14/93 | 16,000 | 6 | | 0 | 1.85 |
| Water Hauling | 5/18/93 | 5,460 | 4 | | 0.06 | 0.95 |
| Water Hauling | 5/19/93 | 5,460 | 1 | | 0 | 3.79 |
| Water Hauling | 5/25/93 | 18,000 | 6 | | 3.01 | 2.08 |
| Water Hauling | 5/31/93 | 14,000 | 6 | | 1.14 | 1.62 |
| May | | 82,920 | 33 | 2513 | 8.12 | 1.74 |
| Water Hauling | 6/5/93 | 12,000 | 5 | | 0 | 1.67 |
| Water Hauling | 6/10/93 | 18,000 | 5 | | 0.28 | 2.50 |
| Water Hauling | 6/16/93 | 18,000 | 6 | | 3.3 | 2.08 |
| Water Hauling | 6/22/93 | 12,000 | 6 | | 1.29 | 1.39 |
| Water Hauling | 6/25/93 | 12,000 | 3 | | 0.33 | 2.78 |
| Water Hauling | 6/28/93 | 12,000 | 3 | | 0.73 | 2.78 |
| June | | 84,000 | 28 | 3000 | 5.93 | 2.08 |
| Water Hauling | 7/2/93 | 12,000 | 4 | | 0 | 2.08 |
| Water Hauling | 7/6/93 | 12,000 | 4 | | 0 | 2.08 |
| Water Hauling | 7/13/93 | 18,000 | 7 | | 0 | 1.79 |
| Water Hauling | 7/16/93 | 6,000 | 3 | | 0 | 1.39 |
| Water Hauling | 7/23/93 | 6,000 | 7 | | 0 | 0.60 |
| Water Hauling | 7/27/93 | 18,000 | 4 | | 0 | 3.13 |
| July | | 72,000 | 29 | 2483 | 0 | 1.72 |
| Water Hauling | 8/6/93 | 18,000 | 10 | | 0 | 1.25 |
| Water Hauling | 8/23/93 | 21,000 | 17 | | | 0.86 |
| August | | 39,000 | 27 | 1444 | | 1.00 |
| TOTAL | | 325,920 | 115 | 2834 | 16.70 | 1.38 |
| | | | | | | |

APPENDIX H

PRECISION ANALYTICS, INC.



N.E. 2345 Hopkins Court • Pullman, WA 99163
TEL. (509) 332-0928

May 4, 1993

Page 1 of 6

SA-ALC/PKOE
1288 Growdon Road, Bldg. 1585
Kelly AFB, TX 78241-5318

Attn: JoAnn Hernandez

Laboratory Reference
Samples: 3117KAB1, 3117KAB2
Report number: KAB3117

Customer Reference
CALL #93-36
Samples: S1-3109-01, S1-3109-02

Date samples received: 4/20/93

All analyses are performed by approved methodologies whenever applicable. Deviations, modifications and/or substitutions with more stringent EPA methodologies are sometimes necessary owing to the variety of matrices being analyzed.

A *Concentration Value* of U indicates a compound could not be detected in the sample above the lower quantitation limit printed in the *Detection Limit* column.

If you have any questions regarding the enclosed laboratory results, please include the above laboratory sample and report numbers in all correspondence.

Respectfully,

Michael McMillan

Michael McMillan, Ph.D.
Chemist

Report Number: KAB3117

Pg 2 of 6

8020

Chemist: McMillan
Client Sample ID: S1-3109-01
Lab Sample Number: 3117KAB1

Date completed: 5/4/93
Sample type: Water
Method: EPA 8020

| Item Number | Compound | Detection Limit μg/L (ppb) | Concentration μg/L (ppb) |
|-------------|---------------------|-------------------------------|-----------------------------|
| 1 | Benzene | 5 | 1319 |
| 2 | Toluene | 5 | 195 |
| 3 | Ethylbenzene | 5 | 41 |
| 4 | Xylene I | 5 | 15 |
| 5 | Xylene II | 5 | 48 |
| 6 | Chlorobenzene | 5 | 5747 |
| 7 | 1,2-dichlorobenzene | 5 | 2700 |
| 8 | 1,3-dichlorobenzene | 5 | 230 |
| 9 | 1,4-dichlorobenzene | 5 | 964 |

Report Number: KAB3117Pg 3 of 6Semi-Volatile Organics

Chemist: McMillan
 Client Sample ID: S1-3109-02
 Lab Sample Number: 3117KAB2

Date completed: 5/4/93
 Sample type: Water
 Method: EPA 8270

| Item Number | Compound | Detection Limit µg/L (ppb) | Concentration µg/L (ppb) |
|-------------|------------------------------------|-------------------------------|-----------------------------|
| 1 | 2-Fluorophenol | \$ | -- |
| 2 | Phenol-d ₅ | \$ | -- |
| 3 | bis(2-Chloroethyl)Ether | 660 | U |
| 4 | 1,4-Dichlorobenzene-d ₄ | * | -- |
| 5 | 2-Chlorophenol-d ₄ | \$ | -- |
| 6 | 2-Chlorophenol | 660 | U |
| 7 | 1,3-Dichlorobenzene | 660 | 85 |
| 8 | 1,4-Dichlorobenzene | 660 | 265 |
| 9 | 1,2-Dichlorobenzene | 660 | 555 |
| 10 | 2-Methylphenol | 660 | 43.7 |
| 11 | Phenol | 660 | U |
| 12 | bis(2-Chloroisopropyl)Ether | 660 | U |
| 13 | Benzyl Alcohol | 1,300 | U |
| 14 | 3-Methylphenol | 660 | U |
| 15 | 4-Methylphenol | 660 | 16 |
| 16 | N-nitroso-Di-n-propylamine | 660 | U |
| 17 | Nitrobenzene-d ₅ | \$ | -- |
| 18 | Hexachloroethane | 660 | U |
| 19 | Nitrobenzene | 660 | U |
| 20 | 2-Nitrophenol | 660 | U |
| 21 | Isophorone | 660 | U |
| 22 | 2,4-Dimethyphenol | 660 | 22 |
| 23 | Benzoic Acid | 3,300 | U |
| 24 | bis(2-Chloroethoxy)methane | 660 | U |
| 25 | 2,4-Dichlorophenol | 660 | U |

Report Number: KAB3117

Pg 4 of 6

Semi-Volatile Organics (cont.)

Client Sample ID: SA-3109-02

Lab Sample Number: 3117KAB2

| Item Number | Compound | Detection Limit μg/L (ppb) | Concentration μg/L (ppb) |
|-------------|------------------------------|-------------------------------|-----------------------------|
| 26 | Naphthalene-d ₈ | * | -- |
| 27 | 1,2,4-Trichlorobenzene | 660 | 6 |
| 28 | Naphthalene | 660 | 84 |
| 29 | 4-Chloroaniline | 1,300 | U |
| 30 | Hexachlorobutadiene | 660 | U |
| 31 | 2-Methylnaphthalene | 660 | U |
| 32 | 4-Chloro-3-Methylphenol | 1,300 | U |
| 33 | Hexachlorocyclopentadiene | 660 | U |
| 34 | 2,4,6-Trichlorophenol | 660 | U |
| 35 | 2,4,5-Trichlorophenol | 660 | U |
| 36 | 2-Fluorobiphenyl | \$ | -- |
| 37 | 2-Nitroaniline | 3,300 | U |
| 38 | 2-Chloronaphthalene | 660 | U |
| 39 | Dimethyl Phthalate | 660 | U |
| 40 | 2,6-Dinitrotoluene | 660 | U |
| 41 | Acenaphthylene | 660 | U |
| 42 | 3-Nitroaniline | 3,300 | U |
| 43 | Acenaphthene-d ₁₀ | * | -- |
| 44 | 2,4-Dinitrophenol | 3,300 | U |
| 45 | Dibenzofuran | 660 | U |
| 46 | Acenaphthene | 660 | U |
| 47 | 4-Nitrophenol | 3,300 | U |
| 48 | 2,4-Dinitrotoluene | 660 | U |
| 49 | Diethyl phthalate | 660 | U |
| 50 | 4,6-Dinitro-2-methylphenol | 3,300 | U |

Report Number: KAB3117

Pg 5 of 6

Semi-Volatile Organics (cont.)

Client Sample ID: SA-3109-02

Lab Sample Number: 3117KAB2

| Item Number | Compound | Detection Limit µg/L (ppb) | Concentration µg/L (ppb) |
|-------------|------------------------------|-------------------------------|-----------------------------|
| 51 | 4-Nitroaniline | ND | U |
| 52 | Fluorene | 660 | U |
| 53 | 4-Chlorophenyl phenyl ether | 660 | U |
| 54 | N-nitrosodiphenylamine | 660 | U |
| 55 | Diphenyldiazene | 660 | U |
| 56 | 2,4,6-Tribromophenol | \$ | -- |
| 57 | 4-Bromophenyl phenyl ether | 660 | U |
| 58 | Hexachlorobenzene | 660 | U |
| 59 | Pentachlorophenol | 3,300 | U |
| 60 | Phenanthrene | 660 | U |
| 61 | Phenanthrene-d ₁₀ | * | -- |
| 62 | Anthracene | 660 | U |
| 63 | Di-n-Butylphthalate | 660 | U |
| 64 | Fluoranthene | 660 | U |
| 65 | Pyrene | 660 | U |
| 66 | 4-Terphenyl-d ₁₄ | \$ | -- |
| 67 | Chrysene | 660 | U |
| 68 | Butyl benzyl phthalate | 660 | U |
| 69 | 3,3'-Dichlorobenzidine | 1,300 | U |
| 70 | Perylene-d ₁₂ | * | -- |
| 71 | Benzo(a)Anthracene | 660 | U |
| 72 | bis(2-ethylhexyl)Phthalate | 660 | U |
| 73 | Benzo(a)pyrene | 660 | U |
| 74 | Di-n-octyl Phthalate | 660 | U |
| 75 | Dibenz(a h)anthracene | 660 | U |
| 76 | Benzo(b+k)fluoranthene | 660 | U |

Precision Analytics, Inc.

Report Number: KAB3117

Pg 6 of 6

Semi-Volatile Organics (cont.)

Client Sample ID: SA-3109-02

Lab Sample Number: 3117KAB2

| Item Number | Compound | Detection Limit µg/L (ppb) | Concentration µg/L (ppb) |
|-------------|--------------------------|-------------------------------|-----------------------------|
| 77 | Benzo(g,h,i)perylene | 660 | U |
| 78 | Indeno(1,2,3-cd)pyrene | 660 | U |
| 79 | Chrysene-d ₁₂ | * | -- |

\$ = Surrogate

* = Internal Standard

Comment: 500 ml of sample were concentrated to 1.8 ml of organic extract; hence, effective detection limits are .0036 of machine detection limits listed.

APPENDIX I

Report of Analysis



Engineering Geotechnical Materials and Environmental Engineering
Geologists, Scientists and Chemists



Raba-Kistner
Consultants, Inc.

P O Box 690287 San Antonio TX 78269-0287
12821 W Golden Lane San Antonio TX 78249
(210) 699-9390

To: Halliburton NUS Corp.
800 Oak Ridge Turnpike
Jackson Plaza, A-600
Oak Ridge, TN 37830
Attn: Cliff Blanchard

Project No.: ASE93-018-00
Task No.: 5000
Assignment No.: 3893
Contract/P.O. No.:
Date Received: 5-14-93
Page 1 of 6 Date: 6-2-93

Sample Type/Sample Loc: Water/Kelly AFB
Date Collected: 5-14-93
Date Completed: 5-27-93
Collected By: Client

TEST METHODS:

| TEST | PREPARATION/DATE | ANALYSIS/DATE |
|----------------|---------------------|---------------------|
| Semi-Volatiles | SW 846 3510/5-17-93 | SW 846 8270/5-21-93 |
| TPH | | EPA 418.1/5-18-93 |
| Volatiles | SW 846 5030/5-17-93 | SW 846 8260/5-17-93 |

All soil and sludge results are reported on the dry-weight basis.
Methods are from EPA SW 846 and EPA 600/4-79-20 or as listed.

By Earl S. Moore
Earl S. Moore
Organic Section Manager

Project No.: ASE93-018-00
Assignment No.: 3893
Page 2 of 6

| BASE/NEUTRAL/ACID EXTRACTABLES | Detection Limit | 3893-1 (\$1W0514 931050D) |
|--------------------------------|-----------------|---------------------------------|
| | ug/L | ug/L |
| Acenaphthene | 10 | <10 |
| Acenaphthylene | 10 | <10 |
| Anthracene | 10 | <10 |
| Benzo(a)anthracene | 10 | <10 |
| Benzo(b)fluoranthene | 10 | <10 |
| Benzo(k)fluoranthene | 10 | <10 |
| Benzo(a)pyrene | 10 | <10 |
| Benzo(g,h,i)perylene | 10 | <10 |
| Benzoinic acid | 50 | 140 |
| Benzyl alcohol | 20 | 26 |
| Benzidine | 10 | <10 |
| Benzyl butyl phthalate | 10 | <10 |
| Bis(2-chloroethyl)ether | 10 | <10 |
| Bis(2-chloroethoxy)methane | 10 | <10 |
| Bis(2-ethylhexyl)phthalate | 10 | 95 |
| Bis(2-chloroisopropyl)ether | 10 | <10 |
| 4-Bromophenyl phenyl ether | 10 | <10 |
| 4-Chloroaniline | 20 | <10 |
| 2-Chloronaphthalene | 20 | <10 |
| 4-Chlorophenyl phenyl ether | 10 | <10 |
| Chrysene | 10 | <10 |
| Dibenzofuran | 10 | <10 |
| Dibenzo(a,h)anthracene | 10 | <10 |
| Di-n-butyl phthalate | 10 | 16 |
| 1,3-Dichlorobenzene | 10 | <10 |
| 1,4-Dichlorobenzene | 10 | <10 |
| 1,2-Dichlorobenzene | 10 | <10 |
| 3,3'-Dichlorobenzidine | 20 | <20 |
| Diethyl phthalate | 10 | <10 |
| Dimethyl phthalate | 10 | <10 |
| 2,4-Dinitrotoluene | 10 | <10 |
| 2,6-Dinitrotoluene | 10 | <10 |
| Di-n-octylphthalate | 10 | <10 |
| 1,2-Diphenylhydrazine | 10 | <10 |
| Fluoranthene | 10 | <10 |
| Fluorene | 10 | <10 |
| Hexachlorobenzene | 10 | <10 |
| Hexachlorobutadiene | 10 | <10 |
| Hexachloroethane | 10 | <10 |
| Indeno(1,2,3-cd)pyrene | 10 | <10 |
| Isophorone | 10 | <10 |
| 2-Methylnaphthalene | 10 | <10 |
| Naphthalene | 10 | <10 |

Project No.: ASE93-018-00

Assignment No.: 3893

Page 3 of 6

| | | |
|----------------------------|----|-----|
| 2-Nitroaniline | 50 | <50 |
| 3-Nitroaniline | 50 | <50 |
| 4-Nitroaniline | 50 | <50 |
| Nitrobenzene | 10 | <10 |
| N-Nitrosodimethylamine | 10 | <10 |
| N-Nitrosodi-n-propylamine | 10 | <10 |
| N-Nitrosodiphenylamine | 10 | <10 |
| Phenanthrene | 10 | <10 |
| Pyrene | 10 | <10 |
| 1,2,4-Trichlorobenzene | 10 | <10 |
| 4-Chloro-3-methylphenol | 20 | <20 |
| 2-Chlorophenol | 10 | <10 |
| 2,4-Dichlorophenol | 10 | <10 |
| 2,4-Dimethylphenol | 10 | 50 |
| 2,4-Dinitrophenol | 50 | <50 |
| 2-Methyl-4,6-dinitrophenol | 50 | <50 |
| 2-Methylphenol | 10 | 14 |
| 4-Methylphenol | 10 | 300 |
| 2-Nitrophenol | 10 | <10 |
| 4-Nitrophenol | 50 | <50 |
| Pentachlorophenol | 50 | <50 |
| phenol | 10 | 120 |
| 2,4,6-Trichlorophenol | 10 | <10 |
| 2,4,5-Trichlorophenol | 10 | <10 |

Project No.: ASE93-018-00

Assignment No.: 3893

Page 4 of 6

Test Results:

| Analyte | Detection Limit (mg/L) | 3893-1 (S1W0514 931050D) (mg/L) |
|---------|------------------------------|--|
| TPH | 1 | 5 |

Project No.: ASE93-018-00

Assignment No.: 3893

Page 5 of 6

Test Results:

| Analyte | Detection Limit (mg/L) | 3893-1 (S1W0514 931050D) (mg/L) | 3893-2 (SW0514 931045C) (mg/L) |
|---------------------------|---------------------------|--|---|
| Acetone | 1 | 2.4 | 12 |
| Bromomethane | 0.1 | <0.1 | 1.3 |
| 2-Butanone | 1 | <1 | <1 |
| Carbon disulfide | 1 | <1 | <1 |
| Chloroethane | 0.1 | <0.1 | <0.1 |
| Chloroform | 0.05 | <0.05 | <0.05 |
| Chloromethane | 0.1 | <0.1 | <0.1 |
| Dichlorodifluoromethane | 0.05 | <0.05 | <0.05 |
| 1,1-Dichloroethane | 0.05 | <0.05 | <0.05 |
| 1,2-Dichloroethane | 0.05 | <0.05 | <0.05 |
| 1,1-Dichloroethene | 0.05 | <0.05 | <0.05 |
| cis-1,2-Dichloroethene | 0.05 | <0.05 | <0.05 |
| trans-1,2-Dichloroethene | 0.05 | <0.05 | <0.05 |
| 1,2-Dichloropropane | 0.05 | <0.05 | <0.05 |
| Methylene chloride | 0.05 | <0.05 | <0.05 |
| 1,1,1-Trichloroethane | 0.05 | <0.05 | <0.05 |
| Trichlorofluoromethane | 0.05 | <0.05 | <0.05 |
| Vinyl acetate | 0.5 | <0.5 | <0.5 |
| Vinyl chloride | 0.1 | <0.1 | <0.1 |
| Benzene | 0.05 | <0.05 | 0.06 |
| Bromodichloromethane | 0.05 | <0.05 | <0.05 |
| Carbon Tetrachloride | 0.05 | <0.05 | <0.05 |
| 2-Chloroethyl vinyl ether | 0.1 | <0.1 | <0.1 |
| 1,2-Dibromoethane | 0.05 | <0.05 | <0.05 |
| Dibromomethane | 0.05 | <0.05 | <0.05 |
| 1,2-Dichloroethane | 0.05 | <0.05 | <0.05 |
| 1,2-Dichloropropane | 0.05 | <0.05 | <0.05 |
| 1,1-Dichloropropene | 0.05 | <0.05 | <0.05 |
| cis-1,3-Dichloropropene | 0.05 | <0.05 | <0.05 |
| trans-1,3-Dichloropropene | 0.05 | <0.05 | <0.05 |
| Methylbutyl ether | 0.05 | <0.05 | <0.05 |
| 4-Methyl-2-pentanone | 0.50 | <0.50 | <0.50 |
| Toluene | 0.05 | <0.05 | <0.05 |
| 1,1,2-Trichloroethane | 0.05 | <0.05 | <0.05 |
| Trichloroethene | 0.05 | <0.05 | <0.05 |
| Bromoform | 0.05 | <0.05 | <0.05 |
| Chlorodibromomethane | 0.05 | <0.05 | <0.05 |
| Chlorobenzene | 0.05 | 0.07 | 0.09 |
| 1,3-Dichloropropane | 0.05 | <0.05 | <0.05 |
| Phylbenzene | 0.05 | <0.05 | <0.05 |
| 2-Hexanone | 0.50 | <0.50 | <0.50 |
| Styrene | 0.05 | <0.05 | <0.05 |
| 1,1,2,2-Tetrachloroethane | 0.05 | <0.05 | <0.05 |
| Tetrachloroethene | 0.05 | <0.05 | <0.05 |
| Total Xylenes | 0.05 | <0.05 | <0.05 |

APPENDIX J

Engineers, Geologists, Chemists, Water Planners, Hygienists and Environmental Scientists



12821 W. Golden Lane
P.O. Box 690287, San Antonio, TX 78269-0287
(210) 699-9090 • FAX (210) 699-6426

December 22, 1994

Ms. Laura Witt
Brown & Root Environmental
800 Oak Ridge Turnpike, Suite A-600
Oak Ridge, Tennessee 37830


Dear Laura,

The samples submitted under chain-of-custody number 6756 were referenced as "soil" on the report dated 04-26-94. The samples submitted were actually carbon; however, our boilerplate default is "soil" for all solid matrices.

If you have any questions or need additional information, please contact me at 210-699-9090, extension 275.

Respectfully submitted,

RABA-KISTNER CONSULTANTS, INC.


AL Weilbacher
Director of Analytical Chemistry

Project No.: ASE93-018-00

Assignment No.: 3893

Page 6 of 6

| | Detection Limit (mg/L) | 3893-1 (S1W0514 931050D) (mg/L) | 3893-2 (SW0514 931045C) (mg/L) |
|-----------------------------|------------------------------|--|---|
| Bromobenzene | 0.05 | <0.05 | <0.05 |
| n-Butylbenzene | 0.05 | <0.05 | <0.05 |
| sec-Butylbenzene | 0.05 | <0.05 | <0.05 |
| tert-Butylbenzene | 0.05 | <0.05 | <0.05 |
| 2-Chlorotoluene | 0.05 | <0.05 | <0.05 |
| 4-Chlorotoluene | 0.05 | <0.05 | <0.05 |
| 1,2-Dibromo-3-chloropropane | 0.05 | <0.05 | <0.05 |
| 1,2-Dichlorobenzene | 0.05 | <0.05 | <0.05 |
| 1,3-Dichlorobenzene | 0.05 | <0.05 | <0.05 |
| 1,4-Dichlorobenzene | 0.05 | <0.05 | <0.05 |
| Hexachlorobutadiene | 0.05 | <0.05 | <0.05 |
| Isopropyl benzene | 0.05 | <0.05 | <0.05 |
| p-Isopropyltoluene | 0.05 | <0.05 | <0.05 |
| Naphthalene | 0.05 | <0.05 | <0.05 |
| n-Propylbenzene | 0.05 | <0.05 | <0.05 |
| 1,1,2,2-Tetrachloroethane | 0.05 | <0.05 | <0.05 |
| 1,2,3-Trichlorobenzene | 0.05 | <0.05 | <0.05 |
| 1,2,4-Trichlorobenzene | 0.05 | <0.05 | <0.05 |
| 1,2,3-Trichloropropane | 0.05 | <0.05 | <0.05 |
| 1,2,4-Trimethylbenzene | 0.05 | <0.05 | <0.05 |
| 1,3,5-Trimethylbenzene | 0.05 | <0.05 | <0.05 |

Report of Analysis

Consulting Geotechnical Materials and Environmental Engineers
Geologists Scientists and Chemists

FILE COPY



**Raba-Kistner
Consultants, Inc.**

P.O. Box 690287, San Antonio, TX 78269-0287
12821 W. Golden Lane, San Antonio, TX 78249
(210) 699-9090

To: Brown & Root Environmental
800 Oak Ridge Turnpike
Suite A-600
Oak Ridge, TN 37830

Attn: Cliff Blanchard

Project No: ASE94-007-00
Task No: 5000
Assignment No: 6756
Contract/P.O. No:
Date Received: 04-19-94
Page 1 of 5 Date: 04-26-94

Sample Type/Sample Loc: Soil / Kelly Air Force Base
Date Collected: 04-19-94
Date Completed: 04-26-94
Collected By: R-KCI

TEST METHODS:

| TEST | PREPARATION / DATE | ANALYSIS / DATE |
|---------------------|--------------------|------------------------------------|
| TCLP Extraction | 1311 / 04-21-94 | |
| TCLP-ZHE | 1311 / 04-21-94 | |
| TCLP-Volatiles | | |
| TCLP-Semi-Volatiles | 3510 / 04-22-94 | 8260 / 04-25-94 8270 / 04-25-94 |

Raba-Kistner Consultants, Inc. (R-KCI) warrants that work will be performed in accordance with sound laboratory practice and professional standards, but makes no other warranty, expressed or implied. In the event of any error, omission or other professional negligence, the sole and exclusive responsibility of R-KCI shall be to reperform the deficient work at its own expense, and R-KCI shall have no other liability whatsoever. In no event shall R-KCI be liable, whether contract or tort, including negligence, for any incidental or consequential damages. This provision is in conflict with other contractual terms, it is understood that this provision will, in all cases, prevail.

By 

Gang Sun, Ph.D.
QA/QC Officer

239

(The reverse of this page is blank.)

Project No: ASE94-007-00
Assignment No: 6756
Page 2 of 5

| Analyte | Detection Limit (mg/L) | 6756-1 (KSI CD 1/2-3688) (mg/L) |
|-----------------------|---------------------------|---------------------------------------|
| TCLP-Semi-Volatiles | | |
| 1,4-Dichlorobenzene | 0.75 | <0.75 |
| 2,4-Dinitrotoluene | 0.013 | <0.013 |
| Hexachlorobenzene | 0.013 | <0.013 |
| Hexachloroethane | 0.03 | <0.05 |
| Nitrobenzene | 0.02 | <0.02 |
| Pentachlorophenol | 3.6 | <3.6 |
| 2,4,6-Trichlorophenol | 0.2 | <0.2 |
| 2,4,5-Trichlorophenol | 5.8 | <5.8 |
| Pyridine | 0.5 | <0.5 |
| Total cresol | 30 | <30 |

Project No: ASE94-007-00
Assignment No: 6756
Page 3 of 5

| Analyte | Detection Limit (mg/L) | 6756-1 (KSI CD 1/2-3688) (mg/L) |
|----------------------|----------------------------------|--|
| TCLP-Volatiles | | |
| Benzene | 0.05 | <0.05 |
| Carbon Tetrachloride | 0.05 | <0.05 |
| Chlorobenzene | 10 | <10 |
| Chloroform | 0.6 | <0.6 |
| 1,2-Dichloroethane | 0.05 | <0.05 |
| 1,1-Dichloroethene | 0.07 | <0.07 |
| 2-Butanone | 20 | <20 |
| Tetrachloroethene | 0.07 | <0.07 |
| Trichloroethene | 0.05 | <0.05 |
| Vinyl Chloride | 0.02 | <0.02 |

Project No: ASE94-007-00
Assignment No: 6756
Page 4 of 5

QA/QC FORM

| ORIGINAL RESULT | MATRIX SPIKE AMT. | MATRIX SPIKE RECOVERY (%) | MATRIX SPIKE DUPLICATE RECOVERY (%) | QC LIMITS | RELATIVE DIFFERENCE | QC RPD | SAMPLE |
|--------------------|-------------------|---------------------------|-------------------------------------|-----------|---------------------|--------|--------|
| | | | | | | (%) | (%) |
| 1,1-Dichloroethene | 10 | 100 | 117 | 128 | 61-145 | 9 | Blank |
| Trichloroethene | 10 | 100 | 100 | 111 | 71-120 | 10 | Blank |
| Benzene | 10 | 100 | 110 | 121 | 76-127 | 10 | Blank |
| Toluene | 10 | 100 | 104 | 115 | 76-127 | 10 | Blank |
| Chlorobenzene | 10 | 100 | 127 | 124 | 75-130 | 2 | Blank |

| QA/QC FORM | | | | | | |
|--------------------------------|-------------------|---------------------------|-------------------------------------|-----------|-------------------------|--------|
| ORIGINAL RESULT | MATRIX SPIKE AMT. | MATRIX SPIKE RECOVERY (%) | MATRIX SPIKE DUPLICATE RECOVERY (%) | QC LIMITS | RELATIVE DIFFERENCE (%) | QC RPD |
| (mg/L) | (mg/L) | (%) | (%) | | | SAMPLE |
| Phenol <10 | 200 | 32 | 17 | 5-112 | 17 | 23 |
| 2-Chloro-phenol <10 | 200 | 60 | 52 | 23-134 | 14 | 29 |
| 1,4-Dichloro-benzene <10 | 100 | 59 | 51 | 20-124 | 15 | 32 |
| N-Nitroso-di-n-propylamine <10 | 100 | 62 | 55 | D-230 | 12 | 55 |
| 1,2,4-Trichlorobenzene <10 | 100 | 67 | 58 | 44-142 | 15 | 28 |
| 4-Chloro-3-methylphenol <10 | 200 | 100 | 92 | 22-147 | 8 | 37 |
| Acenaphthene <10 | 100 | 71 | 64 | 47-145 | 10 | 28 |
| 4-Nitrophenol <10 | 200 | 64 | 64 | D-132 | 0 | 47 |
| ,4-Dinitroto-uene <10 | 100 | 88 | 79 | 39-139 | 11 | 22 |
| entachloro-henol <10 | 200 | 124 | 114 | 14-176 | 8 | 49 |
| | | | | | | BLank |

HALLIBURTON NUS Environmental
Corporation and Subsidiaries

CHAIN OF CUSTODY RECORD

PROJECT NO.: 3688 SITE S-1, KELLY AFB, TX
SAMPLERS (SIGNATURE): P.O.F. - D. O.

| STATION NO. | DATE | TIME | COMP | GRAB | SAMPLE NUMBER | LOCATION (ID) | NO. OF CONTAINERS |
|-------------|-------|------|------|------|---------------------|---------------|-------------------|
| C.D | 04/19 | | | X | K51 - CD 1/2 - 3688 | | 3 |
| \$2 | 1994 | 0832 | | | | | X |

P.O. #: 2041-3688-13
20000313
REMARKS

ONE SAMPLE IN 3 PARTS

SEND ORIGINAL LAB REPORT

OF RESULTS TO:

MR. CLIFF BLANCHARD

Brown & Root Environmental
800 Oak Ridge Turnpike A-600
Oak Ridge, TN 37830
(615) 483-9900
SEND INVOICE TO KAREN SHERRID
AT ABOVE ADDRESS

FAX RESULTS TO:

CLIFF BLANCHARD
(615) 483-2014 AND
Ray Bettencourt
(210) 927-1118

RELINQUISHED BY (SIGNATURE):

RECEIVED BY(SIGNATURE):

DATE / TIME:

Donna Jungletax
RECEIVED BY(SIGNATURE):

RECEIVED BY(SIGNATURE):

DATE / TIME:

RELINQUISHED BY (SIGNATURE):

RECEIVED BY(SIGNATURE):

DATE / TIME:

DONNA JUNGLETAX
RECEIVED BY(SIGNATURE):

RECEIVED BY(SIGNATURE):

DATE / TIME:

APPENDIX K
 TABLE
 IITRI COST SUMMARY - PHASE II
 RF SOIL DECONTAMINATION DEMONSTRATION

| ITEM | UNIT COST (\$) | SUBTOTALS |
|--|----------------|-------------|
| RF SOURCE | | |
| RF TRANSMITTERS | 242,000 | \$883,852 |
| RF CONTROL UNIT | 600,000 | |
| ELECTRICITY | 41,852 | |
| RF APPLICATION | | |
| EXCITER ELECTRODES | 11,280 | \$25,244 |
| COAXIAL TRANSMISSION LINE | 2,300 | |
| GROUND ELECTRODES | 11,664 | |
| RF SHIELD | | |
| DOGHOUSE | 6,664 | \$7,217 |
| MESH SCREEN | 553 | |
| MEASUREMENT/CONTROL | | |
| THERMAL MEASUREMENT WELLS (TMW) | 66 | \$21,670 |
| VACUUM MEASUREMENT WELLS (VMW) | 29 | |
| THERMOCOUPLES (TCs) AND WIRE | 3,437 | |
| VACUUM/PRESSURE GAUGES | 138 | |
| GAS CHROMATOGRAPH | 18,000 | |
| VAPOR COLLECTION/TRANSFER PIPING | | |
| VAPOR BARRIER | 1,492 | \$3,541 |
| GROUND ELECTRODE PIPING | 1,188 | |
| HORIZONTAL EXTRACTION PIPING | 363 | |
| EXTRACTION MANIFOLD | 497 | |
| VAPOR EXTRACTION/TREATMENT | | |
| REGENERATIVE BLOWER | 1,700 | \$251,700 |
| CATOX TREATMENT UNIT | 250,000 | |
| SITE SUPPORT | | |
| UTILITY TRUCK | 35,000 | \$80,050 |
| CELLULAR TELEPHONE | 4,875 | |
| MISCELLANEOUS ODCS | 47,560 | |
| FENCING | 9,200 | |
| GRAVEL | 2,500 | |
| CONCRETE | 7,108 | |
| WASTE DISPOSAL | 7,108 | |
| LIGHTS | 1,700 | |
| SUBCONTRACTOR SUPPORT | | |
| DRILLING FOR SYSTEM INSTALL | 24,664 | \$190,954 |
| IN GROUND SYSTEM ABANDONMENT | 23,390 | |
| RF CONSULTANTS | 100,000 | |
| ANALYTICAL | 42,900 | |
| LABOR | | |
| SITE PREPARATION/SET-UP | 55,688 | \$477,389 |
| TREATMENT | 403,139 | |
| SITE RESTORATION/DEMOBILIZATION | 18,563 | |
| ODC MARKUP | SUBTOTAL | \$1,941,617 |
| ENGINEERING, PROCUREMENT, & PROJECT MANAGEMENT | 10.60% | \$155,208 |
| CONTINGENCY | 15% | \$219,634 |
| | 15% | \$219,634 |
| | TOTAL | \$2,536,093 |

TABLE
IITRI COST DETAILS - PHASE II
RF SOIL DECONTAMINATION DEMONSTRATION

1

| PUT PARAMETERS | | | | | | |
|----------------------|--------|----|--|------------------------------|----|--|
| ATTMENT AREA (FT) | LENGTH | 44 | | EXCITOR TO EXCITOR (FT) | 4 | |
| | WIDTH | 32 | | EXCITOR TO GROUND (FT) | 8 | |
| | DEPTH | 20 | | GROUND TO GROUND (FT) | 4 | |
| CELL AREA (FT) | WIDTH | 16 | | EXCITOR ELECTRODE DEPTH (FT) | 20 | |
| | LENGTH | 32 | | GROUND ELECTRODE DEPTH (FT) | 28 | |
| | DEPTH | 20 | | VAP. BARRIER OVERLAP (FT) | 10 | |

RF SOURCE

RF TRANSMITTERS

25kW/240V TRANSMITTERS INCLUDES TRAILER, DUMMY LOAD, CHOKES, ELECTRIC FIELD MEASUREMENT EQUIPMENT, TRANSFORMERS, MATCHING NETWORKS OR TUNERS, INSTRUMENTATION FOR ELECTRICAL/RF/TEMPERATURE DATA MANAGEMENT, AND TOOLS

| | | | |
|---------------------|---------------------------------------|--------------|---------|
| 100 | POWER REQUIRED FOR SYSTEM (kW) | \$242,000.00 | CAPITAL |
| 25 | INDIVIDUAL TRANSMITTER POWER (kW) | | |
| \$55,000.00 | COST PER TRANSMITTER | | |
| \$22,000.00 | COST FOR TRAILER | | |
| \$242,000.00 | TOTAL TRANSMITTER/TRAILER COST | | |

RF CONTROL UNIT

HOUSED IN 40' SEMI TRAILER WITH COMPUTERIZED INSTRUMENTATION FOR THE MONITORING AND CONTROL OF RF, ELECTRICAL, TEMPERATURE, VAPOR FLOW AND TREATMENT. THIS TRAILER WILL ALSO HOUSE THE SITE OFFICE AND GC LAB AREA.

| | | | |
|---------------------|--|--|--|
| \$600,000.00 | COST FOR CONTROL UNIT (EST/KAI) | | |
|---------------------|--|--|--|

ELECTRICITY

| | | | |
|--------------------|---|-------------|-------------|
| \$0.07 | COST PER KILOWATT HOUR | \$41,852.16 | DISPOSABLES |
| 170 | POWER USAGE IN KW/H DURING HEATING | | |
| 3,360 | HEATING HOURS (168/WK X TREATMENT TIME) | | |
| 571,200 | KWH USED DURING HEATING | | |
| 15 | POWER USAGE IN KW/H DURING COOLING/OTHER | | |
| 672 | COOLING/OTHER HOURS (168/WK X COOLING AND MOB/DEMOB TIME) | | |
| 10,080 | KWH USED DURING COOLING/OTHER | | |
| 581,280 | TOTAL KWH USED FOR PROJECT | | |
| \$41,852.16 | TOTAL COST FOR ELECTRICITY | | |

RF APPLICATION

EXCITOR ELECTRODES

ALL ARE CONSTRUCTED OF SCH 40 COPPER PIPE WITH BOTTOM PLUGS
OUTSIDE TWO EXCITORS ARE 3"-DIAM. TOPPED WITH 3"6" COPPER ELBOWS (90) INSET 4' FROM END OF CELL
INSIDE EXCITORS ARE 2" DIAM. TOPPED WITH 2" X 6" X 6" COPPER TEES
ALL EXCITORS TIED TOGETHER BY 6" DIAM. SCH 40 COPPER PIPE
MATERIALS TO MAKE UP 2 ROWS OF EXCITORS (PIPE AND CAP) REQUIRED

\$11,280.00

CAPITAL

| | | | |
|-------------------|---|--|--|
| 12 | NO. OF 2" DIAM. EXCITORS = CELL LENGTH - INSET/SPACING - NO. OF 3" DIAM. EXCITORS | | |
| 240 | TOTAL LF = NO. OF EXCITORS PER CELL X DEPTH X 2 ROWS | | |
| \$24.00 | COST PER LF FOR 2" DIAM. SCH 40 COPPER PIPE (EST.) | | |
| \$5,760.00 | COST FOR 2" DIAM. EXCITORS = COST PER LF X TOTAL LF | | |
| \$150.00 | COST FOR EACH COPPER 2"6"6" TEE AND BOTTOM PLUG (EST) | | |
| \$1,800.00 | COST FOR TEES/CAPS = EXCITORS PER CELL X COST PER TEE/PLUG | | |

| | | | |
|-------------------|---|--|--|
| 4 | NO. OF 3" DIAM. EXCITORS (PER ROW = 2) | | |
| 80 | TOTAL LF = NO. OF EXCITORS PER CELL X DEPTH | | |
| \$38.00 | COST PER LF FOR 3" DIAM. SCH 40 COPPER PIPE (SAIC EST.) | | |
| \$3,040.00 | COST FOR 3" DIAM. EXCITORS = COST PER LF X TOTAL LF | | |
| \$170.00 | COST FOR EACH COPPER 3"6"6" TEE AND BOTTOM PLUG (EST) | | |
| \$680.00 | COST FOR TEES/CAPS = NO. OF EXCITORS X COST PER TEE/PLUG | | |

COAXIAL TRANSMISSION LINE
 CONSTRUCTED OF 6" SCH 40 COPPER PIPE IN 3 SECTIONS TIED WITH FLANGES
 TIES RF SOURCE TO MID-POINT OF EXCITOR ELECTRODE ROW, EXTENDS 20' FROM GROUND ROW

| | |
|-------------------|--|
| \$120.00 | COPPER ELBOW (EST) |
| \$200.00 | COPPER TEE (EST) |
| \$45.00 | COST PER LF - 6" DIAM. SCH 40 COPPER PIPE (EST.) |
| 42 | TOTAL LF = 0.5 X GROUND ROW LENGTH + 20' |
| \$30.00 | 6" DIAM. COPPER COMPATIBLE FLANGES |
| \$2,300.00 | TOTAL COST = PIPE, 6 FLANGES, 1 TEE AND 1 ELBOW |

\$2,300.00

GROUND ELECTRODES
 ALL GROUNDS ARE CONSTRUCTED OF 3" DIAM. SCH 40 ALUMINUM PIPE WITH COUPLING AND BOTTOM PLUG
 ALL GROUNDS ARE TOPPED WITH 3 1/2" ALUMINUM ELBOWS WITH ALUMINUM BUS BAR BRACKETS
 GROUND ELECTRODES TIED TOGETHER WITH BUS BARS
 MATERIALS TO MAKE UP 3 ROWS OF GROUNDS (PIPE, COUPLING, BOTTOM PLUG, AND ELBOW)

| | |
|------------|---|
| 36 | NO. OF GROUNDS = ROWS X 12 |
| 1008 | TOTAL LF = NO. OF GROUNDS PER CELL X 1.5 CELLS (3 ROWS) X DEPTH |
| \$8.00 | COST PER LF FOR 3" DIAM. SCH 40 ALUMINUM PIPE (EST.) |
| \$8,064.00 | COST FOR 3" DIAM. GROUNDS = COST PER LF X TOTAL LF |
| \$100.00 | COST FOR ALUMINUM ELBOW, COUPLING, AND BOTTOM PLUG SET |
| \$3,600.00 | COST FOR ELBOWS/CAPS = GROUNDS PER CELL X COST PER ELBOW/PLUG |

RF SHIELD

\$11,664.00

CAPITAL

DOGHOUSE
 CONSTRUCTED OF 0.050 CORRUGATED ALUMINUM SHEETS AND 1/8" ALUMINUM END PLATES

| | |
|-------------------|--|
| 5.80 | COST PER SQUARE FOOT OF 2.67 X 7/8 CORRUGATED ALUMINUM |
| 905 | SQUARE FEET OF ALUMINUM SHEET REQUIRED |
| \$5,246.73 | TOTAL COST FOR CORRUGATED ALUMINUM SHEETING |
| 7.05 | COST PER SQUARE FOOT FOR ALUMINUM PLATE END WALLS |
| 201 | SQUARE FEET OF ALUMINUM PLATE REQUIRED |
| \$1,417.05 | TOTAL COST FOR ALUMINUM PLATE |
| \$6,663.78 | TOTAL COST FOR DOGHOUSE |

\$6,663.78

CAPITAL

MESH SCREEN
 EXTENDS 10' OUT FROM PERIMETER OF DOGHOUSE IN ALL DIRECTIONS

| | |
|-----------------|---------------------------------------|
| 0.32 | COST PER SQUARE FOOT OF ALUMINUM MESH |
| 1728 | SQUARE FEET OF ALUMINUM MESH REQUIRED |
| \$552.96 | TOTAL COST FOR ALUMINUM MESH |

MEASUREMENT/CONTROL

\$552.96

DISPOSABLE

THERMAL MEASUREMENT WELLS (TMW)
 TMWs ARE CONSTRUCTED OF 3" DIA GREEN THREAD FIBERGLASS PIPE COMPLETED 2' AGL

| | |
|----------------|---|
| 6 | NO. OF TMWs |
| 180 | LF OF TMWs= NO. OF TMWsX (GROUND ELECTRODE DEPTH + 2' STICKUP) |
| \$7.30 | COST PER 20 LF OF 3" DIAM. GREEN THREAD FIBERGLASS (ACT.) |
| \$65.70 | COST FOR TOTAL LF OF TMWs = TOTAL LF/20 X COST PER 20 LF |

\$65.70

DISPOSABLE

PRESSURE MEASUREMENT WELLS (PMW)
 PMWs ARE CONSTRUCTED OF 1" DIA SCH 40 PVC PIPE COMPLETED 2' AGL

\$28.80

DISPOSABL

| | |
|----------------|---|
| 8 | NO. OF PMWs |
| 30 | LF PER PMW = GROUND ELECTRODE DEPTH + 2" STICKUP LENGTH |
| 240 | LF OF PMWs= NO. OF PMWs X PMW DEPTH |
| \$2.40 | COST PER 20 LF OF 1" DIAM. SCH 40 PVC PIPE (EST.) |
| \$28.80 | COST FOR TOTAL LF OF PMWs = TOTAL LF/20FT X COST PER 20 LF |

THERMOCOUPLES (TCs) AND WIRE

EVERY 3RD EXCITOR ELECTRODE IN A ROW WILL HAVE K-TYPE TCs AT 6', 12' AND 18' DEPTHS
 EACH TC WILL COME WITH 10' OF WIRE, EXTRA WIRE AND PLUG/JACK FOR EACH TC REQUIRED
 RE REQUIRED TO EXTEND 15' FROM TOP OF EXCITOR AT GROUND LEVEL

3
DISPOSABLE

| | |
|------------|--|
| 48 | TOTAL TCs = TCs PER EXCITOR X EXACTERS PER ROW X 2 ROWS |
| \$19.50 | COST PER TC (EST.) |
| \$936.00 | TOTAL TC COST = TOTAL TCs X COST PER TC |
| 176 | LF WIRE FOR TCs AT 6' DEPTH = NO. OF 6' DC X 11 EXTRA FEET |
| 272 | LF WIRE FOR DC AT 12' DEPTH = NO. OF 12' DC X 17 EXTRA FEET |
| 368 | LF WIRE FOR DC AT 18' DEPTH = NO. OF 18' DC X 23 EXTRA FEET |
| 816 | TOTAL LF OF EXTRA WIRE |
| \$584.00 | COST PER 1000 LF OF WIRE (EST.) |
| \$2,336.00 | COST FOR WIRE = TOTAL LF (1000s) X COST PER 1000 LF |
| \$4.30 | COST OF PLUG/JACK FOR EXTRA WIRE (EST.) |
| 48 | TOTAL PLUG/JACKS = TOTAL DC |
| \$165.12 | TOTAL COST FOR PLUG/JACKS = TOTAL PLUG/JACKS X COST PER X 20% DISCOUNT (EST.) |

- VACUUM/PRESSURE GAUGES

MAGNAHELI 0-10" AND 0-40" GAGES

\$138.00 CAPITAL

| | |
|-----------------|------------------------------|
| 46.00 | COST PER GAUGE |
| 3 | GAUGES REQUIRED |
| \$138.00 | TOTAL COST FOR GAUGES |

GAS CHROMATOGRAPH

PORTABLE GC

\$18,000.00 RENTAL

| | |
|--------------------|--|
| 3000.00 | MONTHLY RENTAL RATE FOR PORTABLE GC |
| 6.00 | TOTAL MONTHS NEEDED |
| \$18,000.00 | TOTAL COST FOR PORTABLE GC RENTAL |

VAPOR COLLECTION/TRANSFER PIPING

VAPOR BARRIER

3 LAYER BARRIER, TWO LAYERS OF REINFORCED PLASTIC AND ONE LAYER OF 2" INSULATION
 BARRIER WILL EXTEND 12' BEYOND EDGE OF CELL IN ALL DIRECTIONS
 INSULATION WILL COVER AREA UNDER SHIELD ONLY WITH NO OVERLAP

\$1,492.48 DISPOSABLE

| | |
|-------------------|---|
| 2240 | PLASTIC BARRIER DIMENSIONS (SQ. FT) = (CELL WIDTH + 20') X (CELL LENGTH + 20') |
| 1024 | INSULATION DIMENSIONS (SQ. FT) = CELL WIDTH X CELL LENGTH |
| \$0.13 | COST PER SQ. FT. FOR REINFORCED PLASTIC BARRIER MATERIAL (EST.) |
| \$0.16 | COST PER SQ. FT. FOR 2" FIBERGLASS INSULATION (MCM CARR) |
| \$1,492.48 | COST FOR BARRIER = (.13/SQ. FT. X 4320 SQ. FT.) X 2 LAYERS + (.16/SQ. FT. X 1600 SQ. FT.) X 2 BARRIERS |

GROUND ELECTRODE PIPING

OUR GROUND ELECTRODE TIED TO 2" GREEN THREAD FIBERGLASS PIPE WITH BLACK 2" VACUUM HOSE
 JIP/ELECTRODE JUNCTION = TEE, 2 ADAPTERS, 2 COUPLING SETS, 2" BALL VALVE, AND 2' OF 2" VACUUM HOSE
 EACH SECTION CONSTRUCTED IN TWO PIECES WITH A MIDPOINT FLANGE, AND END FLANGE

\$1,188.42 CAPITAL

| | |
|-------------------|---|
| 34.15 | COST FOR 2" FIBERGLASS TEE (VEE) |
| 5.00 | COST FOR THREADED FIBERGLASS ADAPTER (VEE) |
| 9.15 | COST FOR 2" COUPLING (1 MALE/1 FEMALE) (VEE) |
| 2.94 | COST PER LV. OF VACUUM HOSE (VEE) |
| 19.90 | COST FOR 2" BRONZE BALL VALVE (ESCO) |
| 15.50 | COST FOR 2" FLANGE 15.50 (VEE) |
| 88.23 | COST FOR ONE JUNCTION (TEE, 2 ADAPTERS, 2 COUPLING SETS, BALL VALVE, AND 2' OF VACUUM HOSE) |
| 0.26 | COST PER LF FOR 2" GREEN THREAD FIBERGLASS PIPE |
| 28.00 | COST FOR 2" FIBERGLASS END CAP |
| 43.22 | COST FOR PIPING ONE GROUND ELECTRODE ROW (CELL LENGTH + 10'), 2 FLANGES |
| \$1,188.42 | TOTAL COST = ((JUNCTION COST X JUNCTIONS PER ROW) + PIPING COST) X 3 ROWS |

4
CAPITAL

HORIZONTAL EXTRACTION PIPING
 TWO SECTIONS OF HORIZONTAL PIPING PER CELL CONSTRUCTED OF 2" GREEN THREAD FIBERGLASS PIPE
 EACH SECTION CONSTRUCTED IN TWO PIECES WITH A FLANGE, END CAP, AND 2 ELBOWS

| | |
|-----------------|--|
| 28.00 | COST FOR 2" FIBERGLASS END CAP |
| 15.50 | COST FOR 2" FLANGE 15.50 (VEE) |
| 0.26 | COST PER LF. FOR 2" GREEN THREAD FIBERGLASS PIPE |
| 9.15 | COST FOR 2" SLEEVE COUPLING |
| 23.65 | COST FOR 2" 90 DEG. ELBOW |
| 26 | INDIVIDUAL SECTION LENGTH (CELL WIDTH + 10') |
| 30 | LENGTH OF PIPE IN FT (INDIV. SECTIONS) |
| 1 | SLEEVE COUPLINGS PER SECTION |
| 120.99 | COST FOR ONE HORIZ. EXT. SECTION (PIPE, 2 FLANGES, 4 COUPLINGS, 2 ELBOWS, 1 END CAP) |
| 3 | HORIZ. EXT. SECTIONS |
| \$362.97 | TOTAL COST = HORIZ. EXT. SECTIONS X CELLS INSTALLED |

\$362.97

EXTRACTION MANIFOLD

TIES TOGETHER ALL VAPOR EXTRACTION COMPONENTS FOR TWO CELLS
 COMPONENTS FOR 2 CELLS INCL 3 ROWS GROUND ELECTRODES AND 3 HORIZ. EXTRACTION SECTIONS
 MANIFOLD CONSTR. WITH FLANGE DIVIDING EACH CELL AND VALVE BETWEEN EACH COMPONENT
 FLEXIBLE VACUUM HOSE TIES MANIFOLD TO INDIV. EXTRACTION COMPONENTS

| | |
|-----------------|---|
| 15.50 | COST FOR 2" FLANGE 15.50 (VEE) |
| 0.26 | COST PER LF FOR 2" GREEN THREAD FIBERGLASS PIPE |
| 34.15 | COST FOR 2" FIBERGLASS TEE (VEE) |
| 5.00 | COST FOR THREADED FIBERGLASS ADAPTER (VEE) |
| 9.15 | COST FOR 2" HOSE COUPLING (1 MALE/1 FEMALE) (VEE) |
| 2.94 | COST PER LF OF VACUUM HOSE (VEE) |
| 19.90 | COST FOR 2" BRONZE BALL VALVE (ESCO) |
| 23.65 | COST FOR 2" 90 DEG. ELBOW |
| 106 | LENGTH OF PIPE = 3 X CELL LENGTH + 10' FOR MISC. SECTIONS |
| 6 | VALVES REQUIRED = 3 ELECTRODE ROWS + 3 HORIZ. EXT. SECTIONS |
| 6 | NUMBER OF 3' HOSE SECTIONS WITH 2 COUPLING SETS REQUIRED |
| \$497.13 | TOTAL COST = PIPE, 2 FLANGES, 3 ELBOWS, 6 TEES, 6-3' HOSE SECTIONS WITH COUPLINGS |

\$497.13

CAPITAL

VAPOR EXTRACTION/TREATMENT

\$1,699.80

CAPITA

REGENERATIVE BLOWER

HOUSED ON 40' FLATBED TRAILER WITH CAT/OX UNIT

| | |
|-------------------|--|
| 1053.00 | REGENERATIVE BLOWER COST - GAST MODEL R6350A-2 |
| 56.80 | VACUUM GAUGE |
| 109.80 | MUFFLER |
| 307.50 | FILTER |
| 172.70 | RELIEF VALVE |
| \$1,699.80 | TOTAL COST FOR BLOWER AND ACCESSORIES |

\$250,000.00

CAPIT.

CATALYTIC OXIDATION TREATMENT UNIT WITH NaOH PRECIPITATION

HOUSED ON A 40' FLAT BED TRAILER. UNIT INCLUDES AMBIENT AIR CONDENSER, WATER SEPARATOR,
 CATALYTIC OXIDIZER, AND NaOH PRECIPITATION UNIT.

\$250,000.00 TOTAL COST FOR TRAILER-MOUNTED TREATMENT UNIT

LABOR

LAB

GENERAL

SITE PREPARATION AND DEMOB

| | SALARY | HR RATE |
|------------------------|--------|-----------------|
| PROJECT MANAGER (ENGR) | 60,000 | 28.85 |
| SR RF ENGINEER | 55,000 | 26.44 |
| JR RF ENGINEER | 45,000 | 21.63 |
| SR FIELD TECHNICIAN | 35,000 | 16.83 |
| | 93.75 | |
| | 117.19 | OVERHEAD (125%) |
| | 21.09 | G&A (10%) |
| | 232.03 | CREW HOUR |

OPERATION

| | SALARY | HR RATE | |
|------------------------|--------|-----------------|--|
| PROJECT MANAGER (ENGR) | 60,000 | 28.85 | |
| SR RF ENGINEER | 55,000 | 26.44 | |
| JR RF ENGINEER | 45,000 | 21.63 | |
| JR RF ENGINEER | 45,000 | 21.63 | |
| SR FIELD TECHNICIAN | 35,000 | 16.83 | |
| SR FIELD TECHNICIAN | 35,000 | 16.83 | |
| | <hr/> | <hr/> | |
| | 132.21 | | |
| | 165.26 | OVERHEAD (125%) | |
| | 29.75 | G&A (10%) | |
| | <hr/> | <hr/> | |
| | 327.22 | CREW HOUR | |

5

SITE PREPARATION/SET-UP

INCLUDES FENCING, MATERIAL RECEIPT, TRAILER/SITE SETUP, ELECTRICAL, DOGHOUSE FAB., MISC. ACTIVITIES
4-MAN CREW WORKING 8 HR DAYS, 5 DAYS PER WEEK

\$55,687.50

LABOR

| | |
|-------------|---|
| 6 | TIME REQUIRED IN WEEKS |
| 232.03 | LABOR RATE FOR 4 MAN CREW (INCLUDES ALL INDIRECTS) |
| 40 | CREW HOURS PER WEEK |
| 240 | TOTAL CREW HOURS REQUIRED FOR SITE PREPARATION/SET-UP |
| \$55,687.50 | TOTAL COST FOR SITE PREPARATION/SET-UP |

TREATMENT

INCLUDES RF/SVE OPERATION, PROJECT MANAGEMENT, AND REPORTING
DOES NOT INCLUDE INITIAL 4 WEEK SET-UP OR FINAL DEMOBILIZATION
2 MEN ON SITE 24 HOURS PER DAY 7 DAYS PER WEEK (=56 CREW HRS)

\$403,139.42

LABOR

| | |
|--------------|--|
| 0.1 | CONTINGENCY FACTOR FOR LOST TIME |
| 327.22 | LABOR RATE FOR 4 MAN CREW (INCLUDES ALL INDIRECTS) |
| 56 | CREW HOURS PER WEEK |
| 20 | TOTAL WEEKS OF TREATMENT |
| 1120 | TOTAL CREW HOURS REQUIRED FOR TREATMENT |
| \$403,139.42 | TOTAL COST FOR TREATMENT CREW |

SITE RESTORATION/DEMOBILIZATION

\$18,562.50

LABOR

| | |
|-------------|---|
| 2 | TIME REQUIRED IN WEEKS |
| 232.03 | LABOR RATE FOR 4 MAN CREW (INCLUDES ALL INDIRECTS) |
| 40 | CREW HOURS PER WEEK |
| 80 | TOTAL CREW HOURS REQUIRED FOR SITE RESTORATION/DEMOBILIZATION |
| \$18,562.50 | TOTAL COST FOR SITE RESTORATION/DEMOBILIZATION |

SITE SUPPORT

TRUCKS AND TRAILERS

ONE TON UTILITY TRUCK WITH OVERHEAD WINCH, HYDRAULIC LIFT, AND SMALL TRAILER

\$35,000

CAPITAL

CELLULAR TELEPHONE

\$4,875.00

SERVICES

| | |
|------------|--|
| 750.00 | MONTHLY RENTAL RATE |
| 7 | MONTHS NEEDED |
| \$4,875.00 | TOTAL RENTAL COST FOR CELLULAR TELEPHONE |

\$47,559.72

MISCELLANEOUS ODCS

| | | UNIT | UNIT | EST. |
|----------|----------------------|-------|----------|-------|
| | | | COST | QTY |
| 21.10 | ALUMINUM FOIL | ROLL | 2.11 | 10 |
| 39.84 | BARRIER TAPE | ROLL | 9.96 | 4 |
| 116.10 | BOOT COVERS | PAIR | 11.61 | 10 |
| 455.00 | CHEMICAL TOILET | MONTH | 65.00 | 7 |
| 204.00 | COTTON GLOVES | PAIR | 0.68 | 300 |
| 6.00 | DECON TUB | EACH | 3.00 | 2 |
| 375.00 | 16-GAL EYEWASH | EACH | 375.00 | 1 |
| 205.00 | DRAEGER PUMP | EACH | 205.00 | 1 |
| 132.00 | DRAEGER TUBES | EACH | 33.00 | 4 |
| 5145.00 | FRAC TANK RENTAL | DAY | 35.00 | 147 |
| 546.20 | FULL FACE RESP. | EACH | 136.55 | 4 |
| 53.00 | HARD HATS | EACH | 5.30 | 10 |
| 4929.80 | HNU DETECTOR | EACH | 4,929.80 | 1 |
| 78.85 | HPLC (4L) | 4L | 15.77 | 5 |
| 1253.00 | LEL/O2 METER W/ ACC. | EACH | 1,253.00 | 1 |
| 146.32 | LIQUINOX DETERGENT | GAL | 18.29 | 8 |
| 86.34 | METHANOL (4L) | 4L | 28.78 | 3 |
| 2000.00 | MILEAGE (TRUCK) | MILE | 0.50 | 4000 |
| 84.60 | MSA COMB. CARTRIDGES | EACH | 2.82 | 30 |
| 600.00 | NaOH | LB | 0.15 | 4000 |
| 113.00 | NITRILE GLOVES | PAIR | 1.13 | 100 |
| 5046.00 | OVA | EACH | 5,046.00 | 1 |
| 28.10 | PACKING TAPE | ROLL | 2.81 | 10 |
| 74.00 | PAPER TOWELS | ROLL | 0.74 | 100 |
| 23284.80 | PROPANE (CAT/OX) | GAL | 0.63 | 36960 |
| 10.08 | PIN FLAGS (BDL50) | BDL | 2.52 | 4 |
| 209.60 | SAFETY GLASSES | EACH | 5.24 | 40 |
| 21.60 | SAMPLE BOWL/TROWEL | EACH | 7.20 | 3 |
| 74.20 | SPAN GAS (HNU) | TANK | 37.10 | 2 |
| 72.08 | SPAN GAS (LEL/O2) | TANK | 36.04 | 2 |
| 1850.00 | STEAM CLEANER | EACH | 1,850.00 | 1 |
| 43.45 | SURGEONS GLOVES | BOX | 8.69 | 5 |
| 127.00 | TRASH BAGS | BOX | 6.35 | 20 |
| 104.76 | TYVEK COVERALLS | EACH | 2.91 | 36 |
| 23.90 | ZIPLOCK BAGS | BOX | 2.39 | 10 |

\$47,559.72 TOTAL MISCELLANEOUS ODC COST

\$9,200.00

CAPITAL

FENCING

FENCE DIMENSIONS ARE 300' BY 200', INSTALLED WITH TWO GATES

| | |
|------------|--|
| 11.50 | COST PER LINEAR FOOT FOR FENCING, INCLUDES GATES |
| 800 | TOTAL LINEAR FOOTAGE REQUIRED |
| \$9,200.00 | TOTAL COST |

\$2,500.00

DISPOSABL

GRAVEL

USED TO REGRADE SITE DURING RESTORATION

\$2,500.00 TOTAL COST FOR GRAVEL (EST.)

\$1,400.00

DISPOSAB

CONCRETE

TRANSFORMER PAD

\$1,400.00 8' X 8' CONCRETE PAD WITH FENCING (EST.)

\$1,700.00

DISPOSAB

LIGHTS

PERIMETER LIGHTS FOR SITE SECURITY AND NIGHT OPERATIONS

| | |
|------------|--|
| 85.00 | EST. COST PER LIGHT INCLUDING POST AND ELECTRICAL HOOKUP |
| 20 | NUMBER OF LIGHTS REQUIRED |
| \$1,700.00 | TOTAL COST FOR LIGHTING |

WASTE DISPOSAL

SLUDGE FROM NaOH PRECIPITATION UNIT, LIQUID FROM AMBIENT AIR CONDENSER, EXCESS SOIL,
AND MISCELLANEOUS (PPE, USED HOSE, ETC.)

\$7,107.50

SERVICES

| | |
|----------------|--|
| 2.50 | COST PER MILE FOR HAZWASTE TRANSPORT (EST) |
| 25.00 | COST FOR BULK DRUM TRANSPORT (EST) |
| 0.40 | COST FOR INCINERATION PER POUND (EST) |
| 150.00 | COST PER DRUM FOR HANDLING DURING INCINERATION PER POUND (EST) |
| 350.00 | COST PER DRUM FOR LANDFILL (EST) |
| 300.00 | COST PER DRUM FOR LANDFILL PICK-UP & HANDLING (EST) |
| 0.25 | COST PER GALLON FOR WATER TREATMENT (EST) |
| | |
| 6,000 | NaOH SLUDGE (LB) - (10 DRUMS) |
| \$4,150 | COST TO DRUM, TRANSPORT, & INCINERATE |
| | |
| 5,000 | LIQUID (GAL) |
| 630 | DECON WATER (GAL) |
| \$1,533 | COST TO TRANSPORT (50 MILES) & TREAT |
| | |
| 3 | MISC. (DRUMS) |
| \$1,425 | COST TO TRANSPORT & LANDFILL |

SUBCONTRACTOR SUPPORT**DRILLING AND ABANDONMENT**

\$24,664.20

SERVICES

SYSTEM INSTALL

| | |
|--------------------|---|
| 1.00 | COST FOR 100 LB. BAG SAND BACKFILL (1 CUBIC FOOT) |
| 10.50 | COST FOR 50 LB BAG BENTONITE CHIPS (0.79 CUBIC FEET) |
| 13.00 | COST PER FOOT FOR BORING (4.25" HS AUGER) |
| 15.00 | COST PER FOOT FOR BORING (8" HS AUGER) |
| 100.00 | COST PER HOUR FOR STANDBY, SITE RESTORATION, MISC. CREW TIME |
| 30.00 | COST PER HOUR FOR DECON |
| 250.00 | MOB/DEMOP RATE EACH MOBILIZATION |
| 30.00 | COST PER BORING FOR SAMPLING |
| 12 | GROUND ELECTRODES PER ROW |
| 3 | GROUND ELECTRODE ROWS IN TREATMENT AREA |
| 30 | DEPTH OF GROUND ELECTRODE BOREHOLES |
| 1080 | TOTAL LINEAR FOOTAGE OF GROUND ELECTRODE BOREHOLES |
| 8 | EXCITOR ELECTRODES PER ROW |
| 2 | EXCITOR ELECTRODE ROWS IN TREATMENT AREA |
| 22 | DEPTH OF EXCITOR ELECTRODE BOREHOLES (8' HS AUGER) |
| 352 | TOTAL LF OF EXCITOR ELECTRODE BOREHOLES (8' HS AUGER) |
| 6 | THERMAL MEASUREMENT WELLS |
| 180 | TOTAL LF OF THERMAL MEASUREMENT WELLS (4.25' AUGER) |
| 8 | PRESUURE MEASUREMENT WELLS |
| 127 | TOTAL LF OF PRESSURE MEASUREMENT WELLS (4.25" AUGER) |
| | |
| 1432 | LF OF GROUND/EXCITOR ELECTRODE BORING |
| \$18,616.00 | DRILLING COST AT \$15 PER FOOT |
| | |
| 307 | LF OF PRESSURE/THERMAL MEASUREMENT WELLS |
| \$3,991.00 | DRILLING COST AT \$13 PER FOOT |
| | |
| 12 | NUMBER OF BORING REQUIRING SAMPLING |
| \$360.00 | COST FOR SAMPLING (\$30 EACH) |
| | |
| 12 | REQUIRED AUGER DECONS (BEFORE EACH SAMPLE AND AT END) |
| 1 | TIME FOR EACH DECON (HRS) |
| \$360 | COST FOR DECON |
| | |
| 501 | 100 LB. BAGS OF SAND REQUIRED (7 BAGS PER 20' OF BORING) |
| \$501.20 | TOTAL SAND COST |
| | |
| 52 | 50 LB. BAGS OF BENTONITE REQUIRED (2 BAGS PER BOREHOLE) FOR INSTALLATION |
| \$546.00 | TOTAL BENTONITE COST |

| | | | |
|-----------------|---|--------------------|----------|
| 1 | MOBILIZATIONS FOR ENTIRE TREATMENT AREA | | |
| 250.00 | COST PER MOBILIZATION/DEMobilization | | |
| \$250.00 | TOTAL MOBILIZATION COST | | |
| 4 | STANDBY HRS (EST) | | |
| \$400.00 | COST PER HR FOR STANDBY | | |
| | | \$23,390.00 | SERVICES |

SYSTEM ABANDONMENT (DISMANTLE)

| | | | |
|-------------------|--|--------------------|----------|
| 100.00 | COST PER HR FOR RIG TIME | | |
| 10.50 | COST OF 50 LB BAG BENTONITE CHIPS (0.79 CUBIC FEET) | | |
| 30.00 | COST PER HOUR FOR DECON | | |
| 250.00 | MOB/DEMOB RATE | | |
| 30.00 | COST PER BORING FOR SAMPLING | | |
| 2.00 | TIME IN HOURS TO ABANDONE AN EXCITOR ELECTRODE (PULL & BENTONITE FILL) | | |
| 2.50 | TIME IN HOURS TO ABANDONE A GROUND ELECTRODE (PULL & BENTONITE FILL) | | |
| 2.50 | TIME IN HOURS TO ABANDONE A PMW OR TMW (PULL & BENTONITE FILL) | | |
| 15.00 | COST FOR EACH ABANDONMENT REPORT | | |
| 5.00 | CUBIC FT BENTONITE PER HOLE (EST) | | |
| 10 | NUMBER OF BORING REQUIRING SAMPLING | | |
| \$300.00 | COST FOR SAMPLING (\$30 EACH) | | |
| 10 | NUMBER OF SOIL SAMPLE HOLES | | |
| 12 | AVERAGE DEPTH IN FT OF BOREHOLE (8" DIA) | | |
| \$1,800.00 | COST OF DRILLING | | |
| 16 | NUMBER OF EXCITOR ELECTRODES | | |
| \$3,440 | COST TO ABANDONE | | |
| 36 | NUMBER OF GROUND ELECTRODES | | |
| \$9,540 | COST TO ABANDONE | | |
| 14 | NUMBER OF PMW's AND TMW's EXCITOR ELECTRODES | | |
| \$3,710 | COST TO ABANDONE | | |
| 76 | NUMBER OF HOLES | | |
| \$3,990 | BENTONITE COST | | |
| 12 | REQUIRED AUGER DECONS (BEFORE EACH SAMPLE AND AT END) | | |
| 1 | TIME FOR EACH DECON (HRS) | | |
| \$360 | COST FOR DECON | | |
| 1 | MOBILIZATIONS FOR ENTIRE TREATMENT AREA | | |
| 250.00 | COST PER MOBILIZATION/DEMobilization | | |
| \$250.00 | TOTAL MOBILIZATION COST | | |
| | | \$42,900.00 | SERVICES |

ANALYTICAL

| | | |
|--------------------|--|--|
| SOIL | | |
| 850.00 | ANALYTICAL COST PER SAMPLE FOR VOCs, SVOCs, TPH, MOISTURE, AND SIEVE | |
| 22 | NUMBER OF SAMPLES TO BE ANALYZED (20 SOIL & 2 WATER) | |
| 100.00 | SAMPLE SHIPPING COST PER EVENT | |
| 200.00 | TOTAL SHIPPING COST | |
| \$18,900.00 | TOTAL ANALYTICAL COST | |

| | | |
|---------------------|--|--|
| VAPOR STREAM | | |
| 4000.00 | ANALYTICAL COST PER SAMPLE FOR VOCs, SVOCs, TPH, MOISTURE, AND SIEVE | |
| 6 | NUMBER OF SAMPLES TO BE ANALYZED (20 SOIL & 2 WATER) | |
| \$24,000.00 | TOTAL ANALYTICAL COST | |

TABLE 3
IITRI AMORTIZATION COST DETAILS
RF SOIL DECONTAMINATION DEMONSTRATION

| CAPITAL EQUIPMENT ITEM | EQUIPMENT COST | SALVAGE VALUE | ANNUAL CAPITAL COST | ANNUAL MAINTENANCE COST | ANNUAL AMORTIZATION COST |
|------------------------------|--------------------|------------------|---------------------|-------------------------|--------------------------|
| RF TRANSMITTER | \$242,000 | \$48,400.00 | \$51,071 | 10% | \$24,200 |
| RF CONTROL UNIT | \$600,000 | \$120,000.00 | \$126,623 | 10% | \$60,000 |
| COAXIAL TRANSMISSION LINE | \$11,280 | \$564.00 | \$2,827 | 25% | \$2,820 |
| EXCITOR ELECTRODES | \$2,300 | \$115.00 | \$576 | 25% | \$575 |
| GROUND ELECTRODES | \$11,664 | \$583.20 | \$2,923 | 25% | \$2,916 |
| RF SHIELD | \$6,664 | \$333.19 | \$1,670 | 25% | \$1,666 |
| VACUUM/PRESSURE GAUGES | \$138 | \$0.00 | \$36 | 25% | \$35 |
| GROUND ELECTRODE PIPING | \$1,188 | \$0.00 | \$314 | 50% | \$594 |
| HORIZONTAL EXTRACTION PIPING | \$363 | \$0.00 | \$96 | 50% | \$181 |
| EXTRACTION MANIFOLD | \$497 | \$0.00 | \$131 | 50% | \$277 |
| BLOWER | \$1,700 | \$339.96 | \$359 | 10% | \$170 |
| CATOX TREATMENT UNIT | \$250,000 | \$50,000.00 | \$52,759 | 10% | \$25,000 |
| TRUCKS AND TRAILERS | \$35,000 | \$7,000.00 | \$7,386 | 10% | \$7,759 |
| FENCING | \$9,200 | \$0.00 | \$2,427 | 50% | \$4,600 |
| TOTAL | \$1,171,994 | \$227,335 | \$249,199 | | \$42,306 |
| | | | | | \$375,704 |