


FINAL
02 APRIL 1996

**FY95 LIMITED ENERGY STUDY
AREA B NITRIC ACID PRODUCTION FACILITIES**

**HOLSTON ARMY AMMUNITION PLANT
KINGSPORT, TENNESSEE**



**U.S. ARMY CORPS OF ENGINEERS
MOBILE DISTRICT**

CONTRACT NO.: DACA01-94-D-0007
DELIVERY ORDER NO.: 004

AESE PROJECT NO.: 95094-00

Prepared By:

Affiliated Engineers SE, Inc.
3300 SW Archer Road
Gainesville, FL 32608
(352) 376-5500
(352) 375-3479 - FAX

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unrestricted

Affiliated Engineers, Inc.

3300 S.W. Archer Road
Gainesville, FL 32608
(352) 376-5500
(352) 375-3479 (FAX)

625 North Segoe Road
P.O. Box 5039
Madison, WI 53705-0039
(608) 238-2616
(608) 238-2614 (FAX)

442 Fifth Street
P.O. Box 2206
Columbus, IN 47202
(812) 376-0885
(812) 377-6459 (FAX)

1646 North Carolina Boulevard
Suite 210
Walnut Creek, CA 94596
(510) 933-8400
(510) 933-8401 (FAX)

Westlake Center
1601 Fifth Avenue
Suite 750
Seattle, WA 98101
(206) 624-7588
(206) 624-5242 (FAX)

110 Banks Drive, Suite 203
Chapel Hill, NC 27514
(919) 967-5364
(919) 967-5365 (FAX)

Suite 2, Room 3
771 Airport Boulevard
Ann Arbor, MI 48108
(313) 669-0434
(313) 669-0445 (FAX)




DEPARTMENT OF THE ARMY
CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS
P.O. BOX 9005
CHAMPAIGN, ILLINOIS 61826-9005

--
REPLY TO
ATTENTION OF:

TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited.
Distribution A. Approved for public release.



Marie Wakefield,
Librarian Engineering

Title Page

Table of Contents

Extracted to go with
Executive Summary

4/19/96

Executive Summary

Extracted 4/19/96

In EN-DM files

History


Holston Army Ammunition Plant (HAAP) in Kingsport, Tennessee, manufactures explosives from raw materials. The facility comprises two separate areas designated Area "A" and Area "B".

At Area "B", Nitric Acid production facilities located in Building 302 include energy intensive AOP lines from which dilute nitric acid is obtained. The original chemical and mechanical equipment was placed in service in 1942, employing a process invented in 1935. Significant modifications have occurred over the extended life of the systems, and the current configuration is shown schematically in Figure 1.

19971017 110

LEGEND

-----	WATER
— A —	AIR
— - -	TAIL GAS
— - -	AMMONIA OR AMMONIA/AIR MIXTURE
— — —	PRODUCT OR PRODUCT GAS
//	STEAM
— C —	CONDENSATE
— → —	DIRECTION OF FLOW
(O)	PUMP
— - -	CHILL WATER



AMMONIA OXIDATION PRO
SCALE: NONE

EXISTING

EXHAUST
STACK

TAIL GAS
0 PSIG
118°F
15,450#/HR

TURBINE
302 HP
3,600 RPM
INLET-58 PSIG,
435°F
OUTLET-0 PSIG

TAIL GAS
58 PSIG
60°F
15,450#/HR

4 PSIG
TF
94#/HR

TAIL GAS
80 PSIG
85°F
15,450#/HR
 $C_p = 0.248 \text{ BTU}/^{\circ}\text{F}$

CW
85°F
2530#/HR
5.0 GPM

EXTENDED
ABSORPTION
COLUMN
(TYP. OF 4)

PRIMARY
ABSORPTION
COLUMN
(TYP. OF 4)


FINAL
BLEACHER
(TYP. OF 2)
PRODUCT A
61% NITRIC
94 PSIG
87°F
6830#/HR(

AMMONIA OXIDATION PROCESS FLOW DIAGRAM

SCALE NONE

EXISTING SYSTEM

TAIL GAS
50 PSIG
65°F
15450#/HR
 $C_p = 0.248 \text{ BTU/}^{\circ}\text{F}$





Problem Statement

Demand by the military for explosives has declined in recent years, and continued progressively decreasing demand is forecast. Because plant mobilization to accommodate any increased military demand (i.e., renewed global conflict involving or supported by the United States) may be required on short notice, the production facilities must be maintained in a ready status.

Todays production demands are met by operating one or two of the four 50 ton/day oxidation process lines in Building 302 four continuous 24-hour days, with monthly equivalent single line operation totaling 96 hours.

Equipment providing heat rejection at the cascade cooler and the water chiller employs technology inconsistent with todays emphasis on energy efficiency. Insulation on piping and pressure vessels containing fluids at elevated temperatures is essentially non-existent. Photographs included as Figure 2 show some of these conditions. All of the steam delivered to the process equipment is discharged to drain as steam condensate. Most of the filtered river water used for process heat rejection is discharged to drain after circuiting the heat exchange equipment.

Figure 2



Purpose of the Study

The purpose of this study is to identify and evaluate the technical and economic feasibility of process or equipment modifications pursuant to conservation of energy and reduction of water consumption at the Ammonia Oxidation Process Facilities in Building 302, Area "B". An adjunct requirement is to avoid proposed modifications which would impose additional maintenance and operation requirements.

The following ECO's specifically identified by scope documents, were investigated:

1. Convert air compressor drive turbine from tailgas to steam or to steam augmentation.
2. Recover heat from product gas leaving the air preheater to produce steam.
3. Water conservation.

Additional ECO's selected by the A/E to be studied include the following:

1. Insulate heat exchangers and tailgas piping.
2. Install preformed plate heat exchangers inside insulation on air preheater and tailgas heater vessels for heat recovery to a 30 psig steam system.
3. Inject air compressor intercooler and aftercooler condensate and steam condensate from the ammonia vaporizer into tailgas entering compressor drive turbine for increased power.

Study Approach

Observations of the installation were made during field surveys conducted July 5, 1995 through July 7, 1995 and again on August 18, 1995. To further establish the A/E's understanding of the chemical processes involved, and the energy associated with the chemical reactions, two reports prepared by other consultants were reviewed. From the final report titled Limited Energy Studies by EMC Engineers, Inc. dated August 1992, a "Process Energy Inventory" tabulation for Nitric Acid Manufacturing, Building 302-B, apparently excerpted from Technical Report No. HDC-39-77 was obtained. The table is presented in the appendix under "Reference Material". The formulae for essential chemical reactions for the production of Nitric Acid by the oxidation of ammonia were obtained from Working Summary Report prepared by AAI Corporation dated December 1992.

The schematic of the AOP process included in the project Detailed Scope of Work was reconstructed to reflect existing system configuration confirmed during field surveys.

It was noted that data contained in the schematic of the AOP process from the scope documents and the previously referenced Process Energy Inventory from Technical Report No. HDC-39-77 apparently represented the system prior to installation in 1991 of four new air compressors manufactured by Joy Manufacturing Co., prior to installation in 1982 of the extended absorption columns, and prior to the installation in 1979 of the refrigerated water system (water chiller).

Process Energy Inventory

A molal analysis of the chemical reactions was performed to determine constituents of the tailgas and to establish water vapor (and liquid) quantities required to be condensed and used as diluent for the product nitric acid. From this calculation and source material from compressor and turbine manufacturers literature, an "Existing System Process Energy Inventory" was developed. The manufacturer's literature is presented in the Appendix under "Reference Material" also included in "Reference Material" are tables, formulae, charts and excerpts from various documents used in the development of the energy and chemical analysis. Table 1 shows the inventory data, which was used to prepare the Ammonia Oxidation Process Flow Diagram/Existing System presented as Figure 1 herein. All ECO's were evaluated using this data for baseline comparison.

TABLE 1. EXISTING SYSTEM PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost		
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream	Remarks	
Ammonia Vaporizer	714.1	Stm. Syst.	149.2	Stm. Cond.	Drain				149.2	Drain		
Mixer	178.8 (177.9)	Air NH ₃										
Converter	7136.1	Reaction	2887.4	Reaction	River Water				2887.4	Drain		
Air Preheater			2902.9	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	816.8	Atmosph.		
Tailgas Heater			2211.4	Prod. Gas	TG & Atmos	2001.5	Prod. Gas	Tailgas	209.9	Atmosph.		
Cascade Cooler	4869.4	80% HNO ₃ Reaction	2846.2	Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos				2846.2	Drain		
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens.	River Water				86.5	Drain		
Air Compressor	2018.2	Elect. Mtr	2750.6	H ₂ O Vapor Condens.	River Water				2750.6	Drain	793 hp	
Tailgas Turbine	768.2	Heat Recovered	2097.4	Turbine Exhaust	Atmos.	768.2			1329.2	Exh to Atmosph	302 hp	
Final Bleacher			118.7	Product	Product	118.7	Product	Product				
Unaccounted Losses									673.9			
TOTAL	16724.2		16724.2			4974.5			11749.7			

Assumptions

The following assumptions have been made:

1. A Molar products table based on a hydrocarbon fuel composition of $(CH_2)_n$ will yield suitable results for the products of combustion of NH_3 (ammonia), provided that the percentage of theoretical air is the same composition for the ammonia as the hydrocarbon. (Gas tables by Kennan and Kaye are sufficiently accurate).
2. Air temperature entering the mixer is automatically controlled at 625° F by mixing nominal 100° F, 115 psig air from the aftercooler with uncontrolled air leaving the air preheater.
3. Existing tailgas heater materials of high chrome iron are compatible with high temperature heat transfer fluids substituted for the tailgas.
4. Existing turbines operating on tailgas flow streams will have similar efficiency when operating on steam.

Energy Conservation Opportunities

ECO No. 1: Turbine Conversion to Steam

The existing turbines, manufactured by Dresser-Rand Steam Turbine and Motor Division, used to augment the electric motors driving the air compressors, were basically designed as steam turbines but are currently employed as gas turbines for recovery of energy contained in process tailgas. Based on energy balance documents furnished by the government, calculated shaft output with 15,450 lb/hr, 58 psig, 435°F gas at the turbine inlet is 347 hp with turbine exhaust to atmosphere. At conditions determined independently as work of this report, the calculated turbine output is 302 hp. Inlet temperatures are limited to 750°F maximum.

Replacement of the turbines with new 1,200 hp condensing type units to operate on the Thermodynamic Rankine Cycle with steam/water as the working fluid is proposed. Steam at 300 psig and 525°F from the central plant will be directed to the steam turbine. Turbine exhaust at 2.0 inch Hg vacuum will be condensed in a steam surface condenser using river water as the condensing medium. From the condenser, the condensate will be returned to the central plant by condenser hotwell pumps.

Performance of the Rankine Cycle System in the AOP process is indicated schematically in Figure 3 herein. Shaft energy produced will displace electric motor energy required to drive air compressors. Table 2 shows the energy inventory associated with ECO No. 1.


ECO No. 2: Steam Produced from Product Gas

Introduction of liquid Dowtherm A heat transfer fluid into the existing tailgas heater vessel (liquid in place of tailgas) is proposed to recover heat from the product gas prior to its introduction to the cascade heater. The fluid, the eutectic mixture of diphenyl oxide and diphenyl, would then be pumped through a closed system in which the fluid would release heat in an unfired steam boiler vessel to produce steam at 100 psig and 30°F for use in AOP process equipment or for offsetting steam production in the central plant.

Figure 3


LEGEND

-----	WATER
— A —	AIR
— - -	TAIL GAS
— - -	AMMONIA OR AMMONIA/AIR MIXTURE
— — —	PRODUCT OR PRODUCT GAS
//	STEAM
C	CONDENSATE
— → —	DIRECTION OF FLOW
— O —	PUMP
— - -	CHILL WATER



AMMONIA OXIDATION
SCALE: NONE

STEAM TURBINE




AMMONIA OXIDATION PROCESS FLOW DIAGRAM

BOLD: NONE

ECO NO. 1

STEAM TURBINE DRIVEN AIR COMPRESSOR



OXIDATION PROCESS FLOW DIAGRAM

ECO NO. 1

TURBINE DRIVEN AIR COMPRESSOR

TABLE 2. ECO NO. 1 PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost			Remarks
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream	MBH	Waste Stream	
Ammonia Vaporizer	714.1	Stm. Syst.	149.2	Stm. Cond. to Drain					149.2	Drain			
Mixer	178.8 (177.9)	Air NH_3											
Converter	7136.1	Reaction	2887.4	Reaction	River Water				2887.4	Drain			
Air Preheater			2902.9	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	816.8	Atmosph.			
Tailgas Heater			704.0	Prod. Gas	TG & Atmos				704.0	Atmosph.			
Cascade Cooler	4869.4	80% HNO_3 Reaction	4163.4	Prod. Gas & H_2O Vapor Condens.	River Water Drain & Atmos				4163.4	Drain			
Absorption Columns	1217.3	20% HNO_3 Reaction	86.5	Prod. Gas & H_2O Vapor Condens.	River Water				86.5	Drain			
Air Compressor	2786.8	Turbine	2750.6	H_2O Vapor Condens.	Atmos. River Water				2750.6	Atmos. Drain			
Steam Turbine	10525.0	Steam from Steam Plant	13312.0	Turbine Exhaust	Condens. & River Water	526.5	Stm. Cond.	Stm. Pint	12785.5	Stm. Surf. Cond.	12840 #/hr Steam Rqd. @ 300 psi @ 525°F • 1095 hp		
Final Bleacher			118.7	Product	Product	18.7	Product	Product					
Stack Loss			95.8	Tailgas	Atmos.				95.8	Atmos.			
Unaccounted Losses					89.1						89.1		
TOTAL	27259.6		27259.6					2731.3			24528.3		

This ECO would eliminate the availability of high energy tailgas use in the existing air compressor gas turbine. Release of the low temperature tailgas to atmosphere (from 58 psig) will be a source of objectional noise. It integrates ideally into the proposed system in ECO No. 1. Table 3 shows the energy inventory associated with ECO No. 2, and Figure 4 represents the AOP process with ECO No. 2 incorporated.

ECO No. 3: Water Conservation at Chiller and Cascade Coolers

Filtered river water discharged to drain, is 20°F to 80°F above river water temperature. No contaminants are introduced into the flow streams at Building 302. It is proposed to evaporatively cool the water in an induced draft cooling tower and return it to the heat rejection equipment so that costs at the Central Water Treatment Plant can be reduced. Primarily, savings will be derived from reduced demand for aluminum sulfate and hydrated lime in the flocculation process of the filter plant.

Table 4 and Figure 5 represent the AOP process with proposed ECO No. 3 water conservation incorporated.

ECO No. 4: Insulate Heat Exchangers

Heat is released to the atmosphere by radiation and convection from the dull bare metal surface of the nominal 18 inch diameter pressure vessels and 6 inch diameter tailgas piping. Standard high temperature calcium silicate pipe insulation with protective metal jacket is to be installed to increase recovered energy used in the air compressor gas turbine drive unit. Proposed insulation thickness is 1 inch.

AOP process parameters with proposed insulation are indicated in Table 5 and in Figure 6 herein.

ECO No. 5: Insulated Heater Surfaces with Low Pressure Steam Recovery

This ECO is an adjunct to ECO No. 4 - Insulate Heat Exchangers. Plant steam will still be required for production and process startup, but approximately 80% of steam used in the ammonia vaporizer will be derived from recovered energy.

A new 30 psig steam/condensate system, is proposed. The 30 psig steam is produced in a waste heat steam generator (WHSG) to extract heat from the 480°F turbine exhaust gas. Exhaust gas (tailgas) exiting the WHSG is discharged to atmosphere.


TABLE 3. ECO NO. 2 PROCESS ENERGY INVENTORY


Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost			Remarks
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream	MBH	Heat Lost	
Ammonia Vaporizer	714.1	Stm. Syst.	149.2	Stm. Cond. to Drain					149.2	Drain			
Mixer	178.8 (177.9)	Air NH ₃											
Converter	7136.1	Reaction	287.4	Reaction	River Water				2887.4	Drain			
Air Preheater			2902.9	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	816.8	Atmosph.			
Dowtherm Heater	608.7	10% HNO ₃ Reaction	3234.6	Prod. Gas	Dowtherm & Atmos.	2990.8	Prod. Gas	Dowtherm	243.8	Atmosph.			±2690 #/hr saturated steam produced @ 100 psig
Cascade Cooler	4260.5	70% HNO ₃ Reaction	1949.4	Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos				1949.4	Drain			
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens.	River Water				86.5	Drain			
Air Compressor	2786.8	Elect. Meter	2750.6	H ₂ O Vapor Condens.	River Water				2750.6	Atmos. Drain	1095 hp		
Final Bleacher			118.7	Product	Product	118.7	Product	Product					
Stack Loss			95.8	Tailgas	Atmos.				95.8	Atmos.			
Unaccounted Losses			2549.3						2549.3				
TOTAL	16724.4		16724.4			5195.6			11528.8				

Figure 4

LEGEND

- - - - WATER
- A — AIR
- - - TAIL GAS
- - - AMMONIA OR AMMONIA/AIR MIXTURE
- - - PRODUCT OR PRODUCT GAS
- // STEAM
- C CONDENSATE
- → DIRECTION OF FLOW
- O — PUMP
- - - CHILL WATER
- D — DOWTHERM A






ECO NO. 2
DOWTHERM HEAT EXCHANGER

(2)

TAIL GAS
80 PSIG
85°F
15450#/HR
 $C_p = 0.248 \text{ BTU}/^{\circ}\text{F}$



DATION PROCESS FLOW DIAGRAM

ECO NO. 2

THERM HEAT EXCHANGER

(3)

TABLE 4. ECO NO. 3 PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost		
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream	Remarks	
Ammonia Vaporizer	714.1	Stm. Syst.	149.2	Stm. Cond. to Drain						149.2	Cooling Tower	
Mixer	178.8 (177.9)	Air NH ₃										
Converter	7136.1	Reaction	2887.4	Reaction	River Water				2887.4	Cooling Tower		
Air Preheater			2902.9	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	816.8	Atmosph.		
Tailgas Heater			2211.4	Prod. Gas	TG & Atmos	2001.5	Prod. Gas	Tailgas	209.9	Atmosph.		
Cascade Cooler	4869.4	Reaction	2846.2	80% HNO ₃ Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos				2846.2	Cooling Tower		
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens.	River Water				86.5	Cooling Tower		
Air Compressor	2018.2	Elect. Meter	2750.6	H ₂ O Vapor Condens.	River Water				2750.6	Cooling Tower		
Tailgas Turbine	768.2		2097.4			768.2			1329.2	Exh. to Atmosph		
Final Bleacher			118.7	Product	Product	118.7	Product	Product	302 hp			
Unaccounted Losses									673.9			
TOTAL	16724.2		16724.2			4974.5			11749.7			


Figure 5

COOLING TOWER DATA

566 GPM
108°F EWT
85°F LWT
76°F W.B.
85000 CFM FAN
• 15 HP
6 GPM BLOWDOWN
12 GPM MAKEUP

LEGEND

-----	WATER
— A —	AIR
— - -	TAIL GAS
— - -	AMMONIA OR AMMONIA/AIR MIXTURE
— - -	PRODUCT OR PRODUCT GAS
//	STEAM
— C —	CONDENSATE
— - -	DIRECTION OF FLOW
— O —	PUMP
— - -	CHILL WATER




AMMONIA OXIDATION

SCALE: NONE

EC

INCORPORATE

TAIL GAS
80 PSIG
85°F
15450#/HR
 $C_p = 0.248 \text{ BTU}/\text{lb}$







TABLE 5. ECO NO. 4 PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost		
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream	Remarks	
Ammonia Vaporizer	714.1	Stm. Syst.	149.2	Stm. Cond. to Drain					149.2	Drain		
Mixer	178.8 (177.9)	Air NH ₃										
Converter	7136.1	Reaction	2887.4	Reaction	River Water				2887.4	Drain		
Air Preheater			2128.8	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	42.7	Atmosph.		
Tailgas Heater			2496.7	Prod. Gas	TG & Atmos	2473.6	Prod. Gas	Tailgas	23.1	Atmosph.		
Cascade Cooler	4869.4	80% HNO ₃ Reaction	2092.1	Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos				2092.1	Drain		
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens.	River Water				86.5	Drain		
Air Compressor	1618.6	Elect. Meter	2750.6	H ₂ O Vapor Condens.	River Water				2750.6	Drain	636 hp	
Tailgas Turbine	1168.2	Recovered Heater	2582.1	Tailgas	Atmos.	1168.2			1413.9	Exh. to Atmosph	459 hp	
Final Bleacher			118.7	Product	Product	118.7	Product	Product				
Unaccounted Losses									1432.5			
TOTAL	16724.6		16724.6			5846.6			10878.0			

Figure 6


LEGEND

— - - -	WATER
— A —	AIR
— - - -	TAIL GAS
— - - -	AMMONIA OR AMMONIA/AIR MIXTURE
— — — —	PRODUCT OR PRODUCT GAS
//	STEAM
C	CONDENSATE
— → —	DIRECTION OF FLOW
(O)	PUMP
— - - -	CHILL WATER



AMMONIA OX
SCALE: NONE


TAIL GAS
80 PSIG
85°F
15450#/HR
 $C_p = 0.248 \text{ BTU}/\text{#}$



AMMONIA OXIDATION PROCESS FLOW DIAGRAM

ECO NO.4

1st INSULATION ON HEATERS



ON PROCESS FLOW DIAGRAM

CO NO.4

TION ON HEATERS

Results of integrating this ECO into the AOP process are shown in Table 6 and Figure 7.

ECO No. 6: Water Injection at Gas Turbine

Not developed.

ECO No. 7: Recovered Steam Injected at Tailgas Turbine Inlet

Recovery of relatively pure water obtained from air compressor intercoolers and aftercoolers and from steam trap discharge at the ammonia vaporizer, all of which is presently discharged to waste, will be utilized for makeup to a waste heat steam generating system (WHSG) consisting of two recovery sections, one located in product gas stream leaving the platinum filter and the other in the wet gas stream leaving the turbine, and a steam separator vessel.

Additional boiler water makeup (approximately 10%) from the steam plant will augment the recovered water. Steam from the WHSG will be introduced into the hot tailgas from the tailgas heater to increase turbine output and offset electrical load of the compressor drive motor, and will be discharged to atmosphere along with the tailgas.

Introduction of the steam into the tailgas will be made at a sufficient distance upstream of the turbine inlet, in the existing 6 inch diameter standard black iron piping. The WHSG section in the product gas stream will be constructed of high chromium stainless steel (400 series) for surfaces in contact with product gas. The wet gas WHSG section will be standard steel construction as offered by Clayton Industries, El Monte, CA.

AOP process parameters with the proposed steam injection system, incorporated with the insulation evaluated in ECO #4, are shown in Table 7 and Figure 8 herein.


TABLE 6. ECO NO. 5 PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost			Remarks
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream			
Ammonia Vaporizer	714.1	L.P. Steam	149.2	Steam Cond.	Drain	149.2	Steam Cond.	LP Steam					
Mixer	178.8 (177.9)	Air NH ₃											
Converter	7136.1	Reaction	2887.4	Reaction	River Water							2887.4	Drain
Air Preheater			2128.8	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air				42.7	Atmosph.
Tailgas Heater			2496.7	Prod. Gas	TG & Atmos & L.P. Stm	2473.6	Prod. Gas Prod. Gas	Tailgas L.P. Stm Syst.				23.1	Atmosph.
Cascade Cooler	4869.4	80% HNO ₃ Reaction	2092.1	Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos							2092.1	Drain
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens.	River Water							86.5	Drain
Air Compressor	1618.6	Elect. Meter	2750.6	H ₂ O Vapor Condens.	River Water							2750.6	Drain
Tailgas Turbine	1168.2	Recovered Heat	2582.1	Turb. Exh.	Stack	1758.3	Stack	L.P. Stm Syst.	823.8	Exh. to Atmosph		636 hp	459 hp
Final Bleacher			118.7	Product	Product	118.7	Product	Product					
Unaccounted Losses			1432.5									1432.5	
TOTAL	16724.6		16724.6				6585.9			10138.7			


Figure 7


LEGEND

-----	WATER
— A —	AIR
-----	TAIL GAS
-----	AMMONIA OR AMMONIA/AIR MIXTURE
— — —	PRODUCT OR PRODUCT GAS
//	STEAM
— C —	CONDENSATE
— → —	DIRECTION OF FLOW
— P —	PUMP
— — —	CHILL WATER



TAIL GAS
80 PSIG
85°F
15450#/HR
 $C_p = 0.248 \text{ BTU}/^{\circ}\text{F}$





ION PROCESS FLOW DIAGRAM

ECO NO.6

ITION ON HEATERS
URE STEAM RECOVERY

(3)


TABLE 7. ECO NO. 7 PROCESS ENERGY INVENTORY

Equipment	Heat Gain			Heat Rejected			Heat Recovered			Heat Lost		Remarks
	MBH	Source	MBH	Source	Destination	MBH	Source	Recipient	MBH	Waste Stream		
Ammonia Vaporizer	714.1	L.P. Steam	149.2	Steam Cond.	Tailgas	149.2	Steam Cond.	Tailgas				
Mixer	178.8 (177.9)	Air NH ₃										
Converter	7136.1	Reaction	2887.4	Reaction	River Water				2887.4	Drain		
Air Preheater			2128.8	Prod. Gas	Air & Atmos	2086.1	Prod. Gas	Air	42.7	Atmosph.		
Tailgas Heater	2434.7	40% HNO ₃ Reaction	2496.7	Prod. Gas & H ₂ O Vapor Condens.	TG & Atmos	2473.1	Prod. Gas	Tailgas	23.1	Atmosph.		
Prod. Gas Recov. Boiler	608.7	10% HNO ₃ Reaction	816.9	Prod. Gas	LP Steam	816.9	Prod. Gas	LP Steam			765 #/hr Steam	
Wet Gas Boiler							837.9	Turb Exh.	L.P. Steam	956.6	Stack	786 #/hr Steam
Cascade Cooler	1826.0	30% HNO ₃ Reaction	1275.2	Prod. Gas & H ₂ O Vapor Condens.	River Water Drain & Atmos					1275.2	Drain	
Absorption Columns	1217.3	20% HNO ₃ Reaction	86.5	Prod. Gas & H ₂ O Vapor Condens. & Reaction	Prod. Gas & H ₂ O Vapor Condens.					86.5		
Air Compressor	1425.2	Elect. Meter	2750.6	H ₂ O Vapor Condens.	River Water					2750.6	Drain	560 hp
Tailgas Turbine	1361.6	Recovered Heat	3156.1	Turbine Exhaust	Wet Gas Recov. Blr	1361.6	Wet Gas	Air				535 hp
Final Bleacher			118.7	Product	Product	118.7	Product	Product				
Unaccounted Losses			859.0							859.0		
TOTAL	16724.6		16724.6			7843.5				8881.1		

Figure 8

LEGEND

- - - - WATER
- A — AIR
- - - TAIL GAS
- - - AMMONIA OR AMMONIA/AIR MIXTURE
- - - PRODUCT OR PRODUCT GAS
- // — STEAM
- C — CONDENSATE
- - - DIRECTION OF FLOW
- PUMP — PUMP
- - - CHILL WATER




AMMONIA OXIDATION


SCALE: NONE

EC

STEAM/WATER INJECTORS AND ADD

TAILGAS
 80 PSIG
 85°F
 15405#/HR
 $C_p = 0.246 \text{ BTU}/^{\circ}\text{F}$





ADDITION PROCESS FLOW DIAGRAM

ECO NO. 7

3 INJECTION AT TAILGAS, INSULATE
ND ADD WASTE HEAT RECOVERY

(3)

Calculations

Calculations for energy inventories throughout the product gas and tailgas flow streams were made using published data where available. Heat release from the exothermic reaction in the product gas stream, as indicated on flow diagrams and tables in the material furnished by the government and the operating contractor, was adjusted by application of principles and chemical values from several engineering handbooks. Excerpts from these handbooks are presented in the Appendix, section Reference Material.

Thermodynamic properties of steam and water vapor in air were obtained from "Thermodynamic Properties of Steam"; thermodynamic properties of air were obtained from "Gas Tables". Specific heat data for various gases and liquids were obtained from "Marks' Standard Handbook for Mechanical Engineers" and additional textbooks. Heat loss for bare and insulated pipes was obtained from insulation manufacturers catalogs. Thermodynamic properties of Dowtherm A heat transfer fluid were obtained from "Marks' Handbook" and from tabular data in Platecoil Catalog, Tranter, Inc. In general, where data was obtained from graphically presented material, the diagram is included in the Appendix with the detailed calculations.

Basic formulae, definitions, numerical values and results of calculations for process chemical and thermal parameters are presented in this section.

Detailed calculation sheets are included in Appendix.

Calculations For: Pound Moles per Hour Delivered to Process

$$\text{NH}_3: \frac{\text{lbs/hr}}{\text{mol. wt}} = \frac{1088 \text{ lbs/hr}}{17.0307} = 63.88 \text{ #-mol/hr}$$

Specific Humidity of Air/Vapor Mixture:

$$W = \frac{P_V R_\alpha}{(P_m - P_V) R_V}$$

Where: P_V = Vapor pressure of water @ 100°F dewpoint

P_m = Air/vapor mixture pressure

R_α = Universal gas constant/mol. wt. of air

R_V = Universal gas constant/mol. wt. of H_2O

$$W = \frac{(0.9492 \text{ psia}) (1544/28.9644)}{(129.97 \text{ psia} - 0.9492 \text{ psia}) (1544/18.016)} = 0.0046 \text{ #vapor/#dry air}$$

Air/Vapor Mixture Mass Flow = 16556 lbs/hr

$$H_2O: \frac{16556 \text{ lbs/hr}}{1 + \frac{1}{0.0046 \text{ lbs/# dry air}}} = 75.81 \text{ lbs/hr}$$

$$\frac{\text{lbs/hr}}{\text{mol. wt}} = \frac{75.81 \text{ lbs/hr}}{18.016} = 4.21 \text{ #-mol/hr}$$

Dry Air Mass Flow = 16556 lbs/hr - 75.81 lbs/hr = 16480.19 lbs/hr

$$N_2: \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr} (0.78084)}{28.9644} = 444.28 \text{ #-mol/hr}$$

$$O_2: \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr} (0.20948)}{28.9644} = 119.19 \text{ #-mol/hr}$$

$$A_R: \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr} (0.00934)}{28.9644} = 5.31 \text{ #-mol/hr}$$

$$\text{Other: } \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr} (0.00034)}{28.9644} = 0.19 \text{ #-mol/hr}$$

TOTAL 568.97 #-mol/hr

COMBUSTION CALCULATIONS—MOLAL BASIS



FLUE GAS (F.G.) COMPOSITION
MOLES PER FUEL UNIT (AF)

L	FUEL, O ₂ , AND AIR PER UNIT OF FUEL	FLUE GAS (F.G.) COMPOSITION MOLES PER FUEL UNIT (AF)							
N	FUEL CONSTITUENT	PER FUEL UNIT, LB	MOL. WT	MOLES	O ₂ : MOL. FUEL	O ₂ : THEO. REQD	N ₂	H ₂ O	CO
1	N ₂ TO NO ₂	15.97	2	31.94	31.94				0
2	C TO CO	28.0	12	0	.5	0			
3	CO TO CO ₂	28.0	0	0	.5	0			
4	C UNBURNED, LINE k	12.0	0						
5	H ₂	2	47.91	.5	23.96				23.96
6		32.0	0	1	0				
7	O ₂ (DEDUCT)	32.0	0	1	0				
8	N ₂	28.0	—	0	0.00				
9	CO ₂	4.0	—	0	—				
10	H ₂ O	18.0	0	0	—				
11	ASH			0	—				
12	SUM			63.88	55.90				
	O ₂ AND AIR, MOLES FOR TOTAL AIR (SEE LINE d AT RIGHT)								
13	O ₂ (THEO) REQD = O ₂ , LINE 12			55.90	0				
14	O ₂ (EXCESS) = T.A. - 100% X O ₂ , LINE 12			0					
15	O ₂ (TOTAL) SUPPLIED = LINES 13 + 14			55.90					
16	N ₂ SUPPLIED = 3.73 X O ₂ , LINE 15			208.37	208.37				
17	AIR (DRY) SUPPLIED = O ₂ + N ₂			264.27					
18	H ₂ O IN AIR = MOLES DRY AIR X $\frac{A}{B-A}$			1.96					
19	AIR (WET) SUPPLIED = LINES 17 + 18			266.23					
20	FLUE GAS CONSTITUENTS = LINES 1 TO 18, TOTAL			31.94	0	208.37	25.92	0	

CO, NEGL. O ₂ , 21% CONCENT. N ₂	78%	t	c
TOTAL AIR (T.A.) ASSIGNED or by ORSAT	100	%	d
LINES f, g, h FOR GASEOUS FUELS			e
WT. FUEL UNIT = $\Sigma (\text{MOLES EACH} \times \text{MOL WT})$ LB			f
MOL WT OF FUEL = LINE	17.031	g	
SP WT OF FUEL @ 80 F & 29.9" = $\frac{\text{LINE g}}{394}$ LB CU FT			h
FUEL HEAT VALUE, BTU/LB	CU FT	i	
COMBUSTIBLE IN REFUSE, % "C"	0 %	j	
CARBON UNBURNTED, LB/100 LB FUEL	0.0	k	
= % ASH IN FUEL $\times \frac{100 - \% \text{"C}''}{100 - \% \text{"C}''}$			
EXIT TEMP OF FLUE GAS, t ₁			f
DRY-BULB (AMBIENT) TEMP, t ₁	100	F	m
WET-BULB TEMP	100	F	n
REL HUMID (PSYCHROMETRIC CHART)	100 %	o	
B°, PSYCHROMETRIC PRESSURE, psia	129.97	p	
SAT. PRESS. H ₂ O AT AMB TEMP, IN.	0.95	q	
A°, PRESS. H ₂ O IN AIR, LINES 10 X q,	0.95	r	
TOTAL WET FLUE GAS MOLES	266.23	DRY FLUE GAS 240.31	s
$\frac{0.95}{240.31 - 0.95} = 0.0074$			t

21 • NOTE—FOR AIR AT 80 F AND 60% RELATIVE HUMIDITY, $\frac{A}{B-A} = 0.0212$ IS OFTEN USED AS STANDARD. $\frac{0.95}{240.31 - 0.95} = 0.0074$

*NOTE: FLUE GAS ANALYSIS BY ORSAT, IF CO IS PRESENT IN FLUE GASES, A CARBON BALANCE IS USED TO DETERMINE DISTRIBUTION OF C, THUS:
 ALL C IN FUEL = C IN FLUE GAS CONSTITUENTS + C IN REFUSE, MOLES C IN FUEL = % C BY ANAL + 12% CO BY ORSAT + % CO₂ BY ORSAT + % CO IN FLUE GAS ANALYSIS.
 ALL C IN FUEL = 1.00 - (MOLES C IN FUEL - MOLES C IN FLUE GAS CONSTITUENTS + MOLES C IN REFUSE) X 100.

$$\frac{\% \text{N}_2}{\% \text{O}_2} = \frac{18.084}{20.948} = 3.7275$$

COMBUSTION CALCULATIONS—MOLAL BASIS

$N_2 + 2O_2 \rightarrow 2NO_2$

FLUE GAS (F.G.) COMPOSITION MOLES PER FUEL UNIT (AF)									
FUEL, O ₂ , AND AIR PER UNIT OF FUEL	PER FUEL UNIT	AOL.	FUEL WT	O ₂ MOLES	O ₂ THEO	H ₂ O	CO	CO ₂	O ₂ Avail
1 N ₂ TO NO ₂	31.65	2	2.8	.5	63.29	0	0	0	119.19
2 C TO CO	—	12	0	.5	0	0	0	0	#-moles/hr
3 CO TO CO ₂	—	28	0	.5	0	0	0	0	#-moles/hr
4 C UNBURNED, LINE 1	—	12	0	0	0	0	0	0	b
5 H ₂	—	2	0	.5	0	0	0	0	c
6 N ₂ (DEDUCT)	—	32	0	1	0	0	0	0	d
7 O ₂	32	0	1	0	0	0	0	0	e
8 N ₁	—	28	0	0	0	0	0	0	f
9 CO ₂	—	44	0	0	0	0	0	0	g
10 H ₂ O	—	18	0	0	0	0	0	0	h
11 ASH	—	0	0	0	0	0	0	0	i
12 SUM	—	12	0	0	0	0	0	0	j
O ₂ AND AIR, MOLES FOR TOTAL AIR 100% (SEE LINE d AT RIGHT)									
13 O ₂ (THEO) REQD = O ₂ , LINE 12	63.29	0	0	0	63.29	0	0	0	k
14 O ₂ (EXCESS) = $\frac{I.A. - 100}{100} \times O_2$, LINE 12	0	0	0	0	0	0	0	0	l
15 O ₂ (TOTAL) SUPPLIED = LINES 13 + 14	63.29	0	0	0	63.29	0	0	0	m
16 N ₂ SUPPLIED = $(3.73 \times O_2)_{\text{THEO}}$	14.45	0	0	0	14.45	0	0	0	n
17 AIR (DRY) SUPPLIED = O ₂ + N ₂ (TOTAL)	204.26	0	0	0	204.26	0	0	0	o
18 H ₂ O IN AIR = MOLES DRY AIR $\times \frac{A}{B}$	—	—	—	—	—	0.21	0.21	0.21	p
19 AIR (WET) SUPPLIED = LINES 17 + 18	—	—	—	—	—	304.41	304.41	304.41	q
20 FLUE GAS CONSTITUENTS = LINES 1 TO 18, TOTAL	63.29	0	0	0	63.29	0	0	0	r
21 •NOTE—FOR AIR AT 80° F AND 60% RELATIVE HUMIDITY, $\frac{A}{B - A} = 0.0212$ IS OFTEN USED AS STANDARD.	0.95	0	0	0	0.95	0	0	0	s

NOTE: FLUE GAS ANALYSIS BY ORSAT, IF CO IS PRESENT IN FLUE GASES, A CARBON BALANCE IS USED TO DETERMINE DISTRIBUTION OF C, THUS:

$$\frac{\% N_2}{\% O_2} = \frac{78.084}{20.948} = 3.7271$$

ALL C IN FUEL = C IN FLUE GAS CONSTITUENTS + C IN REFUSE, MOLES C IN FUEL = $\frac{C}{100}$ C BY ANAL. + $\frac{C}{12}$ MOLES C IN REFUSE X % CO₂ BY ORSAT.

Calculations For: Theoretical Pound Moles per Hour Product Gas

NO₂: 31.94 #-mol/hr + 63.29 #-mol/hr = 95.23 #mol/hr

N₂: 208.37 #-mol/hr + 204.26 #-mol/hr = 412.63 #mol/hr

H₂O: 25.92 #-mol/hr + 2.21 #-mol/hr = 28.13 #-mol/hr

From Sheet 1:

$$A_R: \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr (0.00934)}}{28.9644} = 5.31 \text{ #-mol/hr}$$

$$\text{Other: } \frac{\text{lbs/hr} \times \text{mol. fract}}{\text{mol. wt. air}} = \frac{16480.19 \text{ lbs/hr (0.00034)}}{28.9644} = 0.19 \text{ #-mol/hr}$$

$$\text{TOTAL} = 541.49 \text{ #-mol/hr}$$

$$\text{NO}_2 \text{ Percent by Volume} = \frac{95.23 \text{ #-mol/hr (100)}}{541.49 \text{ #-mol/hr}} = 17.59\%$$

$$\text{N}_2 \text{ Percent by Volume} = \frac{412.63}{541.49} = 76.20\%$$

$$\text{H}_2\text{O Percent by Volume} = \frac{28.13}{541.72} = 5.20\%$$

$$A_R \text{ Percent by Volume} = \frac{5.31}{541.49} = 0.98\%$$

$$\text{Other Percent by Volume} = \frac{0.19}{541.72} = 0.04\%$$

$$\text{TOTAL} = 100.01$$

Calculations For: Product Gas Specific Heat at Constant Pressure

$$C_{PPRG} = \frac{W_{N_2} C_{Pn2} + W_{ar} C_{Par} + W_{NO_2} C_{PNO_2} + W_{H_2O} C_{PH_2O}}{W_{PR.G.}}$$
$$W_{N_2} = 412.63 \text{ #moles/hr (28.013)} = 11559.00 \text{ #/hr}$$
$$W_{AR} = 5.31 \text{ #moles/hr (39.948)} = 212.12 \text{ #/hr}$$
$$W_{NO_2} = 95.23 \text{ #moles/hr (46.005)} = 4381.06 \text{ #/hr}$$
$$W_{H_2O} = 28.16 \text{ #moles/hr (18.015)} = \underline{\underline{506.26 \text{ #/hr}}}$$
$$16658.94 \text{ #/hr}$$

From Gas Table @ 1460°R

$$C_{Pn2} = \frac{\varnothing}{\ln T} = \frac{52.867}{\ln 1460} = 7.2558 \text{ ^B/#-mol } ^\circ F$$
$$C_{Par} = \frac{\varnothing}{\ln T} = \frac{41.9242}{\ln 1460} = 5.7539 \text{ ^B/#-mol } ^\circ F$$
$$*C_{PNO_2} = \frac{\varnothing}{\ln T} = \frac{61.639}{\ln 1460} = 8.4597 \text{ ^B/#-mol } ^\circ F$$
$$C_{PH_2O} = \frac{\varnothing}{\ln T} = \frac{58.556}{\ln 1460} = 7.3503 \text{ ^B/#-mol } ^\circ F$$
$$C_{PPRG.} = \frac{412.63 (7.2558) + 5.31 (5.7539) + 95.23 (7.2558) + 28.13 (7.3503)}{(541.49 - 0.19)}$$
$$= 7.2460 \text{ ^B/#-mol } ^\circ F$$

*Assume specific heat of NO₂ (MW = 46) is essentially the same as CO₂ (MW = 44).

Calculations For: Dewpoint of Product Gas

$$P_V = H_2O \text{ mol. fract.} \times P_{PG}$$

Where: P_V = vapor pressure of water.
 P_{PG} = product gas pressure.

$$P_V = 0.0520 \text{ (102 psig)} = 5.304 \text{ psig or } 20.0 \text{ psia}$$

Saturation pressure of H_2O @ 20 psia = 227.96°F

Dewpoint = 227.96°F

Mass Flow of Product Gas Constituents

$$NO_2 = (\text{#-mol/hr}) (\#/ \text{-mol}) = 95.23 (46.008) = 4381.34 \text{ #/hr}$$

$$N_2 = (\text{#-mol/hr}) (\#/ \text{-mol}) = 416.63 (28.016) = 11672.31 \text{ #/hr}$$

$$H_2O = (\text{#-mol/hr}) (\#/ \text{-mol}) = 28.13 (18.016) = 506.79 \text{ #/hr}$$

$$A_R = (\text{#-mol/hr}) (\#/ \text{-mol}) = 5.31 (39.95) = 16772.57 \text{ #/hr}$$

$$\text{Unaccounted} = 17644 - 16773 = 871 \text{ #/hr}$$

$$\text{Apparent Mol. Wt.} = \frac{17644 \text{ #/hr}}{541.49 \text{ #-mol/hr}} = 32.58 \text{ #/ \text{-mol}}$$

$$C_p = \frac{7.2460 \text{ B/\#\text{-mol } } ^\circ F}{32.58 \text{ #/ \text{-mol}}} = 0.2224 \text{ B/\# } ^\circ F$$

Calculations For: Recoverable Heat

$$Q_{REC} = w C_p (T_{IN} - T_{OUT}) = 17644 (0.222) (800 - 400)/1000
= 1570 \text{ MBH}$$

Assume feedwater entering boiler is 300°F and 65 psig


$$W_{STM} = \frac{1570000}{\Delta h} = \frac{1570000}{1183.1 - 282} = 1740 \text{ #/hr} @ 65 \text{ psig}$$

Volumetric Analysis - Product Gas/Bleaching Air:

Constituent	# Moles/Hr in Blching Air	# Moles/Hr in Pr. Gas Entg.	# Moles/Hr in New Pr. Gas	% By Volume
N ₂	74.93	416.63	491.56	76.57
A	0.90	5.31	6.21	0.97
O ₂	20.10	0*	20.10	3.13
NO ₂	0	95.23	95.23	14.83
H ₂ O	0.71	28.13	28.84	4.49
			641.94	99.99

Bleaching Air: 2779 #DA/hr + 15.45 #H₂O/hr = 2794.45 #/hr
moles DA/hr = 2779/28.96 = 95.96

*Assume all available O₂ combines with available N₂:



Calculations For: Absorption Column Spray Water and Tailgas

Spray Water Required = $40.6 + 3.8 + 31.74 - 28.84 = 47.3 \text{ # mol/hr}$

or $\frac{47.3 \text{ # mol/hr} (18.016 \text{ #/#mol})}{8.33 \text{ #/g} (60 \text{ m}^3/\text{hr})} = 1.70 \text{ gpm}$

or $47.3 \text{ # mol/hr} (18.016 \text{ #/#mol}) = 855 \text{ #/hr}$

Tail Gas	# Moles/Hr	Mol. Wt.	#/Hr
O ₂	20.1	32	643.2
N ₂	491.6	28.016	13772.7
NO	31.72	30.008	954.1
H ₂ O	3.8	18.016	68.5
A _R	6.21	39.948	248.1
Other	0.19	42.09	8.0
	553.62		15694.6

Apparent Mol. Wt. = $\frac{15694.6}{553.62} = 28.349$

**Calculations For: 50 Tons/Day of 61% Acid by Volume
(66.124 #-mol/hr HNO₃) & Tailgas**

Constituent	# Moles Ent. Col	# Moles in Product	# Moles in Tailgas
N ₂	491.56	0	491.56
A _R	6.21	0	6.21
O ₂	20.10	0	20.10
H ₂ O	28.84	40.6	3.8
HNO ₃	0	63.48	0
NO	0	0	31.74
Reaction: 3NO ₂ + H ₂ O ----> 2 HNO ₃ + NO			

Water in Reaction -----> $\frac{95.23}{3} = 31.74 \text{ # moles/hr}$

Water in Tailgas -----> $\frac{P_V R_{TG}}{(P_m - P_V) R_V} = \frac{0.5959 (1544/30)}{(80 - 0.5959) (1544/18.016)} = 0.0045 \text{ #/#DTG}$
(Saturated @ 85°F)

Water = 15400 (0.0045) = 69#/hr

Product -----> 63.48 # moles/hr (63.013 #/#mole) + (40.6 #mole/hr) (18.016 #/#mole)
= 4732 #/hr

% HNO₃ = $\frac{63.48 (100)}{104.1} = 60.98 \text{ by Volume}$

% HNO₃ = $\frac{63.48 (63.013) (100)}{4732} = 84.5 \text{ by Weight}$

Calculations For: Product and Tailgas (By Molal Analysis)

Absorption Column Mass Balance:

$$W_{IN} = 491.56 (28.014) + 6.21 (39.948) + 95.23 (46.01) + 28.84 (18.016) + 855 + 20.1 (32)$$
$$= 20418 \text{ #/hr}$$

$$W_{OUT} = 491.56 (28.014) + 6.21 (39.948) + 3.8 (18.016) + 31.74 (30.01) + 20.1 (32) + 4732$$
$$= 20415 \text{ #/hr}$$

$$\text{Tailgas} = 20415 - 4732 = 15680 \text{ #/hr}$$

Calculations For: Tailgas (By Molal Analysis)

$$C_{PTG} = \frac{W_{N_2} C_{PN_2} + W_{AR} C_{PAR} + W_{NO} C_{PNO} + W_{H_2O} C_{PH_2O} + W_{O_2} C_{PO2}}{W_{TG}}$$

$$W_{N_2} = 491.56 \text{ #-Mol/hr}$$

$$W_{AR} = 6.21 \text{ #-Mol/hr}$$

$$W_{NO} = 31.74 \text{ #-Mol/hr}$$

$$W_{H_2O} = 3.8 \text{ #-Mol/hr}$$

$$W_{O_2} = 20.1/553.41 \text{ #-Mol/hr}$$

Calculate C_p @ 350° F (810° R) - Value of ϕ from gas tables

$$C_p O_2 = \frac{\phi}{\ln T} = \frac{51.911}{\ln 810} = 7.751 \text{ B/#-Mol°F}$$

$$C_p N_2 = \frac{\phi}{\ln T} = \frac{48.61}{\ln 810} = 7.2584 \text{ B/#-Mol°F}$$

$$C_p PAR = \frac{\phi}{\ln T} = \frac{38.9994}{\ln 810} = 5.8234 \text{ B/#-Mol°F}$$

$$*C_p NO = \frac{\phi}{\ln T} = \frac{50.146}{\ln 810} = 7.4878 \text{ B/#-Mol°F}$$

$$C_p H_2O = \frac{\phi}{\ln T} = \frac{48.419}{\ln 810} = 7.2299 \text{ B/#-Mol°F}$$

$$C_{PTG} = \frac{491.56 (7.2584) + 6.21 (5.8234) + 31.74 (7.4878) + 3.8 (7.2299) + 20.1 (7.7513)}{553.41}$$

$$7.2732 \text{ B/#-Mol°F}$$

or

$$\frac{7.2732 \text{ B/#-Mol°F} (553.41 \text{ #-Mol/hr})}{15680 \text{ #/hr}} = 0.257 \text{ B/#°F}$$

Cost Data

"Means Mechanical Cost Data", 19th Annual Edition, 1996 was used for unit price data for the majority of line items entered on estimating forms. Pipe fittings and accessories were entered as ±80 percent of run-of-pipe cost. Major equipment pricing, where not included in "Means", was developed from published cost of similar devices tempered by engineering judgement.

ECO costs were developed for a single process line, including equipment shown on the Process Flow Diagrams. Provisions for "Crossover" to permit any one of the five air compressors, for instance, is not included, nor is the provision to interconnect any other new device in one process line with its companion device in an adjacent process line. Additional expenditures to implement similar changes on a second line will not produce additional savings at the present production rate.

Cost estimate analysis sheets for each ECO are included in this section, followed by Life Cycle Analysis Summary sheets from the LCIDD computer program.

Cost analysis rough worksheets are presented in Appendix.

COST ESTIMATE ANALYSIS								DATE PREPARED: 11/14/95
								ESTIMATOR: PDL
PROJECT: HOLSTON AAP AREA B NITRIC ACID					LOCATION: KINGSPORT, TENNESSEE			
TASK DESCRIPTION	QUANTITY		LABOR		EQUIPMENT		MATERIAL	
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	UNIT PRICE	COST
ECO NO. 1								
STEAM PIPING:								
6" ø Sch.40 Undrgr.	250	LF	16.55	4138	1.28	320	31.00	7750
3" ø Sch. 80 Undrgr.	250	LF	17.65	4413	1.28	320	19.50	4875
4" ø Sch. 40	150	LF	11.70	1755	1.40	210	10.60	1590
2" ø Sch. 80	150	LF	7.75	1163	.86	129	5.50	837
Pipe Insul.	300	LF		2000			1000	3000.00
Turbin Mod. Cost		LS		10000			10000	20000.00
15000#/Hr. Stm. Surf. Cndns.	1	EA		10000		2500		30000
Cond. Pump	1	EA		300			1500	1800.00
8" Condnsr Wtr. Piping	300	LF	23	6900	1.81	543	31.00	9300
Pipe Ftgs & Misc.	1	LOT		10000			25000	35000.00
TOTAL				50669		4022		91852 \$146,543.00

COST ESTIMATE ANALYSIS								DATE PREPARED: 11/14/95	
								ESTIMATOR: PDL	
PROJECT: HOLSTON AAP AREA B NITRIC ACID					LOCATION: KINGSPORT, TENNESSEE				
TASK DESCRIPTION	QUANTITY		LABOR		EQUIPMENT		MATERIAL		TOTAL
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	UNIT PRICE	COST	
ECO NO. 2									
STEAM PIPING:									
8" ø Sch.40 Undrgr.	250	LF	17.40	4350	1.28	320	33.50	8375	\$13,045.00
3" ø Sch. 80 Undrgr.	250	LF	17.65	4413	1.28	320	19.50	4875	9608.00
8" ø Sch. 40	150	LF	23.00	3450	1.81	272	31.00	4650	8372.00
2" ø Sch. 80	150	LF	7.75	1163	.86	129	5.50	837	2129.00
Pipe Insul.	1	LOT		2500				1200	3700.00
DOWTHERM PIPE:									
2 1/2" ø Sch. 40	200	LF	9.20	1840	1.12	224	6.40	1280	3344.00
Pipe Insul.	1	LOT		2000				1000	3000.00
Hi Temp Pump (406 GPM)	1	EA		300				3438	3738.00
65 GPM Pump	1	EA		216				1375	1591.00
N ₂ Blntk. Syst.	1	EA		250				1000	1250.00
Unfired Blr. Vessel	1	EA		5000		2500		75000	82500.00
Misc. Acces. & Fittings	1	LOT		20000				40000	60000.00
TOTAL				45482		3765		143030	\$192,277.00

COST ESTIMATE ANALYSIS								DATE PREPARED: 11/14/95	
								ESTIMATOR: PDL	
PROJECT: HOLSTON AAP AREA B NITRIC ACID					LOCATION: KINGSPORT, TENNESSEE				
TASK DESCRIPTION	QUANTITY		LABOR		EQUIPMENT		MATERIAL		TOTAL
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	UNIT PRICE	COST	
FIBERGLASS COOLING TOWER									
600 GPM Ind. Dr.	1	EA		1500		1000		12000	\$14,500.00
Pumps & Piping	1	LOT		3500				7200	10700.00
Elect		LS		3000				5000	8000.00
Sitework/Pads		LS		5000				1000	6000.00
TOTAL				13000		1000		25200	39,200.00

COST ESTIMATE ANALYSIS						DATE PREPARED: 11/14/95	
						ESTIMATOR: PDL	
PROJECT: HOLSTON AAP AREA B NITRIC ACID				LOCATION: KINGSPORT, TENNESSEE			
TASK DESCRIPTION	QUANTITY		LABOR		MATERIAL		TOTAL
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	
Insulation ECO NO. 4							
1" CALCIUM SILICATE:							
18" ø Air Preheater	12	LF	5.40	64.80	9.35	112.20	\$ 177.00
18" ø Tailgas Heater	25	LF	5.40	135.00	9.35	233.75	368.75
8" ø Tailgas Pipe to Turbine	120	LF	3.84	460.80	4.26	511.20	972.00
0.010 S.S. JACKET:							
18" ø Air Preheater	60	SF	4.03	241.80	.93	55.80	297.60
18" ø Tailgas Heater	125	SF	4.03	503.75	.93	116.25	620.00
8" ø Tailgas Pipe to Turbine	315	SF	4.03	1,269.45	.93	292.95	1,562.40
18" ø Flange Sets (Insulation)	10	SF	13.45	134.50	2.71	27.10	\$161.60
18" ø Flange Sets (Jacket)	10	SF	4.03	40.30	.93	9.30	\$49.60
Subtotal			\$2,850.40			\$1,358.55	\$ 4,208.95
15% Conting							631.35
TOTAL Construction Use							\$ 4,850.00

COST ESTIMATE ANALYSIS						DATE PREPARED: 11/14/95	
						ESTIMATOR: PDL	
PROJECT: HOLSTON AAP AREA B NITRIC ACID				LOCATION: KINGSPORT, TENNESSEE			
TASK DESCRIPTION ECO NO. 5	QUANTITY		LABOR		MATERIAL		TOTAL
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	
18" Semicircular							
Plate Heat Exchanger 14' Long	1	EA		100.00		5,000.00	\$ 5,100.00
Clayton Whsg. Waste							
Heat Steam Generator	1	EA		2,000.00		5,000.00	7,000.00
Condensate Cooler	1	EA		100.00		500.00	600.00
Cond. Rcvr/Pump	1	EA		300.00		1,500.00	1,800.00
1-1/4" ø Insulated							
Pipe & Fittings	1	LOT		7,500.00		5,000.00	\$12,500.00
TOTAL				10,000.00		17,000.00	\$ 27,000.00

COST ESTIMATE ANALYSIS								DATE PREPARED: 11/14/95
								ESTIMATOR: PDL
PROJECT: HOLSTON AAP AREA B NITRIC ACID				LOCATION: KINGSPORT, TENNESSEE				
TASK DESCRIPTION	QUANTITY		LABOR		EQUIPMENT		MATERIAL	
	NO OF UNITS	UNIT MEAS	UNIT PRICE	COST	UNIT PRICE	COST	UNIT PRICE	COST
ECO NO. 7								TOTAL
Makeup & Fowtr. Pipe - 1" ø	500	LF	4.65	4138	.57	285	2.89	1445.00
Steam Pipe - 1-1/2" ø	150	LF	5.70	4413	.69	104	3.96	594.00
400 Series St. Stl. Econom.	1	EA		1755		500		185500.00
Waste Ht. Blr. System	1	EA		1,500		150		68600.00
Fdwtr Pump-46 PM/225 TDH	1	EA	72.50	1163			500	500.00
Temperature Controls	1	SET	150.00	2000			850	850.00
6"ø A3126RTP321 Pipe	40	LF	20.00	10000	1.50	60	60	2400.00
Heater Insulation		LS		300				1360.00
Steam Pipe Insul	150	LF	2.49	6900			2.23	335.00
Fdwtr Pipe Insul	150	LF	2.42	10000			2.16	324.00
Surge Tank - 100 Gag	1	EA		25				100.00
Pipe Fittings & Accos.	1	LOT		2000				5500.00
Subtotal				13,315			1,099	267508.00
**Cost W.O. St. Stl. Sect.								\$93,922.00

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)
 INSTALLATION & LOCATION: HOLSTON ARMY AREGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #1 STM. TURB.DRIVE @ AIR COMPR.
 ANALYSIS DATE: 12-21-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 146543.
B. SIOH	\$ 14661.
C. DESIGN COST	\$ 15993.
D. TOTAL COST (1A+1B+1C)	\$ 177197.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 177197.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	2325.	\$ 23831.	15.61	\$ 372001.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
L. OTHER	\$ 3.90	-10538.	\$ -41097.	14.74	\$ -605775.
M. DEMAND SAVINGS			\$ 13050.	14.74	\$ 192357.
N. TOTAL		-8213.	\$ -4216.		\$ -41417.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ 0.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ 0.

B. NON RECURRING SAVINGS(+)/COSTS(-)

ITEM	SAVINGS(+) COST(-)	YR OC	DISCNT FACTR	DISCOUNTED SAVINGS(+)/ COST(-)(4)
	(1)	(2)	(3)	
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 0.

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))\$ -4216.

5. SIMPLE PAYBACK PERIOD (1G/4) -42.03 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ -41417.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= -.23
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): N/A

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)
 INSTALLATION & LOCATION: HOLSTON ARMY AREGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #2 REJCTD HT CNVRTD TO 100# STM
 ANALYSIS DATE: 12-21-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 192275.
B. SIOH	\$ 10576.
C. DESIGN COST	\$ 11537.
D. TOTAL COST (1A+1B+1C)	\$ 214388.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 214388.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	-885.	\$ -9071.	15.61	\$ -141602.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
L. OTHER	\$ 3.90	3445.	\$ 13436.	14.74	\$ 198039.
M. DEMAND SAVINGS			\$ -1855.	14.74	\$ -27343.
N. TOTAL		2560.	\$ 2509.		\$ 29094.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ -1080.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ -15919.

B. NON RECURRING SAVINGS(+)/COSTS(-)

ITEM	SAVINGS(+) COST(-)	YR OC	DISCNT FACTR	DISCOUNTED SAVINGS(+)/ COST(-)(4)
	(1)	(2)	(3)	

d. TOTAL	\$ 0.			0.
----------	-------	--	--	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$	-15919.
---	---------

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))\$ 1429.

5. SIMPLE PAYBACK PERIOD (1G/4) 150.00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 13175.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .06
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): -10.32 %

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)
 STUDY: 95094 LCCID 1.080
 INSTALLATION & LOCATION: HOLSTON ARMY AREGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #3 REDUCED WTR CONSUMP W/ CLNG TWR
 ANALYSIS DATE: 12-21-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 39200.
B. SIOH	\$ 2156.
C. DESIGN COST	\$ 2352.
D. TOTAL COST (1A+1B+1C)	\$ 43708.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 43708.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	-65.	\$ -666.	15.61	\$ -10400.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
M. DEMAND SAVINGS			\$ 0.	14.74	\$ 0.
N. TOTAL		-65.	\$ -666.		\$ -10400.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ 5524.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ 81424.

B. NON RECURRING SAVINGS(+)/COSTS(-)

ITEM	SAVINGS(+) COST(-)	YR OC	DISCNT FACTR	DISCOUNTED SAVINGS(+)/ COST(-)(4)
(1)	(2)	(3)		

d. TOTAL	\$ 0.	0.
----------	-------	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 81424.

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))\$ 4858.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 71024.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.62
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): N/A

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: 95094
 LCCID 1.080
 INSTALLATION & LOCATION: HOLSTON ARMY AREGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #4 INSULATE HEAT EXCHANGERS
 ANALYSIS DATE: 12-21-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 4850.
B. SIOH	\$ 267.
C. DESIGN COST	\$ 291.
D. TOTAL COST (1A+1B+1C)	\$ 5408.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 5408.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	460.	\$ 4718.	15.61	\$ 73656.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
M. DEMAND SAVINGS			\$ 2585.	14.74	\$ 38103.
N. TOTAL		460.	\$ 7303.		\$ 111758.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ 0.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ 0.

B. NON RECURRING SAVINGS(+)/COSTS(-)

ITEM	SAVINGS(+) COST(-)	YR OC	DISCNT FACTR	DISCOUNTED SAVINGS(+)/ COST(-)(4)
(1)	(2)	(3)		

d. TOTAL	\$ 0.	0.
----------	-------	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)	\$ 0.
---	-------

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))	\$ 7303.
--	----------

5. SIMPLE PAYBACK PERIOD (1G/4)	.74 YEARS
---------------------------------	-----------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$ 111758.
--	------------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= (IF < 1 PROJECT DOES NOT QUALIFY)	20.67
---	-------

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR):	19.96 %
---	---------

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: 95094
 LCCID 1.080
 INSTALLATION & LOCATION: HOLSTON ARMY AREGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #5 INSUL HX S W/ NEW 30# STM SYST
 ANALYSIS DATE: 12-21-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 31850.
B. SIOH	\$ 1752.
C. DESIGN COST	\$ 1911.
D. TOTAL COST (1A+1B+1C)	\$ 35513.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 35513.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	460.	\$ 4718.	15.61	\$ 73656.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
L. OTHER	\$ 3.90	664.	\$ 2589.	14.74	\$ 38159.
M. DEMAND SAVINGS			\$ 2585.	14.74	\$ 38103.
N. TOTAL		1124.	\$ 9892.		\$ 149918.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ -132.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ -1946.

B. NON RECURRING SAVINGS(+)/COSTS(-)	DISCNT	DISCOUNTED		
ITEM	SAVINGS(+) COST(-)	YR OC (1) (2)	FACTR (3)	SAVINGS(+)/ COST(-)(4)

d. TOTAL	\$ 0.	0.
----------	-------	----

c. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$	-1946.
---	--------

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))\$	9760.
--	-------

5. SIMPLE PAYBACK PERIOD (1G/4)	3.64 YEARS
---------------------------------	------------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$ 147972.
--	------------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= (IF < 1 PROJECT DOES NOT QUALIFY)	4.17
---	------

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR):	10.73 %
---	---------

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: 95094
 LCCID 1.080
 INSTALLATION & LOCATION: HOLSTON ARMY AREA NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: 95094 AREA B NITRIC ACID PRODUCTION FACILITY
 FISCAL YEAR 1996 DISCRETE PORTION NAME: ECO #7 RECOVERED STM INJECT @ TLGS TURB
 ANALYSIS DATE: 12-22-95 ECONOMIC LIFE 20 YEARS PREPARED BY: LITTLE

1. INVESTMENT

A. CONSTRUCTION COST	\$ 281920.
B. SIOH	\$ 4125.
C. DESIGN COST	\$ 4500.
D. TOTAL COST (1A+1B+1C)	\$ 290545.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$ 0.
F. PUBLIC UTILITY COMPANY REBATE	\$ 0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$ 290545.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1993

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 10.25	683.	\$ 7002.	15.61	\$ 109304.
B. DIST	\$.00	0.	\$ 0.	17.56	\$ 0.
C. RESID	\$.00	0.	\$ 0.	19.97	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	20.96	\$ 0.
E. COAL	\$.00	0.	\$ 0.	17.58	\$ 0.
F. LPG	\$.00	0.	\$ 0.	16.12	\$ 0.
M. DEMAND SAVINGS			\$ 3835.	14.74	\$ 56528.
N. TOTAL		683.	\$ 10837.		\$ 165832.

3. NON ENERGY SAVINGS(+)/COST(-)

A. ANNUAL RECURRING (+/-)	\$ -412.
(1) DISCOUNT FACTOR (TABLE A)	14.74
(2) DISCOUNTED SAVING/COST (3A X 3A1)	\$ -6073.

B. NON RECURRING SAVINGS(+)/COSTS(-)				
ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ -6073.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS ECONOMIC LIFE))$ \$ 10425.

5. SIMPLE PAYBACK PERIOD (1G/4) 27.87 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 159759.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .55
 (IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): .06 %

Pg 55

Extracted to

Go with

Executive Summary

4/19/96

Conclusion

Four of the six ECO's evaluated produce savings to investment ratios greater than 1.25. Not all of these conservation concepts can be accomplished simultaneously. ECO No. 5 is predicated on being incorporated with No. 4, and these two concepts should be considered as one.

Neither ECO No. 1 nor No. 2 is compatible with ECO No. 5, since each of them negates the availability of high energy tailgas on which ECO No. 5 depends.

ECO No. 3 can be incorporated with any combination of other mutually compatible ECO's.

Although integral implementation of ECO's No. 1 and No. 2 could be accomplished, this combination can be eliminated by inspection because No. 1 requires increased steam flow from the central plant at 300 psig, while No. 2 produces excess 100 psig steam to displace central plant steam.

The available groupings of qualifying ECO's do not produce an aggregate cost greater than \$300,000, and therefore cannot be considered for ECIP funding.

We recommend implementation of ECO's No. 7, which at current production rates, will produce calculated electrical savings of 683×10^6 Btu/yr \$3,835 per year in electrical demand costs.

Abbreviations

AESE: Affiliated Engineers SE, Inc.

AOP: Ammonia Oxidation Process

ASME: American Society of Mechanical Engineers

bhp: Boiler Horsepower

ECO: Energy Conservation Opportunity

(ECIP): Energy Conservation Investment Program. This is a federal government program which allocates funds for projects which increase energy efficiency.

HDC: Holston Defense Corporation

HAAP: Holston Army Ammunition Plant

Excess Air: A term used to describe the amount of air that is supplied to fossil fired boilers over and above the amount theoretically required for complete combustion.

hr/yr: hour per year

kWh: kilowatt-hour

lb/hr: pounds per hour

lb/mo: pounds per month

(LCCID): Life Cycle Cost in Design. Government software package used to evaluate projects for ECIP funding.

MBtu/hr: thousand British thermal units per hour

MMBtu/yr: million British thermal units per year

psig: pounds per square inch gauge

SIR: Savings to Investment Ratio

Appendices

**DETAILED
CALCULATIONS**

 <p>AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479</p>	Made By: <u>PDL</u>	Date:	Job No: <u>95094-00</u>
	Checked By: <u></u>	Date: <u></u>	Sheet No: <u>1</u> of <u>1</u>

Calculations For:

VOLUMETRIC ANALYSIS OF PRODUCT GAS

COMPOSITE MOLECULAR WEIGHT OF AIR = 28.96 (FROM MARKS HANDBK)


$$\text{DRY AIR SUPPLIED} = \frac{16465 \text{ #/HR}}{28.96 \text{ #/MOLE}} = 568.54 \pm \text{moles/HR}$$

$$\text{AMMONIA SUPPLIED} = \frac{1088 \text{ #/HR}}{17.032 \text{ #/MOLE}} = 63.88 \pm \text{moles/HR}$$

AMMONIA OXIDATION:



APPARENT ADDITIONAL N₂ OXIDATION:



FROM MARKS
HANDBK

$$\text{OXYGEN SUPPLIED} = (568.54 \pm \text{moles/HR}) \left(\frac{20.948}{100} \right) = 119.10 \pm \text{moles/HR}$$

$$\text{O}_2 \text{ USED IN } 100\% \text{ OXIDATION OF NH}_3 = 63.88 \pm \text{moles/HR} \left(\frac{4}{4} \right) = 11.79 \pm \text{moles/HR}$$

$$\text{O}_2 \text{ USED IN N}_2 \text{ OXIDATION} = 119.10 - 11.79 = 7.31 \pm \text{moles/HR}$$

$$\text{NO}_2 \text{ IN PROD. GAS} = 63.88 \left(\frac{4}{4} \right) + 7.31 \left(\frac{2}{2} \right) = 71.19 \pm \text{moles/HR}$$

$$\text{N}_2 \text{ USED IN N}_2 \text{ OXIDATION} = \frac{7.31}{2} = 3.66 \pm \text{moles/HR}$$

$$\text{H}_2\text{O FROM NH}_3 \text{ OXIDATION} = 63.88 \left(\frac{6}{4} \right) = 95.82 \pm \text{moles/HR}$$

$$\text{H}_2\text{O IN AIR} = \frac{0.0055 \pm \text{moles/HR} \times 16465 \text{ #/HR}}{18.015 \pm \text{#moles}} = 5.03 \pm \text{moles/HR}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: PDL	Date: 12-1-95	Job No: 95094-00
Checked By:	Date:	Sheet No: 2 of _____

Calculations For:

VOLUMETRIC ANALYSIS OF PRODUCT GAS

FROM MARKS HANDBK

CONSTITUENT

MOLES/HR
IN AIR

MOLES/
HR
USED/PRODUCT IN PROD GAS

MOLES/HR
IN PROD GAS

% BY VOL
DRY GAS

N₂ 568.54(78.08) = 443.94

(3.46)

440.28

85.20

AR 20(568.54)(.00934) = 5.31

0

5.31

1.03

NO₂

0 0

71.19

13.78

H₂O

5.03

DRY GAS = $\frac{95.82}{100.85}$

516.78

MOLES/
HR

O₂

119.10

(119.10)

0

617.63

WET GAS

% BY VOL

$$N_2 = 71.29$$

$$AR = 0.86$$

$$NO_2 = 11.53$$

$$H_2O = 16.33$$

$$\text{PARTIAL PRESSURE } P_{H_2O} = (0.1633)(102 \text{ #/in}^2)$$

$$= 16.66 \text{ PSIG.}$$

$$\text{ABSOLUTE PR.} = 16.66 + 14.97 = 31.63 \text{ PSIA.}$$

$$\text{SATURATION TEMP. OF H}_2\text{O}@31.63 \text{ PSIA} = 253.37^\circ\text{F} \rightarrow \text{DEWPOINT}$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By: PDL	Date: 12-1-95	Job No: 95094-00
Checked By:	Date:	Sheet No: <u>3</u> of _____

Calculations For:

PRODUCT GAS

$$C_{P_{PR.G.}} = \frac{W_{N_2} C_{P_{N_2}} + W_A C_{P_A} + W_{NO_2} C_{P_{NO_2}} + W_{H_2O} C_{P_{H_2O}}}{W_{PR.G.}}$$

$$W_{N_2} = 440.28 \text{ # moles/HR} (28.013) = 12333.56 \text{ #/HR}$$

$$W_A = 5.31 \text{ # moles/HR} (39.948) = 212.12 \text{ #/HR}$$

$$W_{NO_2} = 71.19 \text{ # moles/HR} (46.005) = 3275.12 \text{ #/HR}$$

$$W_{H_2O} = 100.85 \text{ # moles/HR} (18.015) = \underline{1816.85 \text{ #/HR}}$$

$$17637.65 \text{ #/HR}$$

$$C_{P_{N_2}} = 0.227 + 0.0000292(1260) = 0.264 \text{ B/#°F}$$

$$C_{P_A} = 4.972 / 39.948 = 0.124 \text{ B/#°F} \quad \left. \begin{array}{l} \text{SE 50 BUFFALO} \\ \text{BL b.} \end{array} \right\}$$

$$C_{P_{NO_2}} = 4.972 / 46.006 = 0.108 \text{ B/#°F}$$

$$C_{P_{H_2O}} = 0.433 + 0.0000166(1260) = 0.454 \text{ B/#°F}$$

$$C_{P_{PR.G.}} = \frac{12333.56(0.264) + 212.12(0.124) + 3275.12(0.108) + 1816.85(0.454)}{17637.65}$$

$$= 0.253 \text{ B/#°F}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:
PDL

Date:
12-1-95

Job No:
95094-00

Checked By:

Date:

Sheet No:
4 of _____

Calculations For:

RECOVERABLE HEAT

$$Q_{REC} = W C_p (T_{IN} - T_{out}) = 17638(0.253)(800 - 400)/1000 \\ = 1785.0 \text{ MBH}$$

ASSUMED FEEDWATER ENTERING BOILER IS 300°F & 65 PSIG


$$W_{STM} = \frac{1785000 \text{ BTUH}}{\Delta h} = \frac{1785000}{1183.1 - 282} = 1980 \text{ #/HR.} \\ @ 65 \text{ PSIG.}$$

VOLUMETRIC ANALYSIS - PRODUCT GAS/BLEACHING AIR:

<u>CONSTITUENT</u>	<u># MOLES/HR IN BLEACHING AIR</u>	<u># MOLES/HR IN PR. GAS ENTG.</u>	<u># MOLES/HR IN NEW PGAS</u>	<u>% BY VOL</u>
N ₂	95.96(.78084) = 74.93	440.28	515.21	72.05
A	95.96(0.00934) = 0.90	5.31	6.21	0.87
O ₂	95.96(.20948) = 20.10	0	20.10	2.81
NO ₂	0	71.76	71.76	10.04
H ₂ O	$\frac{15.45}{18.013} = 0.86$	100.85	$\frac{101.75}{715.03}$	14.23

$$\text{BLEACHING AIR: } 2779 \text{ #/HR} + 15.45 \text{ #H}_2\text{O}/\text{HR} = 2794.45 \text{ #/HR} \\ \text{#MOLES/HR} = 2779/28.96 = 95.96$$

ASSUME ALL AVAILABLE O₂ COMBINES w/ AVAILABLE N₂





AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479


Made By: PDL	Date: 12-1	Job No:
Checked By:	Date:	Sheet No: 5 of _____

Calculations For:

PRODUCT & TAILGAS

CONSTITUENT	# MOLES EST. VOL	# MOLES IN PROD	# MOLES IN TAILGAS
N ₂	$515.2 \times \frac{20.10}{2} = 505.16$	0	505.16
A	6.21	0	6.21
O ₂	0	0	0
NO ₂	$71.76 + 20.10 = 91.86$	0	0
H ₂ O	101.75	166.39 LIQUID	4.74 VAPOR
HNO ₃	$\frac{91.86}{3} = 0$	61.24	0
NO	$\frac{91.86}{3} = 0$	0	<u>30.62</u>
		127.63	546.73

REACTION:



$$\text{WATER IN REACTION} \rightarrow \frac{91.86}{3} = 30.62 \frac{\text{# MOLES}}{\text{HR}}$$

$$\text{WATER IN TAILGAS} \rightarrow \frac{15450 \frac{\text{#}}{\text{HR}} (0.0055 \frac{\text{# H}_2\text{O}}{\text{# DG}})}{(1.00 - 0.0055 \frac{\text{# H}_2\text{O}}{\text{# DG}})(18.015)} = 4.74 \frac{\text{# MOLES}}{\text{HR}}$$

$$\text{PRODUCT} \rightarrow 61.24 \frac{\text{# MOLES}}{\text{HR}} (63.013 \frac{\text{# MOLES}}{\text{# MOLES}}) + (166.39 \frac{\text{# MOLES}}{\text{HR}})(18.015 \frac{\text{# MOLES}}{\text{# MOLES}})$$

$$= 505.5 \frac{\text{#}}{\text{HR}}$$

$$\% \text{ HNO}_3 = \frac{61.24(100)}{127.63} = 47.98 \text{ BY VOLUME}$$

$$\% \text{ HNO}_3 = \frac{61.24(63.013)}{505.5} = 76.34 \text{ BY WEIGHT}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:
PDL

Date:
11-9-95

Job No:
95094-00

Checked By:

Date:

Sheet No:
 of

Calculations For:

ABSORPTION COLUMN OUTLET FLOWS (RATED Production)

$$61\% \text{ DILUTE } \text{HNO}_3 = \frac{50 \text{ TPD}(2000 \text{ #/H})}{24 \text{ HR} (.61)} = 6830 \text{ #/H}$$

$$\text{HNO}_3 \text{ MOL. WT.} = 63.016$$

$$\text{HNO}_3 = \frac{(0.61)(6830)}{63.016} = \frac{40.34}{40.34} \text{ # MOLES/HR}$$

$$\text{H}_2\text{O} = \frac{(0.39)(6830)}{18.016} = \frac{147.85}{90.80} \text{ # MOLES/HR}$$

ASSUME TAIL GAS CONTAINS WATER VAPOR QUANTITY EQUAL TO AMOUNT PRESENT IN SATURATED AIR @ 60 PSIG AND 85°F.

$$\text{H}_2\text{O} = 0.0055 \text{ #/#} (15450 \text{ #/HR}) = 85 \text{ #/HR}$$

$$\text{# MOLES/HR} = \frac{85}{18.016} = 4.72$$

$$\text{SPRAY WATER RQD} = \frac{147.85}{90.80} + 4.72 - \frac{11.94}{45.15} = \frac{140.63}{49.72} \text{ # MOLES/HR}$$

$$\text{OR } \frac{140.63 \text{ # MOLES/HR}}{8.33 \text{ #/L (60 m/HR)}} = 5.06 \text{ GPM}$$

$$\text{OR } 2530 \text{ #/HR}$$

<u>TAIL GAS</u>	<u># MOLES/HR</u>	<u>MOL. WT.</u>	<u>MOLES</u>
O ₂	12.11	32	0.38
N ₂	435.64	28.016	15.55
NO	45.82	30.008	1.53
H ₂ O	4.72	18.016	0.26
	498.29		17.72

$$\text{MOL. WT} = \frac{498.29}{17.72}$$

$$= 28.12$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:

PDL

Date:

12-4-95

Job No:

95094-00

Checked By:

Date:

Sheet No:

6 of _____

Calculations For:

PRODUCT AND TAILGAS (BY MOLAL ANALYSIS)

$$\text{SPRAY WATER ADD'D} = 0.3 \text{ GPM} (8.35 \text{ #/GAL}) (60 \text{ min/HR}) \\ = 150.3 \text{ #/HR}$$

$$\text{TOTAL PRODUCT} = 5205 \text{ #/HR}$$

ABSORPTION COLUMN MASS BALANCE:

$$W_{IN} = 505.16(28.014) + 6.21(39.948) + 91.86(46.01) + 101.75(18.013) + 150 \\ = 20609 \text{ #/HR}$$

$$W_{OUT} = 505.16(28.014) + 6.21(39.948) + 4.74(18.013) + 30.62(30.01) + 5205 \\ = 20610 \text{ #/HR}$$

$$\text{TAILGAS} = 20610 - 5205 = 15405 \text{ #/HR}$$

$$\text{Product \% HNO}_3 = \frac{61.24(100)}{127.63 + 150.3 / 18.013} = 45.04\% \text{ BY VOL}$$

moles HNO₃
moles H₂O + HNO₃

$$\text{Product \% HNO}_3 = \frac{61.24(63.013)(100)}{5205} = 74.14\% \text{ BY WT.}$$

CALCULATE ADDITIONAL SPRAYWATER REQUIRED TO PRODUCE 61% HNO₃ BY WEIGHT:

$$.61(5205 + w) = 61.24(63.013) \\ w = 1121 \text{ #/HR}$$

$$\text{TOTAL PRODUCT} = 5205 + 1121$$

$$= 6326 \text{ #/HR}$$

$$\text{SPRAY WATER} = \frac{(1121 + 150.3)}{8.35(60)} = 2.5 \text{ GPM}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: PDL	Date: 11-9-95	Job No: 95094-00
Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ENERGY INVENTORY AT AIR PREHEATER

EXISTING SYSTEM

HEAT LOSS FROM BARE PIPE:

REF. SCHULLER HEAT TRANSFER TABLES
18⁴ @ 1200°F PIPE OPER. TEMP. - BARE - DULL

$$Q = \frac{54455 \text{ BTUH/FT (15 FT)}}{1000} = 980.2 \text{ MBH}$$

HEAT TRANSFERRED TO AIR:

$$Q = W C_p \Delta T = \frac{16556 (0.24)(625-100)}{1000}$$
$$= 2086.1 \text{ MBH}$$

HEAT REMOVED FROM PRODUCT GAS:

$$Q = 980.2 + 2086.1 = 3066.3 \text{ MBH}$$

HEAT TRANSFERRED TO WATER @ CONDENSER:

$$Q = \frac{500 (6\text{PM})(\Delta T)}{1000} = \frac{500 (77)(140-65)}{1000}$$
$$= 2887.5 \text{ MBH}$$

AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-12-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

COOLING WATER AT CASCADOT COOLEREXISTING SYSTEM

$$Q = (\text{LBS EVAP/HR})(950) + (\frac{15045}{1000} - \text{LBS GWF})(100^\circ - 75^\circ)$$

$$\text{LBS GWF/HR} = W$$

$$\frac{4018.7}{5713.7} (1000) = 950 W + \frac{15045}{1000}(25) - 25 W$$

$$W = \frac{4018.7 - 3860.25}{5713.7 - 2500} = \frac{3927}{3665} \text{ #/HR}$$

$$\text{DRAIN} = 15045 - 3927 = 11520 \text{ #/HR}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-9-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ENERGY INVENTORY AT ABSORPTION COLUMNS

EXISTING SYSTEM

ADDITIONAL WATER CONDENSED:

$$H_2O = (0.0065 \frac{\# H_2O}{\# DRY GAS})(19900 \frac{\#}{HR}) - 85 \frac{\#}{HR}$$

$$= 44.35 \frac{\#}{HR}$$

$$HEAT REMOVED = \frac{44.35(h_{fg})}{1000} = \frac{44.35(873)}{1000} = 38.7 MBH$$

APPROX. HEAT REMOVED FROM GAS:

$$Q = W C_p \Delta T = \frac{(5450)(0.25)(105-85)}{1000}$$

$$= 115.9 MBH$$

FROM TECHNICAL REPORT NO. HDC-39-77,

APPARENT ACID CHEMICAL HEAT LOADING

THE COLUMN IS 112.5 MBH (SEE REFERENCE

MATERIAL IN APPENDIX)

R.G.D. COOLING WATER:

$$CH WTR. GPM = \frac{(38.7 + 115.9)}{(2)50(45-35)} = 15.5 OR 7750 \frac{\#}{HR}$$

$$CH WTR. GPM = \frac{38.7 + 115.9}{50(65-75)} = 30.9 OR 15445 \frac{\#}{HR}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-12-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

WATER CHILLER

ASSUME HEAT REJECTED IN EXTERIOR
ABSORPTION COLUMN IS ONE HALF THE
TOTAL FOR BOTH COLUMNS.

ASSUME CHILLER STEAM REQUIREMENTS
ARE 22.5 #/HR STEAM PER TON OF ROTTING.

$$\text{TONS} = \frac{(115.9 + 38.7) \text{ MBH}}{(2) 12,000 \text{ MBH/TON}} = 6.44 \text{ TONS}$$

$$\text{STEAM} = 6.44 \times 22.5 = 145 \text{ #/HR}$$

BAROMETRIC CONDENSER:

$$\text{HEAT GAIN} = 145(h_{fg}) = 145(1045.8) * \text{Assume } 85^{\circ} \text{ COND. TEMP.}$$

$$= 151640 \text{ BTU/H}$$

FPM AT $\Delta T = 20^{\circ}\text{F}$:

$$\text{FPM} = \frac{151640}{500(20)} = 15 \text{ OR } 7580 \text{ #/HR}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 12-5-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: 7 of _____

Calculations For:

TAIL GAS (BY MOLAL ANALYSIS)

$$C_{P_{TG}} = \frac{w_{N_2} C_{P_{N_2}} + w_{AR} C_{P_{AR}} + w_{NO} C_{P_{NO}} + w_{H_2O} C_{P_{H_2O}}}{w_{TG}}$$

$$w_{N_2} = 505.16(28.013) = 14151.05$$

$$w_{AR} = 6.21(39.948) = 248.08$$

$$w_{NO} = 30.62(30.01) = 918.91$$

$$w_{H_2O} = 4.74(18.015) = \frac{85.39}{15403.43}$$

CALCULATE C_p @ 350°F (810°R)

$$C_{P_{N_2}} = 0.227 + 0.00000292(810) = 0.251$$

$$C_{P_{AR}} = 4.972/39.948 = 0.124$$

$$C_{P_{NO}} = 4.972/30.01 = 0.177$$

$$C_{P_{H_2O}} = 0.432 + 5.0000166(810) = 0.446$$

$$C_{P_{TG}} = \frac{14151.05(0.251) + 248.08(0.124) + 918.91(0.177) + 85.39(0.446)}{15403.43}$$

$$= 0.246 \text{ Btu/lb } ^{\circ}\text{F}$$

TAIL GAS
 85°F
 $C_p = 0.246 \text{ Btu/lb } ^{\circ}\text{F}$

PROD. GAS
 1070°F
 $C_p = 0.253 \text{ Btu/lb } ^{\circ}\text{F}$

PROD. GAS

$t = ?$

$t = ?$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 12-5-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: 8 of _____

Calculations For:

TAIL GAS HEATER

CALCULATE HEATER "EFFICIENCIES" USING EXISTING SYSTEM PARAMETERS:

$$\text{EFF} = \frac{\bar{T}_{\text{tg.out}} - \bar{T}_{\text{tg.in}}}{\bar{T}_{\text{pg.in}} - \bar{T}_{\text{tg.in}}} = \frac{785 - 85}{1070 - 85} = 0.711$$

USING CALCULATED EFF, DETERMINING PROCESS PARAMETERS OF THE INSULATION SYSTEM:

$$\begin{aligned}\bar{T}_{\text{tg.out}} &= \bar{T}_{\text{tg.in}} + 0.711(\bar{T}_{\text{pg.in}} - \bar{T}_{\text{tg.in}}) = 85 + 0.711(1205 - 85) \\ &= 881^{\circ}\text{F}\end{aligned}$$

$$\begin{aligned}Q_{\text{recov.}} &= W_{\text{tg}} C_{\text{pg}} (\bar{T}_{\text{tg.out}} - \bar{T}_{\text{tg.in}}) = 15403.43 (0.246)(881 - 85) \\ &= 3,017,450 \text{ BTUH}\end{aligned}$$

$$\begin{aligned}\bar{T}_{\text{pg.out}} &= \bar{T}_{\text{pg.in}} - \frac{Q_{\text{recov.}}}{W_{\text{pg}} C_{\text{pg}}} = 1205 - \frac{3017450}{17637.65(0.253)} \\ &= 529^{\circ}\text{F}\end{aligned}$$

$$\begin{aligned}Q_{\text{existing}} &= W_{\text{tg}} C_{\text{pg}} (\bar{T}_{\text{tg.out}} - \bar{T}_{\text{tg.in}}) = 15403.43 (435 - 85)(0.246) \\ &= 1,326,235 \text{ BTUH}\end{aligned}$$

$$\Delta Q = 3017450 - 1326235 = 1691215 \text{ BTUH}$$

* A $\approx 0.5\%$ ΔQ SHOULD BE APPROXIMATELY EQUAL TO THE REDUCTION IN PIPE LOSS TO ATMOS. BY ADDING INSUL.

$$\begin{aligned}Q_{\text{insul. loss}} &= 980250 - 41900 + 554300 - 34900 = 1,457,700 \text{ BTUH} \\ \% \text{ ERROR} &= \frac{1691215 - 1457700}{1691215} \times 100 = 13.8\%\end{aligned}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 12-5-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: 9 of _____

Calculations For:
TAIL GAS PIPING

CALCULATE TAIL GAS VELOCITY IN PIPING TO TURBINE:

MTL. - 6" HCl - Use ASTM A312 GRADE TP321

$$SCH. NO. = 1000 P/SB$$

$$P = 90 \text{ PSIG} @ 800^\circ\text{F}$$

$$SE = 12850 \text{ PSI}$$

$$SCH. NO. = \frac{1000(90)}{12850} = 7$$

USE SCHEDULE 105 \rightarrow ID = 6.357 IN

$$A_{ROA} = 31.7 \text{ IN}^2$$

$$\frac{P_1}{RT_1} = \frac{P_2}{RT_2}$$

STANDARD ATMOSPHERE: 518.7°R, 14.696 PSIA, 0.07651 #/FT³

$$V_2 = \frac{14.696(0.07651)(1260^\circ\text{R})}{518.7(90 + 14.696)} = 4.457 \text{ FT}^3/\text{#}$$

$$V = \frac{15403.43 \text{#/HR}(4.457 \text{ FT}^3/\text{#})}{60 \text{ HR} (31.7 \text{ IN}^2 / 144 \text{ IN}^2/\text{FT}^2)} = 5197 \text{ FPM}$$

PIPE DEVELOPED LENGTH = 75 FT.

USE EQUIVALENT LENGTH = 75(1.33) = 100 FT



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: PDL	Date: 12-5-95	Job No: 95094-00
Checked By:	Date:	Sheet No: 10 of _____

Calculations For:

TAIL GAS PIPING

$$N_{RE} = \frac{VD\rho}{\mu} = \frac{51.97 \text{ FT/MIN} (6.357 \text{ IN}) (60 \text{ MIN/HR})}{12 \text{ IN/FT} (4.457 \text{ FT}^3/\#) (0.081 \text{ LB/FT-HR})} \\ = 457,559$$

$$\Delta P = \frac{3.4 \times 10^{-6} f L W^2}{d^5} = \frac{3.4 \times 10^{-6} (0.008) (100) (15403.43)}{(6.357)^5 (4.457)} \\ = 0.28 \text{ PSI}$$

Assuming tailgas pressure leaving tailgas heater is 60 PSIG, calculate steam production capability of heat recovery boiler assuming product gas temperature leaving the boiler of 400°F , feedwater economizer outlet (boiler inlet) temperature of 300°F , and 50°F superheat.

$$W_{STM} = \frac{W_{PG} C_{PG} (T_{PG,IN} - T_{PG,OUT})}{(h_{STM,out} - h_{FW,in})} = \frac{17637.65 (0.253) (529 - 400)}{(1210.0 - 280)} \\ = 619 \text{ #/HR} @ 360^\circ\text{F & 78 PSIA}$$

$$W_{WET GAS} = W_{T,G} + W_{STM} = 15403.43 + 619 = 16022 \text{ #/HR}$$

$$V_{STM} = 6.045 \text{ FT}^3/\# \text{ FROM KEGWAN & KOYES}$$

$$V_{WET GAS} = \frac{6.045 (619) + 4.457 (15403.43)}{16022} = 4.518 \text{ FT}^3/\#$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:
TABLE 1

AMMONIA VAPORIZER:

$$Q_{GAIN_{AM}} = 694 \text{ #/HR} (1273 \frac{\text{BTU}}{\text{#}} - 244 \frac{\text{BTU}}{\text{#}}) = 714126 \text{ BTUH}$$

$$Q_{LOSS_{AM}} = 694 \text{ #/HR} (1 \frac{\text{BTU}}{\text{#}}} (275^\circ - 60^\circ) = 149210 \text{ BTUH}$$

MIXER:

$$Q_{TRANS AIR} = 16556 \text{ #/HR} (0.24 \frac{\text{BTU}}{\text{#}}} (625 - 580^\circ) = 178804 \text{ BTUH}$$

$$Q_{TRANS (NH_3)} = 1080 \text{ #/HR} (0.54 \frac{\text{BTU}}{\text{#}}} (580^\circ - 275^\circ) = 177876 \text{ BTUH}$$

CONVERTOR:

$$CLNG. WTR: Q_{REJ.} = 38499 \text{ #/HR} (1 \frac{\text{BTU}}{\text{#}}} (140 - 65) = 2,887,425 \text{ BTUH}$$

$$Q_{REACTION} = 7136.1 \text{ BTUH} - \text{SEE NEXT SHEET}$$

AIR PREHEATER:

$$Q_{REJ. (AIR)} = 16556 \text{ #/HR} (0.24 \frac{\text{BTU}}{\text{#}}} (625 - 100) = 2,086,056 \text{ BTUH}$$

✓ R.F. SCHULLER HT. TRANSF. TABLE

$$Q_{REJ. (ATMOS)} = 54455 \text{ BTUH/FT} (15 \text{ FT}) = 816825 \text{ BTUH}$$

$$T_{PG OUT} = T_{PG IN} - \frac{Q_{REJAIR} + Q_{REJATM} + 1470 - 2086056 + 816825}{W_{PG} C_{PG}} = 819.7$$

TAIL GAS HEATER:

$$T_{TG OUT} = T_{TG IN} + \Delta F (T_{TG IN} - T_{TG N}) = 85 + 0.711 (819.7 - 85) = 607.4^\circ F$$

$$Q_{TG} = W_{PG} C_{PG} \Delta T = 15450 (0.248) (607.4 - 85) = 2001528 \text{ BTUH}$$

$$Q_{REJATMOS} = 9997 (21) = 209937$$

$$T_{PG OUT} = \frac{T_{PG IN} - (Q_{TG} + Q_{REJAT})}{W_{PG} C_{PG}} = 819.7 - \frac{(2001528 + 209937)}{17644 (0.253)} = 324.3$$

CASCADE COOLER:

$$Q_{REJ_{COOL}} = W_{DG} C_{P_D} \Delta T = 17092 (0.253 \frac{\text{BTU}}{\text{#}}} (607.4 - 105)$$

$$= 2172516.5 \text{ BTUH}$$

$$Q_{REJ_{CONDENS}} = 673,700 \text{ BTUH} - \text{SEE NEXT PAGE}$$

$$Q_{REACT} = 0.8C (6086.7) = 4869,400 \text{ BTUH}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:
PDL

Date:

Job No:

Checked By:


Date:

Sheet No:


_____ of _____

Calculations For:

REACTION HEAT TABLE 1



<u>CONSTITUENT</u>	<u>HEAT OF COMBUSTION</u>	<u>CONSTITUENT LBS/HR</u>	<u>SYSTEM NET HEAT</u>
NH ₃	1163 B/#	1088	(1265,344 BTU/H)
O ₂	-	-	-
NO ₂	(1443.7 B/#) + 33.1 x 10 ³ J/mol (9.48 x 10 ⁹ B/H)	2939 1287	(4,242,963 BTU/H) (1,858,042 BTU/H)
H ₂ O	6827 B/# (LIQUID)	1726.2	11,784,767 BTU/H
	$h_g - h_f = 1856.0 - 313.8 = 1542.2$		2,717,665 BTU/H
			<u>NET = 7,136,082 BTU/H</u>



<u>CONSTITUENT</u>	<u>HEAT OF COMBUSTION</u>	<u>CONSTITUENT LBS/HR</u>	<u>SYSTEM NET HEAT</u>
NO ₂	(1443.7 B/#)	4226	6,101,076
H ₂ O	6827 B/# (LIQUID)	552	(3768,504 BTU/H)
	$h_g - h_f = 1530.3 - 309.8 = 1220.5$		(673,716 BTU/H)
HNO ₃	1190 B/# (LIQUID)	4025	4,789,750 BTU/H
	$h_g - h_f = 206 B/#$		829,150
NO	(1296 B/#)	919	(1,191,024 BTU/H)
			<u>NET 6,086,732</u>

 <p>AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479</p>	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:
TABLE I

PRODUCT

SOLUTION - 1.98.2 # MOLES/HR.

HNO₃ - 61.2 # MOLES/HR

REFERENCE "HEAT OF DILUTIONS OF ACIDS" TABLE

$$\eta = \frac{198.2 - 61.2}{61.2} = 2.2$$

$$\phi_L = 0.952 \text{ cal/mol} = 12351.168 \text{ BTU/°F/mol}$$

$$\text{HEAT OF DILUTION} = \frac{12351.168 \text{ BTU/°F/mol}}{\text{mol}} (61.2 \text{ # MOLES/HR}) (9.48 \times 10^{-4} \text{ BTU/°F})$$

$$= 716 \text{ BTUH}$$

HEAT ABOVE AMBIENT:

$$Q = w C_p \Delta T = 6830 \text{ #/HR} (0.64 \text{ BTU/°F})(87-60)$$

$$= 118022 \text{ BTUH}$$

ABSORPTION COOLER:

$$Q_{REJ} = w_{DG} C_p \Delta T = 170.92 (0.253) (105-85)$$

$$= 86,485 \text{ BTUH}$$

$Q_{REJ\text{CONDENS}} = 0 \rightarrow$ ALL CONDENSATION IN
PRODUCT GAS OCCURS IN
CASCADING COOLER CALC'S.

$$Q_{REAT} = 0.2 (6086.7) = 1217,300 \text{ BTUH}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: _____ Date: _____ Job No: _____
Checked By: _____ Date: _____ Sheet No: _____ of _____

Calculations For:

TABLE 1

TURBINE:

From KEENAN & KAYE @ 324°F (784°R) : $P_{T_1} = 5.144$, $h_1 = 187.92$

$$P_{T_2} = P_{T_1} \left(\frac{P_2}{P_1} \right) = 5.144 \left(\frac{15}{73} \right) = 1.057$$

$$h_{2,TURB} = 119.4$$

$$h_2 = h_1 - E_{TURB}(h_1 - h_{2,TURB}) = 187.92 - 0.725(187.92 - 119.4) \\ = 138.2 \text{ BTU/B#}$$

$$T_2 = 578^{\circ}\text{R} \text{ OR } 118^{\circ}\text{F}$$

$$W_{TURB} = \frac{W_{T_2}}{2545} \Delta h = \frac{15450(187.92 - 138.2)}{2545} = 301.8 \text{ HP}$$

$$Q_{TURB} = 301.8(2545) = 768174 \text{ BTUH}$$

$$Q_{PROJATM} = W C_p \Delta T = 15450(0.248)(118-60) = 222233 \text{ BTUH}$$

$$Q_{REJEXH} = W C_p \Delta T = 15450(0.248)(607.4-60) = 2097418$$

AIR COMPRESSOR:

FROM JOY MFR. CO. TEST PERFORMANCE

CURVE EXTRAPOLATED TO 4195 SCFM

DELIVERY — USE 1095 HP

$$Q_{MTR} = \frac{(1095 - 302)(2545)}{1000} = 2018.2 \text{ MBH}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-12-95	Job No: 95095
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For: TURBINE DRIVE FOR AIR COMPRESSOR ECO #1

USING FIG. 4 (ATTACHED) FROM MARK'S HANDBOOK:

$$\text{RATIO OF COMP} = \frac{(115 + 14.7)^{1/2}}{14.7} = 2.974$$

$$HP = \frac{69(41975 \text{ CFM})(1440)(1.03)^2}{10^6} = 859$$

FROM MULLIER DIAGRAM:

$$\Delta h = 1271 \text{ Btu/lb} - \cancel{1054 \text{ Btu/lb}} = 217 \text{ Btu/lb}$$

STEAM RQD. @ 75% TURB. EFF.:

$$W = \frac{859 \text{ HP} (2545 \text{ Btu/HP})}{217 \text{ Btu/lb} (0.75)} = \cancel{13132 \text{ lb/hr}} / \cancel{229 \text{ (0.75)}}$$

MAX. TEMP FOR CONDENSER:

$$\text{COND. TEMP} = 101^\circ\text{F} @ 2'' \text{ HG}$$

FOR 95% EFFICIENCY STEAM:

$$h_{\text{steam}} = h_f + z(h_g - h_f) = 69.1 + .95(1036.6)$$

$$= 1053.9$$

$$Q_{\text{COND}} = \frac{13132 (1053.9 - 64) \cancel{\text{lb/hr}}}{1000} = \cancel{13228 \text{ MBH}}$$

$$R.V. WTR = \frac{Q_{\text{COND}}}{500(\Delta T)} = \frac{13228}{500(95-64)} = \frac{880}{835 \text{ GPM}}$$

$$\Sigma_{dng} = 227[(1.08R_c)^{0.203} - 1] \quad (4)$$

$\Sigma_{dng} = 0.0456 \bar{m}c_v \Delta t$, where c_v is the specific heat at constant volume and Δt is the isentropic temperature rise. A multiplier of 0.147 applied to the above Σ values gives the bhp per 100 ft³/min at 14.4 psia and 60°F. Figure 4 illustrates a similar empirical solution for Σ , wherein an arbitrary pressure efficiency of 68 percent is applied at $1.5R_c$, 78 percent at R_c , and 87 percent at $4R_c$. Mechanical efficiency of 87 percent is widely accepted, which includes loss allowances of 3 percent for piston-ring friction and piston-rod packing and 3 percent for gearing friction of the crosshead, slipper plates, connecting-rod pins, and crankshaft bearings. The cylinder losses are dissipated by convectional air circulation in the sizes under 300 hp and into the lubricant system in larger sizes. The ring and packing losses are mostly absorbed by the jacket-water system. Where the cylinder power is less than 100 hp, these losses should be doubled.

Temperature Rise

On compression is essentially an adiabatic function, especially when referred to the internal cylinder conditions. The pressure-temperature rise follows the equation

$$T_2 = T_1(KR_c)^{\sigma/m} \quad (5)$$

where η represents the heat leak factor applied in a manner consistent with the thermal efficiency. These factors are less than 1.05 for normal water-jacket cylinders, 1.09 for dry-jet cylinders, 1.11 for forced-air-cooled cylinders with fins, 1.15 for high-velocity water-jacket cooling and the expansion cycle, curve CFD on Fig. 1. There was a time when water was injected into the suction of air compressors to reduce the charge temperature; when the speed of machinery was increased and the clearance volume reduced, the practice was discontinued as hazardous. The temperature drop was substantial, $\eta \approx 1.75$. The scheme is still applied in chemical processes to wash out unsaturated gums and to suppress the charge temperature of exothermic gases. The liquid is usually a light solvent of the same character as the gas and is injected into the suction line. A short, 10-s blast of steam for 2 or 4 h can usually clear the gums from a cylinder. The temperature behavior is only consistent below $4R_c$; and this, the cylinder cooling effect is perceptible because of the reduced mass flow at higher R_c operation. European practice of process sizing includes a warm-up factor, which assumes the gas is heated 20 to 40°F in passing through the cylinder and suction valves. Such a correction complements the volumetric efficiency by a judgment factor of 0.95 to 0.90. Thermocouple probes in the suction valve and in the stream show no such evidence at the ambient-temperature range. American practice has always disregarded such corrections. The warm-up factor also allows for valve and piston-ring leakage. If such leakage is perceptible, the temperature rise is usually cumulative and readily detectable by thermometry.

Compression Efficiency

Compression efficiency is an approximate method of accounting for all the power losses that occur between stagnant inlet and discharge pressures. It presumes that all valve and piping channels offer equal resistance and that the resulting speed and character of the gas are inconsequential.





Fig. 4 Approximate horsepower to compress air or gas. If single-stage, multiply cubic feet actual capacity of free gas per minute by 1,440 to obtain capacity in millions of cubic feet per 24 h. Then capacity in 24 h times horsepower per million as obtained from the chart will give the total horsepower. If two-stage, take the square root of the total number of compressions. Read the horsepower from the chart for this ratio, multiplying the same for the two stages, to which add 3 percent for cooler loss. Note that horsepower is for 14.4 psia intake. If horsepower based on capacity at 14.7 psia, add 2 percent to horsepower.

$$(1.5)^2 = 2.25 \quad HF = 69 \quad \frac{69}{2.25} = 30.9$$

ECO No. 1




JOY MANUFACTURING CO., BUFFALO, NY

TEST PERFORMANCE F07693M1 - CUSTOMER WITNESS TEST

7693

HOLSTEN DEFENSE CORP.

19705Z



1190

SCFM (dry) 14.70, 60, 0.

1150

1110



USE 1095 HP

1070

4000

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: <u>PDL</u>	Date: <u>11-13-95</u>	Job No: <u>95099-00</u>
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO No. 1INACTIVE HEATER LOSS TO ATMOS:

$$\bar{Q} = \frac{21 \text{ FT} (33526 \frac{\text{BTU}}{\text{FT}^2})}{1000} = 704.0 \text{ MBH}$$

$$\bar{Q} = W C_P \Delta T$$

APPARENT PRODUCT GAS CP FROM EXISTG. SYST. CALCS:

$$\bar{Q}_{ex} = 1895,400 = 17644 (C_{P_{ex}})(1070 - 785)$$

$$C_{P_{ex}} = 0.377 \frac{\text{B}/\#\text{OF}}{\text{F}}$$

$$1895,400 = 17644 (0.377)(1070 - T_{LUG})$$

$$T_{LUG} = 1070 - \frac{1895,400}{17644(0.377)} = 964^\circ\text{F}$$

CASCADES CAR-572 DRAINS

$$\bar{Q} = (\#/\text{HR}) h_{fg} + (15445 \frac{\text{#}/\text{HR}}{\text{F}} - \frac{\#}{\text{HR}})^{\frac{8}{3}} \Delta T$$

$$\bar{Q} = W C_P \Delta T = \frac{17644 (0.377)(965 - 105)}{1000}$$

$$= 5720.5 \text{ MBH}$$

$$\#/\text{HR} \Sigma \text{VAP} = 5720.5 \text{COP/HR} - (15445 \frac{\text{#}/\text{HR}}{\text{F}})(155 - 75)$$

$$950 - 25$$

$$= 5767 \frac{\text{#}/\text{HR}}{\text{F}}$$

$$\text{DRAIN} = 15445 - 5767 = 9678 \frac{\text{#}/\text{F}}{\text{F}} \text{ OR } 19 \text{ GPM}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For: ECO No. 1

TAIL GAS RELEASE TO ATMOSPHERE.

$$Q = W C_p \Delta T = 15450(0.248)(85 - 60)/1000 \\ = 95.8 \text{ MBH}$$

ELECT ENERGY SAVINGS

$$\frac{1354.1 \text{ MBH}(1152 \text{ h/yr})}{1000} = 1580 \text{ MILLION BTU/yr}$$

$$\text{ADDITIONAL STREAM RAD,} = \frac{13432 \text{ #/HR}(1285 - 1105.7) \text{ #}}{1000 \text{ BTU}} (1152 \text{ h/yr})$$

$$= 2774 \text{ MILLION BTU/yr}$$

 <p>AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479</p>	Made By: PDC	Date: 12-18-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

TABLE 2

AMMONIA VAPORIZER, MIXER, CONVERTOR AND AIR
PREHEATER CONDITIONS IDENTICAL TO TABLE 1
CALCS.

TAIL GAS HEATER:

$$Q_{\text{RET}} = 33526(21) = 704046 \text{ BTUH}$$

REF. SCHULLER HT. TRANS. TABLE

$$\Delta T_{PG} = \frac{704046}{17644(0.253)} = 157.7^\circ$$

$$T_{LUG} = 1070 - 157.7 = 912^\circ F$$

CASCADE COOLER:

$$Q_{\text{RET}} = W_{DG} C_p \Delta T = 17092(0.253)(912 - 105) = 3,489,691 \text{ BTUH}$$

$$Q_{\text{REJ CONDENS}} = 673700 \text{ BTUH} - \text{SAME AS TABLE 1}$$

$$Q_{\text{REACT}} = 4869400 \text{ BTUH} - " " " "$$

ABSORPTION COLUMNS:

SAME AS TABLE 1

STOAM TURBINE:

$$Q_{\text{GAIN}} = 1095 \text{ HP}(2545^3/\text{HP}) = 2,786,775 \text{ BTUH}$$

$$W_{STM} = \frac{Q_{\text{GAIN}}}{\Delta h_{\text{STIM}}} = \frac{2786775}{1271-1054} = 12,842 \text{ #/HR}$$

$$Q_{\text{RET}} = W_{STM} \Delta h_{\text{STIM}} = 12842(1105.7 - 69.1) = 13,312,017 \text{ BTUH}$$

$$Q_{\text{REJECTEND}} = 12842(1)(110 - 60) = 526.5$$

$$Q_{\text{REC}} = W_{CON} C_p \Delta T = 12842(1)(101 - 60) = 526,522 \text{ BTUH}$$

$$Q_{\text{LOSS}} = 13,312.0 - 526.5 = 12,785.5$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

TABE 2

PRODUCT : SAME AS TABLE 1

STACK LOSS :

$$\text{Q}_{\text{REJ}} = W C_p \Delta T = 15450(0.248)(85-60)$$

$$= 95790 \text{ BTUH}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: <u>PDC</u>	Date: <u>10-10-95</u>	Job No: <u>950 94-00</u>
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO No. 2

HEAT LOSS FROM BARO PIPE °

18" Ø PIPE @ 735°F O/SIDE TEMP. DULL:

$$S = \frac{[(19265 - 9997)(135) + 9997]}{\frac{200}{100}} \frac{21 \text{ FT}}{\text{HR}} = 341.3$$

HEAT TRANSFERRED TO FLOWING GAS:

From Existing System Calcs:

$$Q_{\text{TAIGAS}} = 1341.1 \text{ MBH}$$

APPARENT PROD. GAS SPECIFIC HEAT:

$$C_p = \frac{1341100}{(176445 \text{ HR})(1070 - 785)} = 0.267 \text{ BTU/MBH}$$

$$Q_{\text{GAS}} = \frac{176445 \text{ HR} (0.267 \text{ BTU/MBH}) (1070 - 400)}{1000} \\ = 3156.3 \text{ MBH}$$

THIS IS EXAGGERATE TO 110% OF SYSTEM

$$Q = WC_p \Delta T = \frac{15450 (0.248) (85 - 65)}{1000} \\ = 76.6 \text{ MBH}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	PDL	11-13-95	95094-00
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

ECO No. 2

DOWNTHERM PARAMETERS

$$\text{PUMP SUCTION TEMP} = \frac{\text{STIM TEMP} + \text{Pr.GAS LUG TEMP}}{2}$$

$$= \frac{338 + 400}{2} = 369^{\circ}\text{F}$$

\therefore 725°F ENTERING BOILER

$$Q = W C_p \Delta T \quad \text{Ref. TECHNICAL DATA REF. FROM TRANSFER CATALOG.}$$

$$W = \frac{3156300 \text{ BTUH}}{(0.55 \text{ BTU}/\text{lb}) (725 - 369)} = 16120 \text{ #/HR}$$

$$\text{GPM} = \frac{16120 \text{ #/HR} (7.48 \text{ G/FT}^3)}{50 \text{ FT}^3 (\text{400 M/HR})} = 40 \text{ GPM}$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By: PDL	Date: 12-18-95	Job No: 95094-00
Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TABLE 3

AMMONIA VAPORIZER, MIXER, CONVORTOR AND AIR
 PREHEATER: SAME AS TABLE 1

DOWNTHERM HEATER: (PROD. GAS COOLED TO 400°F - 50°F SCOP)

$$Q_{REJ} = W_C P \Delta T = 17644(0.253)(1070 - 400) = 2990834 \text{ BTUH}$$

REF SCHULLER HT. TRNSF. TABLES

$$Q_{LOSS} = \left[\frac{(19245 - 9997)(135)}{200} + 9997 \right] (15 \text{ FT}) = 243,794 \text{ BTUH}$$

CASCADE COOLER:

$$Q_{PROJ_{GAS}} = W_D C_P \Delta T = 17092(0.253)(400 - 105) = 1,275,661$$

$$Q_{REJ_{COOLERS}} = \text{SAME AS TABLE 1} = 673,700 \text{ BTUH}$$

ABSORPTION COLUMNS: SAME AS TABLE 1

AIR COMP: :

$$Q_{GN} = 859(2545) = 2186300$$

Q_{REJ} = SAME AS TABLE 1

FINAL BLCHR: " " "

STACK LOSS:

$$Q_{PROJ} = W_C P \Delta T = 15450(0.248)(85 - 60) = 95790 \text{ BTUH}$$

$$\text{STEAM: } W = \frac{Q_{REJ}}{\Delta h} = \frac{2747,000}{(1189-168)} = 2690 \text{ #/HR}$$

AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-14-95	Job No: 95094
Calculations For:	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

FILTERED WATER COST - ECO 3

UNIT COST OF FILTERED WATER FROM STEAM
COST CALC'S BY J. BOUCHUAN IN MARCH, 1995.

\$ 148 PER MILLION GALLONS.

SEE APPENDIX
REFERENCE
MATERIAL

PRESSENT ANNUAL CONSUMPTION = 540 $\frac{\text{GAL}}{\text{MI}} (60 \text{ M}/\text{HR})(1152 \text{ HR/YR})$

$$= 37,324,800 \text{ GAL/YR}$$

$$\text{ANNUAL Cost} = \frac{\$ 148.00(37324800)}{1000 \text{ CCF}} = \$ 5524/\text{YR.}$$

$$\text{WATER SAVED} = 540 \text{ GPM} - 5.7 - 11.5 = 522.8 \text{ GPM}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-12-95	Job No: 95c94-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO No. 3

EQUIPTCENG. WATER FLOWLWT

CONVERTER

77 GPM

140°F

CASCADE CLR

24 GPM

100°F

AIR COMPRESSOR

156 GPM

104°F

109 GPM

104°F

174 GPM

101°F

$$\underline{540 \text{ GPM} @ \text{MIXED TSMIP} = 108^\circ\text{F}}$$

AIR COMPRESSOR BALANCED FOR 85°F EWT

CONVERTER SHOULD BE OKAY w/ 160°F LWT

CONSIDER INCREASING FLOW @ ABSORPTION
TOWERS FOR 4°AT RATHER THAN 10°AT.

$$\text{GPM} = \frac{115900 \text{ BTUH}}{500(4)} = 58 \text{ GPM} - 28988 \text{ #/HR}$$

CASCADE CLR DRAIN:

$$Q = W(950) + (58(8.33)(60)) - W(100 - 89)$$

$$W = 3740 \text{ #/HR}$$

$$\text{DRAIN} = 58(8.33)(60) - 3740 \text{ #/HR} = 25050 \text{ #/HR}$$

OR 50 GPM @ 100°F

$$\text{TOWER FLOW} = 77 + 50 + 156 + 109 + 174 = 566 \text{ GPM}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: PDL	Date: 11-13-95	Job No: 95094-00
Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO No. 3

TOWER SECTION 2

566 GPM

128°F EWT

85°F LWT

76°F W.B.

MARLEY NC 3011

± 85000 CFM

15 HP FAN

1% BLOWDOWN - 5.7 GPM

2% MAKEUP - 11.5 GPM

ASSUME FAN EFFICIENCY = 80% = 1.25 TIMES

$$\text{ANNUAL FAN ENERGY} = \frac{15 \text{ HP}(0.8)(1152 \text{ hr})}{0.748 \text{ HP}} = 18481 \text{ KWH/yr}$$

ASSUME PUMPING ENERGY FOR 100% CFD 100%

TOWER SYSTEM OFFSETS THE SAVINGS IN

PUMPING ENERGY AT PUMP 40%.

J. Bouchillon, PE

3/95

1994 1 P.C. 1995
1992, p. C-4

1994 OUT-OF-POCKET COST FOR STEAM, B-200

GIVEN: 1994 AREA B MONTHLY USAGE & PROD. REPORT, BY KEN HARRIS

Sum of individual boilers' steam output = 1,324,620,000 lbs

$$\begin{aligned} \text{Building Steam Output} &= \text{Sum} - \text{internal consumption (turbines, DA, etc)} \\ &\quad \downarrow 16.4\% \text{ (ECAO study, EMC Enginc., 1992, p. C-4)} \\ &= 1,324,620,000 \times .836 = 1,107,382,000 \text{ lbs} \\ &= 1,107 \text{ m Btu} \end{aligned}$$

$$\begin{aligned} \text{Steam Coal, 1994} &= 64,673 \text{ tons} \\ \text{Btu content of coal} &= 64,673 \text{ tons} \times 2000 \times 14,100 \frac{\text{Btu}}{\text{lb}} \\ &= 1,824 \text{ m m Btu} \end{aligned}$$

$$\begin{aligned} \text{Cost of treatment of Sulfuric System backwash water} &= \text{Utilities Cost Report} \\ 50 \text{ gpm ave} \times 60 \frac{\text{min}}{\text{hr}} \times 8760 \times \$.239 \frac{\text{per 1000gal}}{} &= \$ 6,500/\text{yr.} \end{aligned}$$

$$\begin{aligned} \text{Cost of Filter Water for feed water} &= \text{Utilities Cost Report} \\ \frac{1,324,620,000 \text{ lbs}}{8 \text{ lbs water}} \times 0.148 \frac{\text{per 1000gal}}{\text{gad}} &= \$ 24,500/\text{yr} \end{aligned}$$

$$\begin{aligned} \text{cost of electricity (motors, precipitators, etc)} &= \text{Cost of str 2235 per mar '95 elec bill} \\ 412,000 \frac{\text{kWh}}{\text{mo}} \times .035 \frac{\$}{\text{kWh}} \times 12 \text{ mo} &= \$ 173,000/\text{yr} \end{aligned}$$

Cost of fly ash disposal = 15,000 est

Cost of cinder removal = 10,000 est

[Cost of bldg maintenance = 343,391 routine + 529,104 Major = 892,495]

Cost of water treatment chemicals (See Amasis Study 1995) \$ 91,000

Out of Pocket Steam Cost = Coal + electricity + chemicals + FW + bldg steam output + water softening + waste water disposal disp. + fly ash + cinder

$$\begin{aligned} \text{OPSC} &= \frac{\text{per defense fuels, Geo. Tittswinter 1995}}{(45 \times 64,673) + \$ 173,000 + \$ 91,000 + \$ 24,500 + \$ 6,500 + 15,000 + 10,000}{1,107,382,000 \text{ lbs}} \\ &= \frac{3,23 \text{ million}}{1,107} = \boxed{2.92 \frac{\$}{1000 \text{ lbs}}} \quad 3.75 \frac{\$}{\text{Klbs}} \text{ Counting Maintenance} \end{aligned}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-12-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO NO. 4**REF. SHULLER 18" PIPE w/ 1" INSUL. & METAL. JACKET****AIR PREHEATER**

$$Q_{AMOS} = \frac{2792 (15 \text{ FT})}{1000} = 41.9 \text{ MBH} @ 1200^\circ \text{ OPRT. TEMP}$$

TAIL GAS HTR

$$Q_{AMOS} = \frac{(1345 + 1978)(21 \text{ FT})}{2(1000)} = 34.9 \text{ MBH} @ 900^\circ$$

APPARENT PROD. L-GAS CP FROM EXISTING SYST. CALCS:

$$C_p = \frac{3056.500 \text{ BTU}}{17644 \text{ FT}(1470 - 1070)} = 0.434 \text{ BTU}/\#^\circ F$$

NEW AIR PREHEATER LVG. PROD. GAS TEMP:

$$Q = 2086.1 \text{ MBH} + 41.9 \text{ MBH} = W C_p \Delta T = 17644 (0.434) (\Delta T)$$

$$\Delta T = 267.0$$

$$T_{LVG} = 1470 - 267.0 = 1203^\circ F$$

APPARENT PROD. GAS CP @ TAIL GAS HEATER FROM EXISTING SYST. CALCS.

$$Q = W C_p \Delta T = 1895.4 (1000)$$

$$C_p = \frac{18954 \text{ BTU}}{17644 (1070 - 785)} = 0.377 \text{ BTU}/\#^\circ F$$

ASSUME 800°F NOV. T.G. HTR. LVG. PROD. GAS TEMP:

$$Q = 17644 (0.377) (1203 - 800) = 2680.7 \text{ MBH}$$

$$T.G. \Delta T = \frac{2680.7 \text{ MBH}}{15000 (0.24)} = 722^\circ F \quad T_{LVG} = 808^\circ F$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: _____ Date: _____ Job No: _____

Checked By: _____ Date: _____ Sheet No: _____ of _____

Calculations For:

ECO No. 4

USING GAS TABLES FOR AIR @ LOW PRESS:

$$\bar{T}_1 = 1265^{\circ}\text{R}$$

$$h_1 = 308 \frac{\text{Btu}}{\text{lb}}$$

$$P_{r1} = 29.23$$

IDEAL CONDITIONS @ TURB EXH.

$$P_{r2} = P_{r1} \left(\frac{P_2}{P_1} \right) = 29.23 \left(\frac{14.7}{58+14.7} \right) = 5.91$$

$$\bar{T}_{2\text{ IDEAL}} = 815^{\circ}\text{R} \rightarrow 355^{\circ}\text{F}$$

$$h_{2\text{ IDEAL}} = 195.5 \frac{\text{Btu}}{\text{lb}}$$

EFF TURB = 72.5% FROM EARLIER CALCS

$$\text{HP} = \frac{15450 \frac{\text{Btu}}{\text{hr}} (308 \frac{\text{Btu}}{\text{lb}} - 195.5 \frac{\text{Btu}}{\text{lb}}) \cdot .725}{2545} = 495$$

$$h_{2\text{ ACTUAL}} = h_1 - (h_1 - h_{2\text{ IDEAL}}) \cdot (.725) = 226.4 \frac{\text{Btu}}{\text{lb}}$$

$$\bar{T}_{2\text{ ACTUAL}} = 941^{\circ}\text{R} \text{ OR } 480^{\circ}\text{F}$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By:

PDL

Date:

12-19-95

Job No:

95094-00

Checked By:

Date:

Sheet No:

of _____

Calculations For:

TABLE 5

AMMONIA VAPORIZER, MIXER AND CONVERTER
 SAME AS TABLE 1.

AIR PREHEATER:

$$Q_{REJ_{AIR}} = \text{SAME AS TABLE 1}$$

EXTRAPOLATED FROM SCHULER TABLE

$$Q_{REJ_{ATMOS}} = (3200)(15) = 45000 \text{ BTUH}$$

$$\bar{T}_{LUG} = T_{GNT} - \frac{Q_{AIR} + Q_{REJ_{ATMOS}}}{W.C.P.} = 1470 - \frac{2086056 + 45000}{17644(0.253)}$$

$$= 992.6^{\circ}\text{F}$$

$$\text{REVISE } Q_{REJ_{ATMOS}} = 2850(15) = 42750 \text{ BTUH}$$

$$\bar{T}_{LUG} = 1470 - \frac{2086056 + 42750}{17644(0.253)} = 993.1^{\circ}\text{F}$$

TAIL GAS HEATER:

$$\bar{T}_{Gout} = \bar{T}_{Gin} + \text{EFF}(\bar{T}_{Pout} - \bar{T}_{gin}) = 85 + 0.71(993 - 85)$$

$$= 730.6^{\circ}\text{F}$$

$$Q_{REJ_{TG}} = W.C.P. \Delta T = 15450(0.248)(730.6 - 85)$$

$$= 2,473,635 \text{ BTUH}$$

$$Q_{REJ_{ATMOS}} = 1100(21) = 23100 \text{ BTUH}$$

$$\bar{T}_{Pout} = \bar{T}_{gin} - \frac{(Q_{REJ_{TG}} + Q_{REJ_{ATMOS}})}{W.C.P.} = 992.6 - \frac{(2473635 + 23100)}{17644(0.253)}$$

$$= 433.3^{\circ}\text{F}$$

$$\text{REVISE } Q_{REJ_{ATMOS}} = \frac{(85.4 + 13.45)}{2} 21 = 23090 \rightarrow \bar{T}_{Pout} = 433.3^{\circ}\text{F}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

TABLE 5

CASCADE COOLER:

$$Q_{REJ_{CAS}} = W_{DG} C_p \Delta T = 17092 (0.253)(433 - 105) \\ = 1418363 \text{ BTUH}$$

$$Q_{REJ_{CONDENS}} = \text{SAME AS TABLE 1} = 673700$$

ABSORPTION COLUMNS AND FINAL BEACHEOR - SAME
AS TABLE 1

TURBINE:

From KOONAN & KAYO @ 731°F (1191°R) $P_1 = 23.35$ $h_1 = 289.01$

$$P_{T2} = P_{T1} \left(\frac{P_2}{P_1} \right) = 23.35 \left(\frac{15}{73} \right) = 4.80$$

$$THEORETICAL h_2 = 184.72 \text{ BTU}$$

$$h_2 = h_1 - E_{TURB}(h_1 - h_{2_{THEORETICAL}}) = 289.1 - .725(289.1 - 184.7)$$

$$= 213.4$$

$$T_{EXH} = 889^{\circ}\text{R} \text{ OR } 429^{\circ}\text{F}$$

$$W_{K_{TURB}} = \frac{W(\Delta h)}{2545} = \frac{15450(289.01 - 213.4)}{2545} = 459 \text{ HP}$$

$$Q_{REC} = 459(2545) = 1168175 \text{ BTUH}$$

$$Q_{LOST} = W C_p \Delta T = 15450(0.248)(429 - 60) \\ = 1,413,860$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:	Date:	Job No:
Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TABLO - 5

$$\overline{T}_{EXH} = \frac{W_{ST} C_{PST} \overline{T}_{ST} + W_G C_{PG} \overline{T}_G}{W_{ST} C_{PST} + W_G C_{PG}} = \frac{2000(0.5)(400) + 15450(0.248)(535)}{2000(0.5) + 15450(0.248)}$$
$$= 507^{\circ}\text{F}$$

$$W_{K_{TURB}} = \frac{W_{ST} C_{PST} \Delta T_{ST} + W_G C_{PG} \Delta T_G}{2545}$$
$$= \frac{2000(0.5)(731-400) + 15450(0.248)(731-535)}{2545}$$
$$= 425 \text{ HP}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:
ECO No. 5

CURSORY EVALUATION

REASONABLE ENERGY RECOVERY, IF IMPLEMENTED
WITH ECO No. 4, IS THE DIFFERENCE BETWEEN
PREHEATER AND TAIL-GAS HEATERS LOSS TO
ATMOSPHERE WITH & WITHOUT INSULATION

$$\text{PREHEATER: } 980.4 - 41.9 = 938.5 \text{ MBH}$$

$$\text{TAIL-GAS HEATERS: } 554.3 - 34.9 = \underline{\underline{519.4 \text{ MBH}}}$$

$$1457.9 \text{ MBH}$$

ECO No. 4 HEAT REMOVAL REQ'D TO KEEP
TAILGAS TO TURBINE B51000 750°F MFR'S.
MAX. TEMP.

$$Q = 15450 (0.24) (805 - 745) = 222.5 \text{ MBH}$$

20 PSIG STEAM AVAILABLE @ STACK

$$Q = 15450 (0.24) (480 - 275) = 760.1 \text{ MBH}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For: **ECO No. 5**

TURBINE OUTPUT

$$T_N = 745^{\circ}\text{F}$$

$$P_r = 24.38 \quad h_1 = 292.58$$

$$f_{r2} = \frac{14.7(24.38)}{72.7} = 4.93$$

$$h_2 = 185.7$$

$$h_{exh} = 292.58 - (292.58 - 185.7)(.725)$$

$$= 215.09$$

$$T_{exh} = 435^{\circ}\text{F}$$

$$HP = \frac{15450 (292.58 - 215.09)}{2545} = 470.4$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 12-18-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

TABLE 6

AMMONIA VAPORIZER, MIXER, CONVORTOR, AIR PROHEATOR,
CASCADE COOLER AND TURBINE; SAME AS TABLE 5

RECOVERY BOILER:

SATURATION TEMP @ 30 PSIG = 275°F

USING COUNTERFLOW WASTE HEAT BOILER, ASSUME
OUTLET GAS TEMP (T_{T6out}) EQUALS 275°F

$$Q_{T6} = W C_p \Delta T = 15450 (0.248)(429 - 275) = 590066 \text{ BTUH}$$

$$\text{STEAM} \rightarrow W = \frac{Q}{h_{si} - h_{fw}} = \frac{590066}{1172.4 - 188.4} = 560 \text{ #/HR}$$

$$Q_{LNG} = W C_p \Delta T = 15450 (0.248)(275 - 60) = 823794$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-13-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: 1 of 1

Calculations For:

ECO. NO. 6**PROCESS DRY AIR RATE:**

$$M_D = M_w (1 - w) = 19350 \text{ #/HR} (1 - 0.0055) \text{ #/DRY AIR}$$

$$= 19243.6 \text{ #/HR DRY AIR}$$

CONVERT MFG. DESIGN CONDENSATE RATE TO PROCESS DRY AIR RATE:

$$1^{\text{st}} \text{ STG CLR} = 216.4 \frac{(19243.6)}{27706} = 150 \text{ #/HR}$$

$$2^{\text{nd}} \text{ " } = 264.7 \frac{(19243.6)}{27706} = 184 \text{ #/HR}$$

$$\text{AFT COOLER} = 173 \frac{(19243.6)}{27445} = 121 \text{ #/HR}$$

$$455 \text{ #/HR}$$

TURBINE ENTERING CONDITIONS:

$$\text{MASS FLOW} = 15450 + 1149 = 16599 \text{ #/HR}$$

SPRAY MIX PRECISE**T_{MIX} hg****ERROR**

$$Q = 1149 \text{ #/HR} [T_{\text{mix}} - 207] + h_{fg}^{EPA} + (h_{fg}^{EPA} - 1181.0)$$

325	1189.2	-147.9
400	1229.9	-232.3

$$Q = 15450 \text{ #/HR} (0.248 \text{ #/hr})(435 - T_{\text{mix}})$$

316	1184.2	-137.7
-----	--------	--------

$$T_{\text{mix}} = 456.6 - 0.235 \text{ hg}$$

NOT ENOUGH HEAT IS AVAILABLE IN
TAIL GAS TO VAPORIZ THE CONDENSATE

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-13-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: <u>2</u> of _____

Calculations For:

ECO No. 6

EVALUATE FOR INCORPORATION w/ ECO No. 4

$$Q = 1149 \frac{\text{Btu}}{\text{HR}} [T_{mix} - 207] + 897.8 + h_g - 1181.0$$

$$Q = 15450 (0.248) (805 - T_{mix})$$

$$T_{mix} = 953.8 - 0.235 h_g$$

<u>T_{mix}</u>	<u>h_g</u>	<u>ERROR</u>
500°	1280.6	155.5
450°	1229.9	267.4
600°	1330.1	43.8
650°	1354.8	-12.0

USE 640°F TAIL GAS/WATER VAPOR TEMP.

@ TURBINE INLET.

$$h = \frac{15450 (265.9)}{165.99} + 1149 (1340.0) = 340.3 \frac{\text{Btu}}{\text{lb}}$$

$$P_{x_1} = 17.413 \quad S_1 = 1.81$$

$$P_{x_2} = 17.413 \left(\frac{14.7}{72.7} \right) = 3.521 \quad h_{2, \text{DEA}} = 1188$$

$$T_{2, \text{IDEAL}} = 244^\circ\text{F}$$

$$T_{2, \text{DEA}} = 285^\circ\text{F}$$

RECALCULATE USING TURBINE EXHAUST HT.
RECOVERY TO CONDENSATE

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 9-14-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: <u>3</u> of _____

Calculations For:

ECO No. 6

$$\begin{array}{c}
16599 \text{ #/HR} \\
\hline
207^{\circ}\text{F} \quad | \quad 306^{\circ}\text{F} @ 73 \text{ PSIA} \\
\hline
1149 \text{ #/HR} \quad | \quad 1149 \text{ #/HR} \\
h = 270 \quad T \quad h = 1181.2 \\
\hline
16599 \text{ #/HR}
\end{array}$$

(1) ASSUME 100% PLATE CHANGE OF CONDENSATION w/
TAIL GAS TEMP. L.V.G. $T_{L.V.G.} - HX = 220^{\circ}\text{F}$

$$H_{GAS} Q_{AH} = 1149 \text{ #/HR} (h_{L.V.G.} - h_{CUST}) = 1149 (1181.2 - 270) = 104696.9$$

$$\text{ONE SIDE } Q_{AH} = W_G C_p \Delta T + W_S C_p \Delta T = 15450(0.24) \Delta T + 1149(0.5) \Delta T$$

$$\Delta T = \frac{104696.9}{15450(0.24) + 1149(0.5)} = 249.5 \rightarrow T_{L.V.G.} = 20 + 249.5 = 464.5$$

STEAM/TAIL GAS MIXTURE CONDITIONS?

$$C_{ST} = 1149 (h_{\text{mix}} - 1181.2)$$

<u>T_{MIX}</u>	<u>h_{MIX}</u>	<u>ERROR</u>
------------------------	------------------------	--------------

$$Q_{GAS} : 15450(0.24)(805 - T_{MIX})$$

700	1380.2	-542
-----	--------	------

$$T_{MIX} = 585.5 - 0.310 h_{\text{mix}}$$

400	1231.6	-196
-----	--------	------

310	1183.8	-77.5
-----	--------	-------

INSUFFICIENT HEAT IN TURBINE

EXHAUST GAS TO VAPORIZER

CONDENSATE



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:	Date:	Job No:
Checked By:	Date:	Sheet No: <u>4</u> of _____

Calculations For:

ECO No. 6

CONSIDER DELIVERING AMMONIA VAPORIZER
CONDENSATE ONLY:

* USE ORIFICE TRAP FOR CONTINUOUS DRAINAGE

TAIL GAS
15450 #/HR
805°F
 $C_p = 0.24$
58 PSIG

CONDENSATE/STEAM
16144 #/HR
58 PSIG
694 #/HR
100 PSIG
338°F
 $h = 309$

$$15450 \times (805 - T_{mix}) = 694(h_{@mix} - 309)$$

$$T_{mix} = 862.8 - 0.187 h_{@mix}$$

<u>T_{mix}</u>	<u>$h_{@mix}$</u>	<u>ERROR(T_{mix} - calc)</u>
750	140.5	149.9
650	135.55	40.7
540	130.4	(79.4)
600	133.9	(13.9)
615	133.83	2.46

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: <u>5</u> of _____

Calculations For: **ECO No. 6**

TURBINE PROCESS %

GAS

$$P_{r_1} = 16,005 \quad h_1 = 259.7$$

$$P_{r_2} = \frac{14.7}{72.7} (16,005) = 3,236$$

$$T_2 = 227^\circ$$

$$h_2 = +64.5$$

$$h_{exH} = 259.7 - (259.7 - 64.5)(.725)$$

$$= 190.68$$

$$T_{exH} = 335^\circ$$

VAPOR

$$h_1 = 1338.3$$

$$S_1 = 1.80$$

$$h_2 = 1183$$

$$h_{exH} = 1338.3 - (1338.3 - 1183).725$$

$$= 1230.5$$

$$T_{exH} = 380^\circ$$

$$HP = 15450(.24)(615-335) + 694(1338.3-1230.5)$$

1545

$$= 437.3$$

THIS CONCEPT IS ABANDONED



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By:

PDL

Date:

12-12-95

Job No:

95094-00

Checked By:

Date:

Sheet No:

22 of _____

Calculations For:

ECO #7 ITERATION #1

WET GAS HEATER - 2000#/HR STEAM + SPRAY STEAM SATURATION TEMPER.

$$15405(0.246)(T_{wgin} - 85) = 2000(0.50)(324 - T_{wgin})$$

$$\frac{T_{wgin} = 2000(.5)(324) + 15405(.246)(85)}{15405(.246) + 2000(.5)} = 134.8^{\circ}\text{F}$$

$$C_{pg,wg} = \frac{2000(.5) + 15405(.246)}{174.85} = 0.275 \text{ BTU/lb}$$

$$T_{wgout} = T_{wgin} + 0.711(T_{pgin} - T_{wgin}) = 134.8 + 0.711(993 - 134.8)$$

$$= 745.0^{\circ}\text{F}$$

~~$$Q_{ATTEMPERATOR} = W_{wg} C_{pg,wg} (T_{wgout} - 745) = 17405(0.275)(895.7 - 745)$$~~

$$= 721307 \text{ BTUH}$$

~~$$W_{ATTEMPERATOR} = \frac{Q_{ATTEMPERATOR}}{h_{fg}} = \frac{721307}{891.7} = 809 \text{ #/HR}$$~~

$$T_{pgout} = T_{pgin} - \frac{W_{wg} C_{pg,wg} (T_{wgout} - T_{wgin}) + Q_{ATTEMPERATOR}}{W_{pg} C_{pg}}$$

$$= 124.5 - \frac{17405(0.275)(895.7 - 134.8) + 721307}{17644(0.253)}$$

$$= 227.5^{\circ}\text{F}$$

CONDENSATION WILL OCCUR AT 254°F
 IN PRODUCT GAS.

$$Q_{PG ECONOMIZER} = 2000 \text{ #/HR} (1 \frac{\text{E}}{\text{E}}) (240 - 150) = 180000 \text{ BTUH}$$

$$W_{pg_econ} = \frac{Q_{pg_econ}}{h_{fg,16}} = \frac{180000}{944} = 191 \text{ #/HR}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:

PDL

Date:

12-12-95

Job No:

95094-00

Checked By:

Date:

Sheet No:

23 of _____

Calculations For:

TURBINE

PARTIAL PRESSURE $H_2O = .175(58 \text{ PSIG}) = 10.2 \text{ PSIG}$ OR 25 PSIA

$$S = 1.9764$$

$$h_{ST} = 14041.8$$

$$\text{THEOR. } h_{EXHST} = 1334 \text{ @ } 15 \text{ PSIA } \& 600^\circ$$

$$h_{EXHST} = h_{ST} - 0.725(h_{ST} - 1334) = 1404.8 - 0.725(1404.8 - 1334)$$
$$= 1353.5 \text{ B/H}$$

$$T_{EXHST} = 639^\circ F$$

GAS @ $745^\circ F$:

$$P_{r1} = 24.38$$

$$h_{1,GAS} = 292.58 \text{ B/H}$$

$$P_{r2} = P_{r1} \left(\frac{P_2}{P_1} \right) = 24.38 \left(\frac{15}{73} \right) = 5.01$$

$$\text{THEOR. } h_{2,GAS} = 186.46 \text{ B/H}$$

$$h_{2,EXH_G} = 292.58 - 0.725(292.58 - 186.46)$$

$$= 215.64 \text{ B/H}$$

$$T_{2,EXH_G} = 437^\circ F$$

$$15405(0.246)(T_{EXH} - 437) = 2000(0.46)(639 - T_{EXH})$$

$$T_{EXH} = \frac{15405(0.246)(437) + 2000(0.46)(639)}{15405(0.246) + 2000(0.46)} = 476.5^\circ F$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By:
 PDL

Date:
 12-12-95

Job No:
 95094-00

Checked By:

Date:

Sheet No:
24 of _____

Calculations For:

$$C_{PEXH} = \frac{W_{EXH} C_{PEXHG} + W_{EXHST} C_{PEXHST}}{W_{EXH}} = \frac{15405(0.246) + 2000(0.46)}{17405} = 0.271$$

$$\text{W}_{K_{TURB}} = \frac{W_{EXH} C_{PA,TU} (T_{45} - T_{EXH})}{2545} \\ = \frac{17405(.271)(745 - 470.5)}{2545} = 497 \text{ HP}$$

WASTE HEAT BOILER

$$T_{STACK} = 260^{\circ}\text{F} - 155.6^{\circ}\text{F} = 104.4^{\circ}\text{F}$$

$$Q_{BLR} = W_{EXH} C_{PEXH} (T_{EXH} - 260) = 17405 (0.263) (492 - 260) \\ = 1061983 \text{ BTUH}$$

$$W_{STREAM} = \frac{Q_{BLR}}{h_{fg}} = \frac{1061983}{891.7} = 1191 \text{ #/HR}$$

TOTAL H₂O ADDED TO STACK GAS:

~~1191 #/HR~~
~~1191 #/HR~~

~~2000 #/HR~~ - ASSUMED 2000 #/HR

PARTIAL PRESSURE = H₂O @ STACK:

$$P = 0.175(14.696) = 2.57 \text{ PSIA}$$

DEW POINT = 136°F



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:

Date:

Job No:

Checked By:

Date:

Sheet No:

of

Calculations For:

ECO #7 ITERATION 2

CASE A 1800#/HR SATURATED STEAM @ 80 PSIG INJECTED

WET GAS CONDITIONS:

$$W_{TG} C_{PTG} (T_{WG} - 85) = W_{ST} C_{PST} (T_{SAT} - T_{WG})$$

$$[15405(0.248) + 1800(0.5)] T_{WG} = 1800(.5)(324) + 15405(0.248)(85)$$

$$T_{WG} = 130.6^{\circ}\text{F}$$

$$C_{PWG} = \frac{W_{TG} C_{PTG} + W_{ST} C_{PST}}{W_{WG}} = \frac{15405(0.248) + 1800(0.5)}{17205} = 0.274 \text{ Btu}/\#^{\circ}\text{F}$$

$$T_{WGout} = T_{WG} + EFF(T_{PGin} - T_{WG}) = 130.6 + 0.71(993.1 - 130.6)$$

$$= 743.8$$

$$T_{PGout} = T_{PGin} - \frac{Q_{FW} + Q_{EOTAN}}{W_{PG} C_{PPG}} = 993.1 - \frac{17205(0.274)(743.8 - 130.6) + 41024}{17644(0.253)}$$

$$= 336.3^{\circ}\text{F}$$

ECONOMIC:

$$Q_{FW} = W_{FW} C_{FW} \Delta T_{FW} = 1800(1)(324 - 150) = 313200 \text{ Btu/h}$$

$$T_{PGout} = T_{PGin} - \frac{Q_{FW}}{W_{PG} C_{PPG}} = 336.3 - \frac{313200}{17644(0.253)} = 266.1^{\circ}\text{F}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For: TABLE 7

TURBINE:

PERCENT STEAM BY VOLUME:

$$MOL_{ST} = \frac{1800}{18.016} = 99.9$$

$$MOL_{TG} = 546.73$$

$$\% = \frac{99.9 (100)}{546.73 + 99.9} = 15.45$$

$$INLET STEAM PARTIAL PRESSURE = 0.1545 (58) = 8.96 \text{ PSIG}$$

$$h_{ST,in} = 1407.3 \quad S_{ST,in} = 1.983$$

$$INLET STEAM PARTIAL PRESSURE = 0.1545 (15) = 2.47 \text{ PSIA}$$

$$INLET STEAM ENTHALPY = 1186.3 \quad S = 1.9815$$

$$h_{ST,out} = h_{ST,in} + 5 (1407.3 - 1186.3) = 1247.1$$

$$T_{ST,out} = 412^\circ F$$

$$INLET GAS PARTIAL PRESSURE = 58.91 = 49$$

$$P_{r1} = 24.31 \quad h_1 = 292.33 \rightarrow @ 744^\circ F$$

$$INLET GAS PARTIAL PRESSURE = P_{r1} \left(\frac{P_2}{P_1} \right) = 24.31 \left(\frac{16}{63.7} \right) = 5.93$$

$$INLET R. \quad h_2 = 195.71$$

$$h_3 = 292.33 - 0.725 (292.33 - 195.71) = 222.28$$

$$T_2 = 925^\circ R \text{ OR } 465^\circ F$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:	Date:	Job No:
Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TABLE 7

$$W_{ST} C_{P_{ST}} (T_{EXH} - T_{ST, OUT}) = W_{GAS} C_{P_{GAS}} (T_2 - T_{EXH})$$

$$[1800(0.47) + 15405(0.248)] T_{EXH} = 15405(0.248)(465) + 1800(0.47)(412)$$

$$T_{EXH} = 455.4^{\circ}\text{F}$$

$$h_{INLET} = \frac{W_{ST} h_{ST, IN} + W_{GAS} h_1}{W_{ST} + W_G} = \frac{1800(1407.3) + 15405(292.33)}{1800 + 15405}$$

$$= 409.0 \text{ BTU}/\#$$

$$h_{EXH, 2} = \frac{W_{ST} h_{ST, OUT} + W_{GAS} h_2}{W_{ST} + W_G} = \frac{1800(1247.1) + 15405(222.28)}{1800 + 15405}$$

$$h_{EXT} = 329.5 \text{ BTU}/\#$$

$$W_{K_{TURB}} = \frac{(17205)(409.0 - 329.5)}{250} = 537.4 \text{ HP}$$

$$Q_{RE} = 537.4 \text{ HP} = 1367,798 \text{ BTU/H} @ T_{REF} = 14^{\circ}\text{C}$$

$$Q_{RE} = W_C \cdot \dot{V} = 17205(0.274)(455.4 - 62) = 1,863,983 \text{ BTU/H}$$

WASTO HEAT BOILER

$$Q = W_{ST} h_{fg} = 1800(891.7) = 1,605,060 \text{ BTU/H}$$

$$T_{STACK} = T_{EXH} - \frac{Q}{W_{EXH} C_{P_{EXH}}} = 455.4 - \frac{1605060}{17205(0.274)} = 115^{\circ}\text{F}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For:
ECO #1 ITERATION 3

CASE B 1500#/HR SATURATED STEAM @ 80 PSIG INJECTOR

SUBSTITUTION OF 1500#/HR IN FORMULAS OF CASE GIVES
THE FOLLOWING RESULTS:

WET GAS CONDITIONS:

$$T_{WG} = 124.2^{\circ}\text{F}$$

$$C_{PWG} = 0.270 \frac{\text{BTU}}{\text{#lb}^{\circ}\text{F}}$$

$$T_{WGout} = 742.0^{\circ}\text{F}$$

$$TPGout = 352.2^{\circ}\text{F}$$

ECONOMIZER:

ALLOW OUTLET OF ECONOMIZER TO CONTAIN SMALL
PERCENTAGE OF STEAM SUCH THAT $T_{PGout} = 265^{\circ}\text{F}$

$$Q_{FW} = W_{FW} \Delta h_{FW} = W_{PG} C_{PG} \Delta T_{PG}$$

$$\Delta h_{FW} = \frac{17644 (0.233)(352.2 - 265)}{1500} = 259.5 \frac{\text{BTU}}{\text{#lb}}$$

$$Q_{FW, SENS} = W_{FW} C_{FW} \Delta T = 1500(1)(324 - 150) = 261000 \text{ BTUH}$$

FW EQUILIBRIUM:

$$W_{SEC} = W_{FW} \Delta h_{FW} - Q_{FW, SENS} = \frac{1500(259.5) - 261000}{h_{fg}} = 143.8 \frac{\text{#lb}}{\text{HR}}$$

$$Q_{REC} = W_{FW} \Delta h_{FW} = 1500(259.5) = 389250 \text{ BTUH}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TURBINE:

$$MOL_{ST} = 83.26$$

$$MOL_{TG} = 546.73$$

$$\%_o = 13.22$$

$$\text{PARTIAL PR} = .1322(58) = 7.67 \text{ PSIG} \rightarrow 22.37 \text{ PSIA INLET}$$

$$h_{S\text{IN}} = 1403.4 \text{ @ } 742^{\circ}\text{F} \quad S_{S\text{IN}} = 1.985$$

$$\text{PARTIAL PR} = .1322(16) = 2.11 \text{ PSIA}$$

$$T_{HOR} h_{S\text{out}} = 1159 \quad S = 1.985$$

$$h_{S\text{out}} = 1403.4 - 0.725(1403.4 - 1159) = 1226.2$$

$$T_{S\text{out}} = 367^{\circ}\text{F}$$

$$\text{GAS PARTIAL PR} = 58 - 7.67 = 50.3 \text{ PSIG OR } 65.0 \text{ PSIA}$$

$$P_{r1} = 24.16 \quad h_1 = 291.81 \rightarrow @ 742^{\circ}\text{F}$$

$$P_{r2} = 24.16 \left(\frac{16}{55} \right) = 5.95$$

$$T_{HOR} h_2 = 195.9$$

$$h_2 = 291.81 - 0.725(291.81 - 195.9) = 222.28 \text{ Btu/lb}$$

$$T_2 = 465^{\circ}\text{F}$$

$$h_{exH} = 311.4 \text{ Btu/lb}$$

$$T_{exH} = 449.7$$

$$W_{KTURB} = 525 \text{ HP}$$

$$h_{INLET} = 390.4$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

WASTO HEAT BOILER:

$$Q = (W_{ST} - W_{ST,0}) h_{fg} = (1500 - 143)(891.7) = 1210037 \text{ BTUH}$$

$$\overline{T}_{\text{STACK}} = \overline{T}_{\text{EXH}} - \frac{Q}{W_{BTUH} C_{P_{BTUH}}} = 449.7 - \frac{1210037}{16905(0.275)} = 189.4^{\circ}\text{F}$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By:	Date:	Job No:
Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

ECO #7 - ITERATION 4

CASE C 1400#/HR STEAM @ 80PSIG INJECTED @ TAIL GAS
 & WITH PRODUCT GAS LEAVING THE
 HEAT RECOVERY UNIT AT 245°F

WET GAS CONDITIONS:

$$W_{TG} C_{PTG} (\bar{T}_{WG} - 85) = W_{ST} C_{PST} (\bar{T}_{SAT} - \bar{T}_{WG})$$

$$[15405(0.248) + 1400(0.47)] \bar{T}_{WG} = 1400(0.47)(324) + 15405(0.248)(85)$$

$$\bar{T}_{WG} = 120.1^{\circ}\text{F}$$

$$C_{PWG} = \frac{W_{TG} C_{PTG} + W_{ST} C_{PST}}{W_{TG} + W_{ST}} = \frac{15405(0.248) + 1400(0.47)}{15405 + 1400} = 0.266 \text{ BTU/lb}$$

$$\begin{aligned} \bar{T}_{WGout} &= \bar{T}_{WG} + \text{EFF}(\bar{T}_{PGin} - \bar{T}_{WG}) = 120.1 + 0.711(993.1 - 120.1) \\ &= 740.8^{\circ}\text{F} \end{aligned}$$

$$\begin{aligned} \bar{T}_{PGout} &= \bar{T}_{PGin} - \frac{Q_{WG} + Q_{REJAHNUSS}}{W_{PG} C_{PG}} = \frac{(15405 + 1400)(0.266)(740.8 - 120.1) + 41024}{17644(0.255)} \\ &= 993.1 - 635.8 = 362.3^{\circ}\text{F} \end{aligned}$$

ECONOMIZER:

$$Q_{FW} = W_{PG} C_{PG} \Delta \bar{T}_{PG} = 17644(0.253)(362.3 - 245)$$

$$= 523619 \quad ; \quad \Delta h_{fw} = \frac{523619}{1400} = 374.0 \text{ BTU/lb}$$

$$Q_{FWSENG} = W_{FW} C_{FW} \Delta \bar{T}_{FW} = 1400(1)(324 - 85) = 243600 \text{ BTU/H}$$

$$W_{STEC} = \frac{W_{FW} \Delta h_{fw} - Q_{FWSENG}}{h_{fg}} = \frac{1400(374.0) - 243600}{891.7} = 314 \text{ #/HR}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:	Date:	Job No:
Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TURBINS :

$$MOL_{ST} = \frac{1400}{18.016} = 77.7$$

$$MOL_TG = 546.73$$

$$\sigma_D = \frac{77.7}{546.73 + 77.7} = 12.44$$

$$\text{INLET STEAM PARTIAL PRESSURE} = .1244(58) = 7.22 \text{ PSIG}$$

$$h_{STIN} = 1402.9 \quad s_{STIN} = 1.9889$$

$$\text{OUTLET STEAM PARTIAL PRESSURE} = .1244(16) = 1.99 \text{ PSIA}$$

$$T_{HOR.} h_{STOUT} = 1151.4 \text{ Btu/lb}$$

$$h_{STOUT} = h_{STIN} - 0.725(h_{STIN} - 1151.4) = 1402.9 - .725(1402.9 - 1151.4) \\ = 1220.5 \text{ Btu/lb}$$

$$T_{STOUT} = 354.3^\circ F$$

$$\text{INLET GAS PARTIAL PRESS.} = (5.8 - 7.22 = 50.78 \text{ PSIG} @ 741^\circ F \\ \text{OR } 1201^\circ R$$

$$P_{r_1} = 24.08 \quad h_1 = 291.56$$

$$P_{r_2} = P_{r_1} \left(\frac{16}{50.78} \right) = 7.59$$

$$T_{HOR} h_2 = 210$$

$$h_2 = h_1 - EFF(h_1 - 210) = 291.56 - .725(291.56 - 210) \\ = 232.4 \quad T_2 = 506^\circ F$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: _____ Date: _____ Job No: _____

Checked By: _____ Date: _____ Sheet No: _____ of _____

Calculations For:

$$W_s C_{PST} (T_{EXH} - T_{STOUT}) = W_{GAS} C_{P_{GAS}} (T_2 - T_{EXH})$$

$$\underline{[1400(0.47) + 15405(0.248)]T_{EXH}} = 15405(0.248)(506) + 1400(0.47)(354)$$

$$T_{EXH} = 483.7^{\circ}\text{F}$$

$$h_{INLET} = \frac{W_{ST} h_{STINT} + W_G h_1}{W_{ST} + W_G} = \frac{1400(1402.9) + 15405(291.56)}{1400 + 15405}$$
$$= 384.1 \text{ Btu/\#}$$

$$h_{EXH} = \frac{W_{ST} h_{STOUT} + W_G h_2}{W_{ST} + W_G} = \frac{1400(1220.5) + 15405(232.4)}{1400 + 15405}$$
$$= 314.7 \text{ Btu/\#}$$

$$W_{KETURE} = \frac{(1400 + 15405)(384.1 - 314.7)}{2545} = 458 \text{ HP}$$

$$Q_{RSC} = 458(2545) = 1165979 \text{ BTUH}$$

Waste Heat Boiler:

$$Q = (W_{ST} - W_{ST ECON}) h_{fg} = (1400 - 314)(891.7) = 968386 \text{ BTUH}$$

$$T_{STACK} = T_{EXH} - \frac{Q}{W_{W_G} C_{PW_G}} = 483.7 - \frac{968386}{16805(0.266)}$$

$$= 267.1^{\circ}\text{F}$$



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By:

Date:

Job No:

Checked By:

Date:

Sheet No:

____ of ____

Calculations For:

ECO #7 ITERATION 5

FINAL CASE: STEAM & SPRAYWATER INJECTED @ TAIL GAS
 LEAVING TAIL GAS HEATER & WITH
 WASTE HEAT BOILERS IN BOTH
 TURBINE EXH. GAS & PRODUCT GAS LUG
 TAIL GAS HEATER

WET GAS CONDITIONS: (USING ECO #4 RESULTS)

$$W_{TG} C_{PTG} (T_{TG} - T_{WG}) = W_{ST} C_{PST} (T_{WG} - T_{SAT})$$

$$[15405(0.248) + 1500(0.47)] \bar{T}_{WG} = 1500(0.47)(324) + 15405(0.248)(73)$$

$$\bar{T}_{WG} = 888.8^{\circ}\text{F}$$

AT TEMPERATURE SPRAY:

MFRS TURBINE INLET
MAXIMUM MINUS 5°F

~~$$Q_{AT} = W_{WG} C_{Pw} (\bar{T}_{WG} - 745) \rightarrow (15405 + 1500)(0.270)(888.8 - 745)$$~~

~~$$= 656259 \text{ BTUH}$$~~

~~$$W_{AT} = \frac{Q_{AT}}{h_{fg}} = \frac{656259}{891.9} = 736 \#/\text{HR}$$~~

PRODUCT GAS WASTE HEAT BOILER:

* WITH 150°F FEEDWATER, ASSUME PRODUCT GAS
 LEAVING BOILER @ $\frac{225^{\circ}\text{F}}{250}$

$$Q_{REC} = W_{PG} C_{PPG} (T_{POUT} - \frac{225}{250}) = 17644(0.253)(433 - 325)$$

$$= 928498 \text{ W.O. CONSIDERING CONDENSATION}$$

$$W_{STPG} = \frac{Q_{REC}}{C_{Pw} \Delta T_{FW} + h_{fg}} = \frac{928498}{(1)(324 - 150) + 891.7} = \frac{871 \#/\text{HR}}{766}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:

Date:

Job No:

Checked By:

Date:

Sheet No:

of _____

Calculations For:

TURBINE :

$$MOL_{H_2O} = \frac{1500 + 736}{18,016} = 104.1$$

$$MOL_{TG} = 546.73$$

$$\alpha = \frac{104.1 / 83.3}{546.73 + 104.1} = \frac{13.2}{83.3} = +8.5$$

$$\text{STEAM PARTIAL PRESSURE} = 0.185(58) = 10.73 \text{ PSIG INLET}$$

$$= 0.185(16) = 2.96 \text{ PSIA OUTLET}$$

$$h_{S1N} = \frac{1404.9}{7+0.4183/\#} @ 745^{\circ}\text{F} \quad s_{S1N} = 1.974$$

$$\text{THEIR } h_{S1OUT} = 1180.7 \text{ B/H}$$

$$h_{S1OUT} = h_{S1N} - EFF(h_{S1N} - 1180.7) = 1404.8 - 0.725(1404.8 - 1180.7)$$

$$= 1242.3 \text{ B/H}$$

$$T_{S1OUT} = 402^{\circ}\text{F}$$

TAIL GAS :

$$P_{T1} = 24.38 @ 1205^{\circ}\text{R} \quad h_{T1} = 292.58$$

$$P_{T2} = P_{T1} \left(\frac{16}{70} \right) = 5.57$$

$$\text{THEOR. } h_2 = 192.30$$

$$h_2 = h_{T1} - EFF(h_{T1} - 192.3) = 292.58 - 0.725(292.58 - 192.3)$$

$$= 219.9 \text{ B/H} \quad T_{T2OUT} = 455^{\circ}\text{F}$$

$$W_{KTURB} = W_{ST} \Delta h_{ST} + W_g \Delta h_g = \frac{1500}{2545} (1404.8 - 1242.3) + 15405 (292.58 - 192.3)$$

$$= 535 \\ = 582 \text{ HP}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: _____ of _____

Calculations For:

TURBING EXHAUST WASTE HEAT BOILER'S

$$W_{ST} = \frac{W_{ST} C_{PST} (T_{SOUT} - 225) + W_{TG} C_{PTG} (T_{GOUT} - 325) - W_{AT} C_{PAT} (324 - 150)}{C_{PFW} \Delta T_{FW} + h_{fg}}$$

$$= \frac{766 (0.47)(402 - 225) + 15405 (0.248)(455 - 325) - 736 (174)}{(324 - 150) + 891.7}$$

$$= 845 \text{ #/HR}$$

$$\text{TOTAL STEAM} = 876 + 845 = 1716 \text{ #/HR}$$

$$\frac{W_{ST} \text{ ASSUMED}}{1716} = \frac{\Delta T_{REC}}{440 - 225}$$

$$440 - T_{LVG} = \frac{1500 (440 - 325)}{1716}$$

$T_{LVG} = 252^\circ F \leftarrow \text{USE THIS FOR RECOVERY BOILER CUTLET TEMP.}$

$$W_{ST} C_{PST} (T_{EXH} - 402) = W_{TG} C_{PTG} (455 - T_{EXH})$$

$$T_{EXH} = 446^\circ F$$

$$Q_{LOST} = W_{EXH} C_{PExH} \Delta T_{STK} = \frac{16905}{883.286} (0.275) (250 - 60)$$

$$= 9216.90$$

$$Q_{REJ} = W_{EXH} C_{PExH} (T_{EXH} - T_{STK}) = \frac{16905}{77640} (0.275) (446 - 60) = 17944.66$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By: PDL	Date: 12-22-95	Job No: 95094-00
Checked By:	Date:	Sheet No: of _____

Calculations For:

ECO #7A

$$W_{ST} = 1200 \text{ #/HR} - \text{CLAYTON QUOTATION}$$

$$\frac{\bar{T}_{WG2} - \bar{T}_{WG1}}{\bar{T}_{PG1} - \bar{T}_{WG1}} = 0.711$$

$$\bar{T}_{WG2} = \bar{T}_{WG1} + 0.711(\bar{T}_{PG1} - \bar{T}_{WG1})$$

$$W_{ST} C_{PST} (\bar{T}_{ST} - \bar{T}_{WG1}) = W_{TG} C_{PTG} (\bar{T}_{TG1} - \bar{T}_{TG})$$

$$1200(0.47)(324 - \bar{T}_{WG1}) = 15405(0.248)(\bar{T}_{WG1} - 85)$$

$$\bar{T}_{WG1} = \frac{15405(0.248)(85) + 1200(0.47)(324)}{15405(0.248) + 1200(0.47)} = 115.7^{\circ}\text{F}$$

$$\bar{T}_{WG2} = 115.7 + 0.711(993 - 115.7) = 739.5^{\circ}\text{F}$$

$$\bar{T}_{PG2} = \bar{T}_{PG1} - \frac{Q_{RECOV}}{W_{PG} C_{PPG}} = 993 - \frac{(15405+1200)(0.275)(739.5-115.7)}{17644(0.258)} = 367.3^{\circ}\text{F}$$

TURBINE 2

<u>W_{ST} CONSTITUENT</u>	<u># MOLES/HR</u>
N ₂	505.16
A	6.21
NO	30.62
H ₂ O	$4.74 + \frac{1200}{18.016} = 71.35$
	<u>613.34</u>

$$\text{H}_2\text{O \% BY VOL} = \frac{71.35(100)}{613.34} = 11.6$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

$$H_2O \text{ PARTIAL PRESS} = (58 + 14.7)(116) = 8.43 \text{ PSIA}$$

$$h_G = 1403.5 \text{ @ } 739.5^\circ\text{F}$$

$$S_G = 2.0667$$

$$\text{THEOR. } h_2 = 1255.4$$

$$h_2 = 1255.4 - .725(1403.5 - 1255.4) = 1296.1 \quad T_{EVH} = 517^\circ\text{F}$$

$$P_{T1} = 23.94 \quad h_{G1} = 291.05$$

$$P_{T2} = P_{T1} \left(\frac{15}{64.3} \right) = 5.58$$

$$\text{THEOR } h_2 = 192.3$$

$$h_{wg2} = 291.05 - .725(291.05 - 192.3) = 211.34$$

$$T_{wg2} = 420^\circ\text{F}$$

$$W_{KTURB} = \frac{1200(1403.5 - 1296.1) + 15405(291.05 - 211.34)}{2545}$$

$$= 533 \text{ HP}$$

$$1200(.47)(517 - T_{wg2}) = 15405(.275)(T_{wg2} - 420)$$

$$T_{wg2} = 432^\circ\text{F}$$



63°F LESS THAN BASIS FOR
CLAYTON QUOTATION

Assume System W.O. PR. GAS RECOVER &
STEAM INJECTED IN TAIGAS @ OUTLET OF
ABSORPTION COLUMN WILL PRODUCE 525 HP.



AFFILIATED ENGINEERS SE, INC.
 3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500
 FAX (904) 375-3479

Made By: PDL	Date: 12-12-95	Job No: 95094-00
Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

TURBINE INLET/OUTLET PIPING.

WET GAS LEAVING HEATER

$$16905 \text{ #/HR} @ 745^{\circ}\text{F}$$

$$\text{DRY GAS} = 15320 \text{ #/HR}$$

$$\text{H}_2\text{O VAPOR} = 1500 \text{ #/HR}$$

CONSTITUENTS	# MOLES/HR	% BY VOLUME
DRY GAS	1500	82.9% 86.7
H ₂ O	$\frac{1500}{18.015} = 15.74$	17.6% 13.3
	6.5773	
	625.25	

$$\text{H}_2\text{O PARTIAL PRESSURE} = 0.176(58) = 10.2 \text{ PSIG}$$

$$V_{DG} = \frac{P_{ATM} V_{ATM}(T_{DG})}{P_{DG}} = \frac{14.7(13.07)(17405)}{518.7(58-70.2+14.7)} = 7.74 \text{ FT}^3/\text{#}$$

$$V_{H_2O} = \frac{28.64 \text{ FT}^3/\text{#}}{18.38} \text{ FROM KEENAN & KEYES}$$

$$V_{WG} = 15320(7.74) + 2085(28.64) = 9.72 \text{ FT}^3/\text{#}$$

$$\text{VELOCITY} = \frac{16905 \text{ #/HR}}{16905 \text{ FT}^3/\text{#}} = \frac{6.37 \text{ FT}/\text{SEC}}{60 \text{ MIN} (31.7 \text{ IN}^2)} = 8.089 \text{ FPM}$$

$$NRE = \frac{V D \rho}{\mu} = \frac{(8.089 \text{ FT}/\text{SEC})(6.357 \text{ IN})(0.07651 \text{ #/FT}^3)}{(218 \times 10^7 \text{ #/SEC-FT})(60 \text{ SEC/MIN})(12 \text{ IN/FT})}$$

$$= 396759.250648$$

$$\Delta P = \frac{3.4 \times 10^{-6} f L W^2}{d^5} = \frac{(3.4 \times 10^{-6})(0.018)(100)(17405)^2(9.72)}{(6.357)^5}$$

$$= 1.5 \text{ PSI}$$



AFFILIATED ENGINEERS SE, INC.
3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500
FAX (904) 375-3479

Made By:

PDL

Date:

12-12-95

Job No:

95094-00

Checked By:

Date:

Sheet No:

of

Calculations For:

TURBINE EXHAUST VELOCITY

$$r_2 = \frac{(72.7 \text{ PSIA})(9.82 \text{ FT}^3/\text{LB}) (952^\circ\text{F}) - 22.68}{(7205^\circ\text{F})(15.3 \text{ PSIA})} = 36.49 \text{ FT}^3/\text{LB}$$

$$\text{VELOCITY} = \frac{16905 \text{ FT}^3/\text{HR}}{60 \text{ SEC}/\text{HR} (36.49 \text{ FT}^3/\text{LB}) (144 \text{ IN}^2/\text{FT}^2)} = 8220 \text{ IN/SEC} = 18,618 \text{ FPM}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 11-14-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For: **ECO SAVINGS**

No. 1

266543

$$\text{OPERATING HOURS PER YEAR} = 4\% \text{ mo} (34\%) (12 \text{ mo/yr}) = 1152$$

$$\text{ELECT. SAVINGS} = 2,018.2 \times 10^6 \text{ BTU} (1152 \text{ hr/yr}) = 2324.98 \text{ MLC. B/YR}$$

$$\text{STEAM INCREASE} = 12,785.5 \times 10^6 \text{ BTU} (1152 \text{ hr/yr}) = 10537.79 \text{ "}$$

$$\text{DEMAND} = 793(.748) = 593.16 \text{ KW} \rightarrow \$13050$$

No. 2

192277

$$\text{ELECT. INCREASE} = \frac{(2786.8 - 2018.2)(1152)}{1000} = 885.427 \text{ "}$$

$$\text{STEAM OFFSET} = \frac{2990.8 - 1152}{1000} = 3445.402 \text{ "}$$

$$\text{DEMAND} = -302(.748) = -225.90 \rightarrow -4970$$

No. 3

31200

No 4 #4850

$$\text{ELECT. SAVINGS} = \frac{(2018.2 - 1618.6)(1152)}{1000} = 460.339$$

$$\text{DEMAND} = (793 - 636)(.748) = 117.44 \rightarrow \$2585$$

$$\text{No. 5} \quad \$27000 + \$4850 = \$31850$$

COST \$1,400

$$\text{ELECT. SAVINGS} = (2018.2 - 1618.6)(1152) = 460.339$$

$$\text{STEAM OFFSET} = \frac{560}{694}(714.1)(1152) = 663.804$$

$$\text{STEAM PLANT MAKEUP} = (694 - 560)(1152) = 154368 \text{ #/YR}$$

 AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By:	Date:	Job No:
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

No. 7

$$\text{ELECT SAVINGS} = (2018.2 - 1425.2)(1152) \xrightarrow{1000} 683.136$$


$$\text{ADDTL STORM PLANT MARKUP} = 420 \#/\text{HR} (1152) = 483840 \#/\text{YR}$$

\$ 412 ANNUAL RECURRING EXP.

$$\text{DEMAND} = (793 - 560) . 748 = 174.28 \rightarrow \$ 38.35$$

**REFERENCE
MATERIAL**


ENERGY BALANCE-BLDG. 302-B
NITRIC ACID MANUFACTURING



HOLSTON ARMY AMMUNITION PLANT	DRAWN-PB
HOLSTON DEFENSE CORPORATION	DATE-1-14-76
KINGSPORT, TENN.	APP'D-1976
BLDG. 302-B, NITRIC ACID MFG.	SK# 2286

FIGURE 16

ENERGY BALANCE-BLDG. 302B
NITRIC ACID MANUFACTURING



As-Built April 1995 *Broadbent*

HOLSTON ARMY AMMUNITION PLANT	DRAWN-P.
HOLSTON DEFENSE CORPORATION	DATE-2-14.
KINGSPORT, TENN.	APP'D-14
BLDG. 302B, NITRIC ACID MFG.	SK# 2286

55 TPD UNIT

FIGURE 16

HOLSTON ARMY AMMUNITION PLANT
PROCESS ENERGY INVENTORY
NITRIC ACID MANUFACTURING, BUILDING 302-B

<u>Equipment</u>	<u>Heat Recovered</u>			<u>Heat Removed</u>			<u>Heat Lost</u>						
	<u>1000 Btu/hr</u>	<u>Source</u>	<u>1b/hr</u>	<u>1000 Btu/hr</u>	<u>Donor</u>	<u>Recipient</u>	<u>Btu/hr</u>	<u>Source</u>	<u>Gal/min</u>	<u>Blu/hr</u>	<u>Source</u>	<u>Rate</u>	<u>Comments</u>
Ammonia Vaporizer Converter	631.9	Stream	694	563	Ammonia Gas	Product Gas	1,740	R.W.	77.5	69.4	.2 gpm		Based: 45 TPD production.
PRE-Compressor	1536	Reaction		2100	Air	Product Gas	3,400	R.W.	329	307	Machine losses		Mechanical & electrical efficiency.
XRN-Compressor		Elect.		1082	Tail Gas	Air			60	Exhaust Gas			318.8 hp-hr/hr 75% turbine efficiency.
Air Preheater							2,100	Air	16,556*				
Tail Gas Heater							1,440	Tail Gas	15,450*				*Pounds per hour.
Cascade Cooler	4733	Reaction	17,644				7,963	R.W.	581				
Absorption Tower	1331	Reaction		16.3	Condensate	1,256	1,453	R.W.	581				
Bleacher		Feed								112.5	61X Acid	6147 lb/hr	
Total Process Energy	18,213	Added or Recovered											18,645 Removed or Lost

EMC ENGINEERS, INC.
PROJ. # PROJECT
SHEET NO. OF 102
CALCULATED BY DATE
CHECKED BY DATE
SUBJECT

Kingsport, Tennessee

TABLE 28

Process Energy

100%

100%

100%

100%

100%

100%

100%

100%

100%

100%

100%

100%


JOY MANUFACTURING CO. BUFFALO N.Y.

TEST PERFORMANCE F07693M1 CUSTOMER WITNESS TEST

7693

HOLSTEN DEFENSE CORP

14705Z



-1190

SCFM (drgt) 14.70. 60 . 0

1150

1110



USE 1095 HP

1070

4000

vapor pressures (ρ , psia) at various temperatures (t , deg F) are as follows:

t	200	250	300	350	400	450	500
p	0.060	0.227	0.701	1.832	4.117	8.638	16.29
t	550	600	650	700	750	800	
p	28.54	47.01	73.55	110.1	158.6	221.0	

Dowtherm A is the eutectic mixture of diphenyl oxide and diphenyl containing 73.5 percent of diphenyl oxide and 26.5 percent of diphenyl and melting at 53.6°F. It is used as a liquid heating medium at elevated temperatures. Its low vapor pressure permits high temperature without attendant high pres-

sures. Table 32 (Badger, *Ind. Eng. Chem.*, Sept., 1937) gives properties of this eutectic.

Pure Hydrocarbons The vapor pressures of various commercially important pure hydrocarbons are shown graphically in Fig. 25.

Ammonia Vapor The properties of saturated and superheated ammonia vapor have been determined accurately by the NBS (*Circ.* 142, 1923). The principal properties are given in Tables 33 and 34 and Fig. 24. Properties of aqua-ammonia are given in Fig. 26.

In these tables, the entropy s_f and the heat of the liquid b_f are taken as zero at -40°F instead of at 32°F, as is customary in most tables.

Properties of Other Refrigerants Complete and consistent




Fig. 22 Enthalpy-entropy (Mollier) chart for steam. (From "Steam, Its Generation and Use," The Babcock & Wilcox Co., 1963.)

SCHULLER**Thermo-12® Gold****Heat Transfer
Tables****Pipe and Block
Insulation****Nominal Pipe Size 18" Metal Jacket**

Insulation Thickness (inches)	Pipe Operating Temperature (°F)															
	200		300		400		500		600		800		1000		1200	
	HL*	ST*	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST
Bare	1070	200	2442	300	4309	400	6783	500	9997	600	19265	800	33526	1000	54455	1200
1	157	122	306	153	469	183	651	213	854	245	1345	313	1978	390	2792	476
1½	123	114	236	137	360	161	497	185	650	209	1018	263	1490	325	2094	394
2	100	107	192	127	291	146	401	165	523	185	814	229	1188	280	1666	338
2½	85	103	163	120	246	136	338	152	440	169	685	207	997	250	1395	300
3	75	100	142	114	215	128	294	143	383	157	594	190	864	228	1208	271
3½	67	98	127	110	191	123	262	135	341	148	528	177	767	210	1071	249
4	59	96	113	106	170	117	232	128	302	139	467	165	677	194	945	228
4½	56	95	106	105	160	115	218	125	283	135	438	159	635	186	886	218
5	52	93	98	102	148	111	202	121	262	130	405	152	587	176	818	206
5½	48	92	91	100	137	109	187	117	242	126	375	145	542	168	756	194
6	45	91	86	99	129	106	176	114	228	122	352	140	509	161	709	186
6½	43	90	81	97	122	105	166	112	215	119	332	136	481	156	669	178
7	41	90	77	96	115	103	158	110	204	117	315	132	456	151	635	172
7½	39	89	73	95	110	101	150	108	195	114	300	129	434	146	605	166
8	37	88	70	94	105	100	144	106	186	112	287	126	415	142	578	161
8½	36	88	67	94	101	99	138	105	179	111	275	124	398	139	554	157
9	34	88	65	93	97	98	133	103	172	109	265	121	383	136	533	153
9½	33	87	63	92	94	97	128	102	166	107	256	119	369	133	514	149
10	32	87	61	92	91	96	124	101	160	106	247	117	357	130	496	146


Nominal Pipe Size 18" Dull Surface

Insulation Thickness (inches)	Pipe Operating Temperature (°F)															
	200		300		400		500		600		800		1000		1200	
	HL*	ST*	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST	HL	ST
Bare	1070	200	2442	300	4309	400	6783	500	9997	600	19265	800	33526	1000	54455	1200
1	193	105	366	123	554	141	760	160	991	179	1545	219	2257	264	3172	313
1½	144	98	272	112	410	126	561	140	729	154	1130	186	1644	221	2301	261
2	114	94	215	105	323	116	442	127	573	139	886	164	1285	193	1795	226
2½	95	92	179	101	269	110	367	119	476	128	735	150	1065	174	1485	202
3	82	90	155	97	232	105	317	113	410	121	632	140	915	161	1275	185
3½	73	88	137	95	205	102	280	109	362	116	558	132	807	151	1123	172
4	64	87	120	93	180	98	246	104	318	111	489	124	707	141	984	160
4½	60	87	113	92	169	97	230	102	298	108	458	121	662	136	921	154
5	55	86	104	91	156	95	212	100	274	105	422	117	609	131	847	147
5½	51	85	96	89	143	94	195	98	253	103	389	113	561	126	780	140
6	48	85	90	89	134	92	183	97	237	101	364	110	525	122	730	136
6½	45	84	85	88	127	91	172	95	223	99	343	108	495	119	688	131
7	43	84	80	87	120	91	163	94	211	98	325	106	469	116	651	128
7½	41	84	76	87	114	90	155	93	201	96	309	104	446	113	619	125
8	39	84	73	86	109	89	148	92	192	95	295	103	426	111	591	122
8½	37	83	70	86	104	89	142	91	184	94	283	101	408	109	566	119
9	36	83	67	86	100	88	137	91	177	94	271	100	392	108	544	117
9½	35	83	65	85	97	88	132	90	170	93	261	99	377	106	524	115
10	33	83	62	85	93	87	127	90	164	92	252	98	364	105	506	113

HL: Heat Transfer, BTU/hr. per linear ft.

ST: Surface Temperature, °F.


System



The Clayton Waste Heat Recovery System can be used to generate steam or high temperature hot water. Typical combinations of an exhaust gas or waste heat unit with a direct-fired steam generator are shown below and on the next page. Similar combinations are available for high temperature hot water production.

A principal feature of the Clayton Waste Heat Steam Generator is its unique coil design. The coil tube is wound in a spiral pattern with planned and closely controlled spacing between the turns. This provides the desired area to control the velocities of the combustion gases.


Various sizes of boiler tubing with relatively small internal volumes are used in the coil. This highly efficient heating surface arrangement minimizes size and weight





requirements. Several sizes of coils are available in standard production.

The Exhaust Gas Steam Generator has a somewhat different construction. Its heating section may differ in diameter, quantity of coils per section and flue gas area. A set of four or six coils and pipe sizes from 1" to 2" are used. Combinations are put together to produce the required steam output. This provides flexibility in matching exhaust gas rates with standard size sections.

In applications where gas temperatures are below 427 °C (800 °F)—typical of marine diesels—the steam or hot water flow in any section of the unit can be bypassed if one of the spiral coils is damaged. Although the steam or hot water output would be reduced after bypass, complete shutdown is not necessary.







MODEL E-302 WHSG	
LEGEND	
(1)	1-1/4" 300# FLANGE
(2)	1-1/2" 300# FLANGE
(3)	2-1/2" 300# FLANGE
(4)	1" FIN P.T.
(5)	60.00
(6)	50.94
(7)	6.10
(8)	2.75
(9)	3.494
(10)	4.06
(11)	5.10
(12)	1.94
(13)	72.75 0.0
(14)	61.12 8.0 .916 DIA. 24 HOLES
(15)	6.475
(16)	3.47 -THICK
(17)	42.00
(18)	56.18 1.0
(19)	63.25 8.0 .916 DIA. 24 HOLES
(20)	66.45 0.0
(21)	73.00 0.0
(22)	5.50
(23)	78.88 LBS
(24)	5394 LBS
(25)	115 GALL.
(26)	198.2 GALL.
(27)	2320 LBS
(28)	86.4 GALL.
(29)	288 F ²

CLAYTON MFG. CO. 11 MONT CALM, MI.	
PLAN DIMENSIONAL WASTE HEAT STEAM GENERATOR	
DOWNSPOUT	
WEIGHT	12000 LBS
WEIGHT	1764 LBS
WEIGHT	1935 LBS
VOLUME	400 GAL.
HEATING SURFACE	771.4 F ²
DO NOT SCALE DRAWING	
DATE	

CLAYTON WHSG PERFORMANCE

STEAM OUTPUT vs GAS FLOWRATE





may be obtained.
That is, the vapor pressure must increase with temperature.

Barometric Psychrometric Equations
Equations 17
standard barometric constant wetting lines at 51 increases will either relative temperatures.
In many applications (1) may be ignored. How 11g barometric

= source sound power level, dB re 1 pW
= room volume, ft³
= octave-band center frequency, Hz
= distance from the source to the reference-point, ft

equation (1) applies directly to a single control point.

INTERNAL COMBUSTION ENGINES - OBERT

TABLE IIA
APPROXIMATE HEAT-CAPACITY EQUATIONS*

Gas	Molecular Weight	Specific Heat at Constant Pressure (c_p), Btu lb. ⁻¹ R. ⁻¹ $T = \text{Rankine Degrees}$	Range R	Maximum Deviation from Experimental Data (per cent)
N ₂	28.02	0.227 + 0.0000292T	720-1900	Less than 1
H ₂ O	18.016	0.433 + 0.0000166T	720-1900
CO ₂	44.00	0.186 + 0.0000625T	720-1900	Less than 3
CO	28.00	0.226 + 0.0000321T	720-1900	Less than 1
H ₂	2.016	3.35 + 0.000114T	720-1900	Less than 1
CH ₄	16.03	0.208 + 0.000561T	720-1900
O ₂	32.00	0.200 + 0.0000353T	720-1900	Less than 1
Air	28.96	0.220 + 0.0000306T	720-1900	Less than 1
C ₆ H ₁₂	114.14	0.105 + 0.000486T	720-1900

* E. S. Taylor, W. A. Leary, and J. R. Diver, *Effect of Fuel-Air Ratio, Inlet Temperature and Exhaust Pressure on Detonation*, NACA Report No. 699 (1940).

TABLE IIB
HEAT-CAPACITY EQUATIONS*

Gas or Vapor	Equation c_p in Btu mole. ⁻¹ R. ⁻¹	Range R	Maximum Error (per cent)
O ₂	$c_p = 11.515 - \frac{172}{\sqrt{T}} + \frac{1530}{T}$ $= 11.515 - \frac{172}{\sqrt{T}} + \frac{0.05}{T} + \frac{0.05}{1000} (T - 4000)$	540-5000 5000-9000	1.1 0.3
N ₂	$c_p = 9.47 - \frac{3.47 \times 10^3}{T} + \frac{1.16 \times 10^6}{T^2}$	540-9000	1.7
CO	$c_p = 9.46 - \frac{3.29 \times 10^3}{T} + \frac{1.07 \times 10^6}{T^2}$	540-9000	1.1
H ₂	$c_p = 5.76 + \frac{0.578}{1000} T + \frac{20}{\sqrt{T}}$ $= 5.76 + \frac{0.578}{1000} T + \frac{20}{\sqrt{T}} - \frac{0.33}{1000} (T - 4000)$	540-4000 4000-9000	0.8 1.4
H ₂ O	$c_p = 19.86 - \frac{597}{\sqrt{T}} + \frac{7500}{T}$	540-5400	1.8
CO ₂	$c_p = 16.2 - \frac{6.53 \times 10^3}{T} + \frac{1.41 \times 10^6}{T^2}$	540-6300	0.8
CH ₄	$c_p = 4.52 + 0.00737T$	540-1500	1.2
C ₂ H ₄	$c_p = 4.23 + 0.01177T$	350-1100	1.5
C ₂ H ₆	$c_p = 4.01 + 0.01636T$	400-1100	1.5
C ₆ H ₁₂	$c_p = 7.92 + 0.0601T$	400-1100	Est. 4
C ₁₂ H ₂₆	$c_p = 8.68 + 0.0889T$	400-1100	Est. 4

* R. L. Sweigert and M. W. Beardsley, *Empirical Specific Heat Equations Based upon Spectroscopic Data*, Georgia School of Technology Bulletin, Vol. 1, No. 3 (June, 1938).

Gas	Chemical Formula	Molecular Weight M
Acetylene	C ₂ H ₂	26.0
Air	28.9
Ammonia	NH ₃	17.0
Argon	A	39.9
Butane	C ₄ H ₁₀	58.0
Carbon dioxide	CO ₂	44.0
Carbon monoxide	CO	28.0
Dodecane	C ₁₂ H ₂₆	170.3
Ethane	C ₂ H ₆	30.0
Ethylene	C ₂ H ₄	28.0
Helium	He	4.0
Hydrogen	H ₂	2.01
Methane	CH ₄	16.03
Nitrogen	N ₂	28.02
Octane	C ₈ H ₁₈	114.14
Oxygen	O ₂	32.00
Propane	C ₃ H ₈	44.06
Sulphur dioxide	SO ₂	64.07
Water vapor	H ₂ O	18.01

MARK's HANDBOOK

6-10 GENERAL PROPERTIES OF MATERIALS

Specific Gravity and Density of Water at Atmospheric Pressure (Weights are in vacuo)

Temp, °C	Specific gravity	Density,		Temp, °C	Specific gravity	Density,	
		lb/ft³	kg/m³			lb/ft³	kg/m³
0	0.99987	62.4183	999.845	40	0.99224	61.9428	992.228
2	0.99997	62.4246	999.946	42	0.99147	61.894	991.447
4	1.00000	62.4266	999.955	44	0.99066	61.844	990.647
6	0.99997	62.4246	999.946	46	0.98982	61.791	989.797
8	0.99988	62.4189	999.854	48	0.98896	61.737	988.931
10	0.99973	62.4096	999.706	50	0.98807	61.682	988.050
12	0.99952	62.3969	999.502	52	0.98715	61.624	987.121
14	0.99927	62.3811	999.272	54	0.98621	61.566	986.192
16	0.99897	62.3623	998.948	56	0.98524	61.505	985.215
18	0.99862	62.3407	998.602	58	0.98425	61.443	984.222
20	0.99823	62.3164	998.213	60	0.98324	61.380	983.213
22	0.99780	62.2894	997.780	62	0.98220	61.315	982.172
24	0.99732	62.2598	997.304	64	0.98113	61.249	981.113
26	0.99681	62.2278	996.793	66	0.98005	61.181	980.025
28	0.99626	62.1934	996.242	68	0.97894	61.112	978.920
30	0.99567	62.1568	995.656	70	0.97781	61.041	977.783
32	0.99505	62.1179	995.033	72	0.97666	60.970	976.645
34	0.99440	62.0770	994.378	74	0.97548	60.896	975.460
36	0.99371	62.0341	993.691	76	0.97428	60.821	974.259
38	0.99299	61.9893	992.973	78	0.97307	60.745	973.041

PHYSICAL DATA

Average Composition of Air between Sea Level and 90 km Altitude and Dry

Element	Formula	% by vol.	% by mass	Molecular weight
Nitrogen	N ₂	78.084	75.55	28.0134
Oxygen	O ₂	20.948	23.15	31.9988
Argon	Ar	0.934	1.325	39.948
Carbon dioxide	CO ₂	0.0314	0.0477	44.00995
Neon	Ne	0.00182	0.00127	20.183
Helium	He	0.00052	0.000072	4.0026
Krypton	Kr	0.000114	0.000409	83.80
Methane	CH ₄	0.0002	0.000111	16.043

From 0.0 to 0.0005 percent by volume of 9 other gases.

Average composite molecular weight of air 29.9644

Data from "U.S. Standard Atmosphere, 1962," Government Printing Office.

Volume of Water as a Function of Pressure and Temperature (From "International Critical Tables")

Temp, °F (°C)	Pressure in atmospheres						
	0	500	1,000	2,000	3,000	4,000	5,000
32(0)	1.0000	0.9769	0.9566	0.9223	0.8954	0.8739	0.8565
68(20)	1.0016	0.9804	0.9619	0.9312	0.9065	0.8855	0.8675
122(50)	1.0128	0.9915	0.9732	0.9428	0.9183	0.8974	0.8792
176(80)	1.0287	1.0071	0.9884	0.9568	0.9315	0.9097	0.8913

TABLE 136—PROPERTIES OF LIQUIDS

Liquid (at 68°F & 29.92 "Hg or as noted) (100% or % in H ₂ O as noted)	Formula	Sp. Grav.	Spec. Heat	Latent Heat	Vapor pres.	Abs. Visc.	Therm. Cond. k @ 54°F	Thermal Conductivity k
		H ₂ O 1	Btu/lb. hr. ^o F	Btu/lb. hr. ^o F	H ₂ O	cP	Btu/ft. ² hr. ^o F	Btu/in. ² hr. ^o F
Acetic acid	C ₂ H ₄ O ₂	1.049	.468	174	.461	1.22	.099	1.7
Acetone	C ₃ H ₆ O	.791	.528	217	.728	.331	.102	4.0
Ammonia	NH ₃	.618	1.13	518	253	.266	.29	0.5
Amyl acetate	C ₅ H ₁₀ O ₂	.871	.459	187	.002	.447	.073	5.2
Aniline	C ₆ H ₅ NH ₂	1.072	.495	187	.002	.447	.099	—
Benzene	C ₆ H ₆	.879	.406	168	3.01	.647	.081	—
Brine—25%	CaCl ₂	1.228	.687	—	2.67	.318	—	—
Butane	C ₄ H ₁₀	1.189	.814	—	2.02	.265	—	—
Carbon dioxide	CO ₂	.579	.550	158	61.5	1.87	.076	—
Carbon disulfide	CS ₂	1.101	.92	63.1	1.690	.071	—	—
Carbon tetrachloride	CCl ₄	1.263	.240	157	1.160	.376	.083	—
Chloroform	CHCl ₃	1.594	.201	93.8	3.58	.958	.061	—
Ethyl Acetate	C ₄ H ₈ O ₂	1.489	.234	113	6.27	.563	.070	—
Ethyl Alcohol—40%	C ₂ H ₅ O	.789	.622	368	1.73	1.19	.101	—
Ethyl Ether	C ₄ H ₁₀ O	.935	.920	503	1.51	1.25	.224	—
Ethylene glycol	C ₂ H ₆ O ₂	1.115	.57	344	.002	.245	.073	—
Ethylene glycol—50%	—	—	1.067	70	.40	.416	.167	—
Freon 11—12.87 psia	CF ₃ Cl	1.490	.214	78.9	.273	.46	.084	—
Freon 12—82.28 psia	CF ₂ Cl ₂	1.331	.253	60.6	1.53	.27	.052	—
Freon 22—133 psia	CH ₂ Cl ₂	1.215	.298	81.0	27.9	.24	.062	—
Gasoline	—	6.87	.70	—	—	.35	—	—
Glycerol	C ₃ H ₈ O ₃	1.261	.573	—	1.069	.162	—	—
Heptane	C ₇ H ₁₆	.684	.508	157	1.30	.416	.082	—
Hexane	C ₆ H ₁₄	.659	.537	157	4.96	.326	.088	—
Hydrochloric acid—40%	HCl	1.198	.60	178	—	—	—	—
Kerosene	C ₈ H ₁₈	.82	.50	—	—	—	—	—
Methyl acetate	C ₃ H ₆ O ₂	.933	.468	190	6.68	1.8	.085	—
Methyl alcohol	CH ₃ OH	.792	.610	499	3.78	.808	.093	—
Methyl chloride	CH ₃ Cl	.52	.385	177	1.4	.593	.120	—
Milk	—	1.03	.93	—	—	.183	.089	—
Nitric acid	HNO ₃	1.302	—	208	—	—	—	—
Octane	C ₈ H ₁₈	1.03	.523	156	.417	.177	.091	—
Oil, draft gage	—	.834	—	—	—	—	—	—
Oil, lube. (med.)	—	.941	.53	—	—	—	—	—
Oil, olive	—	.91	.45	—	—	—	—	—
Oil, vegetable	—	.92	.33	—	—	—	—	—
Pentane	C ₅ H ₁₂	.626	.434	—	—	—	—	—
Phenol	C ₆ H ₅ O	1.07	.561	158	.001	.240	.069	—
Propane	C ₃ H ₈	.505	.576	150	.258	1.27	.075	—
Sulfur dioxide	SO ₂	1.434	.35	151	96.5	.14	.075	—
Sulfuric acid—98%	H ₂ SO ₄	1.836	.336	202	23.0	.205	—	—
Toluene	C ₆ H ₅ CH ₃	.865	.407	178	.870	.590	.074	—
Turpentine	—	.857	.472	133	.17	1.49	.063	—
Water, 59°F (15°C)	H ₂ O	1.000	1.005	1059	2.0	1.567	.325	—
Water, 68.7°F (20.2°C)	H ₂ O	.999	1.000	1058	.504	1.140	.339	—
Water, 70°F (21.1°C)	H ₂ O	.998	.998	1054	7.07	1.000	.346	—
Water, 212°F (100°C)	H ₂ O	.958	1.006	1053	73.9	.978	.347	—
Water, heavy	D ₂ O	1.108	1.018	894	29.92	.284	.393	—
Water, sea	—	1.025	.94	—	—	—	—	—

Adapted from the data of N. V. Lamer, "Handbook of Chemistry," Handbook Publishers, Inc., Sandusky, Ohio, 1952. Refer to manufacturers' data for exact properties.

TABLE 137—PROPERTIES OF SOLIDS

	Solid	Density	Specific Heat	Thermal Conductivity k
		lb./ft. ³	cp	Blu.in./hr.-ft. ² °F
Asbestos—cement board	—	1.53	.20	1.7
Asbestos—cement board	—	120	.43	4.0
Ashes	—	—	—	0.5
Asphalt	—	82	—	5.2
Bakelite	—	86	—	—
Borax	—	109	.38	—
Brick, common	—	120	.22	5.0
Brick, face	—	130	.22	9.0
Calcium carbonate	—	177	.19	14.4
Calcium chloride	—	134	.16	—
Carborundum	—	195	.16	—
Celluloid	—	87	.36	1.4
Cellulose	—	94	.37	—
Cement, loose	—	94	.20	2.1
Cement, mortar	—	116	.20	5.0
Chalk	—	142	.21	5.8
Charcoal, hardwood	—	34	.20	—
Cinders, loose	—	43	.18	—
Clay, dry	—	63	.22	—
Clay, moist	—	110	.55	—
Coal, anth., solid	—	98	.31	—
Coat, bitum., solid	—	85	.30	—
Coke, solid	—	75	.20	—
Concrete, cinder	—	97	.18	3.5
Concrete, stone	—	140	.19	12.5
Cork	—	15	.48	0.4
Corkboard	—	8	.32	—
Cotton	—	5	.32	0.4
Dry ice	—	97	.12	—
Earth, moist	—	78	.44	—
Ebonite	—	72	.35	1.2
Fats	—	58	.46	—
Feldspar	—	160	.20	—
Flannel	—	—	—	0.7
Glass, crown	—	160	.16	—
Glass, flint	—	215	.13	4.1
Glass, pyrex	—	140	.20	7.5
Granite	—	165	.19	12.5
Graphite	—	99	.20	—
Gypsum, compressed	—	152	.26	306
Gypsum board	—	50	—	—
Hay, baled	—	20	.32	—

LANGE'S HANDBOOK

OF CHEMISTRY

14th EDITION

McGRAW-HILL

TABLE 6.3 Enthalpies and Gibbs Energies of Formation, Entropies, and Heat Capacities of the Elements and Inorganic Compounds (Continued)

Substance	State	ΔH_f° , kJ·mol ⁻¹	ΔG_f° , kJ·mol ⁻¹	S° , J·deg ⁻¹ ·mol ⁻¹	C_p , J·deg ⁻¹ ·mol ⁻¹
Nb ₂ O ₅	c	-1 899.5(42)	-1 765.8	137.3(13)	132.9
NbOCl ₃	c	-879.5	-782	159	132.9
Nitrogen					
N ₂	g	0	0	191.61(2)	31.9
NF ₃	g	-132.1(11)	-90.6	260.8(2)	31.9
N ₂ F ₂ <i>cis</i>	g	67	109	259.8	31.9
<i>trans</i>	g	81.2	120.5	262.6	31.9
N ₂ H ₄ hydrazine	lq	50.6(11)	150.1	121.5(4)	31.9
N ₂ H ₄ hydrazine- <i>d</i> ₄	g	81.6	150.9	248.86	31.9
N ₂ H ₅ ⁺ std. state	aq	-7.5	82.4	151	31.9
N ₂ H ₅ Br	c	-155.6			70.3
std. state	aq	-128.9	-21.8	233.1	-71.6
N ₂ H ₅ Cl	c	-197.1			-64.1
std. state	aq	-174.9	-49.0	207.1	-64.1
N ₂ H ₅ Cl·HCl	c	-367.4			31.9
N ₂ H ₅ OH	lq	-242.7			31.9
undissoc; ss	aq	-251.50	-109.2	207.9	31.9
N ₂ H ₅ NO ₃	c	-251.58			31.9
std. state	aq	-215.10	-28.91	297	
(N ₂ H ₅) ₂ SO ₄	c	-959.0			
std. state	aq	-924.7	-579.9	322	-151
NO	g	90.29(17)	86.60	210.76	31.9
NOBr	g	82.13	82.42	273.42	43.4
NOCl	g	51.71(42)	66.10	261.68(17)	43.4
NOF	g	-65.7(17)	-50.3	248.02	41.9
NOF ₃	g	-163	-96	278.40	41.9
NO ₂	g	33.1(8)	51.3	240.03(13)	31.9
NO ₂ Cl	g	12.1(17)	54	272.19	31.9
NO ₂ F	g	-109.(21)	-66	250.2	41.9
NO ₃	g	69.41	114.35	252.5	41.9
N ₂ O	g	82.4(4)	104.2	220.0	31.9
N ₂ O ₂	g	170.37	202.88	287.52	31.9
N ₂ O ₂ ²⁻ hyponitrite	aq	-17.2	138.9	27.6	
N ₂ O ₃	g	82.8(8)	139.7	308.5(21)	31.9
N ₂ O ₄	lq	-19.56	97.52	209.20	31.9
	g	9.08	97.79	304.38	72.3
N ₂ O ₅	g	11.3(18)	118.0	346.5(42)	31.9
Osmium					
Os	c	0	0	32.5	
OsCl ₃	c	-190.4	-121	130	
OsCl ₄	c	-254.8	-159	155	
OsO ₄	c	-394.1	-305.0	143.9	
Oxygen					
O ₂	g	0	0	205.147(35)	
O ₃	g	142.7(17)	163.2	238.9	
OF ₂	g	24.5(16)	41.8	247.5(4)	
O ₂ F ₂	g	19.79	61.42	268.11	
Palladium					
Pd	c	0	0	37.91	

TABLE I
Combustion Constants

No.	Substance	Formula	Molecular Weight	Lb per Cu Ft	Cu Ft per 1 lb	Sp Gr Air at 1,000.0	Heat of Combustion (Low)	For 100% Total Air			For 100% Total Air		
								Btu per Cu Ft Gross (High)	Btu per Cu Ft Net (Low)	Cu Ft per lb of Combustible Required for Combustion Air	Cu Ft per lb of Combustible Required for Combustion Air	Lb per lb of Combustible Required for Combustion Air	Lb per lb of Combustible Required for Combustion Air
1	Carbon*	C	12.01	14,093	14,093	1.0	3.76	4.76	1.0	3.66
2	Hydrogen	H ₂	2.016	0.0053	187.723	0.0696	3.25	27.5	61,100	51,623	0.5	1.88	2.38
3	Oxygen	O ₂	32.000	0.0846	11.819	1.1053	1.0	1.0	1.0
4	Nitrogen (atm.)	N ₂	28.016	0.0744	13.443	0.9718
5	Carbon monoxide	CO	28.01	0.9740	13.506	0.9672	3.22	3.22	4,347	4,347	0.5	1.88	2.38
6	Carbon dioxide	CO ₂	44.01	0.1170	8.548	1.5282	1.0	1.0	1.0
7	Methane	CH ₄	16.041	0.0424	21.565	0.5543	1013	913	21,879	21,520	2.0	7.53	9.53
8	Ethane	C ₂ H ₆	30.067	0.0803	12.455	1.0488	1792	1641	22,320	20,412	3.5	13.18	16.68
9	Propane	C ₃ H ₈	44.092	0.1196	8.365	1.5617	2790	2185	21,664	19,944	5.0	18.82	23.82
10	n-Butane	C ₄ H ₁₀	58.118	0.1582	6.321	2.0665	3170	3113	21,308	19,680	6.5	24.47	30.97
11	Isobutane	C ₄ H ₁₀	58.118	0.1582	6.321	2.0665	3163	3105	21,257	19,629	6.5	24.47	30.97
12	n-Pentane	C ₅ H ₁₂	72.144	0.1904	5.252	2.4872	4016	3709	21,091	19,517	8.0	30.11	38.11
13	Isopentane	C ₅ H ₁₂	72.144	0.1904	5.252	2.4872	4018	3716	21,052	19,478	8.0	30.11	38.11
14	Neopentane	C ₅ H ₁₂	72.144	0.1904	5.252	2.4872	3993	3693	20,970	19,396	8.0	30.11	38.11
15	n-Hexane	C ₆ H ₁₄	86.169	0.2274	4.398	2.9704	4762	4412	20,940	19,403	9.5	35.76	45.26
16	Ethylene	C ₂ H ₄	28.051	0.0746	13.412	0.9740	1614	1513	21,644	20,295	3.0	11.29	14.29
17	Propylene	C ₃ H ₆	42.077	0.1110	9.007	1.4504	23.36	21.86	21,041	19,691	4.5	16.94	21.44
18	n-Butene	C ₄ H ₈	56.102	0.1480	6.756	1.9316	3084	2885	20,840	19,496	6.0	22.59	28.59
19	Isobutene	C ₄ H ₈	56.102	0.1480	6.756	1.9316	3068	2869	20,730	19,382	6.0	22.59	28.59
20	n-Pentene	C ₅ H ₁₀	70.128	0.1852	5.400	2.4190	3836	3586	20,712	19,363	7.5	28.23	35.73
21	Aromatic series	C ₆ H ₆	78.107	0.2060	4.852	2.6920	3751	3601	18,210	17,480	7.5	28.23	35.73
22	Toluene	C ₇ H ₈	92.112	0.2411	4.113	3.1760	4,484	4,284	18,440	17,620	9.0	33.88	42.88
23	Xylene	C ₈ H ₁₀	106.158	0.2803	3.567	3.6618	5210	4980	18,650	17,760	10.5	39.52	50.0
Miscellaneous gases													
24	Acetylene	C ₂ H ₂	26.036	0.0697	14.344	0.9107	1499	1448	21,500	20,776	2.5	9.41	11.91
25	Naphthalene	C ₁₀ H ₈	128.162	0.3384	2.955	4.4208	5854	5654	17,298	16,708	12.0	45.17	51.17
26	Methyl alcohol	CH ₃ OH	32.041	0.0846	11.320	1.1052	868	768	10,259	9,078	1.5	5.65	7.15
27	Ethyl alcohol	C ₂ H ₅ OH	46.067	0.1216	8.221	1.5890	1600	1451	13,161	11,929	3.0	11.29	14.29
28	Ammonia	NH ₃	17.031	0.0456	21.914	0.5961	441	365	9,668	8,001	0.75	2.82	3.57
29	Sulfur*	S	32.06	3.983	3.983	1.0	3.76	4.76	1.0	3.76
30	Hydrogen sulfide	H ₂ S	34.076	0.0911	10.979	1.1898	647	596	7,100	6,545	1.5	5.65	7.15
31	Sulfur dioxide	SO ₂	64.06	0.1733	5.770	2.2640	1.0	1.41	4.69
32	Water vapor	H ₂ O	18.016	0.0476	21.017	0.6215
33	Air	28.9	0.0766	13.063	1.0000

4-2

*Carbon and sulfur are considered as gases for molar calculations only.

Note: This table is reprinted from *Fuel Flue Gases*, 1941 Edition,
courtesy of American Gas Association.

All gas volumes corrected to 60 F and 30 in. Hg dry.

Table 3-37. HEAT OF DILUTION OF ACIDS*

VIVIAN B. PARKER

ΔH_{dil} , the integral heat of dilution, is the change in enthalpy, per mole of solute, when a solution of concentration m_1 is diluted to a final finite concentration m_2 . When the dilution is carried out by addition of an infinite amount of solvent, so the final solution is infinitely dilute, the enthalpy change is the integral heat of dilution to infinite dilution. Since Φ_L , the relative apparent molal enthalpy, is equal to and opposite in sign to this, only Φ_L is referred to here.

 Φ_L , cal/mol, at 25 deg C (298.15 K)*

n	m	HF	HCl	HClO ₄	HBr	HI	HNO ₃	CH ₂ O ₂	C ₂ H ₄ O ₂
∞	0.00	0	0	0	0	0	0	0	0
500,000	.000111	300	5	5	5	5	5	9	40
100,000	.000555	900	10	10	9	9	11	13	50
50,000	.00111	1,300	16	14	13	12	15	20	53
20,000	.00278	1,800	25	22	22	20	23	23	55
10,000	.00555	2,130	34	30	31	29	31	25	58
7,000	.00793	2,250	40	35	37	34	36	26	59
5,000	.01110	2,360	47	40	44	41	42	26	61
4,000	.01388	2,450	54	43	49	46	46	27	62
3,000	.01850	2,550	60	47	56	52	51	28	62
2,000	.02775	2,700	74	54	68	63	59	28	63
1,500	.03700	2,812	85	58	77	71	65	29	64
1,110	.05000	2,927	97	62	89	81	73	29	65
1,000	.05551	2,969	102	62	92	84	76	29	65
900	.06117	2,989	107	63	97	88	78	30	66
800	.0694	3,015	113	64	102	92	81	31	67
700	.0793	3,037	120	65	108	96	84	32	68
600	.0925	3,057	129	65	115	102	88	32	68
555.1	.1000	3,060	133	65	119	105	89	32	69
500	.1110	3,077	140	65	124	108	92	32	70
400	.1388	3,097	156	64	135	116	97	33	72
300	.1850	3,126	176	61	150	125	103	34	76
277.5	.2000	3,129	182	59	155	128	105	35	79
200	.2775	3,142	212	50	176	146	117	36	82
150	.3700	3,148	242	36	197	154	118	39	88
111.0	.5000	3,156	280	18	225	170	119	42	97
100	.5551	3,160	295	-12	235	176	120	44	101
75	.7401	3,167	343	-14	270	194	121	49	113
55.51	1.0000	3,179	405	-48	314	223	121	54	130
50	1.1101	3,184	431	-61	331	234	121	56	147
40	1.3877	3,192	493	-91	379	260	121	60	155
37.00	1.5000	3,194	518	-103	398	269	121	62	162
30	1.8502	3,200	595	-138	455	301	124	65	183
27.75	2.0000	3,203	627	-149	477	315	126	66	192
25	2.2202	3,208	674	-162	510	336	130	67	204
22.20	2.5000	3,211	732	-173	550	365	139	68	218
20	2.7753	3,214	792	-182	590	396	149	69	233
18.50	3.0000	3,216	838	-187	624	427	159	69	245
15.86	3.500	3,221	946	-196	709	503	189	69	268
15	3.7004	3,227	988	-195	743	536	203	69	277
13.88	4.0000	3,234	1,052	-188	796	588	229	69	291
12.33	4.5000	3,246	1,171	-175	887	676	265	69	313
12	4.6255	3,249	1,190	-170	911	700	277	69	318
11.10	5.0000	3,256	1,271	-150	983	764	313	69	333
10	5.5506	3,265	1,396	-117	1,097	855	368	68	353
9.5	5.8427	3,269	1,462	-97	1,156	920	400	68	363
9.251	6.0000	3,272	1,498	-84	1,196	950	418	67	368
9.0	6.1674	3,274	1,535	-72	1,230	980	437	67	373
8.5	6.5301	3,278	1,618	-40	1,313	1,050	480	66	383
8.0	6.9383	3,282	1,710	+4	1,401	1,115	530	65	392
7.929	7.0000	3,283	1,725	11	1,416	1,130	538	65	394

*One calorie (thermochemical) equals 4.184 joules.

*From: NSR 1965.

Substance

HF
HCl
HClO ₄
HClO ₄ ·H ₂ O
HBr
HI
HIO ₃
HNO ₃
HCOOH
CH ₃ COOH
NH ₃
NH ₃ Cl
NH ₃ ClO ₄
NH ₃ Br
NH ₄ I
NH ₄ IO ₃
NH ₄ NO ₃
NH ₄ NO ₂
NH ₃ CH ₃ O ₂
NH ₃ CN
NH ₃ CNS
CH ₃ NH ₃ Cl
(CH ₃) ₂ NHCl
N(CH ₃) ₂ Cl
N(CH ₃) ₂ Br
N(CH ₃) ₂ I
AgClO ₄
AgNO ₃
AgNO ₂
LiOH
LiOH·H ₂ O
LiF
LiCl
LiCl·H ₂ O
LiClO ₄
LiClO ₄ ·3H ₂ O
LiBr
LiBr·H ₂ O

*25 deg C =

*From: NSR 1965.

Table 3-37. HEAT OF DILUTION OF ACIDS (Continued)

<i>n</i>	<i>m</i>	<i>HF</i>	<i>HCl</i>	<i>HClO₄</i>	<i>HBr</i>	<i>HI</i>	<i>HNO₃</i>	<i>CH₂O₂</i>	<i>C₂H₄O₂</i>
7.5	7.4008	3,286	1,820	61	1,497	1,210	595	63	402
7.0	7.9295	3,290	1,942	135	1,608	1,325	661	61	411
6.938	8.0000	3,291	1,960	146	1,622	1,340	667	61	412
6.5	8.5394	3,296	2,090	229	1,738	1,450	745	58	420
6.167	9.0000	3,302	2,202	306	1,845	1,570	805	55	426
6.0	9.2510	3,305	2,265	348	1,903	1,630	840	53	429
5.551	10.0000	3,316	2,447	481	2,078	1,820	940	49	436
5.5	10.0920	3,317	2,472	499	2,102	1,850	950	49	437
5.0	11.1012	3,335	2,721	730	2,344	2,100	1,098	43	445
4.5	12.3346	3,362	3,025	1,144	2,655	2,460	1,270	37	453
4.0	13.8765	3,400	3,404	1,574	3,089	2,960	1,495	29	462
3.700	15.0000	3,428	3,680	1,893	3,415	3,350	1,645	26	469
3.5	15.8589	3,450	3,882	2,150	3,668	3,660	1,770	21	473
3.25	17.0788	3,483	4,160	2,460	4,005	4,110	1,920	17	481
3.0	18.5020	3,520	4,460	2,880	4,370	4,630	2,101	13	488
2.775	20.0000	3,557	4,750	3,300	4,760	5,190	2,270	9	496
2.5	22.2024	3,607	5,180	4,000	5,300	6,000	2,520	+4	506
2.0	27.7530	3,712	6,260	5,500	6,650	3,060	-5	528
1.5	37.0040	8,240	8,530	3,770	-13	532
1.0	55.506	10,900	11,670	4,715	+11	518
0.5	111.012	77	495
0.25	222.02	129

*From: NSRDS—NBS 2, "Thermal Properties of Aqueous Uni-univalent Electrolytes", V.B. Parker, National Bureau of Standards, 1965.

Table 3-38. HEATS OF SOLUTION*

VIVIAN B. PARKER

 ΔH_s 25 deg C for Uni-univalent Electrolytes in H_2O^+

	Substance	State	ΔH_s		Substance	State	ΔH_s		Substance	State	ΔH_s
34	76										
35	79										
36	82										
39	88										
42	97										
44	101										
49	113										
54	130										
56	147										
60	155										
62	162										
65	183										
66	192										
67	204										
68	218										
69	233										
69	245										
69	268										
69	277										
69	291										
69	313										
69	318										
69	333										
69	353										
69	363										
67	368										
67	373										
66	383										
65	392										
65	394										

*25 deg C = 298.15 K. One calorie (thermochemical) = 4.184 joules.

*From: NSRDS—NBS 2, "Thermal Properties of Aqueous Uni-univalent Electrolytes", V.B. Parker, National Bureau of Standards, 1965.

MARKS HANDBOOK

STEEL PIPE AND TUBING 8-149

cast and their ends cropped; then they are placed in a furnace and heated to a specified temperature. The heated ingot is placed in a press where it is pierced. This hollow cylinder, open at one end, is then descaled and drawn over a mandrel on a horizontal drawbench. The closed end is then burned off, and the hollow forging is chemically descaled. Following this, the forging is straightened, placed in a lathe, and the outer diameter machined to a true dimension. The inside is dressed to remove scale, but no machining is done on the inside.

Code Designations Appropriate ASTM specifications list the physical and chemical properties of materials used in piping systems. The complete compilation of "Steel Piping, Tubing and Fittings" can be purchased from the ASTM, 1916 Race St., Philadelphia, Pa. 19103. The treatment in this section is a brief outline of frequently encountered materials.

Carbon-steel piping is most frequently used as manufactured in accordance with ASTM specifications A106 and A53. The chemical composition of these two materials is identical; both are subjected to physical tests, but those for A106 are more rigorous. For example, the Code for Pressure Piping permits the use of A53 for pressures of 600 lb/in² gage (22,137 N/m²) and less but excludes its use for higher pressures; A106 can be used for pressures not above 2,500 lb/in² gage (92,237 N/m²). A53 and A106 are made in Grades A and B; Grade B has higher strength properties but is less ductile and, for this reason, Grade A is permitted only for cold bending or close coiling. When carbon steel is intended for use in welded construction at temperatures in excess of 775°F (413°C), consideration should be given to the possibility of graphite formation.

Carbon-molybdenum steel piping may be obtained as A204 (electric-fusion-welded), A335 (seamless) or A369 (forged, turned, and bored). This material was developed in past years when steam temperatures were approaching, but not reaching, 1000°F (538°C) under which conditions carbon steel was both unsatisfactory and uneconomical. It has been found that there is a tendency for carbon-molybdenum to show graphitization at temperatures in excess of 800°F (427°C), and its use in welded construction above this value should be with caution.¹

Chromium-molybdenum steel has been used for temperatures up to 1100°F (593°C). In the small diameters, the material is usually available in the seamless construction; because of the inability of the seamless mills to fabricate large-diameter and heavy-walled pipe, it may be necessary to resort to the more expensive hollow-forged or forged-and-bored piping for higher pressures and temperatures. The material for a high-temperature piping system should be selected after a careful review of technical and economic considerations; the following is intended only as being indicative of recent and current practice. For temperatures up to 950°F (510°C), ½ percent Cr-½ percent Mo (A335, Grade P2) is used; for temperatures 950 to 1000°F (510 to 538°C), 1 percent Cr-½ percent Mo (A335, Grade P12) is used; for temperatures 1000 to 1050°F (538 to 566°C), 1¼ percent Cr-½ percent Mo (A335, Grade P11) may be used; for temperatures 1050 to 1100°F (566 to 593°C), 2¼ percent Cr-1 percent Mo (A335, Grade P22) is frequently used. When there is a combination of high temperatures and erosive action, 5 percent Cr-½ percent Mo (A335, Grade 5) has been found desirable.

¹Modern steel-making practices have reduced significantly the problem of graphitization. However, in pipe installed in the 1940s and early 1950s, there have been many failures.

Stainless-steel piping is available in a variety of compositions, most popular of which are ASTM A213, Grade TP321 (16 percent Cr-8 percent Ni, stabilized with titanium) and ASTM A213, Grade TP347 (18 percent Cr-8 percent Ni, stabilized with columbium). Either of these two materials may be used up to 1200°F (649°C); particular care must be given to choice of welding rod to avoid brittleness in the welds.

Refer to Tables 1 and 2, respectively, for permissible stress values for piping materials at low and elevated temperatures.

Schedule Designations Many years ago piping was designated as standard, extra-strong, and double extra-strong. There was no provision for thin-walled pipe, and no intervening standard thicknesses between the three schedules, which covered too great a spread to be economical without intermediate weights. Table 3 lists piping as a function of the schedule number which is given, approximately, by the following relationship: Schedule no. = 1,000 × P/SE , where P is operating pressure, lb/in² gage, and SE is allowable stress range multiplied by joint efficiency, lb/in².

EXAMPLE. Find the required schedule of ASTM A106 Grade B pipe operating at 1,150 lb/in² gage and 600°F.

Table 2 lists SE value as 15,000 lb/in². Substituting, 1,000 (1,150/15,000) = 76.6. Use schedule no. 80, tentatively, but check with Eq. (1), below.

Commercial sizes of wrought-iron and steel pipe are known by their nominal inside diameter (ID) from ½ (0.3175 cm) to 12 in (30.5 cm). Above 12 in ID, pipe is usually known by its outside diameter (OD). All classes of pipe of a given nominal size have the same OD, the extra thickness for different weights being on the inside.

Thickness of Pipe The following notes, covering power piping systems, have been abstracted from Part 2 of the Code for Power Piping (ANSI B31.1-1967).

For inspection purposes, the minimum thickness of pipe wall to be used for piping at different pressures and for temperatures not exceeding those for the various materials listed in Tables 1 and 2 shall be determined by the formula

$$t_m = \frac{PD}{2(SE + Py)} - A \quad (1)$$

where t_m = minimum pipe-wall thickness, in, allowable on inspection; P = maximum internal service pressure, lb/in² gage (plus water-hammer allowance in case of cast-iron conveying liquids); D = OD of pipe, in; SE = maximum allowable stress in material due to internal pressure and joint efficiency, at the design temperature, lb/in²; values of SE given in Tables 1 and 2 include allowance for joint efficiency; y = a coefficient, values for which are listed in Table 4; A = allowance for threading, mechanical strength, and corrosion, in, with values of A listed in Table 5.

The thickness of cast-iron pipe conveying liquid may be taken from Table 14, using the pressure class next higher than the maximum internal service pressure in pounds per square inch. Where cast-iron pipe is used for steam service, the thickness should be calculated by Eq. (1), using SE values listed in Table 1.

Plain-end pipe includes pipe joined by flared compression couplings, lapped joints, and by welding, i.e., by any method that does not reduce the wall thickness of the pipe at the joint.

Physical and Chemical Properties of Pipes, Tubes, Etc. The design of piping for operation above 750°F (399°C) presents many problems not encountered at lower temperatures.

Table 2. Allowable Stress Values for Temperatures 650 to 1200°F (343.4 to 649°C) (Continued)

ASTM spec. No.	Grade	Nominally composition			Spec. min tensile	Longitudinal joint efficiency factor	P No. ^a	650°F	700	Max allowable stress value, lb/in ² , for metal to				
		750	800	850						900	950	1,000		
Automatically welded austenitic steel, A312	TP304H	18Cr-8Ni ^b	75,000	0.85	8	12,050			12,000	11,900	11,750	11,550	11,400	10,600
	TP304H	18Cr-8Ni ^b -Mo ^c	75,000	0.85	8	8,900			8,850	8,700	8,650	8,500	8,350	8,0
	TP316L	18Cr-12Ni-Mo ^c	75,000	0.85	8	13,600			13,450	13,200	12,950	12,600	12,350	11,90
	TP316L	18Cr-12Ni-Mo ^c	75,000	0.85	8	9,600			9,350	9,200	9,000	8,750	8,600	8,3
	TP321H	18Cr-10Ni-1 ^c	75,000	0.85	8	12,850			12,850	12,750	12,650	12,600	12,35	
	TP321H	18Cr-10Ni-1 ^c	75,000	0.85	8	10,350			10,200	9,850	9,600	9,300	9,3	
Seamless A53 carbon steel	A ^d		48,000	1.00	1	12,000	11,650			10,700	9,000			
	B ^e		60,000	1.00	1	15,000	14,350			12,950	10,800			
A106 carbon steel	A ^d		48,000	1.00	1	12,000	11,650			10,700	9,000			
	B ^e		60,000	1.00	1	15,000	14,350			12,950	10,800			
	C ^f		70,000	1.00	1	17,500	16,600			14,750	12,000			

^aThe stress values tabulated include a longitudinal joint efficiency factor where applicable.

The stress values in this table may be interpolated to determine values for intermediate temperatures. The stress values in this table are not tabulated for such materials listed in Table 126 of the ANSI Standard for which allowable stresses are not tabulated may be used. Allowable stresses for such materials shall be taken from Sections V and VIII of the ASME Boiler and Pressure Vessel Code.

^bThe grouping of materials as to P -number classification is made on the basis of hardenability characteristics. The P numbers indicated in this table are identical to those adopted by the ASME Boiler and Pressure Vessel Code. Qualification of welding procedures, welders, and welding operators is required and should comply with the ASME Boiler and Pressure Vessel Code Section IV except as modified by Par. 172.5. The severities and grades of material tabulated should not be used at temperatures in excess of the maximum temperatures for which the allowable stress values are indicated.

^cFor stress values below 650°F which are not tabulated in Table 1, refer to Section I, Table I-1 of the ASME Boiler and Pressure Vessel Code.

^dUpon prolonged exposure to temperatures above about 775°F, the carbide phase of carbon-molybdenum steel may be converted to graphite.

^eUpon prolonged exposure to temperatures above about 875°F, the carbide phase of carbon-molybdenum steel may be converted to graphite. The values tabulated apply to fireclay quality material.

^fAt temperatures over 1000°F these stress values apply only when the carbon is 0.04 percent or higher. At temperatures over 1000°F these stress values apply only when the carbon is 0.04 percent or higher. These stress and thicknesses, the indicated allowable stresses should be reduced by the ratio of 70 divided by 75.

^gFor allowable stress values below 700°F, see Table 1.

^hThe values tabulated apply to fireclay quality material.

ⁱBecause of the relatively low yield strength of these materials, three higher stress values were established at temperatures where the short-time tensile properties govern to permit the use of these alloys here slightly greater deformation is acceptable. The stress values in this range exceed 62% percent but do not exceed 90 percent of the yield strength at temperature. Use of these stresses may result in dimensional changes due to permanent strain. These stress values are not recommended for the flanges of gasketed joints or other applications where tight amounts of distortion can cause leakage or malfunction.

For the properties of steel applicable to high-temperature service (as well as to ordinary service) for pipes, tubes, fittings, bolting material, etc., see Sec. 6. For a discussion of creep properties, see Sec. 5.

Piping of thickness designed in accordance with Eq. (1) may be used for any combination of pressure and temperature for which SE values are listed in Tables 1 and 2. The following summarizes piping-industry practice.

Steam Pressures above 250 (5224 N/m²) and not above 2,500 lb/in² (92,337 N/m²) Temperatures not above 110°F (59.3°C). For pressures in excess of 100 lb/in² (3,690 N/m²), the pipe may be seamless steel (A106), (A312), (A335), or (A376); or electric-fusion-welded steel (A155); or forged-and-lathed steel (A369); or automatic-welded steel (A312). For pressures between 250 and 600 lb/in² (9,224 N/m²) and 22,135 N/m²) the pipe may be seamless steel (A106) or (A33); electric-fusion-welded steel (A155); electric-resistance-welded steel (A135) or (A53). For pressures of 250 lb/in² (9,224 N/m²) and lower and for service up to 750°F (399°C), any of the following may be used: electric-fusion-welded steel (A144) or (A139); electric-resis-

wal fusion-welded steel (A134 or A139); electric-resistance-welded steel (A135); seamless or welded steel (A53), or wrought iron (A72). Copper and brass may be used if the temperature does not exceed 400°F. Cast iron may also be used. For close coiling and cold bending, Grade A seamless steel (A53); or Grade A electric-welded steel (A135), or (A139) is suitable. Pipe permissible for this service may be used for temperatures above 450°F (232°C) if the proper SE is used in calculating the pipe-wall thickness.

Valves below 3 in may have inside stem screws. Stop valves are of cast iron, malleable iron, steel, bronze, brass, or Monel.

Flanged-steel fittings must conform to the 300 lb ANSI Standard B16.5, if of cast iron, to the 250 lb ANSI Standard B16.2; or, for screwed fittings, to the ANSI Standard B16.4. Malleable-iron screwed fittings must conform to the 300 lb MSS SP-31 specifications, except that the 150 lb ANSI Standard B16.3 may be used for pressures not greater than 150 lb. Welded fittings may be used.

Steam Pressures from 25 to 125 lb/in², Temperatures not above 450°F Pipe may be of steel, wrought iron, cast iron, copper, or brass; valve bodies of cast iron, malleable iron, steel, or brass. Fittings are of 125 lb or 150 lb American Standard cast iron with screwed or flanged ends, or of malleable iron with screwed ends.

Steam Pressures 25 lb/in² and less, Temperature up to 1250°F Pipe may be of steel, wrought iron, spiral-riveted steel, brass, copper, or cast iron. Flanged fittings conform to the 25 lb ANSI Standard B16.2. Screwed fittings are of the 125 lb ANSI Standard B16.4 or of the 150 lb ANSI Standard B16.3 for cast iron or malleable iron, respectively, or the B16.15 for bronze. Welded fittings may be used.

Pipe coils are made from any of the commercial sizes of iron, steel, brass, and copper pipe and tubing. Limiting center-to-center dimensions, to which pipe coils can be fabricated in sizes $\frac{3}{4}$ to 2 in, are given in Table 10. Steel tubing cannot be bent to the absolute limits of brass or copper.

Seamless mechanical tubing is obtainable in outside diameters ranging from $\frac{1}{4}$ to $10\frac{3}{4}$ in wall thickness from 20 gage to 2 in (0.091 to 5.08 cm), and in standard pipe weights and

Table 1. Allowable Stress Values for Temperatures up to 650°F (343.4°C)
 (ANSI B36.1.0—1967)

ASTM spec. No.	Grade	Nominal composition	Spec. min tensile	Joint efficiency factor	P. No. ^a	Max allowable stress value, lb/in ² , for metal temperatures not exceeding °F*						
						-20 to 100	200	300	400 ^c	450	500	600
Pipe:												
Welded carbon steel, butt-welded A120, Lap-welded A120,	TP304H ^b	18Cr-8Ni	75,000	0.85	8	15,950	14,050	13,200	12,700	12,350	12,200	12,150
Automatically welded austenitic steel, A312	TP304H ^b	18Cr-8Ni	75,000	0.85	8	15,950	14,650	14,350	13,850	13,600	9,700	9,050
	TP316H ^b	18Cr-12Ni-Mo	75,000	0.85	8	15,950	13,700	12,400	11,450	10,700	13,600	13,600
	TP316LH ^b	18Cr-12Ni-Mo	75,000	0.85	8	15,950	14,300	13,450	13,100	12,850	12,850	9,850
	TP316L ^b	18Cr-10Ni-1Ti	75,000	0.85	8	15,950	14,050	13,000	12,300	11,450	10,900	10,600
	TP321H ^b	18Cr-10Ni-1Ti	75,000	0.85	8	15,950	14,050	13,000	12,300	11,450	10,900	10,600
Electric-fusion-welded austenitic steel:												
A358 Class I ^d	TP304	18Cr-8Ni	75,000	1.00	8	18,750	16,550	15,550	14,950	14,550	10,800	10,650
Class II ^d	TP304	18Cr-8Ni	75,000	1.00	8	18,750	16,000	13,750	12,250	11,400	12,900	12,900
Class III ^d	TP304	18Cr-8Ni	75,000	0.90	8	16,900	14,900	14,000	13,450	10,250	9,700	9,600
Class IV ^d	TP304	18Cr-8Ni	75,000	0.90	8	16,900	14,400	12,400	11,000	16,000	16,000	16,000
Class V ^d	TP316	18Cr-12Ni-Mo	75,000	1.00	8	18,750	17,500	16,900	16,100	12,600	11,900	11,600
Class VI ^d	TP316	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,100	14,600	13,300	14,400	14,400	14,400
Class VII ^d	TP316	18Cr-12Ni-Mo	75,000	0.90	8	16,900	15,750	15,200	14,700	10,700	10,450	10,450
Class VIII ^d	TP316	18Cr-12Ni-Mo	75,000	0.90	8	16,900	14,500	13,150	12,150	15,100	15,100	15,100
Class IX ^d	TP316	18Cr-12Ni-Mo	75,000	0.90	8	16,900	14,800	13,850	13,500	12,800	12,800	12,800
Class X ^d	TP321	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,550	15,550	14,400	13,600	13,600	13,600
Class XI ^d	TP321	18Cr-10Ni-1Ti	75,000	0.90	8	16,900	15,100	14,250	13,900	12,150	11,500	11,500
Class XII ^d	TP321	18Cr-10Ni-1Ti	75,000	0.90	8	16,900	13,750	13,000	12,150	11,500	11,500	11,500
Seamless:												
A120 carbon steel	P5	SCr-14Mo	60,000	1.00	5	10,800	10,600	10,200	9,800	9,600	14,500	14,000
A335 ferritic alloy ^e	P5b	SCr-14Ni-5Si	60,000	1.00	5	15,000	15,000	15,000	15,000	14,500	14,000	13,700
A369 ferritic alloy ^e	P5	SCr-9Mo	60,000	1.00	5	18,000	18,000	15,000	15,000	14,500	14,000	13,700
A312 Austenitic ^e	TP304H	18Cr-8Ni	75,000	1.00	8	18,750	16,550	15,550	14,950	11,400	10,800	10,650
Austenitic ^e	TP304H	18Cr-8Ni	75,000	1.00	8	18,750	16,000	13,750	12,250	16,000	16,000	16,000
Austenitic ^e	TP316H	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,900	16,900	16,300	12,600	11,900	11,600
Austenitic ^e	TP316H	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,100	14,600	13,500	15,100	15,100	15,100
Austenitic ^e	TP316LH	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,800	15,850	15,400	13,500	12,800	12,500
Austenitic ^e	TP316LH	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,550	15,550	14,950	14,500	14,350	14,300
Austenitic ^e	TP316LH	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,550	15,550	14,950	11,400	10,800	10,650
Austenitic ^e	TP321H	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,000	13,750	12,250	16,000	16,000	16,000
Austenitic ^e	TP321H	18Cr-8Ni	75,000	1.00	8	18,750	17,500	15,450	13,750	12,250	11,900	11,600
A376 Austenitic ^e	TP304H	18Cr-8Ni	75,000	1.00	8	18,750	16,900	16,900	16,300	12,600	11,900	11,600
Austenitic ^e	TP316H	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,100	14,600	13,500	15,100	15,100	15,100
Austenitic ^e	TP316LH	18Cr-12Ni-Mo	75,000	1.00	8	18,750	16,800	15,850	15,400	13,500	12,800	12,500
Austenitic ^e	TP316LH	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,550	15,550	14,950	13,500	13,350	13,300
Austenitic ^e	TP321H	18Cr-10Ni-1Ti	75,000	1.00	8	18,750	16,550	15,550	14,950	11,400	10,800	10,650
A430 Austenitic ^e	FP304H	18Cr-8Ni	70,000	1.00	8	17,500	17,500	15,450	13,750	12,250	14,950	14,950
Austenitic ^e	FP316H	18Cr-12Ni-Mo	70,000	1.00	8	17,500	16,100	14,600	13,500	12,600	11,900	11,600
Austenitic ^e	FP316H	18Cr-12Ni-Mo	70,000	1.00	8	17,500	16,800	15,400	14,350	13,500	12,800	12,500
Austenitic ^e	FP316H	18Cr-10Ni-1Ti	70,000	1.00	8	17,500	15,700	14,300	14,350	13,500	12,800	12,500
Austenitic ^e	FP321H	18Cr-10Ni-1Ti	70,000	1.00	8	17,500	15,700	14,300	14,350	13,500	12,800	12,500

**PROBABLE
COST
DEVELOPMENT**

COST ESTIMATE ANALYSIS

INVITATION / CONTRACT NO.

EFFECTIVE PRICING DATE
11-14-95

PROJECT Housing App Area B Niz River Area

LOCATION Kuwait City, Kuwait

CODE A CODE B CODE C

DRAWING NO.
 OTHER

ESTIMATOR PDC

SHT OF

CHECKED BY

TASK DESCRIPTION	QUANTITY	LABOR			EQUIPMENT			MATERIAL			TOTAL			SHIPPING	
		No. of Units	Unit Meas	MH Unit	Total Hrs	Unit Price	Cost	Unit Price	Cost	Unit Price	Cost	Unit	Total WT	Unit WT	Total WT
ECO No. 1															
<u>5" SCA PIPING:</u>															
4" SCH. 40 UNDER.	250	L.F.		16.55	4138	1.28		320	31	7750	12208				
3" SCH. 40 UNDER.	250	L.F.		17.65	4113	1.28		320	19.50	4875	9608				
4" SCH. 40	150	L.F.		11.75	1755	1.40		310	1.65	1590	3555				
2" SCH. 40	150	L.F.		7.75	1163	84		129	5.50	837	2129				
P.P.S INSUL.	300	L.F.			2000					1000	3000				
TURBINE MHS COST	1	L.F.			1000					1000	20000				
1500#HR STN. SURF. CHNGS. 1	50	L.F.		1000	2500					3000	42500				
COND. Piping	1	L.F.			3000					1500	1800				
8" CONDENS. W.R. TUNING	300	L.F.		23	6900	1.81	543	31	—	9300	16743				
Pipe Fittings & Misc.	1	L.F.			1000		—		—	25000	35000				
					50669					4032	91852	146543			

COST ESTIMATE ANALYSIS

LOCATION	PROJECT	INVITATION NO./CONTRACT NO.	EFFECTIVE PRICING DATE	DATE PREP.	COST ESTIMATE ANALYSIS					
					CODE A		CODE B		CODE C	
					<input type="checkbox"/> OTHER	<input type="checkbox"/> DRAWING NO.	<input type="checkbox"/> SHT OF	<input type="checkbox"/> ESTIMATOR PDL	CHECKED BY	
TASK DESCRIPTION	QUANTITY	LABOR	EQUIPMENT	MATERIAL	TOTAL	SHIPPING				
NO. of Units	Unit Meas	MH Unit	Total Hrs	Unit Price	Unit Cost	Unit Price	Unit Cost	Unit Cost	Unit WT	Total WT
STEEL KNEE FORM										
8' x 8' SCH. 40 LINSCH. CF	250		17.62	4350	125	320	33.50	837.5	1304.5	
3" x 8" SCH. 40 LINSCH. CF	250		17.65	4413	125	320	19.50	487.5	960.8	
5' x 8' SCH. 40 QHS HANS.	150		12.5	3430	181	272	51	4650	837.2	
2" x 8" SCH. 40 QHS HANS.	150		17.25	1163	81	129	5.50	837	2129	
Pipe 11506	1	LGT		2500				1200	3700	
Bracing Pipe:										
2 1/2" x 5 SCH. 40 CF	200		9.20	1840	112	224	640	1280	3344	
Pipe insur.	1	LGT		1000				1000	3000	
Hot Tarp Paint (4 bushels)	1	ea								
65 GPM Pump	1	ea		300				3438	3738'	
No. Brkt Syst	1	ea						216	1375	1591
								250	1000	1250
Unfired Br. Valve	1	ea		5000		2500		75000	82500	
All Acces. & Fixtes	1	LOT		30000				40000	60000	
				15182				15182	311030	192277
TOTAL THIS SHEET										

COST ESTIMATE ANALYSIS

PROJECT			INVITATION NO./CONTRACT NO.			EFFECTIVE PRICING DATE		DATE PREPARED			
LOCATION			<input type="checkbox"/> CODE A <input type="checkbox"/> CODE B <input type="checkbox"/> CODE C		DRAWING NO.	SHT OF					
			<input type="checkbox"/> OTHER		ESTIMATOR	CHECKED BY					
TASK DESCRIPTION	QUANTITY	LABOR	EQUIPMENT	MATERIAL	TOTAL	SHIPPING					
LCC NO. 3											
FBRG. CINE. TIN. PK.		No. of Unit Meas	MH Unit	Total Hrs	Unit Price	Unit Cost	Unit Price	Cost	Total Wt		
GCRN PIV IND. DR.	1 EA				1500	1000		12000	14500		
PICKUP & PARK	1 LOT				3500			7200	10700		
DELIVER	1 LS				3000			5000	8200		
STATIONARIES	LS				5000			1000	6000		
					—			—	—		
					18000	1000		25200	39200		
TOTAL THIS SHEET											

COST ESTIMATE ANALYSIS		INVITATION NO./CONTRACT NO.		EFFECTIVE PRICING DATE		DATE PREPARED	
PROJECT Houston APP AREA B NITRIC Acid		<input type="checkbox"/> CODE A <input type="checkbox"/> CODE B <input type="checkbox"/> CODE C		DRAWING NO.		SHT OF	
LOCATION Kingsport Tenn		<input type="checkbox"/> OTHER		ESTIMATOR PDL		CHECKED BY	
TASK DESCRIPTION	QUANTITY	LABOR	EQUIPMENT	MATERIAL	TOTAL	SHIPPING	
	No. of Units	Unit Meas	MH Unit	Total Hrs	Unit Price	Unit Cost	Unit Cost
Insulation ECO #4							
1" Calcium Silicate:							
18" ϕ AIR PRINTER.	12	LF	5 ⁴⁰	6480	9 ³⁵	112 ²⁰	177 -
18" ϕ TAIL GAS HTR.	25	LF	5 ⁴⁰	135 -	9 ³⁵	2.33 ²⁵	368 ²⁵
8" ϕ TUES. PPS TO TUES.	120	LF	3 ⁸⁹	460 ⁸²	4 ²⁶	511 ²⁰	972 -
0.010 S.S. JACKETS:							
18" ϕ AIR PRINTER	60	SF	4 ⁰³	241 ⁸⁰	9 ³	55 ⁸⁰	297 ⁶⁰
18" ϕ TAIL GAS HTR.	125	SF	4 ⁰³	503 ⁷⁵	9 ³	116 ²⁵	620 -
8" ϕ TUES. PPS TO TUES.	315	SF	4 ⁰³	1269 ⁹⁵	9 ³	292 ⁹⁵	1562 ⁹⁰
18" ϕ FANGS SETS (new)	10	SF	13 ⁴⁵	134 ⁵⁰	2 ⁷¹	27 ¹⁰	161 ⁶⁰
18" ϕ FR. SETS (JACKETS)	10	SF	4 ⁰³	40 ³⁰	9 ³	9 ³⁰	49 ⁶⁰
Subtotal				2850 ⁴⁰		1358 ⁵⁵	4208 ⁹⁵
15% Conting.							631 ³⁵
Total Const. - UST							4850 -
							1
TOTAL THIS SHEET							

AFFILIATED ENGINEERS SE, INC. 3300 SW Archer Road Gainesville, Florida 32608 (904) 376-5500 FAX (904) 375-3479	Made By: PDL	Date: 12-22-95	Job No: 95094-00
	Checked By:	Date:	Sheet No: ____ of ____

Calculations For:

ECO #7 COSTS

ASSUMPTIONS

- ① COST OF ST. STEL. FABRICATION IS PROPORTIONAL TO PUBLISHED COST MULTIPLIER FOR 90° PIPE ELBOW FROM MEANS:

SCH. 40 12"Φ 316 SS 90° ELBOW - #1720 MATERIAL

SCH. 40 12"Φ BL. IRON 90° ELBOW - #212 MATERIAL

$$\text{MULTIPLIER} = \frac{1720}{212} = 8.1$$

- ② PUMP AND ACCUMULATOR SKIDS AND BACK PRESSURE REGULATOR INCLUDED IN CLAYTON QUOTATION WILL SERVE BOTH GENERATORS

- ③ STANDARD GENERATOR COST IS 1/3 OF TOTAL QUOTED COST.

ADDO'D COST FOR ST. STEL. GENERATOR WHICH CLAYTON DECLINED TO QUOTE:

$$\text{Cost} = \frac{\$68600}{3} (8.1) = \$185522$$

Clayton INDUSTRIES

P.O. BOX 5530, EL MONTE, CALIFORNIA 91734-1530

QUOTATION No. G-11623

TEL (818) 443-9381 FAX (818) 442-1701

TO: Affiliated Engineers SE, Inc.
3300 SW Archer Road
Gainesville, Florida 32608-1731

TERMS: 20% with Order-Balance Net 30
Subject to Credit Approval

ATTN: Paul Little
(904) 376-5500 -TEL
(904) 375-3479 -FAX

FOB: El Monte, CA - Prepay and Add
APPROX. SHIP DATE: 120 Days
AFTER RECEIPT AND ACCEPTANCE OF ORDER

RE: Clayton Steam Generator


QUANT.	MODEL AND SPECIFICATIONS	UNIT PRICE	TOTAL												
1	<p><u>EGSG-5EC0201 Exhaust Gas Steam Generator</u> Mono-coil, smooth tube, single pass Steam Generator Designed to maintain feedwater inlet temperature to prevent dewpoint corrosion while maintaining High efficiency.</p> <p><u>Conditions</u></p> <table> <tbody> <tr> <td>Gas Flow:</td> <td>20,000 lb/h</td> </tr> <tr> <td>T gas in:</td> <td>495 °F</td> </tr> <tr> <td>T gas out:</td> <td>266 °F</td> </tr> <tr> <td>Gas Press Drop:</td> <td>17.4 inW.C.</td> </tr> <tr> <td>Steam Flow:</td> <td>1,180 pph</td> </tr> <tr> <td>Steam Press:</td> <td>80 psig</td> </tr> </tbody> </table>	Gas Flow:	20,000 lb/h	T gas in:	495 °F	T gas out:	266 °F	Gas Press Drop:	17.4 inW.C.	Steam Flow:	1,180 pph	Steam Press:	80 psig		
Gas Flow:	20,000 lb/h														
T gas in:	495 °F														
T gas out:	266 °F														
Gas Press Drop:	17.4 inW.C.														
Steam Flow:	1,180 pph														
Steam Press:	80 psig														
1	<p><u>Bottom Inlet/Top Outlet Cones</u> Provide transition pieces from 32 inch O.D. exhaust stack to the EGSG. Includes Soot Blower Ring on Inlet Side.</p>														
1	<p><u>Pump & Accumulator Skids</u> Includes the following items mounted on a skid: 1 Feed Pump & Electric Motor Accumulator with Level Control & Pressure Gauge Control Box Including Starter for Clayton Pump Safety Valve(s) Overflow Steam Trap Necessary piping and wiring within skid boundary</p>														
1	<p><u>Back Pressure Regulator.</u> For stabilizing steam system during load fluctuation and operation start-up.</p>														
<p>TOTAL: HEAT RECOVERY SYSTEM</p> <p>NOTE: Freight, Sales Tax, and other fees may apply.</p>			\$68,610												

THIS QUOTATION EXPIRES in 30 Days AND IS SUBJECT TO THE TERMS AND CONDITIONS ON THE FACE AND THE REVERSE SIDE HEREOF. PARAGRAPH 17 OF SUCH TERMS AND CONDITIONS LIMITS ACCEPTANCE OF THIS QUOTATION TO THE TERMS CONTAINED HEREIN, EXCLUDES ANY ADDITIONAL TERMS PROPOSED BY PURCHASER, AND PROVIDES THAT ANY ORDER BY PURCHASER BASED ON THIS QUOTATION (OR ACCEPTANCE BY PURCHASER OF THE GOODS DESCRIBED HEREIN) SHALL CONSTITUTE AN UNCONDITIONAL ACCEPTANCE BY PURCHASER OF EACH AND ALL OF THE TERMS AND CONDITIONS CONTAINED HEREIN, AND A WAIVER BY PURCHASER OF ANY CONFLICTING OR ADDITIONAL PROVISIONS CONTAINED IN ANY OF PURCHASER'S DOCUMENTS RELATING TO THIS TRANSACTION.

ACCEPTANCE

THIS QUOTATION IS ACCEPTED

SUBMITTED BY


 Nick LeJeune - Sales Engineer - 12/22/95

G.M.

COMPANY

BY

NAME _____ TITLE _____ DATE _____

SIGNATURE _____ TITLE _____ DATE _____

STEAM GENERATORS EXHAUST GAS & WATER HEATERS

FROM: Clayton Sales TO: 904 375 3479 DECEMBER 22, 1995 8:14AM #447 P.01

Telephone Conversation



Affiliated Engineers SE, Inc.
3300 SW Archer Road
Gainesville, FL 32608

NICK LO-JOGNO

Conversation With

CLAYTON

Representing

HOLSTON AAP NITRIC ACID FAC.

Project Name

KINGSPORT, TENN.

Location

Routing

95094-00

Project Number

12-22-95


Date

Time

FAXED ONE PAGE QUOTE.

CLAYTON DECLINED TO QUOTE THE
STAINLESS STEEL SECTION BECAUSE OF THE
NITRIC ACID FUMES.

By:



Affiliated Engineers SE, Inc.
3300 SW Archer Road
Gainesville, Florida 32608-1731

FAXED

(904)376-5500 - Office
(904)375-3479 - Fax

FAX TRANSMISSION COVER SHEET

TO:	NICK LO JUANO <small>1F-907-2200</small>	FAX #:	770 907-0548
COMPANY:	CLAYTON INDUSTRIES	PROJECT #:	95094-00
FROM:	PAUL LITCO	PAGES:	3 <small>(incl cover sheet)</small>
DATE/TIME:	12-11-95	Hard Copy to Follow:	No
REMARKS: <u>DESIRE BUDGET PRICING &</u> <u>NOMINAL PERFORMANCE THAT MIGHT</u> <u>BE EXPECTED. I ANTICIPATE EACH</u> <u>UNIT WILL PRODUCE IN EXCESS OF</u> <u>1000#/HR SATURATED STEAM.</u>			

**CLAYTON INDUSTRIES
HEAT RECOVERY SYSTEM
FACT SHEET FOR QUOTATION**

(Designed for initial proposal only to establish
size and budget estimate for basic equipment)

DATE 12-11-95

COMPANY: A B S E

ADDRESS: GAINSVILLE, FL

NAME OF CONTACT: PAUL LITTCO

PRODUCT GAS UNIT

Gas Flow Mass Units 17650

Standard Volume Units (at 75°F or 24°C)

Gas Inlet Temperature

Steam Pressure

Receiver (Feedwater) Temp. (usually 200°F or 93°C)

OPTION* 1. Gas Outlet Temperature

2. Total Heat Transfer

3. Steam Mass Flow Rate

*(Indicate "maximum available" if unknown)

allowable Gas Pressure Drop

Circle appropriate units of measure

17650 (lbs/hr or Kg/hr)

(SCFM or SM³/hr)

350 (F or C)

80 (Psi or bar)

150 (F or C)

(Btu/hr or Kcal/hr)

(lbs/hr or k/hr)

27 (In W.C. or mm - N.C.)

DEW POINT = 255°F $C_p = 0.253 \frac{Btu}{lb \cdot ^\circ F}$

Waste Gas Properties: Percent by Volume: N_2 - 71.3; NO_x - 11.5%; H_2O - 16.4%

Source of Waste Gas (incinerator, oven, turbine, engine, etc.): Chemical Process

Source of Fuel (gas, diesel oil, commercial waste, etc.): NA

Specific Gravity¹ _____ Temp. _____ Specific Heat² _____ Temp. _____

Indicate utilization factor, (8 hours/day, 5 days/week; or 24 hrs/day,

Continuous; standby only, etc.): 24 HRS/DAY

Equipment estimate at job site (size and number of sections): _____

Equipment selection Clayton Engineering: _____

REQUIRES 400 SERIES
STAINLESS STEEL GAS
SIDE CONSTRUCTION. CONDENS-
ATION IS DESIRABLE - NITRIC
ACID WILL BE THE RESULT.

¹Will use the following figures if not available: 1.0 @ 70°F.

²Will use the following figures if not available: .25 @ 800°F.

**CLAYTON INDUSTRIES
HEAT RECOVERY SYSTEM
FACT SHEET FOR QUOTATION**

(Designed for initial proposal only to establish
size and budget estimate for basic equipment)

DATE 12-11-85

COMPANY: AESB
ADDRESS: GAINESVILLE, FL.

NAME OF CONTACT: PAUL LITTCUT

TURBINE EXHAUST UNIT

Gas Flow Mass Units 20000 #/HR

Standard Volume Units (at 75°F or 24°C)

Gas Inlet Temperature 495°F

Steam Pressure 80 PSIG

Receiver (Feedwater) Temp. (usually 200°F or 93°C)

OPTION* 1. Gas Outlet Temperature

2. Total Heat Transfer

3. Steam Mass Flow Rate

*(Indicate "maximum available" if unknown)

wable Gas Pressure Drop

Circle appropriate units of measure

20000 (lbs/hr or Kg/hr)

 (SCFM or SM³/hr)

495 (F or C)

80 (PSI or bar)

150 (F or C)

 (F or C)

 (Btu/hr or Kcal/hr)

 (lbs/hr or k/hr)

27 (In W.C. or mm -

N.C.)

Waste Gas Properties: Percent by Volume: N₂ - 80.2; NO - 4.9%; H₂O - 13.9%

Source of Waste Gas (Incinerator, oven, turbine, engine, etc.): CP = 0.263 B/#°F

Source of Fuel (gas, diesel oil, commercial waste, etc.): N.A.

Specific Gravity¹ _____ Temp. _____ Specific Heat² _____ Temp. _____

Indicate utilization factor, (8 hours/day, 5 days/week; or 24 hrs/day,

Continuous; standby only, etc.): 24 HR/DAY

Equipment estimate at job site (size and number of sections): _____

Equipment selection Clayton Engineering: _____

¹Will use the following figures if not available: 1.0 @ 70°F.

²Will use the following figures if not available: 25 @ 800°F.

**ENERGY
RATE
SOURCE
MATERIAL**

J. Bouchillon, PE

3/95

(Bldg. P. C. L. W.)
J. Bouchillon
7/1/95
PE

1994 OUT-OF-POCKET COST FOR STEAM, B-200

GIVEN: 1994 AREA B MONTHLY USAGE & PROD. REPORT, BY KEN HARRIS

SUM of individual boilers' steam output = 1,324,620,000 lbs

Building Steam Output = Sum - internal consumption (turbines, DA, etc)
16.4% (EEAP study, EMC Engineers, 1992, p. C-4)

$$= 1,324,620,000 \times .836 = 1,107,382,000 \text{ lbs}$$
$$= 1,107 \text{ m Btu}$$

Steam Coal, 1994 = 64,673 tons
Btu content of coal = 64,673 tons $\times 2000 \times 14,100 \frac{\text{Btu}}{\text{lb}}$
= 1,824 m m Btu

Cost of treatment of Sulfuric System backwash water =
Utilities Cost Report
 $50 \text{ gpm ave} \times 60 \frac{\text{min}}{\text{hr}} \times 8760 \times \frac{\$.239}{1000gal} = \$ 6,500/\text{yr.}$

COST of Filter Water for feed water =
Utilities Cost Report
 $\frac{1,324,620,000 \text{ lbs} \times 0.148}{8 \text{ lbs water}} = \$ 24,500/\text{yr}$

cost of electricity (motors, precipitators, etc) =
cost str 2235 for mar 95 elec bill
 $412,000 \frac{\text{kwh}}{\text{mo.}} \times .035 \frac{\$}{\text{kwh}} \times 12 \text{ mo} = \$ 173,000/\text{yr}$

Cost of fly ash disposal = 15,000 est

Cost of cinder removal = 10,000 est

[Cost of bldg. maintenance = \$ 343,391 routine + \$ 529,108 major = \$ 922,465]

COST of water treatment chemicals (See Osmosis Study 1993) \$ 91,000

Out of Pocket Steam Cost = Coal + electricity + chemicals + FW + water softening + waste water disposal + disposal of fly ash + crud

OPSC = $\frac{(\text{Per Defense fuels, Geo. Tiffsworths } 1/95) + (\$ 2.91 \text{ million}) + (\text{bldg steam output})}{1,107,382,000 \text{ lbs}}$

$$= \frac{3.23 \text{ million}}{1,107} = \boxed{2.92 \frac{\$}{1000 \text{ lbs}}} \quad 3.75 \frac{\$}{\text{K lbs}} \text{ Counting maintenance}$$

Kingsport Power Company
PO BOX 117 KINGSPORT TN 37662

1-615-578-2200

Account Number

811112193143000314

HOLSTON ARMY AMM PLANT
POWER SUPPLY CONTR# OAAA19-70-C-0320
P.O. RX 749
KINGSPORT TN 37662

30111935300034 0140028750140028757

MARCH 1995

Please Return This Portion
With Your Payment

Meter Types	Codes
K - Kilowatt Hour	E - Estimated
D - KW Demand	G - Meter Change
A - KVA Demand	O - Off Peak
R - RKVAH	
V - KVAR Demand	

Gross Amount	Last Pay Date For Net Amount	Net Amount
--------------	---------------------------------	------------

\$40,028.75 APR 12 140,028.75

Account Number: (Please Use When You Call or Write)

1-111-93-13-00-3-4

Service Address

HOLSTON ARMY AMM PLANT
CONTR NO 19-70-C-0320
KINGSPORT TN

37662

Month MARCH 1995

Tariff

324 IP TRAN

Office KINGSPORT

From	To	Service	Motor Number	Previous Readings	Present Readings	Meter Constant	Metered Usage	Voltage Constant
C	C	K	34742	07389	07558	34000	4056000	
C	C	D	34742	04572	04637	34000	3326330	
C	C	V	34742		0454	34000	794400	
C	C	K	34742	0638	0638	34000	369600	
C	C	D	34742	0630	0640	34000	12000	
C	C	V	34742		065	34000	60000	
							15000	

Contract Capacity	10,000	RATE BILLING	154,111.36
Billing KVAR		FUEL ADJ	11,950.74 CCR
RKVAH	1,360,000	PROMPT PAYMENT DISCOUNT	13,133.43 CCR
		TOTAL AMOUNT DUE	140,028.75

Metered Demand	8,064.0
Power Factor	
Billing Demand	8,064.0
Metered KWH	4,056,000
Power Factor	
Constant	
Adjusted KWH	4,056,000
Voltage Adj. KWH	
Billing KWH	4,056,000

KINGS
POWER

**TARIFF I. P.
(Industrial Power)**

AVAILABILITY OF SERVICE

Available to industrial and large commercial customers. Customers shall contract for a definite amount of electrical capacity in KW which shall be sufficient to meet normal maximum requirements but in no case shall the capacity contracted for be less than 3,000 KW. Contract capacities will be specified in multiples of 100 KW.

MONTHLY RATE

Tariff <u>Code</u>	Service <u>Voltage</u>	Demand Charge <u>per KW</u>	Energy Charge <u>per KWH</u>	Service Charge
322	Primary	\$ 8.70	2.302 cents	\$ 240.00
323	Subtransmission	\$ 7.79	2.269 cents	\$ 730.00
324	Transmission	\$ 7.60	2.241 cents	\$1,930.00

HDC

HDC

Reactive Demand Charge for each KiloVar of Lagging Reactive Demand
in excess of 50 percent of the KW of monthly metered demand \$ 0.75 per KVAR

MINIMUM CHARGE

This tariff is subject to a minimum monthly charge equal to the sum of the service charge, the product of the demand charge and the monthly billing demand and the fuel clause adjustment.

FUEL CLAUSE

When the unit cost of fuel in the charges for power purchased from Appalachian Power Company under Federal Energy Regulatory Commission rate schedule No. 23 is above or below a base unit price of 15.8563 mills per KWH, adjusted for losses, the bill for service shall be increased or decreased respectively at a rate per KWH equal to the amount that such cost of fuel is above or below the unit base cost of 15.8563 mills per KWH, adjusted for losses, applied to the KWH measured in the period for which the bill is rendered. The adjustment shall be based on the most recent calendar month for which fuel cost data is available.

PROMPT PAYMENT DISCOUNT

A discount of 1.5 percent will be allowed if account is paid in full within 15 days of date of bill.

DETERMINATION OF DEMAND

The billing demand in KW shall be taken each month as the single highest 30-minute integrated peak in KW as registered during the month by a demand meter or indicator, or, at the Company's option, as the highest registration of a thermal type demand meter or indicator, but the monthly billing demand so established shall in no event be less than 60% of the greater of (a) the customer's contract capacity or (b) the customer's highest previously established monthly billing demand during the past 11 months nor less than 3,000 KW.

The reactive demand in KVARS shall be taken each month as the single highest 30-minute integrated peak in KVARS as registered during the month by a demand meter or indicator, or, at the Company's option, as the highest registration of a thermal type demand meter or indicator.

METERED VOLTAGE

The rates set forth in this tariff are based upon the delivery and measurement of energy at the same voltage, thus measurement will be made at or compensated to the delivery voltage. At the sole discretion of the Company, such compensation may be achieved through the use of loss compensating equipment, the use of formulas to calculate losses or the application of multipliers to the metered quantities. In such cases, the metered KWH and KW values will be adjusted for billing purposes. If the Company elects to adjust KWH and KW based on multipliers, the adjustments shall be in accordance with the following:

1. Measurements taken at the low-side of a customer-owned transformer will be multiplied by 1.01.
2. Measurements taken at the high-side of a Company-owned transformer will be multiplied by 0.98.

Issued: October 30, 1992

By: Michael J. Holzaepfel, President
Kingsport, Tennessee

Effective: November 3, 1992
Pursuant to an Order in
Docket Number 92-04425

**SCOPE
OF
WORK**



DEPARTMENT OF THE ARMY
MOBILE DISTRICT, CORPS OF ENGINEERS
P. O. BOX 2288
MOBILE, ALABAMA 36628-0001

April 4, 1995

REPLY TO
ATTENTION OF:

A-E Contracts
Section

Affiliated Engineers SE, Inc.
Mr Carl L. Osberg
3300 SW Archer Road
Gainesville, FL 32608-1731

Gentlemen:

We have a requirement for a Limited Energy Study for Area B Nitric Acid Production Facilities at Holston AAP, TN, in accordance with the enclosed Scope of Work and as will be further defined at the pre-study conference on April 26 at Holston. It is proposed that this work be accomplished by delivery order under Contract Number DACA01-94-D-0007.

You are requested to submit your proposal for accomplishing this work by May 10, 1995. Your proposal should be addressed as follows:

District Engineer
U. S. Army Engineer District, Mobile
Attention: CESAM-EN-MN/Mr. Dan Mizelle
Post Office Box 2288
Mobile, Alabama 36628-0001

You are cautioned that no services for which an additional cost or fee will be charged should be furnished without the prior written authorization of the Contracting Officer.

Please contact Mr. Roger D. Baer at 205/441-5493 if you have any questions concerning this matter.

Sincerely,
O. B. Anderson
O. B. Anderson
Authorized Representative
of the Contracting Officer

CESAM-EN-DM

1 February 1995
Revised 21 March 1995

SCOPE OF WORK

FOR A

LIMITED ENERGY STUDY

AREA B NITRIC ACID PRODUCTION FACILITIES

HOLSTON ARMY AMMUNITION PLANT, TENNESSEE

Performed as part of the
ENERGY ENGINEERING ANALYSIS PROGRAM (EEAP)

SCOPE OF WORK
FOR A
LIMITED ENERGY STUDY

AREA B NITRIC ACID PRODUCTION FACILITIES
HOLSTON ARMY AMMUNITION PLANT, TENNESSEE

TABLE OF CONTENTS

1. BRIEF DESCRIPTION OF WORK
2. GENERAL
3. PROJECT MANAGEMENT
4. SERVICES AND MATERIALS
5. PROJECT DOCUMENTATION
 - 5.1 ECIP Projects
 - 5.2 Non-ECIP Projects
 - 5.3 Nonfeasible ECOs
6. DETAILED SCOPE OF WORK
7. WORK TO BE ACCOMPLISHED
 - 7.1 Perform a Limited Site Survey
 - 7.2 Evaluate Selected ECOs
 - 7.3 Combine ECOs into Recommended Projects
 - 7.4 Submittals, Presentations and Reviews

ANNEXES

- A - DETAILED SCOPE OF WORK
- B - EXECUTIVE SUMMARY GUIDELINE
- C - REQUIRED DD FORM 1391 DATA

1. BRIEF DESCRIPTION OF WORK: The Architect-Engineer (AE) shall:

1.1 Perform a limited site survey of specific buildings or areas to collect all data required to evaluate the specific ECOs included in this study.

1.2 Evaluate specific ECOs to determine their energy savings potential and economic feasibility.

1.3 Provide project documentation for recommended ECOs as detailed herein.

1.4 Prepare a comprehensive report to document all work performed, the results and all recommendations.

2. GENERAL

2.1 This study is limited to the evaluation of the specific buildings, systems, or ECOs listed in Annex A, DETAILED SCOPE OF WORK.

2.2 The information and analysis outlined herein are considered to be minimum requirements for adequate performance of this study.

2.3 For the buildings, systems or ECOs listed in Annex A, all methods of energy conservation which are reasonable and practical shall be considered, including improvements of operational methods and procedures as well as the physical facilities. All energy conservation opportunities which produce energy or dollar savings shall be documented in this report. Any energy conservation opportunity considered infeasible shall also be documented in the report with reasons for elimination.

2.4 The study shall consider the use of all energy sources applicable to each building, system, or ECO.

2.5 The "Energy Conservation Investment Program (ECIP) Guidance", described in letter from DAIM-FDF-U, dated 10 Jan 1994 establishes criteria for ECIP projects and shall be used for performing the economic analyses of all ECOs and projects. The program, Life Cycle Cost In Design (LCCID), has been developed for performing life cycle cost calculations in accordance with ECIP guidelines and is referenced in the ECIP Guidance. If any program other than LCCID is proposed for life cycle cost analysis, it must use the mode of calculation specified in the ECIP Guidance. The output must be in the format of the ECIP LCCA summary sheet, and it must be submitted for approval to the Contracting Officer.

2.6 The following definitions apply to terms used in this scope of work:

2.6.1 "Contracting Officer", "Contracting Officer's Representative", or "Government's Representative" refer to the contracting office of the Mobile District, U. S. Army Corps of Engineers.

2.6.2 "Installation Commander", or "Installation Representative" refer to the military commander of Holston Army Ammunition Plant.

2.6.3 "Plant Manager", Operating Contractor", or "Operating Contractor's Representative" refer to the Holston Defense Corporation, which operates Holston Army Ammunition Plant under contract to the U. S. Army.

2.7 Energy conservation opportunities determined to be technically and economically feasible shall be developed into projects acceptable to installation personnel. This may involve combining similar ECOs into larger packages which will qualify for ECIP or O&M funding, and determining in coordination with installation personnel the appropriate packaging and implementation approach for all feasible ECOs.

2.7.1 Projects which qualify for ECIP funding shall be identified, separately listed, and prioritized by the Savings to Investment Ratio (SIR).

2.7.2 All feasible non-ECIP projects shall be ranked in order of highest to lowest SIR.

2.8 Metric Reporting Requirements: In this study, the analyses of the ECOs may be performed using English or Metric units as long as they are consistent throughout the report. The final results of energy savings for individual recommended projects and for the overall study will be reported in units of MegaBTU per year and in MegaWattHours per year. Paragraph 7.4.2 details requirements for the contents of the final submittal.

3. PROJECT MANAGEMENT

3.1 Project Managers. The AE shall designate a project manager to serve as a point of contact and liaison for work required under this contract. Upon award of this contract, the individual shall be immediately designated in writing. The AE's designated project manager shall be approved by the Contracting Officer prior to commencement of work. This designated individual shall be responsible for coordination of work required under this contract. The Contracting Officer will designate a project manager to serve as the Government's point of contact and liaison for all work required under this contract. This individual will be the Government's representative.

3.2 Installation Assistance.

3.2.1. The Installation Commander will designate an individual to coordinate between the AE and the Holston Defense Corporation. This individual will be the Installation Representative, and all correspondence with Holston Army Ammunition Plant will be addressed to his attention.

3.2.2. The Plant Manager will designate an individual to assist the AE in obtaining information and establishing contacts necessary to accomplish the work required under this contract. This individual will be the Operating Contractor's Representative.

3.3 Public Disclosures. The AE shall make no public announcements or disclosures relative to information contained or developed in this contract, except as authorized by the Contracting Officer.

3.4 Meetings. Meetings will be scheduled whenever requested by the AE or the Contracting Officer for the resolution of questions or problems encountered in the performance of the work. The AE's project manager and the Government's representative shall be required to attend and participate in all meetings pertinent to the work required under this contract as directed by the Contracting Officer. These meetings, if necessary, are in addition to the presentation and review conferences.

3.5 Site Visits, Inspections, and Investigations. The AE shall visit and inspect/investigate the site of the project as necessary and required during the preparation and accomplishment of the work.

3.6 Records

3.6.1 The AE shall provide a record of all significant conferences, meetings, discussions, verbal directions, telephone conversations, etc., with Government representative(s) relative to this contract in which the AE and/or designated representative(s) thereof participated. These records shall be dated and shall identify the contract number, delivery order number, participating personnel, subject discussed and conclusions reached. The AE shall forward to the Contracting Officer within ten calendar days, a reproducible copy of the records.

3.6.2 The AE shall provide a record of requests for and/or receipt of Government-furnished material, data, documents, information, etc., which if not furnished in a timely manner, would significantly impair the normal progression of the work under this contract. The records shall be dated and shall identify the contract number and modification number, if applicable. The AE shall forward to the Contracting Officer within ten calendar days, a reproducible copy of the record of request or receipt of material.

3.7 Interviews. The AE and the Government's representative shall conduct entry and exit interviews with the Plant Manager before starting work at the installation and after completion of the field work. The Government's representative shall schedule the interviews at least one week in advance.

3.7.1 Entry. The entry interview shall describe the intended procedures for the survey and shall be conducted prior to commencing work at the facility. As a minimum, the interview shall cover the following points:

- a. Schedules.
- b. Names of energy analysts who will be conducting the site survey.
- c. Proposed working hours.
- d. Support requirements from Holston Defense Corporation (HDC).

3.7.2 Exit. The exit interview shall briefly describe the items surveyed and probable areas of energy conservation. The interview shall also solicit input and advice from the Plant Manager.

4. SERVICES AND MATERIALS. All services, materials (except those specifically enumerated to be furnished by the Government), labor, supervision and travel necessary to perform the work and render the data required under this contract are included in the lump sum price of the contract.

5. PROJECT DOCUMENTATION. All energy conservation opportunities which the AE has considered shall be included in one of the following categories and presented in the report as such:

5.1 ECIP Projects. To qualify as an ECIP project, an ECO, or several ECOs which have been combined, must have a construction cost estimate greater than \$300,000, a Savings to Investment Ratio (SIR) greater than 1.25 and a simple payback period of less than ten years. The overall project and each discrete part of the project shall have an SIR greater than 1.25. All projects meeting the above criteria shall be arranged as specified in paragraph 2.7.1 and shall be provided with programming documentation. Programming documentation shall consist of a DD Form 1391 and life cycle cost analysis (LCCA) summary sheet(s) (with necessary backup data to verify the numbers presented). A life cycle cost analysis summary sheet shall be developed for each ECO and for the overall project when more than one ECO are combined. The energy savings for projects consisting of multiple ECOs must take into account the synergistic effects of the individual ECOs.

5.2 Non-ECIP Projects. Projects which do not meet ECIP criteria with regard to cost estimate or payback period, but which have an SIR greater than 1.25 shall be documented. Projects or ECOs in this category shall be arranged as specified in paragraph 2.7.2 and shall be provided with the following documentation: the life cycle cost analysis (LCCA) summary sheet completely filled out, a description of the work to be accomplished, backup data for the LCCA, ie, energy savings calculations and cost estimate(s), and the simple payback period. The energy savings for projects consisting of multiple ECOs must take into account the synergistic effects of the individual ECOs. In addition these projects shall have the necessary documentation prepared, as required by the Government's representative, for one of the following categories:

5.2.1. Federal Energy Management Program (FEMP) Projects. A FEMP (or O&M Energy) project is one that results in needed maintenance or repair to an existing facility, or replaces a failed or failing existing facility, and also results in energy savings. The criteria are similar to the criteria for ECIP projects, ie, SIR \geq 1.25, and simple payback period of less than ten years. Projects with a construction cost estimate up to \$1,000,000 shall be documented as outlined in par 5.2 above; projects over \$1,000,000 shall be documented on 1391s. In the FEMP program, a system may be defined as "failed or failing" if it is inefficient or technically obsolete. However, if this strategy is used to justify a proposed project, the equipment to be replaced must have been in use for at least three years.

5.2.2. Low Cost/No Cost Projects. These are projects which the Plant Manager can perform using his resources. Documentation shall be as required by the Plant Manager.

5.3 Nonfeasible ECOs. All ECOs which the AE has considered but which are not feasible, shall be documented in the report with reasons and justifications showing why they were rejected.

6. DETAILED SCOPE OF WORK. The Detailed Scope of Work may be found in Annex A.

7. WORK TO BE ACCOMPLISHED.

7.1 Perform a Limited Site Survey. The AE shall obtain all necessary data to evaluate the ECOs or projects by conducting a site survey. The AE shall document his site survey on forms developed for the survey, or standard forms, and submit these completed forms as part of the report. All test and/or measurement equipment shall be properly calibrated prior to its use.

7.2 Evaluate Selected ECOs. The AE shall analyze the ECOs listed in Annex A. These ECOs shall be analyzed in detail to determine their feasibility. Savings to Investment Ratios (SIRs) shall be determined using current ECIP guidance. The AE shall provide all data and calculations needed to support the recommended ECO. All assumptions and engineering equations shall be clearly stated. Calculations shall be prepared showing how all numbers in the ECO were figured. Calculations shall be an orderly step-by-step progression from the first assumption to the final number. Descriptions of the products, manufacturers catalog cuts, pertinent drawings and sketches shall also be included. A life cycle cost analysis summary sheet shall be prepared for each ECO and included as part of the supporting data.

7.3 Combine ECOs Into Recommended Projects. During the Interim Review Conference, as outlined in paragraph 7.4.1, the AE will be advised of the Plant Manager's preferred packaging of recommended ECOs into projects for implementation. Some projects may be a combination of several ECOs, and others may contain only one. These projects will be evaluated and arranged as outlined in

paragraphs 5.1, 5.2, and 5.3. Energy savings calculations shall take into account the synergistic effects of multiple ECOs within a project and the effects of one project upon another. The results of this effort will be reported in the Final Submittal per par 7.4.2.

7.4 Submittals, Presentations and Reviews. The work accomplished shall be fully documented by a comprehensive report. The report shall have a table of contents and shall be indexed. Tabs and dividers shall clearly and distinctly divide sections, subsections, and appendices. All pages shall be numbered. Names of the persons primarily responsible for the project shall be included. The AE shall give a formal presentation of the interim submittal to installation, command, and other Government personnel. Slides or view graphs showing the results of the study to date shall be used during the presentation. During the presentation, the personnel in attendance shall be given ample opportunity to ask questions and discuss any changes deemed necessary to the study. A review conference will be conducted the same day, following the presentation. Each comment presented at the review conference will be discussed and resolved or action items assigned. It is anticipated that the presentation and review conference will require approximately one working day. The presentation and review conference will be at the installation on the date agreeable to the Plant Manager, the AE and the Government's representative. The Contracting Officer may require a resubmittal of any document(s), if such document(s) are not approved because they are determined by the Contracting Officer to be inadequate for the intended purpose.

7.4.1 Interim Submittal. An interim report shall be submitted for review after the field survey has been completed and an analysis has been performed on all of the ECOs. The report shall indicate the work which has been accomplished to date, illustrate the methods and justifications of the approaches taken and contain a plan of the work remaining to complete the study. Calculations showing energy and dollar savings, SIR, and simple payback period of all the ECOs shall be included. The results of the ECO analyses shall be summarized by lists as follows:

a. All ECOs eliminated from consideration shall be grouped into one listing with reasons for their elimination as discussed in par 5.3.

b. All ECOs which were analyzed shall be grouped into two listings, recommended and non-recommended, each arranged in order of descending SIR. These lists may be subdivided by building or area as appropriate for the study. The AE shall submit the Scope of Work and any modifications to the Scope of Work as an appendix to the report. A narrative summary describing the work and results to date shall be a part of this submittal. At the Interim Submittal and Review Conference, the Government's and AE's representatives shall coordinate with the Plant Manager to provide the AE with direction for packaging or combining ECOs for programming purposes and also indicate the fiscal year for which the

programming or implementation documentation shall be prepared. The survey forms completed during this audit shall be submitted with this report. The survey forms only may be submitted in final form with this submittal. They should be clearly marked at the time of submission that they are to be retained. They shall be bound in a standard three-ring binder which will allow repeated disassembly and reassembly of the material contained within.

7.4.2 Final Submittal. The AE shall prepare and submit the final report when all sections of the report are 100% complete and all comments from the interim submittal have been resolved. The AE shall submit the Scope of Work for the study and any modifications to the Scope of Work as an appendix to the submittal. The report shall contain a narrative summary of conclusions and recommendations, together with all raw and supporting data, methods used, and sources of information. The report shall integrate all aspects of the study. The recommended projects, as determined in accordance with paragraph 5, shall be presented in order of priority by SIR. The lists of ECOs specified in paragraph 7.5.1 shall also be included for continuity. The final report and all appendices shall be bound in standard three-ring binders which will allow repeated disassembly and reassembly. The final report shall be arranged to include:

a. An Executive Summary to give a brief overview of what was accomplished and the results of this study using graphs, tables and charts as much as possible (See Annex B for minimum requirements).

b. The narrative report describing the problem to be studied, the approach to be used, and the results of this study.

c. Documentation for the recommended projects (includes LCCA Summary Sheets).

d. Appendices to include as a minimum:

- 1) Energy cost development and backup data
- 2) Detailed calculations
- 3) Cost estimates
- 4) Computer printouts (where applicable)
- 5) Scope of Work

ANNEX A


DETAILED SCOPE OF WORK

1. The facilities to be studied in this contract are used for the production of nitric acid in Area B at Holston Army Ammunition Plant (HSAAP) in Kingsport, Tennessee. Holston Army Ammunition Plant is a government-owned, contractor-operated (GOCO) facility. The operating contractor is the Holston Defense Corporation (HDC). For reasons of safety and security, access to the plant is controlled. Temporary passes will be required for both personnel and vehicle access.
 - a. A one-week notice should be given by the AE prior to any visit. This time will be needed to make the necessary arrangements for the visit.
 - b. The AE should submit a list of the equipment and instruments they plan to use prior to their arrival. Because of the nature of HSAAP operations, safety regulations prohibit and restrict the use of some equipment on the installation. Having a list of the equipment to be used beforehand, HSAAP will be better prepared at the entrance interview to address the regulations pertaining to the equipment to be used. This will also facilitate coordination of the inspection and permitting of the equipment.
2. The following persons have been designated as points of contact and liaison for all work required under this contract. Mr. Scott Shelton shall be the Installation Representative, and Mr. J. L. Bouchillon shall be the Operating Contractor's Representative.
3. Completion and Payment Schedule: The following schedule shall be used as a guide in approving payments on this contract. The final report for this study shall be due not later than 180 days after Notice to Proceed.

<u>MILESTONE</u>	<u>PERCENT OF CONTRACT AMOUNT AUTHORIZED FOR PAYMENT</u>
Completion of Field Work	25
Receipt of Interim Submittal	75
Completion of Interim Presentation & Review	85
Receipt of Final Report	100

4. Purpose and Background: The purpose of this study is to identify and evaluate Energy Conservation Opportunities (ECOs) for the Ammonia Oxidation Process (AOP), which produces weak nitric acid. Figure 16 on page A-2 illustrates the AOP process. The chemical reactions utilized in the AOP are exothermic, producing large quantities of hot gases. Large amounts of cooling water are also used to cool and condense water vapor in the gases. Electrical energy is used to compress air for the process. Some heat and mechanical energy are already recovered

ENERGY BALANCE-BLDG. 302-B
NITRIC ACID MANUFACTURING



AS BUILT JAN 1995

HOLSTON ARMY AMMUNITION PLANT
 HOLSTON DEFENSE CORPORATION
 KINGSPORT, TENN.
 BLDG. 302-B, NITRIC ACID MFG.

DRAWN-PB
 DATE-1-14-76
 APP'D-NH
 SK# 2286

FIGURE 16

in the process. However, there appears to be room for improvement in the process or by using recovered heat in nearby facilities. Building 302-B houses four 50-ton/day AOP units. Each AOP unit has an air compressor, which is driven by a 1300 HP electric motor. The motor is assisted by a gas turbine, which is driven by the tail gas from the process. At the present production level, one 50-TDP unit operates four continuous 24-hour days twice per month.

5. The AE is encouraged to propose and analyze any ECOs which he believes may save energy, water, or dollars. The AE must become familiar with the process and with the capabilities and limitations of the existing equipment. Due to the limited resources available, proposed ECOs should not impose additional maintenance and operation requirements. In addition to ECOs proposed by the AE, the following ECOs will be evaluated:

- a. Since 300 psig steam is available, revise air compressor turbine drive to steam. There may be variations on this ECO, such as using 300 psig steam exclusively (which might require a different turbine) or using steam (at 300 psig or at a reduced pressure) in the existing turbine to assist the electric motor.
- b. Use the product gas leaving the Air Preheater (Fig 16) to generate steam. Depending on the pressure of the steam generated, the gas could be cooled to perhaps as low as 400 degF. The steam thus generated could be used to drive (or assist in driving) the air compressor, or it could be used to vaporize ammonia, or for heating at the 302-B tank farm.
- c. Identify and evaluate the possibility of water conservation at the cascade coolers and at other points in the process.

6. Government-furnished information. The following documents will be furnished to the AE:

- a. Energy Conservation Investment Program (ECIP) Guidance, dated 10 Jan 1994 and the latest revision with current energy prices and discount factors for life cycle cost analysis.
- b. AR 415-15, 1 Jan 84, Military Construction, Army (MCA) Program Development
- c. TM5-800-2, Cost Estimates, Military Construction.
- d. Tri-Service Military Construction Program (MCP) Index, dated day/month/year.
- e. As-built drawings and process descriptions with quantitative data for the AOP facilities.

8. A computer program titled Life Cycle Costing in Design (LCCID) is available from the BLAST Support Office in Urbana, Illinois for a nominal fee. This computer program can be used for performing the economic calculations for ECIP and non-ECIP ECOs. The AE is encouraged to obtain and use this computer program. The BLAST Support Office can be contacted at 144 Mechanical Engineering Building, 1206 West Green Street, Urbana, Illinois 61801. The telephone number is (217) 333-3977 or (800) 842-5278.

9. Direct Distribution of Submittals. The AE shall make direct distribution of correspondence, minutes, report submittals, and responses to comments as indicated by the following schedule:

AGENCY	EXECUTIVE SUMMARIES REPORTS	FIELD NOTES	CORRESPONDENCE
Holston Army Ammunition Plant ATTN: SMCHO-EN (Mr Shelton) Kingsport, TN 37660-9982	3 3 1** 1		
US AMC I & SA ATTN: AMXEN-C (Mr Nache) Rock Island, IL, 61299-7190	1 1 - -		
Commander US Army Corps of Engineers ATTN: CEMP-ET (Mr Gentil) 20 Massachusetts Avenue NW Washington, DC, 20314-1000	1* - - -		
USAED, South Atlantic ATTN: CESAD-EN-TE (Mr Baggette) 77 Forsyth Street, SW Atlanta, GA 30335-6801	1 1 - -		
USAED, Mobile ATTN: CESAM-EN-DM (Battaglia) PO Box 2288 Mobile, AL 36628-0001	2 2 1** 1		
US Army Logistics Evaluation Agency ATTN: LOEA-PL (Mr Keath) New Cumberland Army Depot New Cumberland, PA, 17070 - 5007	1* - - -		

* Receives Executive Summary of final report only.

** Field Notes submitted in final form at interim submittal.

ANNEX B

EXECUTIVE SUMMARY GUIDELINE

1. Introduction.
2. Building Data (types, number of similar buildings, sizes, etc.)
3. Present Energy Consumption of Buildings or Systems Studied.
 - o Total Annual Energy Used.
 - o Source Energy Consumption.

Electricity - KWH, Dollars, MBTU
Coal - TONS, Dollars, MBTU, MWH
Natural Gas - THERMS, Dollars, MBTU, MWH
Other - QTY, Dollars, MBTU, MWH

4. Energy Conservation Analysis.
 - o ECOs Investigated.
 - o ECOs Recommended.
 - o ECOs Rejected. (Provide economics or reasons)
 - o ECIP Projects Developed. (Provide list)*
 - o Non-ECIP Projects Developed. (Provide list)*
 - o Operational or Policy Change Recommendations.

* Include the following data from the life cycle cost analysis summary sheet: the cost (construction plus SIOH), the annual energy savings (type and amount), the annual dollar savings, the SIR, the simple payback period and the analysis date.

6. Energy and Cost Savings.
 - o Total Potential Energy Savings in MegaBTU per year (and MegaWattHr per year) and first year dollar savings.
 - o Percentage of Energy Conserved.
 - o Energy Use and Cost Before and After the Energy Conservation Opportunities are Implemented.

ANNEX C

REQUIRED DD FORM 1391 DATA

To facilitate ECIP project approval, the following supplemental data shall be provided:

- a. In title block clearly identify projects as "ECIP."
- b. Complete description of each item of work to be accomplished including quantity, square footage, etc.
- c. A comprehensive list of buildings, zones, or areas including building numbers, square foot floor area, designated temporary or permanent, and usage (administration, patient treatment, etc.).
- d. List references, and assumptions, and provide calculations to support dollar and energy savings, and indicate any added costs.
 - (1) If a specific building, zone, or area is used for sample calculations, identify building, zone or area, category, orientation, square footage, floor area, window and wall area for each exposure.
 - (2) Identify weather data source.
 - (3) Identify infiltration assumptions before and after improvements.
 - (4) Include source of expertise and demonstrate savings claimed. Identify any special or critical environmental conditions such as pressure relationships, exhaust or outside air quantities, temperatures, humidity, etc.
- e. Claims for boiler efficiency improvements must identify data to support present properly adjusted boiler operation and future expected efficiency. If full replacement of boilers is indicated, explain rejection of alternatives such as replace burners, nonfunctioning controls, etc. Assessment of the complete existing installation is required to make accurate determinations of required retrofit actions.
- f. Lighting retrofit projects must identify number and type of fixtures, and wattage of each fixture being deleted and installed. New lighting shall be only of the level to meet current criteria. Lamp changes in existing fixtures is not considered an ECIP type project.

g. An ECIP life cycle cost analysis summary sheet as shown in the ECIP Guidance shall be provided for the complete project and for each discrete part included in the project. The SIR is applicable to all segments of the project. Supporting documentation consisting of basic engineering and economic calculations showing how savings were determined shall be included.

h. The DD Form 1391 face sheet shall include, for the complete project, the annual dollar and MBTU (MWH) savings, SIR, simple amortization period and a statement attesting that all buildings and retrofit actions will be in active use throughout the amortization period.

i. The calendar year in which the cost was calculated shall be clearly shown on the DD Form 1391.

j. For each temporary building included in a project, separate documentation is required showing (1) a minimum 10-year continuing need, based on the installation's annual real property utilization survey, for active building retention after retrofit, (2) the specific retrofit action applicable and (3) an economic analysis supporting the specific retrofit.

k. Nonappropriated funded facilities will not be included in an ECIP project without an accompanying statement certifying that utility costs are not reimbursable.

l. Any requirements required by ECIP guidance dated 10 Jan 1994 and any revisions thereto. Note that unescalated costs/savings are to be used in the economic analyses.

m. The five digit category number for all ECIP projects except for Family Housing is 80000. The category code number for Family Housing projects is 71100.

**MINUTES
OF
MEETINGS**

3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500 • FAX (904) 375-3479

MEETING NOTES

HOLSTON AREA B ACID FACILITY STUDY

Project
KINGSPORT, TN

City, State
INTERIM REVIEW

Type of Meeting
11/30/95

Meeting Date

95094-00

Project #
December 1, 1995

Date
1 of 2 MAH
 Page
PDL Typist
 Copies

Present

Representing

Tony Battaglia
 Scott Shelton
 Jerry Bouchillon
 Alex Fancher
 Paul Little
 Carl Osberg

US Army Corps of Engineers
 Holston AAP
 HDC
 HDC
 AESE
 AESE

The purpose of this meeting was to review the Interim Report and the following items were discussed.

1. Reviewed schematic flow diagram of process. Several corrections were noted.
2. AESE to revise energy inventory table and show sample calculations (pages 43-49).
3. ECO No. 1 - needs to be revised to reflect replacing of the existing tailgas turbine with a steam condensing turbine. Noise will be an issue to review if tail gas is going to be exhausted.
4. ECO No. 2 - correct steam output from 31,000 to 3,100 lbs/hr and review using steam to assist turbine.
5. AESE to create a new ECO utilizing insulated air preheater, tailgas heater and plantnium recovery filter, with a once through steam system to assist the turbines.
6. Look at possibility of eliminating/replacing cascade cooler.
7. Plantnium filter needs to be located prior to any waste heat boiler and cascade cooler.
8. Stainless steel needs to be 400 grade for any metals in contact with product gas. AESE to get price quotes from manufacturers for waste heat boiler.
9. Dowtherm A (eutectic mixture of Diphenyl Oxide and Diphenyl) is incompatible with the process if a leak were to occur, and is to be eliminated from consideration for an intermediate heat transfer fluid.
10. Utilizing a cooling tower will jeopardize Pollution Permits (ECO No. 3).
11. Existing chiller has capacity for operating only (2) units at once.
12. Add Conclusions and Recommendations to Executive Summary section of the report.

Project Name: Holston AAP Nitric Acid Production Facility **Date:** December 22, 1995
Project No.: 95094-00 **Page No.:** 2 of 2

13. Starting turbine without tail gas uses 290 amps of electrical power when tail gas is added to turbine the electrical power drops to 220 amps.
14. AESE to investigate chiller revision from a direct-contact steam condenser to a steam surface condenser from which steam condensate can be recovered. Because chiller operates only 5 months out of year, evaluate production level at which this modification will qualify for ECIP.

The above constitutes the writer's understanding of the discussions of this meeting and conclusions reached. Corrections/errors should be noted to the writer within 5 working days.

By:

AFFILIATED ENGINEERS SE, INC.



For Carl L. Osberg, P.E.
Vice President

3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500 • FAX (904) 375-3479

MEETING NOTES

HOLSTON AAP NITRIC ACID PRODUCTION FACILITY

Project

HOLSTON, TN

City, State

EXIT INTERVIEW

Type of Meeting

08/17/95 (AM)

Meeting Date

95094-00

Project #

August 22, 1995

Date

1 of 1

DA

Page

Typist

Copies

Present

Representing

Scott Shelton

SMCHO-EN

Alex Francher

HDC

Carl Osberg

AESE

Paul Little

AESE

The purpose of this meeting was to review the items surveyed and discuss probable areas of energy conservation. The following items were discussed.

Nitric Acid manufacturing process was observed in operation with absorption column #9 operating. Each of the four air compressors were operating, but only one of the four was being loaded. It was noted that compressed air final stage after cooler does not have dewpoint control or other control strategy. The steam jet refrigerating unit was confirmed to utilize a steam surface condenser.

The above constitutes the writer's understanding of the discussions of this meeting and conclusions reached. Corrections/errors should be noted to the writer within 5 working days.

By,



Paul Little, P.E.
HVAC Project Engineer

3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500 • FAX (904) 375-3479

MEETING NOTES

HOLSTON AAP NITRIC ACID PRODUCTION FACILITY

Project

HOLSTON, TN

City, State

EXIT INTERVIEW

Type of Meeting

07/07/95

Meeting Date

95094-00

Project #

July 11, 1995

Date

1 of 1

MAH

Page

Typist

CO

Copies

Present	Representing
---------	--------------

Scott Shelton	SMCHO-EN
Charlie Fowler	HDC - Engineering
Robert Barnes	AESE

The purpose of this meeting was to review the items surveyed and discuss probable areas of energy conservation. The following items were discussed.

1. Bob Barnes briefly reviewed the scope of work for this project. Some options available for saving energy, water or dollars for this project include:
 - Recover heat to generate steam or hot water to supplement or eliminate steam used to vaporize ammonia.
 - Recover heat to generate steam to be used to reduce existing steam used at chiller.
 - Reduce filtered riverwater used at cascade cooler by storing chilled water in a closed loop configuration.
 - Recover heat to generate steam to run turbine at air compressor to reduce electric motor use.
 - Recover hot condensate from vaporizer and/or chiller to be regenerated to steam with waste heat for use at vaporizer or chiller.
 - Use 300 psig or 150 psig steam from existing steam system to run a turbine at the air compressor to reduce or eliminate the electric motor usage.
2. Bob Barnes asked Mr. Fowler if there were any ideas for energy conservation which had been overlooked. Mr. Fowler was not aware of other potential energy saving concepts.
3. Mr. Fowler clarified the capacity of the steam jet chiller. The chiller was relocated from another process and is approximately sized to handle 2 AOP process streams and not 4 as originally estimated by AESE.

The above constitutes the writer's understanding of the discussions of this meeting and conclusions reached. Corrections/errors should be noted to the writer within 5 working days.

By:

AFFILIATED ENGINEERS SE, INC.

Robert A. Barnes, P.E.
 HVAC Project Engineer

3300 SW Archer Road
 Gainesville, Florida 32608
 (904) 376-5500 • FAX (904) 375-3479

MEETING NOTES

HOLSTON AAP NITRIC ACID PRODUCTION FACILITY

Project

HOLSTON, TN

City, State

ENTRY INTERVIEW

Type of Meeting

07/05/95

Meeting Date

Present

Scott Shelton
 Jerry Bouchillon
 Alex Fancher
 Mike Richarme
 Carl Osberg
 Robert Barnes

95094-00

Project #

July 11, 1995

Date

1 of 1

MAH

Page

Typist

CO

Copies

Representing

SMCHO-EN
 HDC
 HDC
 AESE
 AESE
 AESE


The purpose of this meeting was to have an entry interview and the following items were discussed.

1. Mr. Jerry Bouchillon inquired as to the type of data needed to be furnished by HDC. AESE personnel requested information regarding: compressor intercooler water flow; Pump flows; pump curves; motor data; chiller capacity; and chiller steam flow and pressure.
2. Alex Fancher stated that manuals were available by Dupont which had technical data on the AOP process which could contain information useful for this project. The manuals would be located during the AESE field investigation to be reviewed for useful information.
3. Jerry Bouchillon would provide AESE with the name of the stainless steel fabricator who provided equipment for this facility to be used for pricing and special fabrication information.
4. AESE would conduct the field investigation today 07/05/95 instead of the document review listed in the AESE agenda. This would allow Mike Richarme to become familiar with the AOP Facility so he could shorten his field investigation time and depart this evening.
5. Jerry Bouchillon advised that mechanical and electrical drawings of the AOP Facility were downstairs in the engineering plan room. AESE personnel were invited to look through the drawings for relevant information for this project.

The above constitutes the writer's understanding of the discussions of this meeting and conclusions reached. Corrections/errors should be noted to the writer within 5 working days.

By:

AFFILIATED ENGINEERS SE, INC.



Robert A. Barnes, P.E.
 HVAC Project Engineer

3300 SW Archer Road
Gainesville, Florida 32608
(904) 376-5500 • FAX (904) 375-3479

MEETING NOTES

HOLSTON AAP NITRIC ACID PRODUCTION FACILITY

Project

HOLSTON, TN

City, State

PRE-NEGOTIATIONS

Type of Meeting

04/26/95

Meeting Date

95094-00

Project #

May 1, 1995

Date

1 of 2

MAH

Page

Typist

RB

Copies

Present	Representing
Tony Battaglia	US Army Corps of Engineers
Jerry Bouchillon	HDC
Scott Shelton	SMCHO-EN
Bob Lowe	HDC
Robert Barnes	AESE
Carl Osberg	AESE

Tony Battaglia	US Army Corps of Engineers
Jerry Bouchillon	HDC
Scott Shelton	SMCHO-EN
Bob Lowe	HDC
Robert Barnes	AESE
Carl Osberg	AESE

The purpose of this meeting was to review the project scope and the following items were discussed.


1. HDC is investigating purchasing 100 lb steam from Tennessee-Eastman.
2. Acid production facility operates only 2 to 4 days/month but runs continuous during the 2 to 4 days. Currently run two units during this period. Investigate running one unit all week vs two units for 2 to 4 days. Staffing of facility needs to be considered.
3. A more detailed schematic diagram of the system is needed to better understand the system.
4. Steam cost is \$2.94/MBtu at present. Electrical cost is \$.03412/kWH.
5. Nitric acid production process was invented in 1935 and has been active at Holston since 1942. A newer more efficient process is now available and is also active at Holston. A new 300 ton/day unit is presently in use at HDC.
6. A waste heat boiler is a possible option to generate steam to run the air compressors to reduce the electric motor energy use.
7. Alex Fancher is contact point at acid production facility.
8. A steam jet ejector chiller is currently used to cool river water when water temperatures rise in the summer months.
9. Jerry Bouchillon to update flow diagram of process, provide P&I drawings of process, and provide air compressor curves. Data on turbines will be made available at entry interview.
10. Proposal to Corps may also include ideas/approach to project that is different than scope of work.
11. AESE to notify Corps prior to submitting proposal of any special consultants, testing, etc. that is going to be proposed.

Project Name: Holston AAP Nitric Acid Production Facility **Date:** May 1, 1995
Project No.: 95094-00 **Page No.:** 2 of 2

The above constitutes the writer's understanding of the discussions of this meeting and conclusions reached.
Corrections/errors should be noted to the writer within 5 working days.

By:

AFFILIATED ENGINEERS SE, INC.


Carl L. Osberg, P.E.
Vice President