



The Port of Hueneme Confined Aquatic Disposal Project: A Unique Partnership for Contaminated Sediment Management

Presented by
Jack Malone, Ph.D.
Steve Cappellino

May 11, 2011

Report Documentation Page

Form Approved
OMB No. 0704-0188

Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.

1. REPORT DATE 11 MAY 2011		2. REPORT TYPE		3. DATES COVERED 00-00-2011 to 00-00-2011	
4. TITLE AND SUBTITLE The Port of Hueneme Confined Aquatic Disposal Project: A Unique Partnership for Contaminated Sediment Management				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Anchor QEA, 26300 La Alameda Suite 240, Mission Viejo, CA, 92691				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited					
13. SUPPLEMENTARY NOTES Presented at the NDIA Environment, Energy Security & Sustainability (E2S2) Symposium & Exhibition held 9-12 May 2011 in New Orleans, LA. U.S. Government or Federal Rights License					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT Same as Report (SAR)	18. NUMBER OF PAGES 31	19a. NAME OF RESPONSIBLE PERSON
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified			

Overview

- Site and project history
- Confined Aquatic Disposal (CAD) concept
- Partnership strategy and cost allocations
- Permitting and design
- Post-construction monitoring
- Lessons learned
- Project benefits


Project Team

- U.S. Navy (USN)
 - Naval Base Ventura County
 - Naval Facilities Engineering Command (NAVFAC) Southwest
- Oxnard Harbor District (OHD)
- U.S. Army Corps of Engineers (USACE), Los Angeles District
- Anchor QEA, L.P.
 - Everest International Consultants, Inc.
 - iLanco Environmental, LLC

Port of Hueneme



Port of Hueneme – Joint Use



Current Uses

- USN
 - Construction Battalion Center
 - Naval Surface Warfare Center
 - Pacific Missile Test Range
- OHD
 - Produce import/export
 - Roll On/Roll Off automobile import/export
 - Break bulk/specialty cargo


Multiple Sediment Issues in Harbor

- Federal Channel had accumulated approximately 200,000 cubic meters of mostly clean maintenance material
- USACE had authority to deepen Federal Channel by approximately 1.5 meters
- None of the OHD or USN berths had been dredged in decades, resulting in operational constraints
- Contaminated sediments existed within much of Port of Hueneme Harbor

Sediment Contamination

- Totaled approximately 220,000 cubic meters
- Approximately 60 percent from berths and 40 percent from Federal Channel
- Chemicals of Concern (COCs) include PAHs, PCBs, DDT, and TBT
- Mostly fine sands, silts, and clays

Contaminated Sediment



Management Alternatives

- Landfill disposal
- Beneficial reuse
- On-site near shore confined disposal facility (CDF)
- Port fill site at Port of Los Angeles (POLA) or Port of Long Beach (POLB)
- On-site CAD

Rationale for CAD Approach

- Provided an on-site solution
- Not tied to other development or funding
- Provided environmental protection
- Provided local beach nourishment
- Allowed for future Port of Hueneme Harbor deepening to advance
- Restored 100 percent use of USN/OHD wharves
- Provided **complete** solution for all three parties
- Shared resources = cost effective

Construction Sequencing



Construction Sequencing




Construction Sequencing



Step 3: Place Cap Material
onto CAD

Port of Hueneme CAD Cross Section



Funding Strategy

- Challenges
 - Raising funds (total project cost approximately \$14 million)
 - Coordinating budget and funding schedules
 - Contractor negotiations and scheduling
- Opportunities
 - All partners had some funds allocated for smaller individual projects
 - Management and staff committed to success
 - Significant project momentum

Cost Sharing Approach

- Break project into components (e.g., CAD cell excavation, USN berths, OHD berths, cap armor placement, long-term monitoring)
- Estimate costs associated with each component
- Assign components to partners based on either ownership or limitations in authority

Cost Sharing Approach

- Fine tune cost components to accommodate secondary cost sharing strategies and funding schedules
 - Financial balancing to make project more equitable among all partners
 - Recognize previous agreements between partners
 - Account for contaminated sediment ownership allocation

Cost Sharing Approach Responsibilities

Project Feature	Responsibility		
	USACE	USN	OHD
Project Development			
- CEQA/NEPA Permitting		X	X
- Engineering Design		X	X
Contracting			
- Contract Management	X		
Construction			
- Equipment Mobilization	X		
- CAD Cell Excavation		X	X
- Dredging USN Wharves		X	
- Dredging OHD Wharves			X
- Dredging "Hotspots" within O&M Channel	X		
- Capping	X		
- Placing Rock Armor		X	X
- Water Quality Monitoring	X	X	X
- Sediment Confirmational Sampling	X	X	X
- Construction Management	X	X	X
Post-Construction Activities			
- Long-term Monitoring		X	X

Contracting Approach

- USACE had existing contract with Manson Construction for O&M dredging in Port Hueneme and Channel Islands Harbor
- Contract modification issued for additional work
- OHD/USACE signed Cost Sharing Agreement
- USACE/USN Cost Sharing Agreement for dredging was already in place

Contracting Approach

- OHD/USN signed Cost Sharing Agreement for CAD construction and long-term monitoring/liability
- All funds transferred to USACE for contracting and management

Permitting Strategy

- Project subject to California Environmental Quality Act (CEQA) and National Environmental Policy Act (NEPA) regulations
 - Joint NEPA/CEQA document to streamline processes
- Also subject to Clean Water Act (CWA) regulations

Permitting Strategy

- Separate regulatory components
 - USACE O&M dredging and disposal component (NEPA)
 - Supplemental NEPA document for CAD disposal
 - USN berth dredging and disposal (NEPA and CWA)
 - OHD berth dredging and disposal (CEQA and CWA)
 - CAD cell construction and beach nourishment (NEPA, CEQA, and CWA)
- Joint USN/OHD application for permits to construct the CAD and dredge respective wharves

Initial Design Elements

- Contaminated sediment removal
 - Total of approximately 220,000 cubic meters
 - Mechanically dredged using clamshell
 - Restricted dredging required for some berths
- CAD cell construction and contaminated dredged material disposal
 - Hydraulic excavation of CAD cell
 - Material pumped to beach
 - Contaminated material placed via bottom-dump SCOW

Initial Design Elements

- CAD cell cap design
 - Chemical isolation
 - Hydrodynamic modeling
 - Geotechnical (i.e., bulking and settling)
 - Bioturbation

Cap Design Critical Elements

- Ship propeller wash scour from USN destroyers
 - Modeled bottom velocities up to 11.4 feet per second
 - Worst-case assumptions capable of producing greater than 5 feet of scour
- Chemical flux
 - Some aquifers in region experience artesian conditions
 - Final elevation critical to prevent significant upward flux

Project Timeline

- Conceptual design for project completed in April 2007
- Design and permitting completed in August 2008 (16 months from conception)
- Construction began in December 2008
- Construction completed in July 2009
- Approximately 1 million cubic yards of dredging

Monitoring Results

- One year of monitoring completed
 - Hydrographic surveys, sediment cores, sediment chemistry, porewater samples
- CAD cell performing as designed
 - Sufficient cap thickness achieved
 - Contaminant isolation achieved
 - Scour resistance achieved
- Authorized depths restored to USN and OHD berths and to Federal Channel

Lessons Learned

- Commitment to succeed from project partners
 - Managers set the tone for staff
- Leverage existing agreements
 - Streamline legal review and contracting processes
- Internal and external communication is critical throughout process
 - Project team coordination is open and continuous
 - Be proactive in communicating with external stakeholders

Project Benefits

- Recreational: Restored Hueneme Beach
- Operations: Restored full navigation use to Harbor
- Future Growth: Provides clear path for Harbor deepening
- Financial: More than \$30 million in benefits achieved for less than \$14 million in costs

Biggest Accomplishment – A Successful Model for a Teaming Approach

