

# Report Documentation Page

*Form Approved*  
*OMB No. 0704-0188*

Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.

1. REPORT DATE <b>30 SEP 2003</b>	2. REPORT TYPE	3. DATES COVERED <b>00-00-2003 to 00-00-2003</b>			
4. TITLE AND SUBTITLE <b>SFOMC Industrial and Facility Support</b>		5a. CONTRACT NUMBER			
		5b. GRANT NUMBER			
		5c. PROGRAM ELEMENT NUMBER			
6. AUTHOR(S)		5d. PROJECT NUMBER			
		5e. TASK NUMBER			
		5f. WORK UNIT NUMBER			
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>NSWCCD South Florida Testing Facility,,91 North Beach Road,,Dania Beach,,FL, 33004</b>		8. PERFORMING ORGANIZATION REPORT NUMBER			
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)		10. SPONSOR/MONITOR'S ACRONYM(S)			
		11. SPONSOR/MONITOR'S REPORT NUMBER(S)			
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release; distribution unlimited</b>					
13. SUPPLEMENTARY NOTES					
14. ABSTRACT <b>The long-term goal is to support short and long duration testing of shallow water and very shallow water AUV systems and components and to provide overall shallow and deep water capabilities enhancements that support Navy RDT&amp;E needs.</b>					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>Same as Report (SAR)</b>	18. NUMBER OF PAGES <b>3</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

# **SFOMC Industrial and Facility Support**

W. Venezia, W. Baxley  
NSWCCD South Florida Testing Facility  
91 North Beach Road  
Dania Beach, FL 33004

Phone (954) 926-4000 E-mail: [VeneziaWA@nswccd.navy.mil](mailto:VeneziaWA@nswccd.navy.mil), [BaxleyWE@nswccd.navy.mil](mailto:BaxleyWE@nswccd.navy.mil)

Document #: N0001402WX21304

## **LONG-TERM GOAL**

The long-term goal is to support short and long duration testing of shallow water and very shallow water AUV systems and components and to provide overall shallow and deep water capabilities enhancements that support Navy RDT&E needs.

## **OBJECTIVES**

The objective is to provide capability enhancements and thorough industrial and facilities support to all SFOMC projects. These enhancements are to significantly improve meteorological and oceanographic environmental monitoring capabilities both on shore and offshore and above and below the sea surface. Emphasis shall be on monitoring of wind, waves and currents.

## **APPROACH**

The approach was to implement a versatile, robust, reliable, and maintainable sea floor system of multiplexers and sea floor cables capable of high bandwidth data transmission to shore along with specific capabilities enhancements that benefit all the SFOMC projects.

## **WORK COMPLETED**

The SFTF installed a new weather station at the Jetty site in order to provide accurate wind, temperature, and humidity measurements in support of other SFOMC projects. The new station was installed on a 10-meter tower, and located in a clear area, free of obstructions. The system transmits measurements over a solar-powered, wireless telemetry system to an SFTF-designed logging program in the range control facility. This system was designed as a prototype for future remote weather stations that may be deployed in support of SFOMC projects, both along the shoreline as well as at offshore locations on the SFTF range, as required.

The SFTF is currently designing and purchasing the materials to install a fixed platform in 20 ft of water on its range in support of SFOMC projects. The platform will be built of structural steel, will be anchored into the bottom, and will have a top deck elevation of approximately +16 ft above mean low water (MLW). Initially, the platform will support an array of wave staffs, capable of measuring wave height and direction, and a weather station similar to the one located at the SFOMC north campus site. A 16-conductor shore cable runs to the tower site, and it will provide power and telemetry for the platform. A NAVOCEANO tide gauge has been installed at the planned tower location since April

2003, and provides a baseline data set for waves in the vicinity. The planned tower install date is mid-November 2003.

The SFTF is planning to install a RDI ADCP in approximately 270 ft of water in September 2003 to augment other SFOMC environmental sensors in the area. The unit will be installed on a recently laid fiber optic cable, and the data will be telemetered back in real time for addition onto the SFOMC environmental website.

## **RESULTS**

Solid results were achieved in support of all ONR sponsored activities. These include but are not limited to successful integration of the acoustic communication hardware with a robust data telemetry system and installation of additional environmental monitoring systems. Range operations and range related activities increased from 52 total days in FY02 to 119 total days FY03, a 129% increase in use.

## **IMPACT/APPLICATIONS**

The most significant impact of the facility and industrial support was the hardening of the underwater and environmental systems to the point where 24/7 operations are being maintained on all key environmental and data communications systems

## **RELATED PROJECTS**

All SFOMC execution efforts are related to this project as this effort supplies the mechanism by which most work done at sea is accomplished.

This project aids the scientific community and benefits the local community through acquisition and sharing of local geographical, environmental, and oceanographic data and information. Applications of societal relevance include safe navigation, search and rescue operations, beach erosion forcing function measurement, monitoring of transport mechanisms for pollution from sewage plants, harmful algal blooms, and hazardous material tracking.

Of particular impact is the synergy created at SFOMC among scientific and applied users. The meteorological and oceanographic data is being shared with Broward County. The offshore tower is the site for a planned installation of a Broward County's first real-time offshore environmental monitoring system. The installation of the very shallow water wave staff array is expected to benefit Navy modelers seeking ground truth data for coastal process studies as well as coastal engineers engaged in modeling of the dynamics of the beach adjacent to the wave staff array.