

UNCLASSIFIED

AD NUMBER

ADB022525

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 12 AUG 1977. Other requests shall be referred to Electronics Systems Division, Attn: AFSC, Hanscom AFB, MA 01731.

AUTHORITY

USAFGL ltr, 7 Sep 1982

THIS PAGE IS UNCLASSIFIED

AD B 022525

AUTHORITY: USAFGL

1tr 7 Sep 82





13

Report No. 131500-616  
12 August 1977

2<sup>mc</sup>

AD B 0 2 2 5 2 5

LOW PRESSURE ALTITUDE TEST REPORT  
FOR THE  
AN/TRN-41 TACAN NAVIGATIONAL SET

Distribution limited to U. S. Government agencies only;  
Reason: Test and Evaluation. 12 August 1977. Other  
requests for this document must be referred to  
Department of the Air Force, Headquarters Electronic  
Systems Division (AFSC), Hanscom Air Force Base,  
Massachusetts 01731, Attention: PPG.

Prepared for:  
Department of the Air Force  
Headquarters Electronic Systems Division (AFSC)  
Hanscom Air Force Base  
Massachusetts 01731

DDDC  
NOV 3 1977  
RECEIVED  
F

Prepared by:  
E-Systems, Inc., Montek Division  
2268 South 3270 West  
Salt Lake City, Utah 84119

Contract No. F19628-75-C-0200  
CDRL Item A00Y

AD NO. \_\_\_\_\_  
DDC FILE COPY

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER ESD-TR-77-313	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
4. TITLE (and Subtitle) LOW PRESSURE ALTITUDE TEST REPORT FOR THE AN/TRN-41 TACAN NAVIGATIONAL SET		5. TYPE OF REPORT & PERIOD COVERED	
7. AUTHOR(s) None		6. PERFORMING ORG. REPORT NUMBER 14 131500-616	
9. PERFORMING ORGANIZATION NAME AND ADDRESS E-Systems, Inc., Montek Division 2268 South 3270 West Salt Lake City, Utah 84119		8. CONTRACT OR GRANT NUMBER(s) 15 F19628-75-C-0501	
11. CONTROLLING OFFICE NAME AND ADDRESS Electronic Systems Division (AFSC) Hanscom AFB Ma. 01731		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE 12 August 1977	
		13. NUMBER OF PAGES 12 10 P.	
		15. SECURITY CLASS. (of this report) Unclassified	
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A	
DISTRIBUTION STATEMENT (of this Report)			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) Distribution limited to U.S. Government agencies only; Reason: Test and Evaluation. 12 August 1977. Other requests for this document must be referred to Department of the Air Force, Hq ESD (AFSC) Hanscom AFB Ma. 01731 Attention: DRI			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  AN/TR-41 TACAN NAVIGATIONAL SET			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report describes the low pressure test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TR-41.			

408354

LOW PRESSURE ALTITUDE TEST REPORT  
for the  
NAVIGATIONAL SET, TACAN, AN/TRN-41

This report describes the low pressure test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41, 131500-415.

1. **Test Identification.** Low pressure test as defined in Appendix IV-C (low pressure test procedure) of the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41.
2. **Functional Purpose of Test.** This test forms a part of the AN/TRN-41 system qualification tests.
3. **Test Objectives.** To demonstrate that the AN/TRN-41 will meet the low pressure requirements of paragraphs 3.2.5.1.3 and 4.2.1.4.3.4 of Specification No. 404L-701-5017A, Part I of 2 parts (20 August 1976).

4. **Description of Test Articles.** The AN/TRN-41 system consisting of the following was used for the tests:

Receiver-Transmitter	RT-1202/T
Antenna	AS-3132/T
Antenna Support	AB-1237/T
Filter, DC Power	F-1439/T
Interconnecting Cables	

ACCESS	File Section <input type="checkbox"/>	Bit Section <input type="checkbox"/>
NTIS		
DOC		
UNAVAIL		
JUSTIFICATION		
BY	INSTRUCTION/AVIATION/PTTY/PTT/PTT/PTT	
Dist.		
		B

5. **Summary of Test Results.** The AN/TRN-41 showed no functional or physical degradation during the low pressure test.
6. **Description of Test Facilities and Procedures.** The test facilities and test procedures are described in Appendix IV-C of the Equipment Test Plan.
7. **Test Setup Diagrams.** The test setup diagrams are provided in Appendix IV-C of the Equipment Test Plan.

8. **Test Equipment.** See Attachment 1 for test equipment used for the low pressure test and the pretest, test and post test operational tests.

9. **Test Data.** Attachment 2 contains the data sheets for the low pressure test and the pretest, test and post test operational tests.

10. **Test Conditions.** The system was maintained at a pressure equivalent to an altitude of 45,000 feet for 1 hour. The pressure was then increased to an altitude of 13,100 feet and the system operated at that pressure.

11. **Test Results Analysis.** The system operated normally during the low pressure tests and comparison of test data showed that no degradation of performance occurred during the test. No physical degradation was observed in the visual inspection.

12. **Certification.** The data sheets shown in Attachment 2 have been signed by a Montek Quality Assurance representative and a DCAS representative, certifying that the test results are authentic, accurate, current and in accordance with the related test plan.

**ATTACHMENT 1**  
**TEST EQUIPMENT**

## TEST EQUIPMENT

<u>Description/Manufacturer</u>	<u>Model</u>	<u>Calibration Due Date</u>
Oscilloscope, Tektronix	465	7/6/77
Signal Generator, RF, H.P.	612A	6/23/77
Peak Power Meter, Boonton	8900B	9/19/77
Pulse Generator, Data Pulse	110B	5/12/77
Counter, Fluke	1953	8/12/77
Half-Ampl. Det. Montek	131500-702	N/A
RF Detector, Montek	135203-100	N/A
Monitor Ant., Montek	006300	N/A
Test Box - Interconnection - Montek	131500-703	N/A
Power Supply HP	6274B	1/16/78
Power Supply Acopian		12/9/77
Power Supply, Sorensen	QR4075A	9/19/77
Directional Coupler 20 dB, Narda	3042B	N/A
Directional Coupler 10 dB, Microlab	CBA-78	N/A
Variable Attenuator, Weinschel 0-10 dB	905	N/A
RF Attenuator, Weinschel	10 dB	N/A
Multimeter, Fluke	8120A	8/2/77
Altitude Chamber, Sperry Univac	-	N/A
Electronic Monometer, Datametric	1023A	10/7/77
Temperature Controller, Honeywell	152P1-92-111-74	10/7/77



**ATTACHMENT 2**  
**DATA SHEETS**

131500-415

June 30, 1976

APPENDIX IV-K  
DATA SHEET  
ENVIRONMENTAL TEST

TEST Low Pressure (Altitude)  
SYSTEM 002

DATE from 9 May 1977  
to 9 May 1977  
ACCEPTABLE X  
NOT ACCEPTABLE \_\_\_\_\_

REMARKS The system was subjected to the low pressure (altitude) tests as outlined by test procedure 131500-415, appendix IV-C. At the conclusion of the low pressure test, the system operated normally. There was no degradation in performance based on comparison of test data. No discrepancies were noted.

DISCREPANCIES

SIGN OFF INFORMATION

ENVIRONMENTAL TEST ENGINEER \_\_\_\_\_

DATE \_\_\_\_\_

REPRESENTATIVE ENGINEER B.D. Taylor

DATE 5-11-77

QA REPRESENTATIVE M. B. Pruitt

DATE 5-11-77

DCASD OR AF CONCURRENCE Mark A. Clark

DATE 5-11-77

June 30, 1976

DATA SHEET  
OPERATIONAL TESTS  
AN/TRN-41

BEST AVAILABLE COPY

Test ALTITUDE - (LOW PRESSURE

Date 5/8/77

System 003

Time 10:45

Tech

Para. No.	Description	5/8/77 Pre Test max	Test	Post Test	Requirements	Units
6.1	Calibrated RF insertion loss $P_L = 31.2$ dB Used in determining RF peak power.	N/A	N/A	N/A	N/A	N/A
6.2	System turn on normal operation	✓	✓	✓	Check if OK	N/A
6.3.1	Antenna radiated signal 15 Hz	✓	✓	✓	Check if OK	N/A
	135 Hz	✓	✓	✓	Check if OK	N/A
6.3.2	Antenna Speed	66.667	66.669	66.667	66.667 ± .133	ms
6.4.1.1	Correct identity code	✓	✓	✓	Check if OK	N/A
6.4.1.2	Identity period	37.5	38.0	38.0	37.5 ± 3.75	Seconds
6.4.2	Peak power					
	(1) Reading of peak power meter $P_m =$	76mw	76mw	76mw	N/A	Watts
	(2) Convert to dBm - $10 \log P_m \times 10^3 = P_m \text{ dBm}$	18.8 dBm	18.81 dBm	18.81 dBm	N/A	dBm
	Total power output in dBm $P_{m \text{ dBm}} + P_L =$ *Insertion loss see 6.1 above.	50 dBm	50.01 dBm	50.01 dBm	50 dBm	dB
6.4.3.3	Pulse count	7184	7182	7187	7200 ± 180	Counts
6.4.4.2	Pulse shape					
	Width (50%)	3.6 $\mu$ s	3.6 $\mu$ s	3.6 $\mu$ s	3.5 ± 0.5	$\mu$ s
	Rise time (10-90%)	2.2 $\mu$ s	2.2 $\mu$ s	2.2 $\mu$ s	2 ± 0.25	$\mu$ s
	Fall time (90-10%)	2.5 $\mu$ s	2.5 $\mu$ s	2.5 $\mu$ s	2.5 ± 0.5	$\mu$ s
6.4.4.4	Pulse spacing	12.0 $\mu$ s	12.0 $\mu$ s	12.0 $\mu$ s	12.0 ± 0.1	$\mu$ s
6.4.5.2	Delay - 60 ± 10 $\mu$ s 15 Hz trig to first burst pulse.	✓	✓	✓	Check if OK	

June 30, 1976

DATA SHEET  
 OPERATIONAL TESTS  
 AN/TRN-41 (Continued)

No.	Description	Pre Test	Test	Post Test	Requirements	Units
4.5.3	Correct north burst - 12 pulse pairs spaced $30 \pm 0.1 \mu s$	✓	✓	✓	Check if OK	
4.5.5	Delay $40 \pm 10 \mu s$ - 135 Hz trig to first burst pulse	✓	✓	✓	Check if OK	
4.5.6	Correct Aux burst - 6 pulse pairs spaced $24 \pm 0.1 \mu s$	✓	✓	✓	Check if OK	
4.6.5	RT replies to 3300 interrogations	2627	2562	2508	$\geq 2310$ (Counts/Second)	
4.5.7	Demand only mode - times to switch from ON to STBY within 70 seconds	✓	✓	✓	Check if OK	L
4.6.8	STBY mode	✓	✓	✓	Check if OK	
4.6.9	Demand Only mode - time to switch from STBY to ON	✓	✓	✓	Check if OK	
4.6.10	ON AIR mode	✓	✓	✓	Check if OK	
4.7.1	DME ONLY mode	✓	✓	✓	Check if OK	
4.7.2	Switch from DME to TACAN	✓	✓	✓	Check if OK	
4.8.1	Antenna Alarm - Within four seconds	✓	✓	✓	Check if OK	
4.8.2	Alarm Reset	✓	✓	✓	Check if OK	
4.8.3	RT Alarm - Within five seconds	✓	✓	✓	Check if OK	
4.8.4	Alarm Reset	✓	✓	✓	Check if OK	

*510 sec*  
*20*  
*4/19/77*

BEST AVAILABLE COPY

ENVIRONMENTAL DATA SHEET  
ENVIRONMENTAL LABORATORY — DEPT. 330

FACILITY:			
A-1			

A.C. 298K-143	ENV. TECH. R K Davis	TEST SCHED.
ENGINEER OR O.C.M. Rogers (E systems)	PHONE 993-9300, X 288	TEST COMPLETED
TECHNICIAN	PHONE	TEST REMOVED
UNIT TITLE AN/TRN-41	SER.	QTY. 1
		TOTAL UTILIZATION

INSTRUCTIONS TO OPERATOR	TEST TO TERMINATE:	BY:	ENVIRONMENTAL LABORATORY SUPERVISORS APPROVAL
TEST Low Pressure	1. Test per procedure I		D. W. Black
SPEC. Mil-std 810	A. 3.28" Hg or 45,900 ft.		
MIL Method 500.1	B. hold for 1 hr.		DATE
	C. 16.20" Hg or 13,100 ft.		
	D. operate Test Item.		
	E. Return to Ambient pressure.		

DATE	TIME	CHRONOLOGICAL RECORD OF TEST	INITIALS (PRINT)
5/19/77		Place AN/TRN-41 in Altitude chamber.	DWB
		set pressure to 3.28" Hg. hold for 1 hr.	
5/19/77		Reset pressure to 16.20" Hg. After stabiliza-	DWB
		tion. operated Test ITEM	
5/19/77		Return chamber to ambient pressure.	DWB

BEST AVAILABLE COPY

THIS REPORT HAS BEEN DELIMITED  
AND CLEARED FOR PUBLIC RELEASE  
UNDER DOD DIRECTIVE 5200.20 AND  
NO RESTRICTIONS ARE IMPOSED UPON  
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.