

**UNCLASSIFIED**

**AD NUMBER**

**AD152668**

**CLASSIFICATION CHANGES**

TO: **unclassified**

FROM: **confidential**

**LIMITATION CHANGES**

TO:

**Approved for public release, distribution  
unlimited**

FROM:

**Distribution authorized to U.S. Gov't.  
agencies and their contractors;  
Administrative/Operational Use; DEC 1957.  
Other requests shall be referred to Army  
Armament Research and Development Center,  
Dover, NJ.**

**AUTHORITY**

**ARRADCOM ltr 8 Jul 1982; ARRADCOM ltr 8  
Jul 1982**

**THIS PAGE IS UNCLASSIFIED**

THIS REPORT HAS BEEN DELIMITED  
AND CLEARED FOR PUBLIC RELEASE  
UNDER DOD DIRECTIVE 5200.20 AND  
NO RESTRICTIONS ARE IMPOSED UPON  
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A


APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED,

AD 152668

AUTHORITY:

ARRADCOM

174 8 JUL 82



## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

**BEST  
AVAILABLE COPY**

A  
D  
**152608**

# Armed Services Technical Information Agency

ARLINGTON HALL STATION  
ARLINGTON 12 VIRGINIA

FOR

MICRO-CARD

CONTROL ONLY

**1 OF 1**

NOTICE: WHEN GOVERNMENT OR OTHER DRAWINGS, SPECIFICATIONS OR OTHER DATA  
ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED  
GOVERNMENT PURCHASE OPERATION, THE U. S. GOVERNMENT THEREBY INCURS  
NO RESPONSIBILITY, NOR ANY OBLIGATION WHATSOEVER; AND THE FACT THAT THE  
GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE  
DRAWINGS, SPECIFICATIONS, OR OTHER DATA IS NOT TO BE REGARDED BY  
IMPLICATION OR OTHERWISE AS IN ANY MANNER LICENSING THE HOLDER OR ANY OTHER  
PERSON OR CORPORATION, OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE,  
OR COMMERCIALIZE ANY INVENTION THAT MAY IN ANY WAY BE RELATED THERETO.

**QUARTERLY REPORT**

**NNC-Q-3**

**Contract DAI-19-020-501-ORD-(P)-58**

**NATIONAL NORTHERN CORPORATION  
West Hanover, Massachusetts**

AD No. 152668  
ACT A FILE COPY

This document is the property of the United States  
Government. It is furnished for the duration of the contract and  
shall be returned when no longer required, or upon  
recall by ASTIA to the following address:

Armed Services Technical Information Agency, Arlington Hall Station  
Arlington 12, Virginia

**NOTICE: THIS DOCUMENT CONTAINS INFORMATION AFFECTING THE**  
**NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANING**  
**OF THE ESPIONAGE LAWS, TITLE 18, U.S.C., SECTIONS 793 and 794.**  
**THE TRANSMISSION OR THE REVELATION OF ITS CONTENTS IN**  
**ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.**

**Best  
Available  
Copy**

**Confidential**

**THE EFFECT OF ALTITUDE ON DETONATION  
AND FRAGMENT VELOCITY**

**QUARTERLY PROGRESS REPORT 2005-3**

**Contract DAI-19-020-501-ORD-(P)-58**

**TENTH QUARTERLY REPORT**

**NNC-Q-3**

**September, October, November 1957**

**Copy No. 07**

**NATIONAL NORTHERN CORPORATION**

**West Hanover, Massachusetts**

**Confidential**

**58AA 603**

**A Subsidiary of American Potash and Chemical Corporation**

Confidential

NATIONAL NORTHERN CORPORATION  
West Hanover, Massachusetts

THE EFFECT OF ALTITUDE ON DETONATION  
AND FRAGMENT VELOCITY

QUARTERLY PROGRESS REPORT 2005-3

Contract DAI-19-020-501-ORD-(P)..58

TENTH QUARTERLY REPORT

NNC-Q-3

September, October, November 1957

Submitted by:

Arthur W. O'Brien, Jr.  
Charles W. Plummer  
Vasil Philipchuk

Approved by:

*C. M. Saffer, Jr.*

C. M. Saffer, Jr.  
Technical Director

Approved by:



S. J. Porter  
Vice President and  
General Manager

NOTICE: This document contains information affecting the National Defense of the United States within the meaning of the Espionage Laws, Title 18, U. S. Code, Sections 793 and 794. Its transmission or the revelation of its contents in any manner to unauthorized persons is prohibited by law.

Confidential

A Subsidiary of American Potash and Chemical Corporation

CONFIDENTIAL

### 1.0 INTRODUCTION

This is a Quarterly Report of testing accomplished during the period 10 September 1957 through 9 December 1957 for Picatinny Arsenal under supplemented Contract DAI-19-020-501-ORD-(P)-58 and is designated NNC-Q-3.

The first four Quarterly Reports under this contract, NN-Q-1 through NN-Q-4, are concerned with free-air blast testing, and the results are summarized in National's Summary Report NN-P-34. The fifth and sixth Quarterly Reports describe the work on various RDX systems. The seventh and eighth Quarterly Reports describe preliminary determinations for National's current investigation of detonation and fragment velocity of various explosive systems at several simulated altitudes. The ninth Quarterly Report includes the initial results of National's work on velocity of detonation at various simulated altitudes. The results of National's work to date are summarized in the present report.

National Northern Corporation gratefully acknowledges the guidance and assistance of Picatinny Arsenal personnel in this investigation.

### 2.0 OBJECT OF TESTS

The task assigned under this contract, as supplemented, is a survey of various explosive systems for the purpose of determining any change in detonation and fragment velocity with changes in simulated altitude, charge diameter, and degree of confinement of the explosive.

The study of detonation velocity is described in Paragraphs 3.0, 4.0, 5.0 and 6.0 of this Report. The investigation of fragment velocity is detailed in Paragraph 7.0, 8.0, 9.0 and 10.0.

### STUDY OF DETONATION VELOCITY

#### 3.0 CHARGE DATA

3.1 In order to survey possible changes in behavior of various  
Confidential

explosive systems with changes in simulated altitude, charge diameter, and degree of confinement of the explosive, a number of specific conditions have been taken as starting points. In each combination of conditions, five measurements of the detonation velocity of the explosive system are made.

3.2 The explosive systems included in these tests are TNT, H-6, 70/30-RDX/TNT, 70/30-HMX/TNT, and MOX-2B.

3.3 These systems are studied at pressures of 760, 326, 60, and 13 millimeters of mercury, corresponding to simulated altitudes of ground, 30,000, 60,000, and 90,000 feet.

3.4 These systems are tested in cylindrical columns, one and two inches in diameter by eighteen and seven inches long, respectively. These represent estimates of the maximum explosive load that can be tolerated in National's altitude chamber.

3.5 These explosives, with the exception of MOX-2B, are measured for detonation velocity in two conditions of confinement. In one case, bare charges are used; and, in the other, the explosive is loaded in one-quarter-inch-thick steel tubing of appropriate inside diameter. MOX-2B will not sustain detonation in unconfined columns of the selected diameters, and an increase in diameter would require reduction in the length of column to maintain the maximum charge weight allowed in National's chamber. Columns shorter than those now used would cause the experimental error to be too large.

3.6 Subsequent to initiation of the firing program, some difficulty was experienced in detonating TNT columns, unconfined, in these diameters. This difficulty has since been ascribed to the method of casting, in which the molten TNT was poured into heavy paper sleeves. The TNT was finally cast in steel sleeves and removed from the sleeves for testing. These columns were found to

detonate completely.

#### 4.0 TEST EQUIPMENT

4.1 The detonation velocity is measured by timing the passage of the detonation zone over a known column distance. This distance is measured between two electrical probes, each consisting of open-end wire pairs. The passage of the detonation zone closes the open-end pairs and, with associated circuits, generates a sharp pulse. The pulses generated are applied to the start-stop circuits of an electronic counter-chronograph. The counter is the Potter Model 471 operating at 8 megacycles.

4.2 Tests at simulated altitudes are accomplished in National's largest altitude chamber. The chamber has approximate inside dimensions of 12x14x9 feet and may be evacuated to a simulated altitude of 120,000 feet (3 mm. Hg) by a Kinney KD-780 vacuum pump run by a forty horsepower electric motor. Those tests run at "ground" (760 mm. Hg) are accomplished at National's Halifax Testing Range.

#### 5.0 TEST RESULTS

5.1 The tables following include all of the data obtained to date. In these tables, charge density is determined by geometry and net charge weight. The eighteen-inch by one-inch cylinder is calculated to have a volume of 232 cubic centimeters and the seven-inch by two-inch cylinder a volume of 360 cubic centimeters.

## Confidential

<u>Altitude</u> <u>(feet</u> <u>mm Hg.)</u>	<u>Average</u> <u>Charge</u> <u>Density</u> <u>(gm/cc)</u>	<u>Measured</u> <u>Segment</u> <u>(meters)</u>	<u>Measured</u> <u>Time</u> <u>(microseconds)</u>	<u>Velocity</u> <u>of</u> <u>Detonation</u> <u>(meter/seconds)</u>
---	---	--	---	---

H-6, unconfined, in one-inch diameter columns

Ground (760-764 mm Hg.)	1.80 1.78 1.78 1.81 1.79	.302 .295 .303 .305 .303	41.1 41.1 40.9 40.9 41.1	7350 7180 7410 7460 7370
30,000 (226 mm Hg.)	1.81 1.79 1.79 1.81 1.80	.305 .302 .302 .305 .305	40.6 41.2 40.9 40.9 40.9	7510 7330 7380 7460 7460
60,000 (60 mm Hg.)	1.80 1.79 1.79 1.80 1.79	.302 .305 .302 .303 .300	39.2 40.6 40.4 41.1 40.5	7700 7510 7480 7370 7410
90,000 (13 mm Hg.)	1.78 1.78 1.79 1.78 1.79	.302 .302 .302 .303 .290	41.0 41.0 42.1 40.6 41.4	7360 7360 7170 7470 7000

H-6, unconfined, in two-inch diameter columns

Ground (760-764 mm Hg.)	1.83 1.77 1.84 1.75 1.81	.099 .100 .102 .102 .100	14.0 14.5 14.8 15.1 14.8	7070 6900 6890 6750 6760
30,000 (226 mm Hg.)	1.77 1.78 1.84 1.81	.099 .099 .102 .102	14.0 14.2 15.0 14.7	7070 6970 6800 6940
60,000 (60 mm Hg.)	1.97 1.78	.102 .099	14.4 14.1	7080 7020

Confidential

Altitude (feet) (mm Hg.)	Average Charge Density (gm/cc)	Measured Segment meters	Measured Time (microseconds)	Velocity of Detonation (meter/seconds)
--------------------------------	---	-------------------------------	------------------------------------	---

H-6, unconfined, in two-inch diameter columns (Cont'd)

60,000 (60 mm Hg.)	1.78 1.80 1.83	.102 .102 .102	14.9 14.5 14.4	6840 7030 7080
90,000 (13 mm Hg.)	1.78 1.84 1.76 1.84 1.81	.099 .102 .099 .102 .102	14.2 14.6 14.9 14.1 14.2	6970 6990 6840 7230 7180

H-6, confined in 1/4-inch wall steel tubing, one inch diameter columns

Ground (760-764 mm Hg.)	1.72 1.72 1.72 1.66 1.71	.305 .305 .303 .305 .303	42.0 42.0 42.0 43.3 42.9	7260 7260 7210 7050 7180
----------------------------	--------------------------------------	--------------------------------------	--------------------------------------	--------------------------------------

H-6, confined in 1/4-inch-wall steel tubing, two-inch diameter columns

Ground (760-764 mm Hg.)	1.78 1.78 1.77 1.78 1.78	.102 .102 .102 .102 .102	13.9 13.9 14.4 13.6 13.7	7340 7340 7080 7500 7450
30,000 (226 mm Hg.)	1.77 1.78 1.79 1.79 1.77	.103 .102 .103 .102 .103	13.8 14.0 13.9 14.0 14.0	7500 7260 7430 7260 7370
60,000 (60 mm Hg.)	1.78 1.78 1.79 1.79 1.77	.103 .103 .103 .103 .103	12.4 13.9 14.1 14.1 14.1	8330 7500 7300 7300 7300
90,000 (13 mm Hg.)	1.78 1.78 1.78 1.78 1.78	.103 .102 .102 .103 .103	14.0 13.6 13.8 13.1 13.9	7370 7460 7390 7860 7430

Confidential

6.

<u>Altitude (feet)</u> <u>(mm Hg.)</u>	<u>Average Charge Density</u> <u>gm/cc</u>	<u>Measured Segment meters</u>	<u>Measured Time</u> <u>(microseconds)</u>	<u>Velocity</u> <u>of</u> <u>Detonation</u> <u>(meter/seconds)</u>
---	---	--	---	---

HMX/TNT, - 70/30, unconfined in two-inch diameter columns

Ground (760-784 mm Hg.)	1.75 1.76 1.79 1.74 1.80	.098 .100 .100 .102 .102	13.5 14.6 13.1 12.9 13.1	7290 6840 7620 7890 7740
30,000 (223 mm Hg.)	1.80 1.81 1.83 1.78 1.85	.102 .102 .102 .102 .102	13.2 13.5 13.1 13.2 13.2	7730 7560 7790 7730 7730
60,000 (60 mm Hg.)	1.82 1.76 1.76 1.78 1.81	.099 .102 .099 .102 .102	13.1 13.6 13.2 13.1 12.9	7560 7500 7500 7790 7910
90,000 (13 mm Hg.)	1.74 1.80 1.79 1.75 1.77	.102 .102 .102 .102 .099	14.9 12.9 13.0 12.8 13.6	7240 7910 7850 7970 7280

HMX/TNT-70/30, unconfined in one-inch diameter columns

30,000 (223 mm Hg.)	1.63 1.60 1.61	.305 .306 .303	38.1 38.0 38.1	7990 8020 7950
60,000 (60 mm Hg.)	1.71 1.73 1.65 1.68	.302 .305 .306 .306	38.4 38.0 38.5 38.4	7860 8020 8540 7940
90,000 (13 mm Hg.)	1.69	.305	38.4	7940

Confidential

## Confidential

Altitude <u>feet</u> <u>(mm Hg.)</u>	Average Charge Density <u>(gm/cc)</u>	Measured Segment <u>(meters)</u>	Measured Time <u>(microseconds)</u>	Velocity of Detonation <u>(meter/seconds)</u>
--	--	--	---	--

HMX/TNT, - 70/30, confined in 1/4 inch-wall steel tubing, two-inch diameter columns

Ground (760-764 mm Hg.)	1.75 1.59 1.63 1.73 1.73	.102 .102 .102 .103 .103	12.8 13.1 13.2 13.1 12.9	7970 7790 7730 7860 8010
30,000 (226 mm Hg.)	1.72 1.74 1.74 1.74 1.68	.102 .102 .102 .102 .127	13.1 12.6 12.8 13.0 16.0	7790 8100 7970 7850 7940
60,000 (60 mm Hg.)	1.73 1.74 1.76 1.65 1.75	.102 .103 .102 .102 .102	13.1 12.6 12.8 13.1 13.2	7790 8170 7970 7790 7730
90,000 (13 mm Hg.)	1.72 1.73 1.73 1.74 1.75 1.59	.127 .103 .102 .102 .102 .102	16.0 12.6 13.2 12.7 13.0 13.3	7940 8170 7730 8030 7850 7670

RDX/TNT, - 70/30, unconfined, in one-inch diameter columns

Ground (760-764)	1.78 1.72 1.58 1.75 1.76	.305 .302 .305 .302 .303	38.1 36.1 37.6 38.0 37.6	8000 8360 8110 7950 8060
30,000 (226 mm Hg.)	1.68 1.66 1.74	.306 .305 .302	37.9 36.0 38.0	8070 8470 7850
60,000 (60 mm Hg.)	1.70 1.72 1.61 1.62 1.44	.302 .305 .302 .305 .305	37.5 37.8 37.2 36.5 37.7	8050 8070 8120 8360 8090
90,000 (13 mm Hg.)	1.72 1.71 1.62	.305 .305 .302	38.1 38.0 37.9	8000 8030 7970

Confidential

<u>Altitude (feet)</u>	<u>Average Charge Density (gm./cc.)</u>	<u>Measured Segment meters</u>	<u>Measured Time (microseconds)</u>	<u>Velocity of Detonation (meter/seconds)</u>
----------------------------	---	--	---	---

RDX/TNT, - 70/30, unconfined, in one-inch diameter columns (Cont'd)

80,000 (13 mm Hg.)	1.62 1.73	.305 .302	38.4 37.9	7940 7970
-----------------------	--------------	--------------	--------------	--------------

RDX/TNT, - 70/30, unconfined, in two-inch diameter columns

Ground (760-764 mm Hg.)	1.82	.102	12.6	8050
----------------------------	------	------	------	------

30,000 (226 mm Hg.)	1.81 1.81 1.76 1.83 1.78	.103 .099 .099 .102 .102	13.0 13.2 12.2 13.0 13.4	7920 7500 8110 7850 7610
------------------------	--------------------------------------	--------------------------------------	--------------------------------------	--------------------------------------

60,000 (60 mm Hg.)	1.82 1.82 1.77 1.84 1.78	.099 .103 .102 .102 .099	12.6 12.9 12.8 12.6 12.5	7860 7980 7960 8010 7920
-----------------------	--------------------------------------	--------------------------------------	--------------------------------------	--------------------------------------

80,000 (13 mm Hg.)	1.82 1.84 1.84 1.76 1.80	.102 .099 .099 .099 .096	13.2 12.5 12.6 12.6 13.4	7730 7920 7860 7860 7160
-----------------------	--------------------------------------	--------------------------------------	--------------------------------------	--------------------------------------

RDX/TNT, - 70/30, confined in 1/4-inch-wall steel tubing, one-inch diameter columns

Ground (760-764 mm Hg.)	1.72 1.74 1.57 1.71 1.73 1.61 1.62	.305 .305 .305 .305 .305 .305 .305	38.3 38.5 38.0 38.5 38.4 38.1 38.0	7960 7920 8030 7920 7940 8010 8030
----------------------------	--	--	--	--

30,000 (226 mm Hg.)	1.64	.302	37.9	7960
------------------------	------	------	------	------

60,000 (60 mm Hg.)	1.64 1.63	.305 .305	37.9 38.0	8050 8020
-----------------------	--------------	--------------	--------------	--------------

80,000 (13 mm Hg.)	1.66 1.62 1.64	.307 .305 .305	37.9 37.9 37.9	8100 8070 8050
-----------------------	----------------------	----------------------	----------------------	----------------------

(Confidential)

3.

Altitude feet (mm Hg.)	Average Charge Density (gm/cc)	Measured Segment meters	Measured Time (microseconds)	Velocity of Detonation (meter/seconds)
------------------------------	---	-------------------------------	------------------------------------	---

RDX/TNT, - 70/30, confined in 1/4-inch-wall steel tubing, one-inch diameter columns  
(Cont'd)

90,000 (13 mm Hg.)	1.63	.305	38.0	8020
	1.64	.305	37.9	8050
	1.63	.305	37.9	8050

RDX/TNT, - 70/30, confined in 1/4-inch-wall steel tubing, two-inch diameter columns

Ground (760-764 mm Hg.)	1.70	.102	13.2	7730
	1.72	.102	13.1	7790
	1.72	.101	13.0	7770
	1.72	.102	13.9	7340

30,000 (226 mm Hg.)	1.72	.102	12.8	7970
	1.72	.102	12.6	8100
	1.72	.102	13.5	7560
	1.72	.102	12.8	7970
	1.72	.102	15.1	6750

60,000 (60 mm Hg.)	1.70	.102	12.6	8090
	1.74	.102	12.5	8160
	1.73	.102	12.6	8090
	1.72	.102	12.9	7910
	1.71	.102	13.1	7790

90,000 (13 mm Hg.)	1.71	.102	12.8	7970
	1.70	.102	12.6	8100
	1.67	.102	12.6	8100
	1.70	.102	13.0	7650
	1.70	.102	12.7	8030

MOX-2B, confined in 1/4-inch-wall steel tubing, two-inch diameter columns

Ground (760-764 mm Hg.)	2.12	.103	22.3	4630
	2.12	.103	20.9	4940
	2.12	.102	22.1	4590
	2.12	.103	22.1	4660
	2.12	.103	21.4	4820

TNT, unconfined, in two-inch diameter columns

Ground (760-764 mm Hg.)	1.74	.100	19.5	5130
	1.76	.102	19.9	5110

Confidential

Confidential

10.

<u>Altitude</u> <u>Feet</u> (mm Hg.)	Average Charge Density (gm/cc)	Measured Segment meters	Measured Time (microseconds)	Velocity of Detonation (meter/seconds)
--	---	-------------------------------	------------------------------------	---

TNT, unconfined, in two inch diameter columns (Cont'd)

Ground	1.78	.102	18.5	5500
(760-764 mm Hg.)	1.76	.100	19.3	5200
	1.73	.103	19.0	5430

TNT, confined in 1/4-inch-wall steel tubing, one-inch diameter columns

Ground	1.56	.305	44.7	6820
(760-764 mm Hg.)	1.59	.305	45.5	6850
	1.61	.303	44.7	6780
	1.60	.304	44.7	6800
	1.62	.305	44.5	6850
	1.61	.305	44.4	6870

30,000	1.00	.305	46.9	6500
(226 mm Hg.)	1.01	.305	46.9	6500
	1.59	.305	45.4	6720
	1.53	.305	45.4	6720

60,000	1.58	.305	44.8	6810
(60 mm Hg.)				

90,000	1.56	.305	44.8	6810
(13 mm Hg.)	1.59	.305	44.7	6820
	1.59	.305	44.7	6820
	1.58	.305	44.8	6810
	1.55	.305	44.8	6810
	1.64	.305	44.3	6880
	1.62	.305	41.5	7350
	1.57	.305	42.3	7210

TNT, confined in 1/4-inch-wall steel tubing, two-inch diameter columns

Ground	1.57	.102	15.4	6620
(760-764 mm Hg.)	1.57	.103	15.2	6780
	1.61	.102	15.2	6710
	1.58	.102	15.2	6710

60,000	1.58	.102	15.8	6460
(60 mm Hg.)	1.59	.102	15.9	6420
	1.58	.102	15.6	6540
	1.58	.102	15.4	6620
	1.60	.102	15.5	6580

Confidential

Altitude (feet) as in fig.	Average Charge Density (gm/cc)	Measured Segment (meters)	Measured Time (microseconds)	Velocity of Detonation (meter/seconds)
<u>TNT, confined in 1/4-inch-wall steel tubing, two-inch diameter columns (Cont'd)</u>				
90,000 (13 mm Hg.)	1.61	.102	15.6	6540
	1.60	.102	15.6	6540
	1.59	.102	15.6	6540
	1.58	.102	15.6	6540
	1.59	.102	15.6	6580

## 6.0 DISCUSSION OF RESULTS

6.1 National has estimated the experimental error to be  $\pm 3\%$ , maximum, due to three major sources of error:

- (a) Non-uniform density in the charges
- (b) Non-linear velocities over the measured segment
- (c) Precision of measurement in both time and distance

6.2 Density variations within a single column are not readily detected.

The test charges have been inspected by X-ray photography to eliminate any with major flaws.

6.3 Non-linear velocities of detonation occur where steady-state detonation reaction is not established. This is corrected by allowing ample "run-up" explosive column ahead of the segment to be measured. The weight limit and diameter requirements of the test charges determine the length of the charges and restrict the "run-up" column.

6.4 The error in measurement has been estimated to be less than 1%, maximum. Linear distance is accurate within one millimeter and time within one-tenth microsecond.

## STUDY OF FRAGMENT VELOCITY AT SIMULATED ALTITUDE

### 7.0 OBJECTIVE

7.1 The object of this phase of the program is the investigation of the effect of altitude on the velocity fragments produced from steel cylinders by charges of the following explosives:

TNT  
H-6  
MOX-2B  
70/30 - RDX/TNT  
70/30 - HMX/TNT

The four altitudes under investigation are ground, 30,000, 60,000, and 90,000 feet.

### 8.0 Test Items

8.1 Steel cylinders of two configurations are used. Both sizes are fabricated from AISI 1015 steel. One is 1" I.D. x 18" long with a 1/4" wall thickness. The other is 2" I.D. x 7" long with a 1/4" wall thickness.

### 9.0 TESTS

9.1 The major portion of the test program has been completed and velocities obtained on a 6-foot radial distance by counter-chronograph. Accuracy difficulties were encountered at the higher altitudes. Causes are being traced in order to obtain reliable data. Data obtained by the electrical method have been checked by high-speed photography and the two methods found to be compatible at ground level.

### 10.0 COMPUTATIONS

10.1 Theoretical velocities are being computed with known Guernsey constants for ground level velocities for H-6, TNT, and MOX-2B. New values of Guernsey constants of the 70/30 mixtures will be obtained by computation from observed velocities.

Confidential

13.

11.0 FUTURE WORK

The major part of this program has been completed. The entire program with the results of the remaining tests and fragment calculations will be reviewed and summarized in a final report.

Confidential

Confidential

QUARTERLY DISTRIBUTION LIST

Copy 100.

Addressee

Commanding Officer  
Picatinny Arsenal  
Dover, New Jersey  
Attn: Samuel Feltman Amm. Labs.  
Contract Section.....<sup>1, 2, 3</sup>

Contracting Officer  
Boston Ordnance District  
Army Base  
Boston 10, Massachusetts.....<sup>4</sup>

Chief of Ordnance  
Dept. of the Army  
Washington 25, D. C.  
Attn: ORDTA.....<sup>5</sup>

) Director, Armed Services Technical Information Agency (AST)  
Document Service Center  
Knott Building - Dayton 421 Station  
Dayton 2, Ohio.....<sup>6, 7</sup>

Commanding Officer  
Picatinny Arsenal  
Dover, N. J.  
Attn: Samuel Feltman Amm. Labs.  
High Explosives Section, Mr. P. B. Tweed.....<sup>8</sup>

Confidential