

E.A. POLUMBUS, Je

AN RIMEND

Ûz

i.

SUITE 210, G. A. JOHNSON BLDG.

• TABOR 5-6193

DENVER 2. COLORADO

٠

Ţ

FINAL REPORT ON, DRILLING OF PRESSURE INJECTION DISPOSAL WELL ROCKY MOUNTAIN ARSENAL DENVER, COLORADO

Prepared for Department of the Army U.S. Army Engineer District, Omaha Corps of Engineers

Prepared by E. A. Polumbus, Jr., and Associates, Inc. Design and Management Engineers Denver, Colorado - November 30, 1961

Contract DA-25-066-ENG-6033

APR 4



CONTENTS (Detailed Index Precedes Each Section)

14 - A. 17 - A.A.

SECTION	TITLE	DESCRIPTION
1	PURPOSE	Brief statement of purpose of report.
11	ABSTRACT	Summary of well's objectives, operations and results.
111	DESIGN CONSIDERATIONS	Condensation of salient aspects of "Final Design Analysis." In- cludes summary of historical development and design specifi- cations.
14	GEOLOGY	Discussion of structure, forma- tions, and lithology encountered during drilling of well.
V	PHYSICAL OPERATIONS	Discussion of entire operation from inception to final wellhead installation. Includes chronolo- gical synopsis and detailed dis- cussions of individual drilling, testing and completion charac- teristics and/or operations.
VI	DEVIATIONS FROM DESIGN	Discussion of major deviations from the original design empha- sizing conditions encountered that caused the deviation.
VII	RESUME OF ORGANIZATIONAL FUNCTIONS	Discussion of the channels of communication and authority and acknowledgement of the companies and personnel working on the project.
vш	PROSPECTIVE INJECTION RESERVOIRS	General considerations applicable in the selection and discussions of the observed and interpreted physi- cal characteristics of prospective injection reservoirs.
IX	CURSORY CONSIDERATIONS FOR INJECTION WELL OPERATIONS	General discussion of present and future operational considerations and possible problems.

E & FOLLIMBUS IN AND ASSULTATE INC.

. . .

LIST OF FIGURES

En las mais de las

ų.

l

ł

Į

. .

5

Figure No.

Frontispiece - Well bore sketch & stratigraphic section	
Location Map	1
Development Map	2
Structure Map of Southern Portion of Denver Basin	3
Diagrammatic Cross Section	4
Detail "A"	4A
Pre-Fountain Geologic Column	5
Drilling Analysis Chart	6
Casing and Hole Details	7
Well Head Installation	8
Bowen Junk Basket	9
Graphical Representation of Formation	
Evaluation Data	10
Casing Details	11
Schematic Diagram - Three-stage Cementing Operation	12
Special Subsurface Equipment	13

-ii-

T A FOUNDUS OF AND A SOCIATE. HE

LIST OF TABLES

. .

.

-

育にそう

.

7 - 1. 1

	I ADIC NO
Stratigraphic Section	1
Core Description	2
Rig Description , , , , , , , , , , , , , , , , , , ,	3
Summary - Drilling and Coring Performance	4
Hole Deviation	õ
Drilling Mud Record	6
Summary of Cores	7
Coring Equipment Summary	8
Drill Stem Test Report, Test No. 1	g
Drill Stem Test Report, Test No. 2	10
Drill Stem Test Report, Test No. 3	11
Drill Stem Test Report, Test No. 4	12
Drill Stem Test Report, Test No. 5	13
Drill Stem Test Report, Test No. 6	
Drill Stem Test Report, Test No. 7	15
Drill Stem Test Report, Test No. 8	14
Drill Stem Test Report, Test No. 9	10
Drill Stem Test Report, Test No. 10	• (
Drill Stem Test Report, Test No. 11	40
Drill Stem Test Report. Test No. 12	19
	20

-111-1 А. ОСЦИНИЈСТИК АНСТАТИ 1 А. ОСЦИНИЈСТИК АНСТАТИ ОТ 1991 - 199

	Table No.
Drill Stem Test Report, Test No. 13	21
Drill Stem Test Report, Test No. 14	22
Core Analysis Results (Core Laboratories, Inc.)	23
Logging Summary,	24
Casing and Hole Summary	25

.

.

ŧ,

South and the second

 l

ļ

Į

I

-iv-

E A FOUNDER H AND ASSOCIATES IN

الارد من الدين المراجع المراجع المراجع المراجعين المراجع المراجعين المراجع المراجعين المراجع المراجع المراجعين

VOLUME II

1

1

Chronological Log

1

Daily Engineering Report

VOLUME III

Sample Description

Pipe Measurement Record

Electric Logs

Baroid Mud Log

Baroid Core Analysis



. .

PURPOSE

The purpose of this report is to provide the United States Army Corps of Engineers, Omaha District, and the United States Army Chemical Corps with a readily accessible, discernible, and definitive record of all data, activities and events relating to the drilling and completion of the Rocky Mountain Arsenal Pressure Injection Disposal Well. It is intended that this report serve as a comprehensive reference, sufficiently complete to cover minute details, and yet arranged in such a manner that the most salient aspects of the operation may be examined independent of details. The report is presented in three volumes. Volume I includes discussions of the operation from the design phase through the final completion. Detailed statistical and tabular data are included in Volumes II and III.

It is not the intent of this report to discuss the initial injection operations. This is to be covered in detail in a subsequent report of the initial fluid injection characteristics.



ABSTRACT

The Rocky Mountain Arsenal Pressure Injection Disposal Well was drilled for the United States Army Chemical Corps by the United States Army Corps of Engineers, Omaha District. The firm of E. A. Polumbus, Jr., and Associates, Inc., served as consulting and management engineers and consulting geologists to the Corps of Engineers in the design, drilling, and completion of the well. The well was drilled to provide access to underground strata which could be used as waste disposal reservoirs.

Drilling operations on the well, which is located on the Rocky Mountain Arsenal grounds, commenced on March 10, 1961. Loffland Brothers Company was contracted to drill the well. The well was drilled to a total depth of 12,045 feet terminating in crystalline rocks of pre-Cambrian Age. The drilling rig was released on September 28, 1961, and the construction phase of the drilling well operation was considered completed on November 30, 1961, when the well head equipment was installed and the well turned over to the Chemical Corps. This report covers the operation to this stage.

In the design and drilling of the well and in the identification, evaluation, protection, and testing of potential injection reservoirs, broad adaptations of tools, techniques and practices developed in the oil industry were required.

والمتعادية والمعاجر والمعرف والمعارية والمتعادية والمعادية والمعادية والمعادية والمعادية

Problems resulting from natural characteristics of the formations penetrated ranged in severity to economically serious and critically hazardous. Exposure to drilling fluids of the long shale section from 2,020 feet to 8,485 feet for a relatively long period of time, coupled with lost circulation in lower formations, created an intricate and difficult mud control problem as well as a keyscating problem. The highly fractured formations occurring frequently from 9, 600 feet to total depth resulted in coring difficulties, and a reduction in the desired number of drill stem tests as well as lost circulation problems. The quartzitic nature of the rocks below 9,600 feet resulted in slow penetration necessitating the use of a large number of drill collars to achieve high drilling weights, high bit consumption and high frequency of roundtrips to great depths with the crill string. Combinations of the above adverse drilling factors resulted in the necessity of setting the 8 5/8-inch long string of casing at 11, 171 feat instead of 11,400 feet. This in turn necessitated setting a 5 1/2-inch liner ir the open hole below the 8 5/8-inch casing for which no provision was made in the original program.

During the drilling of the well, all formations were critically examined, and where possible, those showing any potential as injection reservoirs were cored and drill stem tested. A total of 639 test of formation were cored and 14 formation tests were attempted. The injection reservoirs with the greatest indicated potential to accept fluids were found

> -3-A FORTUMBEN IN ANY ANY TATE ONE

below 9, 600 feet in fractured portions of the Lyons and Fountain formations and in the pre-Cambrian rocks.

To accommodate the specified injection volume of 400 to 800 gallons per minute at 2,000 psi surface injection pressure and to isolate effectively the potential injection reservoir from shallow fresh waterbearing beds, 20-inch casing was set at 135 feet; 13 3/8-inch casing at 2,020 feet; 8 5/8-inch casing at 11, 171 feet, and a 5 1/2-inch liner placed from 1.,007 feet to 11,975 feet. To insure complete isolation, each string of casing was sheathed with cement for its entire length. Injection of fluids is made through 5 1/2-inch tubing set in a packer at 8,998 feet.

The well was completed with the open hole section in the fractured pre-Cambrian rocks from 11, 975 to 12, 045 feet serving as the present injection zone. Preliminary injection tests showed the zone to be capable of initially accepting the desired volumes of fluid.

E & POLUVEUS JR AND ASSOCIATES INC

. 4 .

INDEX DESIGN CONSIDERATIONS (III)

Ĩ

÷

t

;

ļ

	Page
INTRODUCTION	5
OBJECTIVE DISPOSAL RESERVOIRS	7
CASING AND HOLE PROGRAM	7
MUD PROGRAM	8
EVALUATION PROGRAM	9

E A HOLUMBUS H AND ASSOCIATES INC

....

DESIGN CONSIDERATIONS

INTRODUCTION

Disposal of waste fluids from chemical plants at the Rocky Mountain Arsenal was first recognized as a problem of major consequence when it was found that unsealed evaporation pits permitted leakage into shallow aquifers, contaminating an important water supply near the surface. In order to meet this emergency the Chemical Corps of the U. S. Army scaled a large earthen pond, designated as Pond F (See Figure 1 for location) and commenced accumulating waste effluent into it. The rate at which the waste material accumulated exceeded the rate of evaporation to the extent that the capacity of Pond F was expected to be reached in late 1961. Alternative methods for handling these waste fluids on a more permanent basis in the future were considered by the Chemical Corps, and it was decided to drill a deep pressure injection disposal well near Pond F. The design and drilling of this well were assigned to the U. S. Army Corps of Engineers, Omaha District,

The feasibility of disposing of chemical waste fluids from industrial plants and refineries into subsurface reservoirs has been well established. It is not uncommon to seek suitable injection reservoirs at depths approaching 7,500 feet although the preponderance of wells drilled specifically for this purpose has been considerably shallower.



The design and drilling of a disposal well at the Rocky Mountain Arsenal involved broad adaptations of techniques, practices, and equipment employed in the petroleum industry. In like manner, the identification, evaluation, protection, and testing of potential injection reservoirs in the well required the application of drilling technology, petroleum engineering, and geological practices developed in the petroleum industry.

The Corps of Engineers, therefore, engaged the consulting petroleum engineering firm of E. A. Polumbus, Jr., and Associates, Inc., under an Architect Engineer type contract (Contract No. DA-25-066-eng-6033) to design the injection well, supervise the drilling, provide the necessary engineering and geological services, and manage the project.

The basic design specifications were to locate, evaluate, and provide access through a well bore to an underground reservoir or reservoirs near Pond F. The underground storage facilities were required to be capable of accepting partially treated waste fluids for a number of years at rates up to 800 gallons pe ' minute at a maximum surface injection pressure of 2,000 psi.

The proposed design for the Rocky Mountain Arsenal Pressure Injection Disposal Well was presented in the "Final Design Analysis" submitted to the U. S. Army Corps of Engineers, Omaha District, by E. A. Polumbus, Jr., and Associates, Inc., on July 5, 1960.

OBJECTIVE DISPOSAL RESERVOIRS

Eight geologic formations, or units, underlying the Arsenal grounds were considered as possible injection reservoirs. These are: the Hygiene sandstone, the Godell sandstone, the "J" sandstone, the Dakota sandstone, the Lakota sandstone, the Morrison formation, the Lyons formation, and the Fountain formation. The preliminary estimates indicated that a complete penetration of the Fountain formation, terminating in pre-Cambrian rocks, would require the drilling of an 11,400 foot well.

CASING AND HOLE PROGRAM

the sectors to

The casing and hole program set forth in the Final Design Analysis is summarized as follows:

Depth	Hole Size	Casing Size	Tubing Size
125'	24 "	20 "	
2,0001	17 1/2"	13 3/8"	
11,400'	11 "	8 5/8"	
9,8651			5 1/2"

Since the exact depths of the formations or the exact reservoir to be used for injection would not be known in advance, the program was based on setting the long string of casing to the predicted total depth at the top of the pre-Cambrian rocks with the tubing set at the top of the Fountain formation.

The selection of 5 1/2-inch tubing involved equating horsepower requirements as related to capital investment and operating costs of surface plant facilities versus well costs for the different casing programs. The basic specifications regarding injection rates and pressures versus the pressure drop in the tubing were an integral part of these considerations.

The selection of 5 1/2-inch tubing as the injection string established the requirement for 8 5/8-inch casing when the various mechanical limitations and tolerances were considered. The use of 8 5/8-inch casing in turn dictated the need for drilling an 11-inch hole.

The program requirements for the 13 3/8-inch and 20-inch casings likewise reflected the basic requirement for 5 1/2-inch tubing when all mechanical factors and an allowance for flexibility of the program were considered.

Since contamination and potential contamination of shallow potable water bearing sands with waste effluent was one of the principal factors influencing the decision to drill the Arsenal well, precautions against similar contamination in the well itself were taken. Thus, to prevent migration of waste fluids from lower injection horizons into the shallow sands through the annulus between the well bore and the casing, a program of placing cement behind each string of casing from the casing shoe to the surface of the ground was adopted.

MUD PROGRAM

The anticipated geologic section included a long shale interval from the surface to approximately 8, 200 feet, stratigraphically above the principal objective disposal reservoirs. With the overall economics of the

E A CELEMENT & ARE ARE SEE NO

disposal project as a dominating influence, a mud program was designed that within practical limits would prevent this shale section from swelling and caving during the long period it would be exposed while drilling and extensively testing the lower potential injection reservoirs. The mud program was designed also to minimize damage to potential injection zones. EVALUATION PROGRAM

A more elaborate program of coring, drillstem testing, electric logging, and other data accumulation was necessary in the Rocky Mountain Arsenal well than is normally followed in a well drilled for the sole purpose of obtaining hydrocarbon production. The Arsenal well not only required the identification of any hydrocarbon bearing beds, in order to avoid contamination with waste waters, but also required the gathering of data on all zones offering injection possibilities. All potential reservoir rocks had to be identified and evaluated as drilling progressed since this was a singular operation that could neither be repeated nor could information be substituted from other wells, because of the remotences of previous drilling operations in the area.

An examination of the cuttings samples, the various electric logs, the mud log record, and the drilling records were programmed to provide full coverage of the total interval of the well. For special evaluation of zones of particular interest fifteen cores totalling 750 feet of section and fourteen drillstem tests were scheduled.



Page

at water were

Į

Ī

Ī

I

I

à

1

К

I

Ţ

た

REGIONAL GEOLOGY	10
STRATIGRAPHIC GEOLOGY	11

E. A. FREEDARDERS OF AND AND FAIRS INC.

- 14

GEOLOGY

The following discussion is confined to basic geologic considerations regarding the regional geology, as well as the stratigraphic relationships and lithology of the strata which were encountered. More detailed discussions of physical geologic data and the application of these data to the problems in selecting injection reservoirs are included in the section of this report entitled "Prospective Injection Reservoirs."

REGIONAL GEOLOGY

and a lit solela to back some a nort

The Rocky Mountain Arsenal Pressure Injection Disposal Well was drilled approximately 12 miles northeast of the city of Denver, Golorado, (Figure 2). It is situated a short distance to the east of the axis of the Denver-Julesburg Basin. As determined from surface geological observations, shallow and deep well drilling, and geophysical surveys, the Denver-Julesburg Basin is a north-south trending "trough" or asymmetrical syncline. Strata which are exposed along the mountain front dip steeply eastward. On the east flank of the basin, the strata dip gently westward from the plains of Nebraska and eastern Golorado. As shown on Figure 3 the disposal wellies near the structurally lowest part of the basin, and where the greatest thickness of sedimentary rocks is known to be present.

The Front Range of the Rocky Mountains came into being near the close of the Cretaceous period. As the mountains were formed, the mountain block was elevated and thrust castward over the sediments of the adjacent plains. The Cretaceous and older sedimentary rocks of the basin are thus separated from the pre-Cambrian crystalline rocks of the mountain uplift by a fault of system of faults which extends from Ganyon City, Colorado, northward to the Wyoming-Colorado state boundary and beyond. At places, the stratigraphic displacement along this fault exceeds 10,000 feet. The diagrammatic cross sections (Figures 4 and 4A) show the structure at the mountain front and the relationship between the subsurface rocks at the Arsenal well and the strata which are exposed at the mountain front.

STRATIGRAPHIC GEOLOGY

As the well was being drilled, samples of drill cuttings were taken from the mud stream, washed, and saved at ten foot or lesser intervals. Rock cores were also cut at selected intervals. The sample cuttings were immediately examined with a binocular microscope and under fluorescent light by the well-site geologist. Detailed lithologic descriptions of the sample cuttings are presented in Volume III of this report. The lithology of the cores is described with the samples, and also in Table 2 of Volume I.

Data from the samples and cores, together with interpretations of electric and drilling time logs, provide fundamental information regarding the character and thickness of the formations penetrated in the well. The names and depths of the formations penetrated are shown on Table 1. Brief descriptions of the character of these formations are given in the following paragraphs:

<u>The surface sediments</u> at the well site are recent soils which form a thin cover over windblown sands and water-laid gravels and shales of Pleistocene Age. Below the Pleistocene sediments is a series of poorly consolidated sandstones, arkoses, and dark gray shales of early Tertiary and latest Gretaceous Age. These materials comprising these beds were derived in a large part from the rocks which were eroded from the uplifted mountain block which lay to the west. The rock debris was carried eastward by flowing streams and was deposited in lakes and low lands east of the mountains. These sediments are called the <u>Arapahoe Formation</u>, and with the surface and Pleistocene beds comprise the upper-most 460 feet of strata drilled in the well.

The Lavamie Formation of Upper Cretaceous Age was penetrated in the disposal well between 460 and 1,250 feet in depth. It is composed of interbedded fine gray sandstones and dark gray and carbonaceous shales and some coal beds. The Laramie Formation grades downward into the Fox Hills Formation which was found between 1,250 and 1,480 feet in depth. <u>The Fox Hills Formation</u> is principally a buff, friable, porous sandstone with some sandy shale and clay shale. The Fox Hills, together with the sandstones which occur in the overlying sediments are important sources of potable water in the vicinity of the Arsenal and the city of Denver.

Immediately below the sandstones which yield fresh potable water (surface to 1, 480 feet), there is a thick series of relatively impermeable

-12-

shales and limey shales of Gretaceous Age. These strata effectively segregate the shallow water-bearing sand-tones from deeper porous strata into which waste fluids may be injected in the future. Between the depths of 1, 480 feet and c, 485 fest in the Arsenal well, the Pierre shale (1, 480 to 7, 710 ft.), the Niobrara shale (7, 710 to 8, 978 ft.) and the Carlile shale, the Greenhorn limestone, and the Graneros shale (8, 978 to 8, 485 ft.) constitute an impervious barrier separating the water sandstones and the potential injection reservoirs.

The Pierre shale, 6,230 feet in thickness, is principally a black to dark gray shale of marine origin. At a depth of 5,448 feet in the Arsenal well, the <u>Hygiene sandy zone</u> was encountered. This zone at the Arsenal location is represented by a shaley sand of low permeability and porosity. The Niobrara shale is calcareous or chalky, light gray to gray in color and 368 feet thick. The Carlile shale is darker in color and less calcareous than the Niobrara; the Greenhorn limestone is dense, shaley, and gray to brown in color; the Graneros shale is black, micaceous, and contains thin beds of bentonite near the base. These latter three formations are all marine in origin and aggregate 407 feet in thickness in the Arsenal well. They are sometimes considered as a unit and are then called the "Benton Formation." <u>The Codell sandstone</u>, which is known to be erratically developed, was missing in the well.

The "J" sandstone, the principal oil producing sandstone of the Denver Basin, was the first of the objective sandstones encountered which



showed any significant development. In the Arsenal well it occurs in the interval, 8, 485 to 8, 605 feet, immediately underlying the Graneros shale. The upper 45 feet of this unit consists of quartzitic sandstone showing very slight oil staining. The remaining part of the "J" was found to be irregularly bedded and intermixed fine grained quartzitic sandstone and dark gray shale. Immediately below the "J" sandstone is a dark gray marine shale unit, 28 feet in thickness, called the Skull Creek Shale.

The Dakota and Lakota sandstones which were penetrated between 8, 633 and 8.786 feet underlie the Skull Creek shale and are the lowermost units of Lower Cretaceous Age. The upper sandstone (Dakota) is of fine to medium grain size and is hard to quartzitic. It is separated from the Lakota sandstone by black shales and thin sandy strata. The Lakota sandstone is 56 feet thick and is a fine grained gray, quartzitic sandstone which grades downward into a somewhat sandy dark gray bentonite shale. These two sandstones are oil productive in the northern portion of the Denver Basin, but are unproductive in the vicinity of the Arsenal well.

The Morrison Formation of Jurassic Age lies below the Lakota and was penetrated in the Arsenal well between 8, 786 and 8, 972 feet. It is composed of black, red, and green shales, with a few beds of limestone, hard white sandstone, and anhydrite. The Morrison does not produce oil or gas in the Denver Basin.

The Lykins Formation is Triassic in Age. It underlies the Morrison at depths of 8, 972 to 9, 532 feet. The predominant lithology of the Lykins is reddish silty shale. A 15-foot bed of fine grained quartzitic sandstone occurs at the top of the formation, and at the base there is an 80-foot section of interbedded anhydrite, dolomite, and red silty shale.

<u>The Lyons Formation</u> of Permian Age is 190 feet thick in the Arsenal well. It was penetrated between 9,582 and 9,772 feet. The cores and cuttings samples showed it to consist of fine grained, well cemented to quartzitic, orange colored sandstone interbedded with red to maroon shale. Some of the sandstone cores exhibited cross-bedding. Numero, s fractures were observed in the cores.

The Fountain Formation of Pennsylvanian Age is 2, 108 feet thick in the Arsenal well. It was penetrated in the interval 9, 772 to 11, 880 feet. The uppermost 110 feet of this formation consists of fine grained, feldspathic sandstones, siltstones, and maroon shales. Below this interval the sediments are primarily arkosic sandstones, grits, and pebble conglomerates which are irregularly interbedded with shales and silty shales, all red to reddish brown in color. The clastics are cemented by calcarcous material, by clay, or by a combination of both. Cores taken in the Fountain Formation revealed the presence of fracturing. Immediately below the Fountain Formation, a Regolith or "fossil soil" zone was penetrated from 11, 880 to 11, 895 feet. The regolith is composed primarily of weathered maroon to dark brown shale with a brown, fractured, quartzite bed forming the basal foot. The regolith is interpreted as being the ancient land surface upon which the Fountain Formation was deposited. (Figure 5) Between the base of the regolith and the top of the rocks which were identified as pre-Cambrian (14, 895 to 11, 950 feet) there is a 55-foot section of quartz conglomerate, purple shale and pink dolomite whose age is not as yet definitely determined. Lithologic comparison with rocks of similar stratigraphic position which crop out in the Colorado Springs region indicates that the strata in question are <u>Ordovician (?) or Cambrian (?)</u> in age. The presence of these beds in the Arsenal well represents the northernmost known occurrence of Paleozoic sediments older than the pre-Fountain regolith along the west flank of the Denver Basin.

1

第二日 たい 御長

The pre-Cambrian rocks penetrated in the well are of two types-the uppermost rock which was drilled from 1., 950 to 11, 970 feet has the characteristics of aweathered schist. (Figure 5) In the drill cuttings, it has the appearance of a bright green shale containing an abundance of copper-colored mica and clay minerals. Immediately below the weathered schist, from 11, 970 feet to 12, 045 feet which is the total depth of the well, a crystalline rock identified as pre-Cambrain hornblende granite gneiss containing an intrusive pegmatite was drilled and cored. A core taken in the gneiss section showed vertical fracturing.

INDEX PHYSICAL OPERATIONS (V)

. . . .

÷

ŝ

4

ł

1

Ĩ

CHRONOLOGICAL SYNOPSIS	17
Operations Prior to Drilling	17
Drilling	20
Surface to Intermediate Casing Point (2,020 feet).	20
Intermediate Casing Point to "J" Sandstone (8, 485 feet) .	20
"J" Sandstone to Top of Lyons Formation (9, 582 feet) .	21
Top of Lyons Formation to Bottom of 11" Hole (11, 225 ft.)	22
Setting of 8 5/8-inch Casing at 11, 171 feet	23
11.225 Feet to Total Depth (12.045 Feet)	24
Completion Activities	26
EQUIPMENT	27
Drilling Rig	27
Location Facilities	27
PENETRATION	29
Surface to 'J'' Sandstone (Surface - 8, 485 feet)	31
UTU Conditions to the Top of the Lyong (8, 4951 0, 5921)	32
Top of the Lyons to the Top of the Fountain $(9, 582'-9, 772')$.	33
Top of the Lyons to the Top of the Fountain $(9, 582'-9, 772')$. Top of the Fountain to the Top of the Regolith $(9, 772-11, 880)$	33 34
Top of the Fountain to the Top of the Regolith (9, 782-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045).	33 34 35
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045).	33 34 35 36
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program.	33 34 35 36 36
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program.	33 34 35 36 36
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045) Hydraulics Program	33 34 35 36 36 39
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program.	33 34 35 36 36 39
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING	33 34 35 36 36 39 39
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING	33 34 35 36 36 39 39
Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION DRILLING FLUID	33 34 35 36 36 39 39 41
Join Sandstone to the Top of the Lyons (8, 405-9, 502-9, 772'). Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION DRILLING FLUID 0-2,000 Feet	33 34 35 36 36 39 39 39 41 42
Join Sandstone to the Top of the Lyons (8, 405-9, 562-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING DRILLING FLUID 0-2,000 Feet 2,000 Feet to 7,450 Feet	33 34 35 36 36 39 39 39 41 42 42
Join Sandstone to the Top of the Lyons (8, 405-9, 562-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING Oright FLUID 0-2,000 Feet 2,000 Feet 7,450 Feet to 11, 225 Feet	33 34 35 36 36 39 39 39 41 42 42 42
Join Sandstone to the Top of the Lyons (6, 465-4, 562-9, 772'). Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING 0-2,000 Feet 2,000 Feet 7,450 Feet to 11, 225 Feet 11, 225 Feet to Total Depth	33 34 35 36 36 39 39 41 42 42 43 44
Joint Statustone to the Top of the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING DRILLING FLUID 0-2,000 Feet 7,450 Feet to 7,450 Feet 11,225 Feet to Total Depth Lost Circulation	33 34 35 36 36 39 39 41 42 42 42 43 44
Join Sandstone to the Top of the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION REYSEATING ORILLING FLUID 0-2,000 Feet 7,450 Feet to 7,450 Feet 11,225 Feet to Total Depth	33 34 35 36 36 39 39 41 42 42 43 44 44
Join Statustone to the Top of the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION REYSEATING DRILLING FLUID 0-2,000 Feet 7,450 Feet to 11,225 Feet 11,225 Feet to Total Depth Lost Circulation	33 34 35 36 36 39 39 41 42 42 42 43 44 44 44
J Sandstone to the Top of the Lyons (8, 403 -9, 362) Top of the Lyons to the Top of the Fountain (9, 582'-9, 772'). Top of the Fountain to the Top of the Regolith (9, 772-11, 880) Top of the Regolith to Total Depth (11, 880-12, 045). Hydraulics Program. Coring Penetration HOLE DEVIATION KEYSEATING DRILLING FLUID 0-2,000 Feet 7,450 Feet to 11,225 Feet 11,225 Feet to Total Depth Lost Circulation CORING Summary	33 34 35 36 36 39 39 41 42 42 42 43 44 44 47 47

E A FOLDHUUS AND AS OCIATES INC.

	Page
Problems	48
DRILL STEM TESTS	52
Summary	52
Problema	53
FORMATION LOGGING	56
Ditch Samples	56
Core Samples	56
Mud Logging	57
Electric Logging	59
Summary	59
Problems	59
CASING INSTALLATION	61
20-inch Casing	61
13 3/8-inch Casing	61
8 5/8-inch Casing	62
Hole Preparation	62
Supervision	63
Rate of Lowering	65
Casing Running	66
Cementing Operation	67
First Stage	67
Second Stage	69
Third Stage	70
Operating Procedures	70
Materials and Equipment	71
Testing	74
Liner Installation	75
PRELIMINARY TESTS	77
Injection Tests	77
Production Tests	77
COMPLETION	79
Subsurface Equipment	79
Tubing Installation	79
Tubing Set-Down Weights	80
Stimulation	81
Well Head	81
Surface Safety Devices	83

a daarii aya ∎o #o ji wali a

÷ A 1

Ï

T

سنر بناء درد ا

ł

ć

E A POLUMBUS JK AND ASSOCIATES INC.

. .

PHYSICAL OPERATIONS

CHRONOLOGICAL SYNOPSIS

When reviewed in its entirety, the drilling of the Rocky Mountain Arsenal Pressure Injection Disposal Well was a complex operation. In order to facilitate an understanding of the inter-relationships of various phases of the operation that are discussed separately in other sections of this report, a brief historical chronology highlighting important events and developments from inception to completion of the project is set forth. Further clarification may be facilitated by frequent reference to two illustrations. The first is the frontispiece, which is a schematic drawing of the well. The second is a graphical representation of the drilling history, included as Figure 6. Another suggested reference is the detailed record of each day's operations included as a complete chronological log in Volume II.

Operations Prior to Drilling

E. A. Polumbus, Jr., and Associates, Inc., was first retained by the U. S. Army Corps of Engineers, Omaha District, in December, 1959, to prepare a preliminary design analysis for a deep well waste disposal project for the Rocky Mountain Arsenal to be used as a feasibility study. The preliminary design report, released January 6, 1960, included both the injection well and treatment plant facilities. Subsequent to receipt of this preliminary report, the overall project was divided into two parts for purposes of final design. The treatment plant final design was assigned to A. J. Ryan and Associates of Denver, Colorado. The final design of the pressure injection well was assigned to E. A. Polumbus, Jr., and Associates, Inc., January 25, 1960, under contract No. DA-25-066-eng-6033. This contract provided not only for the final design of the injection well, but also included a provision requiring E. A. Polumbus, Jr., and Associates, Inc., to supervise the drilling of the well, render the necessary engineering and geological services during the construction phase, and manage the project.

Ť

anti-11 - 5 ×

in the second rate

Concurrent with the preparation of the final design veport, E. A. Polumbus, Jr., and Associates, Inc., also prepared detailed drilling specifications and drilling contract details which became a part of the Invitation For Bids (Construction Contract) issued to drilling contractors. Additionally, the casing design requirements were prepared in advance for the Invitation Bid and Award (Supply Contract) forms issued by "he Corps of Engineers to suppliers of tubular goods. The "Final Design Analysis" xeport was submitted to the Corps of Engineers on July 5, 1960.

On November 17, 1960, the first bid invitation was extended to drilling contractors and was based upon a footage type contract to 6,576 feet followed by day-work to total depth. Bids received in response to this invitation were unsatisfactory, and the Polumbus firm was called upon to arrive at a basis that would encourage more acceptable bidding. A second Invitation For Bids was issued on December 28, 1960, based on a day-work type contract. The first issuance of Invitation Bid and Award (Supply Contract) for tubular goods occurred on November 10, 1960. This bid was subsequently cancelled and a new bid invitation for furnishing tubular goods was issued December 7, 1960. The opening date of the final bids for the drilling contract was January 26, 1961. The drilling contract was awarded to Loffland Brothers Company, Contract No. DA-6724, and the required spud date for commencement of drilling operations on the Rocky Mountain Arsenal Pressure Injection Disposal Well was March 15, 1961.

Representatives of the Polumbus firm attended all Bid-opening sessions for the purpose of assisting the Corps of Engineers in the analysis and evaluation of bids submitted.

On February 13, 1961, Loffland Brothers Company received notice to proceed. This immediately launched a series of operations, including preparation of surface location, roads, and mud pits, laying water line and moving in the drilling equipment. The location, officially surveyed on March 4, was previously selected by the Rocky Mountain Arsenal personnel norther. Pond F at a sufficient distance to provide room for the treatment plant facilities between the pond and the well site.

"Rigging up" operations which commenced March 1 proceeded under adverse weather conditions and delayed the spudding of the well until 3:45 a.m. March 10, 1961.

Preparatory to spudding and throughout the course of the operations, E. A. Polumbus, Jr., and Associates, Inc., handled the customary notices of intention to drill, permits, and reports to the state of Colorado regulatory bodies dealing with the drilling of wells.

Drilling

Surface to Intermediate Casing Point (2, 020 feet)

A 12 1/2-inch hole was drilled to 139 feet and reamed to a 24-inch diameter. The 20-inch surface casing was comented at 135 feet. Sufficient coment was employed to provide a coment sheath from the bottom of the casing to the surface.

A 12 1/2-inch hole was then drilled to a depth of 2,030 feet. An Induction-Electric Log and Microlog were run in the open hole interval. The hole was then reamed to 17 1/2 inches. On March 18 the 13 3/8-inch casing was cemented at 2,020 feet. Sufficient cement was used to completely fill the annular space between the casing and the formation from the casing shoe to the surface.

This upper portion of the hole was drilled with a gel chemical type mud.

Intermediate Casing Point to "J" Sandstone (8, 485 feet)

After converting the mud system to Driscose Condet mud, drilling proceeded with an 11-inch hole being cut. At this time, the Baroid mud logging unit was placed in operation.

In the drilling from 2,020 feet to the top of the "J" sandstone at 8,485 feet, 11.9 net drilling days were consumed (Figure 6) which

L A POLUMBUS IN AND ASSOCIATES INC.

represents an average penetration rate of 543 feet per net drilling day. This was done in the March 23 to April 7 period.

1

While drilling at 6,000 feet, a twist-off occurred in the 4 1/2-inch drill pipe immediately above the drill collar assembly. The fish was recovered in 10 1/2 hours and drilling was resumed. Adjustments in rotary speed and other techniques were made to avoid a re-occurrence. This was the only fishing job for drill pipe during the entire course of the drilling operation.

The Baroid mud logging unit recorded a number of gas "kicks" in the Niobrara formation which are typical throughout the Denver-Julesburg Basin.

"J" Sandstone to Top of Lyons Formation (9, 582 feet)

The drilling of an 11-inch hole continued through the 1,097-foot interval from the top of the "J" sandstone to the top of the Lyons formation. This was ponetrated in the April 8 to May 3 period. The drilling and coring consumed 19.4 net drilling days, equivalent to an average penetration of 57 feet per day. (Figure 6)

Five cores, two in the "J" sandstone and three in the Dakota sandstone were cut in this interval. Slight oil staining was noted in the upper portion of the "J" sandstone.

Two drill stem tests in this interval recovered only small amounts of slightly gas cut mud. These tests covered the cored portion of the "J" sandstone and from near the top of the Dakota sandstone into the Morrison formation. Of interest is the fact that the actual rig time from spudding the well to reaching the top of the Lyons formation at 7,582 feet exclusive of shut-down time for mechanical repairs to the rig, was within one day of the time forecast in the design.

Top of Lyons Formation to Bottom of 11" Hole (11, 225 feet)

In the period from May 3 to July 21, the 11-inch hole was drilled and cored from the top of the Lyons formation to 11,225 feet in the Fountain formation, the top of which was encountered at 9,772 feet. Hole difficulties in the nature of key scating and lost circulation made advisable the setting of the 8 5/8-inch casing at 11,171 feet.

The drilling and coring of this 1,643-foot interval consumed 47.3 net drilling days. This is an average penetration of 35 feet per day.

Both the Lyons and Fountain formations were found to be exceptionally hard, which coupled with the presence of fracturing presented complex problems in drilling and coring.

In this interval, fourteen instances of lost circulation were noted. The mud losses per instance ranged from minor amounts to 1, 350 barrels. Since it was believed that the mud losses occurred in fractured zones, an oilfield technique for "healing" lost circulation zone in fractured formations was successfully adopted. This involved discontinuing drilling and mud circulation, spotting a batch or "pill' of lost circulation material at the bottom of the hole, and allowing the well to set or "cure" for an 8 to 12-hour period. Sixteen cores were cut in this interval of the Lyons and Fountain formations. In addition to lost collation problems the combination of hardness of the rocks and frace g caused jamming or wedging in the core barrel, which generally precluied the cutting of full-length 50-foot cores.

The state of the second second

The combination of the various problems was such that a modification in the coring and testing program was instituted. Short cores at periodic intervals were accepted for geological examination and for determinations of physical properties. Instead of testing only the evered intervals, the drill stem testing program was altered to attempt complete coverage of the section.

Due to a known tendency for the Lyons formation sandstones to produce fine sand into a wellbore during tests and the presence of fractures, with the consequent risk of sticking the test tool, no drill stem tests were attempted in the Lyons formation. One test with the Schlumberger Formation Interval Tester was unsuccessful due to the plugging of the tool with lost circulation material in the mud.

In the interval from the top of the Fountain formation to 11,225 feet, eight drill stem tests were run. At a driller's depth of 9,729 feet, an Induction-Electric log, a Sonic log, and a Microlog were run.

Setting of 8 5/8-inch Casing at 11, 171 Feet

In drilling at 11, 178 feet and below, tight hole and bridges in the hole were encountered in addition to the previous difficulties with lost

L A FOLUMBUS JP AND ASSOCIATES INC.

circulation and the extremely hard fractured rock. The tight hole and bridging problem became particularly noticeable when the hole reached a depth of 11,225 feet.

The deflection of the hole to a maximum of 3 1/4 degrees within the 6,700-foot to 8,000-foot interval was not severe or exceptional. However, during the long period of time the hole was exposed to frequent trips with the drill string, a groove or "keyseat" was worn into one side of the hole. The usual techniques were followed in reaming out the keyseat and included the placement of a reamer and keyseat wiper in the drill string.

The increased hazard represented by the presence of a keyseat coupled with the previously mentioned considerations led to a decision to set the 8 5/8-inch casing when the depth of 11,225 feet was reached rather than at 11,400 feet as originally scheduled.

An Induction-Electric log and Sonic log were run at the 11,225 foot depth. Due to the hazardous condition of the hole, other logging was not attempted.

The 8 5/8-inch casing was run and set at 11, 171 fest. Cementation of the complete annulus from the casing shoe to the surface was accomplished by a three-stage cement operation.

11, 225 Feet to Total Depth (12, 045 Feet)

A 6 3/4-inch hole was drilled below the 11-inch hole at 11, 225 feet. This drilling commenced on August 13 and the total depth of the hole, 12,045 feet, was reached on September 10, 1961.
Fifteen net drilling days were consumed in drilling and coring this 820-foot interval. This represents an average penetration rate of 55 feet per day.

Eight cores were taken in this interval. The lowermost core confirmed that the well had reached fractured Pre-Cambrian granite. Three drill stem tests were also run.

At a depth of 11,985 feet, an Induction-Electric log, Sonic log, Microcaliper log and Temperature log were run.

Two occurrences of lost circulation were experienced in drilling this final section. Both occurred below the top of the Pre-Cambrian rocks at 11,950 feet. From this it was interpreted that there were fractures in the Pre-Cambrian granite and a preliminary injection test into the open hole section below the 8 5/8-inch casing was attempted. This was not successful, primarily due to bridging over of the hole at numerous points.

Following the injection test attempt, an additional 60 feet of hole were drilled and cored to the total depth of the well at 12,045 feet.

A 5 1/2-inch liner was cemented at 11,975 feet. The top of the liner extends into the 8 5/8-inch casing to a depth of 11,007 feet.

Completion Activities

After cementing the 5 1/2-inch liner on September 16 the hole was cleaned out to total depth, and an injection into the interval 11,975-12,045 feet was made with the rig pumps using potable city of Denver water. Additionally, a radioactivity log was run. The 4 1/2-inch drill pipe string was used in conjunction with airlifting equipment in the attempt to obtain a representative sample of formation fluid and reservoir pressure data. After recovering approximately 2, 400 barrels of fluid the production rate dropped below the economic limit for air lift operations, and it was decided to install conventional pumping equipment. Formation fluid samples are important from the standpoint of compatability studies with respect to the fluid to be injected into the reservoir.

and the ratio and the section

After the drilling rig moved off the location, a pulling unit was moved in and 2 7/8-inch tubing, pump and rods were installed. Pumping operations were conducted from October 10 to November 27. During this period approximately 2,900 barrels of fluid were produced from the well.

From the air lift and pumping operations, an approximate total of 5, 300 barrels of fluid were produced. Although the plots of laboratory analyses did not show the assymptotic condition indicative of uncontaminated formation fluid, the production rates had declined below practical limits and the pumping operations was terminated.

The pump, rods and 2 7/8-inch tubing were removed and the completion wellhead assembly was installed on November 30, 1961. The casing and hole details of the completed well are shown in Figure 7. The final wellhead assembly is detailed in Figure 8.

-26-

PHYSICAL OPERATIONS (CON'T)

EQUIPMENT

いるないというないという

- 首先建立者 - 中国大学学会

Ť

Drilling Rig

Loffland Brothers Company Rig No. 7, an Ideco PR-1050 14,000 foot rig was utilized in the drilling of the Rocky Mountain Arsenal Pressure Injection Disposal Well. Descriptive details of this drilling rig are presented in Table 3.

Major items of equipment are the rig power, pumps, drill string, and derrick. Three diesel engines provided 1, 350 horsepower and a D-700 and a D-500 mud pump capable of delivering pressures of 2, 727 psi and 2, 350 psi with 5 1/2-inch and 5-inch liners respectively were used. The drill string assembly consisted of 4 1/2-inch Grade E drill pipe with 21 seven-inch and 14 eight-inch drill collars. The derrick was a 142-foot cantilever type mast rated at 900,000 pounds capacity. - it is of interest that the permissible height of the derrick was regulated by the Civil Aeronautics Authority due to the proximity of the location to Denver's Stapleton Airfield. The regulations also required a flashing red identification beacon on the top of the mast.

Location Facilities

Field office facilities were provided by E. A. Polumbus, Jr., and Associates, Inc. A prefabricated building was installed as an office for the representative of the Corps of Engineers and the Chemical Corps. й 11 11 This building was also used as a display area for well progress charts and core and ditch sample displays. It was equipped with telephone services through the Rocky Mountain Arsenal exchange. A mobile trailerhouse was used by E. A. Polumbus, Jr., and Associates, Inc., field supervisory and technical personnel as an engineering field office and a field laboratory for examination of samples by the geologists. It was also used for staff conferences held with the drilling contractor and service representatives as occasion demanded. In order to assure outside communication at all times, two telephones were installed. One was through the Arsenal exchange and the other was tied directly into the Denver telephone exchange.

and a later to

Another prefabricated building was installed on location for dry storage of cores after they had been examined and boxed.

Loffland Brothers Company provided a house trailer for their toolpusher's use. A Baroid mud logging unit contained in a special trailer was located near the rig shale shaker for ready access to mud stream and shale shaker samples. For operating convenience a voice communication system from the unit to the rig floor was provided. Water for the drilling rig and other location requirements was obtained from the Rocky Mountain Arsenal system.

PHYSICAL OPERATIONS (CON'T)

PENETRATION

Franker in Addition

The drilling analysis chart prepared for the Rocky Mountain Arsenal Pressure Injection Disposal Well (Figure 6) provides an accurate, unabridged record of the penetration performance and shows the interrelationships of drilling factors influencing penetration.

The principal factors influencing penetration rate include the following:

- 1. Lithology.
- 2. Hole size.
- 3. Drilling technique: weight on bit and rotation speed of bit.
- 4. Mud properties: weight, viscosity, filtrate loss, solids content.
- 5. Type of drilling bit.
- 6. Hydraulics: mud circulation rate, pump pressure and sizes of drill pipe, drill collars, bit nozzle sizes, etc.
- 7. Hole deviation limitations.

The foregoing factors associated with the drilling of the Arsenal well are depicted graphically and numerically on the drilling chart. The actual penetration performance is recorded by the three curves relating depth on the vertical scale and days from spud on the horizontal scale.

The penetration curve on the left, designated "rotating progress" is composed entirely of cumulative rotating on bottom time and therefore is the prime curve used in relating the various drilling factors to penetration. The curve on the right designated "overall drilling progress" records the depth of the well at any specific lapse of time from spud. Explanatory notes and symbols placed on this curve give the important and significant events related to the drilling history.

1

The middle curve denoted as "net drilling progress curve" is composed of the rotating progress time, plus trip time to change bits, service the rig, drift surveys, and normal mud mixing. It is a pure drilling operations curve uninfluenced by time consumed in dealing with lost circulation, drill stem tests, electric logging surveys, fishing operations, running and cementing casing, etc. This curve is used principally in studying relative penetration performance.

Table 4 is an analysis of the drilling and coring performance in the Arsenal well prepared from the net drilling progress curve of Figure 6. The following sections discuss individually those intervals in the well which exhibited distinct drilling characteristics.

OMPOS JE

Surface to "J" Sandstone (Surface - 8, 485 feet)

1

The net drilling progress rate from the surface to the top of the "J" sandstone at 8, 485 feet averaged 605 feet per day. Considering the fact that a large hole was drilled (12 1/4-inch to intermediate casing point at 2, 030 feet and thereafter 11-inch hole), the greater depth at which the "J" sandstone was encountered compared with most wells in the Denver Basin and the use of mud instead of water in the upper part of the hole, this penetration rate represents an excellent performance.

During penetration of the section to the top of the "J" sandstone, drilling weights were progressively increased from 35,000 to 60,000 pounds while rotation speeds were adjusted downward from 200 rpm to 75 rpm as increased depth was attained and drilling weight added. Average hole deflection was less than i 1/2 degrees with the exception of the interval 6,800 to 7,900 feet where deviation reached a maximum of 3 1/4 degrees.

Rock bits used in penetrating this section were principally OSC-3 type and averaged 530 feet per bit.

The overall drilling progress curve (Figure 6) shows that the top of the "J" sandstone was reached 29 days after spudding the well. Reference to the operational notes on this curve explains the spread of 15 days between the net and overall drilling progress curves as attributable to time devoted to hole enlargement operations for surface and intermediate

> -31-FORMATION OF AND AND 20034

casings, running, comenting and WOC time for these casing strings, rig repairs and one brief fishing operation due to a drill pips twist-off. "J" Sandstone to the Top of the Lyons (8, 485'-9, 582')

Sec. Alder

The abrupt reduction in net drilling progress rate to 89 feet per day between the "J" sandstone and the top of the Lyons formation at 9,582 feet is characteristic of the Denver basin and denotes increasing hardness and sand content in the section.

In drilling this portion of the 11-inch hole, weights of 60,000 to 80,000 pounds and rotation speeds of 55 to 60 rpm were employed. The maximum hole deviation approximated 1 1/2 degrees. Bit types ranging from OSC-1G to W-7R were used. The drilled footage averaged 46 feet per bit, indicative of the increased hardness of this section. Mud properties were maintained in the range of 9.2 to 9.8 pounds per gallon weight, 52 to 78 seconds viscosity, and water loss, 5.5 to 8.7 cc.

The overall time from spud required to reach the top of the Lyons formation at 9,582 feet was 54 1/2 days. At this depth the spread between net and overall drilling progress curves was approximately 21 days compared with 16 days spread at the top of the "J" sandstone. This increase divergence between the two curves was the result of two drill stem tests, hole conditioning, circulating samples, rig repairs, and fishing operations for rock bit cones.

Top of the Lyons to the Top of the Fountain (9, 582'-9, 772')

The 190 feet of Lyons formation (9, 582 to 9, 772 feet) consisting principally of extremely hard quartzitic sandstone proved to be much harder in character and more difficult to penetrate than drilling histories indicated for any other wells reaching this formation in the Denver Basin. All other wells which have reached and penetrated the Lyons formation in varying amounts have been located in considerably shallower portions of the Denver Basin than the Arsenal well, the well being situated in approximately the deepest position in the synclinal trough.

One-half of the Lyons formation was cored in the Arsenal well, and the remaining half was drilled; the net drilling penetration rate averaged 28 feet per day. All hard type rock drilling bits, principally W-7R, were used for which the drilled footage averaged 15 feet per bit.

Drilling weights of about 42,000 pounds and rotation speeds of 55 to 65 rpm proved adaptable to the Lyons drilling. Mud weights averaged 9.8 pounds per gallon, viscosity 56 seconds, and water loss 7.8 cc. Hole deviation was less than one degree for this interval.

The divergence between net and overall rotating progress curves increased 5 days (21 1/2 to 26 1/2) while penetrating the Lyons section. As indicated on the overall progress curve, the drilling history of this formation was characterized by numerous lost circulation intervals associated with fractures in the hard quartzitic sand, requiring considerable time devoted to mixing mud and applying various techniques to heal the lost circulation zones. Top of the Fountain to the Top of the Regolith (9, 772'-11, 880')

化学校学校 化化学校学 化化学学校 化化学学校 化学学校 化合物 医白垩合体 化合物合物 化合物合物 化合物合物

4

-

1

i

The 2, 108 feet of Fountain section (9, 772 to 11, 880 feet) consisting of sandstone, shale, siltstone and arkose was cored (408 feet) and drilled (1, 700 feet). Reference to the net drilling progress curve shows that this section was penetrated much more rapidly than the overlying Lyons formation. The 68 feet per day net drilling rate versus 28 feet per day represents an increase of 2.4 times in the Fountain formation.

Drilling weights of 60,000 to 65,000 pounds and rotation speeds of 50 to 65 rpm were utilized in drilling the 11-inch hole to 11,225 feet. In the 6 3/4-inch hole below this depth, drilling weights of 20,000 pounds and rotation speeds of 40 to 50 rpm were adopted. Hole deviation was permitted to progressively increase from about one degree at 10,000 feet to a maximum of 7 degrees at 11,600 feet.

While penetrating the Fountain, mud weight varied from 8,7 to 9.7 pounds per gallon, viscosity 40 to 117 seconds, and water loss 5,7 to 9.8 cc.

Drilling bit types included W-7 and W-7R rock bits and RG-2BJ insert bits. The average footage for the rock bits was 39 feet per bit or 2.6 times the footage obtained in the Lyons drilling. The RG-2BJ insert bits averaged 51 feet per bit in the Fountain formation.

The overall drilling progress curve indicates that approximately 100 days were utilized in the various operations required to achieve penetration of the Fountain section. The spread between net and overail drilling progress curves was increased by 55 1/2 days while penetrating the Fountain formation.

Ţ

alla integra da unal integra

Actual time drilling and coring (including reaming the core hole) in the Fountain utilized 24.8 and 19.4 days, respectively. The remaining 55.8 days were devoted to the following principal operations as denoted on the overall curve: mixing mud and healing lost circulation in the several fractured sections; running electric logs; drill stem testing; running and cementing 8 5/8-inch casing; WOC; repairing rig; fishing for rock bit cones; and reaming out keyseat within the interval 6, 800 to 7, 800 feet. Top of the Regolith to Total Depth (11, 880'-12, 045')

The 165-foot interval from the top of the Regolith to total depth (11, 880 to 12, 045 feet) consisting of shale, quartzite, conglomerate, dolomite, and pre-Cambrian granite gneiss was penetrated in three net drilling days. The drilled portion (143 feet) averaged 71.5 feet per day, and the 6 3/4-inch RG-1J insert type bits obtained 49 feet per bit. Drilling weights of 20,000 pounds and 40 to 50 rpm were employed. Mud properties were 9.0 pounds per gallon weight, 43 seconds viscosity, and water loss 5.8 cc.

The overall drilling progress time devoted to this interval was 10 days which completed the operations to total depth of 12,045 feet, in elapsed time to 185 days from spud. This last period included, is addition to drilling and coring, time for running electric logs, drill stem testing, mixing mud and healing lost circulation in the fractured granite interval.

-35-

Hydraulics I ogram

A jet sit program was not utilized in connection with the rock bit drilling due to the high mud circulation rates and pump pressures that would be the juired in the 11-inch hole below 4,000 foot depth. High penetration rates obtainable with a conventional rock bit program from surface to 4,000 feet did not warrant jet bits in this portion of the hole. Influencing factors were the extra time required to change pump liners and the additional cost of jet bits.

Coring Penetration

Reference to the drilling and coring statistics presented in Table 4 shows the following analysis of coring penetration characteristics in the Arsenal well.

The five 8 7/8-inch diamond cores in the "J" sandstone to the Lyons interval averaged 22.8 feet cut per core for an average penetration rate of 14.3 feet per day including coring time plus time to ream core hole to full gauge 11-inch hole. Within the same section, drilling penetration time was 6.2 times faster.

Within the Lyons to the Fountain section, eight 8 7/8-inch cores averaged 12.0 feet cut per core at the average rate of 7.8 feet per day coring and rearning core hole. Drilling was 3.6 times faster than coring the Lyons formation. There were thirteen 7 13/16-inch and 6 11/16-inch cores cut in the Fountain formation for an average length of 31.4 feet, and an average of 21.0 feet per day coring and reaming time. Drilling proved to be 3.3 tirkes faster than coring.

ţ

· .*.

1 192

1111

I

The two cores cut in the interval from the top of the Regolith to total depth averaged 11 feet in length at the average rate of 22.0 feet per day coring only.

The following graph shows the relationship existing between average feet cut per core and feet per day cored and reamed in the Arsenal well.



-37-

The fractured intervals cored in the Lyons and Fountain sections caused wedging in the core barrel and limited the length of many cores cut in these formations. Also, lost circulation and the presence of extremely hard quartzitic pieces rolling under the diamond coring head caused "grooving" of the head which limited the length of some cores.

It is indicated from the above graphical relationship that had it been possible to cut average length 50-foot cores, the coring and reaming rate should have approximated 33 feet per day. Based on this figure, the coring and reaming time for 639 feet cut would approximate 20 days rather than the 40.5 days actually required.

Consideration was given in designing the coring program to using 11-inch diamond coring heads to avoid the time and expense of opening up a smaller sized core hole. Equating the cost of the larger diamond coring heads, the relative penetration rates and footage, reaming time, and the added problem of stabilizing the coring assembly in the 11-inch hole, the full hole 11-inch coring program could not be justified.

-38-

PHYSICAL OPERATIONS (CON'T)

HOLE DEVIATION

With the exception of one reading at 370 feet, the hole deviations in the Arsenal well from the vertical stayed within the design limits. Table 5 is a summary of the deviation survey readings taken during the drilling of the well. The maximum deviation of 7 degrees was encountered at 11,600 feet.

KEYSEATING

As the well approached the depth of 11,225 feet, a tight hole condition developed in the 7,000 foot to 7,800 foot interval. Analysis of this interval with respect to hole deviation indicated a strong possibility that a keyseat had developed.

As shown in Table 5 there is a bend or "dogleg" in the hole between 6,700 feet and 8,100 feet from one degree at the top and bottom of the interval to a maximum of 3 1/4 degrees near the middle of the interval. This is portrayed graphically in Figure 6.

This nature of bend and more especially the rate of change in deviation is within the acceptable limits established in the drilling industry. However, in this case, the prolonged exposure of the dogleg to the abrading action of the drill pipe resulted in a groove being worn in the side of the hole somewhere in the interval of the dogleg. The keyseat trouble was

E A FOLUMBUS OF ANY AS OCTATES ON

first manifested while drilling near 11,200 feet. This was approximately 110 days after the keyseat interval was drilled.

.

Ī

Card Contraction

we and the adviction of the fact that the fact of the second seco

1114

「日本の」」というないというないとなって

「ない」となった。という時間でしたであっ

The usual remedial procedure of running a keyseat wiper and string reamers was adopted. However, the severity of the keyseat problem coupled with the acute lost circulation, and a desire to protect the possible injection reservoirs penetrated above the 11,225 foot depth led to a decision to alter the basic program and set the 8 5/8-inch casing at approximately 11,200 feet rather than 11,400 feet. This decision was reached in a joint meeting of representatives of the United States Army Corps of Engineers, the United States Army Chemical Corps, E. A. Polumbus, Jr., and Associates, Inc., and Loffland Brothers Company representatives.



FHYSICAL OPERATIONS (CON'T)

DRILLING FLUID

The drilling mud program employed on the Rocky Mountain Arsenal

Pressure Injection Disposal Well was based on the following considerations:

- The anticipated Pierre shale section from 1,500 feat to 7,800 feet required the use of a drilling fluid which would provide maximum hole protection and minimum shale swelling over the long period that this section would be exposed.
- 2. The drilling fluid must provide protection to any potential injection reservoir interval.
- 3. The drilling fluid must be fairly simple to maintain and provide suitable temperature stability.
- 4. The drilling fluid should provide for maximum penetration rate and bit performance and still furnish suitable rheological properties.

In order to select a drilling fluid which would satisfy all these

requirements, conferences were held with Baroid personnel, and the following mud program was established as offering the best compromise for all the properties desired.

A summary of the mud properties during the drilling operations is included in Table 6 and the following table summarizes the drilling mud program employed on the Arsenal well.

			Water	
Depth	Weight	Viscosity	Loss	Type Mud
0 feet - 2,000 feet	9.0	54	4.4	Gel-chemical
2,000 feet - 7,450 feet	9.5	35	7.5	Low solids driscose- condet
7,450 feet - 9,500 feet	10.0	60- 80	5-7	Gyp Q-Broxin emulsion
9,500 feet - 11,225 feet	9.5	60-100	5-7	Gyp Q-Broxin
11, 225 feet - Total Depth	8.5-9.0	35- 45	5 - 7	Low solids driscose

-41-E A SECUMPTER OF ALL A SECUMPTER OF Constant supervision of the mud program was maintained by Baroid mud logging personnel and E. A. Polumbus, Jr., and Associates, Inc. engineers on a 24-hour per day basis.

0-2,000 Feet

er eine seinen hann die seine fahren daten jaar die der die dereiter

The drilling fluid used in this interval consisted of a bentonite carboxy methyl-cellulose mud with caustic and tannex used as a dispersing agent. The average properties of this system were: weight, 9.0 #/gal.; funnel viscosity, 54 seconds; centipoise viscosity, 26; water loss, 4.4 ccs.; pH, 10.5; chlorides, 300 ppm. This fluid was used until 13 3/8-inch casing was set.

2,000 Feet to 7,450 Feet

Below the intermediate casing string, the drilling mud was converted to a low solids carboxy methyl cellulose mud with condet, a surfactant type material, added to accelerate settling of the drill cuttings and add lubricity to the drilling fluid. Characteristic properties of this type fluid were as follows: weight, 9.4 to 9.5 #/gal.; funnel viscosity, 31 to 38 seconds; plastic viscosity, 4 to 10 centipoises; yield point 0 to 2 grams/100 centimeters². Due to the very low rheological properties exhibited by this type fluid, the suspending properties were relatively low and some fill-up "after trips was expected, and did occur. Past experience with this type drilling fluid indicated that some sacrifice in trip time due to the necessity of cleaning out to bottom must be made in order to achieve the benefits of increased penetration rates and bit footages which may be obtained with this type mud system.

7,450 Feet to 11,225 Feet

Past experience in the Denver-Julesburg Basin indicated that the Niobrara Formation, which contained some anhydrite but was primarily a shale section, was quite susceptible to the swelling of the formation clays when in contast with fresh water. The drilling fluid was therefore converted to a Gyp-Q-Broxin mud at a depth of 7,450 feet in order to adequately condition the hole prior to drilling the Niobrara. Additionally, 25,000 to 30,000 parts per million sodium chloride were added to the mud at this time in order to condition the mud filtrate to more nearly approximate formation water and thereby help reduce filtrate damage to the formation. In order to offset the increase in weight from the salt addition, 5 to 10 percent diesel oil was also added to the mud at this time.

The average properties of the mud before and after conversion to the gyp-base mud were as follows:

		Before Conversion CMC Mud	After Conversion
Mud Properties		Low Solids Condet	Gyp Q-Broxin
Weight	#/gal.	9.3 - 9.5	9.5 - 10.0
Viscosity	seconds	30.0 + 0.35	60 - 90
Viscosity	centipoises	18	36
Initial gel	grams	0	3
10'gel	grams	Ō	25
API Filtrate	ml	7.0	4 - 7
Filter cake thickness	inches	1/32	2/32
Plastic Viscosity	centipoises	5 - 10	20
Yield Point	gm/100 cm	² 0 - 2	12
pH	-	8 - 9	8 - 9
Salt	ppm	850	20.000
Calcium	ppm	•	1,200

-43-POLUMBUS JR AND ASSOCIATES The properties listed for the gyp-base mud were fairly constant to a depth of approximately 9,596 feet at which time lost circulation occurred. Additions of salt to the mud were discontinued after the lost circulation was experienced in order to avoid corresponding weight increases. The mud weight was reduced and maintained between 9.1 #/gal. and 9.5 #/gal. until pipe was positioned at 11, 171 feet.

an gan an na sa san ng baga la nan gan ng pangan ng pangan ng pangan na sa panang na la na na na sa

Lost circulation material concentration was maintained between 10 percent and 30 percent during the periods of lost returns.

The Gyp-Q-Broxin mud was used to a total depth of 11,225 feet at which time casing was run and further drilling was conducted in a 6 3/4inch hole.

11, 225 Feet to Total Depth

1999年の12月の「東京の1994年の」を注意した。たらまたのでは、そこの1997年の1994(より中国株式を取

In order to provide the least expensive mud system and still afford adequate hole protection for drilling in the 6 3/4-inch hole, the drilling fluid was converted to a low solids fresh water driscose mud with the following properties; weight, 8.5 to 9.0 #/gal.; funnel viscosity 35 to 45 seconds, plastic viscosity, 15 centipoises; yield, 7. Approximately 1,000 barrels of this mud were lost during the course of drilling from 11,225 feet to 12,045 feet.

Lost Circulation

The lost circulation experienced during the course of drilling the Arsenal well is indicated on the overall drilling progress curve in Figure 6. Details of quantities lost and depth of occurrence are presented in the following tabulation:

Ĩ.

Well Depth	Barrels Lost	Well Depth	Barrels Lost
9,596	150	10,055	150
9,607	20	10,061	500
9,675	536	10, 110	717
9,705	10	10, 120	450
9,750	97	10, 153	653
9,777	150	10, 210	70
9,810	800	10, 250	114
9,960	49	10, 563	600
9,962	80	10, 573	530
9,968	100	10,610	730
10,013	15	11,080	1350
10,047	200	11, 985	1030
-		Total	9092

The depths represent the position of the bit at the time lost circulation occurred and do not necessarily indicate the point at which fluid was lost.

Experiments conducted as soon as lost circulation became an apparent problem showed that spotting "pills" of lost circulation material on bottom when new fractures were exposed by the drill or core bit, and allowing this to set for a maximum period of 12 hours, generally remedied complete loss of circulation at that particular depth. In the case of partial loss of circulation, a maximum rate of mud loss was calculated above which the aforementioned cure was the most economical solution.

Other considerations connected with the drilling operation limited the use of other techniques in combatting lost circulation. For example, the use of high concentrations of lost circulation material in the mud system necessary for plugging fractures could result in plugging the perforated anchor while conducting drill stem tests and thereby restricting the use of the test data. In like manner, the circulation passages through the core barrel can only tolerate a certain percentage of lost circulation material (25 to 30 percent maximum by volume) before prohibitive pressure drops through the core barrel or possible plugging of the core barrel occurs.

PHYSICAL OPERATIONS (CON'T)

CORING

Summary

In the Rocky Mountain Arsenal Pressure Injection Disposal Well a total of 639 feet of section was cored with a recovery of 575 feet, representing 90 percent. A summary of the depths and recoveries for the 28 cores is presented in Table 7.

The program design anticipated cutting 50 foct or longer cores on each coring run. However, due to extensive fracturing encountered, it was possible only in five cases to cut an interval of 40 feet or greater. The minimum cut only two feet.

Equipment

The special equipment used in the coring operation is summarized in Table 8. For the major portion of the coring, the mechanical assembly consisted of a diamond corchead, a 50-foot core barrel, a set of safety jars, drill collars and the drill pipe. A 30-foot kelly extension was utilized after core No. 3 in order to eliminate drill pipe connections during the cutting of a core. This eliminated the possibility of junk falling under the diamond core head during the operation of making the connection.

On one coring run, No. 22, the core barrel was leng nened to accommodate a 75-foot core. On this run a total of 64 feet was cut,



Cores Nos. 25 and 26 were cut with a Bowen junk basket. This tool, pictured in Figure 9, 's primarily a fishing tool for recovery of junk. Since it utilizes a coring principal, there is an occasional recovery of the formation rock. In such cases in the Arsenal well the recovery has been considered as a core run.

Runs Nos. 1 through 21 cut 4 3/8-inch diameter cores. In the lower portion of the hole, after setting the 8 5/8-inch casing, 3 1/2-inch diameter regular cores were cut. The cores recovered from the junk basket runs were 4 13/16-inch diameter.

Problems

The decision to core a rathole and ream the cored rathole before drilling ahead was primarily influenced by economic considerations. A full size corehead for the 11-inch hole would have cost approximately 75 percent more than an 8 1/2-inch corehead, and the expected life would be the same or less than that of the smaller head. Furthermore, the overall penetration rate including the time required to ream the rathole would be the same for the 8 1/2-inch or 11-inch coreheads. Additional anticipated difficulties in stabilizing the 11-inch corehead with the drill collars and the resultant undue wear also influenced the decision to rathole core.

The extreme hardness of the rock in the "J" sandstone, Dakota sandstone, Lyons formation and Fountain formation resulted in abnormal

-48-

wear and breakage of the teeth or knobs of the drilling bits. Since diamond coreheads are particularly susceptible to damage from loose metal in the hole, precautionary measures to remove the junk from the bottom of the hole were necessary. To remove such junk, extra trips running junk baskets and/or magnets were frequently made prior to coring.

In cutting core No. 3 the corehead was grooved either by loose metal in the hole or pyrite materials from the formation. The earlier procedure in coring had necessitated picking up the core barrel to make a connection. In doing this it is possible for junk or pyrites that had been held in the annulus or on the ledge of the rathole to fall to the bottom while the connection was being made. To eliminate this hazard a 30-foot kelly extension was obtained. Through its use, it was then possible to cut a full 50-foot core without lifting the corehead off the bottom of the hole.

Even though the precautionary measures described above were followed, the second corehead was grooved in cutting core No.5 in the Dakota sandstone. This influenced the decision to forego further coring until the Lyons formation was reached. This decision was also greatly influenced by the lack of favorable indications in cores Nos. 1 through 5.

From core No. 7 it was determined that there was fracturing in the Lyons formation. This was observed in subsequent cores and evidenced by the short intervals cut in the core runs.



In a fractured formation, especially where vertical fractures are encountered, a slight slippage of the core along the fracture plane can cause the core to jam within the barrel. With a core jammed in the barrel, excessive wear on the mechanical components of the barrel can result in bearing and other mechanical failures.

REAL PROPERTY AND A REAL PROPERTY OF A REAL

The usual indication of a jammed barrel is a sharp decrease in penetration rate or a complete halt in the penetration. The short core intervals through the Lyons formation and into the Fountain formation were frequently directly attributable to such jamming.

After entaring the Lyons formation core No. 6 was cut at a depth of 9,614 feet. After cutting 10 feet, circulation was lost and the coring was stopped. There was no recovery from this core.

Lost circulation difficulties continued to the total depth of the hole. Frequently the losses occurred while coring and the operation had to be suspended.

With a long core barrel of a greater diameter than the drill pipe or collars there is always a greater hazard of sticking than with a bit. In addition, the circulation channels through a core barrel offer restrictions not present with a normal drill str^2 g and hit_2

Thus, whenever a hazardous condition such as lost circulation occurs while coring, an accepted practice is to pull the core barrel from the hole and conduct remedial operations with the drill string and bit.



Thus, there were three principal problems encountered in the

coring operations. These were:

- 1. Damage to diamond coreheads from the hard formation or from junk metal in the hole. Pyrites from the formation, especially in the "J", Dakota, and Lakota sandstones, could also have contributed to this type of damage.
- 2. Jamming of the core in the core barrel resulting from the fractured formation.
- 3. Lost circulation during coring with the consequent need to suspend coring.



PHYSICAL OPERATIONS (CON'T)

DRILL STEM TESTS

Summa ry

The original drill stem test program was designed to evaluate any intervals indicated by cores to be of interest. When a change in the coring program was necessitated, a corresponding change in the drill stem testing program was made. Basically, the change resulted in testing long intervals to give approximately full coverage of the formation rather than testing selected short intervals.

In all, fourteen formation tests were attempted. Thirteen of these used conventional drill stem test tools. One attempt was made using a wireline test tool. Details of the tests and the results are shown in Tables 9 through 22. Ten of these tests were mechanically successful. The wireline test tool plugged with lost circulation material and in the remaining three drill stem tests the packer did not isolate the zone to be tested due to the fractured formation.

Drill stem test No. 14, which tested the 11, 171 foot to 11, 185 foot interval of the well, recovered 5, 400 feet of salt water in addition to the water cushion used in the test. This salt water showed a total chioride content of 46, 400 ppm which may not represent a true formation value due to contamination. Fluid recoveries in the remaining tests consisted of drilling mud or contaminated fluids.

> -52-E & POLUMBUE IR AND ASSOCIATES INC

The following tabulation shows the intervals which were tasted. These are also portrayed in Figure 10.

Test No.	Depths	Formation		
1	8,482- 8,556	"J" Sandstone		
2	8,628- 8,821	Dakota-Lakota Morrison		
3	9.662	Lyons		
4	9,845-10,016	Fountain		
5	9,836-10,016	Fountain		
6	9,862-10,057	Fountain		
7	10,076-10,317	Fountain		
8	10, 137-10, 339	Fountain		
9	10, 336-10, 542	Fountain		
10	10, 517-10, 729	Fountain		
11	10,755-10,962	Fountain		
12	11,096-11,439	Fountain		
	(Csg. shoe at 11, 171)			
13	9,660-11,985	Fountain, Regolith,		
	(Csg. shoe at 11, 171)	Pre-Pennsylvanian,		
	•	Pre-Cambrian		
14	11,020-11,985	Fountain, Regolith,		
	(Csg. shoe at 11, 171)	Pre-Pennsylvanian,		
	• • • • •	Pre-Cambrian		

DRILL STEM TESTS

Problems

The two tests run prior to reaching the top of the Lyons Formation presented no particular problems. In test No. 1 the packer failed near the end of the final shut-in period, but this is not uncommon.

Some differinity in 7. Is stem testing the Lyons formation had been anticipated. Testing of Lyons sandstones in other wells in the area had shown that the sandstones have a tondency to produce fine sand into the welibore during tests. The sand can pack around the test tool or tail pipe and cause sticking, thus resulting in a fishing operation. During the operation of cutting core No. 0, the first core cut in the Lyons formation, lost circulation was experienced and no core recovery was obtained. Gore No. 7, cut 2 feet below core No. 6, recovered hard quartzitic sandstone with many vertical fractures.

Thus, with the direct confirmation of fracturing from the cores another hazard to drill stem tosting was established. If the packer on the drill stem test tool should be set in a zone of open fractures the fluid in the annulus above the packer could easily bypass the packer into the interval being tested. In addition to invalidating the test, these bypassing fluids create an increased hazard in that they might carry solid material such as sand or lost circulation material and deposit this around the test tool, resulting in sticking of the tool.

After consideration of these various hazards and the risks involved in the various alternative methods of testing versus the data to be obtained it was decided to forego any drill stem testing in the Lyons formation. Any interpretation would have to be made from the cores and samples obtainable and the logs. More definitive evaluation could be made after cementing 8 5/8-inch casing.

Attor penetration into the Loons formation, mud losses and spot cores indicated the presence of fractures in this section. Since the Fountain formation was not known to produce sand during tests, it was felt that this reduced risk would warrant resumption of the drill stem testing program. This modified program provided for testing long intervals to effect as complete coverage of the remaining section as possible.

l

Tests numbers 4, 5, and 7 were not successful due to packer failures. In these cases it is interpreted that fluids bypassed the packers through fractures in the Fountain formation.

-55-А новымного и ан а с аза с из

PHYSICAL OPERATIONS (GON'T)

the start the

FORMATION LOGGING

Ditch Samples

A program of catching, washing, examining, describing, and preserving ditch samples taken at 10 foot or lesser intervals were followed in the drilling of the well. Samples at shorter intervals were caught whenever required by the geologist on the well. The description of these samples is included in the Sample Log in Volume III of this report.

In all, three sets of samples were prepared. One set was sent to the United States Geological Survey, Ground Water Division, Denver, Colorado. Another was furnished to the State of Colorado Oil and Gas Conservation Commission. With the permission of the United States Army Corps of Engineers, the third set was sent to American Stratigraphic Co., Denver, Colorado, a commercial sample library service. This set is readily available for public use.

In addition to these samples, the personnel of the Baroid Mud Logging unit caught and examined ditch samples at two foot or lesser intervals in the section of the well logged by this equipment. The final "Baroid ppm Log" is included in Volume III of this report.

Core Samples

All of the core material recovered was examined and described immediately after recovery and samples for core analysis were selected.

In general one sample from every foot of clastic material was analyzed. The core descriptions are included in Table 2 and in the Sample Log in Volume III. Gore analysis results are presented in the log portion of Volume III and a portion are shown in Table 23.

Color photographs were taken of many of the cores, particularly those showing fractures, by the resident geologist of the Corps of Engineers.

After being described the cores were labeled, boxed, and stored in a special shed on the location. After the completion of the well, the core samples are to be stored with the United States Geological Survey, Ground Water Division in Denver, Colorado.

Chips were taken from all cores and were included with the three sets of ditch samples. The distribution of these is shown under Ditch-Samples.

Mud Logging

A Baroid Mud Logging Unit was employed on the well from the time of drilling out from under the 13 3/8-inch casing until the completion of the final drill stem test. The "Baroid ppm Log" of the interval from 2,036 feet to 11,985 feet is included under "Logs" in Volume III.

This log presents in graphical form the results of the various analyses and examinations made in the mud logging unit. The following are included:

1. A continuous record of the drilling and coring rate.

- A graphical plot of the lithology and a description of the rocks penetrated. These are prepared from the ditch samples caught at two foot intervals.
- 3. Recordings of the hydrocarbons present in the mud and cuttings.
- 4. Recordings of the properties of the drilling mud.

The Baroid Well Logging Service also provided an on-location core analysis, a copy of which is included in Volume III. In order to substantiate the core analysis data determined by the logging unit, 52 core samples were randomly selected and analyzed by an independent core laboratory. The results of this check revealed essential agreement between the two evaluations. (Table 23.)

Examination of the Baroid Mud Logging Report indicates the absence of any significant hydrocarbon zones. A gas kick of 30 units was indicated through the Niobrara section. This is quite typical of the Niobrara shale throughout the Denver-Julesburg Basin. Additional large gas kicks noticed at 7,700 feet were due to the addition of diesel oil to the drilling fluid. Off-scale deflections were recorded at various other intervals after roundtrips out of the hole with the drill string. This phenomenon was the result of entrained gas in the mud system derived from the gas shows in the Niobrara.

Electric Logging

Summary

An Induction-Electric log and a Gamma Ray Neutron log were taken through the major portion of the Arsenal well. Less complete coverage was made with the Sonic log, Microlog, and Temperature log. Copies of all logs taken in the well are included in Volume III. Table 24 is a tabulation of the various logs, the dates run, and other pertinent data.

Problems

An Induction-Electric log and Microlog were run before setting the 13 3/8-inch casing. A 12 1/2-inch hole was drilled to 2,030 feet and logging was attempted. On the first attempt the sonde encountered a bridge or obstruction at 800 feet. A cleanout trip was made with the bit. Again bridges were encountered. This process was repeated until on the fourth attempt the sondes went to bottom and the logs were run.

Since the hole was to be reamed to 17 1/2 inches the possibility of reaming the hole and then logging was considered during the period of these difficulties. However, the quality of logs run in large diameter holes is frequently very poor. Thus, it was decided to continue the cleanout runs in order to take the logs in the smaller 12 1/2-inch hole.

The logging runs at a drillers depth of 9,729 feet presented no problems.

After the keyseat difficulties developed upon reaching a depth of 11,225 feet, it was decided to log the hole and run the 8 5/8-inch casing. Therefore, an Induction-Electric log and Sonic log were taken.



The Sonic log sonde encountered some bridges going into the hole but it was worked to bottom. Three tight spots were encountered coming out of the hole and it was found that one of the rubber coverings on the sonde had been lost.

1

It had been planned to run a Caliper log in order to calculate the volume of the hole prior to cementing the casing. However, after the difficulties encountered running the Sonic log, it was decided to determine the volume by other means and the log was not run.

In the log runs at a drillers depth of 11, 985 feet, the first attempt to run the Temperature log was a misrun. The second attempt was successful.

The only log taken in the interval from 11, 985 to 12, 045 feet was a Gamma Ray Neutron log. This was run without incident.


CASING INSTALLATION

A summary of the casing and hole program used on the Rocky Mountain Arsenal Pressure Injection Disposal Well is enclosed as Table 25. Figures 7 and 11 graphically portray the casing and hole program and the details of the casing strings. A summary of the individual casing string assemblies are as follows:

20-inch Casing

The 20-inch casing string, which was set at a depth of 135 feet in a 24-inch hole, consisted of 94 #/ft. H-40 casing with short threads and couplings and a Baker Guide Shoe. This casing string would have no severe stresses imposed and serves only to support the loosely consolidated sand and gravel near the top of the hole. Portland cement was circulated around this entire casing string back to the surface.

13 3/8-inch Casing

The following 13 3/8-inch casing string was used in the final installation. This casing string was positioned in a 17 1/2-inch hole at 2,020 feet. This casing string was also cemented with Portland cement with its entire length being protected with this material.

This string includes a Baker Guide Shoe on the bottom and a baffle collar one joint off bottom.

	O, D,	Lbs./ft.	Grade	Coupling	Nom. I. D.	Drift I. D.
Тор	13.375	54.5	J-55	LT&C	12.615	12,459
Middle	13.375	48.0	H-40	LT&C	12,559	12,559
Bottom	13.375	54.5	J-55	LTLC	12.459	12.459

-61-A POLUMBUE PE AND ASSOCIATED IN

The 13 3/8-inch casing string served as a base for the blowout preventers during drilling operations and as a support for the load imposed by the 8 5/8-inch casing and the 5 1/2-inch tubing strings after completion of the well.

8 5/8-inch Casing

The shoe of this casing string was positioned at 11, 171 feet and the casing was cemented over its entire length back to the surface.

	O , D ,	Lbs./ft.	Grade	Coupling	Nom. I. D.	Drift I. D.
Тор	8.625	40.0	N-80	Extremeline	7.725	7.600
Middle	8.625	40.0	H -80	LT&C	7.725	7,600
Bottom	8.625	44.0	N-80	LT&C	7.625	7.500

To position the 8 5/8-inch casing an 11-inch hole was drilled to a total depth of 11, 225 feet. Because of the complexities involved in the cementation of over 11,000 feet of casing from shoe to surface, extensive planning and preparation was necessary. Figure 12 illustrates a typical 3-stage cementing job.

Hole Preparation

The initial operation in the completion procedure is the preparation of the hole for casing running, and placement. The condition of the hole at the time when 8 5/8-inch casing was run was: 20-inch casing cemented at 135 feet, 13 3/8-inch casing cemented at 2,020 feet, and 11-inch hole drilled to 11,225 feet.

The mud properties were: weight, 9.4 ppg; viscosity, 120 seconds; plastic viscosity, 30 cp; yield, 15 gm/100 cm²; water loss, 5 cc; lost

A FOLUMEUN IN AND ANDOTATES IN

circulation material, 15 percent; oil, 10 percent; pH, 8.5; chlorides, 4,200 ppm; and preservative, 0.3 percent.

This mud system was circulated for a sufficient length of time to completely stabilize the bore hole.

Supervision

Prior to the undertaking of any major operation on the Rocky Mountain Arsenal well, consultation was held between representatives of the service companies involved and E. A. Polumbus, Jr., and Associates, management and consulting engineers. A number of specialized meetings were held prior to the installation of this 8 5/8-inch casing string.

From these meetings a series of instructions were printed for the field personnel. The following comments are some of the highlights from these recommendations:

- A Halliburton engineer was on location to supervise making-up of the bottom float equipment.
- A Youngstown engineer was present to inspect the make-up of the joints.
- The pipe was strapped twice while lying on the pipe rack so that a double check was made.
- 4. A catalyic agent was used on all connections in the bottom 90 feet of the assembly for the first casing joints. The pipe grade was N-80 steel and was not welded because of possible crystalization damage.



5. All 49 #/ft. 8 5/8-inch casing was stacked separately.

2172 - 318A

0

- 6. The threads were cleaned with a wire brush and each thread protector was in place before it was pulled up from the walk.
- The casing was handled with extreme care when it was moved from the rack to the derrick.
- A modified API thread lubricant, that is, one without a silicone base, was used on each joint.
- The accuracy of the weight indicator was checked to aid in subsequent calculations.
- All Halliburton surface lines and connections were pressure tested to 5,000 psig.
- 11. Since a professional crew was utilized in running casing, the danger from the standpoint of accidents was greatly reduced. As the running of the casing was to take over 20 hours, laxity on the part of the crew was one of the major problems.

The mechanical aspects of running the casing are summarized in some of the following points:

- The makeup torque for the extremeline casing was 4,500 ft. -lbs.
 The makeup torque for the long-threaded and coupled casing was 4,900 ft. -lbs.
- 2. Fillup of the 8 5/8-inch casing was done as follows:

A POLUMBUS IN AND ASSULTATES INC.

- a. Each joint of the 8 5/8-inch casing was filled with mud during the raising of the next joint preparatory to insertion and makeup.
- b. Each 10 joints the casing was completely filled.
- c. When the bottom of the casing was at a depth of 8, 200 feet, the filling of the casing was discontinued. The Loffland Brothers Company considered this depth to be safe as far as rig requirements were concerned. The remainder of the casing was floated in.
- 3. When setting the casing in the slips and picking up the casing, the slips were set as gently as possible to avoid any quick movement of casing either in setting or releasing.
- Speed of running casing was limited to 1 foot per second to minimize pressure surges at the bottom of the hole.

Rate of Lowering

Because of the zones of lost circulation which were exposed to the well bore at the time the casing placement, extreme care had to be exercised so that pressure surges would not break down the formation and cause a loss of circulatory returns. An extensive investigation indicated that the largest surge would exist at the time of cementation provided that certain limits were adhered to in the rate of lowering the casing string. During the drilling operation it was noted that mud weights which exerted



四年七二十三十二日、一日の日、日本の日、日本の日、日本の一二

1

greater than 6, 300 psi bottom hole pressure would rupture the formation. Therefore, this value was utilized as the maximum permissible bottom hole pressure during the running and placement of casing.

The pressure surge calculations indicated that the maximum pressure obtained in the lowering of the casing would be below the critical value of the formation provided the lowering rate was 1 foot per second or less.

The three major forces exerted at the bottom of the hole during the running of the casing string are:

- 1. The piston-like movement of the casing itself.
- 2. The viscous drag of the mud along the sides of the casing, and
- The inertial effects when the casing is lifted from and placed in the slips.

Casing Running

The making-up of the float shoe and collar by Halliburton engineers began at 5:50 p.m. on 2 August 1961. The bottom 90 feet of casing had its joint locking ability supplemented by a chemical catalytic compound. The casing was in position at 2:15 p.m. on 3 August 1961. The professional crew employed for this operation had made up each joint with air compressor powered tongs. These tongs had a remote gauge which indicated the foot pounds of torque applied to each individual joint of casing.

-66-

The overall casing placement operation was smooth and efficient. At one point when the shoe of the casing was set at approximately 7,500 feet, the rate of lowering was controlled completely by the weight of the casing string. That is, it took the entire weight of the existing string to pass through this interval. As was pointed out in the drilling section of this report, considerable key seat trouble was encountered in this area. After this depth had been passed by the casing shoe, very little resistance was noted.

Gementing Operation

The stage cementing collars were located in the relative position shown on Figure 11. Three separate stages of cement would be necessary to completely isolate the casing from the bore hole. The first stage cementing collar was positioned at 8, 966 feet while the top stage collar was positioned at 4, 507 feet.

First Stage

In view of the fractured condition of the lower portion of the hole, a gilsonite additive was blended with the cement. The bottom hole temperature of 250° F was not sufficient to be detrimental to the gilsonite slurry. Themelting point of gilsonite is 385° F. Twenty-five pounds of gilsonite were blended with each sack of the pozzolanic mixture. Gilsonite is a solid asphaltene hydrocarbon which reduces slurry weight and mimimizes lost circulation by bridging the larger passages of permeability.



The slurry properties with the gilsonite additive were 12, 5 ppg and a slurry yield of 1, 75 cubic feet per sack.

1

the second second

and the second second

「「「「「「「」」」」をいたので、「」」、「」

Because of the bridging characteristics of gilsonite, the first portion of the slurry was a gilsonite-free mixture. Since the cementing operation went as planned, its position at the bottom of the cement column provided protection in the intervals where the maximum pressure from the hydrostatic head was exerted.

The cementing material in the lower stage is subjected to relatively high temperatures. Because of this condition, consideration was given to strength retrogression.

Halliburton Company studies on the strength behavior of different oilwell cements at extremely high temperatures indicate that all of the manufactured cements lose much of their strength at temperatures above 230° F.

Pozmix 140, due to its chemical nature, does not lose strength, but actually increases it at higher temperatures. It has excellent pumping characteristics and has never, to the knowledge of the Halliburton Company, flash set in any deep well. Pozmix 140 was selected as the best cementing material for this first stage operation because of minimized additive requirements and high compressive strength.

To insure adequate mixing, pumping, and displacement times, five-tenths percent of HR-4, a lignon retarder, was blended with the

cement. This concentration of HR-4 permitted over four hours for the operations to be completed.

网络拉拉马马利斯

The cement slurry weight was approximately 12.5 pgg as opposed to a 9.4 ppg mud system. This differential caused the cement to be displaced at the surface on a vacuum until the time of equalization of head pressures. Equalization time occurs when the same equivalent hydrostatic head is present in and outside the casing. During this period of rapid fall, all available pumps were utilized to displace the slurry to minimize hesitations and preclude the possibility of disassociation.

No mud acid or similar material was used ahead of this first stage of cement. At the time of cementation all zones of lost circulation were sealed off. The introduction of mud acid or similar material could disrupt this healing property and cause the loss of the cement to the formation.

Second Stage

A 50-50 pozzolanic Portland cement mixture was utilized in this stage with 6 percent bentonite added to the slurry. The properties were 7.66 gallons of water per sack in a slurry weight of 13.3 ppg. The slurry volume yield was 1.53 cubic feet per sack.

Because of the delay which was experienced between the second and third stages of the cementing operation, due to the necessity for trucking in of materials, a spearhead of 1,000 gallons of mud cleanout acid was circulated ahead of the cement slurry. The extensive circulating time could have left a deposition of mud cake in the annulus which would have had a detrimental effect upon the second stage cement displacement.

and the provide the second second

The second stage cement was retarded with four-tenths percent HR-4 to provide adequate pumping and displacement times.

Third Stuge

The upper stage of cement was a 50-50 mixture of pozzolan and Portland cement with 6 percent bentonite added. The addition of this bentonite increased the slurry volume to 1.5 cubic feet per sack and rendered a slurry weight of 13.3 ppg. No retarders were added to this mixture since adequate time was available for its pumping and displacement.

To summarize, the cementing material for the first stage was pozmix 140. This is a special hear temperature cementing material. The second and third stages were emented with mixtures of 50-50 pozzolanic and Portland cements.

Operating Procedures

During the first stage of cementation the primary limitation of the displacement rate was the allowable surface pressure of 600 psig.

As soon as the preceding cementation was completed, the bomb was dropped opening the next stage ports.

After circulation had been established, circulation was continued until the mud properties become uniform. Before starting to place cement in stages two and three, the hook load equivalent to the weight of pipe below the free point of the cement was slacked off. Fifty thousand pounds of residual weight was necessary to land the slips in the casing head.

To provide for adequate setting times, 24 hours was provided before any stage collars were drilled out.

Materials and Equipment

945 d - - -

Because of the difficulty encountered in lowering the electric log sondes, a caliper log was not available for calculation of cementing volumes. A substitute method of calculation was employed by pumping down tracers and calculating an equivalent hole size from the lag time. This method provided the following volumes: for the first stage 1,030 sacks of pozmix 140 with five-tenths percent HR-4 and 410 sacks of gilsonite-pozmix 140 mixture. The second stage was cemented with 2,550 sacks of 50-50 pozmix and Portland cement with 6 percent bentonite and four-tenths percent HR-4. The top stage was cemented with 2,020 sacks of 50-50 pozmix Portland cement with 6 percent bentonite.

At the rate of displacement permissible in the first stage of the cementation, the friction losses would approximate 300 psi. The equivalent hydrostatic head exerted on the formations would be 5, 700 psia. The difference between this value and the 6, 300 psi permissible bottom-hole pressure would allow 600 psi surface pressure. This was the limiting value for the first stage displacement. The validity of these assumptions was confirmed as the complete cementing job was consummated with no apparent loss of returns.

As mentioned before, the casing was in position on August 3, 1961, at 2:15 p.m. At this time the cementing head was placed on the casing string and circulation was established at 4 p.m.

The first stage cementing job began after the mud system had been equalized at 6:30 p.m., and the mixing of cement began. At 7:35 p.m. the cement had been pumped in the casing and the top plug was positioned to effect the displacement. At 9:35 p.m. the cement had been displaced without incident and the bomb was dropped to open the first stage tool. One hour later 800 psi pump pressure was applied to the casing and the stage tool opened. Circulation was established with a pump pressure of 500 psi. So that the weight below the free point could be slacked off, a minimum of 12 hours waiting on cement time was allowed to elapse.

When the fluid material immediately above the stage collar had been circulated to the surface, it contained approximately 75 barrels of cement. This would indicate that the lower stage was successfully cemented and preparation for stage two began.

Twenty-eight thousand pounds of hook load was safely slacked off since this represented the weight of casing below the top of the hardened cement. On August 4, 1961, at 3:45 p.m. the second stage of the cementing program was inaugurated. One thousand gallons of mud acid was used as a spearhead to the cement mixture. At 3:50 p.m. cement was being pumped into the casing. At 5:25 p.m. the top plug was positioned to facilitate the displacement of the cement from inside the casing. At 6:08 p.m. the plug landed and at 6:30 p.m. the top bomb was dropped to open the upper stage tool. At 6:52 p.m. 800 psi pressure on the casing opened the upper stage tool. Circulation was maintained with a pump pressure of 300 psi. At 8 p.m. it was noticed that approximately 100 barrels of cement were circulated to the pits. This indicated a good cement job and an overlapping of cement area.

For some unexplained reason during the circulation the stage tool malfunctioned and mechanically closed itself. To complete the cementing operation, 6 holes were placed in the casing just above the stage collar at 4, 501 feet.

On August 5, 1961, at 11:55 a.m. circulation was re-established with a pump pressure of 400 psi. At 12:30 p.m. 1,000 gallons of mud acid were pumped into the casing followed by the cement mixture. At 1:20 p.m. the cement was in place inside the casing and the top plug was positioned for the displacement. At 1:50 p.m. the circulatory returns were cement. At 2:05 p.m. approximately 70 barrels of cement had been circulated. At this time the pipe rams were closed and ten additional barrels of cement were pumped in an attempt to scal off the perforations. After the completion of the cementation operations, all of the weight of the casing string was slacked off except the residual weight required to land the casing in the slips of the well head. A period of 24 hours was then allowed for the setting of the final stage of cement.

Testing

Ī

きょう 二 通いす

The 8 5/8-inch casing was set at a depth of 11, 171 feet and cemented in three stages to the surface with 6,050 sacks of cement. Six perforations were made in the casing from 4,501 feet to 4,502 feet.

The top stage collar was drilled out after the 24-hours waiting-oncement time had elapsed and the casing was pressured to 2,000 psi. The pressure testing of the 8 5/8-inch casing was necessary to insure that a segregation existed between the injected water and the shallow ground waters in the event that a hole in the 5 1/2-inch injection tubing developed at a later date.

On August 8, 1961, a series of tests were conducted with the rig pumps and Halliburton pumps to test the cementing job on the 8 5/8-inch casing string. Each of these tests indicated a loss of pressure and a remedial squeeze operation was necessary.

Rather than squeeze the formation with extremely high pressures an attempt was made to repair the existing cement bond. Latex cement was selected because of its good bonding characteristics with all other types of cements. A 50-sack slurry was used with nine-tenths gallons



of latex per sack of mixture. The slurry weight was 15. 1 ppg, the water requirement was 5 gallons per sack, and the slurry yield of the volume was 1.25 cubic feet per sack. A pressure of 2, 500 pei was used to attempt the displacement of the latex cement mixture.

Subsequent testing indicated the leak had not been repaired after suitable waiting-on-comment time. One additional squeeze operation, however, using the same volumes and comment mixtures achieved a satisfactory test.

Liner Installation

1

\$

After the 8 5/8-inch casing had been set, cemented to the surface, and tested, a 6 3/4-inch hole was drilled to the existing total depth of 12,045 feet. After a series of preliminary injection tests had been conducted it was concluded that the additional investment of the liner completion would be warranted.

Because of the availability on the location of the 5 1/2-inch, 23 #/ft. N-80 extremeline tubing, it was selected as the material to be used for the liner. The bottom of the liner was to be positioned at the top of the fractured granite interval while the top of the liner would overlap into the bottom of the 8 5/8-inch casing string.

To minimize the amount of cement moving downward, a magnesium open hole bridge plug was placed at 11,985 feet with a cement plug positioned on top of this obstruction. The liner was then made up with a Baker float shoe shown on Figure 13 and a Baash-RosssLiner Hanger. Because of the high formation temperatures, the cementing material again was pozmix 140. This material was selected because of its resistance to strength retrogression at high temperatures.

د. در در میباد به است. میدانده مواندی به میشاند و روی داد باقی از زیرانی از از مراد از مراد و از مراد و از رو

777 A.

スキズ と思いした

Here's compar-

The liner was run and positioned without incident. After the cement had been displaced, the packing element was withdrawn from the liner hanger and reverse circulation initiated. After the hole had been thoroughly circulated, final completion operations were commenced.



PHYSICAL OPERATIONS (CON'T)

Service and the Constant of the

PRELIMINARY TESTS

-

Two types of tests were conducted at the Rocky Mountain Arsenal Disposal well. The first injection tests to note fluid disposal susceptibility and the second was production tests to attempt to obtain a representative reservoir fluid sample.

Injection Tests

The prospective reservoir exposed from 11, 975 feet to 12, 045 feet was tested to evaluate, in a cursory manner, its injection possibilities. The test results were favorable enough to warrant initial completion. This phase of the completion operations will be covered thoroughly in a subsequent report entitled "Initial Fluid Injection Characteristics Pre-Cambrian Interval" to be released March 15, 1962, by this office.

Production Tests

Before the drilling rig was released, efforts were made to obtain a formation fluid sample employing air lift. A method of lift was necessary since the reservoir pressure was not sufficient to cause natural flow to the surface. The air lift method of production proved to be uneconomical because of the low rate of fluid entry into the well bore.

After the rig was removed, a beam pumping unit was installed to lift the reservoir fluid. After several days of pumping, fluid entry into the well bore again was so small that the continuation of efforts to obtain a sample seemed unwarranted.

ALL ALL THE

-77. A POLUMBUE JR AND ASBOCIATES INC After 1, 100 barrels of fluid, in excess of the injected volume, were recovered the chloride content was approximately 32,000 ppm. The trend of chloride concentration was approaching the 46,000 ppm present in the fluid from drill stem test No. 14.

· · · · · · ·

1.5

「書記」で

.

-78-

PHYSICAL OPERATIONS (CON'T)

COMPLETION

The casing program employed on the Rocky Mountain Arsenal Well effectively exposed the open hole section from 11, 975 feet to 12, 045 feet to the well bore. After preliminary injection tests had indicated the presence of a potential reservoir through this interval, steps were taken to permanently complete the well.

Subsurface Equipment

19日の日の二書を見た二日の業者に考えておき、何いたい、実施した能しただされたができた。

i.

A print of the type packer employed for the subsurface installation is shown on Figure 13. This packer is a Baker Model D, which has proven itself in many years of oilfield operation as one of the more dependable types of packing installation. This packer affects the segregation between the injected waters inside the tubing and the fresh waters in the tubingcasing annulus.

The packer was set by the use of wireline implement which provides the more positive setting mechanism. The packer was positioned just below the first stage cementing collar at 8, 998 feet. The well bore was next prepared to run the 5 1/2-inch 23 #/ft. N-80 extremeline tubing for the injection path.

Tubing Installation

The bottom section of the tubing string is composed of a Baker production tube which is a perforated short length of tubing. This perforated tube has an inside diameter opening of 2 5/16 inches. This dimension is

depicted on Figure 7. The next article of installation was the seal nipple assembly. This assembly actually affects the packoff within the bore of the Baker Model D packer. Both the seal nipples and the production tube pass through or are sealed inside the packer. The tubing itself is positioned at the top of the packer.

Tubing Set-Down Weights

「おやい」を読むない、「ない」をない、「ない」をは、「ない」をなっていた。

After the tubing had been run and positioned at the top of the Model D packer, 65,000 pounds tubing weight was slacked off to compensate for subsurface forces acting to disrupt the tubing to annular seal.

Values of necessary setdown weights were calculated taking into account three forces--two caused by changes in pressure and one by temperature variations. These forces are summarized as follows:

- Force due to internal and external pressure changes acting on the end areas of the packer.
- Force due to internal and external pressure changes acting on the inside or the outside walls of the tubing, causing ballooning or reverse ballooning.
- 3. Force due to temperature changes of the tubing.

Under the conditions of injection the force on the end areas of the packer would produce the resultant of about 7,000 pounds in a downward direction. The ballooning force, force No. 2, resultant, would be 17,000 pounds in an upward direction, and the temperature force, force No. 3, would be 55,000 pounds in an upward direction. The net effect on the setdown weight would be a reduction of 65,000 pounds.

Since this force is equal to the setdown weight employed at the time of the installation, the tubing will be essentially in equilibrium with the overall length of the seal nipple assembly being an insurance factor for tubing annular segregation. Since these calculations were based on the wellhead surface pressure of 2,000 pounds, an additional safety factor is incorporated in the calculations.

Before the tubing was positioned and landed the final time, potable water was circulated into the annular area between the 5 1/2-inch tubing and the 8 5/8-inch casing.

Stimulation

Since a considerable amount of drilling fluid was lost in the open hole section below the 8 5/8-inch casing shoe, 3,000 gallons of mud acid were injected and produced back to cleanup the area immediately surrounding the well bore.

Well Head

The well head serves as a hanger for the casing and tubing as well as a control device at the surface to permit performance of necessary operations under various well conditions. A drawing of the well head equipment installed at the Rocky Mountain Arsenal is shown on Figure 8. The primary sections of the well head are the casing hanger, tubing spool, master value, float toe, and lubricator value. Each of the casing strings requires a hanger positioned at the well head. Each of these casing strings is hung from this hanger by means of a slip and seal assembly. Since the injection pressures will be applied to the tubing spool, it must be a 3,000 pound working pressure which is an API series 900 rating.

Because of the need for running full diameter tools within the tubing, the master value is of sufficient size to allow such tools to pass. A 6-inch series 900 full opening gate value is the smallest value commercially avsilable which met this requirement.

A 6-inch by 6-inch by 4-inch series 900 studded tee is positioned above the master value with a 4-inch outlet oriented to receive the flow line. This opening is commensurate with the diamet 'r of the discharge lines above the injection punips.

The small diameter gate value above this flow line tee allows the introduction of special tools into the well bore without dismantling the well head. This value has an inside diameter opening comparable with 2 1/2-inch tubing.

At the top of this valve, called the lubricating valve, a tapped bull plug leads to a needle valve and gauge which are provided for visual observation of the tubing pressure. All of these fittings are rated at 3,000 psi working pressure. This well head design provides for all foreseeable requirements within the 2,000 psi operating pressure anticipated.

Surface Safety Devices

1

うるう 御きるを見せるない 明明的に かっていためと思いたます。 いいしょう あたって

Circles and Sectors

¥.

7

. And the

5.4

_____. 1

 With the tubing landed in the packer at the bottom end and the tubing in the slips and scaling assembly at the well head, the annular volume between the 5 1/2-inch tubing and the 8 5/8-inch casing becomes a closed chamber. If any leaks occur in this chamber, a pressure sensing device at the well head would be activated. For this reason, a continuous pressure recording device is incorporated in the well head design. By this means any anomalous pressure behavior in the annulus will be detected immediately and remedial steps can be initiated.



E. A. FOLUMBUS ON ANI-ASNO TATES INC

INDEX DEVIATION FROM DESIGN (VI)

																								Page
DRILLING	•	•	•	•	•	4	•	•	٠	•	•	٠	٠	٠	٠	•	•	•	•	•	٠	٠	•	84
GEOLOGY	•	•	٠	•	•	٠	•	•	•	•	•	•	•	•	•	•	٠	•	٠	•	•	•	•	85
CASING AN	D	СС) N	1P	L	E7	[]	21	V	PI	RC	G	R.	A M	A		•			•	•	•		86

.

1

1

1

E & POLUMBUS IN AND ASSOCIATES INF

1

1. 6 . . .

DEVIATION FROM DESIGN

DRILLING

The deviation of actual drilling program details and time schedule from the program and forecasts presented in the Final Design Analysis report released by E. A. Polumbus, Jr., and Associates, Inc., on July 5, 1960 is summarized in the following tabulation:

Items	Estimated	Actual	Difference
Total Depth	11,400'	12,045'	+ 645'
Number of Cores	15	28	• 13
Footage	6891	6391	- 50
Drill Stem Tests	14	14	- 50
Electric Log Runs	2	3	- 1
Casing Strings	3	4	- 1

Time Analysis-Spud to Total Depth

		Days	
Net drilling time	46.67	55.30	+ 8,63
Coring and reaming core hole	30.19	40.50	-10.31
Drill Stem Testing	13,00	13.60	• 0 60
Electric logging	1.50	4.80	- 3, 30
Run, Cement, WOC and recement casing	6.00	18.20	-12.20
Lost circulation, mix mud, condition hole	7.00	31.50	-24.50
Fishing: drill pipe, bit cones, junk, etc.	0.00	8.90	+ 8.90
Contingencies including waiting on orders	5.00	5.90	+ 0.90
Rig repairs	0.00	6.30	+ 6 30
Total Days	109.36	185.00	-75.64

Reference to the DASCO drilling analysis chart (Figure 6) shows that net drilling time in the Arsenal well from surface to the top of the Lyons

at 9,582 feet was 33 days. This compares to 33 net drilling days forecast in the Final Design Report required to reach the top of the Lyons at an estimated depth of 9,746 feet.

The forecast net drilling time from the top of the Lyons to the estimated total depth of 11, 400 feet was 26 days for the anticipated 1, 654 feet net interval. The 1, 818-foot interval penetrated in the Arsenal well from the top of the Lyons at 9, 582 feet to 11, 400 feet required 51.5 net drilling days. The section of this report dealing with Penetration treats of the various factors in the Areenal well contributing to this difference of 25.5 net drilling days.

GEOLOGY

The following tabulation summarizes the estimated versus actual depths of the various geological marker tops in the Arsenal well:

	Depth to Top				
Geologic Formation	Estimated	Actual			
Fox Hills	1,345'	1, 250'			
Pierre Shale	1,455'	1,480'			
Hygiene Zone	5, 325'	5,4481			
Niobrara	7,8051	7, 710'			
Carlile Shale	-	8,078'			
Greenhorn Limestone	-	8,1201			
Granerous Shale	-	8, 345'			
"J" Sandstone	8,576'	8,485'			
Dakota Sandstone	8,816'	8,6331			
Lakota Sandstone	8,916'	8,730'			
Morrison Formation	8,936'	8, 7861			
Lykins Formation	9,341'	8,0721			
Lyons Formation	9,7461	9, 582 '			
Fountain Formation	9,8651	9,772'			
Regolith	-	11,880'			
Ordovician? Cambrian?	•	11,895'			
Pre-Cambrian Schist	•	11,950'			
Pre-Cambrian Gneiss	11.400'	11.9701			

-85-

E A FOLUMBUS IN AND ASSU-TATES IN

CASING AND COMPLETION PROGRAM

11.40

Martin Contraction

. **K**. - **G**.

4

į,

j,

à

5

The principal differences between the program originally designed and the program actually followed were the setting depth of the 8 5/8-inch casing string and the total depth of the well.

Hole conditions dictated the necessity for the premature setting of the casing while the actual depth was some 600 feet deeper than that anticipated. Because of these conditions, a liner completion was necessary to case off the interval from the top of the pre-Cambrian rocks to the bottom of the 8 5/8-inch casing.

The following table summarizes some of the main points of necessary deviation;

	Designed	Actual
Total Depth	11,400 ft. = 300 ft.	12,045 ft.
Casing Setting Depths		
20 -inch	125 ft.	135 ft.
13 3/8-inch	2,000 ft.	2,020 ft.
8 5/8-inch	11,400 ft.	11, 171 ft.
5 1/2-inch	Not Required	11,975 ft. (liner)
Packer Setting Depth	10,000 ft.	9,000 ft. (approx.)
Tubing Required	10,000 ft. (approx.)	9,000 ft. (approx.)
Casing for Liner		
5 1/2-inch	None Required	1,000 ft. (approx.)
Perforating	Jets or Bullets	None Required

INDEX RESUME OF ORGANIZATIONAL FUNCTIONS (VII)

1

<u>مة</u>

	Page
Corps of Engineers	87
Chemical Corps	88
E. A. Polumbus, Jr., and Associates, Inc	89
Loffland Brothers Company	92
Service and Equipment Companies	92

E & FOLUMBUS OF ANE ASSOCIATES HE

RESUME OF ORGANIZATIONAL FUNCTIONS

The design and drilling of the Rocky Mountain Arsonal Pressure Injection Disposal Well was assigned to the U. S. Army Corps of Engineers, Omaha District, by the U. S. Army Chemical Corps. The Corps of Engineers in turn engaged the firm of E. A. Polumbus, Jr., and Associates, Inc., to design the well, supervise the drilling and completion, provide the necessary engineering and geological services, and manage the project. These services were provided for under an Architect-Engineer type contract (contract No. DA-25-066-eng-6033). The design of the treating plant facilities was assigned to A. J. Ryan and Associates under a separate contract.

Corps of Engineers

Colonel H. G. Woodbury, Jr., District Engineer, U. S. Army Corps of Engineers, Omaha District, appointed Lt. Colonel J. M. Frassrand as Contracting Officer for contract DA-6033. Colonel J. J. Haley replaced Lt. Colonel Frassrand in October, 1961. Mr. Ralph E. Rader, Chief Military Design Branch, served as Contracting Officer's Representative throughout the term of the contract.

Other Corps of Engineers supervisory personnel who were directly or closely associated with the project were Mr. J. Ackerman and Mr. Gordon Haugse. Mr. Ackerman was aggressively involved during the initial phases of the negotiations between the Corps of Engineers and the

E A FOLUMBUS IN AND ASSO ATE IN

Polumbus firm. He also was active in later critical phases of an administrative nature. Mr. Haugse functioned throughout the term of the contract in a liaison capacity expediting necessary contacts between Polumbus personnel and the Corps of Engineers.

The Corps of Engineers' field representative was Mr. J. Zeltinger, He was assigned to the well site as a geological observer.

Chemical Corps

1

Although not directly involved in the design or construction phase of the project, the Rocky Mountain Arsenal administrative personnel contributed appreciably to the efficient functioning of the operation. Through their co-operative efforts, Colonel William J. Allen, Jr., Commanding Officer until his retirement, September 30, 1961, his successor, Colonel Charles H. McNary, and Mr. George F. Donnelly, Chief, Engineering Division, effected a well co-ordinated relationship between the Arsenal Complex and the drilling operation.

Mr. John O. Neighbours, Jr., was assigned to the project as an engineering observer on the well site. His familiarity with governmental procedures and visiting government personnel coupled with the knowledge he acquired during the progress of the operation was of considerable aid to the project management.

(b) is a sub-lightering of a state of the state of the

E. A. Polumbus, Jr., and Associates, Inc.

Mr. E. A. Polumbus, Jr., president of the consulting petroleum engineering firm, appointed Mr. O. E. Mechem as project manager for all engineering and operations work done under contract DA-6033. Prior to this contract Mr. E. O. Gregory of the Polumbus firm was in charge of the preliminary design work conducted under the earlier contract, DA-5969. Mr. D. M. Love was appointed to handle the comptroller aspects of the contract which involved matters of finance, accounting, and bookkeeping.

The design, planning, and contracting phases of the contract were handled by various specialists in the Polumbus firm, with the details being handled for the most part by Mr. C. E. Haskett and Mr. Al Samuels. Mr. Mechem personally conducted conferences and negotiations regarding drilling specifications and design of a drilling contract. This effort culminated in a contract (No. 6724) being awarded to the Loffland Brothers Company for the drilling of the well. Mr. Henry Sikso served as Contracting Officer's Representative for the Loffland contract. Inasmuch as E. A. Polumbus, Jr., and Associates, Inc., under contract No. 6033 was authorized to manage the drilling operation under contract No. 6724, a close association developed in the co-ordinated handling of the two contracts. Not only were the physical operations conducted under the direction of the Polumbus firm, but the accounting of expenditures for both contracts was routed through the Polumbus' office comptroller section. Mr. Mechem's duties as project manager for E. A. Polumbus, Jr., and Associates covered all phases of the drilling and completion of the well. He was required to be familiar with all developments on the well, and to be available for conferences at the well site as well as in the various business offices at all times.

The contract called for 24-hour engineering supervision at the well site. Engineers from the Polumbus firm were assigned to regular and relief 12-hour shifts. Mr. Al Samuels was designated as Project Drilling Engineer on the well site. He maintained constant contact with the well either by actually working at the site during one of the 12-hour shifts or through telephone contact with the engineers on duty.

Mr. L. J. Scopel was the Project Geologist and was responsible for all geological aspects of the operation. He was available on 24-hour call throughout the drilling of the well. The Baroid mud logging facilities included operators on the unit on a 24-hour basis. This personnel was under the supervision of the Project Geologist.

Mr. J. H. Garrett was the Project Completion Engineer and directly supervised the completion activities, including injection testing, procurement of formation water samples and the final setting of the well head.

Various other members of the Polumbus staff followed specific phases of the operation and were available for consultation or field

A POLUMBUS OF AND A D SHITE HA

operation in their specialities. Among evere Mr. B. A. Lear as Project Testing Engineer, and Mr. D. A. E. land as Project Reservoir Engineer.

Throughout all phases the Project Manager was informed daily of the progress and developments on the well. He was also notified of any special developments at the time of occurrence. "his information was relayed, daily, to the Corps of Engineers in Omaba. Whenever a question a rose or technical and/or managerial advice were required, the entire staff of the Polumbus firm as well as specialists from the drilling contractor and oilfield service companies were available for consultation. Conferences were held in the Polumbus Denver offices and at the field office for all major decisions.

Following is a list of technical and managerial personnel in the Polumbus organization that were associated directly with the drilling and completion of the Rocky Mountain Arsenal Pressure Injection Disposal Well:

Drilling, Completion, Testing, and Management

E. A. Polumbus, Jr. O. E. Mechem D. M. Love

Ī

Ī

Į

Mart H. Shi

「日本」に「「「「」」」、「「「「」」」」「「「「」」」」「「「」」」」」」、「」」」」、「」」」、「」」」、「」」、「」」、「」」、「」」、「」」、「」」、「」」、「」」、「」」、「」」、「」、」、「」

「「「「「「「「「」」」」を見ていた。「「」」」」

A. Samuels
J. H. Garrett, Jr.
D. A. Rowland
B. A. Lear
L. J. Scopel

President and General Manager Project Manager Comptroller

Project Engineer-Drilling Project Engineer-Completion Project Engineer-Reservoir Project Engineer-Testing and Logging Project Geologist

4,49

E & FOLUMBUR IN AN ANY DUIATES THE

Operations

G.	с.	Welch	Engineer
H.	H.	Sells	Engineer
F.	J.	Kirchman	Engineer
J.	C.	Bosio	Engineer
н.	в.	Shirley	Geologist

Advisory

G.	R.	Downs	Geology
м.	s.	Legge	Drilling Analysis
C.	E.	Haskett	Design Engineer
Ε.	о.	Gregory	Design Engineer

Loffland Brothers Company

The drilling operations staff of Loffland Brothers Company was available for consultation throughout the drilling of the well. Mr. W. C. Walker, the division manager in Casper, Wyoming, was in daily contact with the drilling operation through his superintendent, Mr. K. W. Conner and the location drilling foreman (toolpusher) Mr. Louis Brown. Mr. Brown was in close 24-hour contact with the well. This team of drilling experts was supported by the Loffland drilling engineering staff in Casper, Wyoming, and in Tulsa, Oklahoma.

Service and Equipment Companies

Contract DA-6033 included provisions that required E. A. Polumbus, Jr., and Associates, Inc., to procure specialized services and/or equipment as needed during the drilling and completion of the well. Following is a list of companies that provided such services and/or equipment. Acme Tool Transportation, Inc.

Armco National Supply Division Armco Steel Corporation

Aurora Sand & Gravel Co.

Baash-Ross Division of Joy Manufacturing Co.

Bethlehem Steel Company

Bromley and Siebert Excavating, Inc.

Continental-Emsco Company

Cox Welding Service

The Denver and Rio Grande Western Railroad Co.

Drilco Oil Tools, Inc.

Duke's Truct & Auto Repair

Frohlick Crane Service

G. & L. Tractor Service, Inc.

Halliburton Company

John Bunning Transfer Co., Inc.

Maddox Oil Company

Miers Well Service, Inc.

Miner Machine Company

O'Quinn & Murray, Inc.

Prestons Welding Service

A. J. & J. Welding Service

Associated Oil Field Rentals Division of Homeo

Aurora Welding & Repair Service

Baker Oil Tools, Inc.

Baroid Division National Lead Company

Cable Drilling, Temperature and Well Servicing Co.

Core Laboratories, Inc.

Dalgarno Transportation, Inc.

Dowell Division of the Dow Chemical Co.

Drilling & Service, Inc.

The Farley Machine Works Co.

Grant Oil Tool Company

Hagan Chemicals & Controls, Inc.

Houston Oil Field Material Company, Inc.

Lane-Wells Company

Mid-Continent Supply Co., Inc.

Mine & Smelter Supply Co.

Oil Well Perforators, Inc.

Power Rental Equipjent, Inc.

Schlumberger Well Surveying Corporation

Ï Tombin Transportation Company Treasurer of the United States Headquarters, Rocky Mountain Arsenal Well Completions Incorporated I Winslow Crane Service Wright Petroleum Laboratories al a support a conference

ł.
INDEX PROSPECTIVE INJECTION RESERVOIRS (VIII)

Pa	g	e.
and and the second s	-	

SELECTION PARAMETERS	. 95
Cores	. 99
Formation Logs	. 100
Drill Stem Tests	, 101
Drilling Records	. 102
CHARACTERISTICS OF POTENTIAL INJECTION	
RESERVOIRS PENETRATED	. 104
Hygiene Sandstone	. 104
Codell Sandstone	. 105
"J" Sandstone	. 105
Dakota-Lakota Sandstones	. 106
Morrison Formation	. 107
Lykins Formation	. 107
Lyons Formation	. 108
Fountain Formation	. 109
Pre-Fountain Regolith	. 111
Ordovician? Cambrian?	. 112
Pre-Cambrian	. 112

Ī

I

CALLS IN A LAND

CLAR SON

I

T

T A FOLUMBUR IN AND ANDOLATEN IN

State of the second second

1 . Au. -

Second and State

PROSPECTIVE INJECTION RESERVOIRS

SELECTION PARAMETERS

State of the second second

ころで発展したました

大学の方法でいた

したな

And and State and

In the Final Design Analysis for the Rocky Mountain Arsenal Pressure Injection Disposal well eight of the geologic formations or units to be penetrated were considered as objective horizons in the search for an injection reservoir. The well was completed with the lowermost 70 feet of the well bore, in fractured pre-Cambrian rock, being tested as the initial injection reservoir. This section had not been predicted as a prospective injection reservoir.

The stratigraphic section and the mechanical aspects of the well are summarized in the frontispiece. Table 1 also shows the details of the stratigraphic section.

The interval under test is exposed in the open hole below the 5 1/2inch liner. Regardless of the results of the initial fluid injection it is to be expected that at some time in the future this disposal reservoir will have accepted its capacity of waste fluids at designed injection pressures and a new injection reservoir will have to be sought in the cased portions of the hole. When or before this occurs the potential of the various strata in the well to serve as a waste disposal reservoir should be evaluated. Selection of the next reservoir to be tested will be based not only on the relative merits of the strata, but also on operational factors.

> -95-A POLUMBUS OF AND ANACIATIN OF

It is not within the scope of this report to present a detailed evaluation of the waste disposal reservoir potential of all of the strata of the well. However, a brief discussion of the necessary considerations for such an evaluation is presented and the observed physical characteristics of the various formations are summarized.

There are two basic considerations in estimating the potential of subsurface strata to serve as an injection reservoir, i.e., storage capacity of the rocks and accessibility to this storage. More commonly expressed, it is necessary to ascertain if there is porosity in the rock indicating the existence of storage space and if permeability is present to permit fluid to enter the pore space at desired rates and pressures. The quantitative inter-relationships of these factors and other considerations such as friction and volume are complex, but the basic requirement is permeability and porosity.

Most rocks exhibit some degree of natural permeability and porosity. The natural permeability and porosity of unsealed indigenous fractures in the rocks are also important considerations in that they provide large areal access to the pore space in the matrix rock. Furthermore, fractures can be induced or natural fractures can be enhanced by mechanical means. In calcareous materials acid treatment can increase permeability near the well bore and thus provide increased access to the matrix material.

-96-

A FOLUMBUS & AND ASSOCIATES INC

An idealized injection reservoir would have an interval of highly porous and permeable rock. Open fractures, either natural or induced, would be present, if necessary, to provide rapid distribution of the fluid from the well bore and to give widely distributed contact of the fluid to the porous and permeable rock. Lacking these idealized conditions, compromises and adjustments have to be accepted.

ī

In the case of the Arsenal well, it can be stated that in .ll cases the rocks penetrated in the various objective zones, exhibited low porosities and very low permeabilities. It is doubtful that sufficient matrix permeability and porosity exist to establish any one of the objective zones as a reservoir utilizing a practical thickness of this rock. However, numerous fractures were observed in cores, in portions of a large interval in the well, and additional fracturing is inferred and interpreted to exist from log data and lost circulation occurrences.

It is believed, therefore, that in selecting injection zones in the Arsenal well that determination of the more highly fractured zones will be a prime consideration. Secondarily, the matrix characteristics of the various fractured zones should be compared. These factors should then be considered and balanced against the operational factors before selecting a zone to be tested.

Since the Arsenal well is located a considerable distance from other wells penetrating the same sediments, and since it is so far removed from



the outcrop area, extrapolations are not possible. Thus, it is necessary to assume that the physical characteristics observed in the well bore will be continuous over the radius of influence of the well.

In the programming and the drilling of the Arsenal well, gathering of data was a prime consideration. Economics and operational considerations sometimes forced modifications of this program, but every effort was made to obtain the necessary data for evaluation of the injection reservoir potential of the strata penetrated.

Some of the more important tools and data to aid in this evaluation are listed below:

Cores

Į.

Descriptions Analyses

Formation Logs

Sample Descriptions Induction-Electric Logs Micrologs Sonic Logs Gamma Ray-Neutron Logs Mud Logs

Drill Stem Tests

Drilling Records

Penetration Rate Changes Lost Circulation Zones

E A HO UNBUS IN ANE ANNY SEEN IN

Cores

Cores are the most positive indication of subsurface conditions available. With them it is possible to examine an actual piece of the formation of significant size. The lithology and physical makeup can be seen, fractures can be observed and direct measurements of the physical characteristics of the rock can be made.

Among the most important core measurements available from the pressure injection well at the present time are the matrix permeabilities and porosities measured on the recovered cores. The descriptions of the frequency, size and nature of fractures are also very valuable.

The limitations of core data should be recognized. Cores only provide data over a limited interval. Extrapolations are made and continuity of character is frequently assumed, but the quality of such data is dependent on the percentage of total section cored and the manner of selection of the cored interval. For example, cores objectively taken at pre-determined intervals are statistically more representative of the characteristics of the total section than cores taken wherever some favorable formation characteristics were noted.

During the drilling of the Arsenal well, a total of 28 cores were attempted. These cores cut 639 feet of section from which 575 feet were recovered. This gives a recovery percentage of 90 percent. Table 7 lists the cored intervals and formations as well as the recoveries.

E. A. HOLLIMBERS IN ANY ANY INTERST. 12

Formation Logs

Because of economic and operational limitations, evaluation tools such as cores and drill stem tests are only used in selected or limited portions of a hole. On the contrary the various formation logs normally provide data for the full section penetrated. Most types of logs, however, are records of measurements or observations of various physical properties of the strata. Most frequently these data are not directly applicable to reservoir problems and to be usable, interpretations and calculations based on theoretical or empirical relationships are required.

From the sample logs and the various electrical logs the lithology and thickness of the strata can be determined. The quality of data from a sample log is dependent on such factors as the nature of the rock, the drilling rate, and the nature of the drilling fluids. The primary application is the determination of lithology and only qualitative observations of reservoir parameters such as permeability and porosity are possible.

In addition to their application in the determination of lithology and thickness of strata, the various electrical logs can be utilized in calculating porosities. Especially where core data is available for checking and calibration, usable porosity data can be calculated from the logs.

At the present time there are no recommendable interpretative techniques to estimate formation permeability from the formation logs.



·普·洛二·马克克克·阿拉拉拉·马利·马利尔·马尔尔·马尔克尔克·马利尔

The Sonic log is the most useful tool in calculating porosity, and in addition it gives valuable indications regarding the possible location of fractures or fracture zones. Although these data are not completely definitive, the indications are sufficiently reliable to be used as supporting evidence. One shortcoming of the Sonic log in locating fractures is that it gives no indication of vertical fractures.

A summary of the various logs taken during the drilling and completion of the Arsenal well is shown in Table 24.

Drill Stem Tests

1

From successful drill stem tests, data can be obtained in regard to the fluid contained in the rock, the reservoir pressure, and the overall capacity of the tested interval to transmit fluid. Each of these is applicable in the evaluation of prospective injection reservoirs.

From the standpoint of contamination, it is not desirable to inject waste fluids into any strata considered to have a potential for producing oil or gas within the effective area of the injection reservoir. Although the various samples and logs give some indications of the fluid content of the formation rocks, a drill stem test is the most positive means of actually sampling the formation fluid during the drilling of a well.

Injection in a reservoir is accomplished by compressing the natural reservoir fluids which are assumed to occupy 100 percent of the pore space in the rock at the natural reservoir pressure. The space thus created is

-101-

F A FOLIMIER H AN AT 25 MES IN

then occupied by the waste or injected fluid. If the natural reservoir pressures are abnormally high, excessive injection pressures are required.

The pressure of a reservoir can be obtained from the pressures re orded during 2 drill stem test or from extrapolations made from these pressures.

Calculations from drill stem test pressures may show the overall capacity of the tested interval to transmit fluids. This is, of course, directly applicable to the evaluation of the initial injection capacity of the interval.

A total of 14 drill stem tests including one wireline test were attempted in the well. Of these, ten of the drill stem tests were mechanically successful. Due to the low permeabilities in the rocks tested, it would have required prohibitively long testing periods to have obtained optimum pressure data. Therefore, in many of the tests, it will not be possible to make reliable quantitative pressure interpretations.

The details of each test are shown in Tables 9 through 22. A summary of the tests and intervals is shown on page 53.

Drilling Records

Total State

One of the most valuable tools to assist in evaluating prospective injection horizons is the record contained in the drilling log of occurrences of lost circulation while drilling.

E A FOELMEL OF AND AN COURTER OF

When lost circu ion occurs, it means that in the strata being drilled or in some pot on of the strata already drilled, the natural reservoir pressure has been exceeded by the hydrostatic pressure of the mud column to the extent that mud is being injected into that strata. In essence, by accident, the well becomes an injection well during the period of the mud loss.

The identification or location of the interval of lost circulation is not always possible. However, most frequently the lost circulation occurs in the zone being drilled. A careful analysis of penetration rates, mud characteristics, remedial procedures used and well performance after the resumption of drilling must be coupled with other analyses of cores and formation logs before an interpretation of the location of a lost circulation zone is made. Lost circulation occurrences are graphically portrayed in Figure 10.

E A FREUMURIC & AN ARCLERICE M.

PROSPECTIVE INJECTION RESERVOIRS (CON'T)

CHARACTERISTICS OF POTENTIAL INJECTION RESERVOIRS PENETRATED

In the Final Design Analysis, all of the anticipated objective injection reservoirs to be penetrated in the Arsenal well were considered and discuss. 3. These included the Hygiene sandstone zone, the Codell sandstone, the "J" sandstone, the Dakota sandstone, the Lakota sandstone, the Morrison formation, the Lyons formation, and the Fountain formation. The fracture: pre-Cambrian rock interval which is being initially tested was not originally predicted to be a possible injection reservoir.

In the following discussions frequent reference is made to specific data regarding the various strata. The following list shows where these various data are found in the report:

> Frontispiece and Table 1 Stratigraphic section Sample and core descriptions Sample log - Vol. III Core descriptions Table 2 Core analyses Logs - Vol. III, Table 23 Summary of cores Table 7 Drill stem test summary Page 53 Tables 9 to 22 Drill stem test results Formation logs Vol. III Figure 10 and Vol. II Drilling records

Hygiene Sandstone

I

think ter

The Hygiene sandstone zone in the Arsenal well is composed primarily of sandy shales. Since no sandstone development of significance was noted, this zone is regarded as having no potential as an injection reservoir.

A FOLOMBON IN AND A STITLE D. HD.

Codell Sandstone

There was no recognizable development of the Godell sandstone in the Arsenal well.

"J" Sandstone

The 120-foot interval of "J" sandstone in the Arsenal well between 8, 485 and 8, 605 feet consists of a 45-foot section of quartzitic sandstone containing slight oil staining and some fracturing and 75 feet of intermixed, quartzitic sandstone and dark grey shales.

A total of 62 feet of "J" sandstone was cut in two cores in which the recovery was 100 percent.

From the sandstones recovered, a total of 38 core samples were analyzed. All permeabilities were less than one millidarcy. Porosities ranging from 11.2 percent to 2.1 percent were measured with the arithmetic average porosity being 5.7 percent.

Oil saturations were noted in the "J" sandstone core samples to a depth of 8, 525 feet. Visual examination showed this to be spotty saturation.

A drill stem test was taken in the 8, 482 to 8, 556 foot interval which includes the better developed sandstones and more especially the interval which showed oil staining. The tool was open one hour and recovered only 200 feet of slightly gas-cut mud.

Qualitative analysis of the Sonic log shows some possible fracturing in the "J" sandstone interval. There were no mud losses in the section during the drilling and coring operations.

E & FOLUMEUS ON AND AND DATES OF

The quality of the "J" sandstone as evidenced by the core and log data and the poor recovery in the drill stem test eliminates the "J" sandstone as a potential injection reservoir in this well.

Dakota-Lakota Sandstones

「「「「「「「「」」」」

۴

The Dakota-Lakota sandstones are in the 153-foot interval between 8, 633 and 8, 786 feet in the Arsenal well. The upper sandstones (Dakota) are characterized as being of fine to medium grain size and hard to quartzitic. The Lakota sandstones are fine grained and quartzitic. Both contain some shaly sandstone and a 20-foot shale section separates the two units.

Three cores were taken in the Dakota sandstone. Of the total of 52 feet of section cut, 50 feet were recovered. This represents a recovery of 96 percent.

Thirty-one samples of sandstone from the cores were analyzed. With two exceptions the permeabilities were less than one millidarcy. One sample showed 1.4 md. and one sample, described as fractured, showed 3.5 millidarcies permeability. The porosities ranged from 8.5 percent to 1.7 percent with the arithmetic average being 4.6 percent.

• One drill stem test was taken across the interval from 8,628 to 8,821 feet. This includes the Dakota and Lakota sandstones and an upper shaly portion of the Morrison formation. The tool was open one hour and only 400 feet of slightly gas-cut mud was recovered. A qualitative interpretation of the Sonic log shows some possible fracturing, but this was not verified in the sections cored. There were no mud losses noted during the drilling and coring of the interval.

On the basis of the data obtained, the Dakota-Lakota sandstones are not considered to be potential injection reservoirs in this well.

Morrison Formation

During the drilling of the 186 foot interval of the Morrison formation penetrated between 8, 786 and 8, 972 feet none of the strata exhibited characteristics of sufficient quality to warrant coring or drill stem testing.

From a qualitative analysis of the well logs and other well data, none of the zones are indicated to have significant porosity or indications or permeability to be of interest. Thus, the Morrison formation is not believed to have any potential as an injection reservoir.

Lykins Formation

The Lykins formation is 610 feet thick and was encountered in the interval between 8, 972 and 9, 582 feet. The sediments are red, silty shales with the exception of 15 feet of fine grained quartzitic sandstone near the top of the formation and an 80 foot section of anhydrite and red shale near the base of the formation.

There were no cores or drill stem tests taken in this interval. Some possible fracturing in the 15 foot sandstone interval is indicated by the Sonic log. This sandstone is not considered to be of sufficient thickness

E & ECCENTER FOR ANY A POST ALE OF

for it to be considered as a potential injection reservoir. The only possibility would be to combine this unit with other potential reservoirs.

Lyons Formation

1

The Lyons formation was encountered in the 190-foot interval between 9, 582 and 9, 772 feet in the Arsenal well. It consists of fine-grained orange quartzitic sandstone with thin red to marcon shales.

A total of 95 feet of section was cut in 8 cores taken in the Lyons formation. From this interval 84 feet were recovered which represents an 88 percent recovery.

One hundred thirty-two samples of sandstones from the cores were analyzed. With one exception the permeabilities were less than one millidarcy. The observed porosities ranged from 7.1 to 1.0 percent with the arithmetic average porosity being 3.1 percent.

Extensive fracturing was observed throughout the cores recovered in the Lyons formation. Some of the fractures are closed and others are described as hairline fractures of several inches to open fractures one to two feet in length.

Due to the anticipated mechanical difficulties associated with the presence of fractures and the occurrences of lost circulation and the possibility of loose sand being produced during testing, no attempts were made to test the Lyons formation with conventional drill stem test tools. As an alternative means, one formation test was attempted utilizing the Schlumberger Formation Interval Tester. This test was unsuccessful due to plugging of the tool with lost circulation material in the drilling mud.

-108-

Indications of fracturing in some of the drilled intervals in the formation are noted on the Sonic log. These indications are found principally in the top 130 feet of the formation.

The first lost circulation in the well occurred shortly after drilling into the Lyons formation. A total of eight instances of mud losses were noted in drilling this formation. These ranged in severity from a 10-barrel loss to a 320-barrel loss per occasion.

In the Lyons formation there is a higher density of favorable indications of the zone having the qualifications necessary for a disposal reservoir than in any other interval penetrated. However, it should be mentioned that there is a heavy concentration of core data in the upper 140 feet of the formation. In some of the subsequent drilling, coring was not undertaken due to mechanical and economic considerations. Furthermore, the occurrences of lost circulation may have decreased in subsequent drilling as a result of experience gained while drilling in the Lyons formation.

On the basis of the various characteristics observed it can be stated that the Lyons formation contains prospective injection reservoirs and future testing of this interval is definitely warranted.

Fountain Formation

and the lost

A total interval of 2, 108 feet of Fountain formation was penetrated between 9, 772 and 11, 880 feet in the Arsenal well. The upper 110 feet of the formation consists of fine grained feldspathic sandstones, siltstones, and maroon shales. Below this interval the sediments are primarily arkosic sandstones and conglomerates and red and green shales. The cement for the clastics may be calcareous materials or a combination of calcareous and clay materials.

A total of 408 feet of section was cut in 13 cores taken in the Fountain Formation. The recovery of 359.5 feet represents 88 percent.

The 220 samples analyzed contained 37 samples which showed permeabilities of one millidarcy or greater. The majority of these higher permeabilities are found in the interval between 11, 265 and 11, 300 feet.

The porosities measured in the formation ranged from 7.8 to 0.8 percent with the arithmetic average being 3.2 percent. Of interest is the fact that the average porosity associated with the 37 samples showing permeabilities of one millidarcy or greater is 4.8 percent.

The cores showed a high degree of fracturing to a depth of 10, 400 feet. Below this depth only scattered fracturing was observed in the cores; however, a preliminary interpretation of the Sonic log shows possibilities of scattered fracturing in intervals throughout the formation.

Eleven attempts were made to drill stem test portions of the Fountain formation. Three tests were unsuccessful, but some of the remaining tests yielded usable pressure data. Fluid recoveries were drilling mud or mud contaminated formation water in all but one instance. In test No. 14 which covered the lower portion of the Fountain formation into the pre-Cambrian rocks, 5,400 feet of salt water was recovered.

A FULLIMER F AND AN 7

Numerous occurrences of lost circulation were experienced while drilling and coring in the Fountain formation. The greater number of these mud losses occurred in the interval between 9,960 and 10,250 feet. The lowermost mud loss took place at 11,080 and was the most serious in the well with some 1,350 barrels being lost.

17. Mar 21. ----

As might be expected, the zone where mud loss frequencies were high and the zones where fractures were observed coincide in part. This general interval from the top of the Fountain at 9,772 to a depth of 10,400 feet is thus considered to warrant consideration as a prospective injection reservoir.

The zone of higher permeability noted in the core analyses from 11, 265 to 11, 300 should be carefully analyzed and any other zones showing similar log characteristics should be carefully investigated. Though the average permeability is only 1.7 millidarcies, the nature of this material can be prospective of an injection reservoir if sufficient thickness exists.

Due to the widespread indications of possible fracturing, the entire Fountain formation warrants analysis for injection reservoir prospects, but these two zones specifically mentioned should be given special attention. Pre-Fountain Regolith

The pre-Fountain Regolith encountered between 11,800 feet and 11,985 feet in the Arsenal well is not believed to have prospects as an injection reservoir due to the predominantly shaly nature of the sediments.



Ordovician? Cambrian?

In the 55 foot interval of Ordovician? Cambrian? sediments encountered between 11, 895 to 11, 950 feet there is one 15-foot section of conglomerate and one 10-foot section of dolomite.

Aside from the logs there are no other interpretative data for this interval. A qualitative interpretation of the logs shows sufficient favorable indications to warrant a detailed analysis of these two units.

Pre-Cambrian

いた言葉

The pre-Gambrian rocks were drilled from 11,950 feet to the total depth of the hole at 12,045 feet. The upper 20 feet are a weathered schist and the remainder of the hole drilled in a fractured granite hornblende gneiss containing pegmatite intrusions.

One core in the pre-Cambrian rocks recovered seven feet of the 9 feet cut. No permeability and porosity determinations were made from this core. After cutting this core, lost circulation was experienced.

The final liner was set to 11,975 feet leaving the pre-Cambrian interval from 11,975 to 12,045 feet open. Preliminary injection testing showed the zone to be capable of initially accepting desired volumes of fluid within the pressure limitations imposed.

а до не на «на на за се за

INDEX CURSORY CONSIDERATIONS FOR INJECTION WELL OPERATIONS (IX)

Ţ

The second

The second second I

Î

あるというできまし

いたのであるというのであるというのである

I 1.24

	Page
STIMULATION	113
FLUID COMPATIBILITIES	114
RESERVOIR EQUILIBRIUM	114
CORROSION	115
External a concerción concerción de concerción de la conc	115
internati a a a a a a a a a a a a a a a a a a	115
MIGRATION OF INJECTED FLUIDS	116
PLANT OPERATION	117

crease (and december of the second second

CURSORY CONSIDERATIONS FOR INJECTION WELL OPERATIONS

The final phase of the construction of the disposal well was the physical completion and preliminary injection testing. Indications were that the open-hole interval was capable of accepting 400 to 800 gallons of water per minute with a corresponding surface pressure less than 2,000 psig. The duration of this capability has not yet been established.

STIMULATION

In the event that the disposal reservoir currently exposed to the wellbore stops accepting commercial quantities of waste water within the stipulated pressure limitations, two possibilities are present. First, if the storage capacity of this reservoir has been reached, another reservoir must be exposed by recompletion. Second, if the reservoir has not reached its storage capacity but has a flow impediment in the vicinity of the wellbore, remedial permeability repairs may be warranted. Among the possible repair methods are:

- 1. Acidizing This approach could remove the impediment if the material causing the restriction is acid soluble.
- 2. Hydraulic Fracturing This solution would create new channels of permeability and prop them open with suitable propping agents introduced in the fracture creating fluid.
- 3. Surfactant Treatments This mechanism is to reduce surface tension values and thereby change wetting characteristics. Relative permeability or the ability to flow through a porous media is affected by the preferential wetting characteristics of the material.

- 4. Backwashing This system induces the well to f', w by release of surface back pressure. If the reservoir pressure is insufficient to cause flow to the surface, the well may have to be swabbed or pumped to clean the sand face.
- 5. Additional methods are available for stimulation treatments but are considerably more specialized in their applications.

An investigation of such items as pressure behavior, fluid composition, matrix rock characteristics, nature of the impediment, etc., is required to recommend the type and method of stimulation for the individual zone or zones to be treated.

FLUID COMPATIBILITIES

The large volume of fluid to be disposed of at the Rocky Mountain Arsenal prohibits complete chemical treatment due to economic considerations. The displacement of any undesirable fluid or matrix reaction precipitates from the immediate vicinity of the wellbore minimizes derogatory effects. For this reason a "buffer" water spearhead is injected to keep separated the natural formation connate waters and the injected waste fluids. This separation is effected until the connate waters have been displaced some 100 feet from the wellbore.

RESERVOIR EQUILIBRIUM

In addition to compatibility considerations, the injected water should have innate stability at reservoir conditions of temperature and pressure. In addition, the water must be relatively innert to the reservoir matrix rock.

CORROSION

Two corrosion possibilities exist with injection or producing wells. First there is the possibility of external attack and second the possibility of internal attack.

External

Aleman, and more

The action of ground waters and other sources of possible external corrosion should be minimized at the disposal well because of the complete isolation of the casing from the borehole by the cement sheath. Because of the cost involved in the disposal well, reliance on this sheath alone would not be good operating procedure. Periodic potentiometer surveys and possibly cathodic protection would be warranted. An evaluation of the severity of the problem should be made prior to the initiation of remedial steps.

Internal

The problem of internal corrosion should also be checked for severity prior to the initiation of extensive remedial steps. As a general point of interest, it is not recommended that the tubing be plastic coated, mainly because removal of the plastic coating by decomposition, erosion, abrasion from wireline tools, etc., could result in the deposition of plastic particles on the rock face. In addition, if a complete surface covering of plastic is not affected, there will be points of corrosive concentration which may lead to tubing failure.



There should be no difficulty in inhibiting attack, if it should occur, by the use of appropriate chemical inhibitors. An inhibitor should be selected which will not decompose into a viscous material that could plug the rock face.

The recommendations regarding corrosion are summarized as follows:

- 1. The injection string should not be plastic coated.
- 2. Surface equipment should be inspected at regular intervals to determine if internal attack is occurring. Consideration should be given to a test length of pipe especially installed for internal corrosion inspection purposes.
- A caliper survey should be run in the injection tubing so that the extent of damage may be determined. Results of this survey will indicate if inhibitor injection should be commenced.
- 4. The possible use of coupons should be investigated. These are small pieces of metal placed in the flow stream which may be removed periodically to examine the extent of corrosion.

MIGRATION OF INJECTED FLUIDS

After a fluid has been discharged from a wellbore, two possibili-

ties exist for its vertical migration:

- 1. Around the mechanical installation, and
- 2. Within the reservoirs themselves.

Indications from the cementation operations and from the subse-

quent testing are that the mechanical installation at the Rocky Mountain



Arsenal is sound. Vertical communication, therefore, if it were present, would probably be within the reservoirs. This possibility is minimized because of the massive shale bodies overlying the injection horizons thus providing natural segregation.

PLANT OPERATION

The existing surface facilities will be employed in the reservoir evaluation injection tests. The present installation has four triplex pumps capable of delivering 400 gallons per minute at 2,000 pounds surface pressure. Combinations of these pumps will provide variable rates and consequently, variable pressures conducive to reservoir evaluation techniques.

In subsequent operation of the disposal well plant, three parameters are of extreme importance from a reservoir analysis standpoint. They are time, volume, and pressure.

Volume recordings will give directly the accumulative capacity of the reservoir. The time notation will permit a volume per unit time, thus the rate of injection. The rate-pressure relationship is the criteria for reservoir behavior prognostication.

A careful day-to-day record of surface pressures, rates of injection, cumulative volumes injected and other pertinent observations by the field personnel would provide a firm basis for reservoir performance evaluation, possible stimulation requirements and analytical operating efficiencies.





E & POLUMBUS, JR AND ASSOCIATES, INC.

. . .

1 1300 Aud. 1 -

Figure 2



LEGEND

÷

1

I

. Ц

5

viso → Ceepest Formation Penetrated * 8450'→ Total Depth DEVELOPMENT MAP



SOUTHERN PORTION OF DENVER BASIN

CONTOURED ON PRE-CAMBRIAN SURFACE CONTOUR INTERVAL = 500 FEET

E A POLUMBUS, UR & ASSOCIATES, INC.



Ĩ Ĩ

. 13



ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL

PRE - FOUNTAIN GEOLOGIC COLUMN



- E.A. POLLWELE UP AND ASSUDATED INC

	~ v ~						A																		_
• •	•	• •	 		•	• • • • • •		•••	· · · ·		· · ·	••••	•					1 -	· · ·				• •		• • •
CABE	NG :	H	M	81.Jk	1996	istles	М	JD ₽	QHP	P?!		a wei 9,10 2,5	ं दस्य र		6	IO 12		R DI	May Mand		P	in ir Ecqu	4		de ja Hone:
	2			↓ ¥7⊾	<u> </u>	a Naha		-	PRESS	 				- <u> </u>]	ľ ľ			L		<u> </u>	<u> </u>	.L		• • • • · • •
/105 BUT					, 5 4	· ·	. æi	•			•	r 1/1 	i di		· · ·	· · · ·			· ······		$\sum_{i=1}^{n}$	 			· · · · ·
3				9.2	4	11.0	530		300			5-0	DC		 			•		· · · ·				+	
C 53.					· · ·	•		•			! - 	· •			•	•••		•••				· · ·	•	-	
N.	+			ن دو ا		. 			50 0	6	-	≌C <u></u>			• •						_ _	<u> </u>	• #14 3 <u>4</u> 08-0	+	
ALCO ALC		1 4 4 9 4 9 9 4 9 4 9 9 9 9 9 9 9 9	•	• • • •	35	10 . 9.	-		1 00		״+ד״	*. DC			• • •			•				• •	• •		e English de company C
- 9	+	• •		· ·					· · ·	$\left \right $	\$ 		· 				-							-+-	1944
7 (2) 4 2		• •		9.0	. 34	1.2	160	•	1600	6	6 4	9-1	'oc		• • •	• • •		•	•			· · · ·			- -
13 20		• • •		9.1	72	7-8	440		900		6° 1	9- 7	DC.		• • • •			•				· • · ·	5		
	rue Hag Set ե 			5.1	33	9. 4	460		1000		- en 12-			· · · · · · · · · · · · · · · · · · ·			-		··						
	3			2.3.		. 9.0	sho			د	r. 4.	21-7								•				-	
	e S			9-3	33	9.0	460		1150	i t				i							ł	•			
	33¥4		. 	9.4	53	9.0	.500		1000			-						Ì		•	t 1		165	-	· ·
		; ; #	P	9.1	ÿ	1.0	Ma			6	P ' 60	. 4 8	-	0C		•		•			<u>}</u>	•		·	
				9.4 9.3	39 32	9.0 9.2	5100 1460	•	1300 1300		•		-	! !		•		•		•		} : / .	• • • • • •		
				3.5	. 57 .	7.0	500		116.0					1 1 1					•		ļ		•		
(marar				9.5	33	1.3	50 0		Heo	6-1	۳ ۸	21-7	•••	 	· ·			1			ļ		15		·····
791			1	9.6	78	5.8	500		1400		۰.	c ::						.r.]			ć		25 25	E	
SKO SKS	SKS.			9.5 9.2 9.8	94. 52 54	5.5 7.0 8.7	500 500 500		1 375 1 300 1300	, 19:	-€"k _₽"_⊥	21	**_1	k r	• • • •	4		-			\ \ \		<u>D</u>		
j. v. f.	32/).1).7	56 61	7.4 9.6	560 160		1300			· · · · ·		42		<u>, 11</u>		ן ר.,			7		NO 55	Ł	

Ì

ĺ

Į

.

ľ

ł

6



· · · · · · · · · · · · · · · · · · ·				D	
			DRILLING MTS MT No. IVM SI SIZE 52 2C 53 W7R 54 W7R 55 W7R 56 W7R 57 ROBJ 1/2" 7/8" 58 ROB2J 1/2" 7/8" 59 W7R 60 4444J 1/2" 7/8" 61 W7R 62 W7R 63 W7R 64 W7R 65 W7R 66 W7R 66 W7R 67 RO2BJ 7/8" 68 RO2BJ 7/8" 69 RO2DJ 7/8" 70 RO2BJ 7/8" 70 RO2BJ 7/8" 70 RO2DJ 7/8" 71 W7E 72 W7 73 W7R 74 W7 75 W7R 76 W7R 77 W7R 76 W7R 77 W7R 78 W7 79 W7 80 OWC 81 W7R 82 W7R 83 OWC 84 W7R 84 W7R	DRILLING HTS HI No TYPE IT SHE 1 3CDT 2 YT3 3 OSC3J $1/2^{n}$ 4 OSC3J $7/16^{n}$ 5 DT 6 OSC3 7 DT 8 OSC3 9 TT1A 10 OSC3 11 OSC3 12 OSC3 13 OSC3 14 OSC3 15 TT3 16 DT20 17 E2P 18 W7R 19 W7R 20 W7R 21 OMSY 22 W7R 23 W7R 24 W7R 25 T2 26 W7R 23 W7R 24 W7R 25 T2 26 W7R 27 W7 28 TM 29 C2 30 OWC 31 U/R 32 W7R 33 W7R 34 OWC 35 C2 36 OSC10 37 OSC10	CONTRACTOR LOFFLIED EROTHERS RIG DESCRIPTION Drawworks Ideco PE 1050 Mast I. 10 Drill Engines 3 Catarpillar D.397 I Continuous HP Raing 450Ea.at St Mud Pump Engine Dff Compound Continuous HP Raing 7 At Mud Pumps [1] Enaco D=200 (7 1/2* (2) Ranco D=500 (7 1/2* (3)
			86 W7R 87 W7R 88 W7RJ 3/8" 89 W7R 3/8" 90 W7R 3/8" 91 W7R 3/8" 92 W7R 3/8" 93 W7RJ 3/8" 94 W7R 3/8" 95 W7RJ 3/8" 96 RD-1J 3/8" 98 BD-1J 3/8"	38 OSCIO 39 TTL 40 OMS 41 T2 42 W7R 43 W7R 44 2C 45 W7R 46 W7R 48 W7R 49 W7R 50 W7R 51 W7R	 Net Drilling Progress Curve: (Include mal trips, connections, drift survey mixing, i. e. related to normal drillin Rotating Progress Curve Coring Diamond Drilling Red Arrow: Highlights hezerds Lost Circulation Occurence Including Spot Lost Circulation, Cement Plug Cleanout Difficulties-Trip In Tight Hole-Pulling Out
· · · · · · · · · · · · · · · · · · ·			Note: 9-11" bits t drill on jun drilling cem 1-6 3/4" bit	condition hole. c, ream bridges and nt. used to drill junk.	DRILLING BITS RR-Rerun Bits Rm-Reaming Bits for Core Hole -Diamond Drilling -Diamond Coring
					DRILLING ANALYSIS SERV Copyriate C. A. Johnson Bldg., Denver,
	MIX MED HIX MED HIX MED	-1 -1 -1			

1	,	···				·····			Ł	al and the part of the second seco
CONT	RACTOR	LON	FLAND F		COMPAN	Y	DASCO	Chart	Fig. 46	
		RIG	DESCR	RIPTION	Rig	No. 7	OPERATOR U.S.	ARXY COR	PS OF ENOTH	KERA
Draww	orks_Idecs	Catar	0 <u>50</u> M	ast Lu I	Hoore	1421	WELL Booky Htn.	Armanal	Disposal 4	1
	Continu	ous HP I	Rating 45	DEmail Se	weed Oper	ated	LOC: Sec. 26_T_2	S R 673	<u>.</u>	
Mud P	ump Engine		Compo	und			Spot Loc. G. M			
Mud P	umps (1)	us nr) Júre go,	D. 700	(7.1/2"	=RPM		Adama Count	y. Color	eda	
	(2)	NHÁCO	D-500	(7 1/2*	<u>x 16")</u>	· · · · · · · · · · · · · · · · · · ·	Elev.	G	<u>\$2031</u>	KB
Drill Di	(3)	14	ANA T-							
Drill Co	ollars_9_8"		ID. A	ioi Joint. <u>≥ 2≪</u> _ 7#		3/4# T D	TIA	AE ANALY	(SIS	
Kelly_	4 1/4" Sq.	<u>× 40'</u>		Standpip	xe. 4.1/	2" x 55'	From Spud	Date to T	otal Depth	
SWIVEL	NELIONA]	K3=2_3	5/4"I.D	Hose_3	<u>" - 55'</u>		items:		Days	<i>4</i> ,
WAIL	SOURCE			· · · · · · · · · · · · · · · · · · ·	·····		Drilling on bottom		37.4	20.2
	No	<u>B1</u>	I SUM	MARY	Fast	No. 0.	Coring on bottom		12.1	
Size	Bits Foo	lage	Hours	Hour	Bit	Bot/Bit	(1) Rotating progr	ess Dela et r	49.5	26.7
12 1/11	2 4		DRILLI				Drill trips, rig service.	etc.	۲7•/ 17.9	9.7
11"	62.2 8	711	46.2 710.6	43.9 12.2	677 140	15.4 11 L	Core trips, rmg. hole,	etc.	28.4	15.4
6 3/4"	14.5	665	139.5	4.8	46	9.6	(2) Net Drilling pr	rogress	95.8	51.8
24"	1	138	HEAHIN 4.0	34.K	178	4	Cond, holeLostC1	8 7 <u>6 Mi</u> y	6.3 Mud 31.5	3.4
17 1/4"	2 1	892	34.2	55.6	946	17.1	Circ. samples, waittor	ders	2.7	1.5
6 3/4"	17.8	520 146	138.0	3.8 21.8	29 292	7.7	Surveys: Elec. ing		<u> </u>	7.4
8 7/84		DI	ANOND	ORINO	~74	1.7.4	Fishing		8.9	4.8
8 9/16"	ر 1	18	100.5 9.5	1.9	-	-	Kig up on spud date	OC tert	0.2	0.1
7 13/16	* 2	282	130.2	2.2	-	-	Boven Basket Reco		2.4	1.3
Dia. Po	wen Baske	142 t 6	51.2	2.8	-	-	Spinner Survey		0.7	0.4
			LEGEN	D			Injectivity Test		0.6	الحيف
DRILUNG	CURVES	_::::					Operations	After Roa	185.0 ching T.D	100.0
		THUNG Pr	ograss C	urve			Cord Bolas Last			ays
	mal tripe	connecti	ass Curve		only time	on bottom, nor-	Sat 5t Ceaing A 1	Liner	х_пид 5 4	.8
	mixing, i. (e. related	to norm	al drilling	progress.)	e, normai mud	Mait On Orders & F	lig Repair	r_ 0	.?
	. Rotating P	rograss	Curve	_	,	ļ	Injection Tests		<u>0</u> 1	.6
	- Coring						Anidisang		<u> </u>	
· · · · · · · · · · · · · · · · · · ·		Drilling 	nhén kawa				Blowing Hole		3	.5
•	Lost Circul	ation Oc	giws haza Icurance	ir ci Includina i	mixing L. (mud	Total Time After T D			
•	Spot Lost	Circulatio	on, Ceme	nt Plug					VES	#~~~~~
•	Cleanout D	Difficultie	s-Trip In	I				Lbs/Dey	y Quantity	LbulR.
	Tight Hole	-Pulling	Out				Additive	(HUNDREC	5) (LbsSks)	of Hole
DKILLING	Rerun Bäts					PER LOG	Bentonite	. 30.2	558,000 1be	• 46.3
Rm-	Reaming Bits	for Core	e Hole		K Hole	enlargement	Baroco	- 7.7	141,900 1be	. 11.8
	man d D. Ob				Grea	es bit size	Baroid	- 7.1	132,100 lba	. 11.0
Du	mond Drilling mond Coring				·	J	Line	3.6	∞,150 1bs 65,700 1bs	. 5.7
1							Driscose	- 1.6	29,050 lbs	. 2.4
	DRILLIN	NG AN	ALYSIS	SERVIC	E CO.		Salt.	0.3 0.8	5,800 lbs	0.5
Canyricht	C. A. Jo	hnson l	Bldg., D	enver, C	olorado		Starch	0.8	14,100 1be	1.2
					Septem	ber, 1961	Tannex	. 0.8 . 0.2	14,600 1be	1.2
E I							Carlonor Bare Cor	0.1	1,500 lbs	0.1
		-		1 P	1	g	Soda Ash	0.1	50 1bs 2,300 1bs	0.2
2		· 🚊				-			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	,

L
			3.1. 6.1	. 3.2. 35	10.0						· · [• • · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · ·
1 UC 1				.,	,			5-7" OC						- <u>-</u>	
					• 		1999) (Series - Series (Series (Series)	and the set of the set			,	₩ x: } +		₩ 8 ₩-₩2₩22,000 - 1	••• • ••••• • • · · ·
	•		9. 0	у	†.2	ki a	1600	6-8° & 9-7°00					· .	alina tanàn ambina amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny fisiana amin'ny fisi N	
	- 4 - 1 , rdf - -	+ + 			· • • • • • • •		bi ann ne ine a crainn fá	e en a sur cardon come	· · · ·	······································	······································		•	 	
4	•		9. L	¥	7-8	40	900	6 ⊷8* 4 9⊷7 * DC					5		
		 			1	l ∳≈ }	۹. ۴	t Banka, an the state B	р. ф					ge-gengen ogsåget og at konstander og skore skare skare	
5 M M-1			<u>7,</u> 1	33	9.H	! \{ 0 	1000	11. DC	hat he has		, 			,	4 · · · · · · · · · · · · · · · · · · ·
1.5		; 	3a.	£ .	1.9	- Hare -	<u></u>	the alt T	· ····································		-			· · ·	
0.61			9-5	3 3	3.0	460	1150								
		,	9.4 -	ይ አ	3.0 £.0	,500 346		GUP SC & 25-P	" oc			\mathbb{K}	. HP-	· · · · · · · · · · · ·	
┼┼		 	7.N	л Э	9.0	500	1100							• • •	
	•		5.3	<u>12</u>	9.8	160	1300					:/::			
			2.5		7.0	500			 			ļ . j			
	· · ·		9.5	. 33	8.3	50 0	, Pico	6-8" L 26-7" B			•		45 -	· • • • · ·	
	•		9.8 9.6	60 78	6.8 5.8	500 500	1200 1400					K	20 - 25 -		
H	م .,	-	3.2	58 52	. <u>5.5</u> 7.0	500_ 560	<u> </u>	╡ ╎ ╎ ╎	a¢t		• - •- • -•	<u> </u>	-0 -0		.
	C 273.			56 56	8.7 7.8	500 500	300 300	 }-===================================	i Dic	Ē		$\left \right\rangle$	• 140	· · · · · · · · · · · · · · · · · · ·	
	S		9.7	61	9.6	160	(20 0) 100	5	4 21-7 0		· · ·		; 55 [∎]		
			9-5	\$ 7	7.1	310					· ·			ra #5	
	01 .14	-	9.3	8 0	7.0	120	1200		1		· · · ·		70 - 75 [^]	AR #54	an (***)
			9-5	DZ.	4.U 4.3	310		5 A 21-7			 	<u> </u>	to		
	-	-	.9.2 4.7	540 140	5.¥ 7+7	280	900 10150	L, L, 80) •5 -		
	≝. 		7.0	45 13	7.2 7.2	240 240	1150 150		, ,	ļſ	•••		90 -		
	R		9.0	41.	_ <u>5.</u> #	. Zo . 1	2000		42°° .00	··			95 -	andreas Andreas Angele and a stranger and a Angele and a stranger	
			 			1		 							 } 1
·• •			i	• · •	 f		9924 - 14 201 7 - 14 14 14 14 14 14 14 14 14 14 14 14 14	₹ ₩ • • • • • • • • • • • •	1 Augustan - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 -			I	•		



; ; ~ **** ********************************	.	······································		· · · · · · · · · · · · · · · · · · ·					61 W7R 62 W7R 63 W7R 64 W7R
•								· · · · · · · · · · · · · · · · · · ·	65 W7R 66 W7R 67 R02BJ 68 R02PJ
ана, анана . 1 1 1	• • • • • • • •	• • • • • • • • • • • • • • • • • • •	· · · · · · · · · · · · · · · · · · ·	n na anna an An					69 F02BJ 70 RG2EJ 71 W7E 72 W7
·· •	• 4-	· · · · · · · · ·							75 W7 75 W7R 76 W7R 77 W7R
 	: 				 	 	F 		79 W7 80 ONC 81 W7R 82 W7R
)					1 2 1 1 1 1			• • • • •	83 OHC 84 W7R 85 W7R 86 W7R
· · · · · · · · · · · · · · · · · · ·	•			· · · · · · · · · · · · · · · · · · ·					67 W7R 88 W7RJ 89 W7R 90 W7J 91 W7R 92 W7R 92 W7R
₽ • <u>• • •</u> •	1								94 W7R 95 W7RJ 96 R0-1J 97 R0-1J 98 20-1J
ij		·····	· · · · · · · · · · · · · · · · · · ·				· · · · · · · · · · · · · · · · · · ·		Note: Q-11" b
. J.	Less clac.		E E	1 					drill or drillin 1-6 3/4
	Date Aug & Less Cites	Flatt Four Jack					5		drill or drillin 1-6 3/4
	ALE AND A LEST CITE.	TLAN FOR ANK				Collect Marters	ATTI MU ATTI MU ATTI MU CHEL AUPLE		drill or drillin 1-6 3/4
	O RIE AUG L LOST CINC.						ATTI NO ATTI NO ELEC. MAPER		drill or drillin 1-6 3/4
	O ALL AND A LEY CINC.								drill or drillin, 1-6 3/4
									drill or drillin, 1-6 3/4
			7b 2c 25 1761						drill or drillin 1-6 3/4



		~	مد بد . بر پر بر	ني بەدىرىن	i algan		lloms:		Days	*
TER SC	OURC	E:					Drilling on bottom		37.4	20.2
			BIT SUM	MARY			Coring on bottom		12.1	6.5
No	o .	footage	No.	Feet/	Føet)	Hrij On Norflui	(1) Rotating prograss	5 1 6 4 1	49.5	26.7
1941	15		niours Digitititi	racius: Tairis	Q61	оки) е н	(Percent of Net Dri Drill trips no service at	gu \$2.47.0	79-) 17-0	9.9
4 *	3	2030	46.2	43.9	677	15.4	Core tries, rmg, hole, etc		28.4	15.1
ť	2.2	8711	710.6	12.2	140	11.4	(2) Net Drilling prog	085	95.8	51.8
4 ^a 1	4.5	665	139.5	4.8	46	9.6	Mechanical downlime		6.3	5.4
	1	136	<u>66464</u>	14.5 14.5	138	4.0	Cand hole Last Stra		ud 31.5	17.0
4 =	2	1892	34.2	55.6	946	17.1	Circ. samples, wailforder	\$	2.7	
<u>1</u>	17.8	520	138.0	3.8	29 700	7.7	SULVAVE TIME LUX	n	. 4,1	2.2
••	0.5	140	DT ANOND	CORINE	CYL.	12.4	Fishing.		L 8.2	4.8
B.	3	191	100.5	1.9	-	-	Rig up on spud date	last	0.2	0.1
16" 1+6#	1	18 293	9.5	1.9	-	-	Casing: ream, run, wor	. 1831	10:4	9.10 1 1
/16ª /16ª	i i	142	51.2	2.8	~	2 4	- HOMAN IMAKAL MAKRARA	J ack - Constant	0	0.4
Power	Pee	het 6					Inductivity Tast		0.6	0.0
			LEGE	<u>ND</u>			(3) Overall time to T	D	185.0	100.0
ING C	URVES) 11 a 11.	_	-			Operations A	Her Repo	hing T.D. D.	ayr 🕴
- a cost - •	Overa	ili Deshu	g Prograss				Cord Roles Lost Cir	a.∈ ¥4.w	Mud 5.	3
	Nel D	rilling Pr	rogress Cur	ve (Include	as only time	or bottom, nur	Sold 5th Cantrie 4. Las		¹ 4	8
	smal tr	ios, con	nections, di	itt survæy med deitig	5. TIG SOLVH	te, normat mud	Mait Cn Orders A. Rig	Repair	. 0 .	?
	1110-1114 m/	рікарсіар 1. т. аркі тар	10190 10 100 	ringi Qernero	g program (Late Malls Logging	- بين ە ئەتىرىيە بە لە لەلىرە -	<i>ا</i> نگاستند . 1	A A A A A A A A A A A A A A A A A A A
• • •	Kalatu	ng Progr	ALS CUIVE				And the set of the set	•	. Â	S and
	Coring	الا بالاستان ال					Bloring Hole	·		3
	Rud A	на стан нтоw:Н	ng lighlights he	zarde				مريمدهم بيريوب الالتعويط	and an a sublicit	
ł	Lost C	irculatio	n Occurenc	 Including 	g mixing L. (C. mud	Total Time Alter T.D.		17	3
•	Spot I	Lasi Circ	ulation, Cer	ment Plug			MUD	ADDITIV	E S	
,	Clean	out Diffu	culties—Trip	In			(a 1.5 m	Lbs./Dwy	Quantity et (the state)	LDE.PI.
•	Tight	Hole-Pu	illing Out				Addave			
ING B	175				CAU	PER LOG	Contonista	30.2 5	53,000 100. 51 200 100	40.3
RR-Rei	run Di	is Rite for	Core Hole		p Hole	enlargement	Surgeo	7.7 1	41.900 lbe	. 11.8
NIT!***	Nex na. 19				Gro	ater than 1%	Barnid	7.1 1	32,100 lbs	. 11.0
Diamo	nd Dr	illing				nes on nye	Q.Broot a	. 3.7	68,150 1bs	. 5.7
-Diamo	and Co	ring					Driscone	1.6	29,050 10	. 2.4
Constanting							Constio	. 0.3	5,800 105	. 0.5
· ·	DR	ILLING	ANALY	SIS SERV	ICE CO.		Salt	0.8	14,800 10	. 1.2
	C A	John	ion Bldg.,	Denver,	Colorado	•	Starch Preservativa	0.8	14,600 100	. 1.2
1			-		Septe	aber, 1961	Tannex	. 0.2	4,600 1bs	. 0.4
	و علور ، د دهیچ		• · · · · · · · · · · · · · · · · · · ·		· V	1	Carboner	. 0.1	1,500 168	. 0.1
							Soda Ash	0.1	2.300 15#	. 0.2
				54			Condet	••••	440 1be	j
			3			12 · · ·	Defenser	~ ~	165 lb	J
	H.				5 555		Fibertex	- 2.5	46,500 164	1. 3.9
		33					Plug_cit	. 1.8	33.750 lbs	. 2.8
에서) (1번)	233	13 <u>5</u>					Jalfiaka	0.6	11.050 1be	1. 0.9
긜		114 8					Polyriaka	_ 0.3	6,350 1be	· 0.5
<u>ч</u>	- chen	ਗੁਤਾ	1732772	825323	4443468		Nicatar		1.250 10	a . 0.1
• • •			747	: 🏴 q		t a gan caraana) t co				
j.∎z			RIG	LEASED IN	(ti A,H, y⊶ 2		Total	. 69.7 1	,289,555 11	38.107.1
	ľ	14	T 1		1 26	26	and a second	• 		
• • •	ж,		۲ ^۱ ۵	EPTONALS		- <i>y</i>	in provide a second sec	-		
; 1				1941		t, o una otrebarana	ار با می و می و این از این			
-									-1	
`									4	

İ



FIGURE 8

FIGURE 9

BOWEN JUNK BASKET

f

E A POLUMBUS JR AND ASSOCIATES INC

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DISPOSAL WELL NO 1 FIGURE 10

Conte ala Conte ala Conte de Conte Conte Conte de Conte C is: 1 FRACTURES 4 * · A# K09E HILTSTONE B Dean Fracture 22.7.7.7.22 SILTSTONE LINESTONE, FREE CALCITIC and DOLONITE SANDSTONE -Change Freeture FRACTURES GARGIO BARDID THE OND REMARKS DEPTH MARKERS LITHOLOGY DRILL STEM TEST RESULTS 1470 NOTE ----Beartes organized to Induction - playters ling - ---8480 8480 Tep of "J" Send ANDSTONE ____ 4-7-81 Ð 8490 8490 TINES. mitigt Flaw, 14 min Initial Shet In SCoun Final Flay 40 min Finar Sharas 120 min 943.4 |6 10 19 1 8500 810.1 1 Care No 4-8-61 -<u>-</u>= 111111 PASSURS Initial Flow 202 Finitial Flow 202 Finitial Flow 202 Finitial Flow 202 Hydrootatial: 4808 TangerSurg, Mat Rec E 0510 \$510 5 5 1 <r caré i i , 817 15 R 8 52 0 0520 in an RECOVERY ٢ Mequirad Heavy Jerring to Loosen Core Borrol 200 Ft of slightly ges cut med 81art - Oury Hat - 4-11-61 6530 ____ 55 11111 ----÷ NOTE 20 Petter feiled etter I hour of finel ····· 53 8540 8540 Shul-in Reserved 1 : ____ <1 Care 2 8550 .550 MCTAN MCTAN 1111111 117.21 P DST No. I 200 == ₽ 4-12-61 8560 ÷. == di lore ____ 8570 \$570 8580 8680 <u>...</u> 1 8590 8590 8600 8410 4 ŧ 1 8 620 4620 817 22 D DET NO 2 Te 6621 1 650 8630 i

E & POLUMBUS, JR AND ASSOCIATES, INC.

1.

-

•

-4

- -- --

: ...

i

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PREBBURE INJECTION DISPOSAL WELL

•

I

٢

. -

NO & FIGURE 10

ì

		SILTSTON	E .+	Ц 1 Т н с 4 4 4	St (=		E (ALE CH CLAV	; [D. BILTSTO SHA			CTURES Francisco	N	 -	4E 1994 (1) 1994 (1)	
!		34409704	•• ∭	····	FITE	com	Homeric		-	LINESTO CALCITIC DOLOMIT	NË PREM I	1 	Fraziera 21			lefe festerend 1978 System 1988 Selfe fi ⁿ 1988 Selfe fi ⁿ bese	
05974	FORMATIO	UTHOLDGY	FRACTUR	HES BAROD	DATA BAROID PERMEA- I BILITY	CORING TIME WINUTES PER FOOT	CORE	C 9 D	<u>- RE M</u>	ARKS	REANING and DRILLING BITS	06+11	DATE	09-L1 77 81	57EN 37 UN	A DRILL	576# 57 10175
8640	GANDTA			·	T		8				Tep al		4-13-00 81811 Core to 5		<u>}</u>		
, I	\$4405700			1	() ()	<u> </u>		11111		†			4 :3 51	i - i	• • 2 •	<u>.</u>	+
0630	<u> </u>				<u> </u>	5		1111								Inclust Play Inclust Shat Roopt Plays	5 mm 28 mm 40 min
	1			No cere ene	Ceri	، ک		10000								PACESUA	110 min
	- Turk					2		10000			1			 	 	fattint finn In ital Stuf Firmt Figur	182 n 1187 188
	63				 						╡	8670	Brart Care No 4	 		Hydrastatio Tomporatus	4480 4480 8 204" P
	50		a a a a a a a a a a a a a a a a a a a	<u>ل</u> م م	T SI Gara		0	111111	9979-8 Rec 10		BIT 24 0		4 - 15 - 61			RECOVER	elig hely
:	Siling State		1		T	5			Care Barra	1 Jemme-5	-		\$1411			NOTE	
8690						• 2	0			1		8630	Cere No 8 4-18-81			Wash blow a Fair in 18 a The built of	erossing is a , decreasing und ut the
8700	 										BIT 25 R	●700					
				Capita adja Industion - a unara warr	eted to Actric log Mind		+					8710	 - 			i 	
8720							ļ		·····	ļ	ļ	0720	1		;		:
	LAROTA												Top of				
				1							+	●730	4-18-61		;		
9740				<u></u>					·	; 		8740	ļ ļ	<u>ء</u>)		
8750																,	
	t oi							-+-			ST ZH D	8750	++			i :	
0760				$\left \right $				+			 	8780	↓ ┿──── <u></u>				
8770	362		,						i			17 70			1	(:
								- 11	IOTE In compation casing the	s the Billy" I "Steps DV					+ ,	الــــــــــــــــــــــــــــــــــــ	
9700	•			;	+			÷	Letter mas depth at The 215 s	in place of a 1897 fage somest	BIT 27 0	8780	; ;			ء - ق يتينين	، هد درسه در
8786 8790 '	A SOM							Ĺ	2850 tech Pesmin en Ibrough In	at 50-50 t to annulue is. DV caller		.7.0	1 Yep af Werriken 4 - 19 - 61				
									1				DST NO 2	_{			•••••
0000						<u> </u>		+					4-20-64	-			

E & POLUMBUS, JR AND ASSOCIATES, INC

٠

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA Rocky mountain Arbenal Prensure injection disposal well FIGURE 10.

E.A. POLUMBUS, JR. AND ASSOCIATES, 190

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA Rocky Mountain Arbenal Pressure injection disposal well

NO 8 FIGURE 10. INTERVAL 8740 - 8.880

Source of the second se بالاستغار بمعاسم Ł FRACTURES • • . 5 L*5*ONE ARKOSE SHALE OR CLAY SILTSTONE & SHALE | || Deer frasie/a 102212222 Care Leveland Care Leveland Care Land Here de re ri Bri 148 15' Nore 5440610446 ANN 4444708/TE COLONIE 1.1.1 FURMATION FRACTURES CORE DATA CONVIG COLLED SEPTH MARKERS LTHELOGY DE DATOL THE CAR CORE DATA INVUTES: CORE CARAGE LETT PER POUT 1 Emilas Practica 1 DRILLSTEN NEANING AAD DMLL PG DATE DE DÉCUR DRILL STEN TEST REBULTS 6 E PTH . ł ŝ Depring Sejation is prefuction - mettres seg sefere mercentes. 1841 Coldabase 2730. 97 båis .9729. 1440 9750 9760 9770 į FOUNTAIN 9770 4 ł Last Circ 9780 150 141 Ťċ. 9780 ŧ 9790 Ł ÷4 . 9780. -. 9800 ł 9800 ÷ ł 9810 Lest 24 mours ł 7 817 82 0 05.86 9820 - --• 9830 ţ 98.30 -9840 1 4-4.41 9840 051 No. 4 8 - 3 - 61 I 9880 9850 1 j in S Ì 9860 9960 031 He 0 , ſ ÷ 9870 ī - 4016 9870 **††**† Î 0,04 98 80 5 9680 į ł . í 1 1 ł i ۰. . . t ł ۱ ı. 1 I ÷ i

E & POLUMBUS, UR AND ENDOTATES, NO

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ATBENAL PRESSURE INJECTION DISPOSAL WELL

Contraction and the second second second

_

-

1

• *

100 FIGURE 10.

	5 L*\$*-41	· · · · · · · · ·	10.3E	3MA.	<u>к</u>		Burgan Burgan Subi Subi Sanas Sanas		• • • • • • • • • • • • • • • • • • •	* #88 (771)		- -	98 1474 - 836 147 - 444 - 444 147 - 444 - 444 - 444 147 - 444
210*H	FORMATION	ACTURES CORE FORGET	0414 84805 168854 82117	508045 0 1488 0 1484 185 1677 1601	н-ці во Ани Сояеб	47 ¥	4 4 85	ក់ដែលស្នេ កំពើ ជាសិករដ្ឋស្នេ សំពីភ្លំ	ปรีย ะ ห	DATE	יין 1943 ביי דר דר	578) 578)	∼ийсына И БАК <u>, Б</u> ТЕМ Т <u>К</u> С КЕС, 5
. 985 0		1 1 1 1 1		1894.8 1970 1970 		AL SEVE		(] 		L. BLAFT			
9900				لمربع 				-)etanos in incise : : : : : : :	9900	8 - 28 - 61	94	ii) Mice	(4) - <u>PHESBUMES</u> Hydroolulij 4774 - Tamanaduch 208° E
9910	· · · · · · · · · · · · · · · · · · ·		<u> <1 cen</u>	یا ہے۔ ان کے ان کے ان کا			1		9910		1 		SOTE
9920		 	-• · · · ·						- 9920	 	• • • •	Q.	umen tost ofened Rosat (paukor, fotod opein Tost) million, poblabiy due To communitation mount pattere Mosten treeves
9330		1 (144)1	:				, 	R H V T - PP - Car	9930	, 			
9940			Déplés adardie , induction - mig				<u></u>	Santa Ran B-T 63 - FHTC NEZBU BE-1'd Ant Brit	9940	· ···-		0	PAE 580AF 8 HI Frankle 4828
995 C			nanhara ananraka n k o o no no na na∳n n				· · · · · · · ·	-	9950				NOTE
9960			•			<u>1.0001 Mius</u> Less 60 b (9 340 mins	Returns III Mué IIS	B/T 64 D	9960				foride intendiatoly unen t feel usened fosat packer and fosat filterun test fund in Saftmuturafier forese packers through
9970						Last Teta			9970	·- •	•		
9980 ,			• • • • • • •		•	ا مەرىپى ب	·•		9 9 8 0	<u>ا</u> به دست ا ا	┟╴┽┥		Tibits Tibits Will Play 7 prs
9990 .		• • •	ساله مرز مر			• •• ••••	- 4	•	9990				Pinet Min: 60 min ; Pinet Mill in 120 mis
0.000		· .	4 -	·· · ••••			، پنين (رويندر) ا	BIT 86 D BIT 86 D Bit States Bit smar	107000			! 	initor Figu cigr Init al Diet in 3,052 Pinel Figu 1,280 Finet Diet in 4,335 Heffen Stice 6,822 Tether faite
10,010			· - •	• •		907 Y.M. WINKE #		***	0.010	1 17776 a 1 -			RECOVERY
10.050		· · ·	• .		- -	<u></u>		117 66 0 6 6 9 9 m 9 9 9 8 8 8 1 1 1 9 1 9	0.0 20	Ave al			646'mud, <u>hOTC</u> Mirts Tadiboras vier * offensliene were
10,030		• •	•			9 F 4	، 	<u></u>	0,030				ternatay diugging ana atring dujing saa tipu Misifa Tab finat bula Feeres appears to but IBF a far bafunging to but
.0 ,∪40 _	LUST CIRC NO		· · ·			lagan Lasta	W.d		0,040 <u>.</u>	•		4 4 5	1668 94 võlkudi akamn 1980 -
. 6 with .	SAMPLES	1.,	· ,			4) Compo 200 1	a Naturna 1914 a		10 \$Q	· •	ين { { { } } { } { } { } { } { } { } { } {]	•1 •••

I A POLUMBUS, UR AND ASSOCIATES, INC

ı t

-

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA Rocky Mountain Argenal Pressure injection Disposal Well

-

NO 8 FIGURE 10, INTENVEL 10,060 - 19,220

Ň

< ,

		-	··.)	A##:358	,	HALE C1 A1	л# г		51LT 8 7 0 54 A	he e	*****	*u#t) *****			ORE Smer 14	
I				******		11 () () () () () () () () () (ine: t	; _	L:WESTC CALC:77(DOLDW:7	₩ 7860 K ^{**}	ti Tinand J			.	5828 (83899 5222 3228 788 888 28 12 8658 88 25 ² 16	•e
0EPTH	FORMATION MARKERS	117401044 #F	ACTURES SAN	045 0414 8010 848010 05171 65842		0#11 10 05 [5	LLEO 14 REG		4939	REAMIN(1 374		DATE	(#) (• • •	1578 F 4 T	UN DRI	LL STEM
	1	AU I	· · · ·	1 1 1 1 1 1	THER YOU	4		- <u>-</u>	+	8179		RENCE		<u></u>		ESULTS
	2	SAMPLES	!	i norma a				1	i					ζ		
0,060	{	CIRCL	+			•		Lanesco Mi	150 3201	87 68 2	-	5 · 7 · 4 ·	-	51	fer Da	et .
					1			1		• • • • • • • • • • • • • • • • • • • •	. "4C60		· · ·	nino -	Na 9	1
•				• •	.	+				1	i (;	Ì	1	
10,070		·····							1	1	1 10 0 20	}	!		1	ĺ
			i					1	1		1	51611	<u>†</u>	+	·	· +
10.000					1	i			1	817 70 8	4	091 10 7			1	1
19-01-0	- ^ - ┦ ┦			••••	·	┿┥╼		·		+	10,000	8-18-81			i 4	
			1						1	i		1	:		1	1
0.090			1			1			i	(:				
I						↑ - 		+	÷	- 4	10,090		••• 🖡	<u>ا_</u>		· •
					1				•	:	i	1		i i	ţ.	ĺ
0.00	╾┥╴╾┥									!	10.100	1			1	t
1		40	1		1						•		1	} 	4	1
10.110		SAWFLES	i				1	1 1		1						
		LOST			• • • • • • • • • • • • • • • • • • • •	÷-	-+-	717 4	te al Africa	+ <u></u>	0,110		-	L	! •	
		CIACL	1		Ĵ (· · · · · · · · · · · · · · · · · · ·	ŧ					}	
10.120				1				480 14		;				l I		Í
			1	T	1,7	1	Ť	Loui Ching		M 84 48 0	10,120		+			+
		14				H	S.			7 5	1					j
an a a-i.	••		┫-╢-╢		4	4-	Į.				KU.130					1
į		S. H. Ju	118		1 3					1						
0.140 I					المر ا	la				i		Brert DET No B				
•		· · · · · · · · ·	5 1 15-		7 ¹² 7	ll G	8			•	10,140	\$ -J\$-\$1		E		·
i					1 {		İ.			1			19	4		!
Q.150			1115		2		8								FAT STORES	
	10		1 12		5	Ē	N				10, 30		++	┼╾┼	Temperature	4943. 741 - 741 + 1867 -
	2	1		1	2			- Marie Carrieg - Leel Circula	- 4936916 . Hinn -				Ŷ			
0.180 ₋₄₋					• •• •• ••	·	44	• • • • • • • • • • •	· · · · · · · · · · · · ·		10,100	G+0 Ns (8 1			HOLE	
;	<u>र</u> ्स्			1			1		i	ş	į		П	ΤT	History and	"Referent of Lighty "
0, 170	<u> </u>				1				j	j	. 1	l		\mathbf{O}		
	10			·····	han na san nin I		1+				10,170	·····	++		ALCOVERY	a) - 11
	Ì		1		· •		1 :	1		[•				•1 •1 •1
0,100 <u> </u>		110100	· · · •							[10.180	,		I I	HOTE	
			ļ						····				11		last a mana a last asanad k	le intennist eren eftega
5 190			4				1:	İ		}		•		1 '	1 beninnes 1	Mang In Cau I
чел ду —			·····			<u>↓</u>	┽┽				10,190	e i i tronomi i		ļ	PALSUPLS	
1	- E		i	2				ļ	i		-		1		n tat Paw j	774 - 846
200					;			ì		•					nirati Stay) da 1. di Fuju	4.09 148.0232
							11	·*** # #***** #		•	10,200		┥┽┈		an se se i a Se se si a s	4063 718* F
							1		•	÷						
4210				• • • • •			ļ.,	76 88.	ua ⊾a⊫ ,, ,,	و معر ، ، ،	19,819		31			
	2		·				:1	Lest 8-18413	- 6 1	-*-	•••		D			fallada ang Shiman
220	?						i			!			1 29	330	rati rang Mati Senji ang	126
	+ +'-'	14	• •	····•	· · · · · · · · · · · · · · · · · · ·		÷	• • • • •		···	10,220		11	- -		

LA FOLOMBUS UP AND ASSACIATES, NO

.

. . . .

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARGENAL PRESSURE INJECTION DISPOSAL WELL

FIGURE IQ. んシーラー デオ数型 - M*RHYAK ID,880+ ID,880

.

i		••••••••••	•	·] '	.#+135	-		418 - 44 CLAY	Time	€+(+&¥+ 	14E 8	сяд 1; сант 1;	r 4 11 8 8 9 Frantana		Ĩ	80 +8 (1584) (1997)	1 1 '5 81018'9	
		\$4405.*r.4	• [[]]		14. 15.8.TC	[ni uttat		6.46840 E42637.6 UDL2#1	2 4-4 45 4855 1	C'++++	freeberg			1 (4) 2 4 / 4 1 4 8 8 - 7 8 1	188828188 6412 19858 197 18 - 17 3418	
ртн 9.210	Санка У10н МА Ни Е Я З -	LITH()1059	* #ACTU	415 <u>64</u> 8 (0) (0) (0) (0) (0) (0) (0) (0) (0) (0)	85 041A 010 848 5171 6694 17 8717	0-9 E A- 1 M T T I P	CO4-46 	DHILLE TPS COME	0 	LARKS	DR.LLIN		0A	е о 	Rtit TES Rivi	К*ЕМ Т., Ч.;	04+, (14+ 465;	5 T () 5 T 14 T 5
	Ş			1	i	:		:		:		! !			1	{	!	
				····	, Digiti Maketi Waketi	i adjugta un segeti un segeti	d ng ng hag ng	• +		•		10,230	1 .		1	Q.11	·	·•••• _
0.240		·····			an a a		· •••	;		• • • · · · · · · · · · · ·	-	10,240				 	•	
<u>, 24 7</u>] } ! (0.260	-	•			,	
280					4 8		:	:	<u> </u>	8 - 01	-	}				• - • · 		
	· ++			· -# 	··	•	•••• ••• •	• •	· · · · · · ·			10,240	• • ·•	•			÷ •	
270				; ; ; ;	•••	•	· • •		-••	+		10.270						
260_		*_ 88 8+		- uk	er - mak - 1				1. 		1	10,280						
380				ł						•	-*			••		- •·	. •	
240 L			1-4		······ ·· · · · · · · · · · · · · · ·	 ; ;	;			•••••	······································	10,290		•••		2.	٠	
3¢D ,		# # #.#.	┥┥	**************************************	+	·				·+·	+	10. 3 <u>00</u>	-4	:			,	
	OLINITALIA .			- -					: 	•	:	, , 20.310		. (•	•	
, PC					Sha ie				011 40		0++++ -++++++++++++++++++++++++++++++	• "***** - -	Biert D 97 wa	· , ,		٠	••	
					1996, 1996, 1996, 1996 	48. <u>(***</u>	<u> </u>	101	Pesser Fr Attaining for	died Obt ^o literer 1		10,327	6 - 18 - 6 - 18 -	01 101 101 101 101		•	••••	
ы.		ه، میرد مرد مید. مورد م		: -+	2 				• ••••••••••	.	 	10,330	4	÷.			- يە	
•0 .				•		•			المغار فنتعل	Rubin Mitlacubi	BIT 73 860	10 140	514/1 DST 44					
												· • • • • • • • • • • • • • • • • • • •	• • • • • • •) e •		·	e -	
				•	- 4 1 1	•	••••••••••••••••••••••••••••••••••••••		4 - 1999 - 1999au 1		• - · • · • · • ·	10,350		•••	9 <u>9</u> 		· •	
1 0.		•		•···	• -		·		∙ ∳* ⊔iana		••••••	107240) 	•	
⁷ °,			 	• • • •	••4 •	•			ut			0, 170			 	I	:	
٥.												·		• • • •	2	-	4 -	
•••	T Pr		1. L.	•	· - • · · · · · · ·	order og se o		<u> </u>			· · · · · ·	10,380 ,			11	•••	•	

. I A POLUMBUS OR AND ALAN AFES, MC

.

1

. .

A A R. (MBUS, LR AND ASSOCIATEL AV

...

					401397						- 5	π⊾ ₩£Ι ≎⊷:∎	սեղ Բանգ է է։	*. #41	7	, 18 g Tarag ala	
]] ===================================					 	r 1 & 1 5234854			1 1 10 14 1 1 10 14 1 1 10 14 1 1 10 14 1 1 10 14 14 14 14 14 14 14 14 14 14 14 14 14	al, F 248, FM22 Çatiz	1 13 2444 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	7411444 - 54 		Ba fabaday Terd fabaday Terd fabadaya Terd saya Tara saya Tara saya	
01.0100	гонылт;сн Манаен 3 1		*****	CORE 5 64 8010 1004020	DATA BAN T FERMI	in (ç CA	H-HG - UT I TGOT	िमारा कन्छ र एम्स्	F0 .D j	" <u>I</u> V	4 <i>8</i> K 3	#EAU-6 6 804 DR-621 BITS	4 - (LE #7# 46 1	DATE DECUR- BENEF		ни стания 1 - на 1 - н	u 5 *€* 51 1u:1s
10,300	Į.			t bertens For company	;			Г Т	1			6-T 80 Y			5	1	
10,900					Ť	- 1	ריין גרי גרי	E C					- <u> </u>	· · · · ·			.
 				:					10±	***	1	<u>hari</u> ngan salah s		- 20-41	1		• • • • •
10,420					ina Daartin a Industina Industina Industina	erante e	هد در ۱۰۰ میلود (۱۹۹۰ ۱	†		•			<u>, 10,4 10</u>				608
10.430				• • •	··• •		b		-	·· -·		• • • _	<u>+ 10,420</u>	-•··	•.•	fn dig: Shut - 4 Sunni Anna - F agi Bhai b Tanggrafuri	in 130- - 444 1303 212*
10.440				-#		-*	6 .		. .	ta	.	· • · • •			• • • •	Tibili	1 min 1 0 m
1				i 1	•• • • •		۰. مع ۱			.	4 1 14 - 1 -		10.440	•	•	Prist Shat	57 4 5 90 s
., עובש				•	• · • •	• • •	•	• • • •			• • •	•••••	, 10,450 : :	• .		540	1 26 (194
10.460	N.			••••••	·• · • · = •	- · • ·	• • • •	 	·		8 - www.sa •	• • •		<u>.</u>		Welt, No bist an Wy presed a West have	in Yaati Ine 22a ad in Be
0,470	1			•	••• •••	····•				i		٠	. '0 <u>,</u> 470	· .		9 19 19 19 19 19 19 19 19 19 19 19 19 19	
0,4 80	e T			•	. . .	· • · · ·			•	••		.	(0,4¥0)	· .		*	
9,490				• •	•	•			•	- -	. •	• • •	10,490	• • • •		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
9 .99 9.		· · · · · · · · · · · · · · · · · · ·			†	• • •			±	ء ي د د		•	10,500	ъ и л		•••	
2.510				· • • •	• • • • • • • • • • • • • •		•		!			<u>. #11.74.0</u>	1 (0,61 <u>0 </u>	••• •		• ••••••	
. <mark>; محد د</mark> ا					n • • === = = = = = = = = = = = = = = = =	9 4 0 1	•		•	-4			10, \$20	•	Ţ,	.	·
.532						• • • • • • •	•••		•	• •		• • •	10, 53 0	ا م م		•••••••	
: i	1.1. 			· •	b - s - s	• • •	•		• •	•••••		<u>8.174</u> 0	.19.540			• •	
, 35¢	1 -					• • ••			: • •	- 1				6 24 6- H		,	

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DURBEDTAL

.

,

.___

I

ς

H2 8 FIGURE 10, H1 EH (AL 10,380 10,60

-- ----

FIGURE 10 SPAPHICAL REPRESENTATION OF H*E212 0.115 0.720 FORMATION EVALUATION DATA REGERY MOUNTAIN ARGENAL PRESSURE INJECTION DISPOSAL WELL <u>....</u> ****** 1.1 cratine # RUR 5 "# ę. == -----(147)(148)*#18 545 - 10 •11 \$44.597CAE 0478 (#),59°6# 5° 25' 0564#- #44 ________ 241665784 7857 8832675 PLAN 15 PROVING ALTS 21 FURNEYSCH FILARES MARKERS 1 TH 1257 -**** 10.950 ì., <u> - - - -</u> : : !-(9.589 4 'n 317 12.567 -----transfer adjudged to a bat briefertiet ----w 9 1 7 7 M -----÷ . 916.91 ÷.... 10,570 335 - Lest Code attan ż 10.500 - --# --1.1 . 5.540 ----10,590 ____ 91671 CM0 18 8-30-87 2.596 1 · · · 6.1.70.0 -----.... ::1 and the second se ţ 10,600 . . **i**. i., 730 h K H ١. 146. Q 4 .. 6 ? = in her 9 And a subsect of the subsection of the subsectio 10,620 1222522222 í * * * † † NACCORD 2 . . .520 ٩., GIErs # Hydramera 5:93 In Fac Fray 683 In East State 1043 Einer Flass - 685 ः@ 10,630 ... í • ŗ • 1.51.51 - • 18.630 Fingt Saulia 1270 . ï 1910) 10.440 tints . 1 1 10,640 In-Ind Page Sec. In-rat Sec. 30mm Frag: Page Science Page Bad S 20mm ţ È 🛛 14.51 Que Bar 2 .,650 **π** 1 10,652 2 ARCONANY 100 yalar. 90 mul 10,660 -5,660 . . e 4 Week bing Dood -Smin 0.670 16.670 10,640 . 10,690 -- I .i 5.470 10.700 . . • 2.14 .0.710 . . , ئىا ++1 <u>_ Ł :</u> C.724 5.72

and a conject of the state of the

WHEN OF AND ASSNOTATES INT

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DISPOSAL WEL

No 10 FIGURE 10, Noter (AL 0,780 - 10,840

	ſ		. [.		стана) Събан Събан		IN JE(AL WELI	L • • • • • •	(*1488) 87-1	- 1 1	2 8 g	
]] ======	- []]	·			- 1 AT			i F 	1) Gaar 1			ne regerere Re regerere Cele regerered Fang were	
- LARPTH	FT) PHEATION		*RACTUR	60 0000 CDMC 20000	2414 	<u>منتشبة المناجعة</u> و دومينية	DHILL		 () () () () () () () () () () () () ()	REALING		DATE		19999999999999 81107999-11-59978 11	ì
10.720	L			113.11	T PERNE	# W-W-1.**		EU	<u></u>	BITS		' OC CUM	*7 4 * RUN	HE UNICESTER	'
10,730									(0-T 60 0	1 7 - 19,730	Btart Dat He 10		men ühr die sall Hij - Sen aller: B	-
10,740					Digiting g Indugtings white g iss) (644) 148 - 149 - 910) 1449 - 149 - 48 177 (644)		+-4		•		*- ** ****	NHO I	1899 - 200 - 2008-200 - 2003 1	- •
10,750						-		••••• !	- 40 44 -	···· · · · · · · · · · · · · · · · · ·	10,740	••••••••••••••••••••••••••••••••••••••		K .	4
			-+-+		• • • • • • • • • • • • • • • • • • •		•	······································		•	10,750	- <u>+</u>	-	ج منتقص	· ·
10,160			-++								10,780	•••		·•• ···••	
10,770							; ++	- <u>+</u> - <u>+</u>			10,770	; -• • • • • • • • • • • • • • •		;	•
·9,780			┥╺	! 	:			11 11			10,780	1			-
19,790					;] {					1			i @	1999 - Andre II. Al II. C. C.	· •
0.000				l l l l l	ł					8-7 61 A.D		Brary I Care Marte		de e serve france esta constante se	a
						- 			* * ***** ·		-C. 8:20	())	— , , , . @	\$
, G. M (G ,	1949.0		+ - +-			<u>64 m. 19. 17. 1</u> 1 19. 19. 19. 19. 19. 19. 19. 19. 19. 19.			1 		2.000	· · · · ·		Mit Boumets Mathematical B389 In Fall Form 604	•
. o ' \$ \$9	- 14			31414	<i< td=""><td></td><td>O</td><td></td><td> </td><td></td><td>0.020</td><td>1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1</td><td>- +</td><td>Constant Bour do - 731 Pinas Fiano - 870 Finas Moleste - 1880</td><td>۰.</td></i<>		O		 		0.020	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- +	Constant Bour do - 731 Pinas Fiano - 870 Finas Moleste - 1880	۰.
. 16 ,430 .	ě		4	the's		· · · · · · · · · · · · · · · · · · ·					-12+8 20		•	Tittes In fiel Plan 2 min Inclui, finn 10 - Plana	
ุศรุษฐาน				ing Shave The second	 					•	: 10 140 1			Finde Flans - dag nove Findel Schuttin - FG nove	-
10.836				#Aqta ' 1.041	1			L Sut Pro	10					RECOVENT RECOVENT	•
·*.840						•••• •••••••••••••••••••••••••••••••••				•••• • = ··· • • • · •	10.830	••• •. •••	+-· •	NOTE Webb blav, Coost SI nu	•
• • •				···		*	•		+	, ****	12, 115,		• • •	• • •	•
, ¹ 6 ∎15 , ,				· · · •		∎: ·· .y.			••••••••••••••••••••••••••••••••••••••	i . Mener (m. / m	:2 .6.7 12		ф. С	· ···.	•
, 4.840 ₁ .				· · ···•	·· · ·	• · • • · · •			•**********	<u>817 82 8,0</u>	9 	. 10	a me 	· · · · ·	
iù,89.				· .		and the second second second second second second second second second second second second second second secon		: 	: ; ****		1 1.831 -	iy s a }	•! · · ·	; ;	
													•		

E A PLICHOUS IN AND ALLOCATED INC.

.-

GRAPHICAL REPRESENTATION OF Formation Evaluation Data Rocky Mountain Arbenal Pressure injection disposal well

NO 15 FIGURE 10. PL*E# (AL - 10,8#0 - 11,040

- A POLUMBUS, UR AND ASSOCIATES, INC

E & POLUMBUS, UR AND ASSOCIATES, INC

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA Rocky Mountain Arbenal Pressure injection disposal well

ļ

Ę.

NO 13 FIGURE 10.

E & POLUMBUL, UR AND ASSOCIATES, INC.

المستحد المراجع المستح

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA FIGURE IO. ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DISPOSAL WELL c L O G £ G Е FRACTURES === SHALE OR CLAY . . **. .** SUTSTONE ARKORE SILTSTONE B -----LINESTONE FREE CALCITIC SAN DOLONITE -----44.**408**†.24E Ĩ. ANNYORITE -Cusas freewas ار الال ال CORE DATA CORNEG DRILLED POROSITY PERMEA- MINUTES CORED POSMATION FRACTURES DEPTH DATE D OCCUR-RENCE REAMING DRILLING DITS TEST AUN DRILLSTEN TEST RESULTS RENARKS DEPTH 36.0 ET MARO <u>n</u> . Ş < N N N N ÷. L U. 270 .. 4 11.170 ट्र . . . 3 <1 Ş. \$ <u>وولامانا</u> بر 10000 e 11.380 ≪1 i Ē 11.390 é. 16 380 NR Ne Recevery Rep Escantin P ma Pressure FIRISA Cere 25 ţ Ludeo ... 11.400 ł <u>...</u> i -1 Depths adjusted to Induction-adjusted to where warranised 11.419 ٢ . , <u>11. ezo</u>, i 11.420 ۲ ۱ . . . ----I Drill Stem Test New 13 8 14 results are presented ٢ 11.430 i : ۲ 057 13 BIT 95 880: 11. 440 11.440 ٠ FOUNTAIN', FORMER -----Stort 11.450 2 П . Ccre 24 : 0. 460 III 1 ł <1 2 11,400 2 11,440 C . 3 í Ŧ "Ka Ne 470 Frank Core 24. 8-80-41 8-22-81 Benter Bastel Core D., at N 11.4.00 11,400 1.11.490 ł 11, 490 1 1,500 11.600 01 11 ng Breas 21, 505-11,512 11,510 Drit Brem 11,610 11,520 11.420 11,530 . 11.530

E & POLUNBUS, UR AND ASSOCIATES, INC

(

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PREAMURE IN LECTION DISCOUNT

÷

\$

Ĩ

NO 15 FIGURE 10.

4

1

1

		-			PREB	SURE (JEC		DISPOS	AL WEL	L	CTURES		A E
		BILTETON	•E	+***			ALE DH CLAY			ALE	1 0	******		larad Ha (85818)¥
		34.406704	" <i>∭</i>		HITE [• 00#	9.0 49%	-	CALCIT	TONE, FREE		•····		1419 / 419-6496 Cyra + 949 1997 9 2 1997 9 2
DEPTH	PORMATION	сіїноцору	FRACTURE	S BARDID	DATA BAROID	COMING	DRILLI	20		TEANIN	G	 ۵478	ORILLSTER	W DRILLATEM
11 330		1	<u> </u>	POROSITY	BILITY	MINUTES PER FOOT	CORE	a	-EMARKS	DRILLIN BITS	GI	DCCUR-	TEST	TEST RESULTS
						1							J	
<u>; цацо.</u> ;			┝┥	+				╞┿┅			! 		_ m	
	i			Ρ	<١.		5	╡┩₋ݠ	enen Bannet			Carn Ma 20 8-dd-91	Te 11.02	•
,	╄ <u></u> ┥		╞┼╌┼╴	+	Depths edja								-++	
					wart un	4-14								
	POLINITAIN				1									∳
L.II.870	+													NOTE
														Results are presented on Chart Ne re
. 13 .580	·		┝╍╋╾╄╸	r †							1.11.5.89	-+		
														,
<u>, 11.510</u>	╡ ┍╸ ┥╺╼┽		┝╼╪╾╪╼								11.990	+	$- \Psi$	
:										+		+	╾┼┽	
										BIT 97 D	1.619			
. 11.620		····					+							
· ·								Ì						
			╺┼╶┼┥				┼╌┼	+			11.000	<u> </u>	╺╼┥┤╽	
1.040														
											11.940	++	╶╴┨╼┽┥	
							\downarrow	<u> </u>			11.560			!
, ,				ľ										
							+				11.880	++	-++	· · · · · · · · · · · · · · · · · · ·
;														3
↓	┈┼╼╫		┨╌┨╺┤				╋				1.420	<u> </u>	- 	
11.000					ĺ			<u>, cws</u>	unte Baren Bante		4	Press Bantet		1
							\uparrow	1			1.11, 6.8 0	╋ ╸ ╶╌┿	- 1 200 -	
			┥┥		·						1 17.890		3	t
				1	ļ								1	i
<u>, 11.200</u>			┶┷┿								11.789	ļ	H,988	·
. 1	i		ĺ	ļ		1		ł	!	ı		: i	į	

E A POLUMBUS, JR AND ASS 14TH INC.

· •··· •..

-

.

GRAPHICAL REPRESENTATION OF FIGURE IO. 5. 18 Γ × ↔ ↓ 5*Ε¤+4, 11,700+81,880 FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DISPOSAL WELL CONE Cone Constant Co 4.6.5, FRACT UPES. · · SHALE CH 5 L*8* "NE A##258 1411197068 B 1 Car Freetore R ł EINESTENE SALSTICHT DOLONIE 58503105E 1 Ì ANNIERTE - 6 C 1888 8 8 18 1 19 19 CORE DATA SAHOLD BARGID FORDSITT FEAHEA-.... OFFTH REARING OMILING DEPTH PHILING : DATE C DHILSTEN TEST : RUN 08124 5784 TEST RESULTS REMARKS L.11.200 5 11.710 . ---11.710 Des the adjusted to Industrian - algorith **Ce** 8 es, st 11,121 -ariented 1,720 16720 ÷ 11,780 817 99 0 1 1 16750 1 - } -1 Ì 11.749. 16 740 ÷ 1 2 11,750 ŵ 1.789 T EO'sf send gave 20' OF BANG ZONE NOT .11.710 •• ÷ 0 _u.m . . w -----11,720 Hydrostatid ; tairia: Piper In fiel Bhut In 4:43 610 3859 901 BIT 100 0 0,800 Fingl Figer Fingl Real In Proj Hydrosoft Tomanatura • 11.000 1218 214+1 i . 11, 010 TINED. 11.010 There is a start of the second P.820 . i 0.00 RECOVERYS ł 6330 Hud Lew Cases Last Cares de Bit ALT IOL O HOTES <u>, 11,630</u> 60 Ĩ Test Packar sar in Bård", cesing et bå 50' Hola Upper te mar trän myr it Bastal Care bio 24 630 مرانان معرو i í . 1.848 ÷ ſ ł . U.84Q. Hydrosiate Hydrosiate Finite Fice Finit Fice Finit Hydrosia Tamporatu d 11.840 ----FOUNTAIN i BIT 103 0 0 . . . ÷ 6029 1.77. 3.443 9.144 1 . 11,450 . 5 1 01.4 BIT KH D Set 2'yHa a - 30-61 TIMES 11,860 i laiter Fiam. Interim Bier fr 196 min 93 min MECOVERY 11,870 . 14870 ۰. \$400' Beit Meter , HOTE 15.880 HEGO: ITH 1
 H. 664
 Tast Pecasi pet

 Biter Cave27
 Tast Pecasi pet

 0:3-61

 <t 16880 #17 105 D BEATHERED ۲ Ð SHA. E

E & POLUMBUS, JR AND ASSOCIATES, INC

1.400 :

?

11,610

GRAPHICAL REPRESENTATION OF FORMATION EVALUATION DATA ROCKY MOUNTAIN ARBENAL PRESSURE INJECTION DISPOSAL WELL

FIGURE IO. NO 17 ETUU

RACTURES

ł

1

1

E A POLUMBUS, UN AND ASSO ATES

Figure 12

ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL

Schematic Diagram of Typical Three-Stage Comenting Operation

. . ·

I A F L WE ST A ANY APPENDING . .

MODEL "D" PACKER

TYPE LINER FLOAT SHOE

ł

1

÷

,

SPECIAL SUBSURFACE EQUIPMENT

FIGURE 13

Table 1

STRATIGRAPHIC SECTION ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL SECTION 26, T2S - R67W ADAMS COUNTY, COLORADO ELEVATION KB 5, 203'

		DEPT	ГН
		Below	Sea Level
		Kelly Bushing	Datum
Tertiary, Tertiary-Cretaceou	surface i	to 460'	
Cretaceous			
Laramie		460'	+ 4, 743'
Fox Hills		1,250'	+ 3, 953'
Pierre Shale		1,480'	+ 3, 723'
Hygiene Zone		5,448'	- 245
Niobrara		7,710'	-2,507'
Codell Sand		Absent	
Carlile Shale		8,0781	-2,875'
Greenhorn Limestone		8,120'	-2,917'
Graneros Shale		8,3451	-3, 142'
"J" Sand		8,485'	-3,282'
"Dakota" Sand		8,6331	-3,430'
"Lakota" Sand		8,730'	-3, 527'
Jurassic			
Morrison Formation		8,786'	-3, 583'
Triassic			
Lykins Formation		8,972'	-3,769'
Permian			
Lyons Formation		9,5821	-1,379'
Pennsylvanian			
Fountain Formation		9. 772'	-4.569
Regolith		11, 880'	-6,677'
Cambrian? Ordovician?		11,895'	-6,692'
Pre-Cambrian		11,950'	-6,7471
	TOTAL DEPTH	1 12,045	-6,842'

A 11 11

CORE DESCRIPTIONS ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL SECTION 26, T25 - R67W ADAMS COUNTY, COLORADO

- Core #1 ("J" Sandstone) 8502-8529 Cut 27' Rec. 27'.
- 5' Sandstone, very shaly, dark grey, fine grained. Carbonaceous streaks and material disseminated throughout, tight, oil odor, very weak fluorescence and cut
- 3 1/2' Sandstone, fine, grey with streaks of buff, quartzitic, vertically fractured, streaks of oil stain, faint odor, fluorescence and cut.
- 1' Shale, black, hard.
- 5 1/2¹ Sandstone, fine, grey with streaks of buff, quartzitic, vertically fractured, streaks of oil stain, faint odor, fluorescence and cut.
- 2¹ Sandstone, fine, light grey, quartzitic, no stain, no odor, no fluorescence.
- 1 1/2' Shale, black, thin bedded, poker chips.
- 1 1/2' Sandstone, fine, medium grey, quartzitic, no stain, no odor, no fluorescence.
- 1/4¹ Sandstone, fine, dark grey, very shaly, with carbonaceous material disseminated throughout, oil odor, scattered stain, scattered fluorescence, and weak cut.
- 1/4' Sandstone, fine, medium grey, quartzite, no stain, no odor, no fluorescence.
- 6 1/2¹ Sandstone, fine, dark grey, very shaly, with carbonaceous material disseminated throughout, oil odor, scattered stain, very weak fluorescence.
- Core #2 ("J" Sandstone) 8531-8566 Cut 35', Rec. 35'.
- 35' Reworked sandstone and shale.

A A PRODUCTS OFFICE AND CONTRACTORS OF ST

Core #3	(Dekota-Lakota Group) 8637-8670! Thit and Rec. 341.
12'	Sandstone, fine grained, grey. (- 'zi .c, slightly pyritic, with shale breaks 1/16" thick every - io 6". No show of hydrocarbon
71	Shale, black.
J ,	Shale, black, interbedded with sand, fine grained. Quartritic, 1/16" to 1" thick.
1'	Shale, black, with sandstone pods.
3'	Shale, black, interbedded with sandstone, grey, quartzitic 1/16" to 1" thick.
1'	Shale, black.
2'	Shale, black with sandstone pod inclusions.
· 7 1	Shale, black, fissle.
Core #4	(Dakota-Lakota Group) 8673-8685' Cored 12' Rec. 10'.
10'	Sandstone, fine, medium grey, quartzitic. No shows of hydro- carbon.
Core #5	(Dakota-Lakota Group) 8688-8694' Gut and Rec. 6'.
1/2'	Shale, black.
2'	Sandstone, fine grained, dark grey shale cement. Salt and pepper carbonaceous material disseminated throughout, quartzitic.
1/2'	Shale, black.
3'	Sandstone, fine grained, dark grey shale cement. Salt and pepper carbonaceous material disseminated throughout, quartzitic and pyritic.

4

۲

Core #6 (Lyons Sandstone) 9597-9607 No recovery.

Core #7 (Lyons Sandstone) 9609-9632 Cut and Rec. 23',

23' Sandstone, fine grained, orange to light red, very quartzitic, highly fractured, no shows.

Core #8 (Lyons Sandstone) 9656-9665 Cut 9' and Rec. 9'.

9' Sandstone, fine grained, orange to dark red. Quartisitic, red
9 shale laminae 1/64" or less thick. Separates 1/2" - 1 1/2",
9 sandstone intervals throughout core. Fractures from 9665-9665 1/2, 9668-9669, 9670 1/2-9672.

Core #9 (Lyons Sandstone) 9669-9674 Cut 5', Rec. 5'.

51 Sandstone, fine grained, orange, quartzitic, one hairline fracture and one open fracture exhibited along face of the core.

Depth correction 9681 = 9674

Core #10 (Lyons Sandstone) 9676-9678 Cut 2', Rec. 1 1/2'.

1 1/2¹ Sandstone, fine grained, orange, quartistic, one hairline fracture and one open fracture exhibited along face of the core.

Core #11 (Lyons Sandstone) 9681-9698 Cut 17', Rec. 16 1/2

16 1/2' Sandstone, fine grained, orange, quartzitic, red shale laminae 1/64" or less in thickness separating sandstone bedding from 1/2" to 1 1/2" thick. Open fracture in top 1 1/2". Hairline fractures from 1/4" to 1" long throughout core.

Core#12 (Lyons Sandstone) 9698-9707 Cut and Rec. 91.

9' Sandstone, fine grained, very silty, quartzitic, 1/2" red shale at 9699 3/4".

> Bedding: Horizontal bedding 9698-9698 1/2 10° dip in bedding 9698 1/2-9707

Fractures: 96	98	- 9699	Closed Fracture
96	99	- 9701	No Fracture
97	01	- 9701.5	Open Fracture
97	91.5	- 9702.5	No Fracture
97	02.5	- 9703.5	Closed Fracture
97	03.5	- 9703.75	No Fracture
97	03.75	- 9702	Open Fracture

E A POLUMBUS JR AND ASSOCIATES INC

الدار المحمد المحمد المعيون

Ł

.....

Core #13 (Lyons Sandstone) 9707-9727 Cut and Rec. 201.

Sandstone, fine grained, very silty, quartzitic, abundant maxoon shale partings 9717.8-9718.2'. Dark maroon shale very silty 9726.5-9726.6. 9721.2-9727 interval of core contains ultra silty fine grained sandstone, quartzitic.

Bedding:	Horizontal bedding	9707 - 9718,1
	10 [°] dip in bedding	9718,1 - 9722,5
	Horizontal bedding	9722.5 - 9727
Fractures	: 9708 - 9708.5	Open Fracture
	9708.5 - 9710.2	No Fractures
	9710.2 - 9710.8	Open Fracture
	9710.8 - 9711	Closed Fracture
	9711 - 9711.5	2 Open Fractures
	9711.5 - 9712.5	Closed Fracture
	9712.5 - 9718.5	No Fractures
	9718.5 - 9719.5	Closed Fracture
	9719.5 - 9721.5	Open Fracture
	9721.5 - 9721.7	Closed Fracture
	9723.9 - 9724.1	Open Fracture
	9724.1 - 9724.5	No Fracture
	9724.5 - 9724.7	1 Open and 1 Closed Fracture
	9724.7 - 9725	No Fracture
	9725 - 9725.5	Open Fracture

Core #14 (Fountain Formation) 9892-9935 Cut 43' Rec. 35 1/2'

2 1/2' Siltstone, red, shaly, quartzitic.

11/2' Shale, marcon, with red siltstone laminae.

10' Siltstone, red, quartzitic.

6' Sandstone, red, fine grain, quartzitic.

1/2ⁱ Shale maroon.

.

ł

201

3' Siltstone, red, quartzitic.

1' Shale, maroon, silty.

91/2' Siltstone, red, quartzitic

المراجع المست

1 1/2' Shale, marcon & siltstone bottom 3" gray dolomite.

Open & closed fractures throughout core, fracture surface contain microscopic calcite fill, 9915 contained 2 calcite inclusions 1/2" thick.

E & POLUMBUS JR AND ASSOCIATES INC

	Core #15	(Fountain) 10, 121-10, 158 Cut 37' %.ec. 36'.	
	6'	Siltstone grading to sandstone, fine grained, red, hard, quartsitic, trace of feldspar.	
	21	Siltatone grading to sandstone, fine grained, red, hard, quartsitic, trace of feldspar with few calcite inclusions.	
	1+	Siltstone grading to sandstone, fine grained, red, hard, quartsitic, trace of feldspar with numerous calcite inclusions.	
	31	Siltatona with trace fine grained sandstone, red, hard, quartsitic, abundant feldspar.	
	1/2'	Siltstone with trace fine grained sandstone, red, hard, quartsitic, sbundant feldspar and few thin laminae of black carbonaceous material.	
	1 1/2	Sandstone, fine grained, red, hard, abundant feldspar.	
	31	Sandstone, fine grained with siltstone, red, hard, quartzitic, some feldspar.	
	3'	Sandstone, fine grained with siltstone, red, hard, quartzitic, abundant feldspar.	
	8 *	Sandstone, fine grained with siltetone, red, hard, quartritic, some feldspar, some calcite on fracture planes.	
	4 †	Sandstone fine grained, red, hard, quartzitic, some feldspar.	
	41	Sandstone fine grained, red, hard, quartzitic, abundant feldspar.	
	Vertical fr 10, 138; 10	acture observed in the following intervals: 10, 127-10, 132; 10, 137- , 140-10, 156.	
Bedding is horizontal except as follows:			

 10, 121 1/2-10, 123
 10
 °

 10, 123 1/2-10, 124
 10-15
 °

 10, 133 1/2-10, 135
 20
 °

Core #16 (Fountain) 10, 317-10, 321 Cut 4' Rec. 2'.

2'

5

「いたち」ました

1

Shale, marcon, micaceous.

A POLUMBUS JR AND ASSOCIATES INC.

(Fountain) 10, 388-10, 401 Rec. 12'. C-Core #17 11 Sandstone, greenish-white, fine grained. Highly calcareous, hard, somewhat friable when broken. Irregular bedding. Micaceous. 31 Siltstone, marcon, micaceous with shale laminae. Slightly to moderately calcareous with highly calcareous greenish-white. fine grained sandstone inclusions 1/4 to 1/2" diameter. Flat bedded, hard, 51 Sandstone, pink, fine grained, arkosic, moderately to slightly calcareous, hard. Contains coarse quarts and feldspar grains randomly scattered and quarts and feldspar pebbles near the base. Fractured vertically to near vertically. 94.3 to 95.7 interval contains eight thin (average 1/8" thick), irregular, greenish-white fine grained sandstone beds, highly calcareous. 1/2'. 1/2' shale bed, marcon, noncalcareous, dipping at 30 degrees, hard. 2 1/2' Sandstone, pink, fine grained, arkosic, moderately to slightly calcareous, hard. Fractured vertically to near vertically. Note: Sandstones contain much kaolinite cement. Fractures: 10, 391.5 - 10, 392.0 10, 392.2 - 10, 397.5 10, 398.0 - 10, 400.0 Core #18 (Fountain) 10, 594-10, 644 Cut 50' Rec. 51'. 2.01 Siltstone, very shaly with streaks of arkose, medium, pink, calcareous. 0.21 Arkose, white, fine, very calcareous. 0.81 Arkose, pink, very fine grading to siltsone, very shaly, with fine white sandstone inclusions, calcareous. 1.0" Arkose, fine to medium, very shaly, dark red, 15° dips, calcareous. 4. Oʻ Shale grading to siltstone, dark red, very calcareous. 1.01 Shale and siltstone as next above, noncalcareous with 1" streak of green white medium arkose, noncalcareous. 2.01 Arkose, medium, angular, very shaly, very calcareous, dark red, with white medium gray arkose inclusions, very calcareous, Inclusions cut across bedding planes and they are 2"-5" thick.

Ъ

E A POLUMBUS JR AND ASSOCIATES. INC.

1

Core #18 (Continued)

2

Ī

Į

ļ

ł

Ŧ

۰.

(contrased)	
1,0'	Arkose, red and white, as next above with 3/4" thick bed of white.
3.0'	As next above. Arkose predominantly red with white inclusions in center portion of interval from 2"-4" thick. Upper portion has minute calcareous (white) inclusions.
3,0'	Arkese, medium, very shaly, calcareous, dark red.
1,01	Arkose, medium, red, very shaly with 1/2-2" streaks of white arkose, medium, very calcareous.
1,0'	Shale, dark red, with streaks of white medium arkose, very calcareous.
6.0'	Siltstone very shaly, calcareous, dark red.
4.0'	Arkose fine to medium, very shaly and silty, dark red, very calcareous.
0,51	Arkose, medium, white, very calcareous, dark red.
0.5'	Shale and siltstone, dark red, calcareous.
0.51	Shale and siltstone, as next above with irregular inclusions of gray sandy limestone, dense.
1.0'	Siltstone and shale, dark red, very calcareous.
0.51	Limestone, gray, dense.
7.01	Shale, marcon, hard, calcareous.
0.5'	Shale, as above, with sandstone, dark gray fine inclusions, noncalcareous.
3.5'	Shale, marcon, noncalcareous, hard.
1.0'	Shale, dark red, calcareous and gray dense limestone mixed.
2.0'	Siltstone and shale, dark red, hard, calcareous.
0.51	Arkose, very coarse, angular, very shaly, dark red.
3. is t	Siltstone and shale, micaceous, dark red to maroon with float- ing mica and quarts grains.
2.0'	Arkose, coarse, calcareous, angular, with streaks of siltstone, calcareous.

E A POLUMBUS JR AND ASSOCIATES INC
¢

Core #19	(Fountain) 10, 796-10, 846 Cut 50' Rec. 48'.
6.0'	Shale, red. marcon, micaceous, calcargous.
. 81	Arkose, medium grained, very micaceous (biotite) slightly calcareous, greenish grey.
1.71	Arkose as above with shale streaks, maroon, micaceous.
1, 3'	Arkosic conglomerate with quarts and feldspar pebbles. Matrix pink. Pebbles pink, maroon, black, very shaly.
1.2'	Shale, red, soft.
7.0'	Arkose, medium grained, much biotite mica, kaolinite cement. Two maroon shale partings 2"-4" at 10,809.8 and 10,811.8, whitish pink, slightly calcareous. Streaks very coarse grained to conglomeritic. Dip 15° cross bedded.
4.0'	Maroon shale, micaceous interbedded with pinkish white arkose, coarse grained, minute streaks green shale. Slightly calcareous.
3.5'	Maroon shale, micaceous, streaks green shale and arkose, coarse grained, pinkish white.
2.5'	Arkose, coarse grained, biotite mica, streaks shale, maroon. (Arkose greenish white).
1.51	Shale, maroon, micaceous.
.5'	Arkose, medium to coarse grained, abundant biotite mica, green- ish white. Streaks maroon shale.
1.0'	Shale, marcon, micaceous.
1.5'	Arkose, coarse grained, muscovite and biotite mica, kaolinite cement, marcon and green shale cement.
2.0'	Arkosic conglomerate, green shale and kaolinite cement, streaks maroon shale.
2.0'	Arkosic conglomerate as above with much maroon shale,
1.5'	Arkose very coarse grained, greenish white. Much kaolinite and green shale cement. 0-15 ⁰ dip.
2.0'	Arkose as above, many laminas maroon shale.
1.0'	Shale, maroon, micaceous, streaks arkose as above.
1.2'	Arkose, coarse grained, greenish white, kaolinite cement. 15 ⁰ dip.
1.0'	Shale, maroon, with reddish brown limestone inclusions,

ł

I

;

1

A DOUGHBUS ON AND AND FRATEN INF

• '

Core #19 (Continued)

.

. 7'	Arkose, very fine to very coarse grained, greenish white kaolinite cement. Marcon and green shale laminae, in- clusions brownish red limestone,
1,5'	Shale, maroon, very calcareous. Inclusions reddish brown, dense limestone.
1.0'	Shale, red, reddish brown limestone inclusions.
	Fractures - Closed: 10,802.5 - 10,803.5 10,804.5 - 10,805.0 10,807.0 - 10,812.0 10,823.5 - 10,824.0 10,834.0 - 10,836.0 10,838.0 - 10,839.0 10,839.5 - 10,840.0
Core #20	(Fountain) 11, 044-11, 080 Cut 36' Rec. 344
3.51	Shale, red, with reddish brown limestone inclusions.
. 51	Linnestone, gray, dense.
1.0'	Shale, red, with reddish brown limestone.
6.5'	Shale, red, soft.
1.51	Arkose, coarse, pinkish red, hard and tight, fractured.
2.0'	Shale, red, with reddish brown limestone inclusions.
2,51	Shale, red, soft.
2.01	Shale, dark red, silty.
4.01	Arkose, pinkish white, coarse grained, kaolinite cement.
1.5'	Shale, marcon.
9.0'	Shale, red, soft.

Open Fractures 11,056-57 Close Fractures 11,065-66

E. A. Dr. C. SCOLLE, J.R. Arega Astro-Critical processory

Core #21	(Fountain) 11, 129-11, 178 Cut 49' Rec. 48'.
, 5	Shale, dark red-purple, soft noncalcareous,
6,7	Arkose, medium to very coarse, angular, light maroon, contain- ing muscovite and biotite mica, with pebbles of quarts 1/2" in diameter. Very shaly with maroon shale, noncalcareous.
2.0	Arkose as next above interbedded with marcon shale, non- calcareous.
4,6	Arkose as described above, noncalcareous.
. 2	Shale, dark red.
5,0	Arkose, medium to very coarse, angular, light greenish white, containing muscovite and biotite mica. 20% kaolinite cement and muscovite, light green shale cement. Many streaks of chlorite.
3.5	Shale, dark red, soft.
2,0	Arkose, as described next above.
. 5	Arkose, as described next above interbedded with red shale.
7.0	Shale, red, soft.
2.0	Shale, red, silty, micaceous.
4.0	Arkose, fine to very coarse, angular with pebbles of quartz 1/4" in diameter, very shaly, with green shale cement. Bottom foot slightly calcareous.
1.0	Shale, dark red, soft.
3,5	Shale, dark red, silty.
1,5	Arkose, fine, green-gray, very shaly containing biotite mica.
2.2	Arkose, as next above, interbedded with red shale.
1.3	Shale, red.
. 3	Arkose, as next above, hard and tight.
1.2	Shale, red.
	Closed Fractures: 11, 139 - 11, 139.5 11, 147 - 11, 148.0 11, 152 - 11, 153.0 11, 165 - 11, 166.0

POLIMES JA WHILA & STATES NO

- 1

.

Core #22	(Fountain) 11, 262-11, 326 Cut 64' Rec. 40'.
0,5	Shale, red.
2.0	Arkosé, Coárse, <u>alive green, nönc</u> alcarcous.
5,5	Arkoss, very coarse to conglomeritic, maroon, very shaly with pebbles of quartz, clear to milky, and orthoclase feldspar.
2. 0	Arkose, conglomerate, pink, primarily angular clear quartz and orthoclase feldspar.
1.0	Shale and arkose as next above interbedded.
2.0	Arkose, conglomerate, pink, primarily angular clear quarts and orthoclase feldspar.
1, 5	Shale and arkose as next above interbedded.
6.0	Arkose, very coarse, marcon, angular, very shaly.
2.5	Arkose, conglomerate, pink, primarily angular clear quarts and orthoclase feldspar with 0.3' of marcon shale 1' from base,
2.5	Shale, marcon.
2.5	Arkose, very coarse, pink, primarily angular clear quartz and orthoclase feldspar.
2.0	Arkose, marcon, coarse to very coarse, very shaly, angular,
0.5	Shale, red plastic.
1, 5	Arkose, coarse, maroon, very shaly, with pebbles of quartz, clear to milky, and orthoclase feldspar.
1.0	Arkose, very coarse, pink to green, predominantly angular, clear quarts and orthoclase feldspar.
3.0	Shale, marcon, micaceous.
2.0	Arkose, coarse, maroon, very shaly, with pebbles of quarts, clear to milky, and orthoclase feldspar
1.0	Arkose, coarse, marcon, very shaly.
1.0	Arkose, coarse, marcon, very shaly with pebbles of quartz.

1

•

ł.

ļ

K

E & POLUMBUS IN AND ASPOCIATES INC.

5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a - 5 a

Core #23 (Fountain) 11, 364-11, 394 Cut 30' Rec. 26',

- 2.0 Arkose, white, coarse, predominantly clear quarts, orthoclase feidepar, muscovite mics, angular, white clay coment.
- 3.0 Arkose, marcon, coarse, with scattered pebbles of clear quarts, very shaly.
- 2.0 Arkose, white, coarse to conglomeritic, clear quarts and orthoclass feldepar, white clay cement, angular.
- 1.5 Shale, marcon, micaceous.

ł

- 1.0 Arkose, medium, abundant biotite mica, whitish grey interbedded with maroon shale.
- 3.0 Arkose, very coarse to coarse, whitish pink. Clear quarts, orthoclase feldspar and muscovite and biotite mica, white clay cement, angular.
- 1.5 Shale, maroon, micaceous.
- 11.5 Arkose, coarse, maroon, with pebbles of quarts and orthoclase feldepar, muscovite and biotite mics, angular, very shaly.
 - .5 Shale, maroon, very micaceous.

Fractures: 11, 367-11, 368 11, 369-11, 370

Core #24 (Fountain) 11, 447-11, 475 Cut 28' Rec. 23'.

2.5 Shale, marcon.

- 4.5 Arkose, medium to coarse, white grading to marcon. Clean to very shaly.
- 2.0 Shale, marcon.
- 10.5 Arkose, coarse to conglomeritic, greenish white to pink.
- 1,5 Shale, marcon.

Fractures 11, 453-11, 454

- ------

F & POLUMBUS JR AND ANGOLIATEN INT.

Core #25	(Founatin) 11, 543-11, 545 Cut 2', Rec. 2'. (Bowen junk basket)
, 3	Arkose, coarse, white, with pebbles of quartz and feldspar, fractured.
1.7	Shale, maroon, slickensides.
Core #26	(Fountain) 11, 827-11, 829 Cut 2 ⁴ , Rec. 2 ⁴ . (Bowen junk basket)
1.0	Arkoze, coarse, marcon, very shaly, fractured.
1.0	Shale, maroon.
Core #27	(Regolith) Corrected from 11,872-11,895 (driller's depth) to 11,882-11,895 (E-log depth) Cut and recovered 13'.
2.0	Shale, marcon.
3.5	Shale, purple-maroon, weathered, bottom foot very leached.
2.5	Shale, maroon, silty, weathered.
1.0	Shale, very hard, silty, maroon, with white leached irregular areas.
2.0	Shale, dark brownish red, soft.
2.0	Quartzite, reddish brown, with whitish green leached areas, fractured.
Core #28	Pre-Cambrian 11, 976-11, 985 Cut 9 ¹ , Rec. 6.7 ¹ .
6.0	Biotite, hornblende, granite gneiss, fractured.
.7	Biotite, hornblende, granite gneiss and pegmatite.

Ĭ

I

RIG DESCRIPTION

Company	Leffian	d Brothers		Rig No.	7
Drawworks: Make	Ideco	Model	PR 1050		
Compound: Make_	National	Model_	3 Engine	No. Cha	in s
Rotary Table: Typ	be of Drive	Drawv	vorks		وينيوني والمحمد المحمد الم
Compound Engines Co	: No. <u>3</u> ontinuous HP Ratir	Make	Caterpillar Oper. Speed a	Model	D-397 1150 RPM
Pump Engines: No Co	. Compounded ontinuous HP Ratin	Make	Oper, Speed a	Model	
Mud Pump: (1) M (2) M	ake Emsco ake Emsco	Туре Туре	D-700 D-500	Input HP Input HP_	700 500
Derrick: Make	L. C. Moore	HT	142'	Rated Loa	d <u>900,000</u>
Kelly: OD 41	/4''		1/2''	Length	40'
Swivel: Make	National	Type	R-3	ID;	2 3/4''
Hose: OD			3''	_Length	55'
Standpipe: OD	4 1/2"	_103	3/4"	_Length	50'
Drill Pipe: OD 4	1/2" ID 3 3/	<u>4''</u> Gr	ade <u> </u>	Weight	16.60
Tool 7 ts: Size_		Туре	ХН	ID	
Drill Collars: OD	8'' - 7''	ID	3"/ 2 3/	4''	
Desander: Make	San Angelo	No. C	ones <u>3</u>	Power	Wak 135 GKU
Couplings: Make_		Туре	Siz	eLoc	ation
Torque Convertore	: Make	Туре	Size	Loc	ation
Operating Conditio Rotary Table (ns: Speed: lst Gear_ 4th Gear_	<u>30</u> 21 80_5	nd Gear 50 th Gear 125	3rd Gear	65
Engine Idle: Vacu		S	peed 400 F	PM	
Full Load Conditio Engine Sp Liner Size Mud Weig	ns: eed 1150 9 ht	_rpm_Vacuum Pressure Rotary Sj	uumo	r Stack Tem Pump Speed Depth	900
	i + POL	NBUS JA AND	ABOC ATES PA		

SUMMARY - DRILLING AND CORING PERFORMANCE ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL

Ì

Ì

ļ

i

	Foota Drilled	Gored	Net D1 Da Drilling	rilling <u>ys</u> Coring	Penetra Feet/Net Drilling (2)	ation Day (1) Coring	Cont. No.	ores Ft./Core	Penetration Ratio Drilling/Coring
Surface-"J" 0-8,485" Ton "T", T	8,485'	ı	14.0	ł	606. (530)	ı	ı	ı	
8,485-9,582'	9831	114'	11.0	8.0	89.4 (46)	14.3	ŝ	22.81	6.2
9, 582-9, 772' Fountain - <u>D114</u>	951	951	3.4	12, 1	27.9 (15)	7.8	80	12.0'	3.6
9, 772-11, 880'	1, 700'	4081	24.8	19.4	68.4 / 301 p.1	21.0	13	31.4'	3. 3
Regolith-Total Depth 11, 880-12, 045'	143'	221	2. 1	1.0	(51 inse 71.5	rt) 22.0#	2	11.0	4 4
Total	11, 406'	6391	55.3	40.50	(49) 206.2	15.8	28	22.8	

Includes coring time plus time rearing core hole.
 Figures in parenthesis in drilling parenthesis in drilling parenthesis.

Figures in parenthesis in drilling penetration column denote feet per bit of drilled hole.

(3) Core hole not reamed.

E A POLUMBUS JR AND ASSUCIATES INC

Table 4

ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL HOLE DEVIATION

Deviation	Depth	Deviation	Depth
3/40	i 85 '	1 1/20	7,930
0 0	246'	1 0	8,150'
$1 1/2^{\circ}$	380 '	1 0	8,4801
1/20	500 ⁺	1/40	8,670'
1/20	660*	1/20	8,7504
3/40	820	1/40	8,925
3/40	9671	1/20	9,0301
3/40	1,3001	3/4 0	9,340'
1/20	1,480'	11/40	9,470'
1/40	1,7561	3/40	9,6751
1/40	2,0001	3/40	10,0101
0 0	2,2051	13/40	10, 1504
1/20	2,6291	21/40	10,2001
1/40	3,1001	21/20	10, 330
1 0	3, 590	33/40	10,649'
1 1/20	3, 7201	43/40	11,030'
1 0	4,000'	6 0	11,170'
1 1/40	4,380'	6 °	11, 340;
1 0	5,2551	5 ⁰	11,530
1 0	5,470'	7 °	11,6001
1 0	5,890+	5 °	11,675'
3/40	6,4001	5 °	11,720'
1 0	6,6901	5 °	11 ,7 90'
2 1/2°	7,000'	51/2°	11,835
3 0	7,1001		
3 1/40	7,211'		
3 1/40	7,340'		

(Taken from Loffland Brothers daily drilling report.)

Table 5

t

¢

F A FUICMB SUP AND AS C ATLS INC.

	Ł	F	*	<u>_</u>							8																												-g
c.	w 20 at a 125	15 78 min at 2009	075 intra 11,200		Mula Matteliala Useb ti rus	A VIIT AMOUNT COST		regend:	PV = Mastic Viscos	YP= Yield Haint	· LCM= LOST CINCULAT	Ca . Calculat		sionalize - then 1												,		 -					naterials included	parate report.					Inter cost 1 19791
	***			H1.424 5				Agender.	Z+-0e1	Baroid	ingerme.	1	10,010	Urber Pho	in could	i on c	Earth mark	Princip Fran	Hvd., .rb	5	Article u	E abertes	Y = 14 4	Marine K	Celficine.	Prind Smit	Ĩ	Country Ser	4-Y 900.	1150	Cet somer	v	M. 6. 7	5 10			Darware Sules, Top		
ar state Colorado	county Adams	LUCATION BOCKU MAD. ACTION	2. 3.6 TWE 7.5 EVE 67-W		DO		6 Rudded un mi Access 1 - 4-	20 Avagel Driscose Tonner Country	wrig 20 hole	Logging & set 2,000' 13% cosing	Drive 10 ious solids condet mud	6 634 pumpliners - Ane. velocity 120/min		Daverted to Gyp-OBroxin mud	Added Safe to Jack OI		Vis increased for coring i testing	Coring & testing	increasing Vis w/ Aquayel & Zragel	Flourd and them af and in an are	Fishing - thisted off			Joind content 16%	L FORICA	Coring & reaming	Losing mud	Corina i Fram. 20	3 % lost sirculation material in mid	Lest 100 bbls, mud	Lost complete returns		Lut concert 37.	9 40 Solids - 490 LCM. Inst 2001-LL	LCM- 3% [03+ 100 bbls	LCM - 8% to 10%	LCM- 840 0013. MUD	1	
រ្មី	-050			ι	Ĵ		6	و		2	l	-	~(43	1400	\$80	30	220	880	5	87.	0101	1240	1200	0201	1160	200		8	1080	:	ğ ş	920	820	000	8	000		
Arn	0.50	- se			٤		1	I	1		ł	I	ł	۲	・オ	- In	Ŧ	-	1- V	ه د	و ا	ഹ	5			9	÷	ŋ	n,	- 1	-	"	- נ	a	ત -	-			
+	5	ഫ്	٩		<u>_</u>	Ľ														133			1	ł	130														
202	ect	pue	Ļ		. .	Х				-	Q	2	0.	~ 0	ŝ	٢	Ť		<u>t</u> <u>o</u>	. 64	ų	= !	ď 2	2 -	- 2	5		- in	Ĕ.	20	5.9	00	ď	Ŧ	ۍ ژ	25	0		
1000	H	Ŧ	٤	ł	8	P V				۲	و	71	n s	0 00	=	t	ā. i	23	r (તે	ē.	5	0 V 11 C	<u>n</u> r 1	- 3	50	a≁ n n(c	1 K	5	000	Г ^с	20	5	7	46) tor	30		
1.50	CSSUC4	يد و	F) S	:			300	500	001	100	200	82		500	11.000	1,000	25.48	004.01	13,300	11,000	1,000	8,745	2,215	000	1.425	7.400	25,30	1 950	3.800	0564	0000	3300	3300	3475	1475	1020	1650		
NEAM	ц Д	NEAC	م) الارد الارد	Ŧ,		İ	5.0	000	n T	5.5	9.0	50 (50 a) (- 0	0	8.5	0		9 v - 0	n vo a se	0.3	ارما م	n c			و ہ	ä	<u>.</u>	ò	Q (ç Ç	ý	0	ò	ò	Q 4	ļ	ŝ		
3	3	3	ć	Ś	,		m.		-	×.	ž			7.		<u>र</u>	<u>ر</u> ا ـ		2	_	يم. م	2 ⁴ 2	• • •-,d	بر. ارجا	••		, v∽ 1, c	ંત	્તા	t.d	- v- r.d	بن ابر	24 a.	2 4 3	tro €	ب ⁷ ام م	74 De		
5			وا			i	-	- ((~			(R	લ	rt 1		ډ -	- ~	ત	~	- 1 a	ંત			רי - הי ה			a c	((1	(d	4	- ~		• •	ે (ત	-		
-		,	9-0	-		ł	र्भ 'र	0 . 1 1	9	و ج	アド	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	- 04	9	со Г	. + و	و و ف	0	0.0	5	+ 5	و د م		1	22		و د	2		- el	و ا	ç	<u>म</u> ्	0	, u	, ó	ú		
ۍ د د						ł	<u>0</u>	0 11	1	-	0	0 0		÷Ŧ	ō:	9 9	n x	2.6	99	89	<u>00</u> }	0 0 0	9.00	10	6 0	bo k	 ماز	60 (<u> </u>	. 0	0	*	0	<u>o</u> (rσ οιλο	.ت	7		
z	ž					Ì	0 (0 0)	0	0	0 0	-		n(:	- c	ra Ta	۰ıŋ	و.	n) -		- n	। ≰∓		- d :	ר <i>ק</i> מ די מ	າດ ເກ		۲ ۲ ۲ –	- 0	1	-	ო იი	ירי חי	×π -i∩	- (ດ ດ		
SIC	MPA		i C				9	- 2)	ł																		-	٣					•					
2	ů O		Ę			1	1 0	o C n n	}	1	n e	22	8	5	<u>0</u> :		۲ů	Ť.	t	<u>م</u> .	7	9 -	• 0	_	к 1	0 0	16	ہ مەر	ი იი	- T	9	n I	00 7	r .	- 0	<u>م</u>	-		
ų	LEAC		Ę.		÷		0 0	- 1		9	n,	t 7	رد. جر	و ا	_	á í	900	Ľ.	80	- C		, v ,	i se Q	و. ج	ي د دې د	 9 99	16. 149	ي دو	- 0 - 0	رى رى	۲۵ ≠	i− vj	j.)≟ ' ~{	يو. ارت	5		
aic	NAL NAL	יונייי	יש ט	:		10	0 n 0 - 0	ы с [.] О	0	ლ. ოკ	जि इ. १	5 X 1. A	S P	ۍ د ح	ງ ປີ 🛚	- 0 - 1) 0 =	ч 9	י די הוי	0 0	- 5 - 5	20	. 0 . ~	.ت ور	ەت مۇر	- ም የ	ю m	orij ∞ .	- 6 9	م.	یم	ਰਾਂ। ਨਾ।	ອີດ ຄະ		-0- -	oj o	; -		
A R	ATIO		3	•	:	194) (});	4	5.5	2 9 7 4	6.4	1.69	101		, u	13	8.66	8.75			956	9.53	5	53	6.	5	0.0 1.1 1.1	į	9.74		5	л о 7 о	9.9	0.01		000		
ä	Ż			-				5 m 1 m	μ. Τ	10 10 10 10 10 10	2	50	н- 1- 1-	4-9 	90	- 7	+ +	4-15			رہ ہے۔ 1 ہی	. K	5-3	5	د ا ا	ر ار در	5.14	20	27	5 23	34,5				- - -	- 01 - 01	9	•	

I

•

TABLE 6 Pg I

t

1

T. l

Engrisiane Colorizdo al countr. Adams Location Rocky Mtn. Arsenal	THE AD TWE ALD AND OF
company U.S. Government-Army will Pressure Ibjection Dispos contractor Loffland Bros.	
BAROID DIVISION NATIONAL LEAD COMPANY DRILLING NUD RECORD DULLING MUD RECORD	an start of start VIGCARY Thursday HEADS

_

			. .																																						7	g.
v	18	9		-						,	ļ															,			İ		; ; ,				•						Ī	
5	i 8 1 4		í. 1	ļ		9																																				
1	5 1		5	10101		5																																				•
_	2		i i			2 2																																				-UST
(1	с П	rîv ≌V	ġ			1.120																																				τ.
		•	7			đ				1	÷			•	đ	۶			×	F	ę		_ ;		ų		÷.	-		r	are.		i									5
	5		M10			5					E SO	i e	hi Ki W	anufun.	eher P.	소곡	- Juun		а С	- - - - - - - - - - - - - - - - - - -	7 X 1 X	in the second		i i	1110			1	ъ В. С	ž	S of the second			OTTO						1		
1	2		č ₹	,	-	-				r; eo		-	9	33	Ģ	ი	r≓. An	5	J :	t :	£.	5.	\$;			5 2		2	¥.	1	ຽ∷;	8 .ª		- 6	õ					53		
•	5		101						*						3		5					~		_									icot.	•	2	,200	į	2				
			5		ž				5						ğ			-+					51										20	~ '	2	ef i	Δ.	C 				
) al	i, r		ATME				2%		÷	_			ž	Š	2		š L	2		-	i d d	1	Ŧ	2				L			У		8	bu.		د ب م	1			
	1	A'S	U Z		D TRE		1		5		e,	•		`	יג ג'			• 0				100	a ç Din	Ā,	<u>n</u> : :	-				, S		.1		1	-	S	4					
		1 2.	а 		S AN		C	2	ŭ,		10	•	2 2		d.	8				5		Ť	2	;+	Ę	2				3-		Seat	Ę	g	đ	Fish	Ē			hole		
o p	ņ	ž	ຍ. ກ		MARK		1	+	5		ŧ		させ	•	34	i c	Ĕ,			-		2	<u>;</u>		; ;+ ; ;				ł	¥.		. 5	ō	5	4	9	4	ě,		74		
5	49.04	Ň	JAC .		ä		100	oter	5 PPIS	3	pate	-	Ť		57	Ě					-	÷	į	i l				20		۰. م	\$	ž		pa l	Pul.	5	Ę		~	ۍ م	-	
Õ	ĕ.	γĨ z	9				Ŭ S	ט א ד	8	ž	й Г		ŭ S		55		<u></u>	1		3		ъ.	ة ر	- 0	Ę,	5		Ξ		Ĕ	5	ž.	ų. P	3	2	5191	p.	432	C	5.5		- 1.
316	VIV	CATIO	d				2	ŭ	103	1	วิ		<u>Ū</u>		ŝ	1	Ĩ.	iā	Ċ	Īα		Ú T	107	8	1			Ę	c	Ö V	1	Pear	ЪÅ А	e ū	2	2	Deid	100	ີ່	5 Ja		-
15.5	8	3	2	Ş	}																											_		<u> </u>		•	(-			•		
ц Ш				Ċ	đ		210	1160	120	1400	80	22	140	80	8		88	2 2	35		8	000	240	9		420	8	g	j	88		g	ĝ	8	ŝ,	8 §	3					
ξ.	ŝ																	• •	• •	• -		. 2		-		-	R	сı	,	0.2	73	3	19 19	ក្ ក	n	1 Q	à à					
₫, ⊢	à	gros	~				ĺ																																			
и Цер	tion	ш Т	d n o	ŀ		ď	'n	ũ	ŭ	ā	<u>.</u>	5	+	t -	+ -	- 04	a kr		• - +	• 0-	· \n		2			ول		-	63	۲v) 10	ى		•••	÷ () ,		.	- -	~~		
212	ğ	lan				<u>ر</u> ک	90	9	3	- 5	ð	00	.	0 d	10		9	00					- 60			-		កា ១ (n n N	(- 0 0	- Cf	~	a. G		 	57 93	•	0	~0	-11		
ş	ы р	- H	e V			9	0	0	л 0	а 0	0 0	ներ Մեր	n (n o (יים סים	6 ()) ()	6 ก ม ((ก (0	. ni	רק ס	(n) 0	n o	- 0	ત	`	~	άς Λ	~	ૡૻૡ	11 c 0 c	ζ. δ. Ο	រំណ័ រំត	ŝ	તું બુ		in a	ñ d	ı	ž		- 4		
n S	SSU.	۲ō	Ľ	:	:		132	50	165	55	ŝ	0		2 0	2 2	<i>i</i> č	3	3	Ŷ	9	00	100	ŏ	ğ	ğ	<u>0</u>	ğ	ë (50		۶ ۳	õ,	Š,	0 d	ž č	ğğ С	,	4 0	000	50		
YNY(ξų.	TRAC.	1EEH	Ŧ			'n	ò	ò	Q I	ŀ,	o (ò d	ç	۶v	, 0	و	Ņ	Ģ	Ņ	ó	'n	ò	\$	ų	ί	43	o (o ç	, Q	ŗ,	o,	٩Ņ	ក្នុង	5 Q	a Va	!	5		ასი		
ŝ	MEL	ö	5 2	2			u d	ত ৻৻	দ লে		л Л) o (j .d	г 3	-0 	. 0-	- 04		0	9-	00	00	с.	or	9	-	00 I	o - (a c	50	. 0	· Da) بھ) o	n a	-0	0	•	o~ :	έđ	0		
			~	3		 .		<u> </u>	· ` ·	<u> </u>	× :	×		-~		_						74			-	Χ.												Z		14		
		,	ۈ	1441	•			о. К	. ч	57. 32	0.0 0.0	а с 16 с	ፍ (ት ((C	ה : ד	. d	гб ~~	3	3	ۍ س	3	ۍ م	4	.a	ۍ ه.	<u>с</u>	c((~ ()	n n	(((4	લ	4.	60	10	ાત			• -	~		
		(, ,	-			ف	÷	0	-	× -	-	- 5	o	ف	- ~ ·	00	0	00	ف	Ē	0 0	و	5	ο.	5	गः । जन्म	21	L u	5	1	5	ก่ไ		5	6	;	× •	ې ه د ف	0		
•				2			ų,	=	<u>0</u>		10	× 5	57	5 -	0	3.8	35	35	ત	30	นี	5 C	35	ને	ς β	m	ם נ די	4 (7 7	0 h 7 7	20	÷.	. e. n n	77	50	0 1 11	3			- 10	4		
Z	ž.			3			v a	-	~~	იი	l a) n	((1	6 ल	a	8	16	m	4	Ŧ	đ	എ	Ŧ	n)	61	6	0 3	<u>t</u> :	: 2	Ŧ	2	ع م) u	す	· (ব		0 0	0 0	-		
ັອັ	MP		2	400	·							35)																													
ž	U 0		3	*1.	r		с і А	<u>, 1</u>	ŝ	<u>e</u> :		97	0	0	80	5	ŝ	5	4	å	36	5	<u>6</u>	-	+	<u>e</u> ;	5 5	≰ c	10	5	5	τ <u></u>	- 2	22	5	٩	,	54	13	2		
	Ĭ			5	3		÷.		4.	<u>.</u>) u	, v) in	ę	ų	Ŧ	ŵ	÷	ń.	न् न्	i.	á.	ৰু কু	τ.	ن، د_ (ο- 1	 +	- -	 - 7	÷	m (- ni	5	0	י ו	00 00	1J- 10-	ন ক		
	Ž		b .i	۶ ۲			۰ ، ٥		و. د م. د	ро 1	- 9		·σ :	a	ም ም	ৰ ব	ч 1	σ.	۵-	8	<u>د</u>	о. С.	9.1	a. (<u>с</u> (2.0	٥ تر	r o س	- - -	8" 10	a- c	وير مر	- 0-	٠ ٥	۰.	Ű	0 01	ກັບ ດ	ivi A	oi.		
R N	1 ON		3	í ang	τ		00	t	1 0	5 1 1	12	200	-1		0,58	C.64	3,0	J		5	0.08	¥071	i	١		1		52	ñ	đ	22		ξ.	ç	225	22	ġ,	35.5	5	395.		
n	Z		1	_			و	-	ر ۳-۳	- `				• •••	-	~	-		-		-	~						5		11	=:	= =	-		Ξ	11		2 2	: =	2	-	-
				1 ¥0						<u>ہ</u>		, n	5.2	5.25	5	5	-	<u>بر</u>	÷,	و ا	-	= !	Ľ	1	- 0	- ?) - 1 (iá	r cr L U	4°,	50	- 6	4 6 6	0 0	.	'n.	ι Υ	ی کر 	ē.	44		
			1			- 12	-	_	_	_			-	_	-	_	•					- 1	- (- c	- c	. 5	<u> </u>	<u> </u>	Ċ	Ċ,	- c	Ċ	÷	x	yo (~ 0	0.00	i io	òo.		

TABLE 6 Pg. 2

 $\overline{\ }$

UNING PROCEAM. 2.0 mon of 125. M 13 25 mon of 2.000 h 8 59 mon of 11.200 m ÷ 10-MUD MATERIALS USED (TURU) WATLEIAL IJNIT MIOUNT TOTAL COST IUTAL DEPTH 12.045 time Counic Sonta Solo Ash Gweenn Mir enr Dirt enr Boroco Zengel Boroud Imperview Murster (h) Pana-Sent Tut Flug (Johnson 1) Office Photo Quebrocho Hydries P-4-00-P Anhudrax Sevence Dryage Sales Tex Certerior er or Fiberer N KC Tannes in the L-gron lettate A-zuogel Saratus LOCATION ROCKY MAN. Arsenal REMARKS AND TREATMENT WHUNDUS GOUERIMENT-Army Engr STATE Colorado ... WHUPPESSUre Injection Ursposal. countr. Adam : contractor. Loffland Bros. Location Rocky Mtn. A verbur e INGINEER Fred M. Lang PV YP ራሪ ~ •7 2925 400 400 500 F : 9-- **9**0 0-3-0 N H2 01.41 19.20 ۲u . 19-**9-6**-61 tage 3 of 3 FIC THATL 24 ÷. ه ره و جو ó . ÷ 707 _v, 33 BAROID DIVISION NATIONAL LEAD COMPANY DRILLING MUD RECORD -0-0 WILL W.E Corhom, Jr. LIFTH ANUME VILLOUTY 2 : 11,792 9-0 48 11,927 9-0 48 11,972 9-0 41 11,972 9-0 41 11,825 9-1 41 ż 3 48.294 Da 1

ļ

5

ļ

I

FABLE 6 Pg. 3

ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL SUMMARY OF CORES

Í

Ĩ

			Depths				
Formation	Cor	e Driller's	Adjusted to	Feet	Unit	Feet	Unlt
or Member	No.	Depths	Electric Log	Cut	Total	Rec.	Total
"I" Sandstone	3	8 492. 8 519	8 502 - 8 52G	27		27	
	2	8, 521 - 8 556	8,531-8,566	35		35	
	-	0,021 0,000	0,0010 0,000		62		62
Dakota Sandsto	ne 3	8.623 - 8.657	8. 636 - 8. 670	34	••	34	02
	4	8,660 - 8,672	5, 673 - 8, 685	12		10	
	5	8,675-8,681	8.688 8.694	6		6	
	•	-,	-,,	•	52	·	50
Lyons	6	9.604 - 9.614	9.597- 9.607	10		0	50
	7	9,616-9,639	9.609 9.632	23		23	
	8	9,656 - 9,665	9.656 - 9.665			9	
	9	9.669 - 9.674	9.669 - 9.674	5		5	
	10	9,676 - 9,678	9.676 - 9.678	2		1.5	
	11	9,681- 9,698	9.681- 9.698	17		16.5	
	12	9,698- 9,707	9.698 - 9.707	9		9	
	13	9,707- 9,727	9.707-9.727	20		20	
			,,,,,		95		84
Fountain	14	9,892- 9,935	9,892 - 9,935	43	, -	35.5	•••
	15	10, 121-10, 158	10, 121-10, 158	37		36	
	16	10, 317-10, 321	10, 317-10, 321	4		2	
	17	10, 388-10, 401	10, 388-10, 401	13		12	
	18	10, 594 - 10, 644	10, 594 - 10, 644	50		51	
	19	10, 796-10, 846	10, 796-10, 846	50		48	
	20	11,044-11,080	11,044-11,080	36		34	
	21	11, 129 - 11, 178	11, 129-11, 178	49		48	
	22	11, 262-11, 326	11, 262 - 11, 326	64		40	
	23	11, 364-11, 394	11, 364-11, 394	30		26	
	24	11, 447-11, 475	11,447-11,475	28+		23 *	
	25	11, 543-11, 545	11, 543-11, 545	2		2	
	26	11,827-11,829	11,827-11,829	2		2	
					408	-	359.5
Regolith	27	11,872-11,885	11,882-11,895	13		13	
					13		13
Pre-Cambrian	28	11,976-11,985	11,976-11.985	9		6.7	• •
				•	9		6.7
TOTALS				639	·	575.2	

 Includes 2 feet cut with Bowen junk basket below 26-foot interval cut with conventional diamond core.

E A FORDMENT OF AN AN ONTE ON

ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL CORING EQUIPMENT SUMMARY

I

6 3/4" 6 3/4" 6 3/4" 3/4" 6 3/4" 6 3/4" 6 3/4" 6 3/4" 6 3/4" (Size) 6 3/4" 6 3/4" 6 3/4" 6 3/4" 6 3/4" 6 3/4" 3/4" 6 3/4" 6 3/4" 6 3/4" Jars Ŷ s Extension Kelly 30 30, 301 301 301 105 30. 301 30. 1 ł 301 0.000 ٠ ٠ Length **Core Barrel** 501 501 501 50-501 501 50' 501 501 501 501 501 501 201 501 201 501 501 5/8" 6 5/8" 6 5/8" 5/81 5/8" 6 5/8" 6 5/8" 5/8" 6 5/8" 6 5/8" 1.8/9 6 5/8" 6 5/8" 6 5/8" 6 5/8" 6 5/8" 6 5/8" 6 5/8" 5/8" n b ە م ¢ œ ۍ ور Total Cut By Bit - 96 18. 661 291 1971 Feet Cut 27 35 34 12 9 10 23 9 2 2 2 σ 20 43 37 4 13 50 3/8" 3/8" 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" 3/8" 4 3/8" 4 3/8" <u>..</u> 4 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" 4 3/8" -----Size 7 13/16" 7 13/16" 7 13/16" 7 13/16" 7 13/16" 7 13/16" 8 9/16 8 9/16" 8 7/8" 8 7/8" 8 7/8" 8 7/8" 8 7/8" 8 7/8" 8 7/8" 8 7/8" 1/8 8 7/8" 8 7/8" 0. D. 00 Core No. m \sim i ŝ ヤ Q ~ 11 80 6 12 16 14 15 19 Diamond Type = Ξ : 5 : : : Ξ = = -Ξ z : 2 Ξ : : [Serial No.] Corchead C-18404 C-18404 C-18404 C-18350 C-18350 R-18182 R-18182 R-18182 R-18182 R-18007 R -18182 R - 18 182 R - 18007 R-18674 R-18674 R-18674 R - 19674 R-18674 R-18674

. .

S A PO UMB S JH AND ANSCHATTER IND

Table 8 Pg. 1

Jars (Size)	6 3/4" 6 3/4"	5 3/4" 5 3/4"	5 3/4"			5 3/4"		
Kelly Extension	30' 30'	30' 30'	301			30'		
Barrel Length	50'	75' 50'	501			50' 50'		
Core O.D.	6 5/8" 6 5/8"	5 3/4" 5 3/4"	5 3/4"			5 3/4" 5 3/4"		
Total Cut By Bit		85'	94'		26' (Diamond) 2' (Bowen) 2' (Bowen) 2' (Bowen) 2' (Bowen)		22' 33' 6' <u>6</u> '	
Feet	36' 49'	64' 30'	261	51	5 5	13' 9'	-0 1-0	,
Size 0.D. I.D.	7 13/16" 4 3/8" 7 13/16" 4 3/8"	6 11/16" 3 1/2" 6 11/16" 3 1/2"	6 11/16" 3 1/2"			5 11/16" 3 1/2" 5 11/16" 3 1/2"	Total Cored	
Core No.	20 21	22 23	24		25 26	27 (
Type	Diamond "		=	Bowen junk basket	Bowen junk basket Bowen junk basket	Diamond	Diamond Bowen junk basket	
Corehead (Serial No.)	R - 18675 R - 18675	R - 18778 R - 18778	R-18796			R - 18779 R - 18779	TOTALS	

I

1

ł

Į

E A POLUMBUS JH AND ASSOCIATES INC

Table 8 Pg. 2

Lable 9 Pr. 1

1

DRILLSTEM TEST REPORT

Date: Ap 41 12, 1991	DST. No.:
Lease: R. day Mountain Agronal	Well No.: Diep. 1 W.11 Mp.
Test Interval: 6:66:0006	Formation: [Guil
Total Depth: (3)3	Well Elevation:
Testing Company: Halliburg in	Witness: Bet Line Bel

Test Data

1.48.00.000

ţ

I

Tool Open For Initial Flow @ Tool Closed For Initial Shut In Tool Opened For Final Flow @ Tool Closed For Final Shut In Cushion: <u>N m.</u> Hydrostatic Pressure of Cushi	1 :0ú A. M (@ 1 :20 A. M. 1 :50 A. M. 1 :50 P. M. Feet of 1 :50 P. P.	Top Ch Bottom Packer -2:50 P. M.	oke: 3/ Choke: 1/ s Set @ Feet =	/8" /2' p#i
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	<u>4.8</u> <u>292</u> <u>5.12</u> <u>157</u> <u>292</u> <u>#2.2</u> <u>#2.2</u> <u>8552</u> Nul 2000 - 6	<u>4.332</u> 2.2 452 	7 7 7 7 7 7 7 7 7	Time i <u>نامینی</u> i <u>نامینی</u> i <u>نامینی</u> i <u>نامینی</u>
Gas to Surface in <u>None</u> @ <u>Mcf/Day; in</u> Recovery: <u>200 Set of adentry</u> Remarks: <u>To a opened with we be</u> <u>n according to by ont</u> <u>*Pack - balled to be</u>	minutes @ minute @ good arillin al w increasing il an of test, ar of final cipit	Mcf/D Mcf/D 	/Day; in ay.	minutes

1 abl . 4 Pr. 2

1

LAST MUD CHECK BEFORE TEST

Date: Ap. 11 12, 1961 Test No. : 1

Drilling Mud:

į.

Plastic Viscosity: 3	f*	Chlorides (Cl [*]): 5.00	20
Initial Cal Strength		Calcium (Calc	
10 Minute Gel Strength		Sulfate (SO_):	<u> </u>
Weight: 9.	5		
Fluid Loss:	-1	-	
pH; 9.	0	-	
Mud Resistivity: 0.	2 1.2	Ω 4 84 F	
Mud Filtrate Resistivit	y: 0, 5	A (1 64 F	
Chromatograph Readin,	gs:		
G ₁	C_40,51	M	
C ₂ → M	C ₅ + <u>Not</u>	t decorded	

C3 ______

Recovered Fluid

Sample No.;	ł			
Plastic Viscosity:	304			
Yield Point:				
Initial Gel:				
10 Minute Gel:				
Weight:	8.2			
pH,	8.0			
Resistivity:	0.62	2	<u> </u>	2
Temperature of Sample;	45°F			
Chloride (Cl ⁻);	7,500			·····
Sodium Chloride (Nacl) · [
Calcium (Ca): Rmf:	ن ز ا			
Sulfate (SO ₁):				
Chromatograph Readings:				
C ₁	^C 4			
с,	C +	-		
С,				

•

1 . 11 10 Ph. 1

١

DRILLSTEM TEST REPORT

Date: No.11 20. 196.	DST. No.: _2
Lease: An or Mountain and and	Well No.: Drop. of Well No.
Test Interval:	Formation: Debute, Leis ta, March m
Total Depth:	Well Elevation:
Testing Company:	Witness: Next La Lour Bal

Ŧ

•

Test Data

Tool Open For Initial Flow @ Mi Top Choke: Tool Closed For Initial Shut In @ Mi Bottom Choke: Tool Opened For Final Flow @ Mi Packers Set @ Tool Closed For Final Flow @ Mi Packers Set @					
Cushion: None	Feet of	· _ · _ · · · · · · · · · · · ·	••••••		
Hydrostatic Pressure of Cushi	ion	pei/foot x	Feet .	pei	
Initial Hydrostatic Pressure:	N. 3	: 1:10	157	Time	
Initial Flow Pressure:	·····	:20	_ 27.3	<u> </u>	
Final Flow Pressure:	<u> </u>	<u> </u>	3.0	<u> </u>	
Final Shut In Pressure:	M .8	1554	. 111	<u> </u>	
Pressure Bomb Number;	12:2	;; ;7 .	# 9.		
Depth of Bomb:			.1 7		
Bottom Hole Temperature:	<u></u>				
Gas to Surface in <u>Nus</u> @Mcf/Day; in	minutes (minute @	yMcf Mcf/D	/Day; in	minutes	
Recovery: <u>(0) set 1</u>	ين المنا	<u> </u>		. 13	
List produce with	<u> </u>	/ lw th	1. L L	····	
	••••••••••••••••••••••••••••••••••••••	· · · · · · · · · · · · · · · · · · ·			
	and a state of the second second second second second second second second second second second second second s	a Distanti anti anti anti anti anti anti a			
and a second second second second second second second second second second second second second second second				······	
	aleman and a state of the second second second second second second second second second second second second s	ومالينيا والمراجع المالين والمراجع والمراجع والمراجع والمراجع والمراجع والمراجع والمراجع والمراجع والمراجع وال			
	ان بروان می باشد. بر روی می از می ورون برون می و این از می این این این این این این این این این ای				
	and a second second second second second second second second second second second second second second second				

CELLAR BE COMPANY OF ANY ANY ANY ATSING ME

•

LAST MUD CHICK BEFORE 1274

Date: word 2 . 1964 Lest No : 2

Drilling Mud:

Plastic Viscosity: 20	Chlorides (Cl [*]): 7,500
Yield Point:	Sodium Chloride (Nacl):
Initial Gel Strength:	Calcium (Ca): 960-1,000
10 Minute Gel Strength;	Sulfate (SO ₄):
Weight: 9.8	
Fluid Loss: 5.6	
pH: 9	
Mud Resistivity: 0,40	Q (d) F
Mud Filtrate Resistivity: 0,42	 @ F
Chromatograph Readings:	
$c_1 _ \{M} _ c_4 \{0,1}$	<u>5-0,75M</u>
$C_2 = 0, -2, 3M$ $C_5^+ = 0, 1$	-0,7M
C3	

Recovered Fluid

Sample No.:	<u> (Top)</u>	2 (Middle)	<u> </u>
Plastic Viscosity:	30	25	2 ;
Yield Point:	25	0ر	30
Initial Gel:	15	13	14
10 Minute Gel:	55	-18	48
Weight:	7.8	8,6	8,6
pH.	8	8	3
Resistivity;	0.48	Ω 0.56 Ω	0.6 .7
Temperature of Sample:	70°F	70°F	71.°F
Chloride (CI):	5,000	7,200	7,600
Sodium Chloride (Nacl)			
Calcium-(Ga)-: Rmf	0.38	0.45	0.4
Sulfate (SO ₄); Fluid Loss	4.4	5.4	5.6
Chromatograph Readings	:		
C ₁ <u>21; 30, 0</u>	C	4 2 200, 1. 700	2
C ₂ <u>15; 25; 15</u>	C	+ 100. 1. 200. 540	

C₃_____

--

.

Date: May 22, 1961	DSI. No.: <u>3</u>
Lease: Rocky Mountain Arsenal	Well No.: Disposal Well No. 1
Test Interval: 9662	Formation: Lyons Sandstone
Total Depth: 9729	Well Elevation: 5202 K. B., 5187 G. L
Testing Company: Schlumberger	Witness: Bert A. Lean Del

Test Data

Tool Open For Initial Flow (Tool Closed For Initial Shut In (Tool Opened For Final Flow (Colored For Final Flow (Top Choke: Bottom Choke: Packers Set @			
Cushion: None Hydrostatic Pressure of Cushion	Feet of	psi/foo	otx		Feet =	psi
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	5000					Time
Gas to Surface in <u>Mcf/Day; in</u> Recovery: <u>None</u> Remarks: <u>Tool was completely</u> <u>Test was a misrun.</u>	minutes (minute () plugged	with lo	Mcf/ Bt circ	cf/Da Day.	y; in	minutes
Test was run with the Sc	hlumberg	er For	mation	Inter	val Teste	r

E. A. ECOUPERS A AND AND ADDRESS IN

Date: June 3, 1961	DS1, No.: 4
Lease: Rocky Mountain Arsenal	Well No : Disposal Well No. 1
iest Interval: 9845-10016	Formation: Fountain
Total Depth: 10016	Well Elevation: 5202 K. B, 5187 G. L
Festing Company: Halliburton	Witness: Bert A. Lear Al

Test Data

Tool Open For Initial Flow at Tool Closed For Initial Shut In. (1:44 P.M.	Top Chol Battom C	te: 3/8"	3
Tool Clused For Final Shit In d			98+3	
Cushion: 1700	Feet of	Water		
Hydro ** atic Pressure of Cushie	n	psi/foot x	Feet	psi
	1771	1770	4953	Time
Initial Hydrostatic Pressure:	4776	4779	4852	
Initial Shut In Dressure				
Final Flow Pressure:			·	
Final Shut by Pressure:				
Pressure Bonib Number:	1376	212	193	
Depth of Bomb:	9830	9850	10012	
Bottom Hole Temperature;	206 ° F			
Gas to Surface in	minutes (1Mcf/1	Day; in	minutes
@ Mcf/Day; in	_ minute (y	Mcf/Day	i.	
Recovery:			····	
Remarks:Single packer test.	Packer fa	iled immediately	when tool c	pened.
Reset packer. failed ag	ain. <u>l'est</u>	was a misrun, p h fractures	robably due	to con
TITTE TETTE OFAIL OF ANIA PROF	zorial crist out			
الوالي الوالية العواقية الموسطونوس ومتاريتهم ومتاريتهم ومتالع ماليا متراجع المراجع المراجع والمعارية			-	
				-

A CONTRACT OF A CONTRACT OF A CONTRACT OF A CONTRACT OF A CONTRACT OF A CONTRACT OF A CONTRACT OF A CONTRACT OF

DRILLS, DM LEST REPORT

Date: June 4, 1951	DS.F. No.: 5
Lease: Rocky Mountain Arsenal	Well No.: Disposal Well No. 1
lest Interval: 9836-10010	Formation: Fourtain
Total Depth: 10016	Well Elevation: 5202 R. B. 5187 G. L.
Testing (ompany: <u>Halliburton</u>	Witness: Bert A. Lear Bol

Test Data

Tool Open For Initial Flow @ Tool Closed For Initial Shut In @ Tool Oper.ed For Final Flow @		Top Cho Buitom Packers		
Cushion: 2020	Feet of			
Hydrostatic Pressure of Cushio	n	psi/foot x	Feet =	psi
Initial Hydrostatic Pressure: Initial Flow Pressure:	*	1829	4934	Time
Final Flow Prossure:		· · · · · · · · · · · · · · · · · · ·		
Final Shut in Pressure:				······
Pressure Bomb Number:	1376	212	19%	
Depth of Bomb:	9813	9841	10012	
Bottom Hole Temperature:	206°F	· · · · · · · · · · · · · · · · · · ·	<u></u>	
Gas to Surface in (0Mcf/Day; in Recovery: 2020' water cushio Remark :Two packers, Pac Reset packers, and fail Around packers through	minutes (minute (n plus 1280 kers failed led again. n fractures.	Mcf/Da Mcf/Da Mcf/Da 	Day; in iy. <u>nen tool opene</u> dun 19.001	minutes ad n.munication
* Bomb #1376 - Clock	siopped.			

بمراجع والمراجع المراجع والمراجع

-

- -

۲

DRILLSTEM TEST REPORT

Date: Jun. 7, 1961	DST. 110.: 6
Lease: Rocky Mountain Arsenal	Well No.: Disposal Well No. 1
Test Interval: 9,862 - 10,057	Formation: Fountain
Total Depth: 10,057	Well Elevation: 5202 KB, 5187 G.L.
Testing Company: Halliburton	Witness: Bert A, Lear Sal

Test Data

Ē

Tool Open For Initial Flow @ Tool Closed For Initial Shut In (Tool Opened For Final Flow @ Tool Closed For Final Shut In @ Cushion: 630 Hydrostatic Pressure of Cushio	11:30 A. M. 11:37 A. M 12:07 P. M Feet of n 0. 133 ps	Top Cnok Bottom C Packers water ii/foot x 7.1	e: <u>1/8"</u> hoke: <u>7/8"</u> Set @ <u>9857 and</u> Feet <u>s</u> <u>3</u>	<u>1 986</u> 2 17p∎i
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	4, 822 1, 191 1, 052 1, 239 4, 33 ⁻ 1, 276 9, 839 2200F.	4, 529 Plugged 4, 562 Plugged 4, 393 212 9, 867	4,938 Plugged 4,633 4,127 4,493 193 10,053	Time <u>7 min.</u> <u>30 min.</u> <u>60 min.</u> <u>120 min.</u>
Gas to Surface in <u>None</u> @ <u>Mcf/Day; in</u> Recovery: <u>348' water cushion</u> , Remarks: <u>Charts indicated that perfo</u> <u>during th flow periods</u> . T for <u>calculations</u> , <u>based on</u> <u>Vol. of mud between tool &</u> <u>Vol. of mud lost due to lea</u>	minutes @ minute @ 180' mud cut rations were a The final build rsual e.:amir a hol - below p kag - & resett	Mcf/D Mcf/Day water cushion, lternately plug up curve app a nation, acker = 1951 ing tool (est,)	Day; in 1, 646' mud, ging and clear ars to be usab (0, 1175 - 0. 0 Total	minutes <u>ne</u> <u>330) * 1(.</u> Bols. <u>5 00 Dolo.</u> 21. 0 - 251-
Mud reco ared from form	ition = 19.11	-21.00 = -1.0	7 Bbl.,	

F. A. FULLMUCH, IN ANY ANN CHIES PAIL

ساست بندر الرار ال

• ... •

LAST MUD CHECK BEFORE TEST

1 I. A. .

Bel

Date: Jon 7, 1-61 Test No.: 6

Drilling Mud:

.. ..

-

Plastic Viscosity: 2	:6	Chlorides (CIT): 1 doo
Yield Point: 1	4	Sodium Chl	oride (Nacl): 1 (200
Initial Gel Strength:		Calcium (C	at: : 000
10 Minute Gel Strength:	······································	Sulfate (SO	1,000
Weight: 9.5			
Fluid Loss: 5,2			
pH: 8	·····		
Mud Resistivity: 1.3		O (â	° _E
Mud Filtrate Resistivity;	. 2		~ 0 [*]
Chromatograph Readings:			
$C_1 = 0, \Xi N$	^C 4	0.211	-
C ₂	C ₅ +	0.231	-
C ₃			
iora <u>a</u>			
Recovered Fluid			
Sample No.:	Тор	Middle	Boltom
Plastic Viscosity:	:0	48 - 60	50
Yield Point:			
Initial Gel:	10	15 - 13	20
10 Minute Gel:	50	90 - 90	1.0
Weight:	9	2 9.4	9.4
pH.	8	1.5 - 7	7.5
Resistivity:	1.2 9	1.2 - 2.0	3.5 0
Temperature of Sample:	887 F	60°F - 67°E	
Chloride (Cl ⁻);	000	600-800	500
Sodium Chloride (Nacl)			
Calcium (Ca):	800	300-220	ະະບ
Sulfate (SO_4) :			
Chromatograph Readings:			
$C_1 = \frac{450}{100}, 00, 480, 00$	<u> </u>	Tr. Tr. 50, 220	
C ₂ <u>(0, 10, (0, 420</u>	C_+		
C ₃ <u>6(, Tr. 0, 480</u>			
$\operatorname{Rm}_{i}^{i} = I_{i} (\dots^{Q} \text{ (To)})$	3)		
. 670			
	tom)		
	E A POLISHI.	19 1 1 1 AND C STEN IN	ıt

Date: July 16, 1961	DST. No.: 7
Lease: Rochy Mountain Arsonal	Well No.: Pressure Injection Dispusal Vell No. 1
Test Interval: 10, 000-10, 317	Formation: Fountain
Total Depth: 10.312	Well Elevation: 5, 202 KB, 5, 187 GL
Testing Company: <u>Hailiburton</u>	Witness: Al Samuels

Test Data

Tool Open For Initial Flow @ Tool Closed For Initial Shut In Tool Opened For Final Flow @ Tool Closed For Final Shut In (ű 	Top Chok Bottom C Packers	e: <u>1/8''</u> hoke: <u>7/8</u> Set (4	
Cushion: 1, 200	Feet of	Vater	_	
Hydrostatic Pressure of Cushic	on <u>1.500</u> p	i/foot x 0, 133	Feet _	0.20 p#i
Initial Hydrostatic Pressure: Initial Flow Pressure:	4,)45	<u> </u>	4. 927	Time
Final Flow Pressure. Final Shut In Pressure:				
Pressure Bomb Number:	1, 376	212	193	
Depth of Bomb:	10,053	10, 086	10, 314	
Bottom Hole Temperature:				
Cas to Surface in	minutes @	Mcf/I	ay; in	minutes
@ Mcf/Day; in	minute @	Mcf/Day	•	
Remarks: Packers fo 'el	in indintely.	Misrun		
اند مانانون و با اجرام و القامي » عن محمد بن موجد مارد – عامد و العمومي و القام . 				
والالا والمسود المريمين والمرجو ومرجوع ومعروف والمعيد بمناوي والمرجو	araan magaaga is birahar oo ahaa			
a anna a an an an an ann an an ann an an				
(a) A second s second second second second s second second s second second				

I A LL MED A A A A A A A A

Date: June 18, 1961	DST, No.: 8
Lease: Rocky Mountain Arsenal	Well No. : Pressure Injection Disposal Vell No. 1
Test Interval: 10, 137-10, 339	Formation: Fountain
Total Depth: 10, 339	Well Elevation: 5, 202 KB, 5, 187 GL
Testing Company: Halliburton	Witness: Howard H. Sells

Test Data

•

1

.

Tool Open For Initial Flow (a Tool Closed For Initial Shut In Tool Opened For Final Flow (a Tool Closed For Final Shut In (Cushion: 1,500 Hydrostatic Pressure of Cushio	9:18 AM 9:25 AM 9:56 AM 11:00 AM Feet of 00 1,500 PS	Top Choke Bottom Ch Packers 56 Water /foot x 0,433	: <u>1/8''</u> oke: <u>7/8''</u> et (4 Feet <u>= 6</u>	50p•i
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	4, 918 774-846 4, 119 848-1, 230 4, 069 1, 376 10, 114 218°F	$ \begin{array}{r} 4,861 \\ 1,004-1,012 \\ 4,119 \\ 1,050-1,308 \\ 4,083 \\ 212 \\ 10,144 \\ \end{array} $	$\begin{array}{r} 4, 431 \\ \hline 1, 091 - 1, 12 \\ 4, 230 \\ \hline 1, 221 - 1, 43 \\ 4, 173 \\ \hline 173 \\ \hline 10, 335 \end{array}$	Time 3 7 minutes 31 minutes 5 64 minutes 120 minutes
Gas to Surface in None (a Mcf/Day; in Recovery: 1, 395' water, 73' Remarks: Had a weak blow with 630' of 2 3/4'' I. D. Drill Coll 190' of 2'' I. D. Drill Coll	minutes @ minute @ <u>inuddy water</u> , hen tool pare	Mcf/Day. Mcf/Day. 1, 188' mud. which continue 073 B/Ft. = 1. 0087 B/Ft. = 4	y; in d throughout 6 Bbls mud 6 Bbls mud	minutes the test.
<u>378' of 4 1/2'' X. H. Drill Pip</u>	e :373' x 0. 0 Tota)129 B/Ft. 4. 1 11	9 Bbls mud , l Bbls mud	recovered

a a se mande an are as e state to

• •

1.1.1.17

Date: June 24, 1961	D5T. No.: 9
Lease: Rocky Mountain Arsenal	Well No. : Pressure Injection Disposal No. 1
Test Interval: 10, 336 - 10, 542	Formation: Fountain
Total Depth: 10, 542	Well Elevation: 5, 202 KB, 5, 187 GL
Testing Company: <u>Halliburton</u>	Witness: Alvin Samuels

Test Data

.

ŝ

Tool Open For Initial Flow @ Tool Clused For Initial Shut In Tool Opened For Final Flow @ Tool Clused For Final Shut In (Cushion: 1,560 Hydrostatic Pressure of Cushi	10:58 A. N (4 11:00 A. M 11:30 A. N (3 12:09 P. N Feet of on 0.416 P	1. Top Chok 1. Bottom C 1. Packers 1. Vater si/foot x 1.560	$\frac{1}{8^{11}}$ (hoke: $\frac{7}{8^{11}}$ Set $\frac{9}{10.331}$) Feet = 6	<u>49</u> psi
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	5,088 1,300 603/685 1,505 1,376 10,313 212 F	<u>Clock</u> <u>Stopped</u> 	5.206 843/843 1.389 833/848 1.634 193 10,539	Time
Gas to Surface in @Mcf/Day; in Recovery: <u>1,560' water cus</u> Remarks:	minutes @ minute @ hignplus_129	Mcf/I Mcf/Day '_mud	Day; in	minutes
<u>Tuoi opened with n</u> blow which died in 5 minu	tes.	assed after 22	minutes. Had	L a. Woak

The All Provide March Annal An

....

.

Dete: July 3, 1961	DS1, No.: 10
Lease: Rocky Mountain Arsenal	Well No : Pressure Injection Disposal No.
Test Interval: 10.517 - 10.729	Formation: Fountain
Total Depth: 10, 729	Well Elevation: 5, 202 KB, 5, 187 GL
Testing Company: Halliburton	Witness: Alvin Samuels and Bert A. Lear

Test Data

Tool Open For Initial Flow & Tool Closed For Initial Shut In Tool Opened For Final Flow & Tool Closed For Final Shut In & Cushion: <u>1,700'</u> Hydrostatic Pressure of Cushic	9:30 A. M. 9:33 A. M. 10:03 A. M. 10:53 A. M. Feet of pn 0.416 ps	I op Chok Bottom C Packers Water Water	ie: <u>3/8"</u> hoka: <u>7/8'</u> Set a <u>13,51</u> Feet <u>* 7</u>	<u>2 & 1</u> 0, 517 07Psi
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb; Bottom Hole Temperature:	<u>5, 193</u> <u>1, 043</u> <u>693/693</u> <u>1, 278</u> <u>1, 376</u> <u>10, 499</u> <u>208°</u> F	5.162 $593/597$ 1.008 $723/741$ -1.365 -212 10.531	<u>5,276</u> <u>861/861</u> <u>1/26</u> <u>850/865</u> <u>1,476</u> <u>193</u> <u>10,776</u>	1 i.me <u>3</u> <u>30</u> <u>50</u> <u>120</u>
Gas to Surface in <u>Gas to Surface in</u> <u>Mcf/Day; in</u> <u>Recovery:</u> <u>1,700' water cushi</u> <u>Remarks:</u> <u>No blow when tool</u> <u>in 15 minuter</u>	minutes (; minute @ ion plus 90! of opened. By p	Mcf/Day Mcf/Day mud 	ay; in	minutes

7 able 19

DRILLSTEM TEST REPORT

Date: July 9, 1961	DST. No.:1
Lease: Rocky Mountain Arsenal	Well No.: Pressure Injection Disposal No. 1
Test Interval: 10, 755 - 10, 962	Formation: Fountain
Total Depth: 10,962	Well Elevation: <u>5, 202 KB, 5, 187 GL</u>
Testing Company: Halliburton	Witness: Bert A, Less

Test Data

Tool Open For Initial Flow @	5:13 A. M.	lop Choke	: 3/8"	
Tool Closed For Initial Shut In	@ 5:15 A. M.	Buttom Ch	oke: 7/8"	
Tool Opened For Final Flow @	5:35 A. M.	Packers S	et @ 10, 750	10,755
Tool Closed For Final Shut In	a 6:35 A. M.			
Cushion: 2,000	Feet of	Water		
Hydrostatic Pressure of Cushi	on 0.416 p	i/foot x 2,000	Feet = 832	psi
				Time
Initial Hydrostatic Pressure:	5, 389	5,427	<u>5, 550</u>	
Initial Flow Pressure:	-	904/980	1012/1082	2
Initial Shut In Pressure:	1, 770	1,764	1.840	20
Final Flow Pressure:	970/968	952/946	1045/1045	60
Final Shut In Pressure:	1, 980	1,956	2.041	120
Pressure Bomb Number:	193	212	1. 376	
Depth of Bomb:	10, 735	10.765	10. 595	
Bottom Hole Temperature:	216°F			
			_	
Gas to Surface in	minutes @	Mcf/Da	iy; in	minutes
@ Mcf/Day; in	minute @	Mcf/Day.		
Recovery: 2,000' of water cu	shion plus 90'	of mud		
Remarks:		······		
				•
<u>Fool opened with a</u>	<u>weak blow de</u>	creasing, to dea	id in 51 minut	es,
		nan awar the activation and the age against the firms		
an and a second second second second second second second second second second second second second second seco				

E A RECOMBLISHED AND AND ADDRESS.

DRILLSTEM IEST REPORT

Date:	August 19, 196	1	DST. No.:	12
Lease:	Rocky Mountai	n Arsenal	Well No.:	Disposal Well No. 1
Test Inte	erval: 11,096-1	439 (Cs _ shoe .	Formation:	Fountain
Total De	pth: 11, 439	11.171)	Well Elevat	ion:
Testing	Company: Halli	ourton	Witness:	Howard Sells

Test Data

- -

ł

Tool Open For Initial Flow (Tool Closed For Initial Shut In Tool Opened For Final Flow (Tool Closed For Final Shut In Cushion: 3040 Hydrostatic Pressure of Cushi	7:13 A. M 7:15 A. M 7:35 A. M 8:05 A. M Feet of 0n 0.433 F	M Top Cho M Bottom M Packers M water psi/foot x304	Choke: 3/8 Choke: 7/8 Set @ 11,09 Choke: 7/8	
Initial Hydrostatic Pressure: Initial Flow Pressure: Initial Shut In Pressure: Final Flow Pressure: Final Shut In Pressure: Pressure Bomb Number: Depth of Bomb: Bottom Hole Temperature:	5018 1420/1414 2034 1418/1414 1708 221 11077 200°F	5035 1470/1465 2067 1470/1465 1756 193 1082	5027 1434/1432 2045 1434/1432 1729 212 11112	Time <u>2 min.</u> 20 min. 30 min. 62 min.
Gas to Surfece in @Mcf/Day; in Recovery: <u>3040' water cush</u> Remarks: <u>No blow when to</u> hose was plugged	minutes (k minute (k nion plus 120! ol opened. To d.	Mcf/D mud, pol was not plu	Day; in	minutes

I A FOR MEDIZE UP AT ANY TEM NO

، سیر ا

DRILLSTEM TEST REPORT

Date:	September 5, 1961	DST. No.: 13
Lease:	Rocky Mountain Arsenal	Well No : Disposal Well No. 1
Test Int	erval: 9.660-11.985(Cs. sho	 Formation: Fountain to pre-Cambriar
Total De	epth: 11.985 11,17	1) Well Elevation:
Testing	Company: <u>Halliburton</u>	Witness: <u>Alvin Samuels</u>

Test Data

Tool Open For Initial Flow @ Tool Closed For Initial Shut In Tool Opened For Final Flow @ Tool Closed For Final Shut In @	8:22 A. M. 8:25 A. M. 8:55 A. M. 9:55 A. M.	Top Chol Bottom (Packers	ke: 3/8 Choke: 7/8 Set @ 9,6	60
Cushion: None	Feet of	**		
Hydrostatic Pressure of Cushio	n - P	si/foot x -	Feet .	- p*i
Tablel Hadrostatic Prossures	404.3	4084	4001	Time
Initial Flow Pressures	910/1069	956/1117	840/1100	- 3 min
Initial Shut In Pressure:	3859	3868	3870	$\frac{30}{30}$ min.
Final Flow Pressure:	901/2552	925/2565	925/2560	60 min.
Final Shut In Pressure:	3719	3732	3730	122 min.
Pressure Bomb Number:	221	193	212	
Depth of Bomb:	9640	9645	9677	
Bottom Hole Temperature:	214 ⁰ F			
Gas to Surface in @Mcf/Day; in Recovery:Recoved 5, 330 1	minutes @ minute @ fect of drillin	- Mcf/ - Mcf/Da	Day; in y.	
Kemarks: Opened with str	ong blow deci	reasing to good	blow at end	
· · · · · · · · · · · · · · · · · · ·				

I A FU MERCE OF AND AND STAND TASK NO

DRILLSTEM TEST REPORT

Date:	September	6, 1961	DST. No.:	14	
Lease:	Rocky Mow	ntain Arsenal	Well No.:	Disposal 1	No. 1
Test Interval:	11,020-11,	985 (Car, shoe	Formation:	Fountain t	o Pre-Cambrian
Total Depth:	11,985	(0 1 1, 171)	Well Elevation:	5187 G.L.	; 5203 K.B.
Testing Company	y: Halliburton		Witness:	J. Hardy (Jarrett, Jr.
		فالتريي مترجين بالدميد بسينات وع		······	
Test Data					
Tool Open For L	nitial Flow @	**	Top Cl	noke:	3/8"
Tool Closed For	Initial Shut	ln @	Botton	n Choke:	1/4"
Tool Opened For	Final Flow	@ <u>12:54 P.</u>	M. Packe:	rs Set @ 📃	11,020
Tool Closed For	Final Shut I	n @ <u>3:30 P.</u>	<u>M</u> .	_	
Cushion: $2,00$	00 Feet of y	vater			
Hydrostatic Prei	ssure of Cus	hion 0,433 pai	/foot x 2,000 F	eet = <u>866</u> pe	11
					Time
Initial Hydrostat	ic Pressure;	5,029	5,050		-
Initial Flow Pres	ssure:	-/1,771	-/1.844	•	
Initial Shut In Pr	cssure:		NOT TAKEN		
Final Flow Pres	sure:	-/3,463	-/3,508	*	156 min.
Final Shut In Pre	essure:	4, 128	4, 155	+	93 min.
Pressure Bomb	Number:	221	193	212	
Depth of Bomb:		11,002	11,007	11,035	
Bottom Hole Ter	nperature;	102°F			مينا محميل والنازية البوسكي
	_	متعييل بقلو تهوي متباكر مكاوية			
					_
Gas to Surface 1	n	minutes @	- Mci/Day;	in	minutes
				el Deve	
e	/ Day; In	- minutes	ew	ci/Day.	
Recovery 2.0	001 water cu	shion plus 5 40	O' salt water		
Remarks: Open	ed tool at 12	:45 with no blow	w. Bypassed to	and reop	ened at
12:45 P.M. Had	no blow at b	eginning of tes	t, weak blow aft	er 10 minut	.es,
increasing to fai	r blow in 20	minutes and de	creasing to a ve	ry weak blo	w at
the end of the ter	st.				
 Clock stopped 	- no reading	8,			

E A POLUMBUS IN AND ASSOCIATES INC.

- ·

· \

SPECIAL CORE ANALYSIS RESULTS ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL

Sample No.	Depth Feet	Horisontal Permeability Millidarcys	Porosity Percent	Remarks
1	8,625	0.0	3,4	Dakota SS
2	30	0.0	4.6	41
3	60	0.0	8.6	*1
4	63	0.0	5.3	
5	9,619	0.0	3.8	Lyons SS
6	25	0.0	4.4	11
7	30	0.0	3.8	11
8	35	0.0	5.7	11
9	40	0.1	5.0	**
10	63	1.4	3.5	11
11	71	0.0	4.4	
12	85	0.0	2.7	16
13	90	0,3	3.6	.,
14	95	0.0	5.0	0
15	9,700	0.0	6.0	n
16	05	0.0	4.1	18
17	10	0.0	3.9	
18	15	0.0	3.8	11

(Selected samples analyzed by Core Laboratories, Inc.)

E A POLIME S OR AND AS WORATES IN

	Depth	Horizontal Permeability	Porosity	
Sample No.	Feet	Millidarcys	Percent	Remarks
19	9,720	0.0	6.0	Lyons SS
20	9,902	0.0	4.2	Fountain Arkosa
21	10	0.0	6.1	
22	20	0.0	1.9	11
23	24	0.0	1.0	**
24	10, 125	0.0	4.2	
25	135	0.0	3.9	
26	144	0.0	6.7	# 1
27	156	0.0	3.0	
28	392	0.0	3, 7 7 B	
29	398	0.0	2.0	
30	400	0.0	2.6	
31	596	0.0	4.7	31
32	605	0.0	3.6	**
33	623	0.0	2.9	**
34	427	0.0	6.0	11
36	027	0.0	2.3	11
34	805	0.3	3.5	11
27	811	0.0	3.0	••
37	823	0.0	1.7	11
38	830	0.0	2.9	н
39	11,048	0.0	2.1	0
40	065	0.0	4.7	11
41	071	0.0	2.1	U.
42	130	0,0	5,6	н
43	138	0,6	6.8	11
44 46	140	0.9	6.0	1
46	144	0.3	5.5	11
47	197	0.0	3.9	13
48	165	0.1	3.0	11
49	173	0.0	5.4	11
50	457	0.0	2, 2	11
51	462	0.2	5.8	
52	11, 465	0.2	4.8	11

--

•-- --

E & POLIZMBUS DE ANG ANSOCIATED INC.

ROCKY MOUNTAIN ARSENAL PRESSURE INJECTION DISPOSAL WELL LOGGING SUMMARY

Type Log	Induction-E	lectric		
Dates Run	3-15-61	5-21-61	8-1-61	9-4-61
First Reading	2,0154	9,719'	11,242'	11, 990
Last Reading	1341	2,020'	9,719	11, 166'
Footage Logged	1,881'	7,699'	1,523	8241
Total Depth (Drlr.)	2,0301	9,729'	11,225'	11, 985 '
Hole Size	12 1/4"	11''	11"	6 3/4"
Type Log	Gamma-Ra	y Neutron		
Date Run	9-4-61	9-21-61		
First Reading	11,988'	12,040'		
Last Reading	50'	11,700'		
Footage Logged	11,938'	340'		
Total Depth (Drlr.)	11,985'	12,045'		
Hole Size	6 3/4"	6 3/4"		
Type Log	Sonic			
Date Run	5-21-61	8-1-61	9-4-61	
First Reading	9,718'	11, 234'	11,988'	
Last Reading	2,0201	9,718'	11,166'	
Footage Logged	6, 698'	1,516'	822'	
Total Depth (Drlr.)	9,729'	11, 225'	11,985'	
Hole Size	11"	11"	6 3/4"	
Type Log	Microlog			
Date Run	3-15-61	5-21-61	9-4-61	
First Reading	2,006'	9,717'	11,990'	
Last Reading	134'	2,020'	11,166'	
Footage Logged	1,872'	7,6971	824'	
Total Depth (Drlr.)	2,030'	9,729'	11,985'	
Hole Size	12 1/4"	11"	6 3/4"	
Type Log	Temperatu	re Log		
Date Run	5-21-61	9-4-61		
First Reading	101	11,990'		
Last Reading	9,710'	9,500'		
Footage Logged	9,700'	2,490'		
Total Depth (Drir.)	9,729'	11,985'		
Hole Size	1111	6 3/4"		

(All data taken from heading of log. See Volume III).

Ľ

C. A. POLLMBUR DR. AND ANSPECATED UPD

an part of a constant

5
:
·
۳.
1
Ų.
2
-
Ż
2
÷
1
ç
•
4

PRESSURE INJECTION DISPOSAL WELL CASING AND HOLE SUMMARY **ROCKY MOUNTAIN ARSENAL**

	Hole Size-Ft.	Depth of Hole-Ft.*	Casing Size-Ir.	Weight Lbs. /ft.	Grade	Type	** Length of Casing-Ft.	Bottom of Cementing Shoo From G. L.
Surface String	24	139	20	94.0	H-40	ST&C	118	120
Intermediate String	17 1/2	2,031	13 3/8	54.5	J -55	STLC	485	
				84.0 54.5	H-40 J~55	ST&C ST&C	807 707	
							1.999	2, 005
Long String	11	11, 225	8 5/8	40.0	N -80	Extremeline	6, 85 0	
				40.0	N -80	LT&C	2, 037	
				4 4 . U	08- N	LTEC	2, 260 11, 147	11, 156
liner tett	6 3/4	12, 045	5 1/2	23.0	N - 80	Extremeline	964	11,960
ubing			5 1/2	23.0	N-80	Extremeline	8,998	

Depth is measured from the kelly bushing. To convert to ground level subtract 15.5 feet.

Length is measured from ground level and does not include the landing joint. ***

appurtenance other than casing included in the casing string; such as, cement shoe, Difference between length of casing and bottom of cementing shoe represents any float collars, etc. ----

Baash-Ross liner hanger.

E & PTLUMBUS UR AND ASSOCIATES INC

1

ł • i