

AD-A103 022

CONSTRUCTION ENGINEERING RESEARCH LAB (ARMY) CHAMPAIGN IL F/G 13/5  
NONDESTRUCTIVE TESTING FOR FIELD WELDS: REAL TIME WELD QUALITY --ETC(U)  
JUN 81 F KEARNEY, R WEBER, P WILLIAMS  
CERL-TR-M-295

UNCLASSIFIED

For  
8/20/82



END  
DATE  
FILMED  
9-81  
DTIC

construction  
engineering  
research  
laboratory



United States Army  
Corps of Engineers  
*Serving the Army  
Serving the Nation*


TECHNICAL REPORT M-295  
June 1981

NDT Weld Quality Monitor/Semi-Automatic Welding

**LEVEL**

NONDESTRUCTIVE TESTING FOR FIELD WELDS:  
REAL TIME WELD QUALITY MONITOR—  
FIELD TESTS

AD A103022



by  
F. Kearney  
R. Weber  
P. Williams

DTIC FILE COPY



Approved for public release; distribution unlimited.

81 8 18 1983

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

***DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR***

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CERL-TR-M-295	2. GOVT ACCESSION NO. AD-A103 022	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) NONDESTRUCTIVE TESTING FOR FIELD WELDS: REAL TIME WELD QUALITY MONITOR-FIELD TESTS		5. TYPE OF REPORT & PERIOD COVERED FINAL
7. AUTHOR(s) F. Kearney, R. Weber, P. Williams		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. Box 4005, Champaign, IL 61820		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 4A762731AT41
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE June 1981
		13. NUMBER OF PAGES 16
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Copies are obtainable from the National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  welds nondestructive testing weld quality monitor		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  This report documents the laboratory and field testing conducted on the weld quality monitor (WQM) developed by the U.S. Army Construction Engineering Research Laboratory. Results of the laboratory testing showed that all channels of the weld monitor performed satisfactorily, both independently and in conjunction with each other. Field testing showed a one-to-one correspondence between an anomalous event and WQM output. It has therefore been concluded that the WQM now meets the basic requirements for Army field operations.		

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

425277

11/2

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## FOREWORD

This investigation was conducted by the Engineering and Materials Division (EM), U.S. Army Construction Engineering Research Laboratory (CERL) for the Directorate of Military Programs, Office of the Chief of Engineers (OCE). The research was funded under Project 4A762731AT41, "Design, Construction, and Operations and Maintenance Technology for Military Facilities"; Task A, "Construction Systems Technology"; Work Unit 041, "NDT Weld Quality Monitor/Semi-Automatic Welding." The QCR is 3.07.003. Mr. E. Hunt (DAEN-MPC-E) is the OCE Technical Monitor.

Dr. R. Quattrone is Chief of EM. COL Louis J. Circeo is Commander and Director of CERL, and Dr. L. R. Shaffer is Technical Director.

Accession For	
NTIS GTRM	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/ _____	
Availability Codes	
Dist _____ and/or	
Special	
A	

## CONTENTS

DD FORM 1473	1
FOREWORD	3
1 INTRODUCTION .....	5
Background	
Objective	
Approach	
Mode of Technology Transfer	
2 LABORATORY TEST .....	6
Procedure	
Results	
3 FIELD TEST .....	6
Site Selection	
Test Operations	
Results of Operational Testing	
4 CONCLUSION	9
APPENDIX A: Factors Affecting Weld Metal Mechanical Properties	11
APPENDIX B: Circuit Description	12
APPENDIX C: Opto-electronic Weld Evaluation	13
REFERENCES	15
DISTRIBUTION	

# NONDESTRUCTIVE TESTING FOR FIELD WELDS: REAL TIME WELD QUALITY MONITOR—FIELD TESTS

## 1 INTRODUCTION

### Background

During the welding process, changes in arc voltage, travel speed, and heat input can occur without the operator's knowledge. These changes can cause defects such as porosity, slag inclusions, incomplete fusion, and undercut in the deposited weld metal (Appendix A). The cost of locating and repairing these defects can be a major portion of Army construction costs; welding inspection can constitute 25 to 40 percent of the weld fabrication cost. In addition, weld defects decrease the service life of welded joints. Consequently, it is necessary to monitor the welding parameters to detect, identify, and locate possible defects. A weld monitor with real time output would help the inspector designate suspect areas for nondestructive testing. In addition, by operating in real time, the weld monitor could be used to interrupt welding or to produce corrective signals for the welding power supply at the incipient stage of defect occurrence, thus preventing costly rework.

The need for this type of system is increasing as the Corps of Engineers becomes more involved in projects requiring welding construction, as in the MX Missile programs. To address this need, the U.S. Army Construction Engineering Research Laboratory (CERL) is conducting research to develop a field portable weld quality monitor (WQM). Essentially, the WQM is intended to provide a mechanism to merge the welding engineer's design intent with the actual field welding process.

In the initial phase of study,<sup>1</sup> several requirements were established for the device. It should:

1. Monitor the three primary signals from the weld system: arc voltage, current, and travel speed; compare them to preset limits; and alert the operator if the limits are exceeded.

2. Calculate the heat input, nugget area, and cooling rate from the three primary signals; compare

these values with preset limits; and alert the operator if these limits are exceeded.

3. Be field portable.

4. Interface easily with in-situ welding equipment.

Following development of these requirements, a prototype WQM was designed, fabricated, and tested, using input from a fully automated gas metal-arc (GMA) welding machine.<sup>2</sup> The automated GMA process was chosen to obtain close control and reproducibility of the welding variables during initial testing.

Appendix B describes the WQM circuitry.

### Objective

This study is being conducted in several phases. The first phase established requirements for and developed a prototype WQM device. A field test of this laboratory prototype WQM was conducted to evaluate its performance under field conditions.<sup>3</sup>

The objective of this phase was to conduct laboratory and field tests to determine the adequacy and field applicability to Army construction projects of the WQM design that evolved from the previous work.

Future phases of the WQM study are intended to develop (1) suitable speed sensing systems for manual welding situations, (2) specific radiometric measurement techniques involving acoustic and opto-electronics spectral analysis, and (3) digital processing features using microprocessors to facilitate the programming of the WQM.

Opto-electronic weld evaluation techniques (see Appendix C) now being developed will be used in further WQM development to provide a more powerful configuration.

### Approach

The design of the prototype WQM developed in the initial study was modified to incorporate improvements indicated during actual laboratory welding situations, improvements suggested during consultations with Government and private-sector personnel, and the results of the prior field testing. Hardware was assembled and packaged for field use.

<sup>1</sup>R. Weber, F. Kearney, and S. Joshi, *Development of Weld Quality Monitor*, Interim Report M-183 ADA027644 (U.S. Army Construction Engineering Research Laboratory [CERL], July 1976).

<sup>2</sup>Weber, et al., *Development of Weld Quality Monitor*.

<sup>3</sup>F. Kearney, *Nondestructive Testing for Field Welds: Real Time Weld Quality Monitor*, Interim Report M-251 ADA058129 (CERL, August 1978).



The unit was then installed in a welding situation that would thoroughly test all modes of its operation.

### Mode of Technology Transfer

The results of this study will impact TM 5-805-7, *Welding: Design Procedures and Inspection* (Department of the Army, 15 March 1968).

## 2 LABORATORY TEST

### Procedure

Each channel of the WQM was tested individually with a variable signal similar in current and voltage level to the signal from a welding machine. The limits for each channel were set, and the test voltages were varied to simulate changes in the primary signals. When the status lights indicated that the limit had been exceeded, the test voltage was compared to the preset limit value to check the accuracy of the comparator circuit.

After each channel had been tested successfully, the three simulated primary signals were fed into the monitor simultaneously. The limits were set again and the input voltages varied. All circuits, including the analog computer section, were checked for accuracy and reproducibility.

The monitor was then connected to the CERL welding machine to test the circuitry with actual signals. After the limits were set, a welding arc was established on a test plate.

### Results

Results of the laboratory testing showed that all channels performed satisfactorily, both independently and in conjunction with each other. The warning lights were triggered when the input signal exceeded the limits set by the reference signal, and no difficulties were encountered when the limit span was changed.

While investigating the signals of the three parameters (voltage, current, and speed), it was found that the voltage and amperage signals contained spurious noise signals. These signals were removed by (1) incorporating filters in the data channel to eliminate the peaks and smooth out the signals, thus reducing the chance of damage to components, and (2) replacing the shunt used for the amperage signal source with a Hall effect solid state transducer. (The advantage of using the transducer is that it is not directly connected to the welding cable as the shunt is; instead, it fits around the cable and measures the magnetic field generated by the current passing

through the cable.) The transducer minimized amperage transient signal problems; filters were installed in all channels for field contingencies.

The modifications indicated by the laboratory testing program were incorporated into the monitor before field testing. Figure 1 shows the system assembled for field testing.

## 3 FIELD TEST

### Site Selection

The two general types of welding operations considered for field testing were (1) shop fabrication, which uses automated welding equipment, and (2) field fabrication/repair, which generally involves manual or semi-automatic welding and is more dependent on the operator's subjective judgment.

In addition, it was decided that field tests would be more conclusive if the weld quality monitor were used in conjunction with some other form of non-destructive testing. Three sites were available that offered these combinations: (1) Flint Steel Corporation, Tulsa, OK; (2) a hydroelectric turbine shaft repair job at Ozark Powerhouse, Ozark, AK;<sup>4</sup> and (3) new construction of a wind tunnel facility at USAF Arnold Engineering Development Center, Tullahoma, TN. The Tullahoma, TN, construction the largest welding project ever undertaken by the Corps of Engineers—was chosen. Researchers felt that the time and space constraints of this field erection situation would assess the unit's adaptability most rigorously. In addition to the hardware evaluation, the field test would provide an opportunity for welding personnel from the private sector to appraise the WQM.

### Test Operations

Transporting the WQM and auxiliary equipment from CERL to the Arnold Engineering Research and Development Center (AERDC) for testing required no special handling. The equipment was set up by maintenance personnel and was ready for operation in less than 2 hours. The WQM was set up approximately 25 ft (7.5 m) from the welding station. Figure 2 shows the configuration of the welding station. Figure 3 shows the unit connected for testing.

<sup>4</sup>F. Kearney, *Nondestructive Testing for Field Welds: Real Time Weld Quality Monitor*, Interim Report M-251 ADA058129 (CERL, August 1978).



Figure 1. Field-tested weld quality monitor prototype.



Figure 2. Field welding station showing submerged arc welding unit and windbreak.




Figure 3. Weld quality monitor connected for testing.



Figure 4. Installation of the Hall effect device or welding cable.

Installation of the Hall effect current transductor (see Figure 4) involved simple disconnection and reconnection of one of the leads from the welder power unit; no hard wiring was required.

The voltage sensors were attached to the welding power supply because of the inaccessibility of the slip ring arrangement on the welding head.

The WQM was attached to a submerged arc welding system that connected flange to pipe for penetrations in the test cell. The circular operation of the welding head did not allow for the travel speed to be tested, because no slip ring was available for transmitting the voltages. Therefore, a precision voltage source was used to provide an equivalent speed signal to compute heat input and nugget area. For this mode of operation, a voltage corresponding to a particular welding speed was input to the analog computer module to compute heat input and nugget area (Equations A1 and A3, Appendix A). For example, if the analog module were scaled for 1 volt = 1 in. min, then a 6-volt signal from the precision voltage source would be input for a welding speed of 6 in. min.

Figure 5 shows a typical voltage and current time trace obtained from the WQM. These signals were taken at the output of the signal conditioners before filtering for inputting to the comparators. As shown in Figure 5, the signal is not distorted, and shows the response of the sensors to the voltage and current variations that occur in the arc. Because the parameter data content is preserved in the transduction and conditioning process, the data can be used in several ways from simple alarms to adaptive control systems.

The unit used in this test incorporated an "event" recorder output device, which provided a "blip" mark

on a time baseline to indicate which parameter deviated from the preset limits. It also indicated the direction of error, i.e., high or low excursion. Figure 6 shows a representative trace obtained during the field test.

### Results of Operational Testing

Since the accuracy of the parameter measurement systems and the computational sections was verified in the laboratory, the primary field test criteria were the unit's response and correlation to deviant conditions. The welding operations were visually observed by CERL personnel for each flaw-inducing occurrence, and the event recorder was appropriately annotated at each incident (see Figure 6). The flaw-inducing conditions that occurred were typical of field welds. Three hundred feet of data tape were obtained in the test, with 700 "out of limit" events recorded. Subsequent analysis of the event recorder traces showed a one-to-one correspondence between an anomalous event and the WQM output. Furthermore, the cross-correlation between measured signals, voltage, current, and speed and computed parameters (heat input and nugget area) showed good agreement; e.g., a deviant current value indicated an error in the heat input and nugget area channels.

The correlation of WQM output with flaw-inducing welding events, as determined by this test, indicates that the basic requirements for an Army-fieldable unit have been demonstrated.

## 4 CONCLUSION

Based on the laboratory and field tests, the WQM design is adequate and has field applicability.





Figure 5. Voltage current trace obtained from the WQM for shaft repair weld.



**Figure 6.** Typical trace from the event recorder of the weld quality monitor.

## APPENDIX A: FACTORS AFFECTING WELD METAL MECHANICAL PROPERTIES

### Defects

Changes in arc voltage, travel speed, and heat input during welding can cause several types of defects in the deposited weld metal.

**Porosity** is a void or gas pocket trapped in solidifying weld metal. The reduced solubility of the gas in the metal caused by the decreasing temperature forces the gases out of solution. The gases are originally introduced either by poor shielding, which entrains air, or by chemical reactions in the molten weld metal. Stick electrodes with too long an arc as a result of excessive arc voltage can reduce shielding effectiveness and introduce gas into the metal.

**Slag inclusion** is the entrapment of an oxide or other nonmetallic material under the weld bead. The major source of slag is the coatings on stick electrodes. This defect is related to heat input.

**Incomplete fusion** is the failure of adjacent layers of the weld metal or weld base plate to fuse. Incomplete fusion may result when the adjacent metal is not heated to the melting point because of insufficient heat input.

An **undercut** is a groove melted into the baseplate at the toe of the weld and is caused primarily when **travel speed** is excessive in relation to the welding current.

In addition to the defects caused by improper control, the heat generated by the welding process can change the base metal in the following ways:

1. Grain coarsening
2. Softening (annealing effects)
3. Hardening (phase precipitation or transformation)
4. Segregation of constituents
5. Grain boundary melting
6. Loss of ductility
7. Loss of toughness
8. Residual stresses causing distortion or cracking.

The type of change depends on the chemical composition of the base metal, the electrode, and the heat history of the base plate.

In the two commonly used field welding processes—shielded metal-arc (stick electrodes) and gas metal-arc (bare-wire)—the source of heat for melting the materials is an electric arc. Control of the arc parameters will control the amount of heat generated, the length of time the weld metal is at an elevated temperature, and the cooling rate of the weld zone.

### Base Metal Microstructure

The cooling cycle after a weld pass determines the microstructure of the weld metal and the heat-affected zone. With fast cooling rates, some steels become very hard because of a martensitic transformation. If the cooling rate is sufficiently slow, the metal may be more ductile and the structure ferritic and pearlitic. The type of steel generally determines which of these structures is most desirable. For low-carbon and low-alloy steels, the pearlitic structure is desirable, while for high-strength quenched and tempered steel, the martensitic structure is desirable.

Martensite is undesirable in low-carbon and low-alloy steels designed for yield strengths of less than 80 ksi (552 MN/m<sup>2</sup>) because of its hardness and low solubility for hydrogen at ambient temperatures. This combination of characteristics increases the likelihood of hydrogen cracking in the joint. Use of low-hydrogen stick electrodes and the gas metal-arc welding system reduces this tendency toward hydrogen-induced cracking.

### Cooling Rate Control

Controlling the cooling rate is essential to prevent undesirable microstructure in the weld and heat-affected base plate. A mathematical combination of arc voltage, current, and travel speed known as heat input (HI) has been used to control cooling rate for many years. The equation for calculating heat input is

$$HI \text{ (J in.)} = \frac{\text{voltage} \times \text{amperage} \times 60}{\text{travel speed (in./min.)}} \quad [\text{Eq A1}]$$

The normal maximum has been 55,000 to 60,000 J in. (21 654 to 23 622 J cm) for the field processes mentioned above. Another means of controlling cooling rate has been preheat treatment. Dorschu<sup>3</sup>

<sup>3</sup>K. E. Dorschu, "Control of Cooling Rates in Steel Weld Metal," *Welding Research Supplement* (February 1968).

has shown that the relationship between heat input, preheat temperature, and cooling rate is:

$$CR = \frac{m(T - T_o)^2}{HI} + c \quad [\text{Eq A2}]$$

where CR = cooling rate

T = test temperature, 1000° F (538°C)

T<sub>o</sub> = preheat temperature

m,c = constants

HI = heat input (kJ/in.)

Eq A2 indicates that the higher the preheat temperature and heat input, the slower the cooling rate.

Shultz and Jackson<sup>6</sup> have shown that the cross-sectional area of the weld bead is a useful indicator of weld metal mechanical properties and that a relationship exists between the area and cooling rate. They also found that arc voltage has little or no effect on the nugget area and cooling rate. The relationship that Shultz and Jackson have developed for nugget area, arc current, and speed is:

$$na = 122 \times 10^{-7} \frac{i^{1.55}}{S^{.0903}} \quad [\text{Eq A3}]$$

where na = nugget area (sq in.)

i = arc amperage

S = arc travel speed (in./min).

<sup>6</sup>B. L. Shultz and C. E. Jackson, "Influence of Weld Bead Area on Weld Metal Mechanical Properties," *Welding Research Supplement* (January 1973).

## APPENDIX B: CIRCUIT DESCRIPTION

Figure B1, a block diagram of the weld quality monitor, shows the input signals from the welding arc. These signals are conditioned to standard values and sent to the comparator module, which compares the input signals with a set of limit signals. If the input signals are too high or too low, the appropriate alarm is triggered. The input signals are also transmitted to the analog computer module for calculating of the heat input, cooling rate, and nugget area. The calculated values are then compared to reference signals, and the appropriate alarm is triggered if needed.

<sup>7</sup>R. A. Weber and C. E. Jackson, *Review of Weldability of Construction Materials*, Interim Report M-168 ADA027383 (CERL, January 1976).




Figure B1. Block diagram of weld quality monitor, showing input signals from the welding arc.

## APPENDIX C: OPTO-ELECTRONIC WELD EVALUATION (OWE)

Direct quantitative measurements of certain parameters of welds in process are not possible for several reasons:

1. The high weld temperatures destroy sensors near the weld area.
2. Contacting sensors introduce a discontinuity into the weld process, causing data uncertainty.
3. In the case of manual welding, subjectiveness peculiar to the welder is indeterminant and variable.

Some indirect measurements such as thermocouples are used, but these techniques exhibit time lags, averaging effects, and other factors that decrease the validity and reproducibility of the information.

Because of this inability to measure directly and instantaneously the quantities relevant to a satisfactory weld, a research program was implemented to produce noncontacting instrumentation techniques. These techniques, which use opto-electronic technology, can be used in the field to directly monitor pertinent weld measurements such as cooling rate, weld speed, and heat input. The measurements can then be used as input to the CERL weld quality monitor.

Opto-electronic technology is used to detect the amplitude and wave length of radiation emitted by the welding arc. A photodetector (or an array of photodetectors), which is the primary sensor, has appropriate circuitry to provide the required output information.

### Physics of the Welding Arc

The welding arc can be thought of as a gaseous conductor which changes electrical energy into heat. The welding arc can be defined as a particular group of electrical discharges that are formed and sustained by the development of a gaseous conductive medium. The current carriers for the gaseous medium are produced thermally and by field emission.

The arc current is carried by the *plasma*, the ionized state of a gas composed of nearly equal numbers of electrons and ions. Mixed with the plasma are other states of matter, including molten metals, slags, vapors, neutral and excited gaseous

atoms, and molecules. Measured values of welding arc temperatures normally range between 5000 and 30,000° K, depending on the nature of the plasma and the current conducted by it.

The amount and character of spectral radiation emitted by arcs depend fundamentally on the atomic mass and chemical structure of the gas, the temperature, and the pressure. Spectral analysis of arc radiation shows bands, lines, and continua. Analysis of radiation from organic-type covered electrodes shows molecular bands caused by the existence of vibrational and rotational states, as well as line and continuum emissions from excited and ionized states. The inert gas arcs radiate predominantly by atomic excitation and ionization. As the energy input to arcs increases, higher states of ionization occur, which causes radiation to be emanated from higher energy levels.

In this study, the fundamental method used to develop noncontacting sensors was separation and quantification of segments of weld spectra that could be correlated to specific weld parameters. Figure C1 shows the visible spectrum and a portion of the infrared spectrum emanating from the argon-shielded gas tungsten arc.

### Optical Electronic Transduction Methods

Two methods of segmenting or partitioning weld spectra are (1) selection of photosensors having a spectral response only in the sections of the spectrum to be measured, and (2) use of optical filters to limit the wave length of radiation impinging on the photodetector. For this work, the latter method was used. Figure C2 illustrates the radiation physics and adaptation of optical electronics in the application to welds. Various combinations of commercial photographic filters made it possible to segment the arc spectra into about five bands; this provided adequate resolution to quantify weld flaws, as well as being an extremely flexible procedure. Two examples will briefly illustrate this process.

An analysis of the metallurgical phase diagrams associated with weld nugget area suggested that the normal (acceptable) weld spectrum and a deviant spectrum characterizing a flaw would have wave lengths greater than 700 nanometers. To implement the "front end" of the sensor system, a Wratten-type 89b filter was selected and coupled with a type TIL-63 phototransistor. This provided a sensor system with a photometric "window" of about 700 to 1050 nanometers; thus, the desired spectra were detected while extraneous spectra were attenuated.






Figure C1. Spectrum of the argon-shielded gas tungsten arc.




Figure C2. Opto-electronic system and application to welds.

A fiber optic light pipe was the transmission device between the arc and the phototransistor. Weld arc instability or "sputtering" is one of the most common flaw-inducing conditions encountered in the field. Laboratory testing with radiometers indicated that spectral lines emitted by an unstable arc were very dense in the visible range; a ratton 57 cylinder placed in the front end to quantify this phenomenon showed notable results. Another flaw-inducing condition detected by this device was magnetic arc blow.

Current opto-electronics research is concentrated on developing rugged, high-temperature optical systems that will be durable enough for field use. The results are very encouraging; the fiber optic bundles used in these devices are 1/16 to 1/8 in. (1.6 to 3.2 mm) in diameter and have a pass band in the required range of .4 to 1.9 nm.

#### **Large Scale Integration (LSI) and the WQM**

The primary factor that makes the WQM a practical tool is the confluence of welding engineering and large-scale integration electronics technology. Measurements and recordings of voltage, current, and more recently, acoustic emission data are becoming quite standard. The CERL WQM is innovative and unique in that it uses this data for *in-situ*, *real-time* analysis for *continuous* and *instantaneous* quality assurance.

#### **OWE Status 1980**

In CERL's prototype opto-electronic system configured for field use, the spectrum is segmented and quantified by a grooved spectrograph and linear photodiode array. A high-temperature fiber optic bundle is routed along the flexible cable hose assembly to the welding gun so as not to interfere with normal welding operations. This versatility makes the system applicable to manual welding, which is the principal method used by the Army. CERL has successfully tested this configuration, and has found that it can distinctly characterize flaws caused by slag

inclusions, loss of flux, loss of the argon cover gas, and magnetic arc blow. Figure C3 shows the arc spectral change for an argon gas cover system when the gas flow is interrupted.

#### **REFERENCES**

- Dorsch, K. E., "Control of Cooling Rates in Steel Weld Metal," *Welding Research Supplement* (February 1968).
- Hackforth, H. L., *Infrared Radiation* (McGraw-Hill Book Co., 1960).
- Kearney, F., *Nondestructive Testing for Field Welds: Real Time Weld Quality Monitor*, Interim Report M-251 ADA058129 (CERL, August 1978).
- Schultz, B. L., and C. E. Jackson, "Influence of Weld Bead Area on Weld Metal Mechanical Properties," *Welding Research Supplement* (January 1973).
- Sharpe, R. W., *Research Techniques in Nondestructive Testing* (Academic Press, 1970).
- Simon, R. E., *Electro-Optics Handbook* (RCA, 1974).
- Weber, R. A., and C. E. Jackson, *Review of Weldability of Construction Materials*, Interim Report M-183 ADA027383 (CERL, January 1976).
- Weber, R., F. Kearney, and S. Joshi, *Development of a Weld Quality Monitor*, Interim Report M-183 ADA027644 (CERL, July 1976).
- Welding Handbook* (American Welding Society, 1976).





Figure C3. Spectra obtained from CERL weld quality monitor are spectral analyzer.

# CERL DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: DAEN-ASI-L (2)  
ATTN: DAEN-CCP  
ATTN: DAEN-CW  
ATTN: DAEN-CWE  
ATTN: DAEN-CMM-R  
ATTN: DAEN-CMO  
ATTN: DAEN-CMP  
ATTN: DAEN-MP  
ATTN: DAEN-MPC  
ATTN: DAEN-MPE  
ATTN: DAEN-MPO  
ATTN: DAEN-MPR-A  
ATTN: DAEN-RD  
ATTN: DAEN-RDC  
ATTN: DAEN-RDM  
ATTN: DAEN-RM  
ATTN: DAEN-ZCE  
ATTN: DAEN-ZCI  
ATTN: DAEN-ZCM

## US Army Engineer Districts

ATTN: Library  
Alaska  
Al Batin  
Albuquerque  
Baltimore  
Buffalo  
Charleston  
Chicago  
Detroit  
Far East  
Fort Worth  
Galveston  
Huntington  
Jacksonville  
Japan  
Kansas City  
Little Rock  
Los Angeles  
Louisville  
Memphis  
Mobile  
Nashville  
New Orleans  
New York  
Norfolk  
Omaha  
Philadelphia  
Pittsburgh  
Portland  
Riyadh  
Rock Island  
Sacramento  
San Francisco  
Savannah  
Seattle  
St. Louis  
St. Paul  
Tulsa  
Vicksburg  
Walla Walla  
Wilmington

## US Army Engineer Divisions

ATTN: Library  
Europe  
Huntsville  
Lower Mississippi Valley  
Middle East  
Middle East (Rear)  
Missouri River  
New England  
North Atlantic  
North Central  
North Pacific  
Ohio River  
Pacific Ocean  
South Atlantic  
South Pacific  
Southwestern

## Waterways Experiment Station

ATTN: Library

## Cold Regions Research Engineering Lab

ATTN: Library

## US Government Printing Office

Receiving Section/Depository Copies (2)

## Defense Technical Information Center

ATTN: DDA (12)

## Engineering Societies Library

New York, NY

FESA, ATTN: Library

ETL, ATTN: Library

Engr. Studies Center, ATTN: Library

Inst. for Water Res., ATTN: Library

Army Instl. and Major Activities (CONUS)

DARCOM - Dir., Inst., & Svcs.

ATTN: Facilities Engineer

ARRADCOM

Aberdeen Proving Ground

Army Matls. and Mechanics Res. Ctr.

Corpus Christi Army Depot

Harry Diamond Laboratories

Dugway Proving Ground

Jefferson Proving Ground

Fort Monmouth

Letterkenny Army Depot

Natick Research and Dev. Ctr.

New Cumberland Army Depot

Pueblo Army Depot

Red River Army Depot

Redstone Arsenal

Rock Island Arsenal

Savanna Army Depot

Sharpe Army Depot

Seneca Army Depot

Tobyhanna Army Depot

Tooele Army Depot

Watervliet Arsenal

Yuma Proving Ground

White Sands Missile Range

## FORSCOM

FORSCOM Engineer, ATTN: AFEN-FE

ATTN: Facilities Engineers

Fort Buchanan

Fort Bragg

Fort Campbell

Fort Carson

Fort Devens

Fort Drum

Fort Hood

Fort Indiantown Gap

Fort Irwin

Fort Sam Houston

Fort Lewis

Fort McCoy

Fort McPherson

Fort George G. Meade

Fort Ord

Fort Polk

Fort Richardson

Fort Riley

Presidio of San Francisco

Fort Sheridan

Fort Stewart

Fort Wainwright

Vancouver Bks.

## TRADOC

HQ, TRADOC, ATTN: ATEN-FE

ATTN: Facilities Engineer

Fort Belvoir

Fort Benning

Fort Bliss

Carlisle Barracks

Fort Chaffee

Fort Dix

Fort Eustis

Fort Gordon

Fort Hamilton

Fort Benjamin Harrison

Fort Jackson

Fort Knox

Fort Leavenworth

Fort Lee

Fort McClellan

Fort Monroe

Fort Rucker

Fort Sill

Fort Leonard Wood

INSCOM - Ch, Instl. Div.

ATTN: Facilities Engineer

Vint Hill Farms Station

Arlington Hall Station

## WESTCOM

ATTN: Facilities Engineer

Fort Shafter

## MDW

ATTN: Facilities Engineer

Cameron Station

Fort Lesley J. McNair

Fort Myer

## MSC

HQ USAHSC, ATTN: HSLO-F

ATTN: Facilities Engineer

Fitzsimons Army Medical Center

Walter Reed Army Medical Center

## USACC

ATTN: Facilities Engineer

Fort Huachuca

Fort Ritchie

## MTMC

HQ, ATTN: MTMC-SA

ATTN: Facilities Engineer

Oakland Army Base

Bayonne MOT

Sunny Point MOT

## US Military Academy

ATTN: Facilities Engineer

ATTN: Dept of Geography &

Computer Science

## USAES, Fort Belvoir, VA

ATTN: ATZA-DTE-EM

ATTN: ATZA-DTE-SU

ATTN: Engr. Library

Chief Inst. Div., I&SA, Rock Island.

USA ARRCOM, ATTN: Dir., Instl & Svc

TARCOM, Fac. Div.

TECOM, ATTN: DRSTE-LG-F

TSARCOM, ATTN: STSAS-F

NARAD COM, ATTN: DRDNA-F

AMRC, ATTN: DRXMR-WE

HQ, XVIII Airborne Corps and

Ft. Bragg

ATTN: AFZA-FE-EE

HQ, 7th Army Training Command

ATTN: AETTG-DEH (5)

HQ USAREUR and 7th Army

ODCS/Engineer

ATTN: AEAEN-EH (4)

## V Corps

ATTN: AETVDEH (5)

## VII Corps

ATTN: AETSDEH (5)

21st Support Command

ATTN: AEREM (5)

## US Army Berlin

ATTN: AEBA-EN (2)

## US Army Southern European Task Force

ATTN: AESE-ENG (5)

## US Army Installation Support Activity

Europe

ATTN: AEUES-RP

## 8th USA, Korea

ATTN: EAFE

Cdr, Fac Engr Act (8)

AFE, Yongsan Area

AFE, 2D Inf Div

AFE, Area II Spt Det

AFE, Cp Humphreys

AFE, Pusan

AFE, Taegu

DLA ATTN: DLA-WI

## USA Japan (USARJ)

Ch, FE Div, AJEN-FE

Fac Engr (Honshu)

Fac Engr (Okinawa)

## ROK/US Combined Forces Command

ATTN: EUSA-HMC-CFC/Engr

## 416th Engineer Command

ATTN: Facilities Engineering

## Norton AFB

ATTN: AFRCE-MX/DEE

# EMM Team Distribution

Director of Facilities Engineering  
Miami, FL 34004

West Point, NY 10996  
ATTN: Dept of Mechanics  
ATTN: Library

Chief of Engineers  
ATTN: DAEN-MPO-U  
ATTN: DAEN-MPZ-A  
ATTN: DAEN-MPR  
ATTN: DAEN-RDL

Fort Belvoir, VA 22060  
ATTN: Kingman Bldg, Library  
ATTN: Canadian Liaison Officer (2)

Fort Leavenworth, KS 66027  
ATTN: ATZLCA-SA

Fort McPherson, GA 30330  
ATTN: AFEN-CD

Fort Monroe, VA 23651  
ATTN: ATEN-AD (3)

USA-WES  
ATTN: C/Structures

6th US Army  
ATTN: AFKC-EN

7th US Army  
ATTN: AETTM-HRD-EHD

US Army Science & Technology  
Center - Far East Office

US Army Engineer District  
Philadelphia  
ATTN: Chief, NAPEN-D  
Baltimore  
ATTN: Chief, Engr Div  
Norfolk  
ATTN: Chief, NAOEN-D  
Wilmington  
ATTN: Chief, SAWEN-D  
Charleston  
ATTN: Chief, Engr Div  
Savannah  
ATTN: Chief, SASAS-L  
Jacksonville  
ATTN: Const Div  
Mobile  
ATTN: Chief, SAMEN-C  
ATTN: Chief, SAMEN-D  
Memphis  
ATTN: Chief, LMED-DM  
Vicksburg  
ATTN: Chief, Engr Div  
Louisville  
ATTN: Chief, Engr Div  
St. Paul  
ATTN: Chief, ED-D  
Omaha  
ATTN: Chief, Engr Div  
New Orleans  
ATTN: Chief, LMED-DG  
Little Rock  
ATTN: Chief, Engr Div  
San Francisco  
ATTN: Chief, Engr Div  
Sacramento  
ATTN: Chief, SPKED-D  
Portland  
ATTN: Chief, DB-6  
Seattle  
ATTN: Chief, NPSCO  
Walla Walla  
ATTN: Chief, Engr Div  
Alaska  
ATTN: Chief, NPASA-R

US Army Engineer Division  
New England  
ATTN: Chief, NEDED-T  
North Atlantic  
ATTN: Chief, NADEN-T  
South Atlantic  
ATTN: Chief, SADEN-TS  
Huntsville  
ATTN: Chief, HNDED-CS  
ATTN: Chief, HNDED-SR  
Ohio River  
ATTN: Chief, Engr Div  
Southwestern  
ATTN: SWDED-TM  
Pacific Ocean  
ATTN: Chief, Engr Div  
North Pacific  
ATTN: Chief, Engr Div

AFESC/PRT  
Tyndall AFB, FL 32403

Tinker AFB, OK 73145  
2854 ABG/DEEE

Patrick AFB, FL 32925  
ATTN: XRQ

McClellan AFB, CA 95652  
2852 APG/OE

Naval Air Systems Command  
ATTN: Library  
WASH DC 20360

Naval Facilities Engr Command  
ATTN: Code 04  
Alexandria, VA 22332

Port Hueneme, CA 93043  
ATTN: Library (Code L08A)

Washington, DC  
ATTN: Transportation Research Board  
ATTN: Library of Congress (2)  
ATTN: Dept of Transportation Library

National Defense Headquarters  
Director General of Construction  
Ottawa, Ontario  
Canada KIA OK2

Airports and Construction Services Dir  
Technical Information Reference Centre  
Ottawa, Ontario  
Canada KIA ON8

Kearney, Frank W.

Nondestructive testing for field welds : real time weld quality monitor, field tests/by F. Kearney, R. Weber, P. Williams. -- Champaign, IL : Construction Engineering Research Laboratory ; Springfield, VA : available from NTIS, 1981.

16 p. (Technical report ; M-295)

1. Nondestructive testing. 2. Welded joints -- testing. I. Weber, Robert A. II. Williams, Peter. III. Title. IV. Series : U. S. Army. Construction Engineering Research Laboratory. Technical Report ; M-295

