

AD-A170 408

INSTALLATION RESTORATION PROGRAM
PHASE II--CONFIRMATION/QUANTIFICATION
STAGE 1

FINAL REPORT
FOR
MAXWELL AIR FORCE BASE
MONTGOMERY, ALABAMA 36112

HEADQUARTERS AIR UNIVERSITY
MAXWELL AIR FORCE BASE
MONTGOMERY, ALABAMA 36112

JUNE 1986

PREPARED BY
ENVIRONMENTAL SCIENCE AND ENGINEERING, INC.
P.O. BOX ESE
GAINESVILLE, FLORIDA 32602-3052

U.S.A.F. CONTRACT NO. F33615-84-D-4401, DELIVERY ORDER NO. 6
ESE PROJECT NO. 84-607

Approved for Public Release;
Distribution is Unlimited

USAFOEHL TECHNICAL PROGRAM MANAGERS
DENNIS D. BROWNLEY, MAJ., USAF
GARY L. WOODRUM, 2Lt, USAF

USAF OCCUPATIONAL AND ENVIRONMENTAL HEALTH LABORATORY (USAFOEHL)
TECHNICAL SERVICES DIVISION (TS)
BROOKS AIR FORCE BASE, TEXAS 78235-5501

DTIC FILE COPY

86 7 31 033



NOTICE

This report has been prepared for the United States Air Force by Environmental Science and Engineering, Inc., for the purpose of aiding in the Implementation of the Air Force Installation Restoration Program. It is not an endorsement of any product. The views expressed herein are those of the contractor and do not necessarily reflect the official views of the publishing agency, the United States Air Force, or the Department of Defense.

Copies of this report may be purchased from:

National Technical Information Service
5285 Port Royal Road
Springfield, Virginia 22161

Federal Government agencies and their contractors registered with Defense Technical Information Center should direct requests for copies of this report to:

Defense Technical Information Center
Cameron Station
Alexandria, Virginia 22314

Accession For	
NTIS CRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

REPORT DOCUMENTATION PAGE

1a. REPORT SECURITY CLASSIFICATION Unclassified		1b. RESTRICTIVE MARKINGS None									
2a. SECURITY CLASSIFICATION AUTHORITY N/A		3. DISTRIBUTION/AVAILABILITY OF REPORT Approved for public release; distribution is unlimited									
2b. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A		5. MONITORING ORGANIZATION REPORT NUMBER(S) N/A									
4. PERFORMING ORGANIZATION REPORT NUMBER(S) N/A		7a. NAME OF MONITORING ORGANIZATION USAF OEH/TS									
6a. NAME OF PERFORMING ORGANIZATION Environmental Science and Engineering, Inc.		7b. ADDRESS (City, State and ZIP Code) Brooks Air Force Base, TX 78235-5501									
6b. OFFICE SYMBOL (If applicable) N/A		9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER F33615-84-D-4401, Task Order 6									
6c. ADDRESS (City, State and ZIP Code) P.O. Box ESE Gainesville, FL 32602-3053		10. SOURCE OF FUNDING NOS. <table border="1"><tr><td>PROGRAM ELEMENT NO.</td><td>PROJECT NO.</td><td>TASK NO.</td><td>WORK UNIT NO.</td></tr><tr><td>N/A</td><td>N/A</td><td>N/A</td><td>N/A</td></tr></table>		PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT NO.	N/A	N/A	N/A	N/A
PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT NO.								
N/A	N/A	N/A	N/A								
8a. NAME OF FUNDING/SPONSORING ORGANIZATION USAF OEH/TS		8b. OFFICE SYMBOL (If applicable) TS									
8c. ADDRESS (City, State and ZIP Code) Brooks Air Force Base, TX 78235-5501		11. TITLE (Include Security Classification) Installation Restoration Program Phase II--Confirmation/Quantification Stage I									
12. PERSONAL AUTHOR(S) J.D. Bonds, G.K. Foster, A.P. Hubbard, M.J. Geden, M.T. Park, J.H. Chalkley, and L.D. Tournade											
13a. TYPE OF REPORT Final		13b. TIME COVERED FROM 10/84 TO 6/86									
14. DATE OF REPORT (Yr., Mo., Day) June 23, 1986		15. PAGE COUNT									
16. SUPPLEMENTARY NOTATION N/A											
17. COSATI CODES <table border="1"><tr><td>FIELD</td><td>GROUP</td><td>SUB. GR.</td></tr><tr><td></td><td></td><td></td></tr></table>		FIELD	GROUP	SUB. GR.				18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number) Installation Restoration Program, Phase IIa studies, contamination			
FIELD	GROUP	SUB. GR.									
19. ABSTRACT (Continue on reverse if necessary and identify by block number) <p>-A Phase II, Stage 1 survey was conducted at Maxwell Air Force Base (MAFB), Ala., to confirm the existence of potential contaminants at former disposal and storage sites identified by a Phase I record search. Ten sites were investigated including six landfill or disposal areas, two fire protection training areas, a drum storage area, and surface water drainage areas.</p> <p>Geophysical surveys were conducted at four disposal areas, and 20 ground water monitor wells were installed. Surface waters, ground waters, and sediments were sampled and analyzed for various screening parameters including total organic carbon (TOC), total organic halogens (TOX), phenols, oil and grease, pH, specific conductance, and total dissolved solids (TDS). The samples were also analyzed for specific parameters including cyanide (CN), cadmium (Cd), chromium (Cr), copper (Cu), zinc (Zn), lead (Pb), selenium (Se), silver (Ag), barium (Ba), mercury (Hg), arsenic (As), sulfate (SO₄), nitrate (NO₃), iron (Fe), endrin, lindane,</p>											
20. DISTRIBUTION/AVAILABILITY OF ABSTRACT UNCLASSIFIED/UNLIMITED <input checked="" type="checkbox"/> SAME AS RPT. <input type="checkbox"/> DTIC USERS <input type="checkbox"/>		21. ABSTRACT SECURITY CLASSIFICATION Unclassified									
22a. NAME OF RESPONSIBLE INDIVIDUAL Maj. Dennis D. Brownley/2LT Gary L. Woodrum		22b. TELEPHONE NUMBER (Include Area Code) 512/536-2158									
		22c. OFFICE SYMBOL USAF OEH/TS									

DD FORM 1473, 83 APR

EDITION OF 1 JAN 73 IS OBSOLETE.

Unclassified
SECURITY CLASSIFICATION OF THIS PAGE

19. Abstract (Continued)

methoxychlor, toxaphene, 2,4-dichlorophenoxyacetic acid (2,4-D), and 2,4,5-trichlorophenoxyacetic acid (2,4,5-TP).


Results of the analysis indicate low-level contamination at several study sites. Additional testing is recommended to identify and quantify halogenated organic species and to further evaluate the extent of contamination of the shallow aquifer.

PREFACE

This report describes the Phase II, Stage 1 survey program conducted at Maxwell Air Force Base (MAFB), Ala., under Air Force Contract F33615-84-D-4401, Task Order 6. The work was performed during the period of October 1984 to June 1986 by personnel from Environmental Science and Engineering, Inc. (ESE), Gainesville, Fla. Law Engineering, Inc. provided the well drilling services for the contract. The contract was monitored by Major Dennis D. Brownley and 2Lt Gary L. Woodrum, Technical Services Division, United States Air Force Occupational Environmental Health Laboratory (OEHL), Brooks Air Force Base, San Antonio, Texas. Key contractor personnel included John D. Bonds, Ph.D. (Project Manager), A.P. Hubbard, B.S.E. (Project Engineer), M.T. Park, M.S. (Chemical Analysis Supervisor), John J. Mousa, Ph.D. (Quality Assurance Supervisor), G.K. Foster, B.S. (Site Geologist), M.J. Geden, B.S. (Sampling Team Leader), J.H. Chalkley, M.S. (Geophysics), and L.D. Tournade (Document Coordination).

The ESE project team wishes to express its gratitude for the assistance provided by Major Dennis D. Brownley (OEHL), 2Lt Gary L. Woodrum (OEHL), Captain Mark D. Knuth (MAFB Bioenvironmental Engineer), and various MAFB civil engineering and bioenvironmental engineering staff members in the preparation of this report.

Approved:



Jack D. Doolittle
Vice President
Installation Restoration Program Manager

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
PREFACE	i
TABLE OF CONTENTS	ii
LIST OF TABLES	v
LIST OF FIGURES	vii
SUMMARY	x
 1.0 INTRODUCTION	 1-1
1.1 <u>PROGRAM BACKGROUND</u>	1-1
1.2 <u>INSTALLATION DESCRIPTION AND HISTORY</u>	1-2
1.3 <u>DISPOSAL/STORAGE SITES INVESTIGATED</u>	1-5
1.4 <u>PROJECT STAFF</u>	1-5
 2.0 ENVIRONMENTAL SETTING	 2-1
2.1 <u>TOPOGRAPHY</u>	2-1
2.2 <u>METEOROLOGY</u>	2-3
2.3 <u>REGIONAL GEOLOGY AND HYDROGEOLOGY</u>	2-3
2.4 <u>LOCATIONS OF ONSITE AND OFFSITE WELLS</u>	2-8
2.5 <u>HISTORIC GROUND WATER AND SURFACE WATER MONITORING</u>	2-8
2.6 <u>DESCRIPTIONS OF DISPOSAL AND STORAGE AREAS</u>	2-9
2.6.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS	2-10
2.6.2 SITE 2--SURFACE DRAINAGE SYSTEM	2-10
2.6.3 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3	2-13
2.6.4 SITE 4--FPTA NO. 1	2-15
2.6.5 SITE 5--LANDFILLS 4, 5, AND 6	2-15
2.6.6 SITE 6--C.E. DRUM STORAGE AREA	2-19
2.6.7 SITE 7--LANDFILL NO. 2	2-19
2.7 <u>SUMMARY OF ENVIRONMENTAL SETTING</u>	2-19
 3.0 FIELD PROGRAM	 3-1
3.1 <u>DEVELOPMENT OF FIELD PROGRAM</u>	3-1
3.2 <u>METHODOLOGY</u>	3-8
3.2.1 GEOPHYSICAL SURVEY TECHNIQUES	3-8
3.2.2 PIEZOMETER INSTALLATION AND MONITORING	3-9
3.2.3 MONITOR WELL INSTALLATION AND SAMPLING	3-11
3.2.4 DRILLING LOGS AND BORING PROCEDURES	3-19
3.2.5 SURFACE WATER SAMPLING	3-21
3.2.6 STREAM SEDIMENT SAMPLING	3-22

TABLE OF CONTENTS
(Continued, Page 2 of 3)

<u>Section</u>	<u>Page</u>
3.3 <u>IMPLEMENTATION OF FIELD PROGRAM</u>	3-23
3.3.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS	3-23
3.3.2 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3	3-30
3.3.3 SITE 4--FPTA NO. 1	3-37
3.3.4 SITE 5--LANDFILLS 4, 5, AND 6	3-43
3.3.5 SITE 6--C.E. DRUM STORAGE AREA	3-49
3.3.6 SITE 7--LANDFILL NO. 2	3-53
4.0 RESULTS AND SIGNIFICANCE OF FINDINGS	4-1
4.1 <u>RELEVANT WATER QUALITY CRITERIA AND STANDARDS</u>	4-1
4.2 <u>ANALYTICAL RESULTS</u>	4-6
4.3 <u>GENERAL DISCUSSION</u>	4-6
4.3.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS	4-13
4.3.2 SITE 2--SURFACE DRAINAGE SYSTEM FOR MAFB	4-16
4.3.3 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3	4-24
4.3.4 SITE 4--FPTA NO. 1	4-26
4.3.5 SITE 5--LANDFILLS 4, 5, AND 6	4-26
4.3.6 SITE 6--C.E. DRUM STORAGE AREA	4-31
4.3.7 SITE 7--LANDFILL NO. 2	4-34
5.0 ALTERNATIVE MEASURES	5-1
6.0 CONCLUSIONS AND RECOMMENDATIONS	6-1
6.1 <u>CONCLUSIONS</u>	6-1
6.2 <u>RECOMMENDATIONS</u>	6-2
6.2.1 SITE 2--SURFACE WATER DRAINAGE SYSTEM	6-3
6.2.2 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3	6-5
6.2.3 SITE 5--LANDFILLS 4, 5, AND 6	6-5

TABLE OF CONTENTS
(Continued, Page 3 of 3)

<u>Section</u>	<u>Page</u>
APPENDICES	
APPENDIX A--GLOSSARY OF TERMINOLOGY, ABBREVIATIONS, AND ACRONYMS	A-1
APPENDIX B--RESUMES OF KEY PROJECT PERSONNEL	B-1
APPENDIX C--SCOPE OF WORK AS OUTLINED BY OEHL	C-1
APPENDIX D--QUALITY ASSURANCE PLAN	D-1
APPENDIX E--SAFETY PLAN	E-1
APPENDIX F--PIEZOMETERS, MONITOR WELLS, SURFACE WATER, AND SEDIMENT SAMPLING LOCATION DESIGNATIONS	F-1
APPENDIX G--HORIZONTAL LOCATIONS AND ELEVATIONS OF MONITOR WELLS	G-1
APPENDIX H--GEOPHYSICAL TRACING FOR SITES 1, 3, 5, AND 7	H-1
APPENDIX I--PIEZOMETER BORING LOGS	I-1
APPENDIX J--MONITOR WELL WATER LEVELS	J-1
APPENDIX K--MONITORING WELL BORING LOGS	K-1
APPENDIX L--WELL DEVELOPMENT LOGS	L-1
APPENDIX M--MONITOR WELL, SURFACE WATER, AND SEDIMENT SAMPLING LOGS	M-1
APPENDIX N--CHAIN-OF-CUSTODY DOCUMENTATION	N-1
APPENDIX O--ADDITIONAL QA/QC DATA FOR CHEMICAL ANALYSES	O-1
APPENDIX P--ANALYTICAL RESULTS FOR GROUNDWATERS AND SURFACE WATERS	P-1
APPENDIX Q--REFERENCES	Q-1

LIST OF TABLES

<u>Table</u>		<u>Page</u>
S-1	Summary of Sampling and Analyses for MAFB, Phase II, Stage 1 Survey	xii
S-2	Summary of Sampling and Analyses Recommended for MAFB, Phase II, Stage 2 Survey	xxii
1.3-1	Summary of Ten Sites of Potential Environmental Contamination Identified at MAFB, Ala.	1-6
1.3-2	Prioritized Site Listing	1-9
2.2-1	Climatological Data	2-4
3.1-1	MAFB Phase II, Stage 1 Monitoring and Analysis	3-2
3.3-1	Site 1 Piezometers	3-26
3.3-2	Site 1 Monitor Wells	3-27
3.3-3	List of Analytical Parameters for MAFB Sampling	3-31
3.3-4	Site 3 Piezometers	3-33
3.3-5	Site 3 Monitor Wells	3-35
3.3-6	Site 4 Piezometers	3-39
3.3-7	Site 4 Monitor Wells	3-41
3.3-8	Site 5 Piezometers	3-45
3.3-9	Site 5 Monitor Wells	3-47
3.3-10	Site 6 Piezometers	3-51
3.3-11	Site 6 Monitor Wells	3-52
3.3-12	Site 7 Piezometers	3-57
3.3-13	Site 7 Monitor Wells	3-58
4.1-1	Relevant Maximum Contaminant Levels (MCLs) for Drinking Water	4-2

LIST OF TABLES
(Continued, Page 2 of 2)

<u>Table</u>		<u>Page</u>
4.1-2	Relevant EPA Water Quality Criteria	4-5
4.2-1	Analytical Methods, Detection Limits, and Representative Quality Assurance/Quality Control Data	4-7
4.2-2	Representative Quality Control Data--RCRA EP Toxicity Metals	4-9
4.3-1	Analytical Results for Ground Water Samples from Site 1	4-15
4.3-2	Analytical Results for Surface Water Samples from Site 2	4-18
4.3-3	Analytical Results for MAFB Sediment Samples	4-21
4.3-4	Analytical Results for Ground Water Samples from Site 3	4-24
4.3-5	Analytical Results for Ground Water Samples from Site 4	4-28
4.3-6	Analytical Results for Ground Water Samples from Site 5	4-30
4.3-7	Analytical Results for Ground Water Samples from Site 6	4-33
4.3-8	Analytical Results for Ground Water Samples from Site 7	4-36
6.2-1	Summary of Sampling and Analyses Recommended for MAFB, Phase II, Stage 2 Survey	6-4

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
S-1	Location Map of Sites Where Confirmation Studies Were Performed	xi
S-2	Locations of Piezometers and Monitor Wells at Site 1, Electroplating Waste Disposal Areas	xiii
S-3	Surface Water and Sediment Sample Collection Locations for Site 2	xiv
S-4	Locations of Piezometers and Monitor Wells at Site 3, FPTA No. 2, and Landfill No. 3	xv
S-5	Locations of Piezometers and Monitor Wells at Site 4, FPTA No. 1	xvi
S-6	Locations of Piezometers and Monitor Wells at Site 5, Landfills 4, 5, and 6	xvii
S-7	Locations of Piezometers and Monitor Wells at Site 6, C.E. Drum Storage Area	xix
S-8	Locations of Piezometers and Monitor Wells at Site 7, Landfill No. 2	xx
1.1-1	Location Map	1-3
1.3-1	Potential Sources of Environmental Contamination	1-8
2.1-1	Maxwell Air Force Base Installation Drainage	2-2
2.6-1	Site 1--Electroplating Waste Disposal Areas	2-11
2.6-2	Site 2--Surface Drainage Systems	2-12
2.6-3	Site 3--FPTA No. 2 and Landfill No. 3	2-14
2.6-4	Site 4--FPTA No. 1	2-16
2.6-5	Site 5--Landfills 4, 5, and 6	2-17
2.6-6	Site 6--C.E. Drum Storage Area	2-20
2.6-7	Site 7--Landfill No. 2	2-21

LIST OF FIGURES
(Continued, Page 2 of 3)

<u>Figure</u>		<u>Page</u>
3.2-1	Typical Monitor Well Construction	3-14
3.3-1	Locations of Piezometers and Monitor Wells at Site 1, Electroplating Waste Disposal Areas	3-25
3.3-2	Geologic Cross-Section of Site 1, Electroplating Waste Disposal Areas	3-29
3.3-3	Locations of Piezometers and Monitor Wells at Site 3, FPTA No. 2, and Landfill No. 3	3-32
3.3-4	Geologic Cross-Section of Site 3, FPTA No. 2, and Landfill No. 3	3-36
3.3-5	Locations of Piezometers and Monitor Wells at Site 4, FPTA No. 1	3-38
3.3-6	Geologic Cross-Section of Site 4, FPTA No. 1	3-42
3.3-7	Locations of Piezometers and Monitor Wells at Site 5, Landfills 4, 5, and 6	3-44
3.3-8	Geologic Cross-Section of Site 5, Landfills 4, 5, and 6	3-48
3.3-9	Locations of Piezometers and Monitor Wells at Site 6, C.E. Drum Storage Area	3-50
3.3-10	Geologic Cross-Section of Site 6, C.E. Drum Storage Area	3-54
3.3-11	Locations of Piezometers and Monitor Wells at Site 7, Landfill No. 2	3-55
3.3-12	Geologic Cross-Section of Site 7, Landfill No. 2	3-60
4.3-1	Detectable Concentrations of Various Analytes in Ground Waters at Site 1, Electroplating Waste Disposal Areas	4-14
4.3-2	Detectable Concentrations of Various Analytes in Surface Waters on MAFB, Site 2	4-17

LIST OF FIGURES
(Continued, Page 3 of 3)


<u>Figure</u>		<u>Page</u>
4.3-3	Stream Sediment Sampling Locations, Site 2	4-22
4.3-4	Detectable Concentrations of Various Analytes in Ground Waters at Site 3, FPTA No. 2, and Landfill No. 3	4-25
4.3-5	Detectable Concentrations of Various Analytes in Ground Waters at Site 4, FPTA No. 1	4-27
4.3-6	Detectable Concentrations of Various Analytes in Ground Waters at Site 5, Landfills 4, 5, and 6	4-29
4.3-7	Detectable Concentrations of Various Analytes in Ground Waters at Site 6, C.E. Drum Storage Area	4-32
4.3-8	Detectable Concentrations of Various Analytes in Ground Waters at Site 7, Landfill No. 2	4-35
6.2-1	Locations of Present and Proposed Surface Water Sampling Sites on MAFB	6-3
6.2-2	Locations of Present and Proposed Sediment Sampling Sites on MAFB	6-6

SUMMARY

The Phase II, Stage 1 Installation Restoration Program (IRP) Confirmation/Quantification Survey for Maxwell Air Force Base (MAFB) investigated 10 disposal, storage, and surface water drainage sites. These included five former and present landfills, two Fire Practice Training Areas (FPTA), one former drum storage area, the base surface water drainage system, and a former disposal site for electroplating wastes. The 10 sites were consolidated into 7 sites or study areas for the actual field survey and investigation (see Fig. S-1).

A geophysical survey was performed at four sites to locate buried items, delineate the boundaries of the burial areas, and determine if any leachate plumes were evident in the shallow ground water. Piezometers were installed at each site to determine ground water gradients in order to specify the locations of upgradient and downgradient wells. Twenty shallow monitoring wells were installed and developed at six study site locations on MAFB. Wells, surface waters, and sediments were sampled and analyzed as indicated in Table S-1.

Results from the screening tests [total organic halides (TOX), total organic carbon (TOC), pH, specific conductance, and dissolved solids], and the specific tests (metals, pesticides, phenols, cyanides, nitrate, sulfate, oil and grease, etc.) were used to determine if contamination existed in the shallow aquifer. Contaminants exceeding National Interim Primary Drinking Water Regulations (NIPDWR), National Secondary Drinking Water Regulations (NSDWR), and U.S. Environmental Protection Agency (EPA) criteria for the protection of freshwater aquatic life and human health were found at only a few locations.




**INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base**

**Figure S-1
LOCATION MAP OF SITES WHERE CONFIRMATION STUDIES
WERE PERFORMED**

Table S-1. Summary of Sampling and Analyses for MAFB Phase II, Stage 1 Survey

Site No.	Site Description	Sample Locations	Sample Analyses
1	Electroplating Waste Disposal Areas (see Fig. S-2)	4 monitor wells	pH, specific conductance, total dissolved solids (TDS), phenols cyanides (CN), total organic carbon (TOC), zinc (Zn), nickel (Ni), copper (Cu), chromium (Cr), and cadmium (Cd)
2	Maxwell Surface Water Drainage System (see Fig. S-3)	4 surface water and 11 sediment samples from drainage ditches on MAFB	pH, specific conductance, arsenic (As), Cd, Cr, mercury (Hg), Ni, Cu (sediments only), lead (Pb), Zn, TDS, CN, phenols, oil and grease, total organic halides (TOX), TOC, specific conductivity, moisture, and extractable organics
3	Fire Protection Training Area No. 2 and Landfill No. 3 (see Fig. S-4)	3 monitor wells	pH, As, barium (Ba), Cd, Cu, Cr, iron (Fe), Hg, Ni, Pb, silver (Ag), Zn, nitrogen (NO ₃), sulfate (SO ₄), TDS, CN, phenols, oil and grease, TOX, TOC, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP, fluoride (F), selenium (Se), and specific conductance
4	Fire Protection Training Area No. 1 (see Fig. S-5)	3 monitor wells	pH, As, Ba, Cd, Cu, Cr, Fe, Hg, Ni, Pb, Ag, Zn, NO ₃ , SO ₄ , TDS, CN, phenols, oil and grease, TOX, TOC, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP, F, Se, and specific conductance
5	Landfills 4, 5, and 6 (see Fig. S-6)	4 monitor wells installed during Phase II; 1 existing monitor well	pH, As, Ba, Cd, Cu, Cr, Fe, Hg, Ni, Pb, Ag, Zn, NO ₃ , SO ₄ , TDS, CN, phenols, oil and grease, TOX, TOC, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP, F, Se, and specific conductance



**INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base**






Figure S-3
SURFACE WATER AND SEDIMENT SAMPLE
COLLECTION LOCATIONS FOR SITE 2










Table S-1. Summary of Sampling and Analyses for MAFB Phase II, Stage 1 Survey (Continued, Page 2 of 2)

Site No.	Site Description	Sample Locations	Sample Analyses
6	Civil Engineer (C.E.) Drum Storage Area (see Fig. S-7)	3 monitor wells	pH, As, Ba, Cd, Cu, Cr, Fe, Hg, Ni, Pb, Ag, Zn, NO ₃ , SO ₄ , TDS, CN, phenols, oil and grease, TOL, TOC, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP, F, Se, and specific conductance
7	Landfill No. 2 (see Fig. S-8)	3 monitor wells	pH, As, Ba, Cd, Cu, Cr, Fe, Hg, Ni, Pb, Ag, Zn, NO ₃ , SO ₄ , TDS, CN, phenols, oil and grease, TOL, TOC, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP, F, Se, and specific conductance

Source: ESE, 1985.





Based on the results of this study, recommendations were made to:

1. Discontinue monitoring at Sites 1, 4, 6, and 7;
2. Continue the sediment sampling program;
3. Expand the surface water monitoring program at Site 2 by three monitor stations; and
4. Perform additional analyses at Sites 2, 3, and 5.

A summary of recommendations, including sampling locations and parameters to be analyzed, is presented in Table S-2.

Table S-2. Summary of Sampling and Analyses Recommended for WAFB, Phase II, Stage 2 Survey

Site	Sampling Location	pH	Specific Conductance	Analyses										Rationale for Recommendation
				Specific Conductance	Acid Base/Neutral	Pesticides	Organics	Metals	Trace Metals	Heavy Metals	Organics	Metals	Trace Metals	
2	Surface water sampling locations S 2-1, S 2-2, S 2-3, and S 2-4; new sites S 2-5, S 2-6, and S 2-7	X	X	X	X	X	X	X	X	X	X	X	X	TIC found at low levels. Need gas chromatography/mass spectroscopy (GC/MS) to determine identities and concentrations of organic and chlorinated organics. Need to confirm Hg and As and determine source, if possible. Analyze for metals and cyanide since electroplating was performed in past.
3	Sediment sampling locations S 2-1 through S 2-11; new sites upstream of S 2-1 (1 site), downstream of S 2-8 (1 site), and downstream of S 2-11 (1 site)													TIC found at low levels. Need GC/MS to determine identities and concentrations of organics. Need to confirm Hg and Pb and determine source, if possible. Analyze for metals and cyanide since electroplating was performed in past.
5	HF 3-1, 3-2, and 3-3	X	X	X	X	X	X	X	X	X	X	X	X	Pesticides, TIC, TSC, and low-level metals present. Need to confirm concentrations and identify the organics.
5	HF 5-1, 5-2, 5-3, 5-4, and the other existing well, HF-5, if accessible	X	X	X	X	X	X	X	X	X	X	X	X	Pesticides, TIC, TSC, and low-level metals present. Need to confirm concentrations and identify the organics.

Source: ESR, 1985.

1.0 INTRODUCTION

1.1 PROGRAM BACKGROUND

This report describes Phase II of the Installation Restoration Program (IRP) for Maxwell Air Force Base (MAFB), Alabama. Phase II pertains to the confirmation and quantification of suspected contamination at former hazardous materials/waste storage or disposal sites.

Due to its primary mission, the U.S. Air Force (USAF) has long been engaged in operations dealing with toxic and hazardous materials. Federal, state, and local governments have developed strict regulations to require that disposers identify the locations and contents of disposal sites and take action to eliminate the hazards in an environmentally responsible manner. The primary Federal legislation governing disposal of hazardous waste is the Resource Conservation and Recovery Act (RCRA) of 1976, as amended. Under Sec. 6003 of the Act, Federal agencies are directed to assist the U.S. Environmental Protection Agency (EPA), and, under Sec. 3012, state agencies are required to inventory past disposal sites and make the information available to the requesting agencies. To assure compliance with these hazardous waste regulations, the Department of Defense (DOD) developed the IRP. The current DOD IRP policy is contained in Defense Environmental Quality Program Policy Memorandum (DEQPPM) 81-5, dated Dec. 11, 1981, and implemented by USAF message dated Jan. 21, 1982. DEQPPM 81-5 reissued and amplified all previous directives and memoranda on the IRP. DOD policy is to identify and fully evaluate suspected problems associated with past hazardous contamination and to control hazards to health and welfare that resulted from these past operations. The IRP is the basis for response actions on USAF installations under the provisions of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as clarified by Executive Order 12316.

The IRP has been developed as a 4-phase program:

Phase I--Initial Assessment/Records Search

Phase II--Confirmation and Quantification

Phase III--Technology Base Development

Phase IV--Operations/Remedial Actions

Phase I, Initial Assessment/Records Search, is designed to identify possible hazardous-waste-contaminated sites and potential problems that may result in contaminant migration from the installation.


Engineering-Science (ES) was retained by the Air Force Engineering and Services Center (AFESC) to conduct the Phase I investigation at MAFB (see Fig. 1.1-1 for location). This records search was completed in January 1984.

Phase II of the IRP addresses the confirmation and quantification of the extent and magnitude of contaminant migration from sites identified in Phase I. Phase II, Stage 1 consists of a preliminary survey to confirm or rule out the presence and/or migration of contaminants. If the Phase II, Stage 1 work confirms the presence and/or migration of contaminants, then Phase II, Stage 2 field work would be conducted to determine the extent and magnitude of the contaminant migration.

Environmental Science and Engineering, Inc. (ESE) conducted a contamination assessment under Phase II of the DOD IRP of former waste disposal and/or storage sites at MAFB. The study was performed in response to the findings of the IRP Phase I Records Search, which indicated the potential for contaminant migration from the sites. The contamination assessment consisted of a Phase II, Stage 1 preliminary survey to confirm or refute the presence of contaminants in environmental media at the site.

1.2 INSTALLATION DESCRIPTION AND HISTORY

MAFB is situated in Montgomery County, Ala. (Fig. 1.1-1). The installation is bordered by the city of Montgomery, Ala., on the east



and south and by the Alabama River on the north. Mixed residential and industrial land uses predominate south and west of MAFB. A public housing project and the central business district of Montgomery are east of the base. An extensive undeveloped floodplain lies north of the base along the Alabama River.

MAFB's primary mission is to support the Air University (AU). The 3800 Air Base Wing operates and maintains MAFB and provides logistic support and base services for AU organizations.

The installation was originally a flight school begun in 1910 by Orville Wright with five student fliers and one mechanic. Wright's venture lasted less than a year, and the area which is now MAFB had little use until the outbreak of World War I. In 1918, the U.S. Army leased 300 acres and established the Montgomery Air Intermediate Depot primarily to provide engine and aircraft repair and maintenance support for six other airfields in the southeast. The leased acreage for the base was purchased in 1920. In November 1922, the Montgomery Air Intermediate Depot was renamed "Maxwell Field." Construction of the first permanent buildings on the base was completed in May 1928.

In June 1931, the first troops from the Air Corps Tactical School arrived at Maxwell Field as part of the transfer of that facility from Langley Field, Va. In 1940, the facilities were used by the Southeast Air Corps Training Center to train officers and pilots. Both the Air Corps Tactical School and the Southeast Air Corps Training Center served as flight-training operations rather than maintenance and repair organizations.

In 1946, AU was established and MAFB became the home of the Air Force's center for professional military education. AU provides instruction for more than 500,000 students annually. Active flying on MAFB is limited to a tenant reserve unit.

1.3 DISPOSAL/STORAGE SITES INVESTIGATED

In Phase I, 10 former and active disposal and storage sites were evaluated using the USAF Hazard Assessment Rating Methodology (HARM) system. The sites selected for HARM evaluation were found to have received contaminants and/or to have the potential for contaminant migration. Information regarding the sites is summarized in Table 1.3-1, and approximate locations of these sites are shown in Fig. 1.3-1. Each site was evaluated according to the HARM system with respect to waste characteristics, contamination pathways, receptors, and waste management practices. The 10 sites were consolidated into 7 sites based on location. A numerical score was assigned to each site, and all the sites were ranked as shown in Table 1.3-2. This ranking served as the basis for the development of a Phase II contamination survey work plan.

1.4 PROJECT STAFF

Key personnel participating in the MAFB survey are listed below. Resumes of the project staff are included as App. B.

J.D. Bonds, Ph.D., Chemist:	Project Manager
J.J. Mousa, Ph.D., Chemist:	Quality Assurance (QA) Supervisor
G.K. Foster, B.S., Geologist:	Site Geologist
M.J. Geden, B.S., Geologist:	Sampling Team Leader
J.H. Chalkley, M.S., Environmental Management:	Sampling Team, Geophysics
M.T. Park, M.S., Chemist:	Chemical Analysis Supervisor
A.P. Hubbard, B.S.E.	Project Engineer
L.D. Tournade, B.A., Document Coordinator:	Document Production Supervisor

Table 1.3-1. Summary of Ten Sites of Potential Environmental Contamination Identified at MFB, Ala.


Site No.	Site Name	Period of Operation	Activity
1	Electroplating Waste Disposal Areas	Late 1940s to Mid 1960s	20 to 40 drums of spent electroplating solutions, containing copper, chromium, nickel, cadmium, and cyanide were reportedly disposed of at this site in trenches 8 to 10 ft deep at two locations
2	Surface Drainage System	1940s to Early 1970s	Received considerable quantities of industrial waste solutions, including paint booth water, paint strippers, electroplating rinse water, penetrant oil, dilute acid and caustic, and steam rack corrosion removal component
3	FPTA No. 2	1962 to Present	Prior to 1978, leakage of waste oils, fuels, and solvents from drums and the unlined pit went into soils; after 1978, leakage and spillage from 25 to 35 drums normally stored on the site went into soil and the water-table aquifer
4	FPTA No. 1	1940s to 1962	Waste oils, fuels, and solvents were stored at the site for use in training; these items were spilled on the soils or leached through the bottom of an unlined pit into the soils
5	Landfill No. 4	1956 to Early 1970s	Received household garbage, base trash, and industrial nonliquid wastes (paints, paint sludges, pesticide containers, and solvent sludges)
6	C.E. Drum Storage Area	Mid-1970s to Present	Used as drum storage area for 80 to 90 drums of paints, solvents, and oil/water mixtures
7	Landfill No. 5	Early 1970s to 1974	Received household garbage, base trash, and nonliquid industrial wastes (paints, paint sludges, pesticide containers) during period of operation
8	Landfill No. 6	1974 to Present	Same as Landfill No. 5

Table 1.3-1. Summary of Ten Sites of Potential Environmental Contamination Identified at MAFB, Ala. (Continued, Page 2 of 2)

Site No.	Site Name	Period of Operation	Activity
9	Landfill No. 2	Early 1940s to 1951	Same as Landfill No. 5
10	Landfill No. 3	1951 to 1956	Same as Landfill No. 5

Notes: FFTA = Fire Protection Training Area.
C.E. = Civil Engineer.

Sources: ES, 1984.
ESE, 1985.



INSTALLATION RESTORATION PROGRAM Maxwell Air Force Base

**Figure 1.3-1
POTENTIAL SOURCES OF ENVIRONMENTAL
CONTAMINATION**

Table 1.3-2. Prioritized Site Listing

Priority	Site(s)
1	Electroplating Waste Disposal Areas
2	Surface Drainage System
3	FPTA No. 2 and Landfill No. 3
4	FPTA No. 1
5	Landfills 4, 5, and 6
6	C.E. Drum Storage Area
7	Landfill No. 2

Source: ESE, 1985.

2.0 ENVIRONMENTAL SETTING


2.1 TOPOGRAPHY

MAFB is situated within the Fall Line Hills subdivision of the Gulf Coastal Plain physiographic province. This physiographic division is a narrow band of hilly uplands along the inner margin of the coastal plain, just south of the Fall Line. The Fall Line is the arbitrary boundary separating the Piedmont from the Coastal Plain. The Fall Line Hills subdivision is characterized by frequent rolling hills, extensive surficial dissection, nearly level plains, and mature streams.

The topography of the main sections of MAFB is generally level, with an average elevation of 168 feet (ft) [National Geodetic Vertical Datum (NGVD), 1929]. The only major variation is created by the alluvial terraces of the Alabama River which form the northwestern boundary of MAFB. Maximum local relief at MAFB is approximately 35 ft along the banks of the Alabama River.

MAFB is drained by overland flow to diversion structures and then to area streams, all of which terminate in the Alabama River. The western section of MAFB drains to West End Ditch, which flows around the southwestern installation boundary and joins the Alabama River about 2 miles northwest of the base. The northern, eastern, and southern sections of MAFB drain to local streams and ponds which have outlets to the Alabama River.

Flooding occurs on the northern, western, and southern portions of MAFB (ES, 1984). The 100-year flood limits portrayed in Fig. 2.1-1 are based on the City of Montgomery Flood Insurance Rate Map, published by the Federal Emergency Management Agency (1974), and roughly correspond to the record flood limits (1962) depicted in installation documents.



2.2 METEOROLOGY

Temperature, precipitation, and snowfall data furnished by Det. 9, 24th Weather Squadron are summarized in Table 2.2-1. The mean annual precipitation (all forms) at MAFB is 52.1 inches, and the maximum 24-hour rainfall event is 6.3 inches.

2.3 REGIONAL GEOLOGY AND HYDROGEOLOGY

(Note: Much of this information is excerpted from the Phase I records search conducted by ES in 1984.) Geologic units ranging in age from Upper Cretaceous to Recent have been identified in the Coastal Plain deposits of Montgomery County. These units are typically unconsolidated materials consisting of gravel, sand, silt, clay, chalk, glauconite, and lignite, reposing on a Precambrian crystalline basement complex.

The Coastal Plain sediments form a southerly dipping wedge, with a point of origin at the Fall Line, which extends along most of the Atlantic coast. In Alabama, it extends through Elmore County, north of Montgomery. At the Fall Line, sediment thickness is no more than a few feet; however, at the Gulf of Mexico, these same strata attain thicknesses measured in thousands of feet. The thickness of all unconsolidated deposits at MAFB is 1,008 ft, as measured in U.S. Geological Survey (USGS) Test Well G-33, located approximately 1,000 ft west of the installation near U.S. Route 31. Individual geologic units within the Coastal Plain sediments tend to dip seaward at a shallow rate and thicken substantially. They are not known to be faulted or otherwise disrupted in the Montgomery area; however, past cycles of erosion/deposition may have created significant local variations in unit characters or lithology.

The surficial geology of MAFB is dominated by Quaternary Terrace deposits which occur at ground surface and are approximately 40 ft thick at the USGS Test Well. The terrace materials consist principally of sands, silts, and clays in their upper extent and coarsen with depth (i.e., coarse sands and gravel are prevalent). The lithology of the terrace deposits at MAFB is reported as medium-grained to coarse, poorly sorted sand, sandy clay, and clay (upper extent of the formation).

Table 2.2-1. Climatological Data

Month	Temperature (°F)					Precipitation (inches)					Snowfall (inches)			
	Mean			Daily	Extreme		Monthly			24 Hours	Monthly		24 Hours	
	Max.	Min.	Max.		Min.	Mean	Max.	Min.						
January	57	39	48	82	5	4.2	10.6	0.9	3.3	T	6	3		
February	61	41	51	84	12	4.5	8.5	1.6	5.1	T	2	2		
March	69	48	58	88	20	6.3	14.0	2.3	3.8	T	T	T		
April	77	56	67	93	30	4.5	11.2	1.1	4.3	T	T	T		
May	84	63	74	98	43	4.0	12.9	0.5	4.0	0	0	0		
June	90	70	80	104	52	4.3	11.8	0.5	6.3	0	0	0		
July	91	73	82	105	61	5.6	10.7	2.5	4.7	0	0	0		
August	91	72	82	103	60	4.1	15.4	1.0	5.6	0	0	0		
September	86	67	77	101	42	3.8	8.4	0.1	5.4	0	0	0		
October	78	55	67	96	32	1.8	8.3	T	3.3	T	T	T		
November	66	45	56	87	14	3.5	19.3	0.1	5.9	T	T	T		
December	59	40	49	84	15	5.5	10.1	T	3.6	T	T	T		
Annual	76	56	66	105	5	52.1	19.3	T	6.3	T	6	3		

Notes: Period of Record: 1937-1981.

T = Trace.

°F = degrees Fahrenheit.

Sources: Det. 9, 24th Weather Squadron, 1983.

ESE, 1985.

ES, 1984.

Terrace Deposits are highly variable across the upper extent of MAFB. Alluvial materials (chiefly poorly graded, fine sands and silts) characterize the surficial geology of lowland areas, floodplains, and stream channels. These are recently deposited materials, associated with the development of area streams. The alluvium in the Alabama River Valley is reported to be as much as 90 ft thick.

The major hydrogeologic units identified in the Phase I study as relevant to the assessment of MAFB are Recent Alluvium, Pleistocene Terrace Deposits, Eutaw Formation, Gordo Formation, and Coker Formation. These units are described in the following paragraphs and grouped according to the typical depths (shallow or deep) at which they may be encountered.

The two shallow hydrogeologic units present in the study area are Recent Alluvium and Pleistocene Terrace Deposits. The alluvium consists principally of sand, silt, and clay deposited by the meandering streams (especially the Alabama River) of the area. The alluvial deposits reach a maximum thickness of 40 ft in the study area, adjacent to the Alabama River. Ground water occurs in the alluvium under water-table (unconfined) conditions. Recharge occurs by precipitation falling on any exposed portions of the unit and from the terrace deposits at higher elevations. Flow proceeds downslope with discharge directed to the Alabama River and the underlying Eutaw Formation, with which the alluvium is hydraulically connected. Much of the unit is at or below the level of the Alabama River because of recent increases in the normal pool elevation of the river. The alluvial aquifer is present along the northeastern boundary of MAFB, usually at elevations below 140 ft (NGVD, 1929) within the river channel. Water levels within the unit are usually close to ground surface.

The ubiquitous Terrace Deposits form a significant shallow aquifer which is present beneath MAFB. The unit consists of gravel, sand, silt, and clay deposited by meandering streams (ancestral Alabama River) during

Pleistocene time. The unit occurs at ground surface and is approximately 40 to 50 ft thick across the study area. Ground water usually occurs in the unit under water-table (unconfined) conditions. Recharge enters the unit primarily as infiltrating precipitation. MAFB is situated in the recharge area of this aquifer. Terrace Deposit ground water levels at MAFB range from 2 ft below ground surface to 10 ft below ground surface. Ground water flow within the terrace materials is probably a subdued replica of the topographic surface. Water flow proceeds from higher elevations to lower elevations. Discharge is directed to area surface streams and the underlying Eutaw Formation.

The deep hydrogeologic units present in the study area are, in order of occurrence, the Eutaw, Gordo, and Coker Formations of Upper Cretaceous age. The Eutaw Formation is a regional aquifer which has been extensively developed in the study area. The Eutaw crops out as an arcuate belt 2 miles wide and 11 miles long in northern Montgomery County, just east of MAFB. It extends beneath the installations, where it is unconformably overlain by approximately 40 ft of Pleistocene Terrace Deposits. It is estimated to be 150 ft thick at MAFB (Knowles et al., 1963). Ground water occurs in the Eutaw under water-table conditions in the outcrop area and under artesian conditions elsewhere. The Eutaw is recharged by infiltration of precipitation in its outcrop zones and by downward leakage from Alluvial and Pleistocene Terrace Deposits. The magnitude of leakage from overlying strata is not known. Natural (prepumping) ground water flow in the Eutaw was most likely downdip to the south from the principal recharge zones. Extensive water resource development has altered this scenario locally; large-scale drawdowns in the potentiometric surface of the unit probably direct flow toward major pumping centers such as municipal wells. Eutaw Formation artesian water levels were reported to be approximately 150 ft mean sea level (MSL) at MAFB. The depth to water in the Eutaw is 10 ft below land surface in the well at MAFB Bldg. 1109. At MAFB, ground water flow in the Eutaw was postulated to be east toward municipal wells located

north of Montgomery. The Eutaw is capable of producing large supplies [1,500 gallons per minute (gpm)] of water to wells.

The Gordo Formation is also considered to be a regional source of water but is not as prolific as the Eutaw or underlying Coker. It is exposed in Autauga and Elmore Counties, north of Montgomery. In the study area, it is unconformably overlain by the Eutaw Formation. It generally occurs at a depth of 200 to 400 ft below land surface at the Montgomery west well field, located 2 miles southwest of MAFB. In Montgomery, the Gordo ranges in thickness from 250 to 300 ft and contains water under artesian conditions. Recharge occurs by infiltration of precipitation in the outcrop area (Autauga and Elmore Counties) and by leakage from overlying units. In 1885, some Gordo wells installed just north of Montgomery flowed naturally under artesian pressures. By 1953, such flow had ceased, and water levels declined to about 100 ft below land surface due to the extensive use of the Gordo as a water supply. No reliable, current data are available to describe ground water flow in the Gordo with respect to MAFB; however, the Gordo is capable of furnishing water at 200 gpm.

The Coker Formation is a prolific aquifer of regional importance. The unit crops out north of Montgomery in Autauga and Elmore Counties and dips gently south. It unconformably overlies crystalline basement rocks and is, in turn, unconformably overlain by the Gordo Formation. At MAFB, the Coker occurs at an approximate depth of 500 ft below land surface and is estimated (interpolated from plate 3, Powell et al., 1957) to be 600 ft thick at a test well just west of the installation. The unit is recharged primarily by infiltrating precipitation in its outcrop area. Reliable, current data describing ground water levels and flow directions are not available. It is known that past extensive development of the aquifer and recent use of surface water to offset ground water overdevelopment at first created large-scale lowering of Coker water levels and then permitted some recovery. The Coker is known to be an excellent water source, capable of producing 1,000 gpm of water (Engineering Science, 1984). The period over which this yield could be sustained was not provided in the Records Search report.

2.4 LOCATIONS OF ONSITE AND OFFSITE WELLS

Formerly, MAFB obtained water resources from wells located on the installation. Three inactive wells are located on MAFB. At present, the installation obtains water from the municipal system of Montgomery. The City of Montgomery obtains its water supplies from ground and surface water sources. The surface water intake is located on the Tallapoosa River, near the confluence of the Coosa and Alabama Rivers. The municipal well system consists of 45 wells located west and north of the urban area. Six of the wells are located near the southeast corner of MAFB. Typically, city wells located west of the urban area are screened into both the Gordo and Coker Formations. Some wells located north of the city were reported to be screened into the Eutaw. It is unlikely that the terrace and alluvial deposits are used as water sources in the study area.

2.5 HISTORIC GROUND WATER AND SURFACE WATER MONITORING

Prior to the Phase II study, a ground water monitoring system consisting of three shallow wells was used to observe terrace-deposit water quality near the active landfill. Available information indicated water levels adjacent to the landfill ranged from 7 ft below land surface to 35 ft below ground, respectively. Moreover, the Phase I report mentioned that seepage into the open landfill trench was occurring at the time of the onsite Records Search survey.

Discharge to the West End Ditch is expected based on the assumption that terrace-deposit ground water flow follows topographic influences.

The Phase I report indicated that water resources obtained from the Eutaw, Gordo, and Coker Formations are generally very good. Wells screened into the upper extent of the Eutaw may encounter excessive amounts of iron locally. The Phase I study also indicated that the quality of water obtained from city wells is good; however, specific water quality analysis results for these wells were not available.

Base personnel routinely collect and analyze water samples from various surface drainage locations on MAFB in accordance with National Pollutant Discharge Elimination System (NPDES) Permit No. AL0003727 and AL0003719, respectively. The parameters for each sampling point have included flow, pH, oil and grease, suspended solids, temperature, and fecal coliform. Sampling point 0128NA001 monitors the influent of the surface drainage from a portion of the City of Montgomery to the east side of MAFB. Sampling point 0128NA003 on MAFB monitors surface drainage effluents exiting the installation. Sampling point 0128NA002 on MAFB monitors a drainage stream prior to discharge into an onbase lake. Sampling points 0128NA004 and 0128NA005 monitor surface drainage streams prior to discharge into the West End Ditch. None of the sampling points monitor West End Ditch directly. A review of the NPDES monitoring data for the period May 16, 1979, through March 31, 1983, indicated no water quality problems at the required sampling points.

Beginning in May 1982, the number of parameters analyzed at sampling point 0128NA001 (influent to the base) was expanded to include cyanide, phenols, arsenic, cadmium, lead, and mercury. Monitoring data indicate that levels of arsenic [1.5 milligrams per liter (mg/l) maximum] and lead (1.3 mg/l maximum) are present in the surface drainage entering the base. Levels of phenols and oil and grease are also indicated. Levels of cyanide, cadmium, and mercury were negligible or lower than detectable limits. The surface drainage flows through sampling point 0128NA002 on the east side of the base and enters a series of onbase lakes which drain to the Alabama River. The source(s) of the offbase contaminants has not been identified.

2.6 DESCRIPTIONS OF DISPOSAL AND STORAGE AREAS

The 10 disposal and storage areas described in the Phase I report were prioritized into seven sites (listed in Table 1.3-2). Some of the areas were grouped as sites because they are located close to one another and, therefore, are expected to share ground water flow patterns. Site 3 incorporates Fire Protection Training Area (FPTA) No. 2 and Landfill No. 3. Site 5 incorporates Landfills 4, 5, and 6.

2.6.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS

Electroplating operations were conducted at MAFB from the late 1940s through the early 1970s. From at least the late 1940s through the mid-1960s, spent electroplating solutions were drummed and disposed of in areas (Site 1) near Hopper Lodge (Bldg. 1110) (Fig. 2.6-1). These solutions included copper, chromium, nickel, cadmium, and cyanide compounds. Approximately four to five drums of solutions were disposed of each year during peak plating operation years from the mid-1950s to the early 1960s. It is estimated that approximately 20 to 40 drums of solutions have been disposed of in the area of Site 1.

The electroplating operations ceased in the early 1970s, and the spent solutions were transported to Kelly AFB for disposal in the mid-1970s.

Trench landfilling was the disposal method used at Site 1. In the Phase I report, the typical trench was estimated to be 8 to 10 ft deep and 14 ft wide. The disposal areas reportedly have clay soil, and the areas are covered and closed. A parking lot covers a portion of one of the disposal areas.

2.6.2 SITE 2--SURFACE DRAINAGE SYSTEM

The surface drainage system at MAFB, designated as Site 2, includes open drainage ditches which discharge to the Alabama River. The general drainage patterns on the base are shown in Fig. 2.6-2.

The surface drainage system on the northern and western portions of MAFB received untreated industrial waste solutions from the 1940s through the early 1970s. These wastes included effluent from several washracks, rinse water from electroplating operations, unneutralized acids, and quantities of paint stripper. An internal USAF waste disposal survey was conducted by the Occupational Environmental Health Laboratory (OEHL) in March 1969 to assess industrial waste disposal practices at MAFB. Oil/water separators were installed in the early 1970s for the separation of oily wastes. Also, the practice of neutralizing acid wastes prior to discharge to the surface drainage system began in the early 1970s.





Figure 2.6-1
SITE 1 — ELECTROPLATING
WASTE DISPOSAL AREAS

INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base

SOURCES: ES, 1984.
ESE, 1985.



**Figure 2.6-2
SITE 2 — SURFACE DRAINAGE SYSTEMS**

**INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base**


One of the major drainage ditches, West End Ditch, forms the western part of the southern boundary of MAFB. This ditch is owned and maintained by the City of Montgomery. The channel flows west and then north, eventually discharging into the Alabama River. At the time of the Phase II study, the city was lining the ditch with concrete along a portion of its length.

2.6.3 SITE 3—FPTA NO. 2 AND LANDFILL NO. 3

Landfill No. 3 is situated in the vicinity of FPTA No. 2 (Fig. 2.6-3). Household garbage, base trash (paper, wood, and scrap metal), and industrial nonliquid wastes such as waste paints, empty paint cans, paint booth sludges, and unrinsed pesticide containers were disposed of in this landfill from 1951 to 1956. Trench landfills were used over approximately 10 acres, with trenches averaging 10 ft deep by 14 ft wide. Daily cover was normally applied. The landfill area is closed and has been covered. Landfill No. 3 is located in a floodplain near West End Ditch, and the water table in the area is near the surface.

In 1962, fire protection training activities were moved from FPTA No. 1 to FPTA No. 2, the area of the closed landfill (Fig. 2.6-3). Initially, the training area was constructed as a shallow, unlined pit about 12 inches deep in the center and 35 ft in diameter. Protein foam, AFFF, and Halon® were used as extinguishing agents at this site.

From 1962 through 1973, waste oils, waste fuels, waste solvents, and other ignitable wastes were used for training exercises. Drums of these waste materials were delivered to a holding area just north of the fire pit. Between 25 and 35 drums frequently were stored at this location. Some leakage from these drums is believed to have occurred. Prior to each exercise, the pit area was soaked with water, then the ignitable materials were poured in the pit to conduct the training exercise. At the conclusion of the exercise, residue materials and water soaked into the pit area. Occasionally from 1962 to 1978, water and residual waste ignitable materials would overflow from the pit area to West End Ditch.



In 1978, a concrete liner, sump, oil/water separator, and evaporation pond system were constructed over the unlined fire pit area. This system is currently in operation. Residual fuel is separated and collected. Water is discharged to the evaporation pond and allowed to evaporate. The evaporation pond is unlined and has no discharge to surface waters.

2.6.4 SITE 4--FPTA NO. 1


Fire protection training exercises were conducted in the area currently used for disposal of landscape debris and construction rubble (Fig. 2.6-4). This site was used from the early 1940s to 1962. The training area consisted of a shallow, unlined depressed area no more than 12 inches deep in the center. Training exercises were typically conducted on weekends, and usually two to three exercises were conducted each day. High-pressure water was used to extinguish fires.


Before each exercise, the pit area was soaked with water. Waste oils, waste fuels, waste shop solvents, and other ignitable wastes were stored on an embankment near the area of the fire pit. Between 10 and 20 full or partially full drums were stored at the site. Occasionally, the waste fuels and solvent would be washed out of the pit area during an exercise into a small pond located nearby.

2.6.5 SITE 5--LANDFILLS 4, 5, AND 6

Landfills No. 4, 5, and 6 have been grouped as Site 5. These landfills and the wastes they contain are described in the following paragraphs.

Landfill No. 4 is situated on leased land adjacent to the installation boundary (Fig. 2.6-5). This landfill was operated from 1956 to the early 1970s as a trench landfill. Household garbage, base trash (paper, wood, and scrap metal), and industrial nonliquid wastes such as waste paints, empty paint cans, paint booth sludges, small quantities of solvent sludge, and pesticide containers were landfilled. Refuse was typically burned in the trenches before the daily soil cover was





applied. The landfill covered approximately 12 acres, with trenches averaging 10 ft deep by 20 ft wide. Landfill No. 4 is closed, covered, and revegetated. This landfill is situated in a floodplain near West End Ditch, and the water table in the area is near the surface.

Landfill No. 5 is a 10-acre area situated on leased land south of Landfill No. 4 (Fig. 2.6-5). This landfill was operated from the early 1970s to 1974 for the disposal of household garbage, base trash (paper, wood, and scrap metal), and industrial nonliquid wastes such as waste paints, empty paint cans, paint booth sludges, and pesticide containers. Landfill No. 5 was operated as a trench landfill, with trenches averaging 8 ft deep by 20 ft wide. Burning of refuse was not a practice at this location, and the site is currently closed and covered. This landfill is situated in a floodplain near West End Ditch, and the water table in the area is near the surface.

Landfill No. 6 is a 15-acre leased site where disposal operations have been conducted since 1974 (Fig. 2.6-5). Trench landfilling is used for the disposal of household garbage, base trash, and industrial nonliquid wastes such as waste paints, empty paint cans, paint booth sludges, and pesticide containers. The average trench is approximately 5 ft deep by 20 ft wide. Daily soil cover is applied to the active disposal cell, except during periods of wet weather. Approximately 10 acres of Landfill No. 6 are closed and covered; approximately 5 acres are active. This landfill is situated in a floodplain near West End Ditch, and the water table in the area is near the surface.

In 1981, three monitor wells were installed at Landfill No. 6 and located as shown in Fig. 2.6-5. The monitor wells are 21 to 23 ft deep, and the depth to water in each well is 6 to 7 ft below land surface. Each monitor well is monitored by MAFB on an annual basis for pH, specific conductance, chloride, and iron.

The locations of the ground water monitor wells were specified by State of Alabama personnel. No observation wells were installed to determine ground water flow directions and to assure the wells were downgradient of the landfill area. Therefore, the ground water monitoring data available from the prior study may not be representative of the impact of Landfill No. 6 on the surrounding ground water.

2.6.6 SITE 6--C.E. DRUM STORAGE AREA


The Civil Engineering (C.E.) drum storage area (Fig. 2.6-6) has been used for the storage of waste paints and nonignitable mixtures of oil and water since the mid-1970s. As many as 80 to 90 drums of these wastes have been stored at this site at one time. Since the late 1970s, drums at the C.E. drum storage area have been placed on a concrete pad which drains to an oil/water separator. Before then, drums were stored on the ground. In Phase I, it was reported there were indications that some leakage had occurred, although no details were given.

2.6.7 SITE 7--LANDFILL NO. 2

During the early 1940s through approximately 1951, the base operated Landfill No. 2 (Fig. 2.6-7) for the disposal of household garbage, base trash (paper, wood, and scrap metal), and industrial nonliquid wastes such as waste paints, empty paint cans, paint booth sludges, and unrinsed pesticide containers. Trench landfilling was practiced, and wastes were covered daily. The trenches were approximately 10 ft deep by 15 ft wide. The landfill encompasses about 20 acres and is currently closed and covered. The landfill is situated in a floodplain near West End Ditch, and the water table in the area is near the surface.

2.7 SUMMARY OF ENVIRONMENTAL SETTING

The environmental setting data reviewed for this investigation indicated that the following items are relevant to the assessment of past hazardous waste management practices at MAFB.



**INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base**

**Figure 2.6-6
SITE 6 — C.E. DRUM STORAGE AREA**

- o Study area mean annual precipitation is reported to be 52.1 inches, and net precipitation was calculated to be approximately 8 inches, which represents the meteoric water available for infiltration. The 24-hour maximum rainfall event is 6.3 inches.
- o Many of the Phase II, Stage 1 study areas on MAFB are situated in zones flooded by a 100-year rainfall event.
- o Surface soils at MAFB tend to be moderately to poorly permeable but are underlain by highly permeable soils at shallow depths.
- o The Terrace-Deposit aquifer is present at ground surface at MAFB. Water levels in this unit are shallow (3.5 to 7 ft below ground surface).
- o The Terrace Deposits form the shallow aquifer in the study area and directly overlie and provide recharge to the Eutaw Formation, which is present at shallow depth (40 ft) below ground surface. The Eutaw Formation is a major regional aquifer. No separation exists between the terrace materials and the Eutaw. The water level in the Eutaw was measured at 10 ft below ground surface in a well at MAFB during studies not associated with the current project or other IRP projects.
- o Two major regional aquifers, the Gordo and Coker Formations, exist below and are in contact with the Eutaw Formation. The City of Montgomery obtains most of its ground water supply from these two aquifers.
- o Contaminants, including arsenic and lead, have been detected by previous studies entering MAFB through the surface drainage influent from a portion of the City of Montgomery on the east side of MAFB.

Potential pathways for the migration of hazardous-waste-related contamination exist. Hazardous materials present at ground surface could be mobilized to the area's shallow aquifer (Terrace Deposits) and subsequently discharged to local surface streams or transferred to the underlying Eutaw or Gordo Formations as recharge.

3.0 FIELD PROGRAM

3.1 DEVELOPMENT OF FIELD PROGRAM

The MAFB Phase II, Stage 1 field program was developed based on findings and recommendations of the Phase I Records Search conducted by ES in 1984, additional information obtained subsequent to the Records Search, and discussions with USAFOEHL personnel. A summary of the Phase II, Stage 1 monitoring and analysis work plan is given in Table 3.1-1. The complete scope of work outlined by OEHL appears in App. C. The quality assurance (QA) and safety plans applicable to Phase II, Stage 1 studies are found in Apps. D and E, respectively. In many instances the work scope reflects modifications of Phase I recommendations enacted due to changes in contamination assessment.

The MAFB Phase II, Stage 1 survey was designed primarily as a screening survey to determine whether contamination exists at the sites and is sufficient to warrant further monitoring. In addition to analyses for specific parameters, the survey utilizes general screening parameters such as pH, specific conductance, total phenolics, total organic carbon (TOC), and total organic halides (TOX) to detect the presence of nonspecific classes of pollutants. The parameters pH, specific conductance, TOC, and TOX are often collectively referred to as ground water contamination indicators. For sites where values of screening parameters are high enough to indicate that a problem may exist, additional sampling and analyses are recommended to determine the extent of contamination.

The Phase II, Stage 1 investigations at MAFB involved geophysical surveys, piezometer installation and monitoring, monitor well installation and ground water quality monitoring, surface water quality monitoring, and sediment sampling. This section details the field investigation methodology and program implementation at each disposal and storage site.

Table 3.1-1. MAFB Phase II, Stage I Monitoring and Analysis

Site Description	Monitoring/Analysis Description	Rationale
1. Electroplating Waste Disposal Areas	Perform geophysical survey with electromagnetic (EM) techniques and magnetometer	Attempt to locate the actual burial sites for the electroplating drums
	Install four piezometer wells	Determine flow direction in the shallow aquifer
	Install one upgradient and three downgradient wells (total of four monitor wells)	Sample shallow ground water migrating through the reported disposal site
	Collect four ground water samples and analyze for pH, specific conductance, total dissolved solids (TDS), TOC, and phenols	Indicators of nonspecific ground water contamination
	Cyanide (CN)	Buried wastes reportedly were metal cyanides
	Copper (Cu), nickel (Ni), cadmium (Cd), chromium (Cr), and zinc (Zn)	Contaminants from the metal plating solutions
2. Surface Drainage System	Collect four surface water samples and analyze for: pH, specific conductance, dissolved solids, TOC, and TUX	Indicators of nonspecific contaminants
	Phenols, oil and grease	Drainage system received effluent from washtracks and paint strippers
	Cu, Ni, Cd, Cr, Zn, lead (Pb), arsenic (As), and mercury (Hg)	Drainage system received leachate from electroplating rinsing operations. In addition, some metals were detected in surface streams during nonrelated prior studies on MAFB.

Table 3.1-1. MAFB Phase II, Stage I Monitoring and Analysis (Continued, Page 2 of 5)

Site Description	Monitoring/Analysis Description	Rationale
2. Surface Drainage System (continued)	CN	Electroplating contaminants were metal cyanides
	Collect 11 sediment samples and analyze for the parameters listed above (except TDS, pH, and specific conductance) in the surface waters	Same rationale as for surface water
3. FFTA No. 2 and Landfill No. 3	Perform geophysical survey with EM and magnetometer techniques	Attempt to locate boundaries of disposal areas to assure the monitor wells are located outside burial trenches
	Install three piezometer wells	Determine shallow ground water flow direction
	Install three monitor wells (one upgradient and two downgradient)	Sample shallow ground water to determine if contaminants are present and migrating
	Collect three ground water samples and analyze for: pH, specific conductance, TOC, TDS, and TSS	Indicators of nonspecific contaminants
	Phenols, oil and grease	Landfill and FFTA received phenolics, and oil and grease
	CN, Ni, Zn, and Cu	Contaminants from electroplating operations
	As, barium (Ba), Cd, Fe, Cr, Pb, Hg, fluoride (F), nitrate (NO ₃), selenium (Se), silver (Ag), endrin, lindane, methoxychlor, toluene, 2,4,5-TP, 2,4-Dichlorophenoxyacetic acid (2,4-D), and sulfate (SO ₄)	Potential contaminants from the landfill

Table 3.1-1. MAPB Phase II, Stage 1 Monitoring and Analysis (Continued, Page 3 of 5)

Site Description	Monitoring/Analysis Description	Rationale
4. FYTA No. 1	<p>Install three piezometer wells</p> <p>Install three ground water monitor wells (one upgradient and two downgradient)</p> <p>Collect three ground water samples and analyze for: pH, specific conductance, TDS, TOC, and TOX</p> <p>Phenols, oil and grease</p> <p>CN, Ni, Zn, and Cu</p> <p>As, Ba, Fe, Pb, Hg, Cd, Cr, F, NO₃, SO₄, Se, Ag, endrin, lindane, methoxychlor, toluene, 2,4,5-TP, and 2,4-D</p> <p>Perform geophysical survey</p>	<p>Determine flow direction of the ground water</p> <p>Sample ground water to determine if shallow aquifer is contaminated</p> <p>Indicators of nonspecific contaminants</p> <p>Landfill reportedly received phenols, and oil and grease</p> <p>Contaminants from electroplating</p> <p>Potential contaminants from the landfill</p> <p>Determine the size and location of the disposal site and locate monitor wells outside burial trenches</p> <p>Determine the ground water flow direction</p> <p>Sample ground water to determine if the shallow aquifer is contaminated</p> <p>Indicators of nonspecific contaminants</p>
5. Landfills 5, 6, and 7	<p>Install three piezometer wells</p> <p>Install four ground water monitor wells (one upgradient and three downgradient)</p> <p>Collect five* ground water samples and analyze for: pH, specific conductance, TDS, TOC, and TOX</p>	

*Samples collected from four newly installed wells and one existing well.

Table 3.1-1. MAFB Phase II, Stage 1 Monitoring and Analysis (Continued, Page 4 of 5)

Site Description	Monitoring/Analysis Description	Rationale
5. Landfills 5, 6, and 7 (continued)	Phenols, oil and grease	Landfills reportedly received oil and grease and other items (e.g., paint strippers) containing phenolics
	CN, Ni, Zn, and Cu	Contaminants from electroplating activities
	As, Ba, Fe, Cd, Cr, Pb, Hg, F, NO_3^- , Se, Ag, endrin, lindane, methoxychlor, toxaphene, 2,4,5-TP, 2,4-D, and SO_4	Potential contaminants from activities conducted on MAFB
6. C.E. Drum Storage Site	Install three piezometer wells	Determine the direction of ground water flow
	Install three monitor wells (one upgradient and two downgradient)	Sample shallow ground water to determine if aquifer is contaminated
	Collect three ground water samples and analyze for: pH, specific conductance, TDS, TOC, and TOX	Indicators for nonspecific contaminants
	CN, Ni, Zn, and Cu	Potential contaminants from electroplating operations conducted on MAFB
	Phenols, oil and grease	Oils, greases, solvents, and possibly phenolics were reportedly spilled at this site

Table 3.1-1. MAFB Phase II, Stage 1 Monitoring and Analysis (Continued, Page 5 of 5)

Site Description	Monitoring/Analysis Description	Rationale
7. Landfill No. 2	As, Ba, Be, Cd, Cr, Pb, Hg, F, NO ₃ , Se, Ag, endrin, lindane, methoxychlor, toxaphene, 2,4,5-TP, 2,4-D, and SO ₄	Potential contaminants generated by activities on MAFB
	Perform geophysical survey using EM and magnetometer methods	Determine the areal extent of the disposal area in order to install the wells outside the burial area
	Install three piezometric wells	Determine the ground water flow direction
	Install three monitor wells (one upgradient and two downgradient)	Sample shallow ground water to determine if contaminants are present
	Collect three ground water samples and analyze for: pH, specific conductance, TDS, TOC, and TOX	Indicators for nonspecific contaminants
	CN, Ni, Zn, and Cu	Potential contaminants from electroplating operations
	Phenols, oils and grease	Phenolics, oils and greases reportedly went to the landfills
	As, Ba, Be, Cd, Cu, Cr, F, NO ₃ , SO ₄ , Se, Ag, endrin, lindane, methoxychlor, toxaphene, 2,4,5-TP, and 2,4-D	Potential contaminants generated by activities on MAFB

Source: ESE, 1985.

The boundaries at some of the disposal and storage sites were poorly defined at the surface, overgrown with vegetation, or covered with pavement. Geophysical surveys incorporating electromagnetic (EM) and magnetometer techniques were conducted at several sites to assist in the determination of site boundaries, to locate landfilled wastes, and to attempt the preliminary identification of leachate plumes originating from specific sites.

Piezometers were installed around each disposal and storage site as observation wells in which ground water levels in the unconfined aquifer could be measured. Water-level data were used to determine ground water gradients and identify ground water flow directions. This information was used in determining appropriate upgradient and downgradient locations for monitor wells. Monitor wells were installed in upgradient and downgradient locations at each site for ground water quality monitoring to evaluate potential contaminant migration. In the shallow, unconfined aquifer, three or four monitor wells were installed at each site, and both organic and inorganic contaminants were monitored.

Soil samples were collected during the installation of each piezometer and monitor well, and boring logs were developed describing the subsurface geology at each site. Soil samples were stored at ESE's Gainesville, Fla. laboratory for potential analysis, if subsequently collected ground water samples were found to be significantly contaminated.

Surface water samples were collected at various points along the West End Ditch to evaluate water quality in the ditch and to assess the impact of runoff and ground water discharge from disposal and storage sites. Samples were collected and analyzed from locations within the West End Ditch near the point where the ditch enters MAFB and near its exit from the installation.

Sediment samples were collected from small streams and ditches in the MAFB surface drainage system to evaluate the accumulation of contaminants in the sediment from surface runoff and ground water discharge.

3.2 METHODOLOGY

3.2.1 GEOPHYSICAL SURVEY TECHNIQUES

A geophysical survey was conducted at Sites 1, 3, 5, and 7 on MAFB using EM and magnetometer techniques. These instruments are commonly used to determine the areal extent of disturbed soils, the existence of buried metallic objects, and the existence of leachate emanating from landfill areas into the shallow ground water.

EM instruments measure the resistance of the earth to the passage of an electrical current. EM data are usually read in conductivity rather than resistivity units. These two parameters are inversely related. EM techniques work on the principle of induction. A transmitter coil in the instrument induces small currents in the earth. The receiver coil senses the magnetic fields associated with both the transmitter and the induced current. The ratio of the strengths of these fields is proportional to the conductivity of the earth.

The magnetometer is a fluxgate gradiometer. An audible signal is emitted when its two sensors detect a difference in magnetic field strengths. This indicates a strong local perturbation in the total magnetic field due to the presence of ferromagnetic objects.

The magnetometer survey was performed using two different gain settings on the instrument which provide two different sensitivities, comparable to two different depths of penetration.

The geophysical surveys were conducted as follows:

1. The study areas were gridded and marked, and the location of the grid was noted on a map.

2. EM conduction and magnetometry surveys were conducted over the site referencing all data to the grid location.
3. The data were analyzed in the field to determine the presence of gross anomalies and to interpret their cause.

The EM conductivity survey was conducted to determine the location of contaminant plumes and buried metallic objects. The magnetometer was used to refine the location of ferrous metal objects. The implementation of these techniques is described in Sec. 3.3.

3.2.2 PIEZOMETER INSTALLATION AND MONITORING

Nineteen piezometers were installed at six sites on MAFB. The total footage installed was 449.7 ft, which consisted of 239.7 ft of solid casing and 210 ft of slotted screen. Three piezometers each were placed at Sites 3, 4, 5, 6, and 7, and four piezometers were placed at Site 1, as described in Sec. 3.2. The sample numbering system used for the piezometers is described in App. F.

The borings for all piezometers were completed using a Central Mine Equipment (CME) Model 45 drilling unit equipped with a hollow-stem auger with a 3.25-inch inside diameter and a 6-inch outside diameter. The unit was operated without water, except when necessary, to eliminate cave-in from the boring. The 2-inch polyvinyl chloride (PVC) well pipe and screen were installed through the center of the hollow drill stem and positioned at the appropriate depths. As the auger was withdrawn from the hole, the formation was allowed to collapse around the well screen and casing. This technique prevented collapse of the borehole that could have occurred had the auger been removed from the hole first and the well pipe introduced from the top of the empty hole.

The subsurface material in the 0- to 25-ft-depth interval consisted of unconsolidated gravels, sands, silts, and clays. As a result, the boreholes tended to collapse from a condition known as "running sand" when

the water table was reached. In this condition, hydrostatic pressure caused saturated soil to rise in the dry hollow-stem auger and impede drilling. The sand was typically flushed out by using a rotary bit and circulating drilling water. The total depths and the locations of screened intervals in each piezometer are discussed for each site in Sec. 3.2. Cased depths vary from 15 to 39 ft, with all screens placed below the water table. The ESE Site Geologist maintained regular telephone contact with the Project Manager during the drilling program to make recommendations for well placement when unique hydrogeologic conditions required that well placement or configuration differed from the Work Plan.

The piezometers penetrated the shallow water table to depths of 25 ft or less. The piezometers were installed in a 6-inch borehole and consisted of Schedule 40 PVC pipe (2-inch inside diameter), with 0.010-inch slots (screen) in the bottom 10- or 15-ft interval. Pipe sections were joined by solvent welding. The bottom of the screen was capped before installation, and a vented cap was installed at the top of each piezometer. Filter packs, bentonite seals, and grout seals were not used in piezometer construction. Drill cuttings were backfilled around the screen and casing when placed in the borehole. This prevented contaminants from entering the ground water. A sketch of the well installation was included on the boring log depicting the depths of the bottom of the boring, screen location, coupling locations, cave-ins, cutting backfill, and the height of riser above ground surface.

Boreholes were drilled using procedures that ensured plumbness and cleanliness. Plumbness was obtained by careful leveling of the drill rig before drilling. Drilling was controlled to avoid wobble and chatter in the drill stem.

At each piezometer site, installation began within 48 hours of the time the borings were completed and continued uninterrupted until completion. The screen and casing were carefully cleaned with unchlorinated water

prior to installation in the hole. Solid casing extended from the screen to approximately 2.5 ft above land surface.

It was assumed that the hydraulic gradient at each site was controlled by topography. Piezometers were located and installed in areas to verify this assumption. After the water-level elevations at each site were measured and surveyed (against other piezometers at the same site and not referenced against MSL), the piezometer casings and screens were removed. Each boring was grouted from the top of the collapsed portion to ground level using a grout mixture of 20 parts Portland cement to 1 part bentonite mixed with unchlorinated water. At many sites the monitor wells were installed near the former piezometer locations because the calculations for optimum ground water flow direction indicated these locations were appropriate.

Water-level measurements at the piezometers were obtained using the USGS wetted-tape method, which is accurate to 0.01 ft. The tape was rinsed with water from the approved source, wiped with a fresh cloth, and allowed to air dry between consecutive water-level measurements. At each site, static water-level measurements were obtained in all piezometers within a 1-hour period to ensure consistency among the measurements.

The relative elevation of the ground surface at each piezometer was determined by land surveying. However, piezometer elevations at individual sites were not related to those at other sites.

3.2.3 MONITOR WELL INSTALLATION AND SAMPLING

Twenty, 4-inch-diameter, ground water monitor wells were installed at six sites on MAFB. Total footage installed was 535.3 ft, consisting of 240.3 ft of casing and 295 ft of slotted screen. Three monitor wells each were installed at Sites 3, 4, 6, and 7, and four monitor wells each were installed at Sites 1 and 5. The sample numbering system used for the monitor wells is described in App. F.

Borings for all ground water monitor wells were completed using a Mobile B-53 drilling unit equipped with a hollow-stem auger with a 6-inch inside diameter and a 12-inch outside diameter. The unit was operated without water, except when required by soil conditions ["Running Sand" encountered when augering below the water table in sand and gravel units (consisting of coarse, unconsolidated, unlithified materials) required that approved drilling water be maintained in the auger to inhibit the entry of materials when the bottom plug was removed to collect split-spoon samples]. The 4-inch PVC well pipe and screen were installed through the center of the hollow drill stem and positioned at the appropriate depths. As the auger was withdrawn from the hole, the annular space was backfilled with clean silica sand. This technique prevented collapse of the borehole that could have occurred had the auger been removed from the hole first and the well pipe introduced from the top of the hole.

The augers were occasionally flushed out using a rotary bit and nonchlorinated water before the well casing and screen could be installed. The volume of drilling water lost to the formation during this procedure was recorded in the log.

Subsurface materials encountered during drilling consisted of unconsolidated gravels, sands, silts, and clays. As a result, the boreholes tended to collapse when the boring reached the water table, as described previously.

Split-spoon soil sampling was performed through the total depth of each borehole. Samples were collected every 2.5 ft for the first 10 ft and every 5 ft thereafter. Intact split-spoon soil samples were sectioned and stored in labeled glass jars that were kept in cooled, insulated containers in the field and en route to ESE's laboratory. Each container was marked with the sample depth interval, top and bottom of the sample, date, and time. The split-spoon sampler was cleaned with nonchlorinated water between each sample (i.e., each time a sample was removed from the tube).


The soil samples were retained for potential analysis in case ground water at the site was found to be contaminated. If no contamination was found, soil samples were to be discarded following completion of Phase II.

The total depths of monitor wells and the locations of screened intervals are discussed for each site in Sec. 3.3. Well depths vary from 14 to 40 ft; screened intervals vary from 10 to 20 ft. The ESE Site Geologist maintained regular telephone contact with the Project Manager during the drilling program to make recommendations for well placement when unique hydrogeologic conditions required that well placement or configuration differed from the Work Plan.

Typical monitor well construction in unconsolidated overburden material is shown in Fig. 3.2-1. The placement of the well in the boring was deemed appropriate if the ESE Site Geologist found the soil in the proposed screened interval to be saturated.

The monitor wells were finished in the shallow, unconfined aquifer and were typically 30 ft deep. The wells were constructed of threaded Schedule 40 PVC pipe, with 0.010-inch slotted screen in the bottom 10- to 20-ft interval. A filter pack was placed in the annular space between the screen and the borehole, a bentonite clay seal on the top of the filter pack, and grout in the upper annular space to the surface. The bottoms of the wells were capped before the screens were installed, and vented caps were installed at the tops of monitor wells. Protective steel casings and locking caps were installed over the risers for security.

If the screened interval consisted of clean sand or gravel, the formation was allowed to collapse around the well screen and filter material was added above the cave-in to the appropriate depth. If not, filter material was installed around the entire length and to the top of the well screen. Nonchlorinated water was added, as necessary, to assure that the bentonite pellets expanded to form a tight seal.



NOT TO SCALE

SOURCE: ESE, 1985.

Figure 3.2-1
TYPICAL MONITOR WELL CONSTRUCTION

INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base

The bentonite-cement grout seal extended from the top of the bentonite seal to land surface. Grouting was performed in the presence of the ESE Site Geologist. The grout was pumped into the annular space under pressure using a tremie pipe placed at the top of the bentonite seal to ensure a continuous grout seal. The aboveground protective casing was also sealed in the grout, identifying marks were inscribed on the casing, and protective posts were installed around the well.

Coarse gravel, 0.5 ft thick and extending 4 ft radially from the protective casing, was placed on the ground surface at each monitor well.

The following materials were used in well construction.

1. Casing used in the well was threaded PVC Schedule 40, 4-inch nominal inside diameter. The well screen was factory slotted, with a slot width of 0.010 inch. An oversized slip-on cap was installed on each well.
2. The grout mixture was 10 parts Portland cement to one-half part bentonite (by weight), with a maximum of 10 gallons (gal) of nonchlorinated water per 94-pound (lb) bag of cement. Bentonite was added after mixing the cement and water.
3. Commercially available bentonite pellets manufactured specifically for well-sealing purposes were used in the seal.
4. Sand used in the filter envelope around the well screen was selected for compatibility with the screen slot size and aquifer materials.
5. A 6-inch aboveground protective steel casing was installed at each well, extending approximately 2.5 ft above land surface and seated 2.5 ft into the well seal grout. This casing was vented to the atmosphere via a lockable, hinged cap, which will prevent entry of water but is not airtight. This, and the oversized cap on the well, allows the well to remain at atmospheric pressure. A 0.25-inch-diameter drainage port was installed, centered 0.125 inch above the level of the internal monitor collar. Padlocks which open with the same key were used on all wells.

All well development data were recorded. Well development was performed as soon as possible after well installation.

Wells were developed by pumping with an electric, submersible pump (or a gasoline-powered, centrifugal pump) or by bailing with a PVC bailer until the water was as clear and the well as free of sediment as practical. Bailers were used for wells with yields that could not sustain the flow rate of the submersible or centrifugal pumps. No water was added to the wells during development. The pump or bailer was rinsed with the nonchlorinated drilling water and allowed to air dry prior to use in the next well. Well development data were recorded in the field in a tabular format and included the following:

1. Well identification;
2. Date of well installation;
3. Date of development;
4. Static water level before and 24 consecutive hours after development;
5. Quantity of water lost during drilling and fluid purging, if water was used;
6. Quantity of standing water in well and annulus (30-percent porosity assumed for calculation) prior to development;
7. Specific conductivity, temperature, and pH measurements were taken and recorded at the start, twice during, and at the conclusion of development. Calibration standards were run prior to, during, and after each day's operation in the field;
8. Depth from top of well casing to bottom of well;
9. Screen length;
10. Depth from top of well casing to top of sediment inside well, before and after development;
11. Physical character of removed water, including changes during development in clarity, color, particulates, and odor;
12. Type and size/capacity of pump and/or bailer used;
13. Height of well casing above ground surface; and
14. Quantity of water removed and time for removal.

Wells were allowed to equilibrate for at least 48 hours after installation of the protective casing and were developed until the following conditions were met.

1. The well water was clear to the unaided eye.
2. The sediment thickness remaining in the well was less than 5 percent of the screen length.
3. A volume of water was removed from the well equal to at least five well volumes (including the saturated filter material in the annulus) and a volume equal to that lost during drilling.

A 1-pint sample of the last water obtained during development at each well was obtained and stored in an insulated container chilled to approximately 4 degrees Celsius (°C). This water was examined by the onsite geologist to determine if the well had been sufficiently developed to be used as a monitoring well. The cap and all internal components of the well casing above the water table were rinsed with well water to remove all traces of soil, sediment, and cuttings. This washing was conducted before and/or during development.

All water-level measurements at monitor wells were obtained using the USGS wetted-tape method, which is accurate to 0.01 ft. The tape was rinsed with water from the approved source, wiped with a fresh cloth, and allowed to air dry between consecutive water-level measurements. At least one complete set of static water-level measurements for all wells was made over a single, consecutive 10-hour period.

Each monitor well was surveyed by a registered land surveyor to establish its map coordinates using the Alabama Plane Coordinate System, Western Zone, to an accuracy of at least one in 10 thousand (1:10,000). Additionally, elevations for the natural ground surface at each sampling well and the top of the PVC casing were determined to within 0.01 ft using the vertical datum established by USGS. The surveyor plotted the elevation of each monitor well (top of the PVC pipes) and its map coordinates on the MAFB base map (see App. G).

Ground water sampling began at MAFB after the new monitor wells had been allowed to reach equilibrium. The following procedures were performed during sampling.

1. The depth to water, total well depth, and length of the riser aboveground were measured.
2. During the initial sampling of each monitor well, the depth to the water/sediment interface in the well was measured and recorded.
3. Typically, five volumes of the water in the screen, well casing, and saturated annulus were purged by pumping or bailing before sampling. Fine soils at some of the well locations caused slow recharge rates. In such cases, reduction of well purging to less than five volumes was considered if excessive time would have elapsed attempting to collect one or two samples from low-yielding wells. The amount of fluid purged was measured and recorded.
4.
 - a. All wells were sampled using bailers constructed of inert materials (PVC). No glue was used in the construction of these bailers.
 - b. A dedicated bailer was supplied for each well and remained in the well after sampling. Each bailer was etched with the number of the sampling well.
 - c. The pump and the hoses used for purging were thoroughly cleaned between sampling at each well using the nonchlorinated drilling water.
 - d. After purging, each monitor well was sampled as soon as sufficient water returned to minimize the contact time between the water sample and the well casing.
 - e. During sampling, all equipment was placed on polyethylene sheeting to avoid contact with the soil.
5. Conductivity, pH, and temperature were measured before sampling.

The following data were recorded in a logbook for each well:

1. Well number;
2. Date;

3. Time;
4. Static water level;
5. Depth of well;
6. Number of bailer volumes removed, if applicable;
7. Pumping rate, if applicable;
8. Time of pumping, if applicable;
9. Drawdown water level;
10. In situ water quality measurements such as pH, specific conductance, and temperature;
11. Fractions sampled and preservatives;
12. Weather conditions and/or miscellaneous observations; and
13. Signature of sampler and date signed.

Each sample was labeled for identification by laboratory personnel. The sample label included the project number, a unique sample number, time and date sampled, and sampler's initials. All samples were identified with non-water-soluble ink on ESE's standard preprinted and prenumbered labels immediately after collection. Information concerning preservation methods, sample matrix, and sample location number was included on the labels. Samples were shipped in coolers and were chilled to approximately 4°C from time of sample collection until analysis.

3.2.4 DRILLING LOGS AND BORING PROCEDURES

Before borings were drilled for installation of the piezometers and monitor wells, the ESE Site Geologist reviewed the proposed drilling locations with MAFB Civil Engineering to avoid drilling into buried utilities such as cables or pipes. Based on this review, MAFB Civil Engineering approved all locations and issued appropriate drilling permits. The ESE Site Geologist supervised the drilling and installation of all piezometers and monitor wells, maintained drilling logs, obtained soil samples, and observed the grouting of abandoned borings.

Drilling was performed by Law Engineering Testing Company (LAW) as subcontractor to ESE. In addition to drilling, LAW was responsible for the following requirements:

1. Arrangement of access to all sites where drilling was proposed;
2. Steam cleaning of all drilling equipment before entrance to MAFB;
3. Arrangement with MAFB personnel for the storage of all well-drilling equipment and well-installation supplies in a clean and secure area; clean, unused equipment and supplies were temporarily stored on sheets of disposable polyethylene at each drilling location to eliminate contamination from the native soils;
4. Obtaining unchlorinated water for drilling and well installation; portable tubs were used to hold drilling water during circulation;
5. Recovery of all drill cuttings and disposal in the onbase hardfill area; and
6. Cleaning of drilling tools between borings with unchlorinated water to remove all traces of soil, rock, or other potential contaminants.

The ESE Site Geologist maintained drilling logs in a field notebook for all boreholes. The logs comprised a record of soil characteristics, lithology, piezometer and well construction, and personnel. Each boring was logged in the field notebook as it was being drilled. The following data were recorded in the boring logs:

1. Depths, recorded in feet;
2. Soil descriptions prepared in the field by the ESE Site Geologist in accordance with the Unified Soil Classification System;
3. Descriptions of split-spoon samples, including:
 - a. Classification,
 - b. Unified Soil Classification System symbol,
 - c. Secondary components and estimated percentage,
 - d. Color,
 - e. Plasticity,

- f. Consistency (cohesive soil) or density (noncohesive soil),
- g. Moisture content, and
- h. Texture, fabric, and bedding;
- 4. Descriptions of cuttings, including basic classification, secondary components, and other apparent parameters;
- 5. Percent of secondary soil constituents, based on visual estimates;
- 6. Length of sample recovered in each sampled interval for split-spoon samples;
- 7. Blow counts, hammer weight, and length of fall for split-spoon samples;
- 8. Estimated interval for each sample;
- 9. Depth to water as first encountered during drilling and method of determination; distinct water-bearing zones (if any) below the first zone;
- 10. When drilling fluid was used, fluid losses, quantities lost, and the intervals over which they occurred;
- 11. Type of drilling equipment used, including rod size, bit type, pump type, rig manufacturer, and model number;
- 12. Drilling sequence;
- 13. Special problems;
- 14. Start and completion dates of all borings; and
- 15. Lithologic boundaries.

3.2.5 SURFACE WATER SAMPLING

Before surface water samples were collected, the following site-specific data were recorded in the field notebook:

- 1. Site number or location;
- 2. Date;
- 3. Time (24-hour system);
- 4. Antecedent weather conditions, if known;
- 5. In situ parameter measurements (temperature, conductivity, and pH);
- 6. Fractions and preservatives;
- 7. Any other pertinent observations (e.g., odor or fish); and
- 8. Signature of sampler and date signed.

At the conclusion of each workday onsite, the Sampling Team Leader or designee reviewed each page of the notebook for errors and omissions before dating and signing each reviewed page. All field instrument calibrations were recorded in a designated portion of the notebook at the time of the calibration. Instruments were recalibrated as necessary.

Each surface water sample was collected in a manner that minimized aeration and prevented oxidation of reduced compounds in the sample. The container was filled until it overflowed, and caution was taken to avoid air bubbles. Sample containers were tightly capped. Surface water sampling procedures and precautions for the volatile fraction collection were identical to the ground water procedures.

Each sample was labeled for identification by laboratory personnel. The sample label included the project number, a unique sample number, time and date sampled, and sampler's initials. All samples were identified with non-water-soluble ink on ESE's standard preprinted and prenumbered labels immediately after collection. Information concerning preservation methods, sample matrix, and sample location number was included on the labels. Samples were shipped in coolers and chilled to approximately 4°C from time of sample collection until analysis.

3.2.6 STREAM SEDIMENT SAMPLING

Before sediment samples were collected, the following site-specific data were recorded in the field notebook:

1. Site number or location;
2. Date;
3. Time (24-hour system);
4. Antecedent weather conditions, if known;
5. In situ parameter measurements (temperature, conductivity, and pH);
6. Fractions and preservatives;
7. Any other pertinent observations (e.g., odor or fish); and
8. Signature of sampler and date signed.

At the conclusion of each workday onsite, the Sampling Team Leader or designee reviewed each page of the notebook for errors and omissions before dating and signing each reviewed page. All field instrument calibrations were recorded in a designated portion of the notebook at the time of the calibration. Instruments were recalibrated as necessary.

Samples were collected in a manner that minimized aeration and prevented oxidation of reduced compounds in the sample. Each sample was labeled for identification by laboratory personnel. The sample label included the project number, a unique sample number, time and date sampled, and sampler's initials. All samples were identified with non-water-soluble ink on ESE's standard preprinted and prenumbered labels immediately after collection. Information concerning preservation methods, sample matrix, and sample location number was included on the labels. Samples were shipped in coolers and chilled to approximately 4°C from the time of sample collection until analysis.

3.3 IMPLEMENTATION OF FIELD PROGRAM

The actual work completed at each of the seven sites on MAFB is described. Site 2 is actually a collection of points on base where the surface water and stream sediment samples were collected, and Site 1 and Sites 3 through 7 were those locations where the ground water quality was investigated through the installation and sampling of monitor wells. A description of the subsurface geology is included for those sites where well borings were made.

3.3.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS

The objectives of the investigations at Site 1 were to:

1. Determine the physical extent of the disposal area and, if possible, the locations of the drums;
2. Determine if the hydrogeologic conditions in the area adjacent to the site are conducive to contaminant migration; and
3. Determine if contaminants are migrating from the area.

A detailed geophysical survey incorporating magnetometer and EM techniques was completed at Site 1 to delineate the horizontal extent of the burial area, to confirm the presence of the buried drums, and to locate any leachate plumes emanating from the site. The geophysical tracings for Site 1 are located in App. H.

The results of the survey did not conclusively indicate that the drums of electroplating waste were buried in the area. The results did indicate the locations of many ferrometallic objects in the vicinity of the reported burial area. The monitoring well sites were selected based on the results of this survey and the information obtained from the piezometers.

Four piezometers were installed at Site 1 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the four piezometers are depicted in Fig. 3.3-1. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-1. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels suggested that ground water flow at Site 1 was from east to west and monitor well locations were selected accordingly.

Four monitor wells were installed at Site 1 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the four wells are depicted in Fig. 3.3-1. The monitor well depths, screened intervals, lithology of the screened intervals, depth to water, and number of split-spoon soil samples collected are given in Table 3.3-2. The depth to water for all monitor wells installed for this study is presented in App. J. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. K.




Table 3.3-1. Site 1 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ1-1	24	14 to 24	0	19.15	0
PZ1-2	24	14 to 24	-13.82	6.00	-0.67
PZ1-3	15	5 to 15	-13.16	7.06	-1.07
PZ1-4	16	6 to 16	-14.09	6.02	-0.96

Source: ESE, 1985.

Table 3.3-2. Site 1 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW1-1	25	15 to 25	16.2	6	Gravelly quartz sand
MW1-2	14	4 to 14	5.5	6	Silty, clayey quartz sand
MW1-3	22.3	7.3 to 22.3	8.1	6	Gravelly quartz sand
MW1-4	21.5	6.5 to 21.5	7.4	7	Gravelly quartz sand


*Measured from top of PVC casing.

Source: ESE, 1985.

The soils at Site 1 generally consisted of unconsolidated clays, silts, sands, and gravels through the depths sampled. In most places, the upper 5 to 7 ft were comprised of sandy and silty clays, clayey and silty sands, and clayey silts of varying plasticity and consistency/density. In MW1-2, these soils were underlain by a very plastic, stiff gray clay from 7 to 11 ft deep that maintained a locally perched water body in the overlying silt. Silty and clayey gray to brown sands existed below the clay unit to 15 ft and were underlain by another clay unit of similar character that persisted to a depth of 18 to 19 ft. More shallow water was perched above this second clay in the overlying sands. Beneath the second clay unit was a very dense, poorly graded, slightly clayey, micaceous fine to medium-grained sand, olive in color, that extended to a depth of at least 26.5 ft. The sand held very little recoverable water and seemed almost cemented. The soil below 5 to 7 ft at MW1-1, MW1-3, and MW1-4 was significantly different. The surficial material was underlain by dense, well graded, fine to coarse gravelly sands and sandy gravels that graded from gray in color near the top to yellow and brown at depth. Cobbles exceeded 2 centimeters (cm) in diameter. These sands and gravels were present to at least 25 ft at MW1-1, but at 18 to 24 ft in MW1-3 and MW1-4 graded into the dense, micaceous, olive-colored sand found at the bottom of MW1-2. Depths to ground water at Site 1 varied from approximately 3 ft at MW1-2 to 13.7 ft at MW1-1. A geologic cross section of Site 1 is depicted by Fig. 3.3-2.

Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are available in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor as described in Sec. 3.2 of this report. The elevation and coordinate values for each well are listed on the map in App. G.



MW1-1 through MW1-4 were sampled according to the procedure described in Sec. 3.2.3 of this report. The samples were analyzed for the parameters in List A, Table 3.3-3. Details of the sampling effort are available in App. M.

3.3.2 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3

Site 3 consists of two areas: FPTA No. 2 and Landfill No. 3 (located within the landfill area).

The objectives of the investigations at Site 3 were to:

1. Determine the horizontal extent of Landfill No. 3,
2. Determine if the hydrogeologic conditions in the area adjacent to the site are conducive to contaminant migration, and
3. Determine if contaminants are present in ground waters from the area.

A detailed geophysical survey incorporating magnetometer and electromagnetic techniques was used to delineate the horizontal extent of the disposal area and to determine whether any leachate plumes were emanating from the disposal area or the fire protection training area. The geophysical tracings for Site 3 are located in App. H.

The results of the survey indicated the presence of metallic objects buried in the disposal area. No leachate plumes were detected by the study. The results of the study were used to decide the locations for the monitoring wells.

Three piezometers were installed at Site 3 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the three piezometers are depicted in Fig. 3.3-3. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-4. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels

Table 3.3-3. List of Analytical Parameters for MAFB Sampling

List A

Copper	Cyanide
Nickel	pH
Cadmium	Total dissolved solids
Chromium	Zinc
Total organic carbon	Phenols

List B

Copper	Cyanide
Nickel	pH
Cadmium	Total dissolved solids
Chromium	Zinc
Total organic carbon	Phenols
Lead	Oil and grease
	Arsenic
	Total organic halogens
	Mercury

List C

Total organic halogens	Oil and grease
Total organic carbon	Nickel
Phenols	Cyanide
pH	Sulfate
Copper	Total dissolved solids
Iron	Zinc

National Interim Primary Drinking Water Standards (selected list)

Arsenic	Lead	Endrin	2,4,5-TP
Barium	Mercury	Lindane	
Cadmium	Nitrate	Methoxychlor	
Chromium	Selenium	Toxaphene	
Fluoride	Silver	2,4-D	

Source: ESE, 1985.




Table 3.3-4. Site 3 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ3-1	27.7	17.7 to 27.7	0	10.06	0
PZ3-2	21.0	11.0 to 21.0	-8.77	7.79	-6.50
PZ3-3	16.0	6.0 to 16.0	-11.95	4.02	-5.91

Source: ESE, 1985.

suggested that ground water flow at Site 3 was from east to west, and monitor well locations were selected accordingly.

Three monitor wells were installed at Site 3 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the three wells are depicted in Fig. 3.3-3. The monitor well depths, screened intervals, lithology of the screened intervals, and number of split-spoon soil samples collected are given in Table 3.3-5. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. K.

The soils on the western side of Site 3 were typified by silty clays, clayey silts, and plastic clays to a depth of about 9 ft. Beneath the clays and silts were 4 to 5 ft of silty, fine gray quartz sand and fine to coarse gray quartz sand in varying proportions. The gray sands were underlain by 0 to 3 ft of loose, poorly graded, fine to medium-grained, micaceous, yellow quartz sands, which in turn were underlain by at least 11 ft of very dense, well-graded, fine to coarse, gravelly yellow sands and sandy gravels. Individual cobbles exceeded 5 cm in diameter. Beneath the yellow sands were moderately plastic, stiff, silty, micaceous, dark-olive clay that extended to an unknown depth. The soils on the eastern side of the site differed from those described above in that the surficial clays and silts were significantly thicker. Up to 28 ft of this material, slightly sandy and silty in places, was found above the yellow sands and gravels encountered at about 13 ft to the west. Additionally, a small perched water zone was detected above a very plastic clay at 18 ft. A geologic cross section of Site 3 is depicted in Fig. 3.3-4.


Water depths at Site 3 varied from about 15 ft below ground level at MW3-1 to as shallow as 2.4 ft at MW3-3.

Table 3.3-5. Site 3 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW3-1	37.3	27.3 to 37.3	17.7	8	Gravelly quartz sand
MW3-2	24.2	4.2 to 24.2	9.3	6	Fine to medium, micaceous, quartz sand and gravelly quartz sand
MW3-3	25.2	5.2 to 25.2	4.7	6	Silt, fine sand, sandy gravel and gravelly quartz sand

*Measured from top of PVC casing.

Source: ESE, 1985.



INSTALLATION RESTORATION PROGRAM Maxwell Air Force Base

**Figure 3.3-4
GEOLOGIC CROSS-SECTION OF SITE 3, FFTA NO. 2,
AND LANDFILL NO. 3**

Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are available in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor, as described in Sec. 3.2.3 of this report. The elevation and coordinate values for each well are listed on the map in App. G.

MW3-1 through MW3-3 were sampled according to the procedure described in Sec. 3.2.3 of this report. The samples were analyzed for the parameters in List C, Table 3.3-3.

3.3.3 SITE 4--FPTA NO. 1

Fire protection training exercises were conducted in the area currently used for disposal of landscape debris and construction rubble (Hardfill Area No. 2), as shown in Fig. 3.3-5.

The objectives of the studies at Site 4 were to:

1. Determine if the hydrogeologic conditions at the site are conducive for contaminant migration, and
2. Determine if contaminants are present in the ground water adjacent to the site.

Three piezometers were installed at Site 4 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the three piezometers are depicted in Fig. 3.3-5. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-6. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels suggested that ground water flow at Site 4 was from north to south, and monitor well locations were selected accordingly.




Table 3.3-6. Site 4 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ4-1	25	15 to 25	0	22.60	-1.02
PZ4-2	18.8	8.8 to 18.8	-8.23	13.35	0
PZ4-3	26	16 to 26	-3.20	19.24	-0.86

Source: ESE, 1985.

Three monitor wells were installed at Site 4 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the three wells are depicted in Fig. 3.3-5. The monitor well depths, screened intervals, lithology of the screened intervals, and number of split-spoon soil samples collected are given in Table 3.3-7. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. K.

The surficial soils at Site 4 had been removed at all drilling locations, but a cut in the side of an adjacent hill suggested that the missing soils were 1 to 5 ft of silt and clay underlain by sand and gravel mixtures. The soils actually sampled consisted of dense, well graded, fine to coarse, gravelly quartz sands and sandy gravels, varying from yellow to brown in color, and extending to an undetermined depth. Cobbles exceeded 7 cm in diameter. A geologic cross section of Site 4 is depicted in Fig. 3.3-6.

Ground water levels at Site 4 varied from about 10.9 ft at MW4-3 to 15.8 ft at MW4-1.

Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are presented in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor, as described in Sec. 3.2.3 of this report. The elevation and coordinate values for each well are listed on the map in App. G.

MW4-1 through MW4-3 were sampled according to the procedure described in Sec. 3.2.3 of this report. The samples were analyzed for the parameters in List C, Table 3.3-3.

Table 3.3-7. Site 4 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW4-1	26	16 to 26	18.3	6	Gravelly, medium to coarse sand; and gravelly, fine to coarse quartz sand
MW4-2	26	6 to 26	14.2	6	Medium to coarse gravelly sand and gravel and fine to coarse sand
MR4-3	24.5	4.5 to 24.5	13.6	6	Gravelly, fine to coarse sand; medium to coarse sand; gravel

*Measured from top of PVC casing.

Source: ESE, 1985.




Figure 3.3-6
GEOLOGIC CROSS-SECTION OF SITE 4, FPTA NO. 1

3.3.4 SITE 5--LANDFILLS 4, 5, AND 6

Landfills 4, 5, and 6 were combined to form Site 5 (see Fig. 3.3-7).

The objectives of the investigations at Site 5 were to:

1. Determine the physical extent of Landfills 4, 5, and 6;
2. Determine if the hydrogeologic conditions in the area are conducive to contaminant migration; and
3. Determine if the contaminants are present in the ground water downgradient of the landfill areas.

A detailed geophysical survey incorporating magnetometer and EM techniques was completed at Site 5 to delineate the aerial extent of the disposal area and to locate any leachate plumes emanating from the site. The geophysical tracings are located in App. H.

The results of the survey indicated the boundaries of the landfill area and the location of metallic objects. No leachate plumes were detected migrating from the landfill area. These data were used to select the locations of the monitor wells.

Three piezometers were installed at Site 5 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the three piezometers are depicted in Fig. 3.3-7. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-8. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels suggested that ground water flow at Site 5 was from southwest to northeast, and monitor well locations were selected accordingly.

Four monitor wells were installed at Site 5 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the four wells are depicted in Fig. 3.3-7. The monitor well depths, screened




Table 3.3-8. Site 5 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ5-1	23.5	13.5 to 23.5	0	18.69	0
PZ5-2	19	9 to 19	-12.80	7.44	-1.55
PZ5-3	18.6	8.6 to 18.6	-14.97	4.73	-1.01

Source: ESE, 1985.

intervals, lithology of the screened intervals, and number of split-spoon soil samples collected are given in Table 3.3-9. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. J.

The soils at Site 5 generally consisted of unconsolidated clays, silts, sands, and gravels through the depths sampled. The upper 4 to 12.5 ft of soil were comprised of clayey sands, sandy and silty clays, and inorganic clays of varying plasticity and density/consistency. Beneath these surficial deposits were from 6 to 11 ft of poorly graded, silty, fine sands, slightly clayey and micaceous in places, very coarse in places, usually white to gray, and occasionally brown. This material was underlain by loose, well-graded, fine to coarse, yellow quartz sands, often very gravelly and dense, that extended to undetermined depths. A geologic cross section of Site 5 is depicted in Fig. 3.3-8.

Water depths at Site 5 varied from approximately 1.6 ft below ground level at MW5-4 to about 12.5 ft at MW5-1.

Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are available in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor, as described in Sec. 3.2.3 of this report. The elevation and coordinate values for each well are listed on the map in App. G.


MW5-1 through MW5-4 were sampled according to the procedure described in Sec. 3.2.4 of this report. The samples were analyzed for the parameters in List A, Table 3.3-3. Additionally, one of the former monitor wells at the southeast corner of the present landfill (Landfill 6) was also sampled and analyzed for the same parameters. The other two former monitor wells were broken and could not be sampled.

Table 3.3-9. Site 5 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW5-1	25.4	15.4 to 25.4	15.0	6	Gravelly quartz sand
MW5-2	22.5	7.5 to 22.5	8.3	6	Fine to coarse quartz sand and clayey quartz sand
MW5-3	28	8 to 28	9.9	7	Fine to coarse quartz sand; silty, fine to medium quartz sand; and silty, sandy clay
MW5-4	25.5	10.5 to 25.5	4.0	6	Fine to coarse quartz sand and clayey, silty, fine quartz sand

*Measured from top of PVC casing.

Source: ESE, 1985.



3.3.5 SITE 6--C.E. DRUM STORAGE AREA

The C.E. drum storage area has been used for the storage of waste paints and nonignitable mixtures of oil and water.


The objectives of the investigations at Site 6 were to:

1. Determine if the hydrogeologic conditions in the area are conducive to contaminant migration, and
2. Determine if the ground water contains contaminants which could have originated from the storage area.

Three piezometers were installed at Site 6 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the three piezometers are depicted in Fig. 3.3-9. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-10. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels suggested that shallow ground water flow at Site 6 was from west to east, and monitor well locations were selected accordingly. The very subdued hydraulic gradient measured at the site was a reflection of the almost level topography typical of the immediate area.

Three monitor wells were installed at Site 6 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the three wells are depicted in Fig. 3.3-9. The monitor well depths, screened intervals, lithology of the screened intervals, and number of split-spoon soil samples collected are given in Table 3.3-11. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. J.

The soils at Site 6 generally consisted of unconsolidated clays, silts, sands, and gravels through the depths sampled. The upper 23 to 25 ft were comprised almost entirely of stiff, moderately plastic, silty,



**Figure 3.3-9
LOCATIONS OF PIEZOMETERS AND
MONITOR WELLS AT SITE 6, C.E. DRUM STORAGE AREA**

Table 3.3-10. Site 6 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ6-1	31.5	16.5 to 31.5	0	29.54	0
PZ6-2	38.3	23.3 to 38.3	-0.29	29.30	-0.05
PZ6-3	39	24 to 39	-1.51	28.16	-0.13

Source: ESE, 1985.

Table 3.3-11. Site 6 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW6-1	39.6	24.6 to 39.6	29.0	9	Gravelly, fine to coarse quartz sand; silty sand; sandy silt
MW6-2	39.7	24.7 to 39.7	30.0	9	Gravelly, fine to coarse quartz sand; silty sand
MW6-3	40	25 to 40	29.5	9	Gravelly, fine to coarse quartz sand; clayey silt

*Measured from top of PVC casing.

Source: ESE, 1985.

slightly sandy, mottled, gray to brown clays. The clays contained up to 5-percent organic matter in places that existed as small nodules and fracture infillings. Below the clays were 4 to 5.5 ft of silty, micaceous, fine, gray quartz sands and clayey, micaceous gray silts that contained up to 5-percent organic matter. Beneath the fine sands and silts were dense, well-graded, fine to coarse, gravelly, yellow quartz sands that persisted to undetermined depths. Individual cobbles exceeded 2 cm in diameter. A geologic cross section of Site 6 is depicted in Fig. 3.3-10.

The water depth at Site 6 varied from approximately 26.5 ft relative to ground level at MW6-1 to 27.5 ft at MW6-2..


Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are available in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor, as described in Sec. 3.2.3 of this report. The elevation and coordinate values for each well are listed on the map in App. G.


MW6-1 through MW6-3 were sampled according to the procedure described in Sec. 3.2.4 of this report. The samples were analyzed for the parameters in List C, Table 3.3-3.

3.3.6 SITE 7--LANDFILL NO. 2

During the early 1940s through approximately 1951, the base operated Landfill No. 2 for the disposal of household garbage, base trash (paper, wood, scrap metal), and some industrial nonliquid wastes such as waste paints, paint cans, paint booth sludges, and unrinsed pesticide containers (Fig. 3.3-11).



INSTALLATION **RESTORATION PROGRAM** **Maxwell Air Force Base**



The objectives of the investigations at Site 7 were to:

1. Determine the areal extent of the landfill,
2. Determine if hydrogeologic conditions favor contaminant migration, and
3. Determine if contaminants are present in the ground water.

A detailed geophysical survey incorporating magnetometer and EM techniques was completed to delineate the horizontal extent of the landfill and to locate any leachate plumes emanating from the site. The geophysical tracings are located in App. H.

The results of the survey indicated the boundaries of previous landfilling activities and the locations of buried metallic objects. No leachate plumes were detected migrating from the disposal area. These data were used to select the locations for the monitor wells.

Three piezometers were installed at Site 7 to determine the configuration of the water table and predict the direction of shallow ground water flow at the site. The locations of the three piezometers are depicted in Fig. 3.3-11. The piezometer depths, screened intervals, relative casing elevations, absolute water levels, and relative water levels are given in Table 3.3-12. Borehole lithologies are described in the piezometer drilling logs located in App. I. Piezometer water levels suggested that shallow ground water flow at Site 7 was from east-northeast to west-southwest, and monitor well locations were selected accordingly.

Three monitor wells were installed at Site 7 to evaluate the quality of the shallow ground water in the vicinity and to determine whether contaminants were migrating from the site. The locations of the three wells are depicted in Fig. 3.3-11. The monitor well depths, screened intervals, lithology of the screened intervals, and number of split-spoon soil samples collected are given in Table 3.3-13. Individual borehole lithologies are described in detail on the monitor well drilling logs in App. K.

Table 3.3-12. Site 7 Piezometers

Piezometer Number	Depth (ft)	Screened Interval (ft)	Relative Casing Elevation (ft)	Water Depth (ft)	Relative Water Elevation (ft)
PZ7-1	23.5	8.5 to 23.5	0	15.75	0
PZ7-2	22	12 to 22	-4.27	11.55	-0.07
PZ7-3	20.8	10.8 to 20.8	-5.75	10.60	-0.60

Source: ESE, 1985.

Table 3.3-13. Site 7 Monitor Wells

Well Number	Depth (ft)	Screened Interval (ft)	Depth to Water* (ft)	Soil Samples Collected	Screened Interval Lithology
MW7-1	24.3	14.3 to 24.3	15.8	6	Fine to coarse quartz sand
MW7-2	22.3	7.3 to 22.3	13.8	6	Fine to coarse, gravelly quartz sand and fine, silty sand
MW7-3	22	7 to 22	12.7	6	Fine to coarse quartz sand and gravelly quartz sand

*Measured from top of PVC casing.

Source: ESE, 1985.


The soils at Site 7 generally consisted of unconsolidated clays, silts, sands, and gravels through the depths sampled. The surficial soils consisted primarily of 4.5 to 9.5 ft of clayey, silty sands; silty, sandy clays; and clayey, gravelly sands of varying plasticity and density/consistency. Colors ranged from yellow and brown to gray. These soils were underlain by 4 to 9 ft of dense, silty, fine, gray quartz sands and dense, poorly sorted, fine to medium, gray quartz sands. These sands were occasionally yellow in color. Three to 7 ft of loose to dense, well graded, fine to coarse, gray quartz sands were found at subsequent depths, and below these were an unknown thickness of dense, well graded, fine to coarse, gravelly yellow quartz sands. A geologic cross section of Site 7 is depicted in Fig. 3.3-12.

The depth to ground water at Site 7 varied from approximately 10.2 ft relative to ground level at MW7-3 to 14.8 ft at MW7-1.

Each of the four monitor wells was developed as described in Sec. 3.2.3 of this report. Details of the development effort are available in App. L.

The elevations and horizontal coordinates of each of the wells were determined by a licensed surveyor, as described in Sec. 3.2.3 of this report. The elevation and coordinate values for each well are listed on the map in App. G.

MW7-1 through MW7-3 were sampled according to the procedure described in Sec. 3.2.4 of this report. The samples were analyzed for the parameters in List C, Table 3.3-3.



4.0 RESULTS AND SIGNIFICANCE OF FINDINGS

4.1 RELEVANT WATER QUALITY CRITERIA AND STANDARDS

Pursuant to Sec. 1412 of the Public Health Service Act, as amended by the Safe Drinking Water Act (Public Law 93-523), the U.S. Environmental Protection Agency (EPA) has promulgated National Interim Primary Drinking Water Regulations (NIPDWR) (EPA, 1984a) and National Secondary Drinking Water Regulations (NSDWR) (EPA, 1984b). These regulations establish primary and secondary maximum contaminant levels (MCLs) for certain inorganic and organic substances in drinking water. The NIPDWR address contaminants which adversely affect health, while the NSDWR address contaminants that affect aesthetic qualities relating to the acceptance of drinking water. At considerably higher concentrations of the secondary contaminants, health implications may also exist, as well as aesthetic degradation (EPA, 1984a; 1984b).

The State of Alabama has adopted the Federal primary and secondary MCLs as Domestic Water Supply Criteria (at the point of withdrawal) for surface waters of the state (State of Alabama, 1982).

Standards established by these regulations are not directly applicable to the surface waters or ground waters sampled during the MAFB Phase II, Stage 1 survey, as the regulations pertain to public drinking water systems. However, MCLs established by EPA regulations can be used to indicate the quality of the surface waters and ground waters relative to drinking water. The relevant MCLs established by EPA are shown in Table 4.1-1.

EPA (1976) has also developed water quality criteria for the protection of human health and aquatic life, pursuant to Sec. 304 of the Clean Water Act. In 1980, EPA criteria (EPA, 1980) were updated for the 64 toxic pollutants or pollutant categories named in Sec. 307A of the

Table 4.1-1. Relevant Maximum Contaminant Levels (MCLs) for Drinking Water*

Parameter	EPA Drinking Water Standards
	<u>Primary Standards† (ug/l)</u>
Arsenic	50
Barium	1,000
Cadmium	10
Chromium	50
Lead	50
Mercury	2
Nitrate	10,000
Selenium	10
Silver	50
Endrin	0.2
Lindane	4
Methoxychlor	100
Toxaphene	5
2,4-D	100
2,4,5-TP	10
	<u>Secondary Standards** (ug/l except for pH)</u>
Copper	1,000
Iron	300
pH	6.5 - 8.5
Total dissolved solids	500,000
Zinc	5,000

*MCLs are given only for parameters for which analytical results are reported in the MAFB Phase II, Stage 1 study.

†EPA National Interim Primary Drinking Water Regulations.

**EPA National Secondary Drinking Water Regulations.

Source: ESE, 1985.

Clean Water Act, based on evaluation of new toxicological and environmental data and changes in the methodology of hazard/risk assessment. The 1980 criterion for mercury was additionally revised in 1981 (EPA, 1981). The 1980 and 1981 EPA criteria supersede the 1976 criteria for the 64 toxic compounds, since the former were evaluated by more advanced methodology. The new EPA criteria considered the acute and chronic adverse effects of water pollutants on aquatic organisms, nonhuman mammals, and humans and have been designed to protect aquatic life and humans from effects of exposure to the pollutants.

The level of protection afforded aquatic organisms by the 1980 and 1981 EPA criteria is that most aquatic life would be protected and aquatic ecosystem functions would be preserved but that a few untested species might be adversely affected if the highest allowable concentrations persisted for long periods of time. The 1980 and 1981 EPA criteria specify concentrations both in terms of 24-hour averages and maximum concentrations not to be exceeded at any time. Since the sampling program in the MAFB Phase II, Stage 1 survey did not quantify 24-hour averages, assessment of potential effects on aquatic life has been made by comparison to EPA criteria, which are the maximum allowable concentrations at any time.

The State of Alabama has promulgated water quality standards for the protection of aquatic life. The latest revisions of these standards in 1982 are based on the 1976 EPA criteria (EPA, 1976) and the revised EPA criteria (EPA, 1980; EPA, 1981c), which relaxed some of the limits (notably mercury). Assessment of the significance of the effects on aquatic life due to contaminants at MAFB takes into account the new Federal criteria. The Alabama standards do not identify specific MCLs for toxic substances, only that such substances shall not be present in amounts that would be deleterious or interfere with designated beneficial uses. Federal criteria provide these guidelines.

Human-health criteria have been incorporated by EPA into the 1980 and 1981 criteria, based on the carcinogenic, toxic, or organoleptic (taste and odor) properties of the 64 toxic pollutants. For noncarcinogens, the criteria have been based on the prevention of adverse health effects in humans due to toxicity. In the case of suspected or known carcinogens, the criteria represent incremental increases in the cancer risk to exposed populations. In assessing the human-health significance of contaminants at MAFB, the incremental risk level chosen was 10^{-6} . This level is the concentration of a specific contaminant, which is projected by the EPA risk analysis to potentially increase the incidence of cancer by no more than one case per 1,000,000 individuals. The applicable human-health criteria (for human consumption of water and organisms taken from water containing the contaminant), along with the criteria for the protection of freshwater aquatic life for the principal contaminants analyzed for at MAFB, are shown in Table 4.1-2. The methodology for development of the criteria for protection of both human health and aquatic life are summarized in EPA (1980). No sediment criteria have been developed.

Ground water samples collected at MAFB were taken from the unconsolidated deposits underlying the study sites. Ground water in this formation could discharge to downgradient surface drainages and thus form a component of the surface water base flow. The surface waters of MAFB, natural drainages, and channelized natural drainages all discharge directly or indirectly into the Alabama River. The Alabama River, the reach adjacent and immediately downstream from MAFB, is classified for beneficial usage, including wildlife and aquatic life usage and propagation, and recreation (State of Alabama, 1982).

The Alabama River in the reach adjacent and downstream of MAFB is commonly used for recreation, including sport fishing, and for limited commercial fishing. For these reasons, the following criteria have generally been considered the critical concentrations upon which assessment of significant contamination is based: (1) the maximum

Table 4.1-2. Relevant EPA Water Quality Criteria

Parameter	Criteria for Freshwater Aquatic Life (ug/l)				Human-Health Criteria (ug/l)		
	Acute Toxicity Level	Chronic Toxicity Level	Maximum 24-hour Average	Maximum Concentration	Potable Water Taste/Odor Control†	Ingestion of Water and Aquatic Organisms	
						Ambient Criterion	10 ⁻⁶ Incremental Cancer Risk
Cadmium			0.012**	1.5		10	
Chromium, trivalent		44		2,200**		170,000	
Chromium, hexavalent			0.29	21		50	
Lead			0.75**	74**		50	
Nickel			56**	1,100**		13.4	
Zinc			47	180	5,000		
Arsenic, trivalent				440		0††	0.0022
Copper			5.6**	12**	1,000		
Mercury			0.20	4.1		0.144	
Silver		0.12		1.2		50	
Endrin			0.0023	0.18		1	
Toxaphene			0.013	1.6		0††	0.00071
Cyanide			3.5	52		200	
BHC, G (Lindane)	100		0.080	2		0††	0.186
Selenium	760		35	260		10	
Phenol	10,200	2,560			300	3,500	

*Toxicity may occur at lower concentrations among species more sensitive than those tested. Zero level may not be attainable.

†Organoleptic data used as basis for taste and odor control have no demonstrated relationship to adverse human-health effects.

**Based on calculation with assumed water hardness of 50 mg/l.

††Zero level may not be attainable.

Source: ESE, 1985.

drinking water contaminant level, (2) the criterion for protection of freshwater aquatic life, or (3) the criterion for protecting human health when both aquatic organisms and water are ingested.

4.2 ANALYTICAL RESULTS

Sample collections and in situ measurements were performed between Jan. 14 and Jan. 19, 1985. Samples were split and sent to the ESE laboratory in Gainesville, Fla., and the OEHL laboratory at Brooks AFB in San Antonio, Tex. Chain-of-custody data are presented in App. N. All proposed analyses were performed by the ESE laboratory. Analytical methods used and the detection limits are presented in Table 4.2-1.

The detectable concentrations of various analytes in ground waters, surface waters, and sediments are found in Sec. 4.3. Representative quality assurance/quality control (QA/QC) data for the various analytes are presented in Tables 4.2-1 and 4.2-2. A summary of additional QA/QC control data generated during the various chemical analyses performed for this project are found in App. O.

4.3 GENERAL DISCUSSION

Results of analyses on environmental samples collected during the MAFB Phase IIa survey are discussed in terms of relevant water quality standards and criteria whenever possible. Ground waters sampled during the survey are not classified by any State of Alabama or Federal regulations. They will be compared to the NIPDWR and NSDWR MCLs. Of the parameters analyzed in this survey, MCLs are established for all the parameters listed in Table 4.1-1.

Where MCLs are not available for direct comparison, EPA criteria for surface water nearest the site can be used to compare with ground water quality. This is an indirect comparison, and in order to estimate the

Table 4.2-1. Analytical Methods, Detection Limits, and Representative Quality Assurance/Quality Control Data (Continued, Page 2 of 2)

Parameter	Method	Units	Detection Limit	Spiked Sample	Target Value	Pound Value	Percent Recovery	Replicate Sample	First Value	Second Value	Method Blank
Mercury	EPA 265.1	µg/l µg/g-soil	0.2 µg/l 0.07 µg/g-soil	469508	5.0	4.6	92	469501	*	*	*
Iron	EPA 200.7	µg/l	4 µg/l	469400	100	105	105	469509	*	*	*
Sulfate	EPA 375.4	mg/l	1 mg/l	469509	3.8	4.1	107	469500	20.5	18.4	*
Barium	EPA 200.7	µg/l	5 µg/l	469400	100	104	104	469500	30.2	30.1	*
Fluoride	EPA 340.2	mg/l	0.1 mg/l	469509	0.99	0.89	90	469501	0.066	0.060	*
Nitrate	EPA 353.2	mg/l	0.01 mg/l	469500	0.125	0.123	98	469500	0.085	0.085	*
Selenium	EPA 270.3	µg/l	1 µg/l	469516	5.0	5.4	108	469503	*	*	*
Silver	EPA 200.7	µg/l	5 µg/l	469509	100	109	109	469500	*	*	*
Endrin	EPA 608	µg/l	0.005 µg/l	Laboratory pure water	0.043	0.040	93	469500	*	*	*
Lindane	EPA 608	µg/l	0.001 µg/l	Laboratory pure water	0.023	0.018	78	469500	*	*	*
Methoxychlor	EPA 608	µg/l	0.027 µg/l	Laboratory pure water	0.23	0.21	91	469500	*	*	*
Toxaphene	EPA 608	µg/l	0.120 µg/l	NA	NA	NA	NA	469500	*	*	*
2,4-D	EPA 615	µg/l	0.030 µg/l	Laboratory pure water	0.41	0.30	73	469500	*	*	*
2,4,5-TP	EPA 615	µg/l	0.007 µg/l	Laboratory pure water	0.094	0.070	74	469500	*	*	*
pH	EPA 150.1	Standard units	NA	NA	NA	NA	NA	469508	5.3	5.3	NA

NA = Not applicable.

* = Below detection.

Use Table 4.2-2 for quality control data for the eight EP toxicity metals.

Source: ESR, 1985.

Table 4.2-1. Analytical Methods, Detection Limits, and Representative Quality Assurance/Quality Control Data

Parameter	Method	Units	Detection Limit	Spiked Sample	Target Value	Found Value	Percent Recovery	Replicate Sample Value	First Value	Second Value	Method Blank
Total Organic Carbon (TOC)	EPA 415.1	mg/l µg/g-soil	1 mg/l 1,000 µg/g-soil	469517	50	53	106	469516	1.6	1.8	*
EP Toxicity	40 CFR 261.24	µg/l	1	1	1	1	1	1	1	1	1
Ignitability	40 CFR 261.21	deg-C	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total Organic Halogens (TOX)	EPA 9100	µg/l µg/g-soil	5 µg/l 5 µg/g-soil	469517	250	283	113	469508	32.4	31.3	*
Oil and Grease	EPA 413.2	mg/l µg/g-soil	0.1 mg/l 100 µg/g-soil	Laboratory pure water	18.3	17.1	94	469300	354	334	*
Total Dissolved Solids	EPA 169.1	mg/l	1 mg/l	NA	NA	NA	NA	469480	65	69	NA
Copper	EPA 200.7	µg/l µg/g-soil	3 µg/l 2 µg/g-soil	469408	100	99.9	99.9	469403	17.3	16.3	*
Nickel	EPA 200.7	µg/l µg/g-soil	9 µg/l 0.5 µg/g-soil	469500	100	102	102	469500	*	*	*
Cadmium	EPA 200.7	µg/l µg/g-soil	3 µg/l 0.1 µg/g-soil	469509	100	109	109	469500	*	*	*
Chromium	EPA 400.7	µg/l µg/g-soil	6 µg/l 3 µg/g-soil	469500	100	96.7	96.7	469500	*	*	*
Cyanide	EPA 335.2	µg/l µg/g-soil	10 µg/l 0.7 µg/g-soil	469510	19.9	18.5	92.7	469510	*	*	*
Zinc	EPA 200.7	µg/l µg/g-soil	3 µg/l 0.5 µg/g-soil	469400	100	111	111	469500	49	47	*
Phosphate	EPA 420.1	µg/l µg/g-soil	1 µg/l 1 µg/g-soil	469515	59.6	57.0	95.7	469510	1.6	1.7	*
Lead	EPA 239.2 (waters) EPA 200.7 (soils)	µg/l µg/g-soil	20 µg/l 2 µg/g-soil	469511	25.0	26.4	106	469502	*	*	*
Asbestos	EPA 210.3	µg/l µg/g-soil	1 µg/l 1 µg/g-soil	469517	5.0	4.9	98	469505	*	*	*

Table 4.2-2. Representative Quality Control Data--RCRA EP Toxicity Metals

Parameter	Detection Limit (ug/l)	Spiked Sample	Target Value	Found Value	Percent Recovery	Replicate Sample	First Value	Second Value	Method Blank
Arsenic	1.0	484900	5.0	3.8	76	484900	*	*	*
Barium	1.0	484900	538	473	88	484900	871	876	*
Cadmium	3.0	484900	100	109	109	484900	*	*	*
Chromium	6.0	484900	100	86	86	484900	*	*	*
Lead	20	484900	100	106	106	484900	*	*	*
Mercury	1.0	484900	5.0	5.1	102	484900	*	*	*
Selenium	1.0	484900	100	98	98	484900	*	*	*
Silver	5.0	484900	100	109	109	484900	*	*	*

*Below detection.

Source: ESE, 1985.

potential impact of ground water quality on the receiving surface water, the following factors must be taken into account:

1. Rate of migration of any contaminant from shallow ground water to the adjacent surface water, and
2. Fate of the contaminant once it reaches the surface water (e.g., degree of dispersion or mixing, degree of dissolution, adsorption on sediments or vegetation).

With the limited data available for the MAFB Phase II, Stage 1 sites, these factors cannot be quantified. Thus, if ground water concentrations of pollutants exceed adjacent surface water criteria, it cannot be said with certainty that the surface water will be adversely impacted. However, if ground water parameters are within adjacent surface water criteria, it can be stated with certainty that the surface water criteria will not be exceeded due to local ground water discharge.

EPA water quality criteria are listed in Table 4.1-2 for metals, pesticides, cyanide, and phenolic compounds. EPA water quality criteria are not established for all compounds analyzed in the MAFB Phase II, Stage 1 survey.

There are no criteria or standards for direct evaluation of TOX data. If used in a rigorous manner [e.g., Resource Conservation and Recovery Act (RCRA) ground water compliance monitoring], extensive background data are required to determine statistically whether monitoring well levels are significantly higher than background well levels. When used as a screening indicator, as is the case with the MAFB Phase II, Stage 1 survey, such data are not available.

Because TOX concentrations were found in all monitor wells, including the background monitor wells, the MAFB Phase II, Stage 1 TOX results may be indicative of background levels or may indicate a positive interference in the analysis. If an interference is responsible for the concentration indicated, this positive interference may be due to the

presence of inorganic halides (e.g., chlorides) in the samples. Inorganic chlorides were not determined but are commonly found in ground water leaching from landfill areas. The TOX analysis was developed as a screening analysis for drinking water and was adopted by EPA for landfill monitoring. It has since been found that the TOX analysis is subject to positive matrix interferences, particularly inorganic halides (Dressman, 1984). Documentation on the magnitude of these interferences is not currently available in the literature.

The analytical method for TOX consists of:

1. Passing the sample through a carbon column to adsorb all organics, including halogenated organics;
2. Washing the carbon column with a potassium nitrate solution to reduce the concentrations of inorganics, especially chlorides;
3. Heating of the carbon column, including the adsorbed organics, to convert any chlorinated organics into inorganic chlorides; and
4. Coulometrically measuring the concentrations of chlorides (compared to chlorinated phenol used as a standard).

Theoretically this method should detect all organic halogens including organochlorine pesticides, chlorinated phenols, and volatile organohalogens. Although this method is designed to reduce the interference by inorganic halides, the possibility exists that some interferences can remain (i.e., if the water sample contains 10 mg/l as chloride and the potassium nitrate rinse is 99.9-percent efficient, a positive TOX value of 10 ug/l would be obtained). There are no data available to establish background levels of TOX in the MAFB area. Because the TOX method is used for screening and the identification of potential problems from high-level concentrations of organic solvents (e.g., tetrachloroethylene, trichloroethylene, etc.) leaching into the ground waters or surface waters from landfills, the detection of low levels of TOX may not be indicative of contamination. Because there are no standards promulgated for the direct evaluation of TOX, an arbitrary

concentration must be established to use as a guideline in determining if a potential contamination problem exists. The MCL for drinking water may be used to establish this arbitrary concentration. A drinking water standard of 100 ug/l for trihalomethanes (e.g., chloroform) has been established by EPA. This concentration would represent a TOX value of 29.7 ug/l (as converted from chloroform). If the assumption is made that the chloride concentrations in the samples are at least 10 mg/l and a positive interference of 10 ug/l can occur, a reasonable arbitrary TOX value of 40 ug/l can be established as the guideline. The TOX value of 40 ug/l will be used in this report as an indicator of the potential presence of contaminants and the possibility that additional analyses may be required.

Inspection of the MAFB data indicates that TOX analyses fall in the range of 10 to 88 micrograms per liter (ug/l), with only five water samples exceeding 40 ug/l. Some or all of the TOX could be a result of positive interference. Because the data are insufficient to verify the presence of interferences or to quantify their magnitude, additional analyses (purgeable aromatics and organic halogens, EPA Methods 601 and 602) will be required.

TOC is a measure of both biodegradable and nonbiodegradable organic carbon in water. TOC can be used as an indicator for organic contaminants leaching from landfills, oil spills, etc. and contaminating surface water or ground water. There are no criteria or standards for direct evaluation of TOC data since the source of background organic carbon levels varies from site to site. Background TOC concentrations in natural water samples can vary widely, depending primarily on the rate of decomposition of organic matter in the soil. Background TOC concentrations at MAFB are probably in the range of 10 to 12 mg/l. TOC data for this survey are evaluated subjectively as an indication of general organic contamination.

4.3.1 SITE 1--ELECTROPLATING WASTE DISPOSAL AREAS

Detectable concentrations of various analytes in the ground water from MW1-1, MW1-2, MW1-3, and MW1-4 are presented in Fig. 4.3-1. In addition, all analytical data from the analysis of ground water at Site 1 is presented as Table 4.3-1. The entire data set for all ground water samples analyzed during this study is presented in App. O.

The pH values determined at this site vary from 4.8 to 6.6. NSDWR regulations specify that acceptable pH values should range between 6.5 and 8.5, unless affected by natural conditions. A comparison of the pH values at Site 1 with values from other locations on the base indicates that the shallow ground water on MAFB tends to be acidic. Therefore, the pH values less than 6.5 are not indicative of contamination problems.

Analyses for metals used in the plating process (e.g., Cd, Cr, Cu, Ni) and cyanides did not yield any concentrations above the detection limit. This does not assure that the metals are not present in the disposal area but only indicates they are not present in the ground water at this time.

Concentrations of Zn varying from <3.0 ug/l to 54.0 ug/l were detected in the ground water. These concentrations are very low and are well below the 5,000-ug/l NSDWR MCL and the 180-ug/l maximum criterion for the protection of aquatic life.

TOC values for the four wells vary from 2.5 to 5.1 mg/l. These data do not indicate the availability of any large sources of organic carbon in the disposal area at the time of sampling. Because the background TOC for MAFB probably ranges to a high of 12 mg/l, these samples at Site 1 are indicative of background levels.

Phenols ranged from 4 ug/l in ground waters from MW1-2 and MW1-3 to 7 ug/l at MW1-4 and 12 ug/l at MW1-1. These values are well below the




Table 4.3-1. Analytical Results for Ground Water Samples from Site 1

Parameters	GW1-1*	GW1-2	GW1-3	GW1-4
pH, field (std units)	6.60	4.80	5.80	4.90
Cadmium, diss. (ug/l)	ND†	ND	ND	ND
Chromium, diss. (ug/l)	ND	ND	ND	ND
Copper, diss. (ug/l)	ND	ND	ND	ND
Nickel, diss. (ug/l)	ND	ND	ND	ND
Zinc, diss. (ug/l)	ND	21.0	54.0	12.0
Carbon, TOC (mg/l)	2.5	5.1	2.7	4.4
Phenols (ug/l)	12	4	4	7
Residue, diss. (mg/l)	54	153	26	80
Sp. Cond., field (umhos/cm)	75.0	203	95.0	77.0
Water Temp. (°C)	19.2	17.0	18.1	17.5
Cyanide (ug/l)	ND	ND	ND	ND

*GW1-1 indicates a ground water sample from Monitor Well 1 at Site 1.
†ND = Not detected.

Source: ESE, 1985.

acute toxicity level, chronic toxicity level, and the human-health criteria established by EPA.

The specific conductance values indicate a specific conductance in MW1-2 which is slightly higher than the other wells. MW1-2 is downgradient of the disposal site and could be expected to have an elevated conductivity if any contaminants are migrating from the disposal site. The entire data set for the chemical analyses performed is presented in App. O.

4.3.2 SITE 2--SURFACE DRAINAGE SYSTEM FOR MAFB

Surface Waters

Surface water samples were collected at four locations on MAFB. These locations along with detectable concentrations of various pollutants are shown in Fig. 4.3-2. The data for all surface water analyses are presented as Table 4.3-2. The results of all surface water analyses completed at MAFB during this study are presented in App. O.

Arsenic (As) values varying from 6 to 30 ug/l were detected in surface waters from the point where the West End Ditch enters MAFB to a point downstream of Sites 1, 3, and 5. The As concentrations have been reported in previous surface water samples collected in other surface water drainage ditches (ES, 1984). The concentrations determined in this present study are below the 50-ug/l MCL established by NIPDWR. The As was determined as total As, and no attempt was made to detect concentrations based on valence state. If all the As were in the trivalent state, it would not exceed the criteria for the protection of freshwater aquatic life, but would exceed the human health standards. The source of As is unknown, but could originate either off or on MAFB since it is found in both offbase and onbase samples.

Chromium (Cr) concentrations of <6 ug/l to 8.1 ug/l were determined. No attempt was made to determine the Cr concentrations with respect to valence state. Regardless of the valence state, Cr concentrations are




Figure 4.3-2
DETECTABLE CONCENTRATIONS OF VARIOUS
ANALYTES IN SURFACE WATERS ON MAFB, SITE 2

Table 4.3-2. Analytical Results for Surface Waters from Site 2

Parameters/Sample Location	SW2-1*	SW2-2	SW2-3	SW2-4
Arsenic, total (ug/l)	6.0	23	30	25
Cadmium, total (ug/l)	ND†	ND	ND	ND
Chromium, total (ug/L)	ND	8.1	ND	7.5
Mercury, total (ug/l)	ND	ND	ND	0.7
Nickel, total (ug/l)	ND	ND	ND	ND
Lead, total (ug/l)	26.1	25.0	30.2	37.0
Zinc, total (ug/l)	57	117	66	110
Residue, diss. (mg/l)	67	87	82	68
Phenols (ug/l)	8	8	6	11
Oil & Grease, IR (mg/l)	ND	0.8	0.8	0.9
TOX (ug/l-CL)	88	80	82	45
Carbon, TOC (mg/l)	11.9	12.8	12.9	13.5
Sp. Cond., lab (umho/cm)	63.0	96.8	82.8	63.0
Cyanide (ug/l)	ND	ND	ND	ND

*SW2-1 indicates a surface water sample from Location 1 at Site 2.

†ND = Not detected.

Source: ESE, 1985.

below the maximum concentration allowable under NIPDWR (50 ug/l) and the criteria for the protection of freshwater aquatic life (21 ug/l for hexavalent and 2,200 ug/l for trivalent). The low levels of Cr may be from natural sources (clays at MAFB).

Mercury (Hg) was detected (0.7 ug/l) in sample SW-4 downstream from Sites 1, 3, and 5. This concentration is less than allowable under NIPDWR but exceeds concentration criteria for the protection of human health (0.14 ug/l) and freshwater aquatic life (maximum 24-hour average of 0.2 ug/l). Hg has not been reported in previous samples of surface water at MAFB.

Lead (Pb) values vary from 25 to 37 ug/l. These values are less than the NIPDWR standard of 50 ug/l and the 74-ug/l maximum concentration allowable for the protection of freshwater aquatic life. The Pb concentrations may represent background values. However, the surface runoff from an adjacent highway may contribute to the Pb concentrations. Pb concentrations have been reported in previous surface water samples from MAFB.

Zinc (Zn) concentrations ranging from 57 ug/l to 117 ug/l were detected. These values are within the standards allowed and probably represent background concentrations of Zn.

Phenol concentrations ranged from 6 ug/l to 11 ug/l. These values are within the standards allowed and probably represent background concentrations.

Oil and grease concentrations were determined to range from <0.1 mg/l to 0.9 mg/l. No standards are available for this parameter; however, concentrations less than 1 mg/l are usually considered to be background levels.

TOX concentrations were determined to range from 45 ug/l to 88 ug/l, with the highest concentration found at the point where West End Ditch enters MAFB. The TOX concentrations determined are above the arbitrary

value of 40 ug/l, which was selected to designate a positive response. Therefore, these samples may contain chlorinated organic compounds as contaminants. Since these data are insufficient to verify the presence of interferences or to quantify their magnitude, additional analyses [purgeable aromatics and organic halogens (EPA Methods 601 and 602)] will be required.

TOC concentrations ranged from 11.9 mg/l to 13.5 mg/l. These concentrations approximate the background levels of 10 to 12 mg/l present at MAFB. These concentrations at or slightly above the background may reflect the influence of organics being washed from an adjacent highway.

Sediments

The concentrations of the various analytes found in the sediment samples are presented in Table 4.3-3. Many of these analytes are generally representative of background levels of the various constituents. It should be noted, however, that Hg concentrations of 0.47 microgram per gram (ug/g) and 0.21 ug/g were determined at sampling locations S2-4 and S2-11 (see Fig. 4.3-3).

In addition, Pb concentrations at locations S2-3, S2-4, S2-6, S2-7, S2-8, and S2-11 were determined to range from 77 to 380 ug/g. The source of the lead may be runoff from areas where MOGAS or AVGAS was used for fire training activities and disposed of in landfills. In addition, this stream flows adjacent to a highway, and surface runoff containing particulate lead from gasoline engines would enter the stream and be deposited in the sediments. The results of all sediment analyses completed as part of this study at MAFB are also presented in App. O. In addition, the analytical results for all samples are presented in Table 4.3-4.

Table 4.3-3. Analytical Results for MAFB Sediment Samples

Parameters	Sample Numbers										
	S2-1	S2-2	S2-3	S2-4	S2-5	S2-6	S2-7	S2-8	S2-9	S2-10	S2-11
Moisture (% wet wt)	26.0	23.0	19.0	39.0	29.0	28.0	40.0	34.0	26.0	22.0	26.0
Cadmium, sed (ug/g-dry*)	0.3	0.2	0.4	0.9	0.3	1.0	0.8	0.9	0.3	0.3	0.4
Chromium, sed (ug/g-dry)	9.8	3.3	11.2	20.8	16.0	16.0	27.6	26.1	13.0	15.1	14.8
Copper, sed (ug/g-dry)	11	3	14	28	24	27	33	26	8	8	17
Mercury, sed (ug/g-dry)	ND†	ND	ND	0.47	ND	ND	ND	ND	ND	ND	0.21
Nickel, sed (ug/g-dry)	2	0.6	3	8	5	6	11	7	4	5	5
Lead, sed (ug/g-dry)	51	12	100	99	39	120	380	280	41	43	77
Zinc, sed (ug/g-dry)	22	6	46	116	63	149	334	118	39	36	72
Cyanide, sed (ug/g-dry)	ND	ND	ND	1	ND	ND	0.8	0.8	0.8	ND	ND
Arsenic, sed (ug/g-dry)	7.4	3.6	4.0	7.1	2.0	7.3	3.6	3.4	1.1	1.4	1.5
Phenols, sed (ug/g-dry)	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TOX**, sed (ug/g-dry)	ND	ND	ND	ND	ND	ND	5.70	ND	ND	ND	ND
TOC††, sed (ug/g-dry)	1760	3120	4320	17400	5490	19600	7500	22300	6490	5380	5810


*ug/g = micrograms per gram.

†ND = Not detected.

**TOX = Total organic halogen.

††TOC = Total organic carbon.

Source: ESE, 1985.



4.3.3 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3

The locations of the sampling points and detectable concentrations of various analytes at Site 3 are presented in Fig. 4.3-4. The pH values determined for these samples (5.2 through 5.9) are outside the range recommended (6.5 to 8.5) by NSDWR. The values seem typical for the MAFB ground water and probably represent background levels.

Concentrations of barium (Ba), Zn, iron (Fe), nitrate (NO₃), and sulfate (SO₄) were detected in samples from Site 3. None of these parameters, except Fe in MW3-1, exceeded NIPDWR or NSDWR standards or the criteria for the protection of freshwater aquatic life or human health. Fe, detected at a concentration of 568 ug/l, exceeded the NSDWR standard of 300 ug/l. The concentrations determined are probably representative of background levels.

Phenol values were determined to vary from <1 ug/l to 6 ug/l. These values are probably representative of background levels.

TOX values of 21 to 32 ug/l were detected in ground waters at Site 3. These values do not necessarily indicate the presence of significant chlorinated organic compounds, as positive interferences may be represented.

TOC concentrations range from 1.4 mg/l to 3.5 mg/l. These concentrations are considered background levels for the site.

Lindane was detected at concentrations of 0.17 and 1.3 ug/l in downgradient wells 3-3 and 3-2, respectively. Analyses were performed using a second GC column to confirm the existence of lindane in the samples. The second column was used to confirm the presence of the lindane in the sample. Lindane concentrations were not calculated from the second column chromatogram because the second column is normally used only to confirm the presence of a compound.


Table 4.3-4. Analytical Results for Ground Water Samples from Site 3

Parameters	Sample Location		
	GW 3-1	GW 3-2	GW 3-3
pH, field (std units)	5.60	5.20	5.90
Arsenic, diss. (ug/l)	ND†	ND	ND
Barium, diss. (ug/l)	30	19	33
Cadmium, diss. (ug/l)	ND	ND	ND
Copper, diss. (ug/l)	ND	ND	ND
Chromium, diss. (ug/l)	ND	ND	ND
Iron, diss. (ug/l)	568	70	91
Mercury, diss. (ug/l)	ND	ND	ND
Nickel, diss. (ug/l)	ND	ND	ND
Lead, diss. (ug/l)	ND	ND	ND
Silver, diss. (ug/l)	ND	ND	ND
Zinc, diss. (ug/l)	48.7	ND	17.8
Nitrogen, NO ₂ + NO ₃ (mg/l-as N)	0.085	0.712	0.655
Sulfate (mg/l)	41	14	43
Residue, diss. (mg/l)	101	55	145
Phenols (ug/l)	6	ND	6
Oil & Grease, IR (mg/l)	ND	ND	ND
TOX (ug/l-CL)	32	25	21
Carbon, TOC (mg/l)	3.5	1.4	3.2
Endrin (ug/l)	ND	ND	ND
BHC,G (Lindane)(ug/l)	ND	1.3	0.17
Methoxychlor (ug/l)	ND	ND	ND
Toxaphene (ug/l)	ND	ND	ND
2,4-D, total (ug/l)	ND	ND	ND
2,4,5-TP/silvex (ug/l)	ND	ND	ND
Fluoride (mg/l)	0.15	ND	0.11
Sp. Cond., field (umhos/cm)	91.0	67.0	264
Water Temp. (°C)	17.0	17.6	16.4
Selenium, diss. (ug/l)	ND	ND	ND
Cyanide (ug/l)	ND	ND	ND

*GW3-1 indicates a ground water sample from Monitor Well 1 at Site 3.

†ND = Not detected.

Source: ESE, 1985.



The lindane values obtained are less than the 4-ug/l criterion promulgated under NIPDWR but exceed the concentrations recommended for the protection of human health. The detection of lindane is indicative of low-level ground water contamination, probably from items formerly buried in Landfill No. 3.

4.3.4 SITE 4--FPTA NO. 1

The locations of MW4-1, 4-2, and 4-3, along with detectable concentrations of various analytes, are presented in Fig. 4.3-5. In addition, the analytical results for all ground water samples from Site 4 are presented in Table 4.3-5.

As with prior sites discussed, the pH values at Site 4 are less than the recommended range under NSDWR. This is indicative of the acidic-trending ground water found under the installation.

Low-level concentrations of Ba, Fe, Zn, NO₃, SO₄, and phenols were detected at Site No. 4. The concentrations detected were all less than applicable standards or criteria and probably represent background levels.

TOX concentrations ranging from 16 to 26 ug/l were determined. These concentrations do not necessarily represent high concentrations of chlorinated organic compounds, since positive interferences may be occurring.

TOC values ranged from 1.9 to 4.9 mg/l and are not indicative of large sources of available organic carbon in the ground water. These concentrations are probably representative of background levels.

4.3.5 SITE 5--LANDFILLS 4, 5, AND 6

The locations of MW5-1 through MW5-5, along with detectable concentrations of various analytes, are presented in Fig. 4.3-6. The analytical results for all ground water samples collected at Site 5 are presented in Table 4.3-6.

Table 4.3-5. Analytical Results for Ground Water Samples from Site 4

Parameters	Sample Location		
	GW4-1*	GW4-2	GW4-3
pH, field (std units)	5.60	5.50	5.20
Arsenic, diss. (ug/l)	ND†	ND	ND
Barium, diss. (ug/l)	74	32	22
Cadmium, diss. (ug/l)	ND	ND	ND
Copper, diss. (ug/l)	ND	ND	ND
Chromium, diss. (ug/l)	ND	ND	ND
Iron, diss. (ug/l)	5	ND	ND
Mercury, diss. (ug/l)	ND	ND	ND
Nickel, diss. (ug/l)	ND	ND	ND
Lead, diss. (ug/l)	ND	ND	ND
Silver, diss. (ug/l)	ND	ND	ND
Zinc, diss. (ug/l)	5.6	ND	ND
Nitrogen, NO ₂ + NO ₃ (mg/l-as N)	0.802	0.567	0.749
Sulfate (mg/l)	80	60	150
Residue, diss. (mg/l)	121	69	76
Phenols (ug/l)	8	1	3
Oil & Grease, IR (mg/l)	ND	ND	ND
TOX (ug/l-CL)	26	20	16
Carbon, TOC (mg/l)	4.9	1.9	2.8
Endrin (ug/l)	ND	ND	ND
BHC,G (Lindane)(ug/l)	ND	ND	ND
Methoxychlor (ug/l)	ND	ND	ND
Toxaphene (ug/l)	ND	ND	ND
2,4-D, total (ug/l)	ND	ND	ND
2,4,5-TP/silvex (ug/l)	ND	ND	ND
Fluoride (mg/l)	ND	ND	0.12
Sp. Cond., field (umhos/cm)	149	88.0	92.0
Water Temp. (°C)	19.0	19.9	17.1
Selenium, diss. (ug/l)	ND	ND	ND
Cyanide (ug/l)	ND	ND	ND

*GW4-1 indicates a ground water sample from Monitor Well 1 at Site 4.
†ND = Not detected.

Source: ESE, 1985.




Figure 4.3-6
DETECTABLE CONCENTRATIONS OF
VARIOUS ANALYTES IN GROUND WATERS
AT SITE 5, LANDFILLS 4, 5, AND 6

INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base

Table 4.3-6. Analytical Results for Ground Water Samples from Site 5

Parameters	Sample Location				
	GW5-1*	GW5-2	GW5-3	GW5-4	GW5-5
pH, field (std units)	5.70	5.30	5.70	4.80	4.60
Arsenic, diss. (ug/l)	ND†	ND	ND	ND	ND
Barium, diss. (ug/l)	19	41	25	26	23
Cadmium, diss. (ug/l)	ND	ND	ND	ND	ND
Copper, diss. (ug/l)	ND	ND	ND	ND	ND
Chromium, diss. (ug/l)	ND	ND	ND	ND	ND
Iron, diss. (ug/l)	60	22	199	253	<4
Mercury, diss. (ug/l)	ND	ND	ND	ND	ND
Nickel, diss. (ug/l)	ND	ND	ND	ND	ND
Lead, diss. (ug/l)	ND	ND	ND	ND	ND
Silver, diss. (ug/l)	ND	ND	ND	ND	ND
Zinc, diss. (ug/l)	ND	10.6	21.3	ND	3.8
Nitrogen, NO ₂ + NO ₃ (mg/l-as N)	0.462	0.252	0.597	1.03	0.360
Sulfate (mg/l)	18	27	44	11	30
Residue, diss. (mg/l)	92	122	150	63	74
Phenols (ug/l)	3	2	5	2	3
Oil & Grease, IR (mg/l)	ND	ND	ND	ND	ND
TOX (ug/l-CL)	34	32	36	49	23
Carbon, TOC (mg/l)	1.4	3.4	3.2	<1.4	ND
Endrin (ug/l)	ND	ND	ND	ND	ND
BHC,G (Lindane)(ug/l)	0.17	0.26	1.3	1.5	0.34
Methoxychlor (ug/l)	ND	ND	ND	ND	ND
Toxaphene (ug/L)	ND	ND	ND	ND	ND
2,4,5-TP/silvex (ug/l)	ND	ND	ND	ND	ND
2,4-D, Total (ug/L)	ND	ND	ND	ND	ND
Fluoride (mg/l)	0.14	ND	ND	ND	ND
Sp. Cond., field (umhos/cm)	146	186	170	79.0	36.0
Water Temp. (°C)	16.7	17.5	18.1	16.6	16.1
Selenium, diss. (ug/l)	ND	ND	ND	ND	ND
Cyanide (ug/l)	ND	ND	ND	ND	ND

*GW5-1 indicates a ground water sample from Monitor Well 1 at Site 5.

†ND = Not detected.

Source: ESE, 1985.

The pH values for ground waters at Site 5 vary from 4.6 to 5.7. These values are considered to be representative of the background pH.

Concentrations of Ba, Fe, Zn, NO₃, SO₄, and phenols are detectable in many of the wells at Site 5. The concentrations detected are less than the standards for NIPDWR and NSDWR or the criteria for protection of freshwater aquatic life or human health. The concentrations detected are representative of background levels.

TOX values range from 23 to 49 ug/l. The 49-ug/l concentration was detected in the well (MW5-4) immediately adjacent to and downgradient of the current landfill. This value may be indicative of the presence of chlorinated organic compounds as contaminants. Additional analyses (EPA Methods 601 and 602) will be required to confirm these results.

TOC values at Site 5 vary from <1.4 mg/l to 3.4 mg/l. These values are considered background and do not indicate a large availability of organic carbon in the ground waters downgradient from the site. The pesticide lindane was detected in the ground water samples from all five monitor wells at concentrations ranging from 0.17 ug/l to 1.5 ug/l. This indicates low-level contamination of the ground waters at Site 5. The concentrations detected are less than allowable under NIPDWR standards; however, they do exceed the maxima recommended for the protection of human health. These waters are not used on MAFB as a source of drinking water, and no private potable wells are located downgradient of this site.

4.3.6 SITE 6--C.E. DRUM STORAGE AREA

The locations of MW6-1, MW6-2, and MW6-3 and detectable concentrations of various analytes in the ground water at Site 6 are presented in Fig. 4.3-7. The analytical results for all ground water samples from Site 6 are presented in Table 4.3-7.




Table 4.3-7. Analytical Results for Ground Water Samples from Site 6

Parameters	Sample Location		
	GW6-1*	GW6-2	GW6-3
pH, field (std units)	5.90	4.80	5.70
Arsenic, diss. (ug/l)	ND†	ND	ND
Barium, diss. (ug/l)	50	252	120
Cadmium, diss. (ug/l)	ND	ND	ND
Copper, diss. (ug/l)	ND	ND	ND
Chromium, diss. (ug/l)	ND	ND	ND
Iron, diss. (ug/l)	ND	ND	ND
Mercury, diss. (ug/l)	ND	ND	ND
Nickel, diss. (ug/l)	13	23	25
Lead, diss. (ug/l)	ND	ND	ND
Silver, diss. (ug/l)	ND	ND	ND
Zinc, diss. (ug/l)	26.7	62.6	38.2
Nitrogen, NO ₂ + NO ₃ (mg/l-as N)	0.604	3.78	1.50
Sulfate (mg/l)	14	48	226
Residue, diss. (mg/l)	304	262	224
Phenols (ug/l)	3	2	3
Oil & Grease, IR (mg/l)	ND	ND	ND
TOX (ug/l-CL)	14	24	36
Carbon, TOC (mg/l)	15.7	12.6	5.1
Endrin (ug/l)	ND	ND	ND
BHC,G (Lindane)(ug/l)	ND	ND	ND
Methoxychlor (ug/l)	ND	ND	ND
Toxaphene (ug/L)	ND	ND	ND
2,4-D Total (ug/L)	ND	ND	ND
2,4,5-TP/silvex (ug/l)	ND	ND	ND
Fluoride (mg/l)	0.14	ND	ND
Sp. Cond., field (umhos/cm)	430	241	336
Water Temp. (°C)	17.2	18.2	18.3
Selenium, diss. (ug/l)	ND	ND	ND
Cyanide (ug/l)	ND	ND	ND

*GW6-1 indicates a ground water sample from Monitor Well 1 at Site 6.

†ND = Not detected.

Source: ESE, 1985.

The pH values at Site 6 range from 4.8 to 5.9. These values are considered background for the site and are acceptable even though they are outside the 6.5-to-8.5-range specified under NSDWR.

Ba, Zn, NO₃, SO₄, and phenols were determined at various concentrations in the samples. The concentrations were all less than the levels allowable under NIPDWR, NSDWR, and the criteria for the protection of freshwater aquatic life and human health. Nickel (Ni) concentrations of 13, 23, and 25 ug/l were detected in the samples. Although these concentrations are less than the criteria for the protection of freshwater life, the two higher values exceed the human-health criterion of 13.4 ug/l. No potable water wells are located downgradient of this area, and any ground water entering the Alabama River would probably be diluted to values conforming to the acceptable criteria range. These Ni concentrations may be representative of background concentrations, since no prior sources are known at this site.

TOX concentrations at Site 6 vary from 14 to 36 ug/l and may be indicative of positive method interferences rather than ground water contamination by chlorinated organic compounds.

TOC concentrations range from 5.1 to 15.7 mg/l. These concentrations are relatively elevated when compared to other TOC values in ground waters at MAFB. Although Site 6 formerly received spillage from petroleum products directly on the soils, the elevated values possibly represent only limited migration of these petroleum products into the ground water because oil and grease values are less than 0.1 mg/l. These values would be indicative of other organic compounds in the ground water at this site.

4.3.7 SITE 7--LANDFILL NO. 2

The locations of MW7-1, MW7-2, and MW7-3, along with detectable concentrations of various analytes, are presented in Fig. 4.3-8. The analytical results for all ground water samples from Site 7 are presented in Table 4.3-8.

Table 4.3-8. Analytical Results for Ground Water Samples from Site 7

Parameters	Sample Location		
	GW7-1*	GW7-2	GW7-3
pH, field (std units)	4.60	4.80	5.90
Arsenic, diss. (ug/l)	ND†	ND	ND
Barium, diss. (ug/l)	49	31	117
Cadmium, diss. (ug/l)	ND	ND	ND
Copper, diss. (ug/l)	ND	3.1	ND
Chromium, diss. (ug/l)	ND	ND	ND
Iron, diss. (ug/l)	ND	66	7,200
Mercury, diss. (ug/l)	ND	ND	ND
Nickel, diss. (ug/l)	ND	ND	ND
Lead, diss. (ug/l)	ND	ND	ND
Silver, diss. (ug/l)	ND	ND	ND
Zinc, diss. (ug/l)	ND	13.1	101
Nitrogen, NO ₂ + NO ₃ (mg/l-as N)	2.43	1.37	0.581
Sulfate (mg/l)	7	23	65
Residue, diss. (mg/l)	51	71	136
Phenols (ug/l)	1	3	3
Oil & Grease, IR (mg/l)	ND	ND	ND
TOX (ug/l-CL)	12	30	10
Carbon, TOC (mg/l)	2.4	ND	3.9
Endrin (ug/l)	ND	ND	ND
BHC,G (Lindane)(ug/l)	ND	ND	ND
Methoxychlor (ug/l)	ND	ND	ND
Toxaphene (ug/L)	ND	ND	ND
2,4-D Total (ug/L)	ND	ND	ND
2,4,5-TP/silvex (ug/l)	ND	ND	ND
Fluoride (mg/l)	ND	0.11	1.09
Sp. Cond., field (umhos/cm)	56.0	102	260
Water Temp. (°C)	18.5	18.4	19.9
Selenium, diss. (ug/l)	ND	ND	ND
Cyanide (ug/l)	ND	ND	ND

*GW7-1 indicates a ground water sample from Monitor Well 1 at Site 7.

†ND = Not detected.

Source: ESE, 1985.

As with the other sites previously discussed, the pH of ground waters at Site 7 is acidic and ranges from 4.6 to 5.9. Other detectable parameters including Ba, SO₄, Zn, NO₃, and phenols were found at concentrations within the acceptable limits under NIPDWR, NSDWR, and the criteria for the protection of freshwater life and human health.

Concentrations of Fe at Site 7 varied from <4 ug/l at MW7-1 to 7,200 ug/l at MW7-3. The higher value exceeds the concentration under NSDWR. NSDWR is primarily for aesthetic or organoleptic qualities and does not necessarily represent values which will cause potential human-health problems. The high Fe value is indicative of limited ground water contamination at the site.

TOX concentrations range from 10 to 30 ug/l. These concentrations may represent positive interference or background and do not necessarily indicate the presence of significant chlorinated organic compounds in the shallow aquifer.

The TOC values range from <1.7 to 3.9 mg/l. These values are representative of background TOC levels in the ground water at Site 2.

5.0 ALTERNATIVE MEASURES

Three categories of alternatives are possible for the sites investigated:

- I. Take no further action;
- II. Conduct further monitoring to determine the need, if any, of cleanup; or
- III. Undertake corrective actions to mitigate any contamination.

Category I (No Further Action) is appropriate for sites where there is little, if any, evidence to indicate that the site is or will ever be a source of significant contamination. This is a difficult decision in that one can never be absolutely sure no problem will ever exist at a site. However, reasonable judgments must be made so that resources can be allocated to sites that have the highest potential for environmental or human-health problems.

Category II (Additional Monitoring) is appropriate where insufficient evidence exists to place a site in either Category I or III. This category should be utilized with care since there is some risk that delay could allow contamination to spread and worsen the problem. That goal should be to gather enough evidence in a timely manner to resolve the question of whether or not the site should be cleaned up.

Category III (Mitigation) is appropriate where there is clear indication that current or future human or environmental problems will exist. The priority for actions would depend on the magnitude of the threat and whether that threat was current or future. Mitigative actions may include (but are not limited to) removal, containment, treatment, or stabilization of the contamination.

Category II (Additional Monitoring) is judged to be the only appropriate alternative for three of the seven Phase II, Stage 1 sites at MAFB.

These sites are:

1. Site 2, Surface Drainage System (surface water and sediments);
2. Site 3, FPTA No. 2 and Landfill No. 3; and
3. Site 5, Landfills 4, 5, and 6.

Criteria for recommending additional analyses for these zones are listed below.

1. Results reported for one or more screening or specific parameters at one or more sampling locations within the zone are positive and indicate that contamination may exist within the zone;
2. Existing information, particularly the records search, indicates that the contaminants of concern may have been disposed of or spilled within the zone; and
3. Available data for the site are insufficient to proceed to Category I (No Further Action) or Category III (Mitigative Action).

Recommendations for additional monitoring at the sites listed above are given in Sec. 6.0.

Two alternatives were considered for the remaining four sites-- Category II (Additional Monitoring) and Category I (No Further Action) . These sites include:

1. Site 1, Electroplating Waste Disposal Areas;
2. Site 4, FPTA No. 1;
3. Site 6, C.E. Drum Storage Area; and
4. Site 7, Landfill No. 2.

The three criteria listed previously were used to decide whether these sites would be recommended for additional analyses or for no further action.

These sites were dropped from further consideration based on the fact that the first set of screening samples did not indicate the presence of contaminants in the ground water at the sites.

6.0 CONCLUSIONS AND RECOMMENDATIONS

6.1 CONCLUSIONS

Most evidence of ground water and surface water contamination at MAFB is based on general screening analyses. These analyses have the advantage of relatively low cost, but they do not identify specific compounds. Analyses for phenolics and TOC measure classes of compounds, portions of which are synthetic organic compounds and portions of which are the result of the natural decay of organic matter. TOX is a measure of total organic halogens which are mostly synthetic. As discussed in Sec. 4.3.1, the TOX data suggest a positive interference most likely caused by inorganic halides.

A conservative attitude requires that positive results be investigated via expanded sets of analyses. Since the suspected positive TOX interference can be neither verified nor quantified, this assumption also holds for TOX data. An exception to this approach to TOX can be made in cases where the Phase I records search and all other available information indicate that there were no significant quantities of halogenated organic compounds used, spilled, or disposed of at the study site.

Indications of organic contamination in ground water require analyses for purgeable organics, base/neutral extractable organic compounds, and acid extractable organic compounds which are three groups of the EPA Priority Pollutant List. Approximately one-third of the base-neutral extractable organics are halogenated and, in theory, should be detected by the TOX analysis. Acid extractable organics are all phenolic compounds or creosols. The expanded set of analyses would again include metals, cyanides, and pesticides, based on the Phase I record search information and the screening analysis conducted in Phase II, Stage 1.

Field measurement of pH and specific conductance for all water samples are included with recommended analyses since these are generally performed at no additional cost and can provide useful information.

6.2 RECOMMENDATIONS

This section presents recommendations for Phase II, Stage 2 work at MAFB on a site-by-site basis. One or both of the following criteria were used in selection of Phase II, Stage 2 sampling locations for specific zones:

1. Phase II, Stage 1 sampling locations which indicated the greatest potential for contamination were recommended for further analyses; and
2. Locations where samples were not collected during Phase II, Stage 1 and, based on the results obtained in the study, might provide additional useful information.

6.2.1 SITE 2--SURFACE WATER DRAINAGE SYSTEM

The surface water monitoring program should be expanded to include three additional sites. The new surface water monitoring sites are included in Fig. 6.2-1. Samples should be collected and analyzed for purgeable organics, base/neutral extractables, organics, acid extractables, pesticides, and metals to determine specific contaminants in the surface waters. A summary of the analyses recommend for Site 2 during the MAFB Phase II, Stage 2 study is presented in Table 6.2-1. New data should be examined and compared with previous data to determine if As concentrations are consistently higher at onbase locations. Field pH and specific conductivity should be determined during sampling. Additional data searching should be performed to determine the source of As and Hg in the surface water samples. Based on the results of these analyses, additional actions may be necessary.

The sediment monitoring program should also be continued. Additional sediment sampling sites should be added to determine if the Hg and Pb concentrations are indicative of contamination or natural background.




Figure 6.2-1
LOCATIONS OF PRESENT AND PROPOSED SURFACE
WATER SAMPLING SITES ON MAFB

Table 6.2-1. Summary of Sampling and Analyses Recommended for MAFB, Phase 11, Stage 2 Survey

Site	Sampling Locations	pH	Specific Conductance	Analyses														Rationale for Recommendation
				Gas Chromatography/Mass Spectrometry				Pesticides	CN	Cu	Cr	Cd	Ni	Fe	Hg	As		
				Acid Extractables	Base/Neutral Extractables	Acid Extractables												
2	Surface water sampling locations S 2-1, S 2-2, S 2-3, and S 2-4; new sites S 2-5, S 2-6, and S 2-7	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	TTC found at low levels. Need GC/MS to determine identities and concentrations of organic and chlorinated organics. Need to confirm Hg and As and determine source, if possible. Analyze for metals and cyanide since electroplating was performed in past.	
	Sediment sampling locations S 2-1 through S 2-11; new sites upstream of S 2-1 (1 site), downstream of S 2-8 (1 site), and downstream of S 2-11 (1 site)		X	X	X	X	X	X	X	X	X	X	X	X	X	X	TTC found at low levels. Need GC/MS to determine identities and concentrations of organics. Need to confirm Hg and Pb and determine source, if possible. Analyze for metals and cyanide since electroplating was performed in past.	
3	MW 3-1, 3-2, and 3-3	X	X	X	X		X										Pesticides, TTC, TUX, and low-level metals present. Need to confirm concentrations and identify the organics.	
5	MW 5-1, 5-2, 5-3, 5-4, and other existing wells, if accessible (5-5, etc.)	X	X	X	X		X										Pesticides, TTC, TUX, and low-level metals present. Need to confirm concentrations and identify the organics.	

Source: ESE, 1985.

The new sediment sampling sites should be located upstream of S2-1 (1 new site), upstream of S2-4 (2 new sites), downstream of S2-6 (1 new site), downstream of S2-8 (1 new site), and downstream of S2-11 (see Figure 6.2-2). Based on the results of these analyses, additional actions may be necessary.


6.2.2 SITE 3--FPTA NO. 2 AND LANDFILL NO. 3

Ground water samples should be collected at MW3-1, MW3-2, and MW3-3. These samples should be analyzed for purgeable organics, base/neutral extractable organics, acid extractable organics, pesticides, Fe, Cd, Cu, Ni, Cr, and field pH and specific conductance. A summary of the analyses recommended for Site 3 during the MAFB Phase II, Stage 2 study are presented in Table 6.2-1. Based on the results of these analyses, additional actions may be necessary.

6.2.3 SITE 5--LANDFILLS 4, 5, AND 6

Ground water samples should be collected at MW5-1, MW5-2, and MW5-3. These samples should be analyzed for purgeable organics, base/neutral extractable organics, acid extractable organics, pesticides, Fe, Cd, Cu, Ni, Cr, field pH, and specific conductance. Based on the results of these analyses, additional actions may be necessary.

A summary of the analyses recommend for Site 5 during the MAFB Phase II, Stage 2 study is presented in Table 6.2-1.



SOURCES: ES, 1984.
ESE, 1985.

**INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base**

**Figure 6.2-2
LOCATIONS OF PRESENT AND PROPOSED SEDIMENT
SAMPLING SITES ON MAFB**

APPENDIX A--GLOSSARY OF TERMINOLOGY, ABBREVIATIONS,
AND ACRONYMS

APPENDIX A

GLOSSARY OF TERMINOLOGY, ABBREVIATIONS, AND ACRONYMS

AFB	Air Force Base
AFESC	Air Force Engineering and Service Center
Ag	Chemical symbol for silver, a metal used in photographic emulsions and other industrial operations; toxic to humans and aquatic life at low concentrations
As	Chemical symbol for arsenic
AU	Air University
Ba	Chemical symbol for barium
Cd	Chemical symbol for cadmium, a metal used in batteries and other industrial applications; highly toxic to humans and aquatic life
C.E.	Civil Engineering
°C	degrees Celsius
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
cm	Centimeter(s)
CME	Central Mine Equipment
CN	Chemical symbol for cyanide
Contamination	Degradation of natural water quality to the extent that its usefulness is impaired; degree of permissible contamination depends on intended use of water
Cr	Chemical symbol for chromium, a metal used in plating, cleaning, and other industrial applications; highly toxic to aquatic life at low concentrations, toxic to humans at higher levels
Cu	Chemical symbol for copper

DEQPPM	Defense Environmental Quality Program Policy Memorandum
Det.	Detachment
Disposal of hazardous waste	Discharge, deposit, injection, dumping, spilling, or placing of any hazardous waste into or on land or water so that such waste, or any constituent thereof, may enter the environment, be emitted into the air, or be discharged into any waters, including ground water
DOD	Department of Defense
Downgradient	In the direction of decreasing hydraulic static head; the direction in which ground water flows
EM	Electromagnetic
EPA	U.S. Environmental Protection Agency
ES	Engineering-Science
ESE	Environmental Science and Engineering, Inc.
°F	degrees Fahrenheit
F	Chemical symbol for fluoride
Fe	Chemical symbol for iron, a metal commonly found in water as a consequence of dissolution of geologic materials; relatively nontoxic
FPTA	Fire Protection Training Area
ft	Foot (feet)
gpm	Gallon(s) per minute
HARM	Hazard Assessment Rating Methodology
Hazardous waste	As defined in RCRA, a solid waste or combination of solid wastes which because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to an increase in mortality or an increase in serious, irreversible, or incapacitating reversible illness; or pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, disposed of, or otherwise managed

Hg	Chemical symbol for mercury
IIA	Initial Installation Assessment
IRP	Installation Restoration Program
LAW	Law Engineering Testing Company
lb	Pound(s)
MAFB	Maxwell Air Force Base
MAJCOM	Major Command
MCL	Maximum contaminant level
mg/l	Milligram(s) per liter
MSL	Mean sea level
MW	Monitor well
NGVD	National Geodetic Vertical Datum
Ni	Chemical symbol for nickel, a metal used in batteries, plating, and other industrial applications; highly toxic to humans and aquatic life
NIPDWR	National Interim Primary Drinking Water Regulations
NO ₃	Chemical formula for nitrate, a common anion in natural water
NPDES	National Pollutant Discharge Elimination System
NSDWR	National Secondary Drinking Water Regulations
OEHL	Occupational and Environmental Health Laboratory
Pb	Chemical symbol for lead, a metal additive to gasoline and used in other industrial applications; toxic to humans and aquatic life; bioaccumulates
pH	Negative logarithm of hydrogen ion concentration; an expression of acidity or alkalinity
QA/QC	Quality assurance/quality control
RCRA	Resource Conservation and Recovery Act
Se	Chemical symbol for selenium, a metal with numerous applications as a catalyst; toxic to humans and aquatic life

SO ₄	Chemical formula for sulfate, a common anion in sea water
TDS	Total dissolved solids
TOC	Total organic carbon
TOE	Total organic extractables
TOX	Total organic halogens
2,4-D	2,4-Dichlorophenoxyacetic acid
2,4,5-TP	2,4,5-Trichlorophenoxyacetic acid
ug/g	Microgram(s) per gram
ug/l	Microgram(s) per liter
USAF	U.S. Air Force
USGS	U.S. Geological Survey
Zn	Chemical symbol of zinc, a metal with a wide variety of industrial applications, particularly corrosion-resistant; highly toxic to aquatic life, slightly toxic to humans at high dose levels

APPENDIX B--RESUMES OF KEY PROJECT PERSONNEL

JOHN D. BONDS, Ph.D.
Senior Scientist/Project Manager

ESE PROFESSIONAL RESUME

SPECIALIZATION

Project Management, Atmospheric Chemistry, Water Chemistry, Industrial Hygiene, Quality Assurance, Hazardous Waste

RECENT EXPERIENCE

Initial Assessment for Hazardous Wastes at Army Installations, Team Leader--Comprehensive study at 48 Army installations to determine both past and present history with respect to the use of hazardous substances, quantities used, disposal methods and disposal sites. Also includes a current assessment of safety practices and compliance with regulations.

Initial Assessment Studies for the United States Air Force, Team Leader--Comprehensive studies at 2 Air Force bases to determine both past and present history with regard to the use and disposal of toxic and hazardous materials. Conducted in accordance with the Department of Defense Installation Restoration Program policies.

Initial Assessment Studies for the Naval Energy and Environmental Support Activity, Team Leader--Evaluating 2 Naval installations with regard to past hazardous waste generation, storage, treatment, and disposal practices. Investigations include records review, aerial and ground site surveys, employee interviews, and limited sampling and analysis including geophysical techniques. Determine extent of contamination at former disposal/spill sites, potential for contaminant migration, and potential effects on human health and the environment.

Phase II Confirmation Studies to Determine the Presence and Migration of Hazardous Wastes from Military Installations, Team Leader--Five comprehensive field studies to determine the actual sites where hazardous substances were used, their current concentrations in soils, surface waters and groundwater, and an assessment of the quantities which may migrate from the installation. The study also included recommendations for decontamination operations.

Determination of Hazardous Chemicals in Landfills, Project Manager--Several studies in which field sampling techniques and laboratory methods were developed to determine the existence and concentrations of explosive gases generated by landfill operations, priority pollutants escaping to the atmosphere and contaminating the groundwater.

Preparation of Quality Assurance Guidelines for EPA Project Officers, Project Manager--Preparation of QA guidelines for use by EPA project officers in selecting contractors for projects requiring sampling and analysis. Also included guidelines for quality assurance audits of the field sampling and analysis portion of any awarded contract. EPA publication 600/9-79-046 entitled Quality Assurance Guidelines for IERL-Ci Project Officers was produced under this project.

J.D. BONDS, Ph.D.

Page 2

Air Compliance Testing of Industrial Sources, Project Manager--Various projects involving compliance testing at petroleum refineries, Kraft pulp mills, power plants, iron and aluminum smelting operations, and various other industries.

Ambient Air Monitoring, Project Manager--Various projects to determine ambient air concentrations of sulfur oxides, particulates, nitrogen oxides, carbon monoxide, photochemical oxidants, priority pollutant organics, and hydrocarbons.

EDUCATION

Ph.D.	1969	Analytical Chemistry	University of Alabama
B.S.	1963	Chemistry	University of Alabama
U.S. EPA Air Pollution Training Institute: Quality Assurance for Air Pollution Measurement Systems--workshop graduate (1977)			

ASSOCIATIONS

American Chemical Society
American Industrial Hygiene Association
Air Pollution Control Association

REPORTS AND PUBLICATIONS

More than 50 reports and publications on Installation Assessments, source air emissions, hazardous materials and quality assurance.

GEORGE K. FOSTER
Geologist

ESE
PROFESSIONAL
RESUME

SPECIALIZATION

Geology, Clay Mineralogy, and Portland Cement Chemistry

RECENT EXPERIENCE

United States Air Force, Maxwell AFB, Team Hydrogeologist--

Served as hydrogeologist for the pre-performance survey and prepared detailed plans for the emplacement of monitor wells around hazardous waste disposal areas on the installation.

University of Florida, Graduate Teaching Assistant--Responsible for X-ray analysis, clay mineralogy, and engineering geology. Also acted as Lab Instructor for clay mineralogy.

Analex, Aurora, Colorado, Well-Site Geologist--Responsible for collecting and logging drill cuttings, monitoring downhole gases and drill rates, and observing DSTs and corings.

Florida Mining and Materials Corp., Brooksville, Florida, Lab Technician--Responsibilities included testing and quality control of Portland cement raw materials and microscopic analysis of cement clinker.

EDUCATION

M.S.	1984	Geology/Clay Mineralogy	University of Florida
B.A.	1980	Geology	University of South Florida

MICHAEL J. GEDEN, B.S.
Water Resources

ESE
PROFESSIONAL
RESUME

SPECIALIZATION

Geophysical Investigation, Geologic Structure and Process,
Geomorphology, Field Sampling and Techniques

RECENT EXPERIENCE

Ohio Superfund Site, Task Manager--Conducted a multitechnique geophysical survey at an abandoned hazardous waste site in northeastern Ohio. Also supervised installation of monitoring wells.

Solite Corporation, Project Geologist--Conducted a geophysical survey at a hazardous waste site in northeast Florida. Sampled surface and ground water and installed monitoring wells.

Pinellas County, Subproject Manager--Geophysical survey of refuse-to-energy plant and active landfills. Design and installation of ground water monitoring wells. Aquifer testing and analysis through use of single well slug tests.

Geophysical Investigations for Uncontrolled Disposal Site, Scientist--Conducted investigations to locate buried drums using remote sensing techniques. More than 1,000 drums were located and excavated.

Midwest Manufacturer, Project Scientist--Installation and sampling of ground water monitor wells to determine extent of ground water contamination. Aquifer testing and analysis through use of single well slug tests.

Florida Manufacturer, Associate Scientist--Conducted multitechnique geophysical survey. Design, construction, aquifer analysis, and sampling of ground water monitoring system to determine extent of subsurface contamination.

Aero Corporation, Associate Scientist--Construction, aquifer analysis, and sampling of ground water monitor wells to determine effectiveness of wastewater treatment process.

Ida-Con Corporation, Associate Scientist--Design, siting, construction, and sampling of ground water monitor wells to test effectiveness of surface water retention ponds.

Seminole Electric Cooperative, Project Scientist--Installation and aquifer testing of ground water monitor wells as part of siting study for new electric-generating station.

Alabama Army Ammunitions Plant Ground Water Monitoring, Associate Scientist--Installation, development, and sampling of ground water monitor wells and piezometric clusters.

M.J. GEDEN, B.S.

Page 2

Georgia Pacific, Associate Scientist--Installation and development of ground water monitor wells and piezometric transects in Santa Fe Swamp.

USATHAMA-Ft. Navajo, Ft. Wingate, Bluegrass, Phoenix, AAAP, Lima, and Savannah Army Depots, Associate Scientist--Compilation and preparation of field drilling data for entry into U.S. Army computer system.

General Electric Company, Project Scientist--Monthly sampling of ground water monitor wells to monitor integrity of surface chemical retention ponds.

EDUCATION

B.S. 1979 Earth Science Northeastern Illinois University

ESE

ALLEN P. HUBBARD, B.S.E., P.E.

Department Manager, Hazardous Materials Engineering

**PROFESSIONAL
RESUME**

SPECIALIZATION

Hazardous Waste Management, Remedial Actions, Industrial Waste
Operations Design and Permitting

RECENT EXPERIENCE

Environmental Audits and Records Search of U.S. Army Facilities,
Project Team Engineer--Served for two years on this project to assist
the U.S. Army in its Installation Assessment Program. Project teams
conduct onsite environmental surveys which assess current and past
waste management activities at military installations. Hazardous and
toxic waste management is emphasized. The team engineer inspects
industrial operations, POL storage and transfer facilities, wastewater
treatment facilities, RCRA permitting and compliance, status, central
records, and compliance of transportation, property sales and disposal.
Interviews are conducted with current and former employees. In a
following report, recommendations are presented for upgrading to comply
with state, federal, and army regulations. Sites included: Fort
Buchanan, PR; Fort Benjamin Harrison, IN; Fort Leavenworth, KS; Fort
McPherson, GA; Fort Knox, KY; and Fort Bragg, NC.

Hazardous Waste Delisting Projects, Project Manager/Engineer--Four
separate projects for three plants in the steel finishing industry.
Projects included negotiation with state and federal agencies (in
different states), sampling and analysis, and formal petition documents
to exclude listed hazardous wastes from RCRA regulations according to
40 CFR Part 260.22.

Evaluation and Conceptual Design of Solid Waste Management Facilities
for Coal-Fired Power Plants, Project Engineer--Part of the siting and
licensing of three coal-fired generating stations for Florida Power
Corporation, Atlantic City Electric, and Soyland Electric Cooperative.
Involved in estimating ash characteristics and quantities, evaluating
FGD processes, and conceptual design of flyash landfills.

RCRA Closure Plans for Hazardous Waste Treatment and Storage
Facilities, Project Manager/Engineer--Developed plans for five separate
clients for closure of hazardous waste treatment, storage, disposal
facilities (TSDFs). Types of operations included hazardous waste
incinerator, burning ground, and storage tank farm, chemical/physical
treatment system, land treatment facility, surface impoundments. Final
plans complied with 40 CFR Part 265.

Regional Hazardous Waste Inventory, Tampa Bay Area Regional Planning
Council (TBARPC), Task Leader of abandoned dumps and landfill practices
of multicounty study mandated by state law. Project encompasses a year-
long survey of all hazardous waste generators and TSDFs in the TBARPC
area. Includes evaluation of hazardous wastes at sanitary landfills
and site surveys of abandoned dumps. Objectives are interference of
total waste generation rate from a partial sample and location of
suitable areas for siting of offsite storage or treatment facilities.

A.P. HUBBARD, B.S.E
Page 2

Hazardous Waste Remedial Action/Decontamination Study, Alabama Army Ammunition Plant, Project Engineer--Project to develop and implement corrective measures for decontamination of buildings, process equipment, sewers and soil to control surface water and ground water contamination at U.S. Army ammunition plant. Developed decontamination alternatives with consideration of risk, cost and technical feasibility.

EDUCATION

B.S.E. 1979 Environmental Engineering University of Florida

REGISTRATION

EIT 1979 Florida

ASSOCIATION

American Society of Civil Engineers

PUBLICATIONS

"Operating and Monitoring Requirements for Hazardous Waste Land Treatment Facilities." Hearne, S.R., P.E., Hubbard, A.P., Hart, Robin, Ph.D. Proceedings from National Conference on Risk and Decision Analysis for Hazardous Waste Disposal. 1981. Sponsored by Hazardous Materials Control Research Institute.

"Delisting Hazardous Wastes at Industrial Plants--Procedures and Case Study." Hubbard, A.P., Frey, E.E., Ruen, M.J. Proceedings of the Industrial Wastes Symposia, 55th Annual Conference of the Water Pollution Control Federation. 1982.

ESE

PROFESSIONAL RESUME

JOHN J. MOUSA, Ph.D.
Quality Assurance Manager

SPECIALIZATION

Quality Assurance, Environmental Sampling and Analysis, Analytical Chemistry, Water Quality Assessment, Environmental Fate and Assessment Studies, Trace Organic Residue Analysis, Gas Chromatography and High-Pressure Liquid Chromatography

RECENT EXPERIENCE

ESE Corporate Quality Assurance Manager--Responsible for auditing quality control, implementation of department and division level QC programs, providing independent peer review of project deliverables.

Research and Development--Responsible for staffing, direction, review and technical quality of projects involving environmental/fate studies, trace organic residue analysis, environmental sampling and analysis, special instrumental techniques and analytical methods development.

Remedial Investigation and Feasibility Study for the French Limited and Sikes Pit Abandoned Waste Disposal Sites, Quality Assurance Manager--Prepared QA plans and performed quality assurance/quality control duties for field sampling, analysis, and report preparation.

Environmental Contamination Assessment of Army Munitions Manufacturing and Storage Facilities, Laboratory Manager/Subproject Manager--Managed laboratory analyses for four environmental assessment studies conducted for U.S. Army Toxic and Hazardous Materials Agency. Work involved methods development certification and trace organics analysis in water, soil, and sediment samples.

Sampling and Analysis of Boundary Monitoring Wells, Project Manager--Sampling and analysis of ground water for trace organics and inorganics at industrial explosives manufacturing facility. Supervised methods documentation and analysis.

Analytical Methods Development for Hazardous Compounds in Water and Soil, Project Manager--Development of analytical method for seven organic compounds at part-per-billion and part-per-million level in water and soil. Includes development of HPLC screening method for organics in water. Compounds include hazardous munitions and related degradation products.

Effluent Guidelines BAT Review-Printing and Publishing and Gum and Wood Industries, Project Manager--Supervised and coordinated laboratory analyses for priority pollutants in industrial wastewaters.

John J. Mousa, Ph.D.

Page Two

EDUCATION

Ph.D.	1973	Analytical Chemistry	University of Florida
B.S.	1970	Chemistry (Summa Cum Laude)	University of Houston

ASSOCIATIONS

- American Chemical Society
- Society of Environmental Toxicology and Chemistry (SETAC)
- American Society for Testing and Materials (ASTM)
- Phi Kappa Phi Honor Society

ENVIRONMENTAL SCIENCE AND ENGINEERING, INC.

MEREDITH T. PARK, M.S.

Professional Resume

Areas of Specialization

Hazardous Waste; Analysis, Field Investigation, and Contamination Assessment; Inorganic Chemistry; Marine Chemistry

Experience

Staff Scientist, Chemistry Division, ESE, Gainesville, Florida, 1984-Present. Atomic Spectroscopy Department Manager, ESE, 1979-1984.

Department of Defense (DOD) Installation Restoration Program (IRP), Project Manager--Responsible for project/task management as well as task technical support within the program structure. IRP is the DOD identification and control program for past hazardous materials released at military facilities under CERCLA.

Rocky Mountain Arsenal, Environmental Program, Task Manager--Managing ongoing task involving analytical methods development and subsequent analysis of environmental soil and sediment samples.

West Virginia Ordnance Works Environmental Survey, Task Manager--Managing ongoing 10,000-manhour comprehensive environmental contamination survey for the above CERCLA (Superfund) site, ranked 86th on the National Priorities List (NPL).

Sharpe Army Depot, Task Manager--Managing ongoing chemical analysis task for ground water contamination assessment.

Maxwell Air Force Base, Environmental Survey, Task Manager--Managing ongoing 1,000 manhour environmental survey involving analysis of surface water, sediments, and hazardous wastes.

Aberdeen Proving Ground Environmental Survey, Project Manager--Managed 1,500-manhour exploratory ground water and surface water contamination survey at Edgewood Arsenal, Maryland.

Volunteer Army Ammunition Plant, Task Manager--Managed chemical analysis task involving testing of ground waters and soil samples.

Atomic Spectroscopy Department Manager--Responsible for trace metals analysis for a wide range of samples. Also responsible for analytical methods development by atomic absorption and inductively coupled plasma emission spectroscopy.

Environmental Assessment Studies for Oil Recovery Steamflood Project in Sumatra, Indonesia, Project Chemist--Conducted water quality analysis of an oil field steamflood project for Caltex Pacific Indonesia. Instructed local technicians in chemical analyses and laboratory techniques.

Florida Acid Deposition Study--Responsible for trace metals portion of a multiyear study investigating acid rain. Analyses performed using inductively coupled plasma emission spectroscopy and atomic emission spectroscopy.

Florida Institute of Phosphate Research--Responsible for providing analytical support for a research study of the limnology of reclaimed lakes in central Florida. Supervised analysis of water and sediment samples by atomic absorption (AA) and by inductively coupled argon plasma (ICAP) spectroscopy.

Hazardous Waste Characterization for RCRA Compliance, Project Manager--Ongoing project providing analytical services for clients filing applications or fulfilling monitoring program requirements for RCRA compliance. Involves elutriation of samples and subsequent analysis for trace metals and pesticides.

Laboratory Manager, Connell Metcalf and Eddy, Inc., Coral Gables, Florida, 1979 to 1980.

Staff supervisor of biological and chemical techniques performing a wide variety of environmental analyses. Involved in multi-disciplined environmental community, benthic and planktonic community structure study for a nuclear power plant, and master planning and related environmental studies for Metropolitan Dade County marinas. Responsible for analysis of industrial effluents and process streams.

Chemical Oceanographer, Everglades National Park, National Park Service, 1979.

Responsible for development of an automated monitoring system to assess long-term changes in the estuarine and marine waters of the Everglades National Park and for developing computerized data management procedures.

Marine Chemist, College of Marine Studies, University of Delaware, 1978 to 1979.

Supervisor of Marine Chemistry Laboratory with managerial and technical duties. Work included investigation of pathways of cadmium transport in terrestrial vegetation, research concerning nitrogen fluxes in estuarine systems, and the monitoring of drinking water for excessive nitrate levels. Responsible for report preparation and the drafting of proposals.

M.T. Park
Page 3

Analytical Chemist, Virginia Associated Research Campus, William and Mary College, 1976 to 1978.

Involved in an environmental benchmark study designed to assess the potential environmental impact of oil exploration on the mid-Atlantic outer continental shelf. Developed analytical procedures for analyzing marine sediments and organisms by flame and flameless atomic absorption spectrometry. Responsible for data reduction and interpretation, and the preparation of progress reports to the funding agency (Bureau of Land Management, Department of the Interior).

Research Assistant, U.S. Army Corps of Engineers, Port Hampton Roads, Virginia, 1975 to 1976.

Conducted contract work involving water quality monitoring of the Craney Island Dredge Material Disposal Area. Work concerned with fate of trace metals in an estuarine environment. Responsible for project design, analytical quality control, and data interpretation. Acted as liaison between the University and Corps of Engineers.

Laboratory Technician, Sanitation District Commission, Lamberts Point Treatment Plant Laboratory, Hampton Roads, Virginia, 1972 to 1975.

Performed wide range of chemical analyses, including determination for nutrients, fecal coliform, dissolved oxygen, carbon, and heavy metals. Gained experience with various means of instrumental analysis including spectrophotometry, organic carbon techniques, and atomic absorption spectrophotometry.

Education

M.S.	1976	Chemical Oceanography	Old Dominion University
B.A.	1968	Chemistry	Duke University

Affiliations

American Chemical Society
American Society of Limnology and Oceanography

Publications

Adams, D.D. and Park, M.T.. 1976. Water Quality Monitoring of the Craney Island Dredge Material Disposal Area. Port of Hampton Roads, Virginia. April 1975 to March 1976. Technical Report, No. 29, Institute of Oceanography, Old Dominion University, Norfolk, Virginia. 189 p.

Gaby, R., Langley, S.P., Park, M.T., and Curry, R.W. 1980. Key Largo Coral Reef Marine Sanctuary--Literature Survey and Water Quality Monitoring Program. National Oceanic and Atmospheric Administration, Office of Coastal Zone Management. 196 p.

Newman, J.R., Novakova, E., Bergdoll, M.K., and Park, M.T. 1984. Ducks as Site Specific Bioindicators of Trace Metal Pollution. Presented at the Society of Environmental Toxicology and Chemistry, Fifth Annual Meeting, November 1984.

Julia H. Chalkley, M.S.
Senior Associate Scientist/Geologist

ESE
PROFESSIONAL
RESUME

SPECIALIZATION

Geology and Hydrogeology, Environmental Permitting, Environmental and Hazardous Waste Management

RECENT EXPERIENCE

Ground Water Monitoring Plan, Project Manager--Investigated existing ground water monitoring program for industrial facility including field sampling, recommended plan to correct deficiencies, and trained industrial personnel in field sampling techniques.

Initial Installation Assessment, Naval Facilities, Team Geologist--Evaluation of two Naval installations with regard to potential for environmental contamination from past hazardous waste generation, storage, treatment, and disposal practices. Responsibilities included assessment of geohydrology of potential contamination sites, identification of pollutant migration pathways, and recommendation for further study.

Phase II Confirmation Study, U.S. Air Force, Project Geologist--Field team leader for sampling of ground water monitor wells to determine extent of ground water contamination at abandoned and current disposal sites.

Environmental Permit Application, Staff Editor and Reviewer--Prepare EPA Parts A and B applications for commercial hazardous waste disposal facilities, including facility designed for subsurface disposal of hazardous wastes in solution-mined salt caverns, large industrial above- and below-ground landfill and incineration complex, and several facilities with treatment ponds and lagoons.

Evaluation of Surface and Subsurface Hazardous Waste Disposal Sites, Staff Geologist--Performed investigations of subsurface geology and geohydrology at potential deep well disposal sites, salt domes for use as mined repositories, and landfill sites.

EDUCATION

M.S.	1985	Environmental Management	University of Houston
B.S.	1980	Geology	Florida State University

LINDA D. TOURNADE
Senior Technical Writer and Editor

ESE PROFESSIONAL RESUME

SPECIALIZATION

Technical Writing and Editing, Publications Management, Document Coordination, and Historical Research

RECENT EXPERIENCE

Technical Editor/Document Coordinator for U.S. Army Toxic and Hazardous Materials Agency (USATHAMA) Waste Treatment Technology Contracts--Responsible for coordination and management of report production, including liaison with project manager and client in regard to client requirements, report organization, writing assignments, report format, quality control, word processing, graphics, printing/binding, and distribution.

Subproject Manager for Environmental Contamination Survey of Sharpe Army Depot for USATHAMA--Responsibilities include monitoring and controlling document production budget, preparing cost and performance reports, editing, and document coordination of draft and final technical plans, management plans, and community relations plans, as well as presentation materials for regulating liaison meetings and public workshops.

Technical Editor/Document Coordinator for Assessment of Contamination at Phoenix Military Reservation for USATHAMA-- Edited and coordinated production of presentation materials, draft and final assessment reports, and draft technical and management plans for remedial action alternatives assessments.

Technical Editor/Document Coordinator for Installation Assessment of U.S. Military Academy, West Point--Responsible for editing and managing production of draft and final assessment reports detailing past and current use of toxic and hazardous materials at West Point and subinstallations.

Subproject Manager for Installation Restoration Program Records Search for U.S. Air Force Installations--Researching history, mission, and organization of U.S. Air Force installations and writing sections for records search documents. Installations include Cape Canaveral Air Force Station, Patrick Air Force Base (AFB), Vandenberg AFB, Columbus AFB, and Andersen AFB. Additional responsibilities include editing sections authored by other team members, monitoring and controlling document production budget, and coordinating and managing report production.

L.D. Tournade
Page 2

EDUCATION

B.S. 1985 Journalism/Technical University of Florida
(Candidate) Communication

ASSOCIATIONS

Society for Technical Communication, Secretary-Treasurer for North-Central Florida Chapter

APPENDIX C--SCOPE OF WORK AS OUTLINED BY OEHL

16 JUL 1984

INSTALLATION RESTORATION PROGRAM
PHASE II - CONFIRMATION/QUANTIFICATION (STAGE 1)
MAXWELL AFB ALABAMA

I. DESCRIPTION OF WORK

The purpose of this task is to undertake a field investigation at Maxwell AFB Alabama (1) to determine the presence or absence of contamination within the specified areas of investigation; (2) if contamination exists, determine the potential for migration of those contaminants in the various environmental media; (3) identify additional investigations necessary to determine the magnitude, extent, direction and rate of migration of discovered contaminants; and (4) identify potential environmental consequences and health risks of migrating pollutants.

The Phase I IRP Report (mailed under separate cover) incorporates the background and description of the sites for this task. To accomplish this survey effort, the contractor shall take the following actions:

A. General

1. All exploratory well drilling and borehole operations shall be monitored with a photoionization meter or equivalent organic vapor detection device to identify potential generation of hazardous and/or toxic materials. In addition, drill cuttings shall be monitored for discoloration and odor. During drilling operations, if soil cuttings are suspected to be hazardous, the contractor will place them in proper containers and test them for EP Toxicity and Ignitibility. Results of monitoring shall be included in boring logs. A maximum of six samples shall be collected for EP Toxicity and Ignitibility testing.

2. All water samples collected shall be analyzed on site by the contractor for pH, temperature and specific conductance. Sampling, maximum holding time, and preservation of samples shall strictly comply with the following references: Standard Methods for The Examination of Water and Wastewater, 15th Ed. (1980), pp. 35-42; ASTM, Part 31, pp. 76-86, (1980), Method D-3370; and Methods for Chemical Analysis of Waters and Wastes, EPA Manual 600/4-79-020, pp. xiii to xix (1979). All chemical analyses (water and soil) shall meet the required limits of detection for the applicable EPA method identified in Attachment 1.

3. Locations where sediment samples are taken or where soil exploratory borings are drilled shall be marked with a permanent marker, and the location marked on a project map of the site.

4. Field data collected for each site shall be plotted and mapped. The nature, magnitude, and potential for contaminant flow within each zone to receiving streams and ground waters shall be estimated. Upon completion of the sampling and analysis, the data shall be tabulated in the next R&D Status report as specified in Item VI below.

5. Determine the areal extent of the sites by reviewing available aerial photos of the base, both historical and the most recent panchromatic and infrared.

6. Split all water and soil samples as part of the contractor's specific Quality Assurance/Quality Control (QA/QC) protocols and procedures. One set of samples shall be analyzed by the contractor and the other set of samples shall be forwarded for analysis through overnight delivery to:

USAF OEHL/SA
Bldg 140
Brooks AFB TX 78235

The samples sent to the USAF OEHL/SA shall be accompanied by the following information:

- a. Purpose of sample (analyte)
- b. Installation name (base)
- c. Sample number (on containers)
- d. Source/location of sample
- e. Contract Task Numbers and Title of Project
- f. Method of collection (bailer, suction pump, air-lift pump, etc.)
- g. Volumes removed before sample taken
- h. Special conditions (use of surrogate standard, special nonstandard preservations, etc.)
- i. Preservatives used

This information shall be forwarded with each sample by properly completing an AF Form 2752 (copy of form and instructions on proper completion mailed under separate cover). In addition, copies of field logs documenting sample collection should accompany the samples.

Chain-of-custody records for all samples, field blanks, and quality control duplicates shall be maintained.

7. An additional 10% of all samples, for each parameter, shall be analyzed for quality control purposes, as indicated in Attachment 1.

8. For ground water monitoring wells, comply with U.S. EPA Publication 330/9-S1-002, NEIC Manual for Ground Water/Subsurface Investigations at Hazardous Waste Sites for monitoring well installation. Only screw type joints shall be used.

9. Wells shall be of sufficient depth to collect samples representative of aquifer quality and to intercept contaminants if they are present. Well development shall proceed until the discharge water is clear and free of sediment to the fullest extent possible.

10. Elevations of all newly installed monitoring wells shall be surveyed with respect to bench mark on base to an accuracy of ± 0.05 feet. Horizontally locate the new wells to an accuracy to ± 10 feet and record on site map.

11. Water levels shall be measured at all contractor installed wells to the nearest 0.01 foot, and locations recorded on a project map and specific site maps.

12. All monitor wells shall be drilled using the following specifications:

a. Each well shall be drilled with a 8-inch outside diameter drill bit using hollow-stem auger equipment. Soil samples shall be taken every 2.5 feet to a depth of 10 feet, and then every 5 feet to a maximum depth of 25 feet, except at the C.E. Drum Storage Area where samples shall be taken every 2.5 feet to a depth of 10 feet, and then every 5 feet to a maximum depth of 70 feet. Samples shall not be analyzed in Stage 1, but will be retained in the event that contamination is detected in the ground water. These samples shall be collected using split spoon samplers. Total number of soil samples to be archived shall not exceed 167. Each pilot boring log and well completion summaries shall be included in the Final Report (as specified in Item VI below).

b. The average depth of each of these wells shall be 25 feet; except for the C.E. Drum Storage Area, where the average depth shall be 70 feet. Total footage of wells installed shall not exceed 635 linear feet. Each well shall be constructed of 4-inch diameter Schedule 40 PVC casing using threaded, non-glued fittings. Each well shall be screened to 8 feet below the water-table surface, as it is encountered during drilling. Total screened casing shall not exceed 345 feet. The screen shall consist of 4-inch diameter, 40 PVC with 0.010-inch slots. The screen shall be capped at the bottom. All connections shall be flush-joint threaded. Each well shall be gravel-packed with a grain size distribution compatible with the screen and the formation. The pack will be emplaced from the bottom of the borehole to the top of the screen. Granulated or pelletized bentonite shall be tremied above the sand/gravel pack to a minimum thickness of five feet. Grout shall be emplaced from above the top of the bentonite seal to the land surface. Each well shall be completed with installation of a cap and locking hasp and shall be clearly numbered with an exterior paint.

13. Each well shall be developed with a PVC or stainless steel bailer or electric powered submersible pump until clean of suspended solids.

14. Wells shall be purged prior to sampling. Purging will be complete when five well volumes of water have been displaced or until the pH, temperature, specific conductance, color, and odor of the discharge is noted to stabilize. Purging operations shall be conducted using a PVC or stainless steel bottom-discharge bailer or bladder pump. All sampling shall be conducted using a 2-inch stainless steel Kemmerer sampler, bailer, or bladder pump. As the first step of ground water sampling operations at each well, water level measurements shall be taken to the nearest 0.01 foot with respect to an established surveyed mark-point on top of the well casing.

15. Second-column confirmation shall be required when detection limits exceed values identified in Attachment 1, for EPA Methods 509A and 509B. Second-column confirmation shall be conducted on a maximum of 50% of the samples collected for these analyses. Total number of samples for Methods 601 and 602 in Attachment 1 include these confirmation analyses.

16. Sediment samples will be collected using a hand piston sampler. Total number of sediment samples shall not exceed 11.

17. Piezometers shall be installed for determination of ground water flow. Total piezometer footage for this project shall not exceed 635 linear feet.

B. In addition to items delineated in A above, conduct the following specific actions at the following sites on Maxwell AFB:

1. Electroplating Waste Disposal Site

a. Conduct a geophysical survey incorporating magnetometer and electromagnetic (EM) techniques to delineate the horizontal extent of the burial site, confirm the location of buried drums, and locate any leachate plumes.

b. Install a total of 4 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 25 feet; therefore, total piezometer footage shall be 100 feet.

c. Install one well upgradient and three wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 100 feet. Screened casing shall not exceed 15 feet per well, for a maximum of 60 feet, for this site. Each well shall be sampled once, for a total of 4 samples. Analyze the samples for the parameters listed in Attachment 2, list A.

2. Surface Drainage System

a. A total of 6 sediment samples shall be taken from the West End Ditch, 3 adjacent to the electroplating waste site and 3 adjacent to landfills 4, 5 and 6.

b. One sediment sample shall be taken from the ditch flowing across landfill 5 into the West End Ditch.

c. A total of 3 sediment samples shall be taken from the drainage ditch located southeast of the C.E. Drum Storage Area.

d. One sediment sample shall be taken from the drainage ditch that empties into the lake in the northeast corner of the base, where the concrete lining discontinues.

e. Analyze all 11 sediment samples for the parameters listed in Attachment 2, list B, excluding total dissolved solids.

f. Analyze 4 surface water samples from various locations along West End Ditch for the parameters in Attachment 2, List B.

3. Landfill No. 3 and FPTA No. 2

a. Conduct a geophysical survey incorporating magnetometer and electromagnetic techniques to delineate the horizontal extent of the landfill and locate any leachate plumes.

b. Install a total of 3 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 25 feet; therefore, total piezometer footage shall be 75 feet.

c. Install one well upgradient and two wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 75 feet. Screened casing shall not exceed 20 feet per well, for a maximum of 60 feet for this site. Each well shall be sampled once, for a total of 3 samples. Analyze the samples for the parameters listed in Attachment 2, list C.

4. Fire Protection Training Area No. 1

a. Install a total of 3 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 25 feet; therefore, total piezometer footage shall be 75 feet.

b. Install one well upgradient and two wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 75 feet. Screened casing shall not exceed 20 feet per well, for a maximum of 60 feet for this site. Each well shall be sampled once, for a total of 3 samples. Analyze the samples for the parameters listed in Attachment 2, list C.

5. Landfill Nos. 4, 5, and 6

a. Conduct a geophysical survey incorporating magnetometer and electromagnetic techniques to delineate the horizontal extent of the landfill areas and locate any leachate plumes.

b. Install a total of 4 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 25 feet; therefore, total piezometer footage shall be 100 feet.

c. Install one well upgradient and three wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 100 feet. Screened casing shall not exceed 15 feet per well, for a maximum of 60 feet for this site. Each well shall be sampled once, for a total of 4 samples. Analyze the samples for the parameters listed in Attachment 2, List C.

d. Sample each of the three existing wells to the south and east of Landfill No. 6 one time for a total of three samples (if the wells are accessible). Analyze the samples for the parameters listed in Attachment 2, List C.

6. C.E. Drum Storage Area

a. Install a total of 3 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 70 feet; therefore, total piezometer footage shall be 210 feet.

b. Install one well upgradient and two wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 210 feet. Screened casing shall not exceed 20 feet per well, for a maximum of 60 feet for this site. Each well shall be sampled once, for a total of 3 samples. Analyze the samples for the parameters listed in Attachment 2, list C.

7. Landfill No. 2

a. Conduct a geophysical survey incorporating magnetometer and electromagnetic techniques to delineate the horizontal extent of the landfill area and locate any leachate plumes.

b. Install a total of 3 piezometers to determine the depth and configuration of the water table for predicting shallow ground water flow. The average depth for each piezometer shall be 25 feet; therefore, total piezometer footage shall be 75 feet.

c. Install one well upgradient and two wells downgradient to evaluate ground water quality. Total footage of wells shall not exceed 75 feet. Screened casing shall not exceed 15 feet per well, for a maximum of 45 feet for this site. Each well shall be sampled once, for a total of 3 samples. Analyze the samples for the parameters listed in Attachment 2, list C.

C. Well Cleanup

All well drill cuttings shall be removed and the general area cleaned following the completion of each well. Only those drill cuttings suspected as being a hazardous waste (based on discoloration, odor, or organic vapor detection instrument) shall be properly containerized (according to local civil engineering office requirements) by the contractor for eventual government disposal. The suspected hazardous waste shall be tested by the contractor for EP toxicity and ignitibility. The contractor is not responsible for ultimate disposal of the drill cuttings. Disposal will be conducted by base personnel.

D. Data Review

Results of sampling and analysis shall be tabulated and incorporated in the Informal Technical Information Report (as specified in Item VI below) and forwarded to the USAF OEHL for review. Results shall also be forwarded as available in the next monthly R&D status report.

E. Reporting

1. A draft report delineating all findings of this field investigation shall be prepared and forwarded to the USAF OEHL (as specified in Item VI below) for Air Force review and comment. This report shall include a discussion of the regional/site specific hydrogeology, well and boring logs, data from water level surveys, groundwater surface and gradient maps, water quality and soil analysis results, available geohydrologic cross sections, and laboratory quality assurance information. The report shall follow the USAF OEHL supplied format (mailed under separate cover).

2. The recommendation section will address each site and list them by categories. Category I will consist of sites where no further action (including remedial action) is required. Data for these sites are considered sufficient to rule out unacceptable health or environmental risks. Category II sites are those requiring additional monitoring or work to quantify or further assess the extent of current or future contamination. Category III sites are sites that will require remedial actions (ready for IRP Phase IV actions). In each case, the contractor will summarize or present the results of field data, environmental or regulatory criteria, or other pertinent information supporting these conclusions.

F. Meetings

The contractor's project leader shall attend one meeting with Air Force headquarters and regulatory agency personnel to take place at a time to be specified by the USAF OEHL. The meeting shall take place at Maxwell AFB for a duration of one day (eight hours).

II. SITE LOCATION AND DATES:

Maxwell AFB AL
Date to be established

III. BASE SUPPORT: Maxwell AFB will provide the following base support:

A. Secure permission from legal landowner of the area surrounding landfills 4, 5, and 6 for soil boring and monitor well installations.

B. Determine structural soundness of the bridge across the West End Ditch between landfills 3 and 4.

C. Conduct site preparation between landfills 4, 5, and 6 so that drill rigs can maneuver into position.

IV. GOVERNMENT FURNISHED PROPERTY: None

V. GOVERNMENT POINTS OF CONTACT:

1. Maj Dennis D. Brownley
USAF OEHL/TSS
Brooks AFB TX 78235
(512) 536-2158
AV 240-2158

2. Capt Mark D. Knuth
USAF Rgn Hospital Maxwell/SGPB
Maxwell AFB AL 36112
(205) 293-5848
AV 875-5848

VI. In addition to sequence numbers 1*, 5, and 11 in Attachment 1 to the contract, which are applicable to all orders, the sequence numbers listed below are applicable to this order. Also shown are data applicable to this order.

- * Forward a copy of the R D Status Report to all government POC's identified in Section V.

<u>Sequence No.</u>	<u>Block 10</u>	<u>Block 11</u>	<u>Block 12</u>	<u>Block 13</u>	<u>Block 14</u>
3	O/Time	*	*		
4	One/R	4 Mar 85	19 Mar 85	12 Aug 85	**

- * Upon completion of analytical effort before submission of first draft report.

** Two draft reports will be required. After incorporating Air Force comments concerning the first draft report, the contractor shall supply the USAF OEHL with one copy of the second draft report. Upon acceptance of the second draft, the USAF OEHL will furnish a distribution list for the remaining 24 copies of the second draft. The contractor shall supply 50 copies plus the original camera ready copy of the final report.

Attachment 1
Analytical Methods and Required Detection Limits
(For Water Unless Otherwise Shown)

PARAMETER	METHOD	DETECTION LIMIT	SAMPLES	QA	TOTAL SAMPLES
Total Organic Carbon (TOC)	EPA 415.1	1000 µg/L (1000 µg/g soil)	31	4	35
EP Toxicity	40 CFR 261.24	**	5	1	6
Ignitibility	40 CFR 261.21	***	5	1	6
Total Organic Halogens (TOX)	EPA 9020	5 µg/L (5 µg/g. soil)	27	3	30
OIL and Grease (using IR)	EPA 413.2	100 µg/L (100 µg/g. soil)	27	3	30
Total Dissolved Solids (TDS)	EPA 160.1	1000 µg/L	31	3	34
Copper	EPA 220.1	20 µg/L (2 µg/g. soil)	31	3	34
Nickel	EPA 249.1	100 µg/L (10 µg/g. soil)	31	3	34
Cadmium	EPA 213.2	10 µg/L (1 µg/g. soil)	31	3	34
Chromium	EPA 218.1	50 µg/L (5 µg/g. soil)	31	3	34
Cyanide	Standard 412	10 µg/L (1 µg/g. soil)	31	3	34
Zinc	EPA 289.1	50 µg/L (5 µg/g. soil)	31	3	34
Phenols	EPA 420.1	1 µg/L (1 µg/g. soil)	31	3	34
Lead	EPA 239.2	20 µg/L (2 µg/g. soil)	27	3	30

<u>PARAMETER</u>	<u>METHOD</u>	<u>DETECTION LIMIT</u>	<u>SAMPLES</u>	<u>QA</u>	<u>SAMPLES</u>
Arsenic	EPA 206.2 or 206.3	10 µg/L (1 µg/g, soil)	27	3	30
Mercury	EPA 245.1	1 µg/L (.1 µg/g, soil)	27	3	30
Iron	EPA 236.1	100 µg/L	16	2	18
Sulfate	EPA 375.4	1000 µg/L	16	2	18
Barium	EPA 208.2	200 µg/L	16	2	18
Fluoride	EPA 340.2	100 µg/L	16	2	18
Nitrate	EPA 353.2	100 µg/L	16	2	18
Selenium	EPA 270.3	10 µg/L	16	2	18
Silver	EPA 272.2	10 µg/L	16	2	18
Endrin	Standard 509A	.02 µg/l	24	3	41.....
Lindane	Standard 509A	.01 µg/L	24	3	41.....
Methoxychlor	Standard 509A	.20 µg/L	24	3	41.....
Toxaphene	Standard 509A	1.0 µg/L	24	3	41.....
2,4-D	Standard 509B	.06 µg/L	24	3	41.....
2,4,5-TP	Standard 509B	.06 µg/L	24	3	41.....
pH	-----	-----	31	-----	31

* Detection limit for TOC must be 3 times the noise level of the instrument. Laboratory distilled water must show no response; if it shows a response, corrections of positive results must be made.

us/L of solution

** Metal

As	10
Ba	200
Cd	10
Cr	50
Pb	20
Hg	1
So	10
Ag	10

*** Find if sample is ignitable at 140 degrees F. or below. If so, it is a hazardous waste.

**** Total of 41 includes second column confirmation for 50% of the samples (14).

Attachment 2

LIST OF ANALYTICAL PARAMETERS AT MAXWELL AFB

List A

Copper	Chromium	pH	Total Dissolved Solids
Nickel	Total Organic Carbon	Zinc	
Cadmium	Cyanide	Phenols	

List B

Copper	Total Organic Carbon	Lead	Phenols
Nickel	Total Dissolved Solids	Cyanide	Arsenic
Cadmium	Oil and Grease	pH	Mercury
Chromium	Total Organic Halogens	Zinc	

List C

Total Organic Halogens	Total Dissolved Solids	Copper	Cyanide
Total Organic Carbon	Phenols	Iron	Sulfate
Oil and Grease	pH	Nickel	Zinc

Interim Primary Drinking Water Standards (selected list)

Arsenic	Fluoride	Selenium	Methoxychlor
Barium	Lead	Silver	Toxaphene
Cadmium	Mercury	Endrin	2,4-D
Chromium	Nitrate	Lindane	2,4,5-TP

APPENDIX D--QUALITY ASSURANCE PLAN

APPENDIX D
QUALITY ASSURANCE PLAN

The purpose of the QA Plan is to provide processes for controlling the validity of the data generated in all phases of the sampling and analysis efforts proposed under the scope of work. The procedures detailed as follows describe the general methodologies during the study and when implemented will provide documentation of the individual work elements and mechanism by which "data gaps" can be controlled. It should be noted that procedures outlined below may not apply to all circumstances which may arise during the course and scope of the study. Deviation from these procedures will be noted in the field logbooks and discussed with OEHL personnel to determine corrective actions.

Two types of audit procedures will be used by QA to assess and document performance of project staff--system audits and performance audits. These are performed at frequent intervals under the direction of the Project QA Supervisor. These audits form one of the bases for corrective action requirements and constitute a permanent record of the conformance of measurement systems to QA requirements.

System audits are inspections of training status, records, QC data, calibrations, and conformance to Standard Operating Procedures (SOPs) without the analysis of check samples. System audits will be performed periodically on laboratory and office operations or on field operations. The development and approval of the project Work Plan constitutes the initial system audit for this study.

The systems audit protocol is summarized as follows:

1. Field Operations--The Project QA Supervisor will periodically check:

- a. Field notebooks, logsheets, bench sheets, tracking forms, and report any inconsistencies and/or omissions;
 - b. Field sampling plans; and
 - c. Sample site briefing package.
2. Laboratory Operations--The Project QA Supervisor will periodically check:
 - a. Parameter and/or laboratory notebooks;
 - b. Instrument logbooks;
 - c. Sample log-in, dispensing, and labeling for analysis;
 - d. Updating of QC criteria for spike recoveries; and
 - e. Final approval of data from each sample lot.In addition, the Project QA Supervisor will monitor all analyses to assure complete adherence to approved analytical methods.
3. Final Reports--The Project QA Supervisor will review all final reports and deliverables to OEHL.

Performance audits will include evaluation and analysis of check samples. A performance evaluation sample from EPA will be analyzed periodically along with the regular samples.

ESE's laboratory is certified for drinking water analysis by the Florida Department of Health and Rehabilitative Services according to the regulations set forth under the Florida Safe Drinking Water Act (Chapter 403.863, F.S.). ESE is also certified by the National Institute for Occupational Safety and Health (NIOSH) through their NIOSH Proficiency Analytical Testing (PAT) Program.

ESE routinely participates in performance test sample programs administered by:

1. EPA, Environmental Monitoring and Support Laboratory-Cincinnati (EMSL-CI);
2. EPA, Environmental Monitoring and Support Laboratory-Research Triangle Park (EMSL-RTP);
3. EPA, Region IV;
4. Florida Department of Environmental Regulation;

5. Florida Department of Health and Rehabilitative Services;
6. Alabama Department of Health;
7. U.S. Army Corps of Engineers, South Atlantic Division; and
8. American Industrial Hygiene Association (AIHA) (ESE is an AIHA-accredited laboratory).

The results of these interlaboratory studies will be periodically evaluated by the Project QA Supervisor during the project as part of the performance audits.

D.1 WELL DRILLING

Prior to drilling any test borings and installing any monitoring wells, each proposed drilling location will be cleared with the Base Civil Engineering Department to avoid drilling into buried cables, pipes, etc. The Civil Engineering Department will approve all locations. If required, appropriate drilling permits will be acquired.

Prior to commencement of any portion of the proposed drilling plan the drilling subcontractor will complete the following requirements:

1. Arrange access to all sites where drilling of wells is proposed.
2. Steam clean all drilling equipment prior to movement to Maxwell AFB.
3. Arrange with Maxwell AFB personnel for the storage of all well-drilling equipment and well-installation supplies in a clean and secure area. At each drill location, clean unused equipment/supplies will be temporarily stored on sheets of disposable polyethylene to eliminate contamination from the native soils at the well location.

The ESE Site Geologist will be present during drilling of all wells and will maintain drilling logs. Any abandoned borings will be grouted in the presence of the ESE Site Geologist. All grout will be mixed and installed according to standard specifications.

The drilling will be performed under subcontract and will proceed as follows:

1. Unchlorinated water for drilling and well installations will be obtained by the driller. Portable tubs will be used to hold drilling water during circulation, if required.
2. All drill cuttings will be recovered and stored in 55-gallon (gal) drums. Disposal of the cuttings will be the responsibility of Maxwell AFB.
3. Drilling will be conducted by the drilling subcontractor under the direct supervision of the assigned ESE Geologist.
4. Between borings, the drilling tools will be cleaned with unchlorinated water to remove all traces of soil, rock, or other contaminants.

D.2 BORING PROCEDURES AND SOIL SAMPLING

The borings for all ground water monitoring wells will be completed using a truck-mounted portable drilling unit equipped with a hollow-stem auger device with a 6-inch (minimum) inside diameter and 8-inch (minimum) outside diameter. The unit is operated without water, unless necessary, and produces an 8-inch diameter borehole. The 4-inch PVC well pipe and screen are installed through the center of the hollow drill stem and positioned at the appropriate depths. As the auger is withdrawn from the hole, the annular space is backfilled with suitable packing material. This technique prevents collapse of the borehole that may occur if the auger is removed from the hole and the well pipe introduced from the top of the empty hole.

Eight-inch boreholes extending to a minimum depth of 25 ft below ground surface will be excavated. The material at Maxwell AFB consists of unconsolidated gravels, sands, silts, and clays to this depth, and the boreholes may have a tendency to collapse. Continuous split-spoon soil sampling will be concomitant with boring, and most boreholes will be sampled through their expected depth of 25 ft.

The split-spoon soil samples will be retained by the driller and subsequently stored by ESE. If ground water proves to be contaminated, the soil samples will be analyzed for the same pollutants; if not, they will be disposed of following completion of the Phase II program. The split-spoon samples must be of undisturbed soil and, therefore, the samples must be pushed ahead of the auger in all instances, and sampling must be continuous.

Split-spoon soil samples will be sectioned and stored in labeled glass containers and kept in cooled, insulated compartments in the field and enroute to the laboratory at ESE. Each container will be marked with the sample depth interval, top and bottom of the sample, date, and time. The split-spoon sampler must be cleaned with approved, dechlorinated water between each sampling event (i.e., each time a sample is removed from the tube).

Monitor well depths and screening lengths are discussed for each of the sites individually in Sec. 3. Well depths vary from 20 to 30 ft and are screened into and below the water table from 5 or 10 to 20 or 30 ft. The ESE Site Geologist will maintain regular contact with the major command (MAJCOM) during the drilling program and will make recommendations for well placement to MAJCOM in the event that unique geohydrologic conditions dictate variation of the plans presented in this document.

D.3 WELL-DRILLING LOGS AND DOCUMENTATION

The driller and the ESE Site Geologist will both maintain accurate drilling logs for all boreholes excavated. The names of all persons present and involved in the drilling operation will be recorded in the logs. Each well will be fully described on a well log as it is being drilled. Transcription of the log from a field notebook to log form will not be permitted. Upon completion of each well, information from the well logs will be transferred to OEHL. Data included in the logs are:

1. Depths will be recorded in feet and fractions thereof.
2. Soil descriptions, in accordance with the Unified Soil Classification System, will be prepared in the field by the Site Geologist.
3. Soil samples will be fully described on the log. For split-spoon samples, the description will include:
 - a. Classification,
 - b. Unified Soil Classification System symbol,
 - c. Secondary components and estimated percentage,
 - d. Color,
 - e. Plasticity,
 - f. Consistency (cohesive soil) or density (noncohesive soil),
 - g. Moisture content, and
 - h. Texture/fabric/bedding.Cutting descriptions will include basic classification, secondary components, and other parameters that are apparent.
4. Numerical, visual estimates will be made of secondary soil constituents. If terms such as "trace," "some," or "several" are used, their quantitative meanings will be defined in a general legend.
5. The length of sample recovered for each sampled interval for drive (split-spoon) samples will be recorded.
6. Blow counts, hammer weight, and length of fall for split-spoon samples will be recorded.
7. Rock core, if obtained, will be fully described on the log. Core description will include:
 - a. Classification by rock type,
 - b. Lithologic characteristics,
 - c. Bedding characteristics,
 - d. Color,
 - e. Hardness,
 - f. Degree of cementation,
 - g. Texture,
 - h. Structure,

- i. Degree of weathering,
 - j. Solution or void conditions,
 - k. Primary and secondary permeability estimates and rationale, and
 - l. Length of core recovered and rock quality designation (RQD).
- 8. The estimated interval for each sample will be specified.
 - 9. Depth to water will be indicated along with the method of determination, as first encountered during drilling. Any distinct water-bearing zones below the first zone also will be noted.
 - 10. When drilling fluid is used, fluid losses, quantities lost, and the intervals over which they occur will be recorded.
 - 11. The drilling equipment used will be described generally on each log, including such information as rod size, bit type, pump type, rig manufacturer, and model.
 - 12. The drilling sequence will be recorded on each log.
 - 13. All special problems will be recorded.
 - 14. The dates for the start and completion of all borings will be recorded on the log.
 - 15. Lithologic boundaries will be noted on the boring log.
 - 16. The boring logs will be submitted to the OEHL within 10 working days after each individual boring is completed. In cases where a monitoring well is inserted into the boring hole, both the log for that boring and the installation sketch will be submitted within 10 working days.

Evaluation of the existing geologic and hydrogeologic data at Maxwell AFB indicates that the ground water sampling wells to be installed at Maxwell AFB may be screened totally within a saturated soil column. Although screening intervals may be proposed in other sections of the plan, the actual screened interval will be determined by evaluation of the geologic data obtained during the drilling operations.

D.4 DESCRIPTION OF GROUND WATER SAMPLING WELLS

Fig. D-1 shows a typical well configuration for a monitor well in unconsolidated, overburden material. The placement of the well screen in the saturated soil will be deemed appropriate if standing water is found in the boring at the well site after waiting overnight.

The monitor wells will penetrate the shallow water table and, in general, will extend to depths up to 30 ft. The well will be installed in a 6- to 8-inch borehole and will consist of threaded Schedule 40 PVC pipe (which is resistant to low pH and cyanide-rich ground water), with 0.010-inch slots (screen) in the bottom 5- or 10-ft interval, a gravel pack in the annular space between the screen and the borehole, a bentonite clay seal on top of the gravel pack, and grout in the upper annular space to the surface. The bottom of the well will be capped before installation, and a vented cap will be installed at the top of each monitor well. A protective steel casing and a locking cap will be installed for security reasons.

D.5 GROUND WATER SAMPLING WELL INSTALLATION PROCEDURES

When a boring is completed, the ESE Site Geologist will visually inspect the hole to ensure plumbness and cleanliness. Plumbness will be obtained by careful leveling of the drill rig prior to commencement of the drilling. Additionally, the drilling will proceed in an efficient and controlled manner to eliminate wobble/chatter in the drill stem. No problems are expected from artesian systems.

All well installations will begin within 48 hours of boring completion and, once begun, will continue, uninterrupted, until completion. Any temporary casing used to maintain the borehole will remain in the hole up to and including the time of grouting. The well screen and casing will be carefully cleaned with unchlorinated water prior to installation in the hole. All well screens will have a solid bottom. Solid casing will extend from the screen to approximately 2.5 ft above land surface.




Figure D-1
TYPICAL MONITOR WELL CONSTRUCTION

INSTALLATION
RESTORATION PROGRAM
Maxwell Air Force Base

Filter material will be installed around and to the top of the well screen. As the 5-ft bentonite seal is placed on top of the filter material, unchlorinated water from the approved source will be added, when necessary, to assure that the pellets expand to form a tight seal. Properly wetted bentonite pellets are the most time-effective form of bentonite for this application.

The bentonite-cement grout seal will extend from the top of the bentonite seal to the land surface. Grouting will be completed as a continuous operation in the presence of the ESE Site Geologist. The grout will be pumped into the annular space under pressure using a tremie pipe placed at the top of the bentonite seal to ensure a continuous grout seal. The protective casing will be sealed in the grout. Identification and protective posts will be installed around the well to prevent damage to the wells by vehicular operation. A coarse gravel pad, 0.5-inch thick, extending 4 inches radially from the protective casing, will be placed at each water sampling well.

The following materials will be used in well construction:

1. Casing used in the well will be threaded PVC Schedule 40, 4-inch nominal inside diameter. The well screen will be factory slotted, with a slot width of 0.010 inch. A screw-on cap will be installed on each of the wells. The four monitor wells at the electroplating waste disposal site (Site 1) will be constructed of corrosion-resistant stainless steel able to withstand low pH and cyanide waste waters.
2. Grout will be composed by weight of 10 parts Portland cement to one-half part bentonite, with a maximum of 10 gal of approved water per 94-pound (lb) bag of cement. Bentonite will be added after mixing of the cement and water.
3. Bentonite pellets used in the seal will be a commercially available product designed for well-sealing purposes.
4. Sand material used in the filter envelope around the well screen will be selected to be compatible with both the screen

slot size and aquifer materials. A coarse sand is recommended, but, if the well is screened in a gravel horizon, coarser material should be used.

5. A 6-inch protective iron casing will be installed around all wells. This casing will extend approximately 2.5 ft above land surface and will be seated 2.5 ft into the well seal grout. This casing will be vented to the atmosphere via a lockable, hinged cap. This cap will prevent entry of water but will not be airtight. In this manner, the well will be in open connection to the atmosphere to allow for water level stabilization. A 0.25-inch diameter drainage port will be installed, centered 0.125-inch above the level of the internal monitor collar. The same key will be used for all padlocks at the site.
6. A sketch of the well installation will be included on the boring log and show, by depth, the bottom of the boring, screen location, coupling location, granular backfill, seals, grout, cave-in, and height of riser above ground surface. The actual composition of the grout, seals, and granular backfill will be recorded on each sketch.
7. Well sketches will include the protective casing detail.
8. After the grout seal has set (approximately 24 hours), it will be checked for settlement, and additional grout (of approved composition) will be added to fill any depressions.

D.6 WELL DEVELOPMENT

The initial development or the purging of the drilling fluid from monitor wells will be recorded and submitted to MAJCOM within 3 working days after development. The development will be performed, as soon as practical, after well installation. The following data will be recorded for development:

1. Well designation.
2. Date of well installation.
3. Date of development.

4. Static water level before and 24 consecutive hours after development.
5. Quantity of water loss during drilling and fluid purging, if water is used.
6. Quantity of standing water in well and annulus (30-percent porosity assumed for calculation) prior to development.
7. Specific conductivity, temperature, and pH measurements taken and recorded at the start, twice during, and at the conclusion of development. Calibration standards will be run prior to, during, and after each day's operation in the field.
8. Depth from top of well casing to bottom of well.
9. Screen length.
10. Depth from top of well casing to top of sediment inside well, before and after development.
11. Physical character of removed water, including changes during development in clarity, color, particulates, and odor.
12. Type and size/capacity of pump and/or bailer used.
13. Description of surge technique, if used.
14. Height of well casing above ground surface.
15. Quantity of water removed and time for removal.

Development of wells will be accomplished with an electric-powered submersible pump until the water is clear and the well sediment-free to the fullest extent practical. Four-inch Schedule 40 PVC wells will not permit the use of a 4-inch submersible pump. A 3-inch pump will be available for use at Maxwell AFB. If well yields cannot sustain the flow rate of the submersible pump, a bottom discharge bailer will be used. Water will not be added to the well to aid in development. The pump or bailer will be rinsed with the approved drilling water and allowed to air dry prior to use in the next well. Well development data will be recorded in the field in a tabular format.

Well development will begin no sooner than 48 hours after completion of the mortar collar placement. Development will proceed until the

following conditions are met:

1. The well water is clear to the unaided eye.
2. The sediment thickness remaining in the well is less than 5 percent of the screen length.
3. At least five well volumes (including the saturated filter material in the annulus) have been removed from the well.
4. A 1-pint (pt) sample of the last water obtain from the development process for each well is retained and stored in an insulated compartment maintained at 4 degrees Celsius (°C). This water was examined by the onsite geologist to determine if the well had been suitably developed to be used as a monitor well.
5. The cap and all internal components of the well casing above the water table are rinsed with well water to remove all traces of soil/sediment/cuttings. This washing will be conducted before and/or during development.

D.7 WATER LEVEL MEASUREMENTS

All water level measurements at the various wells will be obtained using the U.S. Geological Survey (USGS) wetted-tape method. This procedure is accurate to 0.01 ft. The tape will be rinsed with water from the approved source, wiped with a fresh cloth, and allowed to air dry between consecutive water level measurements.

At least one complete set of static water level measurements for all wells will be made over a single, consecutive 10-hour period. Relative water levels in the wells will also be determined.

D.8 SURVEYING

Each water sampling well installed at Maxwell AFB during this study will be surveyed by a professional land surveyor registered in the state of Alabama.

Each water sampling well will be surveyed to establish its map coordinates using the Alabama Plane Coordinate System, Western Zone,

with an accuracy no less than 1:10,000 (one in ten thousand). Additionally, elevations for the natural ground surface at each sampling well and the top of the PVC casing will be determined to within 1/100 ft using the vertical datum established by USGS.

The surveyor will plot each well site on the Maxwell AFB base map (supplied by ESE). The elevations of both the top of the monitor well (top of the PVC pipe) and of the ground surface at the well at each site will be noted on the map adjacent to the point representing that location. Additionally, the map coordinates for each point will be included on each map or appended to the map in tabulated form.

D.9 GROUND WATER SAMPLING

Ground water sampling at Maxwell AFB will begin after the new monitor wells have been allowed to reach equilibrium (no less than 14 days after well development). The following procedures will be followed on the day of sampling:

1. The depth to water will be measured from the top of casing.
2. The well depth will be sounded and recorded. The depth of the water in the well will be calculated.
3. During the initial sampling of a new monitor well, the depth to the water/sediment interface in the well will be measured and recorded.
4. Samples will be taken after the fluid in the screen, well casing, and saturated annulus has been exchanged five times. In the event of low well yields (e.g., in the presence of fine-grained sediments and/or limited bedrock fracturing), some wells may have slow recovery rates. A decision to reduce the well purging to less than five volumes will be recommended by ESE only if excessive time would elapse attempting to collect one or two samples from low-yielding wells. This decision will be subject to approval by the USAF. The amount of fluid purged will be measured and recorded. Sampling will be accomplished by a bailer constructed of inert materials (PVC). No glue will be used in the construction of these bailers.

5. To protect the wells from contamination during sampling procedures, the following guidelines will be followed:
 - a. A separate bailer will be supplied for each well. After each bailer is used to sample each well for the first time, it will be allowed to remain in the well. Each bailer will be etched with the number of the sampling well.
 - b. If a pump is used to purge the standing water from the well, the pump and the hoses will be thoroughly cleaned between the samples, using the approved drilling water source. All sampling, however, will be performed with the dedicated bailer.
 - c. All sampling equipment will be protected from ground water contact by polyethylene plastic sheeting to prevent soil contamination from tainting the ground water samples.
6. Conductivity, pH, and temperature will be measured prior to sampling.
7. If the wells are flowing, a flow rate will be determined, and five volumes of water will be allowed to flow out of the well prior to sampling.

Inert threaded PVC well casings will be used in this program.

Adsorption of certain compounds on the plastic surface may affect the apparent ground water concentration. However, the following precaution will be taken to minimize adsorption of analytes by PVC. Each well will be purged and then sampled as soon as sufficient water returns. In this manner, the contact time between the water sample and the PVC will be kept to the shortest possible period.

During the sampling of each monitor well, information regarding the sampling will be kept in a notebook. The following data will be collected:

1. Well number;
2. Date;
3. Time;

4. Static water level;
5. Depth of well;
6. Number of bailer volumes removed, if applicable;
7. Pumping rate, if applicable;
8. Time of pumping, if applicable;
9. Draw down water level;
10. In situ water quality measurements such as pH, specific conductance, and temperature;
11. Fractions sampled and preservatives;
12. Weather conditions and/or miscellaneous observations; and
13. Signature of sampler and date.

Each sample will be carefully labeled so it can be identified by laboratory personnel. The sample label will include the project number, sample number, time and date, and sampler's initials. All samples will be identified with non-water-soluble ink on a standard preprinted and prenumbered label immediately after collection. Information concerning preservation methods, matrix, and sample location will be included on the label. Samples will be shipped in styrofoam ice chests and will be kept below 4°C from time of sample collection until analysis.

D.10 SURFACE WATER SAMPLING

Prior to surface water sampling, the following data will be noted and recorded in the field notebook:

1. Site number or location;
2. Date;
3. Time (24-hour system);
4. Antecedent weather conditions, if known;
5. In situ parameter measurements (temperature, conductivity, and pH);
6. Fractions and preservatives;
7. Any other pertinent observations (odor, fish, etc.); and
8. Signature of sampler and date.

At the conclusion of each day in the field, the Sampling Team Leader will review each page of the notebook for errors and omissions. He/she will then date and sign each reviewed page.

All field instrument calibrations will be recorded in a designated portion of the notebook at the time of the calibration. Adverse trends in instrument calibration behavior will be corrected.

The sample will be collected in a manner which will minimize its aeration and prevent oxidation of reduced compounds in the sample. The container will be filled until it overflows without air bubbles and then tightly capped. Special attention will be given to minimize air contact with the water sample. Sampling procedures and precautions for the volatile fraction collection are identical to the ground water procedures.

Each sample will be carefully labeled so it can be identified by laboratory personnel. The sample label will include the project number, sample number, time and date, and sampler's initials. All samples will be identified with non-water-soluble ink on a standard preprinted and prenumbered label immediately after collection. Information concerning preservation methods, matrix, and sample location will be included on the label. Samples will be shipped in styrofoam ice chests and will be kept below 4°C from time of sample collection until analysis.

D.11 SOIL AND SEDIMENT SAMPLING

Prior to soil and/or sediment sampling, the following data will be noted and recorded in the field notebook:

1. Site number, location, or designation;
2. Date;
3. Time (24-hours system);
4. Antecedent weather conditions, if known;

5. Any other pertinent observations (e.g., vegetation, substrate characteristics, etc.); and
6. Signature of sampler and date.

At the conclusion of each day in the field, the Sampling Team Leader will review each page of the notebook for errors and omissions. He/she will then date and sign each reviewed page.

D.12 SOIL SAMPLING

The soils collected during this study will consist of the split-spoon samples collected during the drilling of wells. These samples will be collected and placed in glass wide-mouth jars with Teflon®-lined lids. Sample containers will be labeled with a preprinted label, chilled to 4°C, and shipped to the laboratory for storage. These samples were analyzed in the Phase IIa study. If contaminants are found, these samples are available for analysis in the Phase IIb study.

D.13 SEDIMENT SAMPLING

1. All sediment samples will be collected with a hand piston sampler or other appropriate device.
2. After sampling, depth of water at each sampling point will be measured and recorded.
3. Sampling equipment will be thoroughly cleaned with water from an approved source and solvent rinsed with acetone and hexane and allowed to air dry.
4. Sediment samples will be placed in glass containers with Teflon®-lined lids, shipped under ice, and stored at 4°C.

D.14 LABORATORY

The Laboratory Task Manager is responsible for implementing the laboratory QC procedures. The QA Supervisor will monitor the performance of the analysts and the Chemical Analysis Supervisor for implementation of proper QC checks and to final approve all data.

For analyses conducted in this project, the following QC checks will apply:

1. At least five standards for standard curve (three standards for organic analyses) [for gas chromatograph/mass spectrometer (GC/MS) analyses and metals analyses by inductively coupled argon plasma (ICAP) one calibration standard is run and a daily response factor is established after initial calibration],
2. Correlation coefficient for curve is greater than 0.995,
3. Percent recovery for spikes is within acceptance criteria as described below,
4. Samples are within range of standards,
5. At least 10 percent of the samples are replicates (except GC/MS), and
6. At least 5 percent of the samples are spiked.

D.15 DATA ANALYSES AND REPORT REVIEW

Peer review of all deliverable reports and data supporting this project will be performed by technically qualified individuals from each major discipline represented in the particular deliverable. Fig. D-2 is a sample Deliverable Review Form to be used in this project.

[illegible]

SEE SHEET 3 OF 3 FOR
CONTINUATION OF PROPERTY
LINE AND CLEAR ZONE

E 848,000

E 850,000

N 872,000

APPROACH

CLEAR ZONE 2000' X 3000'

ZONE

Cemetery

GLIDE ANGLE 50:1

WATER

4-2 4-3

CLEAR

GLIDE ANGLE 50:1

TAXIWAY 3017

N 870,000

3-2

5-2

3-3

5-3

5-4

3-1

Fire And Rescue Training

C

TAXIWAY F 3028 (CLOSED)

X TAXIWAY 2

NW-SE RUNWAY 7000' X 300'

TRUE BEARING N 50°17' E 3028

81



10

11

12


13

E 856,000

E 858,000

MONITOR WELL

Latitude	Longitude	Pt No.	
32° 23' 19.858"	86° 22' 17.154"	A	870
32° 22' 20.86 "	86° 21' 34.47 "	B	864
32° 22' 07.369"	86° 22' 14.958"	C	869
32° 22' 00.631"	86° 22' 10.463"	1-1	862
32° 22' 03.687"	86° 22' 16.682"	1-2	863
32° 22' 00.319"	86° 22' 16.632"	1-3	862
32° 21' 58.826"	86° 22' 16.514"	1-4	862
32° 23' 11.759"	86° 22' 18.469"	3-1	869
32° 23' 11.108"	86° 22' 28.659"	3-2	869
32° 23' 08.025"	86° 22' 27.438"	3-3	869
32° 23' 37.039"	86° 21' 59.973"	4-1	872
32° 23' 32.467"	86° 22' 00.824"	4-2	871
32° 23' 32.404"	86° 21' 58.888"	4-3	871
32° 22' 54.899"	86° 22' 35.420"	5-1	868
32° 23' 08.791"	86° 22' 28.872"	5-2	869
32° 23' 04.211"	86° 22' 27.220"	5-3	869
32° 22' 58.387"	86° 22' 24.878"	5-4	868
32° 23' 33.378"	86° 21' 25.695"	6-1	872
32° 23' 34.204"	86° 21' 21.952"	6-2	872
32° 23' 32.989"	86° 21' 23.403"	6-3	872
32° 22' 12.942"	86° 21' 24.521"	7-1	863
32° 22' 05.976"	86° 21' 26.283"	7-2	863
32° 22' 06.058"	86° 21' 39.021"	7-3	863



13

14

15

E 860,000

K

MONITOR WELL LOCATIONS

Latitude	Longitude	Pt. No.	Northing	Easting	Elevation
32° 23' 19.858"	86° 22' 17.154"	A	870,707.7240	848,383.8400	168.08
32° 22' 20.86 "	86° 21' 34.47 "	B	864,784.2920	852,107.5590	
32° 23' 07.369"	86° 22' 14.958"	C	869,447.5870	848,585.4250	159.33
32° 22' 00.631"	86° 22' 10.463"	1-1	862,707.1132	849,042.2059	162.79
32° 22' 03.687"	86° 22' 16.682"	1-2	863,010.2693	848,505.5396	152.00
32° 22' 00.319"	86° 22' 16.632"	1-3	862,669.9996	848,513.3909	154.04
32° 21' 58.826"	86° 22' 16.514"	1-4	862,519.2560	848,525.0737	153.26
32° 23' 11.759"	86° 22' 18.469"	3-1	869,888.0336	848,279.6937	160.28
32° 23' 11.108"	86° 22' 28.659"	3-2	869,813.1057	847,406.5249	153.70
32° 23' 08.025"	86° 22' 27.438"	3-3	869,502.6444	847,514.4790	149.67
32° 23' 37.039"	86° 21' 59.973"	4-1	872,459.6674	849,838.7418	156.76
32° 23' 32.467"	86° 22' 00.824"	4-2	871,996.8199	849,770.7059	152.56
32° 23' 32.404"	86° 21' 58.888"	4-3	871,992.1922	849,936.7780	153.29
32° 22' 54.899"	86° 22' 35.420"	5-1	868,168.9200	846,843.9653	163.41
32° 23' 08.791"	86° 22' 28.872"	5-2	869,578.7316	847,390.7370	153.16
32° 23' 04.211"	86° 22' 27.220"	5-3	869,117.3890	847,537.3000	153.50
32° 22' 58.387"	86° 22' 24.878"	5-4	868,530.8987	847,744.3478	148.95
32° 23' 33.378"	86° 21' 25.695"	6-1	872,120.9177	852,781.9734	158.17
32° 23' 34.204"	86° 21' 21.952"	6-2	872,207.8439	853,102.0953	158.70
32° 23' 32.989"	86° 21' 23.403"	6-3	872,083.7056	852,978.9644	158.44
32° 22' 12.942"	86° 21' 24.521"	7-1	863,993.0914	852,969.5769	165.15
32° 22' 05.976"	86° 21' 26.283"	7-2	863,287.5294	852,825.9739	162.76
32° 22' 06.058"	86° 21' 39.021"	7-3	863,284.1161	851,733.2756	160.05


J

I

N 870,000

H

G



G

F

E

D

C

B

5-3

5-4

5-1

N 868,000

N 866,000

N 864,000

Flickerball Fields

Ball Park No 13

LAKE 2

Playground Area 2003

LAKE 1

Ball Park No 12

Ball Park No 11

Ball Park No 10

Ball Park No 9

TAXIWAY E (CLOSED) 3015

ASSAULT TAXIWAY STRIP 3014

TAXIWAY D (CLOSED) 3029
N-S RUNWAY 4000 X 300' (CLOSED)

INSTRUMENT RUNWAY 3030

36


3026 TAXIWAY C

TAXIWAY B (CLOSED)

3040

FAT AREA

TRUE BEARING



APRON 3034
5700 X 300 (CLOSED)
APRON 3033

PARKING APRON 3001

RANDOLPH

DANIELL

BARKSDALE

MITCHELL

MAXWELL

WALNUT

ASH STREET

BLVD.


SELBRIDGE ST

CHANUTE

CLEAR 2000' X 3000' ZONE 07-1

US HWY NO 31

US HWY NO 31



LEGEND

EXISTING




BUILDING, PERMANENT




BUILDING, SEMI-PERMANENT



BUILDING, TEMPORARY



ROADS AND PARKING



TRAIL OR EARTH ROAD



FENCE

NORTH




PROJECT

M

HORIZONTAL

ENVIRONMENT


1	1-29-85
REV	DATE



N 868 000

N 866,000

NORTH



**CONSULTING ENGINEERING
SERVICES, INC.**

MONTGOMERY, ALABAMA

PROJECT NO. ESE 84-607-0200

**MONITOR WELLS
HORIZONTAL & VERTICAL CONTROL
FOR
ENVIRONMENTAL SCIENCE AND ENGINEERING INC.
GAINESVILLE, FLORIDA**

REV	DATE	DESCRIPTION	INITIAL
1	1-29-85	WELLS 7-1, 7-2 & 7-3	B.H.

PLAN REVISIONS

GRID BASED ON ALABAMA STATE PLANE COORDINATE SYSTEM, WEST ZONE

E

N 866,000

D

C

N 864,000

B

A

E 848,000

E 850,000

LAKE 2

Playground Area
2001

LAKE 1

Ball
Park
No 12

Ball
Park
No 11

Ball
Park
No. 10

Ball
Park
No. 9

Ball
Park
No. 8

Ball
Park
No. 7

Ball
Park
No. 6

ASSAULT TAXIWAY STRIP
3014

3029

TAXIWAY D (CLOSED)

N-S RUNWAY
4000' X 300' (CLOSED)

3040

CLEAR

GLIDE ANGLE
50:1

SHOT FALL
ZONE

APPROACH

ZONE

I-2

I-3

I-4

I-1

2

3

4



LEGEND


EXISTING



BUILDING, PERMANENT




BUILDING, SEMI-PERMANENT



BUILDING, TEMPORARY



ROADS AND PARKING



TRAIL OR EARTH ROAD




FENCE



RESERVATION BOUNDARY



RIGHT OF WAY OR EASEMENT



DRAINAGE DITCH




INDEX CONTOUR



INTERMEDIATE CONTOUR

CONTOUR INTERVAL 5 FEET




MONITOR WELL



CONTROL POINT

NORTH

MAG DEC 1° 29'
(OCT 1974)



E 856,000

E 858,000


9

10

11

12

13



N 865,000

NORTH



MAG DEC 1° 29'
(OCT 1974)




SCALE IN FEET

AIRFIELD ELEVATION 169 FEET

13

14

 CONSULTING ENGINEERING SERVICES, INC. MONTGOMERY, ALABAMA			
PROJECT NO. ESE 84-607-0200 MONITOR WELLS HORIZONTAL & VERTICAL CONTROL FOR ENVIRONMENTAL SCIENCE AND ENGINEERING INC. GAINESVILLE, FLORIDA			
REV	DATE	DESCRIPTION	INITIAL
1	1-29-85	WELLS 7-1, 7-2 & 7-3	B.H.
PLAN REVISIONS GRID BASED ON ALABAMA STATE PLANE COORDINATE SYSTEM, WEST ZONE			
DEPARTMENT OF THE AIR FORCE DIRECTORATE OF CIVIL ENGINEERING DCS/P&R - WASHINGTON, D. C.			
AIR UNIVERSITY COMMAND MONITOR WELL LOCATION MAP MAXWELL AIR FORCE BASE MONTGOMERY, ALABAMA			
SCALE: 1"=400'		DATE JANUARY 28, 1985	
U.S. ARMY ENGINEER DISTRICT, MOBILE MOBILE, ALABAMA		TAB NO. MO2061-8501 SHEET 1 OF 1	

APPENDIX E--SAFETY PLAN

APPENDIX E
SAFETY PLAN

This element consists of the activities necessary to ensure the safety of all ESE and subcontractor personnel and the general public during onsite and laboratory activities. This will be done by indoctrination of all personnel in the requirements of the Maxwell AFB safety plan prior to site activities and by ensuring that all personnel are adequately trained; provision of adequate safety equipment; medical surveillance for personnel exposed to potentially toxic chemicals; provision for safe, legal sample transport and handling; provision for the safe conduct of field inspections, construction, and well drilling operations; and provision, as necessary, of exclusion areas and decontamination activities to prevent contamination migration impact to onsite personnel, the general public, or the environment.

Principal physical hazards at Maxwell AFB during sampling and analysis involve the operation of the drilling rigs, operation of soil boring equipment, and operation of field testing equipment.

Chemical hazards at the site involve the potential inhalation of or skin contact by solvents, plating wastes, and cyanides during the drilling operations and the sampling of ground water. Also, the potential for skin contact with sediments potentially contaminated with plating wastes and other nonspecific toxic materials is a concern at Maxwell AFB.

It is anticipated that all sampling will be conducted using Level D protection. Level C protection (full-face canister masks equipped with organic vapor cartridges worn by samplers and drilling crew) will be required in these areas if organic vapors are detected in the atmosphere at breathing level during operations.

The decontamination assumptions for equipment such as drilling rigs which are costed into the proposed scope include the decontamination between borings or well installations using approved drilling water in an area provided by the Base Civil Engineer. It must be recognized, however, that although the above decontamination activities are considered to be sufficient to prevent hazard to the public health or onsite personnel, regulatory review of the work plan may result in additional requirements. These would impact the time requirement for decontamination of equipment, as well as introducing construction costs for building a separate decontamination wash rack, storage of drill cuttings, and providing for storage, treatment, and testing of the decontamination water. Additional costs would be required for such an upgraded decontamination program.

APPENDIX F--PIEZOMETERS, MONITOR WELLS, SURFACE WATER,
AND SEDIMENT SAMPLING LOCATION DESIGNATIONS

APPENDIX F
PIEZOMETERS, MONITOR WELLS, SURFACE WATER,
AND SEDIMENT SAMPLING LOCATION DESIGNATIONS

SAMPLE NUMBERING SYSTEM

The sample numbering system for piezometers and ground water monitor wells consists of the site number followed by the number indicating the order in which the wells were drilled at the study site (e.g., Well 3-3 indicates the well was the third well drilled at study site number 3). The actual sample numbers assigned to the ground water samples collected from the monitor wells were selected by the ESE Laboratory data computer system and are unique numbers for the samples. The piezometer/monitor well numbers and the ground water sampling site designations and sample numbers are presented in Table F-1.

The sampling location designations for the sediment sampling sites were arbitrarily selected and sequentially numbered from one to eleven. These sites and the numbers issued to the samples collected from these sites are listed in Table F-2. The site designation 2 is indicative of the fact that the entire drainage system of MAFB was declared Site 2 in the work plan.

The sampling location designations for the surface water sites were also arbitrarily selected and numbered one through four. These sites and the numbers issued to the samples collected at these sites are listed in Table F-3. The surface water samples were collected in the surface drainage system on MAFB, which had been designated as Site 2 in the work plan.

Table F-1. Piezometer/Monitor Well Numbers and Ground Water Sampling Site Designations and Sample Numbers

Site	Piezometer/ Monitor Well Number	Ground Water Sampling Site Designation	Ground Water Sample Number
1	1	GW1-1	469200
1	2	GW1-2	469201
1	3	GW1-3	469202
1	4	GW1-4	469203
3	1	GW3-1	469500
3	2	GW3-2	469501
3	3	GW3-3	469502
4	1	GW4-1	469503
4	2	GW4-2	469504
4	3	GW4-3	469505
5	1	GW5-1	469507
5	2	GW5-2	469508
5	3	GW5-3	469509
5	3	GW5-4	469510
5	5*	GW5-5	469511
6	1	GW6-1	469512
6	2	GW6-2	469513
6	3	GW6-3	469514
7	1	GW7-1	469515
7	2	GW7-2	469516
7	3	GW7-3	469517

*This was an existing well which was arbitrarily assigned the 5-5 designation.

Source: ESE, 1985.

Table F-2. Sediment Sampling Site Designation and Sediment Sample Number

Sediment Sampling Site Designation	Sediment Sample Number
S2-1	469300
S2-2	469301
S2-3	469302
S2-4	469303
S2-5	469304
S2-6	469305
S2-7	469306
S2-8	469307
S2-9	469308
S2-10	469309
S2-11	469310

Source: ESE, 1985.

Table F-3. Surface Water Sampling Site Designation and Sample Numbers

Surface Water Sampling Site Designation	Surface Water Sample Numbers
SW2-1	469400
SW2-2	469401
SW2-3	469402
SW2-4	469403

Source: ESE, 1985.

APPENDIX G--HORIZONTAL LOCATIONS AND ELEVATIONS OF
MONITOR WELLS

APPENDIX H--GEOPHYSICAL TRACING FOR SITES 1, 3, 5, AND 7


MAFB


Site # 1

Electronics disposal site

11-25-84 MAG

H-1





1-37-81 JMS

Reverend Bridget
(line 1074)
Doubles by K. H. H. H.

NOT TO SCALE

Secretary Boundary of South

Handy
PAC call

Handy
PAC call

Handy
PAC call

Handy
PAC call

Meeting
1/15/2011

Landfill No. 2.
Site No. 7



APPENDIX I--PIEZOMETER BORING LOGS

Site Maxwell AFB

SHEET 1 OF 3

Boring No. PZ 1-1 w/gradient

Location Coordinates N

Hole Size 6 in Slot 0.010 in

E

Screen Length 10 ft Mat'l S. 640 PVC

Filter Materials None

Diameter 2 in

Grout Type None

Casing Length 14 ft + 3 ft S.V. Mat'l S. 640 PVC

Development N/A

Diameter 2 in

Static Water Level

Date Start 12/4/84 Finish 12/4/84

Top of Well Elevation

Contractor ESE Driller Lawry

Drill Type hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	0	CL	Silty clay, 25% silt, 5% R 5/8 (yellow-red), mod. plastic, stiff, dry, flood plain	PVC cap				Log based on cutting returns only
	5	ML	Clayey silt, 70% clay, 10% R 4/5 (brown), sl. plastic, med. consist., moist, flood plain	G.L.				Contact @ 2.5 ft sharp but approximate
	10	CL	Silty, sandy clay, 15% silt, 20% sand, 5% muscovite, 7.5 R 5/8 (strong brown), cl. plastic, med. consist., damp, flood plain	joint				Contact @ 4.0 ft gradual and approximate
	15	SP	Med. gr. quartz sand, 3% muscovite, mod. round, poorly graded, 7.5 R 5/8 (strong brown), non plastic, loose, dry, fluvial	2 in PVC casing				6 in borehole
	20	SW	Fine to med. quartz sand, mod. round, well graded, 10 R 6/8 (brown-yellow), non plastic, loose, moist, fluvial	joint				Contact @ 11.0 ft sharp
	25			2 in PVC screen				Cuttings
	30							Contact @ 15.0 ft approximate and gradual
	35							1st H ₂ O @ about 12 ft based on wet cutting to surface

Signed George K...

Approved

Site Maxwell AFBSHEET 2 OF 3Boring No. PE 1-1, upgradeLocation Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/4 Finish 12/4

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse sand, 20% gravel (pebbles to 0.5 in diam), 10-12% (yellow brown), non plastic loose, wet, fluvial				6 in borehole	
	SW						2 in PVC screen	
	SW						Sand- cavings	
	25	EOH	Med to coarse quartz sand, 50% gravel (to 3.0 in diam), non plastic, loose, wet, fluvial				EOH, EOH 24 ft	PVC end cap

Signed [Signature]

I-2

Approved _____

Site 11' round FFB
Boring No. PZ 1-1 Wagonchins, Site I

SHEET 3 OF 3

- 0700 - Driller, ESE on-site
- Rig: CME 45
3/4" hollow stem auger (O.D. = 6 in.)
- Crew: Mike, Randy
- 0710 - Set up rig
- Begin augering
- 0740 - Down to 24 ft - 1st H₂O near 18 ft
- 0745 - Drop spoon down auger to clean out the bottom - sand
leaved inside
- 0755 - Utilities people arriving (gas, electric, sewer, etc.)
- Will go to different sites with them to get clearance to
bore shortly
- 0800 - Spoon out of hole (14.26 24.2)
- 0815 - Pull auger install well to 24.0 ft (screen 12 to 22 ft)
- 0820 - ~~Install~~ Pull auger - managed to push
well to 24.2 ft - ~~push in casing~~
- 0830 - 1 of 2 utility people to inspect site
- 0920 - Inspection complete (well installation complete ~ 0900)
Return to Site I
Drill rig buried in mud trying to move over to
concrete pier on Site I
- 1000 - Air Force came assist in freeing truck from mud
(called ESE 1st Brn)
- 1020 - Return to rig - attempt again to free truck (rig)
- Materials used: 10 ft screen, 17 ft casing

12/4/94
DATE

George T. [Signature]
SIGNED

APPROVED

Site Li Lowell #FB

SHEET 1 OF 3

Boring No. PZ 1-2, Longwood, Site T Location Coordinates N

Hole Size 6 in Slot 0.010 in E

Screen Length 10 ft Mat'l SL 40 PVC Filter Materials none

Diameter 2 in Grout Type none

Casing Length 14 ft + 30 ft S. U. Mat'l SL 40 PVC Development N.A.

Diameter 2 in Static Water Level

Date Start 12/1/84 Finish 12/4/84 Top of Well Elevation

Contractor ESE Driller Law Eng. Drill Type Hollow Stem Auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	0	SC	Med sand, 50% clay, 54R 4/6 (yellow-bell), mod graded, mod round, mod plastic, med. consist; damp, flood plain				PVC slip caps	Log based on cuttings only
	5	ML	clayey silt, 40% clay, 546/2 (light blue gray), sh. plastic, soft, wet, flood plain				G.L.	contact @ 2.0, 7.5, and 11.0 ft approximate and gradational
	10	CL	silty clay, 30% silt, 546/1 (gray), mod. plastic, stiff, moist, flood plain				joint	Pushed water in silt close ~ 7.5 ft
	15	CH	virginian clay, 546/1 (gray) to 104R 5/8 (yellow brown), mottled colors, v plastic, stiff, moist, flood plain				6 in borehole	cuttings
	20	SC	Fine to coarse sand, 25% clay, well graded, sub angular to round, sh. plastic, loose, v wet, fluvial, 104R 7/6 (yellow)				2 in PVC casing	contact @ 15.0 ft approx and gradational
	25						joint	15 ft significant water near 15 ft @ top of bank - wet sand to surface
	30						2 in PVC casing	

Signed Law Eng.

I-4

Approved

Site Linwell A.F.B.

Boring No. PZ-1-2, Longdient, Site I

SHEET _____ OF _____

- 0900 - Rig stuck in mud moving into hole - see preceding narrative
- 1110 - Rig freed & ready to move onto new hole chosen on drier ground 30 ft to the south inside the playground area (NW corner)
- 1115 - Water run: Hose on outlet was too large to fit into water tank; Took 10 or 15 minutes to rig up a system
- 1140 - Fill info complete
- 1145 - Lunch
- 1230 - Clean auger w/ ~~effluent~~ (butane) with kerosene (unchlorinated) using rig pump
- 1255 - Back rig onto new hole location & set up. A few raindrops fell, but doesn't look too bad!
- 1300 - Begin augering
- 1320 - Down to 24 ft
- Take spoon sample at 24.0 ft (Dillon's house!)
A few more raindrops!
- 1335 - Pull screen (no flow counts taken)
- 1345 - Install well to 24 ft (screen 14 to 24 ft)
- 1355 - Pull auger
- 1410 - ~~Have rig run + clean auger~~
Water in hole @ 7.5 ft
Water in pipe @ 17.5 ft
- 1410 - Waiting for radiator to be installed before moving rig off hole - DOWNTIME
Rain light but steady
- 1430 - Repair complete
Move off hole to clean auger
- 1500 - Move to new hole
- Wellbore: 10 ft screen, 17 ft casing

12/4/84
DATE

George P. [Signature]
SIGNED

APPROVED

Site Maxwell AFB


SHEET _____ OF _____

Boring No. PZ 1-3, Long-term SilentLocation Coordinates N _____Hole Size 6 in Slt 0.010 inE _____Screen Length 10 ft Mat'l Sch 40 PVCFilter Materials noneDiameter 2 inGrout Type noneCasing Length 5 ft + 3 ft S.U. Mat'l Sch 40 PVCDevelopment N.A.Diameter 2 in

Static Water Level _____

Date Start 12/4/84Finish 12/4/84

Top of Well Elevation _____

Contractor ESEDriller Law EngDrill Type Hollow Stem Auger

Signed _____

I-7

Approved _____

Site Maxwell AFB
Boring No. PZ 1-3, Roundabout, Site I

SHEET _____ OF _____

1510 - Set up on-site
1515 - Begin augering
1530 - Down to 18 ft
Install well to 15.3 ft (Screen 5.3 to 15.3 ft)
1540 - Pull augers
1550 - Measure off hole
Run for water to clean augers
1620 - Water timer back - clean augers
1645 - Augers reamed

Note: Plan to install PZ 2-4 with afternoon (12/5)
to Thursday (12/6) before going to install
PZ 1-1 well morning (12/5) @ 0800

1650 - Set up on PZ 1-4
1700 - Dispersal activity

12/4/04
DATE

George P. [Signature]
SIGNED

APPROVED

SHEET OF

Location Coordinates N

E

Filter Materials *None*

Grout Type 4 one

Grout Type none

Development N. 4.

Static Water Level

Top of Well Elevation

Drill Type *Half on 5th corner*

Signed George R. K.

I-9

Approved

Site Naval AFB
Boring No. PZ1-4, Downgrad., Site I

SHEET _____ OF _____

0630 - ESTE arrive on-site

0725 - Dullens arrive on-site

0735 - ~~ESTE~~ Begin augering


0745 - Down to 18 ft (overballed 3 ft)
Install well to 16 ft (screen 6 to 16 ft)

0800 - Installation complete

0805 - (Cleaning casing while I go after the support
managers who will accompany us to Site II near
the end of the N-S runway)

0830 - Auger clean, depart site.

12/5/94
DATE


SIGNED

APPROVED

Site Maple A.F.B.


SHEET _____ OF _____

Boring No. PZ 3-1Location Coordinates N _____Hole Size 6 in Slot 0.010 inE _____Screen Length 10 ft Mat'l Sch 40 PVCFilter Materials noneDiameter 2 inGrout Type noneCasing Length 17.7 ft + 2 ft SU Mat'l Sch 40 PVCDevelopment N.A.Diameter 2 in

Static Water Level _____

Date Start 12/6/84 Finish 12/6

Top of Well Elevation _____

Contractor ESE Driller Low Eng.Drill Type Hollow Stem AugerSigned George R. [Signature]

I-11

Approved _____

Site Maxwell AFB

SHEET _____ OF _____

Boring No. PZ 3-1Location Coordinates N _____

Hole Size _____ Slot _____

E _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/6/84 Finish 12/6

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
20			Sandy gravelly clay, 35% fine to med sand, 5% gravel (<1 cm) 104R6/6 (brown, yellow) sl. plastic, med. consist., moist, flood plain					2 in borehole cased sand PVC screen
25								Split spoon sample @ 29 ft (29 to 31) was gravelly sand, very clean + wet; water level @ 19.9 ft, indicating we missed the top of the sand or the water is confined
30			Inorganic clay, 545/1 (gray), very plastic, soft, v. wet, flood- plain. Fine to coarse sand, 20% gravel				PVC and cap Elev 29 ft Elev 29 ft	

Signed George Boes

I-12

Approved _____

Site Naval AFB
Boring No. PZ 3-1, upgrad. Site III

SHEET _____ OF _____

- 1415 - Arrive, set up on site
1420 - Begin augering - monitor w. H-NV
1450 - Down to 29 ft
Knows plug out of auger w. spoon sampler
we still haven't hit sand (probably!), but there's
about 2 or 3 inches of H₂O in bottom of auger
Spoon brought up coarse sand & gravel, wet, clean (but
only a handful)
1505 - Water measured in auger @ 19.9 ft (G.L.)
Attempt to install well to 29 ft - sand has heaved
about 3 ft inside auger
Tough time pushing well through the plug
1520 - Pulling auger & pushing well down simultaneously
Well down to 27.7 ft w. 2 ft S.U. (screen 17.7 to 27.7)
Water measured @ 19 ft (G.L.) inside well
1550 - Auger finally out - bottom 2.0 ft or so encased
in the clay, slide clay - explains why the sand
wasn't reaching the surface; all flights were clogged.
Will take a long time to recover!
1625 - Water run - auger still not clear
Measure water in well @ 17.5 ft (G.L.)
" " " hole @ 9.2 ft (was 8 ft - dropping)
1700 - Water @ 17.2 ft (G.L.)
Water truck return - resume design
1730 - Recover complete
Repair site

12/6/04
DATE

George P. Ross
SIGNED

APPROVED

Site Naval AFBSHEET 1 OF 3Boring No. 72-3-2, Rought, Site IIILocation Coordinates NHole Size 6 in Size 0.010 inEScreen Length 10 ft Mat'l Sch 40 PVCFilter Materials noneDiameter 2 inGrout Type noneCasing Length 11 ft + 2.5 ft Mat'l Sch 40 PVCDevelopment N.A.Diameter 2 in

Static Water Level

Date Start 12/7/84 Finish 12/7

Top of Well Elevation

Contractor ESE Driller Law EngDrill Type Hollow Stem Auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery Box or Sample #	Sketch of Construction	Remarks
	0						Log based on cuttings only
	CL		Silty clay, 25% silt, 104 R 4/5 (dk brown), mod. plastic, soft, moist, flood plain			PVC slip cap Vent GL	
	5	CL	Silty clay, 30% silt, 104 R 6/6 (yellow), mod. plastic, stiff, v. moist, flood plain				joint
	CL		Silty clay, 15% silt, 7.54 R 5/8 (strong brown) to 546/2 (lt olive gray), mottled, stiff, damp, flood plain				PVC casing cuttings
	10	SC	clayey fine sand, 140% clay, well graded, 546/2 (lt olive gray), med dense, moist, flood plain				1st H ₂ O near 9 ft based on wet cuttings to the surface
	SW		F-11 sand, 5% gravel, well graded, med round 547/1 (lt gray), loose, wet, fluvial				6 in borehole
	SW						joint
							PVC screen
							caved sand
							All contact approximate & gradual

Signed George Bond

Approved

Site MaxwellSHEET 2 OF 3Boring No. PZ 3-2Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/7/84 Finish 12/7

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	26	SW	F-10 sand, 15% gravel, well graded, med round, 104R6/6 (brown, yellow, non plastic, loose, wet, fluvial					
		EOH	Near bottom of hole clot of gravel (50%) to 5 in diameter					

George Rock
Signed

I-15

Approved

Site Naval AFB
Boring No. PZ 3-2, Douglas, Site III

SHEET 3 OF 3

- 1115 - Set up on-site
1120 - Begin auguring
Encountered debris (glass, metal, bricks) @
about 2-3 ft - abandon hole, move
20 ft north and several ft west, start again
1130 - Start auguring
Encountered debris again - more hole
1135 - Encountered red concrete - more hole
1140 - Start auguring
Debris again - stop, more hole
1145 - Start auguring - no debris
1155 - Down to 22 ft
1200 - Install well to 21.1 ft (approx 11.1 to 21.1, 2.5 S. U.)
Pull auger
1215 - Auger out
1220 - Close auger
Water measured @ 8.2 ft (TOC), 5.7 ft G.L.
1300 - END
1400 - Return for rig
- Depart site.

12/7/84
DATE

George P. [Signature]
SIGNED

APPROVED

Site Maxwell AFB SHEET _____ OF _____
 Boring No. PZ3-3, Drowned Site IV Location Coordinates N
 Hole Size 6 in Slot 0.010 in E
 Screen Length 10 ft Mat'l Sch 40 PVC Filter Materials none
 Diameter 2 in Grout Type none
 Casing Length 6 ft + 2 ft SW Mat'l Sch 40 PVC Development N.A.
 Diameter 2 in Static Water Level _____
 Date Start 12/7/84 Finish 12/7 Top of Well Elevation _____
 Contractor ESE Driller Low Eng. Drill Type Hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	0		PVC slip cap					Log based on cuttings only
		CL	Sandy, silty clay, 20% f-med. sand, 10% silt, 3% mica, 104R 4/3 (brown) ol. plastic, soft, moist, flood plain					cuttings PVC casing
	5	CL	Silty clay, 20% silt, 104R 6/2 (lt brown, gray), med. plastic, soft, moist, flood plain					Contacts @ 3 ft + 6 ft approximate & gradational.
		ML	Silt 104R 7/1 (gray), ol. plastic, soft, moist, flood plain					Contacts @ 13 ft very approximate
	10	SW	Fine to med. sand, 10% gravel (to 1/4 in), 5% clay, 104R 7/1 (gray), non plastic, loose, wet, fluvial					Split spoon sample 14.0 to 15.5 ft
	15	SW	Fine to coarse sand, well graded, med. round, 104R 7/8 (yellow) to 7.54R 5/8 (strong brown), loose, wet, fluvial					6 in borehole cased sand PVC screen PVC end cap
							Box 16 ft	
							Box 18 ft	

George K. [Signature]
 Signed

I-17

Approved

Site

Boring No. FE 3-3, downyad, Site 11

SHEET _____ OF _____

- 0730 - FSE, Drillers on-site
- 0745 - Set up rig
- 0750 - Begin augering, monitor w HNU
- 0815 - Down to 14 ft
- 0830 - Splice spoon sample (my choice) 14 to 15.5 ft
- 0840 - Spoon out
- 0840 - Sand heard 4 ft inside augers
- 0840 - Place well + try + pull augers, dislodge plug
- 0855 - Still having problems
- 0910 - Well got stuck inside augers + couldn't remove plug
- 0910 - Pull augers + well
- 0920 - Wash plug out of augers + ~~reinsert into hole~~ water in hole for 5.0 ft - must be confined!
- 0920 - Hole stayed open to 7.0 ft (top of sand?)
- 0922 - Back into hole w. augers
- 0930 - Back down to 18 ft
- 0945 - Install well to
- 0945 - Pull augers - same problem! Having rough time!
- 1000 - Allowing 1st head to cool off!
- 1000 - Still can't pull augers w/o the pipe
- 1040 - Flush water down pipe to free (50 gallons)
- 1040 - No go! Pull augers + well again!
- 1040 - ~~That augers but both plug + to down 3.0 ft~~
- 1040 - Sand had now crusted free + did not have to pull well for 3.0 ft
- 1050 - Well set @ 16 ft (arena 6 to 16, 2 ft SU)
- 1100 - Augers closed
- 1105 - Cutting to surface (caved to 7 ft)
- 1105 - Repair site

12/7/04
DATE

George *[Signature]*
SIGNED

APPROVED

Site Maxwell AFBSHEET 1 OF 3Boring No. PZ-4-10.010 inLocation Coordinates NHole Size 6 inSlot 0.010 inEScreen Length 10 ftMat'l Sch 40 PVCFilter Materials coarse sandDiameter 2 inGrout Type noneCasing Length 15 ft + 3 ft SVMat'l Sch 40 PVCDevelopment N.A.Diameter 2 in

Static Water Level

Date Start 12/8/84Finish 12/8/84

Top of Well Elevation

Contractor ESEDriller LawrenceDrill Type Hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
			PVC slip cap					Log based on cuttings only
			U-vent					
								6 in borehole
			Sandy, gravelly clay, 20% med sand, 15% gravel (to 5 in), 5/4 R 4/6 (yellow, red), sl plastic, med coarse, damp, fluvial					Well is up against a 10 ft deep cut in the hillside
			Med to coarse gravelly sand, 30% gravel (to 5 in), well graded, mod. round, 7.5/4 R 5/8 (strong brown), non plastic, loose, wet, fluvial					cuttings below 3 ft seem wet enough to be saturated, but no water inside auger @ 14 ft; don't want to knock plug out of auger, so we pulled them to check for water
			Med to coarse sand, 40% gravel (to 8 in), well graded, mod round, 7.5/4 R 5/8 (strong brown), non plastic, loose, wet, fluvial					PVC screen
								coarse sand

Signed

I-19

Approved

SHEET 2 OF 3

Location Coordinates N

[REDACTED]

Filter Materials

Grout Type _____

Development _____

Static Water Level _____

Top of Well Elevation _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Med to co. sand, 15% gravel (to 0.5 cm), well graded round, 104R 7/6 (yellow), non plastic, loose, v. wet, fluid					6 in hole cover sand 1st H ₂ O near 21.5 ft level or water level in auger PVC screen PVC overcap 25 ft

Signed George Bost I

I-20

Approved

Site Maywell AF-B
Boring No. 024-1

SHEET 3 OF 3

- 0730 FSE on-site
Drill crew picking up pipe & water before coming
out here this A.M.
selected location for boreholes, Site IV
- 0855 Puller on-site
Cleaning yesterday's augers!
- 0920 Set up on hole
- 0925 Began augering
- * Note: well is along the edge of landfill area next
to a 10 ft deep cut in the hillside - natural
elevation here is 10 ft higher than present
- 0935 Pull auger & check for water in hole @ 14 ft
Hole raised to 9 ft; no water in hole!
Maybe water below 9 ft?
- 0950 Down to 25 ft - water measured in auger @
21.5 ft (t.l.)
- 0955 Grout all well to 25 ft (screen 15 to 25, 3 ft S.V.)
- 1000 Pull auger
P is running poorly (running, sputtering); may need
work after this hole!
- 1010 Auger out
Hole raised to 14 ft - no water in hole
Water in well @ 23 ft TOC, 2 ft 6 in
- 1020 Cuttings to surface
- 1025 Pull off hole
Clean augers
- 1030 Move to next hole

12/8/84
DATE

George Kost
SIGNED

APPROVED

SHEET 2 OF 3Site MAFBBoring No. PZ 4-2Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/8/84Finish 12/8

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20 (GW)		Gravel, 40% used to coarse sand, well graded, round (to 3 in diameter), 104R6/8 (brown-yellow), non plastic, loose, wet, fluvial					

George Post
Signed

I-23

Approved _____

Site MAFB
Boring No. PZ 4-2

SHEET 3 OF 3

1035 - Set up on-site

Begin auguring - monitor w H-NU

1045 - Down to 14 ft

Water measured in auger @ 9.8 ft, G.L.
(no clay plug - sand total depth of hole)

1050 - Down to 21 ft

Run for screen sections

Water inside auger @ 15.8 ft, G.L. ??

1105 - Helmer back w. screen (10 min DOWN TIME)

Install well to 18.8 ft (screen 8.8 to 18.8, 3.9 ft S.U.)

1110 - Begin pulling auger

* Hole is not straight - gravel kept it from being
so, + auger hard to pull

1125 - Can't get the well to break through the bottom
of the auger + it comes up with them

1140 - Well not (to 18.8 ft)

Water in well @ 13.6 ft TOC, 9.8 ft G.L.

Caved @ 4 ft

Cuttings to surface

1145 - Clean auger

1150 - Auger clean

Reinstall S.U.

to 18.8 ft

None to rest hole - FOOD LATER!

12/8/84
DATE

Leslie Noels
SIGNED

APPROVED

Site MAFB
 Boring No. PZ 4-3 Location Coordinates N
 Hole Size _____ Slot E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 10/8/84 Finish 10/8 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	GW	Coarse sand / gravel mix, well graded, round, 7.5# RS/8 (strong brown), non plastic, loose, wet, fluvial; (pebbles to 2 cm)					6 in borehole water @ 20 ft approximate & gradational coarse sand PVC screen PVC end cap
	25	SW						
	26	EDH						
							EDW, EDH 26 ft	

George Foster
 Signed

I-26

Approved

Site M.A.F.B.

Boring No. FE 4-3

SHEET 3 OF 3

1200 Set up on hole
Begin augering - Monitor w. 4-PV
1215 Down to ~~49 ft~~ 18.5 ft
Water inside auger @ ~ 17.5 ft (1 ft H₂O inside)
Resume augering
1222 Down to 23 ft
Water in auger @ ~ 17.90 ft
Let set for 5 minutes + remeasure!
1227 Water @ 17.1 ft
Resume augering
1230 Down to 28 ft
Anitell well to 26 ft (cored 16-26 ft, 2 ft S.U.)
1240 Pull auger
Hole cased to 10 ft
Water in well @ 19.4 ft, TOC, 17.8 ft R.L.
Cuttings to surface
1250 Wash auger & then LUNCH
1300 Lunch Break

12/8/84
DATE

George [Signature]
SIGNED

APPROVED

SHEET 1 OF 2

Site Waukegan 47B

Boring No. 725-

Hole Size 1/2 in Slot 0.010 in

Screen Length 1045 Mat'l Sch 40 PVC

Diameter 2 in

Casing Length 12.5 + 2 ft S.V. Mat'l 54.40 PVC

Diameter 2 in

Date Start 12/7/84 Finish 12/7

Contractor ES E Driller Lan E

Location Coordinates N

E _____

Filter Materials 423

Group Type 4072

Development 1/4

Specific Motor Level

Top of Hull Elevation _____

Drill Type *Hall's Steam crane*

BRILL type 11 35 12

[illegible]


Signed

I-28

Approved

SHEET 2 OF 3

Site NAFB
 Boring No. PZ 5-1 Location Coordinates N
 Hole Size _____ Slot E
 Screen Length _____ Mar'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mar'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 12/7/84 Finish 12/7 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse sand, 30% gravel (to 5 mm diam), well graded, round, 104R 5/8 (yellow brown), non- plastic, loose, wet fluvial					6m borehole cased sand PVC screen PVC end caps EDW 23.5 ft EWH 25 ft

George Foster
 Signed

I-29

Approved

Site

Boring No. PZS-1

SHEET

3 OF 3

1430 - Set up on-site

1435 - Begin augering - H1V monitoring

1500 - Drill to 25 ft

1504 - Set well inside auger

1507 - Pull augers - coming up fairly w/o the well!

Upper 13 ft of the 25 ft of auger in hole came
up dry - water is at least 13 ft deep

Lower 5 ft or so of auger (flight) filled w.
coarse sand & gravel!

1515 - Clean augers

Well set @ 23.5 ft (down 13.5 - 23.5, 2 ft S.V.)

Water level @ 19.2 ft TOC, 17.2 ft GL

Cased to 17 ft

Cuttings to surface

* Mr. M auger (property owner) stopped in for
a friendly visit while drilling

1530 - Depart site

12/7/04
DATE

[Signature]
SIGNED

APPROVED

Site Marine AFB SHEET 1 OF 4
 Boring No. PZ 5-2 Location Coordinates N
 Hole Size 6 in Slot 0.010 in E
 Screen Length 10 ft Mat'l 9440 PVC Filter Materials none
 Diameter 2 in Grout Type none
 Casing Length 9 ft + 2 ft SW Mat'l 9440 PVC Development N.A.
 Diameter 2 in Static Water Level
 Date Start 10/18/84 Finish 10/19/84 Top of Well Elevation
 Contractor FSE Driller Law Eng. Drill Type Hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	0							
	5	SC	clayey sand, 30% clay, f.-cs. grained, well graded, med round, 104R5/4 (yellowish brown), al. plastic, loose, moist, fluvial					Log based on cuttings only
	10	CL	silty clay, 20% silt, 104R5/3 (brown), mod. plastic, med. consist, moist, flood-plain					Contact @ 5 ft approximate gradational
	15	SW	Fine to coarse quartz sand, well graded, round, 54 7/11 (light gray), non plastic, loose, wet, fluvial					Contact @ 10 ft sharp
	20	SW						PVC casing
	25							1st H ₂ O @ 10 ft, based on wet cuttings + water to surface
	30							PVC screen
	35							covered sand
	40							6 in level

Signed George Vost

Approved _____

Site MAFB
Boring No. PZ 5-2

SHEET 3 OF 4

- 12/8 1335 - ESE return from lunch
Spent 45 minutes looking for a way
onto the site - possibly found one!
- 1425 - Drillers return
1435 - Move onto site - we made it!
Set up rig
1445 - Begin augering - H-111 monitoring
1455 - Encountered something hard - almost lost hole
Clear a space in the brush 10 ft closer to
West End Ditch
1505 - Begin augering again
1525 - Down to 21 ft (overdilled 2 ft intentionally)
Install well
1530 - Pulled about 10 ft of auger & well became
lodged inside auger & couldn't pull the plug
1600 - Well & auger stuck, well stuff inside. Last
auger
1610 - Removing a stiff clay plug inside last auger
1615 - Going back into hole w. auger, clay plug
1620 - Back to 20 ft
1640 - Sand leaked through clay plug for 7 ft into
auger - well wouldn't go through
1650 - Tried again with larger clay plug
Same thing happened
will drill new hole several ft over
1715 - Depart site
- 12/9 0715 - ESE on-site
0730 - Drillers on-site
0745 - Begin augering
0955 - Down to 19 ft
0900 - Install well

→ See next page

12/8/84
DATE

George Foster
SIGNED

APPROVED

Site MAFB
Boring No. 225-2

SHEET 4 OF 4

12/9 0900 Pull augers - come up w/o well!
0905 Augers put
Cased to 12 ft, water in hole @ 8 ft
Water in well @ 7.7 ft TOC, 5.7 ft b.l.
Well set @ 19 ft (screen 9 to 19, 2 ft S.U.)
0815 Lower augers

12/9/84
DATE

George Rod
SIGNED

APPROVED

Site Maxwell AFB

Boring No. PZ 5-4

Location Coordinates N

Hole Size 6 in Slot 0.010 in

E

Screen Length 10 ft Mat'l Sch 40 PVC

Filter Materials none

Diameter 2 in

Grout Type none

Casing Length 8.6 ft + 2.3 ft Mat'l Sch 40 PVC

Development N.A.

Diameter 2 in

Static Water Level

Date Start 12/7/84 Finish 12/7

Top of Well Elevation

Contractor ESF Driller Lawry

Drill Type Hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
								Log based on cuttings only
			2 in PVC slip cap					
			Vent					
			G.L.					
	0	ML	clayey silt, 30% clay, 104R 7/3 (very pale brown), sh. plastic, soft, dry, flood plain					cuttings
			Silty clay, 20% silt, 7.54R 5/8 (stony brown)					6 in bowhole
	5	CL	to 5.46/2 (lt dr. gray), mod. plastic, med. consist., dry, flood plain					PVC casing
			clayey silt, 30% clay, 2.54 7/4 (pale yellow), mod. plastic, soft, med, flood plain					All contacts approximate + gradational
	10	ML	clayey silt, 10% sand, 20% clay, 10% silt, well graded, 2.54 6/2 (light brown gray), sh. plastic, loose, med, flood plain					1st H ₂ O near 7 ft based on wet cuttings to surface
		SC	Fine to co. sand, 10% gravel (to 0.5 in), well graded, 10% sand, 2.54 7/4 (pale yellow), non plastic, loose, med, flood plain					
	15	SW						PVC screen
								caved sand

Signed George

I-35

Approved

Site Maple AFBSHEET 2 OF 3Boring No. PZ 5-4Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/7/89 Finish 12/7

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery %	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to med. sand, 20% gravel, well graded, round, 2.547/4 (pale yellow), non plastic, loose, med, fluvial				 EOW 18.6 ft EOW 21 ft	PVC screen PVC end cap 6 in borehole At about 21 ft had about a lot of resistance & chatter - probably gravel

Signed George R. Rader

I-36

Approved _____

Site Mapwell AFB

Boring No. PZ 5-4

SHEET 3 OF 3

1550 Set up on-site (Dory or cleared up a path)
1555 Begin auguring - monitor w H-NV
1610 Down to 12 ft
1615 Install well to 10.6 ft (sewer 8.6 to 10.6, 2.3 ft S.V.)
1650 Augers out - tough time!
~~1655~~ Pull off site
1705 - water measured @ 9.4 ft TUC, 7.1 ft G.L.
Will clean augers tomorrow

Sand cased to 15 ft

12/7/84
DATE

Georger
SIGNED

APPROVED

Site Mapwell AFB

SHEET _____ OF _____

Boring No. PZ-6-1

Location Coordinates N _____

Hole Size _____ Slot _____

E _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/5/84 Finish 12/5

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
20		Ch	Silty clay, 30% silt, 1% mica, 10% mica, 10% mica (brown, yellow), mod. plastic, stiff, moist, flood plain				6 in borehole	
25		SM	Fine to med quartz sand, 20% silt, 5% mica, mod. well graded, mod round, 2.547/4 (pale yellow), non plastic, loose, v. wet, fluid				joint	
30			No cutting returns below about 30 ft, but probably sand: coarse sand				PVC screen	
							cuttings	
							1st H ₂ O near 26 ft based on wet cuttings to surface.	
							when pulling augers fine to coarse gravelly sand filled the lower 8 to 10 ft of the flights	
							ECW 31.5 ft	
							PVC and cap	
							sand savings	
							ECW 37.4	

George Post
Signed

Approved

Site Mapwell #FB
Boring No. PZ 6-1, upgrad., Site VI

SHEET _____ OF _____

1305 - Arrive on-site

- Rig stuck in mud moving onto hole

1345 - Rig freed + set up

1350 - Begin augering

1430 - Down to 37 ft. (overdrilled 2 ft intentionally)

1435 - Install well to 33.8 ft (screen 19.8 to 33.8; 2.8 ft S.U.)

1445 - Installation complete

Pull augers

1455 - Well clogged on augers + pulled up about 3 or 4 ft -

couldn't push it back down

Will measure water level tomorrow + if then water @

least 5 ft of water in well will pull it + red of

continue pulling augers - having a very rough time!

1525* Well ended up being 31.5 ft deep in 2.8 ft S.U.

- Water measured in well @ 26.2 ft (H.L.) -

there's 5.3 ft water in well

1530 - Pull off hole

Clean augers

1555 - Cleaning complete

~~8:00~~

1600 - Move onto PZ 6-2

17/5/84
DATE

George [Signature]
SIGNED

APPROVED

Site Maxwell AFB

SHEET 3 OF 4

Boring No. PZ 6-2, Douglass Site VI

Location Coordinates N

Hole Size 6 in Slot 0.010 in

E

Screen Length 15 ft Mat'l Sch 40 PVC

Filter Materials none

Diameter 2 in

Grout Type none

Casing Length 23.3 + 2.5 ft SU Mat'l Sch 40 PVC

Development N.A.

Diameter 2 in

Static Water Level

Date Start 12/5/84 Finish 12/6/84

Top of Well Elevation

Contractor FSE Driller Law Eng

Drill Type Hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	0		PVC slip cap vent					Log based on cuttings only
	0	CH	Inorganic clay, 104 R 5/6 (yellow brown), very plastic, stiff, moist, flood plain					cuttings joint
	5	CH	Inorganic clay, 104 R 5/6 (yellow brown) to 54 7/1 (light gray), mottled colors, v. plastic, stiff, damp, flood plain					All contact. approximate gradual color change in borehole PVC casing joint
	10							
	15	CL	Silty clay, 20% silt, 104 R 6/6 (brownish yellow), mod. plastic, med. consist., damp, flood plain					joint

Signed George P. [Signature]

I-41

Approved

SHEET 2 OF 4Site MAFBBoring No. ME 6-2Location Coordinates NHole Size SlotEScreen Length Mat'l

Filter Materials

Diameter

Grout Type

Casing Length Mat'l

Development

Diameter

Static Water Level

Date Start 12/5/84Finish 12/6

Top of Well Elevation

Contractor

Driller

Drill Type

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
20	CL		Silty clay, 30% silt 2.546/4 (light yellow. brown), mod. plastic, med. consistency, moist flood plain				PVC casing cuttings joint	
25	CL		Fine to med sand, 25% silt, well graded, med. round, 104R 5/4 (yel- low-brown), sh plastic, wet, fluvial				All contacts approximate & gradational 6 in core hole caved sand	
30	SW		Fine to coarse sand, 20% gravel (to 1.0 mm diam), well graded, mod. round, non plastic, v. wet, fluvial (see REMARKS)				joint PVC screen	
35	SW						Cuttings from below about 30 ft were mixed with clay from above coming up the hole, + color is impossible to determine	
							Eqw 38.3 Ft	

Signed

I-42

Approved

SHEET 3 OF 4Core MAFBCasing No. PZ6-2Location Coordinates NE

Hole Size _____ Slot _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 12/5/84Finish 12/6

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	40		Washed to coarse sand, 30% gravel (< 1.0 mm), well graded, med. sand, non plastic, loose, wet, 2.546/4 (2 yellow brown) fluvial					6 in. borehole When pulling auger coarse sand & gravel (clean) were found on lower section
	45							

Signed

George P. [Signature]

I-43

Approved

Site MA.F.B.
Boring No. FE 6-2

SHEET 4 OF 4

12/5 1600 - Begin augering
Rain falling gently!
1645 - Down to 43 ft (overdrilled 3 ft intentionally)
1650 - Install well to 38.3 ft (even 23.3 & 38.3, 2.5 F + S.W.)
1700 - Pull 1st auger - complete. 12/6/84
1720 - Depart site.
It is pouring rain!

12/6 0700 - Water run
0730 - Drillers, E.S.F. arrive on-site
Bill Ross, John Naguall (E.S.F.) arrived last
into (2:30); showed them where to begin
well leveling.
0740 - Continue pulling augers
0820 - Augers out
- Clean augers
- Water measured in well @ 29 ft TOL, 26.5 ft G.L.
0850 - Down complete
Depart site (hide!)

12/6/84
DATE

George Ross
SIGNED

APPROVED

Site Magwell AFB

SHEET 1 OF 4

Boring No. PZ 6-3, Rounding, Site VI

Location Coordinates N

Hole Size 6 in Slot 0.010 in

E

Screen Length 15 ft Mat'l Sch 40 PVC

Filter Materials none

Diameter 2 in

Grout Type none

Casing Length 24 ft + 2 ft SU Mat'l Sch 40 PVC

Development N.A.

Diameter 2 in

Static Water Level

Date Start 12/6/84 Finish 12/6

Top of Well Elevation

Contractor ESE Driller Low Eng

Drill Type Hollow Stem Auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Flow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			PVC slip cap					Log based on cuttings only
			vent					
			CL					
			Clayey silt, 30% clay, 104R 3/4 (dk yellow brown), sl. plastic, soft, damp, flood plain					Contacts @ 2.5, 6, 12 ft approximately + gradational.
			Inorganic clay, 7.54R 5/8 (strong brown), v. plastic, stiff, damp, flood plain					Contacts @ 16 and 17.5
			Inorganic clay, 104R 5/6 (yellow brown), to 547/1 (gray), mottled colors, very plastic, stiff, damp, flood plain					6 in borehole cuttings PVC casing
			Sandy, silty clay, 25% fine sand, 10% silt, 104R 6/8 (brown, yellow), sl. to med. plastic, soft, moist, flood plain; 1.5 ft thick fine sand/silt lens with perched water					joint
			CL					1st H ₂ O near 16 ft; then perched zone
			SM					
			CL					

Signed George V. [Signature]

I-45

Approved

Site Maxwell AFBSHEET 2 OF 4Boring No. PZ6-3Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/6/84 Finish 12/6

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____


Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	* Recovery	Box or Sample #	Sketch of Construction	Remarks
20		CL	Silty, sandy clay, 20% silt, 15% fine sand, 104R6/8 (brown, yellow), sl. plastic, 4cft, moist, flood plain					Cutting covered sand PVC casing 6 in borehole joint
25		SM	Fine sand, med. graded, 10% clay, 10% silt, 104R6/8 (brown, yellow), loose, v. wet, fluvial					Increase in drill rate @ 25 ft; Lots of water to surface below 25 ft - probably top of sand @ 25 ft
30		SW	Fine to med sand, 10% silt, 104R6/8 (brown, yellow), loose, v. wet fluvial					Sand idles off because of con- tamination by uphole clays.
35		SW	Fine to coarse sand, 15% gravel, well graded, mod. round, non plastic, loose, v. wet, fluvial					Contact @ 25, 29, 35 ft very approximate & gradational EOW 39 ft

Signed G. J. [Signature]

I-46

Approved _____

Site Wayne DAFB
 Boring No. PZ 6-3 Location Coordinates N
 Hole Size _____ Slot _____ E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 12/16/84 Finish 12/8 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	40	SW						6 in. borehole.
		EOH					EOH 41 ft	
	45							

George Post
 Signed

I-47

Approved

Site Manuel AFB.

Boring No. PZ6-3

SHEET 4 OF 4

0900 - Set up on hole

0910 - Begin augering - Monitor w. H-VU

- Hit piece of concrete (LARGE!)

- Move hole about 1 ft & start again

0945 - Down to 44 ft (overdrilled 3 ft intentionally) [41 ft]

0950 - Install well to 38 ft (screen 23 to 38 ft)

1005 - Pull augers

1020 - Having a hard time w. augers - well keeps pulling up as well

1055 - Augers out

Well shifted to 39 ft (screen 24 to 39 ft, 2 ft S.V.)

Clean auger

1130 - Decom complete

Cuttings shoveled into well - cased to 19 ft
cuttings 19 ft to G.L.

1135 - Deposit site

LUNC #1

12/6/84
DATE

George P. S.
SIGNED

APPROVED

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
CL	20	?	Sand No cutting returns below about 20 ft.		PVC screen			Coarse sand ~ 6 in loose Below 20 ft drilled like sand, but no returns.
25					PVC and cap			When pulling augers, the loose 10 or 15 ft of flight were filled w. ft to coarse gravelly sand, very wet, orange suggesting sand below ~ 20 ft.
							EOWR 23.5 Ft EOH @ 24.5 Ft	

Approved

SHEET _____ OF _____

0835 - Set up on site.
0840 - Begin augering
0900 - Down to 24 ft
Install well?
0915 - Well set @ 23.5 ft (screen ~~to 24 ft~~ to 23.5 ft)
0920 - Pull augers
Water inside well @ 15 ft
0935 - Clean augers
0950 - Deposit site.

12/5/84
DATE

George [Signature]
SIGNED

APPROVED

SHEET _____ OF _____

Signed

Approved

Site NAFB SHEET _____ OF _____

Boring No. PB 7-2 Location Coordinates N

Hole Size _____ Slot _____ E

Screen Length _____ Mat'l _____ Filter Materials _____

Diameter _____ Grout Type _____

Casing Length _____ Mat'l _____ Development _____

Diameter _____ Static Water Level _____

Date Start 12/6/84 Finish 12/6 Top of Well Elevation _____

Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse sand, 20% gravel, well graded, 2.54 7/2 (light gray), non plastic, loose, wet, fluid					
		EOH					EOH 23 ft	

Signed George P. O'S

I-53

Approved _____

Site Hamwell AFB
Boring No. PZ 7-2, Longrad, Site VII

SHEET _____ OF _____

- 12/5 1000 - Set up on-site -
1010 - Begin augering - Monitor w. H-NU
Encountered plastic debris, wood (likely
landfill material) @ about 3 ft depth
1015 - Abandon hole & select a new location, another time
1020 - Depart site to assist clearance for new site from
utility people


- 12/6 1250 - ESE on-site
- Required clearance for new hole location
- Drill crew returns (water run 1230 - 1250)
- Set up rig
1305 - Begin augering
1320 - Down to 23 ft
Install well to 22 ft (screen 12 to 22 + 1.9 ft S.W.)
1340 - Augers out - installation complete
1350 - Clean auger
+ ~~check for water~~
* Water measured in well @ 11.7 ft T.C., 9.7 ft G.L.
Formation caved @ 9.5 ft (top of water?)
Cutting to surface (cleared w. H-NU)
1416 Depart site

12/6/84
DATE

George R. [Signature]
SIGNED

APPROVED

Site MAFB SHEET _____ OF _____
 Spring No. PZ 7-3 Location Coordinates N
 Hole Size _____ Slot E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 12/5/84 Finish 12/5 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery %	Box or Hox or Sample #	Sketch of Construction	Remarks
	20	EOH	Fine to coarse sand, 25% clay, well graded, mod. sand, 54 5/2 (olive gray), sl. plastic, loose, very wet, fluvial				 6 in borehole cased sand PVC end cap EOH, EOH 20.8 ft.	

George Port
 Signed

I-56

Approved

Site Manuel AFB
Boring No. PZ 7-3, Downgrad Site VII

SHEET _____ OF _____

1030 - Set up on-site

1040 - Begin augering

NOTE: Field recently seeded in grass (rye) + very soft because of rain - may be tough working off hole.

1100 - Down to 20 ft

Install well to 20.8 ft (screen 10.8 to 20.8 ft), 2.4 ft S.C.

1100 - Pull augers

Water measured in pipe (well) @ 13 ft (B.L.)

1115 - Water run (will clean augers off-site)

1120 - Depart site

1130 - Lunch

1205 - Water Run

1235 - Water truck returns

Clean augers

1300 - Move to next hole

17/5/04
DATE

George B. [Signature]
SIGNED

APPROVED

APPENDIX J--MONITOR WELL WATER LEVELS

APPENDIX J


Monitor Well Water Levels (1-15-85 through 1-19-85, initial sampling event)

Well Designation	Depth to Water (ft)*	Stick Up (ft)	Depth to Water (ft)†
MW1-1	16.2	2.5	13.7
MW1-2	5.5	2.5	3.0
MW1-3	8.1	2.7	5.4
MW1-4	7.4	2.5	4.9
MW3-1	17.7	2.7	15.0
MW3-2	9.3	2.5	6.8
MW3-3	4.7	2.3	2.4
MW4-1	18.3	2.5	15.8
MW4-2	14.2	2.5	11.7
MW4-3	13.6	2.7	10.9
MW5-1	15.0	2.5	12.5
MW5-2	8.3	2.5	5.8
MW5-3	9.9	2.5	7.4
MW5-4	4.0	2.4	1.6
MW6-1	29.0	2.5	26.5
MW6-2	30.0	2.5	27.5
MW6-3	29.5	2.5	27.0
MW7-1	15.8	1.0	14.8
MW7-2	13.8	2.7	11.1
MW7-3	12.7	2.5	10.2

*Measured from the top of PVC casing.
†Measured from ground level.


Source: ESE, 1985.

APPENDIX K--MONITORING WELL BORING LOGS




FIELD BORING PROFILE FOR STATION: MXMW7-1

DATE COMPLETED: 1/4/85
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:




FIELD BORING PROFILE FOR STATION: MXMW7--2

DATE COMPLETED: 12/20/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:



FIELD BORING PROFILE FOR STATION: MXMW7--3

DATE COMPLETED: 12/20/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPEMENT:



K-4


FIELD BORING PROFILE FOR STATION: MXMW1-1

DATE COMPLETED: 12.20.84

WELL DIAMETER: 4"

DRILLING METHOD: HOLLOW STEM AUGER


DEVELOPEMENT:



K-5

FIELD BORING PROFILE FOR STATION: MXMW1-2

DATE COMPLETED: 12/17/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPEMENT:



FIELD BORING PROFILE FOR STATION: MXMW1-3

DATE COMPLETED: 12/18/84


WELL DIAMETER: 4"

DRILLING METHOD: HOLLOW STEM AUGER

DEVELOPMENT:




DATE COMPLETED: 12/16/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:



K-8


FIELD BORING PROFILE FOR STATION: MXMW3-1

DATE COMPLETED: 12/21/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:




FIELD BORING PROFILE FOR STATION: MXMW3-2


DATE COMPLETED: 1/5/85
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPEMENT:




FIELD BORING PROFILE FOR STATION: MXMW3--3
 DATE COMPLETED: 1/3/85
 WELL DIAMETER: 4"
 DRILLING METHOD: HOLLOW STEM AUGER
 DEVELOPEMENT:



DATE COMPLETED: 1/7/85
 WELL DIAMETER: 4"
 DRILLING METHOD: HOLLOW STEM AUGER
 DEVELOPEMENT:



FIELD BORING PROFILE FOR STATION: MXMW4-2
 DATE COMPLETED: 1/6/85
 WELL DIAMETER: 4"
 DRILLING METHOD: HOLLOW STEMRAUGER
 DEVELOPEMENT:




FIELD BORING PROFILE FOR STATION: MXMW4-3

DATE COMPLETED: 1/6/85

WELL DIAMETER: 4"

DRILLING METHOD: HOLLOW STEM AUGER

DEVELOPEMENT:




FIELD BORING PROFILE FOR STATION: MXMW5-1

DATE COMPLETED: 12/14/84

WELL DIAMETER: 4"


DRILLING METHOD: HOLLOW STEM AUGER

DEVELOPMENT:




FIELD BORING PROFILE FOR STATION: MxMW5-2

DATE COMPLETED: 12/15/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPEMENT:




FIELD BORING PROFILE FOR STATION: MXMW5-3

DATE COMPLETED: 1/11/85
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:



FIELD BORING PROFILE FOR STATION: MXMW5-4

DATE COMPLETED: 12/16/84
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:




FIELD BORING PROFILE FOR STATION: MXMW6-1


DATE COMPLETED: 1/9/85

WELL DIAMETER: 4"

DRILLING METHOD: HOLLOW STEM AUGER

DEVELOPEMENT:





FIELD BORING PROFILE FOR STATION: MXMW6-3

DATE COMPLETED: 1/8/85
WELL DIAMETER: 4"
DRILLING METHOD: HOLLOW STEM AUGER
DEVELOPMENT:

SHEET 1 OF 5

Site Maxwell AFBBoring No. MW 1-1 Second attemptLocation Coordinates NHole Size 12 in Slot 0.010 inEScreen Length 10 ft Mat'l Sch 40 PVC

Filter Materials

Diameter 4 in

Grout Type

Casing Length 15 ft + 2.5 ft S.U. Mat'l Sch 40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 12/20/84 Finish 12/20/84

Top of Well Elevation

Contractor ESE Driller Low GungDrill Type 4" hollow stem auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked, steel casing					Log based on split spoon samples, cuttings, drill rate
0			Sandy, silty clay, 20% very fine sand, 20% silt, silty, 7.54 R5/B (strong brown), damp, N.A.B. flood plain; less sandy + more silty below 3 ft	2	10	1		grout
		CL	clay, silty, v. fine sand, 20% clay, 15% silt, 10.4 R5/B (yel. brown), silty, dense, damp, N.A.B., flood plain	6	9			All contacts approximated + gradational
5		SC	Fine to med sand, 3% clay, poorly graded, round, 5.4 R2 S/B (yellow red), non plastic, dense, damp, N.A.B., fluvial	7	15	2		joint
		SP	Very fine to med sand, 2% clay, 2% gravel (< 2 in), well graded, round, 5.4 R2 S/B (yel. red), non plastic, dense, moist, N.A.B., fluvial	17	20			Bentonite seal
		SW	Fine to coarse sand, 1% clay, well graded, round, 10.4 R6/B (brown, yellow), non plastic, dense, moist, N.A.B., fluvial	7	12	3, 4		PVC casing
10		SW	Fine to coarse sand, 70% gravel, 4% clay, well graded, round, 10.4 R6/B (brown, yellow), non plastic, v. dense, wet, N.A.B., fluvial	7	16	5, 6		12 in borehole
		SW		12	14			bagged sand
				14	16	7, 8		joint
15		SW		14	16	7, 8		1st H ₂ O near 14 ft based on wet spoon sample
				26	33			PVC screen
								caved sand

Signed

K-21

Approved

Site M.A.F.B.SHEET 2 OF 5Spring No. MW 1-1Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 12/20/84 Finish 12/20/84

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse sand, 20% gravel, 5% clay, well graded, round, 104R 7/8 (yellow), non plastic, dense, wet, N.A.B., fluvial	12 9 13	8	9		

Signed George R. [Signature]

K-22

Approved _____

SHEET 5 OF 7

Site Mammoth Hills
Boring No. MW 1-1 (1st attempt)

Boring No. MW 1-1 (1st attempt)

Hole Size 12. in Slot 0.010 in

Screen Length Mar '15 60 PVC

Diameter 4 in

Casing Length _____ Mar '1 Sub 40 PVL

Diameter 4 in

Date Start 12-19-84 Finish

Contractor FSE Driller Law E

Location Coordinates N _____

Filter Materials

Grout Type _____

Development

Static Water Level _____

Top of Well Elevation _____

Drill Type Wolven Steam Auger

Drill Type Wet Pan Steam Angle

Signed

K-23

Approved

Site Maxwell AFB


Boring No. NW 1-1

SHEET

4 OF 5

- 12/19 0730 ESTE, Driller on-site
Calibrate H-NV
Span @ 9-8 = 65 ppm
Utilities man is supposed to be here now to clear site.
- 0745 No utilities man! Make phone call!
- 0850 Driller back for coffee
- 0851 Man shows up - clears site
- 0930 Driller returns, set up rig
- 0945 Begin augering
Auger to 2.5 ft
Span 2.5 to 4 ft
Auger to 5 ft
H-NV detected 10 ppm close B.G. @ ground level
- 1000 Discontinue augering - clear site
- 1015 Called Charlie ~~Phillips~~ (Harry (safety man))
+ described condition to him: white to gray smoke, capsa, fumes coming up inside auger from about 4 ft below ground level - registered c. 10 ppm on H-NV; after several minutes the white smoking was down to almost 5 ppm (no reading in breathing zone)
- 1030 Driller + helper with respirator pull auger + load rig - move across road; they were fit tested for smogless beforehand
Auger + plug cleaned thoroughly + taken off-site
- 1045 Cuttings shoveled into 5 gal. plastic bucket w. lids + sealed for air force disposal
Hole grouted to 5 ft
Area roped off, contained cuttings inside roped area
- 1115 Decon complete - Roped site
Will change a new hole location + have it closed this afternoon or tomorrow
Move to NW 7-3

12/19/84
DATE


SIGNED

APPROVED

Site MAFB

Boring No. AW 1-1

SHEET 5 OF 5

12/20 1600 Arrive on site, for second attempt
 1605 Auger to 2.5 ft - monitor w. H-NV
 Spoon 2.5 to 4 ft
 Auger to 5 ft
 Spoon 5 to 6.5 ft
 Auger to 7.5 ft
 Spoon 7.5 to 9 ft
 Auger to 10 ft
 Spoon 10 to 11.5 ft
 1640 Setting up lights + generator
 Auger to 15 ft
 Spoon 15 to 16.5 ft
 1700 Auger to 20 ft
 Spoon 20 to 21.5 ft
 Auger to ~~22~~ 24 ft
 2 ft of sand inside auger
 1720 while waiting for water truck check out
 other sites
 Auger to 28 ft - only 1 ft of sand inside auger
 1750 Set well to 25 ft
 Pull auger - had a very tough time
 1845 Lowered to 17 ft
 Add sand to 9 ft (3 bags - (6 small ones))
 1910 Bent pellets to 6 ft (2 pellets)
 1940 Grown to surface (1 bag cement, 5 ft bent)
 Auger cleared
 2000 Depart site. - will load auger in A.M.
 * Well set @ 25 ft, 10 ft screen, 2.5 ft S.V.
 * Used 250 gal H₂O to make well (75% return)
 * Materials - 17.5 ft riser, 10 ft screen, 3 bags sand,
 2 bentonite pellets, 1 bag cement, 5 ft bent powder,
 1 steel casing w/ back

12/20/84
 DATE

George Foster
 SIGNED

APPROVED

SHEET 1 OF 4

Site Wapnet AFB

Boring No. MW 1-2

Hole Size 12 in Slot 0.010 in

Screen Length 10 Mat'l Sch 40 PVC

Diameter 2 in

Casing Length 4 ft + 2.5 ft Mat'l Sch 40 PVC

Diameter 2 in

Date Start 12/16/84 Finish 12/17/84

Contractor FSE Driller Law Eng.

Location Coordinates N

E

Filter Materials Bagged sand

Grout Type 20/1 cement / bent.

Development

Static Water Level

Top of Well Elevation

Drill Type Hand Operated Auger

12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Slow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked steel casing					Log based on split spoon samples, cuttings, drill rate
0	0	CL	Sandy clay, 35% med to co. sand, 54 4/6 (yellow red), mod. plastic, med. consist, damp, N.A.B., flood plain	4	11	1		
		CL to ML	Interbedded clay + clayey silt, 54 6/1 (gray), sl. to v. plastic, med. consist, damp, N.A.B., flood plain	5				Probably some perched H ₂ O above 4.5 ft in the silt lenses.
5	5	CL	Silty clay, 10% silt, 54 6/1 (gray), v. plastic, stiff, damp, N.A.B., flood plain	4	14	2		
		CH	Inorganic clay, 54 6/1 (gray) to 104 R 5/6 (yellow brown), mottled, v. plastic, stiff, damp, N.A.B., flood plain	8	13			
10	10	SM	Silty fine sand, 25% silt, 5% clay, 5% muscovite, 54 5/2 (dine gray), non plastic, dense, moist, N.A.B., flood plain	6	13	4, 5		
		SC	Sand/clay mixture, 54 7/4 (yellow), very wet	10				
15	15	CH	Inorganic clay, 54 6/1 (gray) to 104 R 5/6 (yellow brown), v. plastic, stiff, moist, N.A.B., flood plain	2	12	7		
				8	10			

Signed

K-26

Approved

Site N.A.F.B.SHEET 2 OF 4Spring No. NW 1-22Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/16/84 Finish 12/17

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample	Sketch of Construction	Remarks
	20	CH	Med. sand, 10% black grains, 5% clay, 5% muscovite, poorly graded, round, 546/4 (lt. olive) to 10426/8 (brown, yellow), non plastic, v. dense, moist, fluvial, N.A.B.	14 24 47	14	8 9		12 in. boulders Lenticular pellets Grout
	25	SP	Fine to med sand, 10% black grains, 5% clay, 5% muscovite, poorly graded, round, 546/4 (lt. olive) to 10426/8 (brown, yellow), non plastic, very dense, moist, fluvial N.A.B.	21 38 53	14	10 11	EOH 25F.	The sand below ~19 ft (beneath the clay) is moist but not saturated.

Signed

K-27

Approved

Site Maxwell AFB

Boring No. NW 1-2

SHEET 3 OF 4

12/16 1115 Arrive on-site
 Set up rig
 1145 Lunch, place coils
 1245 Begin augering - monitor w. H-VU
 Auger to 2.5 ft
 Spoon 2.5 to 4 ft
 Auger to 5 ft
 Spoon 5 to 6.5 ft
 Auger to 7.5 ft
 Spoon 7.5 to 9 ft
 Auger to 10 ft
 1400 Spoon 10 to 11.5 ft
 Auger to 15 ft
 Spoon 15 to 16.5 ft
 Auger to 20 ft
 Spoon 20 to 21.5 ft
 Auger to 25 ft
 1500 Spoon 25 to 26.5 ft
 Sand below 19 ft (beneath a thick clay) is not
 saturated to at least 26.5 ft; grout the hole
 up to 20 ft & allow to set overnight
 Plan to get the well @ 15 ft tomorrow
 Used 3 bags cement, 15# bent. powder
 1630 Depart site
 12/17 0630 FSE, Bullen on-site
 Cement top @ 19 ft (total of 6 ft)
 Add bent. pellets to 16 ft (1 1/2 bushels)
 0730 Pellets bridged in auger - use auger plug to remove;
 don't work
 Use rotary bit to remove bridge
 0815 Add sand from 16 to 15 ft 14 ft (2 bags)
 Install well to 14 ft (10 ft screen)
 0915 Add sand to 3 ft (8 bags) (includes 2 bags above)

12/16/94
 DATE

George Ford
 SIGNED

APPROVED

Site Maxwell AFB
Boring No. MW 1-2

SHEET 4 OF 4

12/17 1000 Bent pellets to 2 ft (1 bucket)
cont. Grout to surface (2 bags cement, 10# bent powder)

1010 Cleaning auger - flights clogged with clay & mud on sides coated in bentonite

1100 Still cleaning auger, cleaning into

* NOTE: Spent 30 min, 10/16, mixing grout & pumping down hole (used 3 bags cement, 15# bent, but only about 2/3 was used in this hole - the rest was used to fill in PZ 5-2 hole)

On 10/17 spent about 30 min adding bent pellets to the bottom of this hole; pellets bridged & we spent an hour or so removing the plug

1140 Will clean up site after the clay has had time to dry out

Depart site, move to MW 1-3

* Well set @ 14 ft (10 ft screen & 2.5 ft S.U.)

* Used 200 gal H₂O to make well (75% return)

* Materials - 6.5 ft riser, 10 ft screen, 8 bags sand, 5 bags cement, 2.5# bent powder, 2 1/2 buckets pellets, 1 steel casing w/lock

12/17/84
DATE

George Frost
SIGNED

APPROVED

Site Maple AFBSHEET 1 OF 4Boring No. MW 1-3Location Coordinates NHole Size 12 in Slot 0.016 inEScreen Length 15 ft Mat'l 1 1/2 in 40 PVCFilter Materials formation + bagged sandDiameter 2 inGrout Type 30/1 cement / bentoniteCasing Length 7.3 ft + 2.7 ft S.U. Mat'l 1 1/2 in 40 PVC

Development

Diameter 2 in

Static Water Level

Date Start 12/17/84 Finish 12/18/84

Top of Well Elevation

Contractor ESE Driller Low Eng.Drill Type Fuller Stem Auger
12 in O.D., 6 in I.D.

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Flow Counts	Recovery Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked steel casing				Log based on spoon sample, cuttings, drill rate
0		SC	Clayey fine sand, 15% clay, 10426/6 (brownish yellow), sl. plastic, loose, dry, N.A.B., flood plain	19	10 1		grout
		SM	Silt/fine sand mixture, 546/1 (gray), sl. plastic, dense, dry, N.A.B., flood plain	17			PVC casing
5		SW	Silty fine sand, 25% silt, 5% clay, 546/1 (gray), sl. plastic, loose, wet N.A.B., flood plain	578	8 2		bentonite seal
		SW	Very fine to very coarse sand, 40% gravel (to 2 cm) 546/1 (gray), non plastic, v. dense, wet, N.A.B., fluvial	36	10 3		15 H ₂ O near 6 ft based on water contact in spoon sample
10		SW	Fine to coarse sand, well graded, sl. round, 546/3 (pale olive), non plastic, med. density, wet, N.A.B., fluvial	36	11 4		bagged sand
		SW	Fine to very coarse sand, 25% gravel (to 2 cm), well graded, round, 2.547/4 (pale yellow), non plastic, dense, wet, N.A.B., fluvial	31	10 5		Doesn't seem to be any perched water as in MW 1-2
15		SW					PVC screen
							12 in lockhole
							formation sand (caved)

Signed George

K-30

Approved

Site MAFB

SHEET _____ OF _____

Spring No. NW 1-3Location Coordinates N _____

Hole Size _____ Slot _____

E _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/17/84 Finish 12/18/84

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Slow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SP	Fine to med sand, 10% clay, 10% black grains, 5% mica, etc, poorly graded, 54.5/3 (cline), sh. to non plastic, very dense, moist, NAB. fluvial					The confining clay layer above the green sand in NW 1-2 was not present in this hole

Signed _____

K-31

Approved _____

Site Naval AFB
Boring No. AW-3

SHEET 3 OF 4

- 12/17 1140 Set up on-site - Calibrate H-NU
1150 Begin augering
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
1230 LUNCH
1305 Auger to 15 ft
Spoon 15 to 16.5 ft
1310 Belt on rig motor slipped off
Fan bearing shot.
Discontinue activities for the day to repair rig
1700 Depart site
12/18 0630 Arrive on-site - Calibrate H-NU motor
Allowing rig to warm up in order to introduce
"STOP LEAK" to isolation to fill a hole
0710 Begin augering
Auger to 20 ft
Spoon 20 to 21.5 ft
0830 Auger to 22 ft - no bearing sands!
0900 Install well
Add lagged sand from 22 to 18 ft (1 bag)
Sand cased from 18 to 12 ft
0930 Add sand from 12 to 4 ft (6 bags)
* Representative of the "Grounds" Department came by
+ he + I went to FTA #2 to discuss removing
a fence along the West End Ditch to allow the
rig to move closer to the ditch
1000 Backfilled pellets to 2.5 ft (1 bucket)

12/17/84
DATE

George [Signature]
SIGNED

APPROVED

Site Maple AFB
Boring No. MW 1-3

SHEET 4 OF 4

12/18 1005 Mixing grout
cont 1030 Grout to surface (2 bags cement, 10# bent. powder)

* Well set @ 22.3 ft (15 ft screen, 2.7 ft S.V.)

* Used 0 gal H₂O to make well!

* Materials - 10 ft riser, 15 ft screen,
7 bags sand, 10# bent. powder, 2 bags cement,
10# bent. powder, 1 steel casing w/locks

1040 Coring up PZ 1-3 after pulling
Papers into after cleaning auger

1050 Calibrate H-NU

Span @ 9.8 - 65 ppm

Err, OK

12/18/84
DATE

George [Signature]
SIGNED

APPROVED

Site M.A.F. Base
 Boring No. M41-4
 Hole Size 12 in Slot 0.010 in
 Screen Length 15 ft Mat'1 SL40 PVC
 Diameter 4 in
 Casing Length 6.5 ft + 2.5 ft + 5 ft Mat'1 SL40 PVC
 Diameter 4 in
 Date Start 12/18/84 Finish 12/18/84
 Contractor ESE Driller Low Eng

Location Coordinates N
E
 Filter Materials formation + lagged sand
 Grout Type 20/1 cement / Presto
 Development _____
 Static Water Level _____
 Top of Well Elevation _____
 Drill Type 4" hollow stem auger
12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC dip cap					Log based on spoon samples cuttings, drill notes
			6 in locked steel casing					grout
	0	CL	Sandy, silty clay, 30% sand, 10% silt, 545/2 (dk drab to 7.54R4/6 (slaty brown), soft, al. non plastic, damp, U.A.B., flood plain	3	13	1		Contact @ 3.6 ft sharp
	5	SC	Fine to coarse clay, sand, 30% clay, well graded, 546/1 (gray), al. plastic, loose, moist, U.A.B., fluvial	5	2	2		Bentonite seal
	5	SW	Fine to med sand, 10% clay, well graded, 546/2 (br drab gray), non-al. plastic	3	8	3		PVC casing
	10	GW	Loose, wet, U.A.B., fluvial	10	11	4		1st H ₂ O near
	10		Sandy gravel, 40% 1/2 - 1/4 in. sand, well graded, round, 547/3 (pale yellow), non plastic, dense, wet, U.A.B., fluvial	10	5	5		5 ft logged on wet spoon sample
	15	SW	Fine to coarse sand, 15% gravel (to 1 cm), well graded, round, 547/4 (pale yellow), non plastic, dense, wet, U.A.B., fluvial, *10% black grains	3	14	6		All contents below 5 ft approximate & gradational
	15		Very fine to v. coarse sand, 5% gravel (to 1 cm), well graded mod. round, 104R6/8 (brown yellow), non plastic, loose, wet, U.A.B., fluvial	4	8	7		12 in borehole
				4	4	8		lagged sand
								PVC screen
								caved sand

Signed [Signature]

K-34

Approved

SHEET 2 OF 3Site MAFBSpring No. MW 1-4Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/18/84Finish 12/18/84

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to v. coarse sand, 5% clay, well graded, 10 # R 6/8 (brownish yellow), non plastic, loose, wet, N.A.B., fluid	45	0	X	12 in. borehole caved sand PVC screen PVC end cap	
	25	SC	Hole overdrilled to 25 ft - when pulling auger the bottom flights (3 or 4 ft) were found to be clogged w. the dense, fine clayey sand.	X	5	9	EDH 21.5 ft	
		EDH				10	EDH 25 ft	No blow counts taken on last spoon sample because we had to drive it through sand heaved up in the auger to reach virgin soil.

Signed George [Signature]

K-35

Approved _____

Site Magwood AFB
Boring No. MW 1-4

SHEET 3 OF 3

1100 Set up on site
1115 LUNCH
1200 Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft - only recovered 1 in. of material
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
1315 Spoon 10 to 11.5 ft - made 2 attempts as first yielded
no sample
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
Spoon 20 to 21.5 ft - only recovered an inch of sample,
of medium quality
Auger to 22 ft
Spoon 22 to 23.5 ft
Overhaul to 25 ft (sand barrel several ft under auger)
1350 Water run
1430 Water timer returns
Wash out hole w. return line
1455 Pull return line
1500 Install well to ~22 ft
Hole cased to 18 ft
1530 Add sand from 18 to 3 ft (4 bags) (partially cased)
1550 Band pellets to 2 ft (1 bucket)
1620 Grout to surface (3 bags cement, 15 # bent.)
(also grout P=1-4)
1700 Deposit site
* Used 250 gal H₂O to make well (75% return)
* Well set @ 21.5 ft, 15 ft screen, 2.5 ft S.V.
* Materials - 9 ft riser, 15 ft casing, 4 bags sand,
1 bucket pellets, 3 bags cement, 15 # bent. pipe,
1 steel casing w/lock

17/18/84
DATE


SIGNED

APPROVED

Site Mapwell AFBSHEET 1 OF 4Spring No. MW 3-1Location Coordinates NHole Size 12 in Slot 0.010 inEScreen Length 10 ft Mat'l 3/4" PVCFilter Materials formation sand, bagged sandDiameter 7 inGrout Type 20/1 cement/bentoniteCasing Length 27.3 ft + 27.5 ft Mat'l 3/4" PVC

Development

Diameter 4 in

Static Water Level

Date Start 12/21/84 Finish 12/21/84

Top of Well Elevation

Contractor FSE Driller Law EngDrill Type Hollow Stem Auger12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
0			4 in PVC slip cap 6 in locked steel casing					Log based on split spoon samples cutting, drill rate
		CH	Inorganic clay, 10% silt, 54 R5/6 (yellow red) G	12	15	1		grout
			104 R5/8 (yellow brown), mod plastic, hard, dry, mottled, flood plain	26		2		Contacts at 4.5, 7, 9.5, 13 ft + approximately + gradual
5		CL	Silty clay, 25% silt, 104 R5/8 (yellow brown) to 54 7/2 (lt gray), mod plastic, stiff, dry, mottled, flood plain	37	18	3		PVC casing
			Silty, sandy clay, 15% silt, 15% fine sand, 104 R5/8 (yellow brown) to 54 7/2 (gray), mod plastic, stiff, dry, mottled, flood plain	17	10	4		Contacts at 16.2 ft sharp
		CL		21	15	5		
10		CL		9	18	6		12 in lock hole
			Sandy, silty clay, 70% fine sand, 10% silt, 7.5 4 R5/8 (strong brown) to 54 7/2 (lt gray), sl. plastic, stiff, damp, mottled, flood plain	20				15 H ₂ O near 13 ft based on wet spoon sample @ 15 ft
		SM		12	16	7		bentonite seal
15			Silty fine sand, 25% silt, 54 7/2 (lt gray), non plastic, damp, wet, N.A.B., flood plain	17				cased sand
		SP		28				

Signed

K-37

Approved

Site MAFBBoring No. M43-1Location Coordinates N

Hole Size _____ Slot _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/21/84 Finish 12/21/84

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft.)	Depth (ft.)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SP	Fine to med sand, 2% clay, poorly graded, round, 7.54R 5/8 (silts brown), non plastic, dense, wet, N.A.B., fluvial	2 3 4	18	8		PVC casing
		CH	inorganic clay, 54.5/1 (gray), very plastic, soft, moist, N.A.B., flood plain					caved sand
			clayey sandy silt, 20% clay, 20% fine sand, 5% mica, 54.4/1 (dk gray), sl. plastic, soft, moist, N.A.B., flood plain	1 2 3	18	9		12 in borehole
	25	ML						bestonite seal
								bagged sand
	30	SW	Fine to med sand, 40% gravel (to 2 in), well graded, round, 104.27/6 (yellow), non plastic, very loose, wet, N.A.B., fluvial	1 2 4	5	10		caved sand
								joint
								Auger plug coated with sand & gravel when pulled to take 30 ft sample
								PVC screen
	35							PVC end cap
								EOW, EOH 37.3 ft

Signed _____

K-38

Approved _____

Site Mapwell AFB
Boring No. MW 3-1

SHEET 3 OF 4

- 0600 - Driller called to say they'd be late this AM because someone stole their tools & they had to tell the police (stolen from the hotel)
- 0700 - Arrive on-site (MW 1-1) & load auger; move to MW 3-1
- 0800 - Begin augering; calibrate H-NV, monitor hole
- Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
- 0910 - Spoon 15 to 16.5 ft
Auger to 20 ft
Spoon 20 to 21.5 ft
Auger to 25 ft
- 1015 - Spoon 25 to 26.5 ft
- 1045 - Auger to 30 ft
Spoon 30 to 31.5 ft
Auger to 40 ft (overbilled 3 ft)
- 1130 - Lunch
- 1230 - Water run - 250 gal
- 1300 - Take soil from MW 1-1 (1st attempt) to Driller Storage area
- 1400 - While Driller runs out the auger & pump record of the well casing fluorescent orange (MW 1-1, 7-2, 7-3)
- 1410 - Water run - 500 gal
- 1450 - Water run - 750 gal
- 1630/1530 - Water run - 1000 gal

12/21/84
DATE

George [Signature]
SIGNED

APPROVED

Site MAF.B.

Boring No. MW 3-1

SHEET

4 OF 4

1700 - Supplies run

- Only 3 ft of sand/gravel inside auger

1750 - Set well & attempt to pull auger

well fell to ~ 37 ft, but acceptable (wanted 38 ft)

- Cased to 24 ft

- Add sand to 22 ft (1 lb bag = 2 in bag)

Pellets to ~~21.5~~ 21.5 ft

Braked about 5 ft from bottom of auger

Attempt to push them out the bottom with pipe

1900 - Couldn't remove bridge

Pulled auger all the way out - hole cased to 16 ft

1930 - Add pellets to 13 ft - 3 buckets

2000 - Grout to surface (5 bag cement, 25 lb powder)

* Used 1000 gal H₂O with 75% recovery (~250 gal still in hole)

* Well set @ 37.3 ft, 10 ft screen, 2.7 ft S.V.)

* Materials - 30 ft screen, 10 ft screen, 5 bags cement, 25 lb lead powder, 3 buckets pellets, 1 bag sand, 1 steel casing w/ lock

Note - Also grouted PE 3-1.

Note - Well was supposed to be placed to 35 ft; driller placed it to 37 ft (unavoidably); who pays for the extra 2 ft??

Note - Because of the pellet bridge in the auger the clay seal couldn't be properly placed; the suitability of the well will be determined during development, but if not acceptable the driller says he'll take it.

2045 Depart site - return 1/3/84

12/21/84
DATE

George R. R.
SIGNED

APPROVED

Site Maywell AFB
 Boring No. 11W 3-2 Location Coordinates N
 Hole Size 12 in Slot 0.010 in E
 Screen Length 30 ft Mat'l Sch 40 PVC Filter Materials granular & coarse sand
 Diameter 4 in Grout Type 20/1 cement / 2 1/2 in
 Casing Length 4.2 ft + 2.5 ft Mat'l Sch 40 PVC Development
 Diameter 4 in Static Water Level
 Date Start 1/5/85 Finish 1/5/85 Top of Well Elevation
 Contractor ESF Driller Lawrence Drill Type Hand Pump from surface
12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked steel casing					Log based on spade spoon samples, cuttings drill rate
0	0	CL	Silty clay, 25% silt, 104R 5/4 (yellow brown), mod plastic, med. consist, damp, N.A.B., flood plain	4	10	1		grout PVC casing 12 in lockhole
5	5	CH	Landfill debris (glass, plastic)	5	5	joint		Below 3.5 ft encountered land- fill debris
			Inorganic clay, 104R 6/8 (brown, yellow) to 546/1 (gray), v. plastic, soft, damp, mottled, flood plain	2	11	2		best estimate sand
			Inorganic clay, 545/1 (gray) v. plastic, soft, moist, N.A.B., flood plain	3	18	3		1st H ₂ O near 9 ft, based on wet sand in spoon foot
10	10	SW	Fine to v. coarse quartz sand, well graded, round, 546/1 (gray), non plastic, dense, N.A.B., wet, fluvial	5	10	4		bagged sand PVC screen
				14	5	5		
15	15	SP	Fine to med meaceous sand, 15% muscovite, 5% black grains, poorly graded, round, 2.54 6/4 (lt. brown, yellow), non plastic, loose, N.A.B., wet, fluvial	5	12	6		Contacts @ 4.5 ft and 13.5 ft approximate; other contacts sharp
				24	4			- covered sand

Signed George

K-41

Approved

SHEET 2 OF 4

Site MAFB
 Spring No. MW 3-2 Location Coordinates N
 Hole Size _____ Slot _____ E _____
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 1/5/85 Finish 1/5/85 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box of Sample	Sketch of Construction	Remarks
26	SW		Fine to co. sand, 3% black grains, well graded, round, 2.5-4/6 (dus yellow), non plastic, very loose, wet, N.A.B., fluvial	2	18	7		12 in. loose hole PVC screen coarse sand PVC end caps
25	SW		Fine to co. sand, 15% gravel (< 1 mm), well graded, round, 2.5-4/6 (dus yellow), non plastic, very loose, wet, N.A.B., fluvial			8		
	EO#							

Signed George K-42
 K-42

Approved


Site Marwell AFB

Boring No. MW 3-2

SHEET 3 OF 4

0630 Assume on-site
Calibrate #1-VU - 65 ppm @ Span 9.8
Water seen
0710 Water truck returns
Rig hard to start (very cold)
0730 Move onto hole, set up rig
0805 Begin auguring
I had the fence taken down & we were as close to
the edge of the lower end ditch as possible (within
5 ft)
Augers to 2.5 ft
Spoon 2.5 to 4 ft
Lower part of spoon (3.5 to 4 ft) Landfill debris - glass,
plastic, concrete, etc. - were as close to the edge
of the fill area as possible
Augers to 5 ft - out of the fill material now!
0825 Spoon 5 to 6.5 ft
Augers to 7.5 ft
Spoon 7.5 to 9 ft
Augers to 10 ft
0845 Spoon 10 to 11.5 ft
Augers to 15 ft
Spoon 15 to 16.5 ft
0920 Augers to 20 ft (had problem making connection)
Spoon 20 to 21.5 ft
0940 Augers to 25 ft
0945 Sound hole - 7 ft of sand inside augers
Prepare to rotate out the hole
1005 Bit out - ready for well - add 1 1/2 sand from 27 to 25 ft
Drillable well to ~ 25 ft
Can't pull augers, chain broken
1030 Stop to go to store for new chain
1105 Chain in hole & ready to resume operation
1120 Augers are coming up!

1/5/85
DATE


SIGNED

APPROVED

Site M. AFB
Boring No. MW 3-2

SHEET 4 OF 4

1140 Sand cased to 12 ft
Add sand to 4.7 ft (7 bags = 14 little bags)
Well is set @ 24.2 ft (shifted up 0.8 ft); Top 0.5 ft of
screened section is not visible, on top of the 20 ft
screen is @ 4.7 ft rather than 4.2 ft; did not load
the sand filter pack along the top of the screen in order
to avoid the landfill debris, accumulated from 3.5 to
4.5 ft from the well.

1235 Pellets to 3.5 ft (1 bucket)
LUNCH

1315 Mixing cement - (1 bag cement, 5# bentonite powder)

1330 Grout to surface &
Cleaning pump

1415 Disposal notes

* Used 200 gal H₂O to make well (75% return)


* 4.000 pump @ 2.6 ft (20 ft screen, 2.5 ft S.V.)

* 1 bucket pellets, 1 bag cement, 5# bentonite powder,
1 steel casing w/ stick

* Well set @ 24.2 ft (20 ft screen, 2.5 ft S.V.)

* 1 bucket pellets, 1 bag cement, 5# bentonite powder,
1 steel casing w/ stick

1/5/85
DATE


SIGNED

APPROVED

Site Maxwell AFB

Boring No. MW 3-3

Hole Size 12 in Slot 0.010 in

Screen Length 20 ft Mat'l SA 40 PVC

Diameter 4 in

Casing Length 5.2 ft + 2.3 ft Mat'l SA 40 PVC

Diameter 4 in

Date Start 1/3/85 Finish 1/3/85

Contractor ESE Driller Law Eng.

Location Coordinates N

E

Filter Materials formation + bagged sand

Grout Type SPN cement/limestone

Development

Static Water Level

Top of Well Elevation

Drill Type Hollow Stem Auger

12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
0			4 in PVC casing cap 6 in steel locked casing					Log based on split spoon sampler cuttings, drill rate
	0	CL	Silly clay, 20% silt, 3% muscovite, 54711 (lt gray) to 104R518 (yellow brown), mottled, mod. plastic, red. cement, damp, flood plain	24	16	1		PVC casing 2 grout 12 in hole hole limestone seal joint
	5	ML	Clayey silt, 20% clay, 5% muscovite, 54711 (lt gray) to 2.54614 (lt. yellow brown), mottled, sl. plastic, very stiff, dry, flood plain	12	15	2		
	7	ML to SM	Interbedded clayey silt and silty fine sand, 54711 (lt gray), non to sl. plastic, soft, wet, flood plain	4	17	3		1st H ₂ O near 7 ft based on wet spoon sample @ 7.5 ft
	10	ML to SP	Interbedded clayey silt and fine to med sand, 54711 (lt gray) to 104R718 (yellow), to 7.54R518 (strong brown), mottled, non to sl. plastic, med density, wet, flood plain, (10% muscovite)	22	10	4		bagged sand All contacts approximate & gradational
	15	GW	Gravel (to 5 in), 40% fine to coarse sand, well sorted, round, 2.54716 (yellow), non plastic, U. dense, wet, N.A.B., fluvial	12	8	5		PVC screen joint caved sand

Signed George Paul

K-45

Approved

SHEET 2 OF 4

Site MAFB
 Boring No. MW 3-3 Location Coordinates N
 Hole Size _____ Slot _____ E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 1/7/85 Finish 1/3/85 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse quartz sand, 10% gravel, well graded, round, 2.54 7/6 (yellow), non plastic, very dense, wet, N.A.B., fluvial	315 59 1/4	8	6		12 in. Corbice gravel sand PVC screen
	25	CL	Silty micaceous clay, 20% silt, 15% mica, 543/6 (dark olive), mod. plastic, stiff, moist, N.A.B., flood- plain					Green clay cutting to surface when cleaning hole w. rotary bit (from bottom)
		EOH						Green clay on bit (auger) when pulled from hole

Signed [Signature]
 K-46

Approved

Site Mamwell AFB
Boring No. MW 3-3

SHEET 3 OF 4

11/3 0700 ESE on-site
0730 Driller w. full water truck on-site
0740 Attempted to start rig, but had problems
0745 Rig finally started but now stuck in the mud (rained
last night)
0830 Rig freed - move back to MW 3-1 + load augers
0845 Set up on MW 3-3
Cleaning rig, cleaning drill pipe.
0935 Began augering
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Calibrated MW - 6.5 ft span 9.8
0945 Supply run to hardware store (25 min DOWNTIME)
Calibrated MW - 6.5 ft span 9.8
1025 Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
1050 Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
1110 Spoon 15 to 16.5 ft
Auger to 20 ft
1130 Auger plus stuck made auger (heaving sand & gravel)
1140 Plus freed
Spoon 20 to 21.5 ft
Auger to 2.5 ft
1215 LUNCH
1300 Return to site

11/3/85
DATE

George Foster
SIGNED

APPROVED

K-47

Site M.A.F.B.

Boring No. M10 3-3

SHEET

4 OF 4

- 11/3 1305 10 ft of sand/gravel Leaned under auger
 1310 Hook up rotary bit & clean out auger
 1335 Still rigging up bit - having problem - line plugged w. cement
 1400 Water lines cleared (50 min duration)
 Begin w. rotary bit - overdrill to ~ 27 ft
 1430 Pull rotary bit
~~Start~~ Hole stayed open to 27 ft - add 2 small bags sand (= 1 lg. bag) to 25 ft
 1440 Install well to ~ 25 ft
 1445 Pull auger
 Well set @ 25.2 ft, 20 ft screen, 2.3 ft S.V.
 H₂O cased to 15 ft
 Add sand from 15 to 3.8 ft (18 small bags)
 1600 Bore pellets to 2.8 ft (1 1/2 buckets)
 1640 Bore to surface (1 1/2 bags cement, 7.5 # bentonite)
 Spend 35 min attempting to free water truck buried in the mud - soil is soft & wet everywhere
 Will have to call tow truck or get some back-hauling equipment to pull out the truck (+ possibly the rig) tomorrow A.M.
 1700 Depart site.
 11/4 0700 Attempt again to free water truck & rig; no avail.
 0800 Bulldozer pulls out both.
 0830 Depart site, water run
 * Used 400 gal H₂O to make mud (75% return)
 * Well set @ 25.2 ft (20 ft screen, 2.3 ft S.V.)
 * Materials = 20 ft screen, 7.5 ft casing, 20 small bag sand (= 16 lg. bags), 1 1/2 buckets pellets, 1 1/2 bags cement, 7.5 # bent. powder, 1 steel casing w/ lock

11/3/85
 DATE

George K. [Signature]
 SIGNED

APPROVED

Site U. S. Air Force Base

Boring No. MW 4-1

Hole Size 12 in Slot 0.010 in

Screen Length 10 ft Mat'l Sch 40 PVC

Diameter 4 in

Casing Length 16 ft + 25 ft + 50 ft Mat'l Sch 40 PVC

Diameter 4 in

Date Start 11/7/85 Finish 11/7/85

Contractor ESE Driller Law Eng

Location Coordinates N

E

Filter Materials formation sand

Grout Type 30/1 cement/sand

Development

Static Water Level

Top of Well Elevation

Drill Type Hollow Stem Auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap					Log based on split spoon samples, cuttings, drill rate
			Gravelly fine to med sand, 45% gravel, well graded, round, 7.54R 5/8 (strong brown), non plastic, dense, dry, N.A.B., fluvial	12	8	1		
				21				
				22				
			Sandy gravel (to 8 in), 40% fine to med sand, well graded, round, 7.54R 5/8 (strong brown), non plastic, dense, dry, N.A.B., fluvial	13	12	2		
				27				
				31				
			Gravelly fine to med sand (40% gravel (to 5 in), well graded, round, 104R 7/8 (yellow), non plastic, dense, sl. damp, N.A.B., fluvial	19	12	3		
				27				
				29				
			Gravelly med to coarse sand, 35% gravel (to 3 in), well graded, round, 104R 7/8 (yellow), non plastic, dense, sl. damp, N.A.B., fluvial	15	9	4		
				16				
				19				
			Gravelly med to coarse sand, 25% gravel (to 2 in), 104R 6/8 (brown, yellow), non plastic, dense, med, N.A.B., fluvial	9	8	5		
				13				
				13				

Signed George S.

K-49

Approved

SHEET 2 OF 4Site NAFBBoring No. NW 4-1Location Coordinates NE

Hole Size _____ Slot _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 11/7/85 Finish 11/7/85

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Gravelly fine to med. quartz sand, 30% gravel (6-3 cm), well sorted, round, 104 R7/4 (v. pale brown), non plastic, dense, wet, N.A.B., fluvial	6 23	3	6		
	25	SW						
		SW						
		EOW						

Signed George P. [Signature]

K-50

Approved _____

Site Alapwell AFB
Boring No. MU 4-1

SHEET 3 OF 4

0700 Arrive on-site, set up rig
0715 Water truck arrives w. full tank
Calibrate H-NV; 65 ppm @ Span = 9.5
Rig hard to start
0745 Augers to 2.5 ft - begin H-NV monitoring
Spoon 2.5 to 4 ft
Augers to 5 ft
Spoon 5 to 6.5 ft
0820 Driller left to use phone
0845 Driller returns (25 min DOWN TIME)
Resume operations
Augers to 7.5 ft
0900 Spoon 7.5 to 9 ft
Augers to 10 ft
Spoon 10 to 11.5 ft
Augers to 15 ft
0910 Spoon 15 to 16.5 ft - 1st H₂O
Augers to 20 ft
Spoon 20 to 21.5 ft
Augers to 25 ft
0945 Sound hole - water ~ 19 ft G.L., sand 3 ft up augers
Water pulled for return setup below. If - 1 drum
for repairs (75 min DOWN TIME)
1100 Repairs complete - water @ ~ 18 ft G.L. in augers
Run return pit down hole
1140 Driller repairs much of the work in sand (went well ~ 25 ft)
Add another auger & augers to 28 ft - there is only
about 6 in of material in augers!
1150 Install well to ~ 26 ft
Pull augers using chain & hydraulics
Sand cased to 12.5 ft
1220 Add bent. pellets to 10 ft (2 buckets) + then some
more from 5 to 4 ft (1 bucket); cased sand bottom
240 LUNCH

1/7/85
DATE

George Foster
SIGNED

APPROVED

Site NAFB
Boring No. AW 4-1

SHEET 4 OF 4

1320 Grows to surface (3 bags cement, 15# bent. powder)
(clean auger)

1415 Deposit hole

* Well set @ 2 ft (10 ft screen, 2.5 ft S.I.)
* Used 750 gal H₂O (56 gal returned) to make well
* Materials: 18.5 ft screen, 10 ft screen, 3 bucket,
perforated 3 bags cement, 15# bent. powder,
1 steel casing w/ lock

7/7/85
DATE

George Foster
SIGNED

APPROVED

Site Lawrence AFB
 Boring No. NW 4-2 Location Coordinates N
 Hole Size 12 in Slot 0.010 in
 Screen Length 20 ft Mat'l SL 40 PK Filter Materials formation + bagged sand
 Diameter 4 in Grout Type 20/1 cement / bentonite
 Casing Length 6 ft + 2.5 ft + 5 ft Mat'l SL 40 PK Development _____
 Diameter 4 in Static Water Level _____
 Date Start 1/5/85 Finish 1/6/85 Top of Well Elevation _____
 Contractor ESF Driller Law Eng Drill Type 12 in DP, 6 in IP

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked steel casing					Log based on split spoon samples, cuttings, drill rate.
0		SW	Gravelly fine to coarse quartz sand, 20% gravel (to 2 in), well graded, round, 7.5 < R 5/8 (strong brown), non plastic, dense, dry; N.A.B., fluvial	7 13 15	8	1		grout bentonite seal
5		SW	Med to coarse gravelly sand, 25% gravel, well graded, round, 10 < R 7/8 (yellow), non plastic, dense, dry; N.A.B., fluvial	9 16 19	10	2		All contractors are experienced and crackle-free
10		GW	Gravel (to 7 in), 45% fine to coarse sand, well graded, round, 10 < R 7/8 (yellow), non plastic, very dense, wet, N.A.B., fluvial	14 16 19 24 29	8	3		PVC casing bagged sand casing sand 1st H ₂ O near 9.5 ft based on wet spoon sample
15		GW		18 26 37	10	4		12 in borehole PVC screen
						5		joint

Signed [Signature]

K-53

Approved

Site MAFBSHEET 2 OF 4Spring No. MW 4-2Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 1/5/85Finish 1/6/85

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
20		GW	Gravel (to 5 in), 40% fine to coarse sand, well graded, round, 104 R 7/8 (yellow), non plastic, very dense, wet, N.A.B., fluvial	19 26 31	18	6		
25		ECH					ECH, ECH 26 ft	

Signed George Pross

K-54

Approved _____

Site Maxwell AFB
Boring No. MW4-2

SHEET 3 OF 4

- 11/5 1430 Arrive on-site
1450 Begin augering - monitor w. H-NV
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
1525 Auger plug caught on bottom of auger - pull auger
+ free
1530 Resume operations
Back to 7.5 ft w. auger
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
Spoon 20 to 21.5 ft
Auger to 25 ft
1630 Sound hole - ~ 3 ft of sand/gravel inside auger
Secure site for later pull auger up from bottom
1700 Depart site
- 11/6 0630 FSE, Dullin on-site (helping other water)
0700 Pump starting up
0715 Water truck on-site
Measured water inside auger - 9 ft G.L.
Calibrated H-NV; Span at 9.6 = 65 ppm
0730 Take auger back down to 25 ft + sound hole
Still ~ 2 ft of mud in auger
0740 Prepare to set up the hole
0810 Out w. rotary bit
0815 Install well - fell to ~ 26 ft

1/5/85
DATE

[Signature]
SIGNED

APPROVED

Site MAFB

Boring No. M.W. 4-2

SHEET 4 OF 4

0820 Full screen

Sand carried to 6 ft

Add sand to 3.3 ft (2 small bags = 1 lg. bag)

0850 Ream pellets to 2.3 ft (2 buckets)

0920 Grout to surface, clean auger

0930 Different area

* Used 175 gal H₂O to make well (75% water)

* Well set to 20 ft screen, 3.5 ft S (1.)

* Materials - 8.5 ft screen, 20 ft screen, 1 bag sand,
2 buckets pellets, 1 bag cement, 1 bag powder,
1 steel casing w/ Rod

1/6/85
DATE


SIGNED

APPROVED

Site Manner AFBSHEET 1 OF 3Boring No. 1144-3Location Coordinates NHole Size 12 in Slot 0.010 inEScreen Length 20 Mat'l 2.40 PVCFilter Materials formation sandDiameter 4 inGrout Type 20/1 cement / bentoniteCasing Length 4.5 + 2.7 + 5.0 Mat'l 2.40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 1/6/85 Finish 1/6/85

Top of Well Elevation

Contractor FSE Driller L. G. GungDrill Type Horizontal auger12 in 2 P, 4 in I.D.

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample	Sketch of Construction	Remarks
0			4 in PVC slip cap 6 in locked steel casing					Log based on split spoon samples, cutting, drill rate
			Sandy gravel (to 5 in), 40% fine to coarse sand, well graded, round, 10-20 (yellow), non plastic, dense, N.A.B., al. damp, fluvial	8	11	1		grout
			Gravelly fine to m. sand, 40% gravel (to 7 in), well graded, round, 10-20 (yellow), non plastic, dense, N.A.B., al. damp, fluvial	13	10	2		PVC casing
			Gravelly fine to m. sand, 20% gravel (to 2 in), well graded, round, 10-20 (yellow), non plastic, dense, N.A.B., al. damp, fluvial	12	13	3		Contacts approximate + gradation
			Md to co. gravelly sand, 30% gravel (to 1 in), well graded, round, 10-20 (brown-yellow), non plastic, dense, wet, N.A.B., fluvial	10	10	4		al
				12	8	5		joint
				13				12 in borehole
				16				1st H ₂ O near 10.5 ft
								based on water contact in spoon samples
								Measured H ₂ O in auger @ 9.5 ft, G.L.
								coarse sand
								joint
								PVC screen

Signed [Signature]

K-57

Approved

Site MAFBSHEET 2 OF 3Boring No. MA 4-3Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 1/6/85 Finish 1/6/85

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SV	Med to coarse sand, 10% gravel (to 0.5 cm), well graded, round, 104 R 6/8 (brown, yellow), non-plastic, dense, N.T.B., wet, fluvial	16 19 20	1	6		12 in boulder covered sand PVC screen PVC end cap ECW 24.5 ft EOH 25 ft

Signed 

K-58

Approved _____

Site Marwell AFB
Boring No. MW 4-3

SHEET 3 OF 3

0940 Set up on site
0945 Begin casing - monitor w. H-111
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
1010 Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
1040 Spoon 20 to 21.5 ft
Only recovered about an inch of material - drilled out
a sample catcher for the spoon - will see about
getting more after this hole.
1055 Auger to 25 ft - add 3 ft more casing
Rig up rotary bit to clean hole, begin drilling
1100 Withdrawing
1130 Resume drilling (normal truck return)
1155 Pull rotary bit
Sand barrel back up 1 ft
Attempt to install well - fell to 23.7 ft, (i.e.)
Attempt to pull casing - won't come up
Winch casing w. derrick & pull w. hydraulics
1210 Auger comes up - well fell to ~ 24.5 ft
Sand barrel to 3 ft
1230 Run pellets to 2 ft (2 buckets)
1300 Grout to surface
* Used ~ 350 gal H₂O to make well (75% return)
* Well est. @ 24.5 ft (20 ft screen, 2.7 ft S.V.)
* Materials - 7.2 ft casing, 30 ft screen, 3 bags cement,
15# powder, 2 buckets pellets, 1 steel casing w/ foot
1315 Depart site 1/6/85 George [Signature]
DATE SIGNED

APPROVED

Site M.A.F.B. (Marshall)

SHEET 1 OF 5

Boring No. MW 5-1

Location Coordinates N

Hole Size 12 in Slot 0.010 in

E

Screen Length 10 ft Mat'l Sch 40 PVC

Filter Materials Formation + lagged sand

Diameter 4 in

Grout Type 20/1 cement/bentonite

Casing Length 15.4 ft + 2.5 ft S.V. Mat'l Sch 40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 12/13/84 Finish 12/14/84

Top of Well Elevation

Contractor ESE Driller Law Eng

Drill Type Hollow stem auger

12 in OD 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
			PVC slip cap					
			6 in locked steel casing					
0		CL	Sandy clay, 35% fine to c. sand, 7.54R 4/6 (strong brown), al. plastic, soft, damp, N.A.B. flood plain	7 10 14	11"	1		Log based on split spoon samples, cuttings, drill rates
5		SM	Fine sand, 10% silt, 5% clay, mod. gradab, mod. round, 7.54R 5/8 (strong brown), non plastic, loose, damp, N.A.B., flood plain	4 5 4	12"	2		Contacts 4.5, 7.5, 15 ft approximately + gradational
10		SM	Very fine sand/silt mixture (50/50), 7.54R 5/8 (strong brown), non plastic, loose, damp, N.A.B., flood plain (5% muscovite)	4 4 4	18"	3		12 in borehole joint
15		SW	Very fine to red sand, mod. graded, round, 5% clay, 10.4R 5/6 (yellow brown), non plastic, v. loose wet, N.A.B., fluvial	1 2	18"	5		4 in PVC casing
								grout
								bentonite seal
								1st H ₂ O near 15 ft based on wet spoon sample
								12 in borehole filter pack
								4 in PVC screen

Signed

K-60

Approved

Site Maxwell AFB

SHEET 2 OF 5

Boring No. NW 5-1

Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 12/13/84 Finish _____

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
20			Gravel, 50% med. to coarse quartz sand, well graded, mod. round, 104R 6/6 (brownish yellow), non plastic, very dense, N.A.B., wet, fluvial	12				12 in borehole Cased to 20 Ft 4 in PVC screen formation sand (caved) PVC end cap EOW 25.4 Ft EOW 29 Ft
				25				
				25				
25								
30								

Signed George P. [Signature]

K-61

Approved _____

Site Maple A.F.B.
Boring No. NW 5-1

SHEET

3

OF

5

12/13/20 Set up on-site
Calibrate H-NV
- 65 ppm @ 9.8 span setting
- Zero OK
Rig: Motor B-53
Pump: 2-1/2 monopump
Casing: 10 ft threaded 4 in Sch 40 PVC
Screen: 1 threaded 4 in Sch 40 PVC, 0.010 in slots
Spoon: one, 18 in X 1.75 in, two 24 in X 1.75 in (I.D.)
Hammer: 140 lb
Fall: 30 in

1315 Begin auguring
Down to 02.5 ft
Spoon 2.5 to 4.0 ft
Auger to 5.0 ft
Spoon 5.0 to 6.5 ft
1340 Auger to 7.5 ft
Spoon 7.5 to 9.0 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
1400 Auger to 15 ft
Spoon 15 to 16.5 ft
1st H₂O near 15 ft
Auger to 20 ft
Spoon 20 to 21.5 ft
1430 Auger to 25 ft
1440 Run for supplies (screen & pipe)
1450 Supplies here (10 min DOWNTIME)
Pulling out the auger plug
Sand holed 8 ft inside auger
1500 Rigging up screen box to wash out auger
Run inside auger
1545 Water run

12/13/84
DATE


5255

APPROVED

Site NAFB
Boring No. NW 5-1

SHEET

4 OF 5

1600 Water truck returns - someone took outlet
hose from pump

Leave to call city water dept.

Tap into fire hydrant on Foster Rd.

1650 Full water truck!

Resume rotary drilling to flush out augers

Comment: Type I Portland, Blue Circle, Inc., 94 # bags

Sand: Silica (sand blasting), Crosby-Cornucopia

Sand & Gravel, Selma, Ala., 50 # bags

1830 Plan to overdrill (auger) to 30 ft tomorrow - there's
still 2 ft of sand & gravel inside augers
Depart site

12/14

0630 ESE, Bullen on-site

Auger to 30 ft, then lifting auger up

Just 0.5 ft of sand inside augers

0700 Install well

Water run

0740 Water truck returns

Pull well + lift augers w. hydraulics to about 26 ft

0815 Reinstall well + pull augers

Screen length is 10.1 ft with end cap (w/o the)

Rin length is 9.9 ft, each section (the)

0845 Well set @ 25.4 ft w. 2.5 ft S.U. (screen, 15.4 ft, 25.4 ft)

Cancel to 20 ft (top of gravel/sand?)

0930 Sand to 12 ft (6 bags)

0945 Bentonite pellets, Peltonite by Rotamix, Inc., 5 gal.
buckets, to 10 ft (2 buckets) (50 # buckets)

12/14/84
DATE

George B. B.
SIGNED

APPROVED

Site 11A FB
Boring No. MW 5-1

SHEET 5 OF 5

12/14
cont

1020 Grout to surface (4 bags cement, 20# bent. powder)
1045 Grouting complete
Cleaning equipment, flushing pump lines
1200 Descon complete
Depart site
Will pull piezometer + grout later

- * Used ~ 400 gal. H₂O to make well (75% recovery)
- * Well depth 25.4 ft, 10 ft screen, 2.5 ft S.U.
- * Materials - 17.9 ft riser, 10 ft screen, 6 bags sand, 2 buckets bent. pellets, 4 bags cement, 20 lb bent. powder, 1 steel casing w/locks

12/14/84
DATE

George Ross
SIGNED

APPROVED

Site Maxwell AFB
 Boring No. 11W-5-2 Location Coordinates N
 Hole Size 12 in Slot 0.010 in E
 Screen Length 15 ft Mat'l Sch 40 PVC Filter Materials formation + lagged sand
 Diameter 4 in Grout Type 201 cement, bentonite
 Casing Length 7.5 ft + 2.5 ft SU Mat'l Sch 40 PVC Development
 Diameter 4 in Static Water Level
 Date Start 12/14/84 Finish 12/15/84 Top of Well Elevation
 Contractor ESF Driller Law Eng Drill Type Hollow Stem Auger
12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			PVC dip cap 6 in locked steel casing					Log based on spiral spoon samples, cuttings, drill rate
0								
		SC	clayey sand, 30% clay, 7.54R4/4 (dk, yellow brown) to 104R7/1 (light gray), sl. plastic, soft, damp, N.A.B., flood plain	2 3 4	8'	1		grout Contact @ 4.5 ft 9.0 ft approximately bentonite seal Contact @ 11 ft sharp
5		CH	Inorganic clay, 104R5/8 (yellow brown) to 547/1 (lt. gray), very plastic, red. concret., damp, mottled, flood plain	3 5 7	13	2		12 in borehole PVC casing grout PVC screen lagged sand
10		SC	Interbedded clayey sand + clay, 546/1 (gray), sl. to v. plastic, dense + stiff, damp, flood plain	4 6 7	10	3		
		SW	Fine to coarse granitic sand, well graded, subang., 54 8/1 (white), non plastic, loose, wet, fluvial	10 20	18	4		1st H ₂ O @ 11 ft based on wet sand in sampler
15		SC	Fine clayey sand lens, 7.54R5/8, sl. plastic, wet	6 8 7	14	5		Contact @ 15.5 ft sharp
		SW	v. fine to med. sand, 5% micaceous, well graded, round, 2.547/14 (yellow), non plastic, loose, wet, fluvial					caved sand

George R. ...
 Signed

K-65

Approved

Site NAFBSHEET 2 OF 4Boring No. MWS-2Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/14/84 Finish 12/15/84

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to coarse quartz sand, 1% muscovite, well graded, mod. round, 104R 1/16 (yellow), non plastic, very loose, wet, N.A.B. fluvial	12	18	6, 7		12 in borehole gravel sand PVC screen PVC end cap
	6	EXT						

Signed George P. [Signature]

K-66

Approved _____

Site Maxwell AFB
Boring No. NW 5-2

SHEET 3 OF 4

12/14 1200 Set up on-site
Pull PZ 5-2
Move 10 ft to the south for NW 5-2
1300 Lunch
1400 Prepare to start
1440 Auger to 2.5 ft
Spoon 2.5 to 4.0 ft
Auger to 5.0 ft
Spoon 5 to 6.5 ft
1500 H-NV calibrated
Span @ 9.8 = 65 ppm
Zero OK
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
1520 1st sand + water @ 11 ft - no (O) reading on H-NV
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
1540 Spoon 20 to 21.5 ft
Water level in auger @ 8.9 ft, G.L.
1600 Drive drill to 25 ft (plan to stop well @ 22 ft) to
attempt to remove 7 ft of sand in auger
Mix up & auger down several times - no luck
Fill auger w. water & repeat - no luck
1650 Pull auger to 20 ft, fill w. water, & leave overnight
12/15 0600 Driller arrive
0630 ESE arrive
Digger come for load of sand
Still 2 ft of sand in auger
0645 Rig up rotary bit to clean out auger

12/14/84
DATE

George Post
SIGNED

APPROVED

Site Maxwell AFB

Boring No. MW 5-2

SHEET

4 OF 4

12/15
cont

0700 Out of water (found in town for sand)

DOWNTIME - 2 hours

0900 Truck w. water & sand returns

Recommence filling - clearing hole in rotary bit

0940 Hole cleared out - 9 ft.

Pipe run - 20 min DOWNTIME

1000 Pipe's here - clean w. water & brushes

1005 Install well to 22.5 ft (screen 7.5 to 22.5 ft)

1050 Augers pulled to 10 ft

Hole cased to 12 ft

Add sand (working into hole w. water)

1050 Water run

1130 Water truck back

Resume sanding

1200 Sand to 4 ft (6 bags, from 12 to 4 ft)

Bentonite pellets to 2.5 ft (1 bucket)

Grows to surface

* Used 225 gal to make well (water?) (75% 1200 gal)

* Well set @ 22.5 ft, 15 ft screen, 2.5 ft S.O.

* Materials - 25.0 ft sides, 15 ft screen,
6 bags sand, 1 bucket bent. pellets

1230 Clearing augers

1245 Depart site - move to S-4

Calibrate H-MU

Spence 9.8 - 65 ppm

Zinc, OK

12/15/84
DATE

George Post
SIGNED

APPROVED

SHEET 1 OF 9

Site Maxwell AFB

Boring No. 11W5-3

Hole Size 12 in Slot 0.010 in

Screen Length 2018 Mat'l Sch 40 PVC

Diameter 4 in

Casing Length $8' + 25' = 33'$ Mat' 1 $5' + 40' = 45'$

Diameter 4 1/2

Date Start 11/10/85 Finish 11/11/85

Contractor ESE Driller L. L. Long

Location Coordinates N

E _____

Filter Materials formation & sieved sand

Grout Type 20/1 cement / L. Water

Development _____

Static Water Level _____

Top of Well Elevation _____

Drill Type Hollow Stem Auger

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Flow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	0		PVC slip cap 6 in locked steel casing					Log based on spoon samples, cuttings, drill rate
	CL		Silty clay, 20% silt, 7.54R 5/8 (strong brown) to 547/1 (lt. gray), mod plastic, soft, mottled, moist, flood plain	5	6	1	G.L. grout	PVC casing
5	CL		Sandy, silty micaceous clay, 20% f. sand, 10% silt, 5% muscovite, 546/1 (gray) w. some 7.54R 5/8 (strong brown), mod. plastic, soft, N.A.B., moist, flood plain	7 21 3 4 5	12	2		A piece of wood was wedged in the foot of the spoon (sample 1) Lentinite seal
10	CL		Silty, sandy micaceous clay, 20% silt, 10% fine sand, 5% muscovite, 2% dk green nodules, 546/1 (gray), mod. plastic, v. soft, N.A.B., wet, flood plain	2 1 3	6	3		12 inch ribbed lagged sand joint
15	SM		Silty, at clayey f. to med sand well graded, 20% silt, 5% clay, 5% muscovite, 7.54R 5/8 (strong brown) to 2.54 7/4 (pale yellow), non plastic, loose, colors alternate, wet, flood plain	4 5 6	10 1	4	PVC screen	1st H ₂ O based on water level in augers near 12 ft (probably shallower) Water later measured @ 10 ft in augers
							joint	All contacts approximate & gradational

Signed George Foster

K-69

Approved

Site MAFB SHEET 2 OF 4
 Boring No. 165-3 Location Coordinates N
 Hole Size _____ Slot _____ E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 1/10/85 Finish 1/11/85 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	U. fine to coarse sand, 5% silt, 5% muscovite, 5% black grain, well graded, 104R 7/8 (yellow), non plastic, loose, wet, N.A.B. fluid	2 3 2	18	6		logged sand coarse sand 12 in loose hole Counter at 23 ft approximate and graduated PVC screen PVC end cap EOW 28 ft EOW 29 ft
	25	SW to SC	U. fine to coarse sand, 5% silt, 5% clay, 5% black grain, 5% muscovite, well graded, 104R 5/8 (yellow brown), non plastic, loose, wet, N.A.B. fluid	3 5 6	18	7		
	30	FOH						

Signed

K-70

Approved

Site Marwell AFB
Boring No. 11W 5-3

SHEET 3 OF 4

1/9 Rig stuck, moving onto hole — wait for dryer in AM

1/10 0800 Dryer pulls on rig
Rig moves onto hole along path set by dryer

0830 Worker truck stuck & pulled out by dryer

0845 Set up rig
Calibrate 4-111; 65 ppm @ Span = 7.31
Starting to rain — may never get rig out!

0900 Auger to 2.5 ft
Spoon 2.5 to 4 ft

Auger to 5 ft
Spoon 5 to 6.5 ft

Auger to 7.5 ft

Spoon 7.5 to 9 ft

Auger to 10 ft

0935 Spoon 10 to 11.5 ft

Auger to 15 ft

Spoon 15 to 16.5 ft

Auger to 20 ft

1010 Spoon 20 to 21.5 ft

Would like to put 15 ft of screen (from 8 to 23 ft) but
cutter is out of 5 ft section; plan to set well @
28 ft (w. 20 ft of screen)

1015 Sand moved up auger — can't get auger plug
back down

Auger to 25 ft

1035 Spoon 25 to 26.5 ft

Auger to 29 ft — ~10 ft inside auger

1100 Driller lets to see about supplies — we're close out of
PVC, wire (casing)

1430 Can't get any more threaded PVC until tomorrow afternoon;
will attempt to heat-weld a piece of 10 ft unthreaded river
to the 20 ft of threaded screen (with a slip coupling)

1445 Rig up to wheel on hole w. rotary bit
Rig has stopped

1/10/85
DATE

George [Signature]
SIGNED

APPROVED

Site MAFB
Boring No. MWS-3

SHEET 4 OF 4

1110 500 H₂O welling did not work
Driller gone to Birmingham for pipe, will
return in AM (~1100)

1111 1100 Driller, FSE on-site (w. threaded casing!)

1115 Wash out hole again in rotary bit

1125 Well set in auger

Begin pulling screen

Well fell to 29 ft, pull up to 28 ft

1150 Sand caught to 19 ft

Add sand to 5 ft (14 m bags = 7 q. bags)

1215 Pellets to 4 ft (1 bucket)

1245 Grout to surface

* Used 500 gal. H₂O to make well (75% return)

* Well set @ 28 ft (screen 8 to 28, 2.5 ft S.O.)

* Materials = 10.5 ft riser, 20 ft screen, 14 small
bags sand, 1 bucket pellets, 1 bag cement,
1 lb. bent. powder, 1 steel casing w/lock

We will probably have to be pulled off-site by
the boys

11/1/85
DATE

[Signature]
SIGNED

APPROVED

SHEET 1 OF 4

Site Maxwell AFB

Boring No. MW 5-4

Location Coordinates N

Hole Size 12 in

Slot 0.010 in

E

Screen Length 15

Mat'l Sch 40 PVC

Filter Materials formation + bagged sand

Diameter 4 in

Grout Type 20M cement / bentonite

Casing Length 10.5 ft + 2.4 ft SW

Mat'l Sch 40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 12/15/84

Finish 12/16/84

Top of Well Elevation

Contractor ESR

Driller Law Eng.

Drill Type Hollow Stem Auger

12 in O.D., 4 in I.D.

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
			PVC dip top					Log based on split spoon samples, cuttings, drill rate
			6 in steel locked casing					
0			Silly clay, 25% silt, 104R 7/1 (lt gray) to 104R 5/8 (yel. brown), mod. plastic, stiff, dry, N.A.B., mottled colors, flood plain	8	9	1		
		CL	Fine to coarse sand, well sorted, non plastic, loose, med, fluvial	7	14	2		Actual thickness of unit marked 5.5 to 6.5 ft is unknown but no more than 1 ft
5		SW	Organic clay, 10% silt, 104R 7/1 (lt gray) to 104R 5/8 (yel. brown), U. plastic, stiff, sl. lump, N.A.B., mottled, flood plain (moist below 8.5 ft)	4	14	3		Perched H ₂ O between 4.5 + 5.5 ft
		CH	Organic clay, 10% silt, 5% muscovite, 545/1 (gray) to 104R 6/6 (brown. yellow), U. plastic, stiff, no N.A.B., mottled, flood plain	3	16	4		Increase in drill rate @ ~ 12.5 ft
10		CH	In reddish v. fine to fine micaceous sand and clays micaceous silt, 545/1 (gray), non to sl. plastic, loose, med, flood plain	1	14	5		True water table near 12 ft
		SM						PVC screen joint
		SW						cased sand

Signed George Jones

K-73

Approved

SHEET 2 OF 4

Site Alameda AFB

Boring No. MW 5-4

Hole Size _____ Slot _____

Screen Length _____ Mat'l _____

Diameter _____

Casing Length _____ Mat'l _____

Diameter _____

Date Start 12/15/84 Finish 12/16

Contractor _____ Driller _____

Location Coordinates N _____

E _____

Filter Materials _____

Grout Type _____

Development _____

Static Water Level _____

Top of Well Elevation _____

Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery %	Box or Sample #	Sketch of Construction	Remarks
20	20	SW	Fine to coarse sand, well graded, round, 104R 6/8 (brown, yellow), non plastic, loose, U.A.B., wet, fluvial	2 2 2	9	6		12 in borehole cased sand PVC screen PVC end cap EOW 25.5 Ft EOW 29 Ft
25	25							
30	30	EOB						

Signed George V. [Signature]

K-74

Approved _____

Site Manned AFB
Boring No. NW 5-4

SHEET 3 OF 4

- 12/15 1300 Arrive + set up on-site
Pull + group piezometer (PZ 5-4) (1 bag cement)
1330 LUNCH
1430 Begin digging - monitor w. H-NV
Augers to 2.5 ft
Spoons 2.5 to 4.0 ft
Augers to 5 ft
Spoons 5 to 6.5 ft
Augers to 7.5 ft
Spoons 7.5 to 9 ft
Augers to 10 ft
1515 Spoons 10 to 11.5 ft
Augers to 15 ft
Spoons 15 to 16.5 ft
Augers to 20 ft
1600 Spoons 20 to 21.5 ft
Augers to 29 ft (overbilled 4 ft to aid in setting well to 25 ft)
Sand heaved 10 ft up inside augers!
1630 Depart site + bring off cement, etc. near Site T
- 12/16 0630 ESE, Bullen arrive on-site
Clean augers w. rotary bit
0725 Water run
0800 Water time returns
Resume wash drilling - 3 more ft of sand to remove!
0820 Calibrate H-NV
Span @ 9.5 = 65 ppm
Zero, OK
0900 Install well, pull augers
0915 Cased to 17 ft - begin adding sand
Sand to 7 ft (7 bags)
1000 Pellets to 5.5 ft (1.5 buckets)

12/15/84
DATE

George Foster
SIGNED

APPROVED

Site Maxwell AFB
Boring No. MW 5-4

SHEET 4 OF 4

12/16/84 1000 Mining spent
1035 Ground to surface

- * Well placed @ 25.5 ft, 15 ft screen, 2.4 ft S.O.
- * Used 300 gal H_2O to make well (75% return)
- * Materials - 13 ft run, 15 ft screen, 7 bag sand, 1 1/2 bucket pellets, 4 replacement, 20 lb lime powder, 1 steel casing w/ lock

1035 Cleaning auger
Cleaning site

1100 Depart site - move to Site I

12-16/84 George Rose
DATE SIGNED

APPROVED

Site Unamed AFB

SHEET OF

Boring No. 11W6-1

Location Coordinates N E

Hole Size 12 in Slot 1" O.D. in

Screen Length 15 ft Mat'l Sch 40 PVC

Filter Materials formation + layered sand

Diameter 4 in

Grout Type 20/1 coarse / bentonite

Casing Length 24 ft + 25 ft SU Mat'l Sch 40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 1/9/85 Finish 1/9/85

Top of Well Elevation

Contractor FSE Driller Law, C.

Drill Type Hollow Stem Auger 12 in O.D., 6 in I.D.

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	0		4 in PVC slip cap					Log based on split spoon samples, cuttings, drill rate
			6 in locked steel casing					
	0	CL	Silty clay, 15% silt, 5% "organic" nodules, 104R5/8 (yellow brown) to 547/1 (lt. gray), mod. plastic, med. consist., damp, mottled, flood plain	57	13	1		PVC casing
	5			9				grout
				11	15	2		joint
	5		Silty clay, 20% silt, 7.54R 5/8 (strong brown) to 547/1 (lt. gray), mod. plastic, stiff, damp, mottled, flood plain	15				Contacts approximate and very gradational
		CL		7	18	3, 4		
	10			16				12 in lock hole
				17				
				8	18	5, 6		
				13				
				20				
		CL	Silty clay, 30% silt, 10% very fine sand, 7.54R 5/8 (strong brown) to 547/1 (lt. gray), mod. plastic, stiff, damp, mottled, flood plain					joint
	15			8	14	7, 8		
				10				
		CL	S.l. silty clay, 10% silt, 547/1 (lt. gray), mod. plastic, stiff, damp, N.+B., flood plain	16				bentonite seal

George Ford
Signed

K-77

Approved

Site MAFB SHEET _____ OF _____
 Boring No. 11W6-1 Location Coordinates N _____
 Hole Size _____ Slot _____ E _____
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 1/9/85 Finish 1/9/85 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Eleva- tion (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	CL	Silty, sandy clay, 20% silt, 15% very fine sand, 7.54R 5/8 (strong brown) to 54 7/1 (lt. gray), mod plastic, stiff, damp, mottled, flood plain	4 10 15	16	9, 10		Leontom's lead 12 in. loose hole bagged sand PVC casing joint
	25	CL to ML	Interbedded silty clay and clayey, sandy silt, 10% mica, 5% organic matter, 54 7/1 to 7/2 (lt. gray), non to mod. plastic, stiff, very damp, flood- plain	8 13 14	18	11, 12		1st H ₂ O near 27 ft level on water measure inside auger joint
	30	SM	Silty, micaceous fine sand, 15% silt, 10% mica, 104R 7/6 (yellow) with some lenses 7.54R 5/8 (strong brown), non plastic, dense, wet, U.A.B., fluvial	14 18 37	18	13, 14		contact at 31 ft sharp; all other approx- imate & grada- tional
	35	SW	Gravelly fine to coarse sand, 20% gravel (to 2 cm), well graded, round, 104R 7/6 (yellow), non plastic, dense, wet, U.A.B., fluvial	1 2 3	18	15, 16		PVC screen caved sand

George J. [Signature]

K-78

Approved

Site MAYB SHEET _____ OF _____

Boring No. MW 6-1 Location Coordinates N _____

Hole Size _____ Slot _____ E _____

Screen Length _____ Mat'l _____ Filter Materials _____


Diameter _____ Grout Type _____

Casing Length _____ Mat'l _____ Development _____

Diameter _____ Static Water Level _____

Date Start 1/9/85 Finish 1/11/85 Top of Well Elevation _____

Contractor _____ Driller _____ Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	40	SW	Gravelly fine to coarse sand, 30% gravel (to 1.5 in), well graded, round, 104 R 7/8 (yellow), non plastic, loose, wet, N.A.B., fluvial					PVC screen PVC anchor Cased sand 12 in loose hole
	45	EDH						

Signed [Signature]

K-79

Approved _____

Site Maxwell AFB

Boring No. 1142 (6-1)

SHEET _____ OF _____

1200 Set up on-site

1230 Begin augering - monitor w H-NV

Auger to 2.5 ft

Spoon 2.5 to 4 ft

Auger to 5 ft

Spoon 5 to 6.5 ft

Auger to 7.5 ft

Spoon 7.5 to 9 ft

Auger to 10 ft

Spoon 10 to 11.5 ft

Auger to 15 ft

1255 Spoon 15 to 16.5 ft

Auger to 20 ft

Spoon 20 to 21.5 ft

Auger to 25 ft

Spoon 25 to 26.5 ft

Auger to 30 ft

Spoon 30 to 31.5 ft

Auger to 35 ft

1350 Spoon 35 to 36.5 ft

Auger to 40 ft (adv. ft sand in auger)

1410 Auger to 43 ft + attempt to set well

Could not pull auger w/o well

Pull well out, lift auger, auger back down to 43 ft

Install well

Pull auger - coming up w/o well!

Well placed @ 40 ft (15 ft screen, 2.5 ft S.V.)

Sand cased to 27 ft


Add sand to 20 ft (10 sm bags = 5 lg bags)

1555 Bens. pellets to 107 ft (3 buckets)

1630 - Ground to surface - clean auger (4 bags cement; 20# probe)

1645 Depart site

1/9/85
DATE


SIGNED

APPROVED

Site MAFB
Boring No. NW6-1

SHEET _____ OF _____

- * Well set @ 39.6 ft (15 ft screen, 2.5 ft S.V.)
- * Used 25 gal. H₂O to make well (0% recovery)
- * Materials: 27.5 ft casing, 15 ft screen, 10 small bags sand (= 5 lb. bags), 3 bucket pellets, 4 bags cement, 20# lb. powder, 1 steel casing w/ lock

1/9/85
DATE

George [Signature]
SIGNED

APPROVED

Site Manassas AFB

SHEET _____ OF _____

Boring No. NW 6-2Location Coordinates N _____Hole Size 12 in Slot 0.010 inE _____Screen Length 15 ft Mat'l Sch 40 PVCFilter Materials formation + washed sandDiameter 4 inGrout Type 20/1 cement / bentoniteCasing Length 24.2 + 25 ft Mat'l Sch 40 PVC


Development _____

Diameter 4 in

Static Water Level _____

Date Start 1/9/85 Finish 1/9/85

Top of Well Elevation _____

Contractor ESF Driller Law EngDrill Type Hollow stem auger12 in OD, 6 in ID

Signed

K-82

Approved

Site MAFB

SHEET _____ OF _____

Boring No. 1146-2Location Coordinates N _____

Hole Size _____ Slot _____

E _____

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____

Date Start 1/9/85Finish 1/9/85

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
20	CL		Silty clay, 30% silt, 7.542 5/8 (silts brown), to 54711 (Lo. gray), mod plastic, stiff, damp, mottled, flood- plain	10 12 14	18	8, 9		centimeter seal bagged sand PVC casing
25	SM		Silty, micaceous fine sand, 20% silt, 10% muscovite, 5% black grains, 54711 (Lt. gray), non plastic, loose, occasional clay stringers, moist, flood plain	12 14 17	11	10, 11		All contents approximate and gradational PVC screen
30	SW		Fine to coarse gravelly sand, 20% gravel (to 1.5 in) 5% f. black grains, well graded, round, 10427/8 (yellow), non plastic, loose, N.A.B., wet, flood	7 12 22	12	12, 13		joint caved sand 12 in borehole
35	SW		Fine to coarse gravelly sand, 30% gravel (to 2 in), 3% black grains, well graded, round, 10427/8 (yellow), non plastic, loose, N.A.B., wet, flood	1 2 4	12	14		

Signed George J. [Signature]

K-83

Approved _____

SHEET OF

Boring No. 11416-2

Location Coordinates N _____

Hole Size	Slot
1/8"	1/8"
3/16"	3/16"
1/4"	1/4"
5/16"	5/16"
3/8"	3/8"
7/16"	7/16"
1/2"	1/2"
9/16"	9/16"
5/8"	5/8"
3/4"	3/4"
7/8"	7/8"
1"	1"

E *Journal of the American Academy of Child and Adolescent Psychiatry* 1999;38:1031-1036

Screen Length **Mat'l**

Filter Materials

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development

Diameter

Static Water Level _____

Date Start 1/9/85 Finish 1/9/85

Top of Well Elevation

Contractor _____ Driller _____

Drill Type

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
40	SW		Fine to coarse gravelly sand, 30% gravel (to 2cm) 3% black grains, well graded, round, 104R718 (yellow), non plastic, loose, N.A.B., wet, fluvial					

Signed *Chengita*

K-84

Approved

Site Manuel AFB
Boring No. RLW 6-2

SHEET _____ OF _____

0730 Set up on-site
0740 Calibrate H-NU, 65 ppm @ Spm = 7.32
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
Spoon 20 to 21.5 ft
0830 Auger to 25 ft
Spoon 25 to 26.5 ft
Auger to 30 ft
Spoon 30 to 31.5 ft
Auger to 35 ft
Spoon 35 to 36.5 ft
0905 Auger to 44 ft (overfilled 4 ft laterally)
0910 Install well (see fr. of sand in augers but wire
going to top is 11C well set @ ~ 38 ft)
0915 Begin pulling augers (w. chain + hydraulics)
will look to ~ 39.7 ft, 0.3 ft short of desired depth
but quite acceptable!
Continue pulling augers
Sand cased to 20 ft
Add sand to 20 ft (12 in. bags = 6 lig. over)
0945 Bore. pellets to 17 ft (3 Buckets)
1015 Grout to surface
1045 Down site

1/9/85
DATE

George [Signature]
SIGNED

APPROVED

Site MAFB
Boring No. MWB-2

SHEET _____ OF _____

- * Well set @ 39.7 ft (15 ft screen, 2.5 ft S.V.)
- * Used Ogal H₂O to make well
- * Materials - 27.5 ft casing, 15 ft screen,
12 in. large sand (= 6 lb. bag), 3 1/2 inch pellets,
2 large cement, 15# bent. powder, 1 steel casing
w/ hook

1/9/85
DATE

[Signature]
SIGNED

APPROVED

Site Maxwell GFBSHEET 1 OF 5Spring No. MW 6-3Location Coordinates NHole Size 12 in Slot 0.010 inEScreen Length 15 ft Mat'ls 1.5 lb 40 PVCFilter Materials formation + bagged sandDiameter 4 inGrout Type 20/10 cement / bentoniteCasing Length 25 ft + 2.5 ft SU Mat'ls 1.5 lb 40 PVC


Development

Diameter 4 in

Static Water Level

Date Start 1/7/85 Finish 1/8/85

Top of Well Elevation

Contractor ESE Driller L. W. EngDrill Type Hollow Stem Auger12 in OD, 6 in ID

Signed

K-87

Approved

SHEET 2 OF 5

Site NAFB
 Boring No. MW 6-3 Location Coordinates N
 Hole Size 12 in Slot 0.010 in E
 Screen Length Mat'l SCH 40 PVC Filter Materials _____
 Diameter 4 in Grout Type _____
 Casing Length Mat'l SCH 40 PVC Development _____
 Diameter 4 in Static Water Level _____
 Date Start 11/7/85 Finish 11/8/85 Top of Well Elevation _____
 Contractor ESF Driller Law Eng. Drill Type Follow Stem Auger


Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
20	CL		Silty inorganic clay, 25% silt, 547/1 (lt. gray) to 104R 516 (yellow. brown), 5% organic matter, mod. plastic, stiff, damp, mottled, flood plain	13 18 26	18	7 8		Log closed on split spoon samples, cuttings, drill rate
25	ML		Clayey silt, 25% clay, 10% mica, 547/1 (lt. gray), 2% organic matter, st. plastic, stiff, moist, flood plain	7 10 14	19	9 10		PVC casing lagged sand 12 in borehole joint PVC screen
30	SW		Fine to coarse sand, 10% black grains, well graded, 2.547/4 (pale yellow), non plastic, dense, wet, fluvial	12 32 42	18	11 12		1st H ₂ O near 27 ft based on water level in augers Contact @ 30.4 ft sharp caved sand
35	SW		Gravelly fine to coarse sand, 25% gravel (to 2 in), well graded, round, 104R 718 (yellow), non plastic, v. dense, wet, N.A.B., fluvial	5 12 37	18	13		

Signed _____

K-88

Approved _____

Site MAFB
 Boring No. MW 6-3 Location Coordinates N
 Hole Size _____ Slot _____ E
 Screen Length _____ Mat'l _____ Filter Materials _____
 Diameter _____ Grout Type _____
 Casing Length _____ Mat'l _____ Development _____
 Diameter _____ Static Water Level _____
 Date Start 11/7/85 Finish 11/8/85 Top of Well Elevation _____
 Contractor _____ Driller _____ Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	40		Gravelly fine to coarse sand, 25% gravel (to 2 in), well graded, round, 2.54 7/6 (yellow), non-plastic, v. loose, wet, N.A.B. fluid					PVC screen PVC end caps 12 in borehole gravel sand EOW 40 ft
	45	EC#					EOW 44 ft	

George Doster
 Signed

K-89

Approved _____

Site Maxwell AFB
Boring No. MW 6-3

SHEET

4 OF 5

- 117 1430 Set up on-site
1445 Begin auguring - monitor with NU
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
1530 Spoon 20 to 21.5 ft
Auger to 25 ft
1545 Spoon 25 to 26.5 ft
1630 Auger to 30 ft
Spoon 30 to 31.5 ft
Auger to 35 ft
Spoon 35 to 36.5 ft
Water measured @ 27.5 ft G.L.
1700 Overdrilled to ~44 ft pulled up to 40 ft - 4 ft of
sand leaked inside auger
Repair motor - returning and in A.M.
118 0730 Arrive on-site
Water in auger @ 27.2 ft, G.L.
0755 Auger to 44 ft - only 2 ft of sand in auger (2 ft pulled out!)
0805 Set well to ~42 ft; will pull up to 40 after
pulling auger several ft
0810 Pulling auger w. chain / hydraulics
Well pulled up to 40 ft
Pull rest of auger (Continue!)
0835 Hole came to 39 ft
4 ft sand @ 20 ft (13 small bags = 6.5 bag (avg))

11/7/85
DATE

George [Signature]
SIGNED

APPROVED

Site MAFB

Boring No. MW 6-3

SHEET

OF

0900 Bentonite pellets to 110 ft (3 buckets)

Pull auger all the way out

0935 Grout to surface (3 bags cement, 15# bent. powder)

1030 Clean auger

Calibrate SH-NU; 65 ppm @ Span 9.9

1040 Deposit site

* 10 gal. O. gel H₂O to make well

* Well set @ 40 ft (15 ft screen, 2.5 ft S.U.)

* Materials - 27.5 ft mesh, 15 ft screen, 3 bags cement,
15# bent. powder, 3 buckets pellets, 13 small bags
sand (= 6.5 lb. bags), 10 gal casing w/ lead

1/8/85
DATE

George Kest
SIGNED

APPROVED

Site Maxwell FFBSHEET 1 OF 4Boring No. MW 7-1Location Coordinates NHole Size 12 in Slot 0.010 inE Screen Length 10 ft Mat'l Sub 40 PVCFilter Materials formation + bagged sandDiameter 4 inGrout Type 20/1 cement / bentoniteCasing Length 14.3 ft + 1 ft Mat'l Sub 40 PVCDevelopment Diameter 4 inStatic Water Level Date Start 1/4/85 Finish 1/4/84Top of Well Elevation Contractor ESB Driller Low EngDrill Type Hollow Stem Auger12 in OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip cap 6 in locked steel casing					Log based on split spoon samples, cutting, drill notes
0		SC	Clayey, silty fine sand, 20% clay, 20% silt, 2.54 R 4/8 (red) to 10.4 R 6/8 (brown, yellow), sil. plastic, dense, dry, mottled colors, flood plain (5% muscovite)	9	18	1		
				16	20	2		
5		SM	Silty, clayey fine sand, 20% silt, 15% clay, 2.54 R 4/8 (red) to 10.4 R 6/8 (brown, yellow), sil. plastic, dense, damp, mottled, flood plain (5% muscovite)	6	16	3		
				10	11	4		
		SM	Silty, clayey very fine sand, 35% silt, 10% clay, 10.4 R 6/8 (brown, yellow) to 5.4 7/2 (lt. gray), sil. plastic, dense, damp, mottled, flood plain (7% muscovite)	6	16	5		
10		SM	Silty, clayey fine sand, 10% silt, 10% clay, 10.4 R 6/8 (brown, yellow), non to sil. plastic, med. consist, v. damp, N.A.B., flood plain (7% muscovite)	4	13	6		
		SW	Interbedded fine to coarse sand and micaceous clay, 5.4 7/2 (lt. gray) to 7.5 4 R 6/8 (red, yellow) non to very plastic, soft, wet, mottled slightly, flood plain	2	18	6		
15		CH		3	4			

Signed

R-92

Approved

Site MAFBSHEET 2 OF 4Spring No. NW 7-1Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____

Static Water Level _____


Date Start 1/4/85 Finish 1/4/85

Top of Well Elevation _____

Contractor _____

Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	% Recovery	Box or Sample #	Sketch of Construction	Remarks
20	SW		Very fine to med micaceous quartz sand, 20% micaceous well graded, med sand, 10% 7/8 yellow, non plastic, loose, wet, N.A.B., fluvial	236	18	7, 6		12 in Corshole bagged sand PVC screen coarse sand PVC end cap EW 24.3 ft EDH 25 ft
25	SW							
25	EOH							

Signed George P. K-93

K-93

Approved _____

Site Maxwell AFB
Boring No. M427-1

SHEET 3 OF 4

0900 Move onto hole. C cleaned w. flu. carbon, airport
manure
Calcrete H-NV; 65 ppm @ span = 9.8
0915 Waiting for water truck so auger can be cleaned
prior to use.
0935 Water truck returns
Cleaning auger
1000 Begin augering - monitor w. H-NV
Auger to 2.5 ft
Spdon 2.5 to 4 ft
Auger to 5 ft
Spdon 5 to 6.5 ft
Auger to 7.5 ft
Spdon 7.5 to 9 ft
Auger to 10 ft
Spdon 10 to 11.5 ft
Auger to 15 ft
Spdon 15 to 16.5 ft
Auger to 20 ft
Spdon 20 to 21.5 ft
1105 Auger to 25 ft
1120 Sound hole - only 1 ft of seal in auger
Materials run
1205 Driller returns w. pipe, sand, etc (45 min DOWNTIME)
Water measured inside auger @ ~15.5 ft, G.L.
1215 Install well to ~25 ft (10 ft sealed)
Pull auger, well pulled up to ~24.5 ft
Sand sealed to 20 ft
Add sand from 20 to 10 ft (8 small bags)
1255 Bent pellets to 7.6 ft (2 buckets)
~~to surface~~ 2 UNCH
1340 Mixing grout (3 1/2 bags cement, 20# bent powder)
1400 Grout to surface

1/4/85
DATE

Deane R. [Signature]
SIGNED

APPROVED

Site NAFB
Boring No. NW 7-1

SHEET 4 OF 4

1400 PZ 7-1 removed & grouted
Will clean auger after moving off hole
1420 Depart site.

- * 0 gal H_2O used to make well
- * Well set @ 24.3 ft (10 ft screen, 1.0 ft S.V.)
(supplies manager requested no more than 1 ft stick up)
- * Materials - 15.3 ft casing, 10 ft casing, 3 1/2 bag cement, 20 # bent. powder, 2 buckets pellets, 8 small bags and 4 lg. bags, 1 steel casing w/lock

Will spend the rest of the afternoon setting up on NW 3-2, collecting supplies from stores for the weekend, conducting inventory, locating protective post for wells, etc.

1/4/85
DATE

George [Signature]
SIGNED

APPROVED

Site Maxwell AFBSHEET 1 OF 3Boring No. MW 7-2Location Coordinates NHole Size 12 inSlot 0.010 inEScreen Length 15 ftMat'l sch 40 PVCFilter Materials formation + 1/2" sandDiameter 7 inGrout Type 26.1 cement / 16.1 waterCasing Length 7.3 ft + 2.7 ftMat'l sch 40 PVC

Development

Diameter 9 in

Static Water Level

Date Start 12/20/84Finish 12/20/84

Top of Well Elevation

Contractor F&EDriller Law Eng.Drill Type Hollow stem augerrem OD, 6 in ID

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC skin cap 6 in locked steel casing					Log based on split spoon samples, sitting, drill notes
0		CL	Silty sandy clay, 15% silt, 15% fine sand, 104 R/4/3 (brown), mod plastic, soft, moist, N.A.B., flood plain	2	15	1		grout PVC casing bentonite seal
		ML	clayey silt, 25% clay, 104 R 5/4 (yellow brown), al. plastic, soft, moist, N.A.B., flood plain	3	3			All contents approximate & operational ex- cept @ 11 ft
5		CL	Sandy, silty clay, 20% fine sand, 15% silt, 546/1 (gray) to 104 R/5/18 (yellow brown), mottled, mod plastic, soft, moist, flood plain	4	14	2		contour @ 11 ft sharp
		SM	Silty clayey very fine to fine sand, 30% silt, 5% clay (up to 20% clay in places), 54 6/1 (gray) to 104 R/5/18 (yellow brown), mottled, non to al. plastic, med density, moist, flood plain	4	18	4		PVC screen
10		SW	Fine to coarse sand, 3% muscovite, 2% clay, well graded, mod. round, 547/11 (light gray), non plastic, dense, moist, N.A.B., flood plain	7	17	6		1st H ₂ O near 11 ft based on wet spoon sample
15		SW	Fine to coarse sand, 25% gravel (<0.5 in), well graded round, 548/2 (white), non plastic, v. dense, moist, N.A.B., flood plain	10	18	7		bagged sand 12 in borehole
				20	25	8		caved sand

Signed

K-96

Approved

Site MAFBSHEET 2 OF 3Boring No. MW 7-2Location Coordinates N

Hole Size _____ Slot _____

E

Screen Length _____ Mat'l _____

Filter Materials _____

Diameter _____

Grout Type _____

Casing Length _____ Mat'l _____

Development _____

Diameter _____


Static Water Level _____

Date Start 12/20/84 Finish 12/20/84

Top of Well Elevation _____

Contractor _____ Driller _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
20		SW	Mud to coarse quartz sand, 20% gravel (to 2 cm), well graded, round, 104R 718 (yellow), non plastic, dense, wet, N.A.B., fluid	6 13 18	15	9		12 in borehole cased sand PVC screen PVC end cap Elev 22.3 ft Elev 24 ft

Signed George Bond

K-97

Approved _____

Site Alapall AFB
Boring No. MW 7-3

SHEET 3 OF 3

- 1030 Move onto site w. rig
Helpers still cleaning auger @ 7-3
- 1040 Reason for MW 7-3 complete.
Prepara to commence augering
- 1045 Auger to 2.5 ft - mounted w. H-NV
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 6.5 ft
Auger to 7.5 ft
Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
- 1130 Spoon 15 to 16.5 ft
Auger to 20 ft
Spoon 20 to 21.5 ft
Auger to 25 ft (concluded 2 ft)
Snd heard inside auger - will return out after lunch
- 1150 Lunch
- 1230 Work on run
- 1320 Begin w. return bit
- 1345 Well set, pulling auger
Well set @ 22.3 ft (15 ft screen, 2.7 ft S.U.)
Cased to 15 ft
Add sand to 4 ft (8 bags; actually 16 small bags)
- 1450 Bent. pellets to 3 ft (1 bucket)
Grout to surface (3 bags cement, 15 # bent. powder)
- 1455 Repair site after cleaning auger
- * Wash 200 gal H₂O to make well (75% return)
* Well set @ 22.3 ft (15 ft screen, 2.7 ft S.U.)
* Materials - 10 ft liner, 15 ft screen, 8 bags sand,
1 bucket pellets, 3 bags cement, 15 # bent. powder,
1 add casing w/ lock

12/20/84
DATE

[Signature]
SIGNED

APPROVED

Site Manwell AFB

SHEET 1 OF 4

Spring No. NW 7-3

Location Coordinates N

Hole Size 12 in Slot 0.010 in

E

Screen Length 15 ft Mat'l Sub 40 PVC

Filter Materials formation + lagged sand

Diameter 4 in

Grout Type 20/4 cement / bentonite

Casing Length 7 ft + 2.5 ft sub Mat'l Sub 40 PVC

Development

Diameter 4 in

Static Water Level

Date Start 12/19/84 Finish 12/20/84

Top of Well Elevation

Contractor FSE Driller Low Eng

Drill Type Hollow stem auger

12 in CP, 6 in FD

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
			4 in PVC slip 6 in locked steel					Log based on split spoon samples, withings, drill rate
0		SC	Clayey, gradully fine to coarse sand, 20% clay, 10% gravel, well graded, 7.54 R (1/6) (strong brown), al. plastic, loose, damp, N.A.B., flood plain	37	7	1		grout
		SM	Silty clayey fine sand, 30% silt, 20% clay, 54 S (1) (gray), al. plastic, med. dense, damp, N.A.B., flood plain	4				bentonite seal
5		SC	Clayey, silty fine sand, 30% clay, 20% silt, 54 S (1) (gray), al. plastic, soft, moist, N.A.B., flood plain	1	0	2		PVC casing
		SP	Fine to med sand, 3% clay, poorly graded, round, 54 G (1) (gray), non plastic, med. density, wet, N.A.B., fluvial	45	14	3, 4		7 ft H ₂ O near 7 ft based on water measured inside auger
10		SW	Med to coarse sand, 5% gravel, well graded, 54 G (1) (lt gray), non plastic, dense, wet, N.A.B., fluvial	108	12	5		All contacts approximate and gradational
		SC	Interbedded fine to coarse sand and inorganic clay, 7.54 R 5/8 (strong brown), non to v. plastic, loose to soft, wet, fluvial/flood plain	23	18	6		joins
		SW						12 in lockhole
								lagged sand
								caved sand

Signed George Kook

K-99

Approved

Site NAFBSHEET 2 OF 4Boring No. AW 7-3

Hole Size _____ Slot _____

Location Coordinates N _____

Screen Length _____ Mat'l _____

E _____

Diameter _____

Filter Materials _____

Casing Length _____ Mat'l _____

Grout Type _____

Diameter _____

Development _____

Date Start 12/19/84 Finish 12/20/84

Static Water Level _____

Contractor _____ Driller _____

Top of Well Elevation _____

Drill Type _____

Elevation (ft)	Depth (ft)	Legend	Classification of Materials	Blow Counts	Recovery	Box or Sample #	Sketch of Construction	Remarks
	20	SW	Fine to very coarse sand, well graded, round, 104 & 6/8 (brassy yellow), non-plastic, dense, wet, N.A.B., fluvial	10 28 28	13	7 8		12 in borehole cased sand PVC screen PVC sand cap
	25	SW	Coarsely sand, 35% gravel (< 3mm), 5% clay, well graded, round to angular, 7.54 R 5/6 (siliceous brown), non plastic, very dense, wet, N.A.B., fluvial					

Signed _____

K-100

Approved _____

Site Matwell AFB

Boring No. MW 7-3

SHEET 3 OF 4

1120 Arrive on-site
1130 Lunch
1215 Go to Wimp Locksmith & pick up keys for
Lease Eng.
1300 Return to Base & call John Bonds,
Luther Bonds to discuss site cleanup,
protective gear, etc.
1310 Return to site - Driller attempting to free a
lost using torch technique (had to cut it off)
1330 Driller goes for parts (hardware store)
Hoffers to replace 4 locks with new ones on
pressure installed wells
1405 EST back to site
1515 Driller returns
~~1515~~
1520 Begin auguring
Auger to 2.5 ft
Spoon 2.5 to 4 ft
Auger to 5 ft
Spoon 5 to 10.5 ft - Occasional (sample 2 in cutting)
Auger to 7 ft - plaster, metal, glass debris coming
up the auger
1545 Discontinue auguring while changing H-NL with
portable generator
1555 Calibrate H-NL - 0 ppm above background
Auger to 7.5 ft - carefully monitoring w. H-NL
1600 Spoon 7.5 to 9 ft
Auger to 10 ft
Spoon 10 to 11.5 ft
Auger to 15 ft
Spoon 15 to 16.5 ft
Auger to 20 ft
1615 Spoon 20 to 21.5 ft

12/19/84
DATE

[Signature]
SIGNED

APPROVED

K-101

Site Maxwell AFB

Boring No. MW 7-3

SHEET 4 OF 4

1630 Auger to 24 ft (overdrilled 2 ft)

1640 Set well

1645 Could not push the auger plug out with this well

Pull well

Will return and the auger 12/20/84

1700 Repair site

12/20 0630 F&S, drillers on-site

0645 Rotate out auger while I take broken auger
back to welding shop (20 min trip)

0730 Set well, pull auger

well set @ 22 ft

Sand cement to 16 ft

0830 Add sand from 16 to 4 ft (8 bags)

Bent pellets to 3 ft (1 bucket)

~~Bring to surface~~

Supply run (45 min DOWNTIME)

0915 Water run (30 minutes)

1000 Bring to surface (3 bags cement, 15 # powder)

1010 Repair site

* Well set @ 22 ft (15 ft screen, 2.5 ft S.V.)

* Used 200 gal H₂O to make well 75% return

* Materials - 9.5 ft screen, 15 ft screen, 8 bags sand,
1 bucket pellets, 3 bags cement, 15 # powder, 1 wheel
casing w/ rock

Note: Removed & grouted PZ 7-3 using Deft over grout!

12/19/84
DATE

George Noel
SIGNED

APPROVED

APPENDIX L--WELL DEVELOPMENT LOGS

WELL DEVELOPMENT

AT Grams

Richter steady, very cool

0700 (1) Well 1-2

G. Foster has steady pumped 90 gallons from this well
No drilling fluid lost

3" Submersible pump

Well depth = 14.0'

Date of installation

Date of development 1/9/85

Beginning static water level (S) 0930 = 8.00' - 1.59'

From TOC

PVC stringer = 1.83' above ground

1/10/85

Sediment = 15.88' below TOC

1000 Initial ST Readings = 70

One well volume =

22.9 ~~100~~ gallons

cond

pH

11220	1315	1555	0920
14.5	16.5	16.4	16.3
140	140	173	189
4.0	4.6	4.5	4.5

Initial 1/2 d. turbid - 1/2 d. turbid

Pumping rate = 17 gpm

10 gallons removed before pump run dry 1000

8 gallons removed before pump run dry 1100

17 gallons removed before pump run dry 1300

18 gallons removed before pump run dry 1441

10 gallons " " " " 1557

8 gallons " " " " 1710

1/10/85 16 gallons before pump run dry 0800

Water is slightly turbid, no odor at first - decreasing turbidity w/ pumping

71 + 90 = 161 gallons removed as at 17:0 - water is very slightly

turbid - will continue tomorrow

1/11/85 14 gallons removed

Total volume removed = 191 gallons - sample taken 2120 1/10/85

Water is still slightly turbid

Final water level 0930 1/10/85 8.20' - 1.36

1/10 TOC

3142 End water level 1030 1/11/85 8.00' - 1.56

below TOC

Continued on Page

Read and Understood By

I-1

Signed

1/21/85

Date

AT 6.00

Break for lunch 11:00 - 12:00

(2) Well 1-3 23 h

Pump: Honda WB20X mechanical pump w/ PVC standpipe

Well depth = 23.3

Date of installation

Date of development: 1/9/85

Beginning static water level @ 1324 = 10.00 - 1.89

below TOC

PVC standpipe = 2.80'

Depth to sediment = 24.65' below TOC initial

24.66' below TOC final

Rate of pumping = 30 liters/min

~~PVC standpipe~~

Initial

Final

~~water volume pumped~~

1245

1308

1325

1343

1245 Initial X Readings

°

14.0

18.4

19.6

19.7

Samples

and

99

100

100

100

taken

pH =

5.5

5.5

5.4

5.5

1347

of hybrid

v.s. hybrid

fringe of

hardness

On volume to be removed = 31.5 gallons including annulus

Total volume of water removed = 425 gallons - pumped for 1 hr. 3 min

Final water level @ 1352 = 10.00 - 1.39 below TOC

1/10/85 24 hr final water level @ 1330 10.00 - 1.88 below TOC

Continued on Page

Read and Understood By

L-2

Signed

Date

Signed

Date

1/2/85

PROJECT

MAXWELL AFB

Continued From Page _____

ATEXONS

③ Well 1-4

Centrifugal blower pump w/ PVC standpipe

63 gallons of
drilling water remain
in hole

Well depth = 21.5'

Date of installation

Date of development 1/9/85

Beginning static water level @ 13.95 = 13.00 - 5.37 below TDC

PVC stickup = 1.86'

Depth to sediment = 22.23' below TDC

Rate of pumping = 16.5 liters/min until well dries out completely

Start pumping 1812 - water is extremely muddy to start

SET readings Initial 1330 1700 Final (0856 1/10/85)

T 20.1 19.3 18.6 17.2

cond 109 63 53 54

pH 5.1 4.9 4.8 4.9

Volume tally One Volume to be removed = 34 gallons

1.4 min = 9 gal

2.2 min = 5 gal

2.6 min = 14 gal

2.1 min 16 gallons

2.5 min 20 gallons

1.8 min 14 gallons

2.4 min 19 gallons

2.3 min 18 gallons

3.5 min 20 gallons

2.4 min 19 gallons

2.5 min 20 gallons

2.5 min 20 gallons

2.6 min 21 gallons

2.5 min 20 gallons

2.4 min 21 gallons

2.5 min 21 gallons

2.6 min 21 gallons

2.6 min 21 gallons

2.6 min 21 gallons

Turbidity decreased somewhat by beginning of SET reading

Pumping rate increased to 30 l/min

Water is still showing considerable turbidity even

after 160 gallons pumped

300 gallons pumped as of 1720 - will continue tomorrow

morning

304 gallons total removed - sample taken 0855 1/10/85

Water is still fairly turbid

Final water level @ 22.23 1/10/85 - 9.00 - 1.03

24 hr. water level @ 1015 1/11/85 13.00 - 5.39

below TDC

Continued on Page

Read and Understood By

L-3

1/21/85

13.96

1/10/85

ATEVANS

cloudy, cool, occas. lt. rain

(4)

Well MAX 1-1

Centrifugal Hand pump w/ stand pipe

Well depth = 28.0'

Screen length = 10.0'

Date of installation 12/20/84

Date of development 1/10/85

Initial GWL @ 1015

18.03 - 1.90

below TDC

Settlement depth = 27.48' below TDC

PVC standup = 2.18' above ground

Start pumping 1026 at rate of 24 l/min = 6.3 gpm

Water is very turbid, yellowish brown color

SET Readings

Initial (1030)

1040

1102

Final (1124)

FO

19.6

20.4

20.6

20.7

CAL

100

49

40

38

pH

5.3

5.0

4.6

4.6

One well volume = 24.6 gallons

62 gallons of drilling water
remain in hole

Water is clearing up considerably with continued pumping

Pumped for 60 minutes = 380 gallons removed

Water is almost clear, still some
yellowish brown turbidity

Final water level @ 1130 = 18.00 - 1.88

below TDC

24hr. water level @ 1140 = 17.00 - 2.89

below TDC

Continued on Page

Read and Understood By

L-4

Signed

Date

Signed

Date

1/21/85

1/10/85 ATEVANS

⑤ Well 7-3

contingent Honda pump/standpipe

Well depth = 22.0'

Screen length = 15.0'

Date of installation 12/30/84

Date of development 1/10/85 - 1/11/85

Initial GWL @ 1148 1300 - 1.22'

below TDC

Sediment depth = 22.9' below TDC

PVC stickup = 2.02'

2.9 g/min

Rings at rate of 30 l/min before wellbore runs dry

Initial (1345) 0935 1/10/85 1140 1/11/85 1642

ETW

SET

T

CWD

Temp

19.4

12.9

17.2

17.2

445

345

287

271

6.5

6.0

6.1

6.1

2 min 16 g

1.2 min 10 g

1.2 min 10 g

1.2 min 10 g

1.2 min 10 g

1.2 min 12 g

1.2 min 8 g

1.2 min 8 g

1.2 min 10 g

1.2 min 10 g

1.2 min 10 g

1.2 min 12 g

1.2 min 12 g

water is grayish-brown, very muddy at first, starting to clear after 30 gallons

One volume = 27.2 gallons

50 gallons drilling fluid remaining in hole

Well takes up to 1 hr. to recover - will continue developing

1/11/85

Final water level

~~9.52 - 1.97~~

17.66 - 1.93

1/

1/15/85 80,000 gallons removed by intermittent pumping

1/16/85 100,000 gallons removed by intermittent pumping - sampled 1645

Final water level @ 1650 = 24.05 - 1.85'

water is still somewhat turbid some sand


Final sediment = 28.98' below TDC

Continued on Page

24 hr. water level = 23.00 - 3.90

L-5

Read and Understood By



1/21/85

Date

PROJECT _____

Continued From Page _____

⑥ Well 7-2

Centrifugal Submersible pump

Depth of well = 22.9'

Screen length = 15.0'

Date of installation = 12/20/84

Development date = 1/15/85

Initial GWL @ 1311 17.00 - 4.06'

below TOC

Sediment depth = 24.10' below TOC

DVC stickpoint 2.42

Pumps at rate of 17 gpm

1/11/85

1/14/85

Final

Initial (1527)

0848

0918

0341

Time Amt

SCT

T⁹

18.4

17.5

18.0

18.7

0.7m 12 gal

cond

175

107

93

92

pH

5.8

5.0

4.8

4.3

One well volume = 26.1 gal

50 gallons of drilling fluid
remaining in hole

1500 - Had to stop pumping well because submersible pump froze up. Unable to free impeller after 30 minutes of backflushing. Initial water was very muddy and sandy contains much very fine sand. Pump had been located 1 ft above top of sediment to prevent clogging but enough was picked up by pump to jam impeller. Well closed and locked.

1615 - Took apart submersible to clear sand out, will reach out completely tonight before reassembly. Will resume purging of well with centrifugal pump about 5. Further has

1730 55 gallons removed by the centrifugal pump

Continued on Page _____

Read and Understood By

L-6

1/21/85

Signed _____

Date _____

PROJECT _____

1/11/84 Resume pumping with centrifugal pump at rate of 30 l/min
start 0830 - should pump continuously

water is almost clear

0845 Total volume removed = 465 gallons - water is clear.
sample taken


0950 Final water level = 15.00 - 1.96' below TAC

1/11/85 24-hr. water level = 12.00 - 4.05' = 13.95' below TAC

Continued on Page _____

Read and Understood By

L-7

1/21/85
Date

1/11/85 ATEP
 cloudy, breezy, cold

② Well 4-1

Centrifugal pump

Well depth = 260'

Screen length 10.2'

Date of installation 1/7/85

Date of development 1/11/85

(1110) Initial draw = 20.06 - 1.84'

Sediment depth = 28.24' below TOC

PVC stickup = 2.42'

250 gallons of fluid remain
 in hole

Start pumping at 1045 - rate 20.2/min = 5.8 gpm

SCT Initial 1112 1200 1230 1300 final

SD 17.7 18.5 18.5 18.5

cond. 155 145 143 140

pH 5.6 5.6 5.6 5.6

One well volume = 28.0 gallons

Water starts turbid - yellowish brown - clears up
 completely within 5 min.

Total volume pumped (145 min) = 770 gallons

Sample taken 1310 - water is clear

Final sediment depth = 28.44' below TOC

Final water level @ 1315 24.00 - 5.81 below TOC

@ 24 hr. water level 22.00 - 3.82 below TOC

Continued on Page

L-8

Read and Understood By



1/21/85

PROJECT

MAXWELL AFB

Notebook No.

Continued From Page

1/11/85 ATENARI

⑧ Well 4-2

Well depth = 20.0'

44 gallons drilling fluid remaining in hole

Date of installation 1/6/85

Rate of development

initial GWL @ 1500

20.0' - 2.23'

below TOC

Sediment depth

22.78'

below TOC

PVC stringer = 2.55'

Dr. with volume = 35.0 g

Pump rate 20 g/min - start pumping 1530

	SGT	Initial (1548)	1600	(1620)	1640	Final
20 min 11g	TO	12.5	15.7	18.7	18.7	18.7
20 min 11g	cond	180	187	138	138	94
24 min 13g	pH	6.0	5.8	5.6	5.6	5.5

2.1 min 17g

5.0 min 11g

3.5 min 15g

4.0 min 22g

3.5 min 18g

2.5 min 17g

2.5 min 14g

2.7 min 15g

2 min 14g

3.5 min 17g

2.3 min 14g

Water is initially yellowish-brown and very turbid, cleared up rapidly after 40 gallons pumped

Started pumping continuously after 100 gallons

Water is clear except for fine sand

Sample taken 1723 - Total volume removed = 230 gallons

1716 Final water level = 16.0' - 2.43' below TOC

24 hr water level = 14.0' - 1.01' below TOC

Final sediment depth = 28.35' below TOC

Continued on Page

Read and Understood By

L-9

1/21/85

1/12/85 AT GCR-5
Mostly cloudy, wind, COLO.

⑨ G-1

250 gallons drilling fluid in hole

Well depth = 37.3'

Screen length = 12.0'

Installation Date: 12/21/84

Sev date = 1/12/85

24-hr PVC stickup = 2.35'

24-hr well volume = 49 gallons

0825

Static GWL = 30.0' - 2.58' below TSC

Sediment depth = 39.5'

1/12/85 1/14/85

Static	10:43	17.25	14.04	11.47 final
SGT TO	17.2	17.9	16.6	17.4
cond.	235	94	105	96
CH	6.1	3.7	5.6	5.6

Well depletes quickly, but fast recovery

Water is grayish brown, turbid - This well will be very slow to develop

As of 1725, 160 gallons removed by intermittent pumping

9 to 10 gallons remained after 30 minute wait

Will resume tomorrow morning - water is almost clear

Additional 200 gallons removed 1/12-14/85 by intermittent pumping. Total volume removed = 360 gallons

Water is still slightly turbid - sample taken 1150 (1/14/85)

End GWL @ 1155 (1/14/85) 30.00 - 4.15 = 25.85' below TSC

Final sediment = 39.5'

24-hr. GWL = 20.0' - 2.61' =

below TSC

Continued on Page

Read and Understood By

L-10

[Signature]

1/21/85

PROJECT

MAXWELL AFB

Continued From Page _____

1/12/85 ATENKES

(19) Well 43

Well depth = 24.5'

Screen length = 20.0'

Sediment depth = 27.03' below TOC

PVC stickup = 2.36'

One well volume = 340 gallons

22.60' - 8.47'

Start Pumping at rate of 18 L/min 0945

Static GWT @ 0945 22.60' - 8.47'

Below TOC

T	16.7	19.0	12.6	19.8
---	------	------	------	------

SC	Cond	25	71	59	58
----	------	----	----	----	----

pH	5.3	5.3	5.2	5.0
----	-----	-----	-----	-----

Inlet (GWS)	1006	1034	1050	Final
-------------	------	------	------	-------

280 gallons to be removed

88 gallons drilling fluid remain in hole

Installation date = 1/6/85

Development date = 1/12/85

Water initially is yellowish-brown, very turbid - clears up with pumping

Completely clear after 120 gallons removed

Pwell pumps continuously

Time pumped = 70 min Total vol removed = 335 gallons

Sample taken 1053 - water is clear

Final GWT @ 1057 = 24.05' - 10.46' Below TOC

Final sediment depth = 27.23' below TOC

24-hr GWT = 24.00' - 10.44' Below TOC

Continued on Page _____

Read and Understood By

L-11

[Signature]

1/2/85

Date

ATEVANS 1/12/85

⑦

Well 3-2

Centrifugal pump w/ standpipe

Well depth = 29.2'

Screen length = 20.0'

Installation date = 1/5/85

Development date = 1/12/85

Initial GWL @ 11:00 = 11.00' - 1.85' = 9.15' below TOC

Sediment depth = 20.25.48'

PVC stickup = 2.29'

Start pumping 1124 at rate of 20 gpm = 3.3 g/m

One well volume = 38.5 gallons

Volume to be removed = 245 gallons

Initial (1127) "

SGT	T ₉	18.8	19.5	19.5	20.1
	rod	73	89	74	71
	pot	5.0	5.2	5.1	5.0
		1127	1138	1200	1219

Water initially is greyish and materially turbid,
cleared up completely after 30 gallons

Final GWL @ 12:27 11:00 - 1.81

Final sediment depth = 25.76'

Sample taken 1230

Pumped for 65 minutes = 345 gallons removed

Water is clear

24-hr. GWL = 12.00 - 2.89' below TOC

Continued on Page _____

Read and Understood By

L-12

1/21/85

PROJECT

MAXWELL AFB

ATEKAM 1/12/85

(12)

Well 3-3

Centrifugal pump, 1/2" standpipe

Well depth = 282

Screen length = 20'

Installation date = 1/3/85

Development date = 1/12/85

Initial GWL @ 1355 = 6.00' - 1.51' = 4.49' below TDC

Sediment depth = 26.94'

Start pumping 1400 at rate of 30 l/min

One well volume = 50.5 gallons

PVC stickup = 2.03'

SGT T 18.5 19.7 19.2 18.1

cond 6.54 104 92 92

pH 6.0 5.1 5.0 5.0

1402 (initial) 1532 1450 1520

Water initially turbid and yellowish-brown - clears up rapidly

Very slight turbidity by 1520 - sample taken 1530

Pumped for 90 min - 480 gallons removed

Final GWL @ 1532 = 6.00' - 1.73'

Final sediment depth = 27.00'

24-hr GWL @ 1320 6.00' - 1.53' = 4.47' below TDC

Continued on Page _____

L-13

Read and Understood By

Steve Vukobratovic

1/21/85

PROJECT _____

MAXWELL AFB

Continued From Page _____

ATC/ENR 1/12/85

(13) Well S-4
centrifugal pump w/ standpipe
Well Depth = 255
screen length = 15.0'
PVC stringer = 1.48'

75 gallons drilling water
remain in hole

320 gallons to be removed

Installation Date 12/16/84

Development date 1/12/85

Initial GWT @ 1545 7.00' - 2.24' below TOC

Sediment depth = 25.20' (very soft bottom)

1548 Start pumping at rate of 20 gpm

5CT T 19.6 19.6 18.5 19.6

pond 120 82 80 85

pH 5.3 5.3 5.3 5.1

1550 (initial) 1626 1630 1658 (final)

One well volume = 49 gallons

Water initially yellowish-brown and very turbid,
clears up after 40 gallons somewhat
Even after 200 gals water still has
some turbidity - yellowish-brown clay

Pumped for 75 min - 400 gallons pumped
Water still has some yellowish-brown turbidity - no sand
Sample taken 1703

Final GWT @ 1705 = 7.00' - 2.03'


Final sediment depth = 25.26.73'

24-hr GWT = 7.00 - 2.23' below TOC

Continued on Page _____

L-14

Read and Understood By



1/21/85

ATE 1/13/85

Fair, slight breeze, very cold

(14) Well 5-1

Centrifugal pump w/ standpipe

Well depth 25.4'

Screen length = 10.0'

PVC stickup = 3.13'

Installation date 12/11/84

Development date 1/13/85

Initial GRL @ 0833 20.00 - 1.14 = 18.86' below TOC

Sediment depth 22.90' below TOC

One well volume = 14.4 gallons

1/3/85

1/14/85

1/14/85

SCT	T ^o	18.15	17.00	0848	1046
		17.3	17.5	13.6	12.7
		17.5	18.8	13.7	10.8
		0.3	6.8	6.3	5.8

0840 Both centrifugal pumps are frozen solid and will not start
 George is looking for a propane torch to heat the pumps


0955 Pump started and working, but water is too deep to
 pump effectively through centrifugal pump, so we are
 using new submersible pump which arrived yesterday. Because
 of rapid depletion of water, well will have to be pumped
 intermittently. Rate = 17 gpm - well is slow to recover

25 sec 6 gallon

25 sec 6 gallon

1300- Pumping only with difficulty, well does not seem to recover
 sufficiently to allow pumping of a full column of water.

Continued on Page

Read and Understood By
L-15


1/21/85

Date

PROJECT _____

MAXWELL AFB

Continued From Page _____

ATC/ers 1/13/85

1/5/85

100 gallons removed by bailing well by hand using
1" PVC - stainless steel bailer. Water initially very
muddy and yellowish-brown, clear with continued
bailing somewhat

1/16/85

100 gallons pumped intermittently with
centrifugal pump w/ standpipe

Final water level @ 1048 = 25.00 - 2.80

Final sediment depth = 25.30'

Water is almost completely clear -
trace of sand - sample taken 1046

Continued on Page _____

L-16

Read and Understood By

1/21/85

Notebook No. _____

Continued From Page _____

PROJECT

MANWELL AFB

1/13/85 ATEVAN

(10) S-3

Well depth = 28.0'

Screen length = 20.0'

Date of installation 1/14/85

Date of development 1/17/85

125 gallons drilling fluid remain in hole
375 gallons to be removed

Obs well volume = 50.3 gallons

Initial GWL @ 1027

9.00 - 1.18 below TOL

Sediment depth

28 29.60' below TOL

PVC pickup = 2.95'

Start pumping 1035 at rate of 20 l/min initial - reaches to 4.5 gpm

OCT

T° 17.8 20.3 21.7 21.9

cond 444 90 82 83

pH 8.4 5.2 5.2 5.2

Initial (1037) 11.5 11.35 12.08 (final)

Water initially shows yellowish-brown turbidity -
clears rapidlySample taken 1210 - water is almost completely clear
Pumped for 95 minutes - 430 gallons removed

Final GWL @ 1215 = 10:00 - 199

Final sediment depth = 29.65'

24-hr water level = 9.00 - 1.19'

Continued on Page _____

Read and Understood By

L-17

Stan Venter

1/21/85

ATE 1/13/85

Centrifugal pump w/ standpipe
Well S-2

Well depth = 22.5'

Screen length = 15.0'

Date of installation 12/15/84

One well volume = 36.3 gallons

Initial GWL @ 1438

Sediment depth = 24.90'

Stickup PVC = 2.0'

Start pumping @ 1445 at rate of 20.2 24 L/min = 6.3 gpm

SCT	T ⁰	18.5	20.5	20.2	20.0
	cond	153	114	110	109
	pH	5.6	5.2	5.2	5.2

Water is turbid, yellowish-brown at start, clears up rapidly with pumping

Final GWL @ 1530 = 10.00 - 1.25 = 8.25' below TDC

End sediment = 24.93'

Water is almost completely clear, sample taken 1536

Placed for 50 min. = 315 gallons removed

1540 - 1640 - George's truck got stuck - spent 1 hr. freeing it

24-hr. water level = 10.00 - 1.81 = 8.19' below TDC

Continued on Page

L-18

Read and Understood By

Sam Decker

1/21/95

ATE 1/19/85

Cloudy, very cold, breezy

No drilling fluid remaining in hole
180 gallons to be pumped

⑦ 6-3 Submersible pump

Well depth:

Screen length:

Date of installation

Date of development 1/19/85

Original well volume = 35.5 gallons

Initial GWL @ 0550 33.00 - 3.25 = 29.25' below T&C

Sediment depth = 42.72'

PVC Stickup = 2.50'

Start pumping 0900 - rate = 7.9 gpm

SCT:

TP	16.1	18.3	18.8	18.6
cond.	190	229	222	220
pH	5.1	5.1	5.1	5.1
Initial (0900)	0918	0926	0935 (final)	

Water very turbid, yellowish-brown at first, cleared up rapidly

Pumped for 46 minutes = 320 gallons removed

Water is clear - sample taken 0941

Final water level @ 0943 = 31.00 - 1.78 = 29.22' below T&C

Final sediment depth = 42.80'

Continued on Page _____

Read and Understood By

L-19

Sinned

1/24/85

Date

PROJECT

MAXWELL AFB

Notebook No.

Continued From Page

ATF/ONS

1/15/85

Centrifugal pump w/ hose

(18) Well 7-1

Well depth = 24.3'

Screen length = 10.0'

Installation date = 1/4/85

Development date = 11/14/85

One well volume = 21.0 gallons

PVC stickup = 10'

Initial GW @ 1025 17.00 - 1.21 = 15.79' below TOL

Sediment depth = 24.80'

Flow pumping 1028 at rate of 3 gpm

No drilling fluid remaining
in hole

Volume to be removed = 105 gallons

ST	Initial 1034	1030	1100	1112 (final)
T	12.9	21.0	21.1	21.8
cond	62	77	75	79
pH	5.1	5.6	5.0	5.0

Water is turbid greyish-brown - clears up after
40 gallons removedPumped for 55 minutes = 165 gallons removed
Water is clear - sample taken 1128

1125 Final GWL = 12.00 - 0.70 = 11.30' below TOL

Final sediment = 25.3' below TOL

1/15/85 24 hr. GWL = 12.00 - 1.19' = 10.81' below TOL

Continued on Page

L-20

Read and Understood By

1/21/85

OJECT

MAXWELL AFB

Notebook No. _____

33

Continued From Page _____

ATEVANS 1/14/85

(19) Well 45-2

Well depth

Screen length

Installation date

Development date

PVC stickup = 2.521

One well volume = 34 gallons

Initial GWL @ 1412 3200 - 2.48 = 29.52' below T&C

Sediment depth = 42.28' below T&C

Start pumping 1428 at rate of 7.9 gpm

	1432 (inches)	1444	1458	1515	field
SCD	T°	18.4	19.1	18.5	19.2
	and	278	247	289	289
	pH	5.5	5.1	5.0	5.0

Water is initially yellowish-brown, very turbid,
clears up rapidly with pumping.

1530 Total water level = 3200 - 2.42

Final Sediment depth = ~~42.28~~ 42.77'

Pumped for 52 min = 410 gallons removed

Water is clear - sample taken 1530

1/15/85 24-hr. GWL = 3200 - 2.46 = 29.54' below T&C

Continued on Page _____

Read and Understood By

L-21

1/21/85

Date

AT EVANS 1/15/83

Clear, breezy, cold

(20) Well G-1

Submersible pump off

Depth of well

Screen length

Installation date

Development date = 1/15/83

Initial GWT @ 1546

 $35.00' - 6.03' = 28.97'$ below TOS

Sediment depth

41.8' below TOS

PVC stickup = 2.18'

One well volume = 33.3 gallons

No drilling fluid remaining in hole
156 gallons to be removedSubmersible pump jammed at 1630. attempted to free it
w/o without success - will take it apart and clean it tonight

1/15/83 Skit pumping 0903 at 10 gpm with submersible pump

SGT	0910 (init)	0930	0932	0950
T _s	16.3	17.0	18.1	18.2
load	333	298	280	272
pH	5.4	5.2	5.5	5.5

Water is initially brownish - very turbid, clears rapidly
with pumpingPumped for 50 min - 500 gallons removed
water is clear, sample taken 1000Final GWT @ 1003 = $35.00 - 6.06' = 28.94'$ below TOS

Final sediment depth =

Continued on Page _____

Read and Understood By

L-22

J. C. 11.1

1/16

APPENDIX M--MONITOR WELL, SURFACE WATER, AND
SEDIMENT SAMPLING LOGS

WELL SAMPLING DATA

0128NA014 GN 850046

Well Sampling:

Well Number GW 1-1 Time 1400

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 16.2 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469200

1. Depth of well 25 (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 25 (hr, min)
8. Total volume pumped ~~25~~ 12.5
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 6.6

Conductivity 75 uhmos/cm

Temperature 11.2 °C

Fractions Collected (circle): ☒ CF ☒ V ☐ M ☐ RP ☐ CI ☐ RS ☐ H
☐ O ☐ P ☒ F ☒ B ☐ T ☐ R ☐ UP ☒ NF

Signed JHC Chatkley Date 1/10/89
M-1

Read and Understood By:

Signed _____

Date _____

WELL SAMPLING DATA

0128 NA 014 GN 85 ~~0046~~ 0047

Well Sampling:

Well Number GN 1-2 Time 1515

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 5.5 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469201

1. Depth of well 14 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped pumped dry 2x (hr, min)
8. Total volume pumped _____
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.8

Conductivity 203 uhmos/cm

Temperature 17.0 °C

Fractions Collected (circle):

☒ CF ☒ S ☒ M RP Cl RS H
O P ☒ Z F ☒ B T R UP NF

JAC
[Signature]
Signed

1-18-85
Date

Read and Understood By:

[Signature]
Signed

1-18-85
Date

WELL SAMPLING DATA

0128 NA 014 AN 05004g

Well Sampling:

Well Number GW1-3 Time 1645

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 8.1 TOC (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 409202

1. Depth of well 22.3 (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 42 (hr, min)
8. Total volume pumped 210 gal
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.8Conductivity 95 uhmos/cmTemperature 18.1 °CFractions Collected (circle): C CF S M RP Cl RS H
O P 2 F B T R UP NFSigned MTL
W. Chatterjee
Date _____
M-3

Read and Understood By:

Signed _____

Date _____

WELL SAMPLING DATA

0128 NA014 GN85 0049

Well Sampling:

Well Number GW1-4 Time 1545

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 7.4 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 4109203

1. Depth of well 21.5 (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 40 (hr, min)
8. Total volume pumped 200 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.9Conductivity 77 uhms/cmTemperature 17.5 °CFractions Collected (circle): C CF S N M RP CI RS H
O P E F B T R UP NF

WJH

Signed

Date

Read and Understood By:

Signed

Date

0128 NA 008 GN 85 0014

WELL SAMPLING DATA

Well Sampling: AN3-1

Well Number GN3-1 Time 1050

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 17.7 TOL (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information: Sample Number 469500

1. Depth of well 37.3 (ft)
2. Diameter of well 4" (inches)
3. Method of collection _____ (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped _____ (hr, min)
8. Total volume pumped 220 ME gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.6

Conductivity 91 uhmos/cm

Temperature 17.0 °C

Fractions Collected (circle):

C CF S N M RP CL BS H
O P L F B T R UP NE

Read and Understood By:

MJG
JAR
Signed _____ Date 11/15/95

Signed _____ Date _____

0128 NA 008

WELL SAMPLING DATA

GN 83 0015

Well Sampling: GW 3-2Well Number MN 3-2 Time 1530

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 9.3 70 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469501

1. Depth of well 24.2 (ft)
2. Diameter of well 4" (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 51 (hr, min)
8. Total volume pumped 255 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.2Conductivity 67 umhos/cmTemperature 17.6 °C

Fractions Collected (circle):

<input checked="" type="radio"/>	CF	<input checked="" type="radio"/>	V	<input type="radio"/>	M	<input type="radio"/>	RP	<input type="radio"/>	CI	<input type="radio"/>	RS	<input type="radio"/>	H
<input checked="" type="radio"/>	P	<input checked="" type="radio"/>	F	<input checked="" type="radio"/>	B	<input type="radio"/>	T	<input type="radio"/>	R	<input checked="" type="radio"/>	UB	<input checked="" type="radio"/>	NE

Read and Understood By:

Signed

Date

Signed

Date

WELL SAMPLING DATA

C138 M-100 6455 0016

Well Sampling:

GW 3-3

MW 3-3

Well Number

~~GW 3-3~~

Time 1145

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 4.66 TOC (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469502

1. Depth of well 25.2 (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 55 (hr, min)
8. Total volume pumped 275 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.9Conductivity 264 uhmos/cmTemperature 16.4 °C

Fractions Collected (circle):

☒ C ☐ CF ☒ S ☒ V ☐ M ☐ RP ☐ SI ☐ RS ☐ H
☐ O ☐ P ☐ F ☐ B ☐ T ☒ R ☒ TP ☒ W

Read and Understood By:

Signed

Date

M-7

Signed

Date

WELL SAMPLING DATA

0128 NA 009 GN 85 0017

Well Sampling:

Well Number GW 4-1 Time 12:15

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) 10.3 ART (ft)
4. Distance to water (before pumping) 13.6 TOL (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 50

1. Depth of well 26 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 3 (gpm)
at finish 3 (gpm)
7. Total time pumped 50 (hr, min)
8. Total volume pumped 150 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.8Conductivity 149 uhmos/cmTemperature 19.0 °C

Fractions Collected (circle):

☒ CF ☒ S ☒ N ☐ M ☐ RP ☐ Cl ☐ RS ☐ H
☒ P ☒ E ☒ F ☒ T ☐ R ☒ UP ☒ NF ☒ X²

Read and Understood By:

Signed

Date

Signed

Date

0128 NA 009 ~~01~~ ON 85 0018

WELL SAMPLING DATA

Well Sampling:

Well Number GW 4-2 Time 1215

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 14.2 TOC (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information: Sample Number 469504

1. Depth of well 26 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped 14 (hr, min)
8. Total volume pumped 140 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.5

Conductivity 88 uhms/cm

Temperature 19.9 °C

Fractions Collected (circle): ☒ CF ☒ S ☒ N ☐ M ☐ RP ☐ Cl ☐ RS ☐ H
☐ O ☐ P ☒ Z ☒ F ☒ B ☐ T ☐ R ☒ JP ☒ NE ☒ X²

[Signature]
Signed _____ Date 1/16

Read and Understood By:

[Signature]
Signed _____ Date 1/24/77

0128 NA 009

WELL SAMPLING DATA

GN 850019

Well Sampling:

Well Number GW 4-3 Time 1030

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) ~~13.6~~ 13.6 (ft) *24*
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469505

1. Depth of well 26 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) silt
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped ~~32~~ 32 (hr, min)
8. Total volume pumped 160 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 9.2Conductivity 92 uhms/cmTemperature 17.1 °C

Fractions Collected (circle):

C CF S N M RP CI RS H
O P L F B T R UP NE X

Read and Understood By:

Signed

Date

Signed

Date

WELL SAMPLING DATA

0128 NA 010 GNB50020

Well Sampling:

Well Number 5-1 Time 1800

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 15 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469507

1. Depth of well _____ (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 12 (hr, min)
8. Total volume pumped 60
9. Field analysis performed:

Dissolved Oxygen _____ mg/l
pH 3.7
Conductivity 146 uhmos/cm
Temperature 16.7 °C

Fractions Collected (circle):

☒ C ☐ CF ☒ S ☐ M ☐ RP ☐ CI ☐ RS ☐ H
☒ O ☐ P ☒ F ☐ B ☐ T ☐ R ☒ UP ☒ NF

Read and Understood By:

JHC
JHC
Signed _____ Date 1-10-85

Signed _____ Date _____

WELL SAMPLING DATA
0128 NA 010 GN 830021

Well Sampling:

Well Number GW5-2 Time 1645

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 8.25 TOC (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469508

1. Depth of well 22.5 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear
6. Approximate pumping rate: at start 3 (gpm)
at finish 3 (gpm)
7. Total time pumped 60 min (hr, min)
8. Total volume pumped 180 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.3

Conductivity 186 uhmos/cm

Temperature 17.5 °C

Fractions Collected (circle): ☒ CF ☒ S ☒ M RP Cl RS H
☒ U P ☒ C F ☒ S T R ☒ UP ☒ X²

[Signature]
Signed _____ Date 1/11/60

Read and Understood By:

[Signature]
Signed _____

1/11/60
Date _____

WELL SAMPLING DATA
0128NA010 ~~0128~~ GN850022

Well Sampling:

Well Number GW 5-3 Time 1600

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 9.9 TOC (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information: Sample Number 469509

1. Depth of well 28 (ft)
2. Diameter of well 4" (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear / silty
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped 34 (hr, min)
8. Total volume pumped 340 gals.
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.7

Conductivity 170 uhms/cm

Temperature 18.1 °C

Fractions Collected (circle):

☒ C ☐ CF ☒ S ☒ N ☐ M ☐ RP ☐ Cl ☐ RS ☐ H
☒ O ☐ P ☒ 2 ☐ F ☐ E ☐ T ☐ R ☒ UP ☒ NT ☒ R2

Read and Understood By:

Signed

Date

Signed

Date

0128 NA 0.0 WELL SAMPLING DATA
GNB5 0023

Well Sampling:

Well Number GW 5-4 Time 1525

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 4.0 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469510

1. Depth of well 25.5 (ft)
2. Diameter of well 4" (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 45 min (hr, min)
8. Total volume pumped 225 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.8

Conductivity 79 uhmos/cm

Temperature 16.6 °C

Fractions Collected (circle):

CF G N M RP CI RS H
O P Z F B T R UP NF

Read and Understood By:

JHC
1-17-85
Signed _____ Date _____

Signed _____

Date _____

WELL SAMPLING DATA
0128 NA010 GNB50024

Well Sampling: Existing site 5 GWS-5

Well Number well Time 1645

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 5.5 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469511

1. Depth of well 25 (ft)
2. Diameter of well 4 2" (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
Bailed 60 bailers then pumped at finish 5 (gpm)
7. Total time pumped 19 (hr, min)
8. Total volume pumped 12 bailed + 95 gals pumped
= 107 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.6

Conductivity 36 uhmos/cm

Temperature 16.1 °C

Fractions Collected (circle): C CF S M RP CI RS H
P F T R U AF

Read and Understood By: _____

MJG
MA Chaff
Signed _____ Date 1-17-85

Signed _____

Date _____

WELL SAMPLING DATA
0128 NA 011 QNB5 0025

Well Sampling:

Well Number 6W6-1 Time 1000

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 29 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469512

1. Depth of well 39.6 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped 22 (hr, min)
8. Total volume pumped 220 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.9

Conductivity 430 uhms/cm

Temperature 17.2 °C

Fractions Collected (circle):

G CF S M RP Cl RS H
O P L F B T R UP VE

Read and Understood By:

Signed

Date

Signed

Date

0128NA011 GN850026

WELL SAMPLING DATA

Well Sampling:

Well Number GW6-2 Time 1230

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 30.0 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469513

1. Depth of well 39.7 (ft)
2. Diameter of well 4" (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped 20 min (hr, min)
8. Total volume pumped 200 gal
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.8

Conductivity 241 uhms/cm

Temperature 18.2 °C

Fractions Collected (circle):

☒ C ☒ CF ☒ S ☒ M ☒ RP ☒ Cl ☒ RS ☒ H
☒ O ☒ P ☒ F ☒ E ☒ T ☒ R ☒ UP ☒ NF

Read and Understood By:

MTK
JAP
Signed _____ Date 1-17-85

Signed _____ Date _____

WELL SAMPLING DATA
0120NA011 GNB50027

Well Sampling:

Well Number GW 6-3 Time 11:15

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 29.5 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469314

1. Depth of well 40 (ft)
2. Diameter of well 4" (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) silty red/brown
6. Approximate pumping rate: at start 10 (gpm)
at finish 10 (gpm)
7. Total time pumped 30 min (hr, min)
8. Total volume pumped 300 gals
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 8.7

Conductivity 330 uhms/cm

Temperature 18.3 °C

Fractions Collected (circle):

CF SV M RP CI RS H
UP EF BT UR UF VF

Read and Understood By:

JHC

JHC
Signed

1-17-85
Date

[Signature]
Signed

1/17/85
Date

WELL SAMPLING DATA
0128NA013 GN 850043

Well Sampling:

Well Number GW 7-1 Time 1000

Water Level in Well:

1. Distance from top of pipe to ground 1.0 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 15.8 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information: Sample Number 469515

1. Depth of well 24.3 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) clear
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 20 (hr, min)
8. Total volume pumped 100
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.0

Conductivity 54 uhms/cm

Temperature 18.5 °C

Fractions Collected (circle): 8 CF 3 M RP CI RS H
O P 2 F 3 T R UP NE

MTG
Signed [Signature]

Date 11/19/85

Read and Understood By:

Signed [Signature]

Date [Signature]

WELL SAMPLING DATA

0128 NA 013 GN 85 0044

Well Sampling:

Well Number GW7-2 Time 1130

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 13.8 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469510

1. Depth of well 22.3 (ft)
2. Diameter of well 4 (inches)
3. Method of collection Bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped 30 (hr, min)
8. Total volume pumped 150
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 4.8


Conductivity 102 uhmos/cm

Temperature 18.4 °C

Fractions Collected (circle):

☒ G ☒ CF ☒ S ☒ M ☒ RP ☒ CI ☒ RS ☒ H
☒ P ☒ F ☒ T ☒ R ☒ U ☒ N

Read and Understood By:


 Signed _____ Date 1/18


 Signed _____ Date 1/18

WELL SAMPLING DATA

0128 NA 013 GN 85 0045

Well Sampling:

Well Number GW 7-3 Time 1300

Water Level in Well:

1. Distance from top of pipe to ground 2.5 (ft)
2. Held length (before pumping) _____ (ft)
3. Wet length (before pumping) _____ (ft)
4. Distance to water (before pumping) 12.7 (ft)
5. Held length (after pumping) _____ (ft)
6. Wet length (after pumping) _____ (ft)
7. Distance to water (after pumping) _____ (ft)

Sampling Information:

Sample Number 469517

1. Depth of well 22 (ft)
2. Diameter of well 4 (inches)
3. Method of collection bailer (bailer, hand pump, etc)
4. Depth or interval from which sample taken _____ (ft)
5. Appearance (clear, milky, color) _____
6. Approximate pumping rate: at start 5 (gpm)
at finish 5 (gpm)
7. Total time pumped pumped dry 2x (hr, min)
8. Total volume pumped _____
9. Field analysis performed:

Dissolved Oxygen _____ mg/l

pH 5.9Conductivity 260 uhms/cmTemperature 19.5 °C

Fractions Collected (circle):

☐ C ☐ CF ☒ S ☒ N ☒ M ☐ RP ☐ CI ☐ RS ☐ H
☐ O ☒ R ☒ Z ☐ F ☐ B ☐ T ☐ R ☒ UP ☒ NF

Read and Understood By:


Signed

Date

Signed

Date


Samples ATE & JDB



MAXWELL AFB ①
 0850
 collecting point SW 2-4
 5 2-6
 Sediment Collection point
 5 2-4
 @ 0917 CST
 1-17-85
 Water 2.4' at middepth
 2.5' at sides
 Collecting point ditch 10' across
 ~ 3' from end of ditch
 good flow due to rains

Samples collected at iron stake

Time 0850 hrs CST
 Stream \approx 4' depth in center, 2.5' on bank
 Water very turbid, brown color
 Water up due to rain
 Overcast
 Sediment samples collected under 2.5-3.0' water \approx 1 meter from east bank
 Water samples collected \approx 1.3 meter from east bank



Sediment S-2-4

collected at 0930 HRS CST

Stream \approx 4' deep in center

swollen by rain 25'

stream width \approx 25'

Stream muddy, good flow (not measured)

sample collected \approx 3' from east bank under 2.5' of water

Sediment S-2-5

collected South of bridge

adjacent to bridge at 0940 HR CST

stream conditions same as S-2-4

Stream width \approx 15' under bridge

sediment collected approx 3' from east bank of ditch under 2.5' of water


Surface runoff in to West end ditch

[Signature]
1-18-87

③

~~EST~~
S 2-11

Sediment



collector time S 2-11
= 1025 CST

sample collected $\approx 75'$ N of
bridge at point in ditch
after end of concrete liner
ditch $\approx 20'$ wide

4.5' deep in center


sampled $\approx 3'$ from western
bank


show flow in stream (unpercep^{tion})

overcast -

stream muddy, with oil
sheen ~~and~~ on top and
smell of oil

collectors = JD and $\frac{1}{2}$ AT ~~and~~ 1-18-83





SW 2-3

(surface water)

in West end ditch directly west
of GW 1-

S 2-3

Time = 11:35

CST

Stream ≈ 1.5 → 2' deep
≈ 10 ft width

Water samples at mid depth
sed ≈ 3' from east bank



(6)

S 2-2 1150 HRS

in west end ditch
adjacent to Well 1-3

sediment collected $\approx 3'$ from east bank
silty sand,
depth $\approx 2'$
width $\approx 15'$

Trailer + made park on other side of ditch

S 2-1 1155 HRS

- in west end ditch $\approx 40'$ south of well 1-4
- $\approx 3'$ from east bank
- $\approx 12'$ width
- bottom very sandy
depth 2'

 1-18-85


surface water

SW 2-2

1210 hrs CST

(7)

≈ 250' west of concrete portion of ditch,
at culvert entering ditch




[Signature] 1-18-85

(8)

Surface Water SW 2-1 1250 CST

ditch \approx 2' deep
3' wide
low or no flow
standing water
water dirty from
rains

one VOA
bottle
No septon
will collect
sample
later
collected
1400



Maxwell AFB

→ 
N 1-18-85

APPENDIX N--CHAIN-OF-CUSTODY DOCUMENTATION

STOREY MAP # 4577 GJA DD:
LAP COORD. TOM PARK

... FIELD LOGSHEET ...
FT. WAXWELL AFB

ENVIRONMENTAL SCIENCE & ENGINEERING
PROJECT NUMBER: H442514
JULY 1985
PROJECT

[illegible]

DATE	TIME	LOCATION	WIND	WAVE	SEA	TEMP	WIND	WAVE	SEA	TEMP
1969200	GW-1-1	B 3	C 2	N 2	N 2	1-18	6.6	75	19.2	

Q	B	C	V	N		
459201	0	0	0	0	1-18-85	170
GVI-2						
					48	203
					155	170

[illegible][illegible]

⑤ S ⑦ Z ⑧ NF 1510 4.7 11 12.1

969204
B B C L N W
S S Z Z N=NF

469205

NOTE -CHANGE OR ENTER SITE ID'S AS NECESSARY% UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED
-CIRCLE FRACTIONS COLLECTED. ENTER DATE, TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES
-HAZARD CODES: I=IGNITABLE C=CORROSIVE R=REACTIVE T=TOXIC WASTE H=OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN
-PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RECEIVED BY (NAME/ORGANIZATION/DATE/TIME)

RECEIVED BY	DATE	TIME	LOCATION	REMARKS
7202 90m	ESB	1400	1700	
COLD ROOM	Kelly, Craydall	ESB	1-21-85	25

1-19-85

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840

2014年12月

STOREY MAP # 4593 G4C DO:
LAB COORD. TOM PARK

185 *** FIELD LOGSHEET ***
 PROJECT NAME: HANVELL AFB

1637AS
FROJ

ENVIRONMENTAL SCIENCE & TECHNOLOGY
PROJECT NUMBER: P44201.6

[illegible]

67508
F03-1

(n) n c u N

① 2 NF 11F ② ③ ④ ⑤ ⑥ ⑦ ⑧ ⑨ ⑩ ⑪ ⑫ ⑬ ⑭ ⑮ ⑯ ⑰ ⑱ ⑲ ⑳ ㉑ ㉒ ㉓ ㉔ ㉕ ㉖ ㉗ ㉘ ㉙ ㉚ ㉛ ㉜ ㉝ ㉞ ㉟ ㊱ ㊲ ㊳ ㊴ ㊵ ㊶ ㊷ ㊸ ㊹ ㊺ ㊻ ㊼ ㊽ ㊾ ㊿

1-15-85

459502 (CV)-2

NO.	NAME	AGE	SEX	REL.	DATE	TIME	PLACE	REMARKS
1	1-13-83	1145	5.9	264	16.4			

069-1
C C S C M N W

	P	B	C	N	M
469504					
604=2					

2 2 MF NF

#69305
Cue=3
B B C C N W
O O S Ue UP

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	52
--	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	----

U	D	S	U ²	U ³	U ⁴
1	2	MF	MF	MF	MF

405630	1-5N5	CU5-1	1
1	1	1	1
2	2	2	2
3	3	3	3
4	4	4	4
5	5	5	5
6	6	6	6
7	7	7	7
8	8	8	8
9	9	9	9
10	10	10	10
11	11	11	11
12	12	12	12
13	13	13	13
14	14	14	14
15	15	15	15
16	16	16	16
17	17	17	17
18	18	18	18
19	19	19	19
20	20	20	20
21	21	21	21
22	22	22	22
23	23	23	23
24	24	24	24
25	25	25	25
26	26	26	26
27	27	27	27
28	28	28	28
29	29	29	29
30	30	30	30
31	31	31	31
32	32	32	32
33	33	33	33
34	34	34	34
35	35	35	35
36	36	36	36
37	37	37	37
38	38	38	38
39	39	39	39
40	40	40	40
41	41	41	41
42	42	42	42
43	43	43	43
44	44	44	44
45	45	45	45
46	46	46	46
47	47	47	47
48	48	48	48
49	49	49	49
50	50	50	50
51	51	51	51
52	52	52	52
53	53	53	53
54	54	54	54
55	55	55	55
56	56	56	56
57	57	57	57
58	58	58	58
59	59	59	59
60	60	60	60
61	61	61	61
62	62	62	62
63	63	63	63
64	64	64	64
65	65	65	65
66	66	66	66
67	67	67	67
68	68	68	68
69	69	69	69
70	70	70	70
71	71	71	71
72	72	72	72
73	73	73	73
74	74	74	74
75	75	75	75
76	76	76	76
77	77	77	77
78	78	78	78
79	79	79	79
80	80	80	80
81	81	81	81
82	82	82	82
83	83	83	83
84	84	84	84
85	85	85	85
86	86	86	86
87	87	87	87
88	88	88	88
89	89	89	89
90	90	90	90
91	91	91	91
92	92	92	92
93	93	93	93
94	94	94	94
95	95	95	95
96	96	96	96
97	97	97	97
98	98	98	98
99	99	99	99
100	100	100	100

ENVIRONMENTAL SCIENCE & ENGINEERING PROJECT NAME: MAXWELL AFB
 PROJECT NUMBER: 844231-2 DATE: TIME: AN. SUBSET PH SJ COND UN/CM M. TEMP C

STORY MAP # 4592 GAC
 LAB CODED. TCM MARK

ESF # SITE/STA HAZ2 FRACTIONS(CIRCLED) 11/10/85
 459512 EV6-1 N B C C N N
 0 0 S S U³ UP
 7 2 NF NF

459513 EV6-2 P B C C N N
 0 0 S S U³ UP
 2 2 NF NF

459514 EV6-3 P B C C S N
 0 0 S S U³ UP
 2 2 NF NF

459515 EV7-1 P B C C N N
 0 0 S S U³ UP
 2 2 NF NF

459516 EV7-2 B B C C N N
 0 0 S S U³ UP
 2 2 NF NF

459517 EV7-3 P B C C N N
 0 0 S S U³ UP
 2 2 NF NF

459518 B B C C N N
 0 0 S S U³ UP
 2 2 NF NF

459519 B B C C N N
 0 0 S S U³ UP
 7 2 NF NF

NOTE -CHANGE OR ENTER SITE ID'S AS NECESSARY UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED
 -CIRCLE FRACTIONS COLLECTED. ENTER DATE/TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES
 -HAZARD CODES: I-IGNITABLE C-CORROSIVE N-REACTIVE T-TOXIC A-ASTE H-OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN
 -PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RELINQUISHED BY: (NAME/ORGANIZATION/DATE/TIME) RECEIVED BY: (NAME/ORGANIZATION/DATE/TIME)

1 *20090-1ESE 11/10/85* *Federal Express - Tom Pak ESE 11/10/85*
 2
 3

OTHER FIELD NOTES:

ENVIRONMENTAL SCIENCE & ENGINEERING 01/09/85 PROJECT NAME: MAYN L AFB LOGSHEET *** STORET MAP # 4583 GJC JDI: 301
PROJECT NUMBER: 4423100 LAR COORD. TOM PARK

ESE # SITE/STA MAZ? FRACTIONS(CIRCLE) DATE TIME AV. SUBSET PH SJ COND J4/CM W. TEMP C
400 941 10

459500 G43-1 P R C C H N
O O S S UP UP
Z Z NF NF

459501 G43-2 R B C C V N
O O S S UP UP
Z Z NF NF

459502 G43-3 R B C C V N
O O S S UP UP
Z Z NF NF

459503 G44-1 P B C C H N
O O S S UP UP
Z Z NF NF

459504 G44-2 R B C C H N
O O S S UP UP
Z Z NF NF

459505 G44-3 R B C C H N
O O S S UP UP
Z Z NF NF

459506 G44-4 R B C C H N
O O S S UP UP
Z Z NF NF

459507 G45-1 P B C C H N
O O S S UP UP
Z Z NF NF

459508 G45-2 P B C C H N
O O S S UP UP
Z Z NF NF

459509 G45-3 R B C C H N
O O S S UP UP
Z Z NF NF

459510 G45-4 R B C C H N
O O S S UP UP
Z Z NF NF

459511 G45-5 R B C C H N
O O S S UP UP
Z Z NF NF

1-16-85 12.5 5.6 149 19.0

1-16-85 12.5 5.5 88 17.9

1-16-85 10.5 5.2 92 17.1

5.7 146 16.7

5.3 186 17.5

5.7 170 18.1

4.8 79 16.4

4.6 36 16.1

ENVIRONMENTAL SCIENCE & ENGINEERING PROJECT NAME: 469513 FIELD LOGSHEET *** DD: 4320 GWC
PROJECT NUMBER: 469513 LAB COORD: TOM PARK

ESE # SITE/STA HAZ? FRACTIONS(CIRCLED) DATE TIME AN. SUSSET PH SU COND JM/CM W. TEM C

469512 46-1 1-17-85 1000 5.9 430 17.2
469513 46-2 1-17-85 1200 4.8 241 18.2
469514 46-3 1-17-85 1105 5.7 336 18.3

469515 46-4 1-17-85 1105 5.7 336 18.3
469516 46-5 1-17-85 1105 5.7 336 18.3
469517 46-6 1-17-85 1105 5.7 336 18.3
469518 46-7 1-17-85 1105 5.7 336 18.3
469519 46-8 1-17-85 1105 5.7 336 18.3

NOTE -CHANGE OR ENTER SITE ID'S AS NECESSARY; UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED
-CIRCLE FRACTIONS COLLECTED. ENTER DATE, TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES
-HAZARD CODES: I=IGNITABLE C=CORROSIVE R=REACTIVE T=TOXIC W=OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN
-PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RELINQUISHED BY: (NAME/ORGANIZATION/DATE/TIME) RECEIVED BY: (NAME/ORGANIZATION/DATE/TIME)
1 Kelly Bergdoll ESE 1-21-85 0900
2
3

OTHER FIELD NOTES: See note sample 469513 469508

TH 0031

STREET MAP W 483 G4C
LAB COORD. T3M MARK

PROJECT NAME: M3V000 AFB

ENVIRONMENTAL SCIENCE - ENGINEERING 1/10/85

FILE LOCHESET ***
DATE 1-18-85

AV. SUBSET PM SJ COND JH/CM M. TEMP C

1100 911 10

469512 G4C-1 P B C C N N
O O S S UP
Z Z NF NF

469513 G4C-2 P B C C N N
O O S S UP
Z Z NF NF

469514 G4C-3 E B C C N N
O O S S UP
Z Z NF NF

469515 G4C-1 N B B C C N N
O O S S UP
Z Z NF NF

469516 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469517 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469518 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469519 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469520 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469521 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469522 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469523 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469524 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469525 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469526 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469527 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469528 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469529 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469530 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469531 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469532 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469533 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469534 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469535 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469536 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469537 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469538 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

469539 G4C-1 B B C C N N
O O S S UP
Z Z NF NF

469540 G4C-2 B B C C N N
O O S S UP
Z Z NF NF

469541 G4C-3 B B C C N N
O O S S UP
Z Z NF NF

NOTE -CHANGE OR ENTER SITE ID'S AS NECESSARY: UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED
-CIRCLE FRACTIONS COLLECTED. ENTER DATE, TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES
-HAZARD CODES: I=IGNITABLE C=CORROSIVE R=REACTIVE T=TOXIC WASTE H=OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN
-PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RECEIVED BY: (NAME/ORGANIZATION/DATE/TIME)

1-18-85 1700

2-18-85 1700

3-18-85 1700

OTHER FIELD NOTES:

Note sample 469515,

ENVIRONMENTAL SCIENCE & ENGINEERING 12/22/85 *** FIELD LOGSHEET *** STORET MAP # 473A MAKEP DD: PROJECT NAME: MAXWELL AFB LAB COORD.

PROJECT NUMBER: 84421105

USE #	SITE/STA	HAZ	FRACTIONS(CIRCLE)	DATE	TIME	AN. SUBSET
484900	U1-1A		C	12/17/84		
484901			C			
484902			C			

NOTE -CHANGE OR ENTER SITE ID'S AS NECESSARY UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED
-CIRCLE FRACTIONS COLLECTED. ENTER DATE, TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES
-HAZARD CODES: I=IGNITABLE C=CORROSIVE R=REACTIVE T=TOXIC WASTE H=OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN
-PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RELINQUISHED BY: (NAME/ORGANIZATION/DATE/TIME) RECEIVED BY: (NAME/ORGANIZATION/DATE/TIME)

1 G. Foster ESE TSM Pak ESE 12/21/84

2

3

OTHER FIELD NOTES:

ENVIRONMENTAL SCIENCE & ENGINEERING

PROJECT NUMBER: H420120

31/09/85

PROJECT NAME: MAXFILL AFB

STORET MAP # 4578 SEDE
LAB COORD. TOM PARK

DATE: 1-17-85

AV. SUBSET PH SJ

DATE	TIME	AV. SUBSET	PH	SJ
1-17-85	1155			
1-17-85	1150			
1-17-85	1135			
1-17-85	0930			
1-17-85	0950			
1-17-85	0850			
1-17-85	0917			
1-17-85	1050			
1-17-85	1100			
1-17-85	1045			
1-17-85	1035			

NOTE - CHANGE OR ENTER SITE ID'S AS NECESSARY: UP TO 6 ALPHANUMERIC CHARACTERS MAY BE USED

- CIRCLE FRACTIONS COLLECTED. ENTER DATE, TIME, FIELD DATA (IF REQUIRED), HAZARD CODE AND NOTES

- HAZARD CODES: I=IGNITABLE C=CORROSIVE R=REACTIVE T=TOXIC WASTE M=OTHER ACUTE HAZARD; IDENTIFY SPECIFICS IF KNOWN

- PLEASE RETURN LOGSHEETS WITH SAMPLES TO ESE

RECEIVED BY (NAME/ORGANIZATION/DATE/TIME)

1 Kelly England/ESE/1-21-85/0900

OTHER FIELD NOTES:

APPENDIX O--ADDITIONAL QA/QC DATA FOR CHEMICAL
ANALYSES

PGSUN REPORT FOR

SUMMARY REPORT FOR STORE1 95 0 SP.COND.LAB(UMHU/CH)

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

63.0000 63.0000 0.00

TOTAL # OF REPLICATES 1

PGSUN REPORT FOR
SUMMARY REPORT FOR STIMET 503 0 DILGR,IREMS/LJ

SPIKE ANALYSIS RESULTS

TARGET CONC.	FOUND CLAC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
18.2575	17.5051	95.8788	18.2575	17.1275	93.8106
18.2575	17.4020	95.7526	18.2575	17.4193	95.4093
AVERAGE Z RECOVERY=	95.21	STANDARD DEVIATION=	0.956	# OF SPIKES	4

FOCUS REPORT FOR

SUMMARY REPORT FOR SITE# 010 0 NITROGENOZ+NO3/ML-AS M)

SPINE ANALYSIS RESULTS
 TARGET CONC. 0.1250 Z RECOVERY 98.0175 FOUND CONC. 0.1292 Z RECOVERY 103.3376
 AVERAGE Z RECOVERY= 100.68 STANDARD DEVIATION= 3.762 # OF SPINES 2
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 0.0451 0.0251 0.00 0.5811 0.5933 2.09
 3.9323 4.0489 2.92
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 1.5543 1.6698 3
 TOTAL # OF REPLICATES 3

FGSN REPORT FOR

SUMMARY REPORT FOR STORET 000 0 CARBON, FOC (MG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 10.0000 FOUND CONC. 10.5500 Z RECOVERY 105.5000
 50.0000 52.9550 105.9100
 AVERAGE Z RECOVERY = 106.59 STANDARD DEVIATION = 1.541 # OF SPIKES 3
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 3.5400 3.9300 10.44 1.6854 1.7264 2.40
 37.0000 35.6000 6.21 3.1440 3.1960 1.64
 1.6406 1.0450 11.73
 AVERAGE CONCENTRATION 9.4187 AVERAGE Z DIFFERENCE # OF VALUES 5
 TOTAL # OF REPLICATES 5

FGSUN REPORT FOR

SUMMARY REPORT FOR STORLI 945 0 SULFATE (MG/L)

SPIKE ANALYSIS RESULT:
 TARGET CONC. 16.6667 FOUNO CONC. -0.0091 Z RECOVERY -0.5398 Z RECOVERY 75.2385
 1.9600 1.7724 90.3932 3.8462 4.0798 106.0740
 9.0909 10.7931 118.7240
 AVERAGE Z RECOVERY= 77.98 STANDARD DEVIATION= 46.839 # OF SPIKES 5
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 20.5133 18.4405 10.82 5.3587 4.5167 17.85
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 12.1931 13.9133 2
 TOTAL # OF REPLICATES 2

FUSION REPORT FOR

SUMMARY REPORT FOR STONE 951 0 FLUORIDE (MG/L)

SPIKE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
0.9901	1.1231	113.4361	0.9901	1.1173	112.8490
0.9901	0.9273	93.6608	0.9901	0.8910	89.9861

AVERAGE Z RECOVERY = 0.4593 86.7933
 99.35 STANDARD DEVIATION = 12.629 # OF SPIKES 5

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.3470	0.3511	1.17	1.4405	1.5352	6.36
0.0850	0.0605	0.41	0.0642	0.8406	2.78
0.0070	0.0868	1.22			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.5679 3.9076 5

TOTAL # OF REPLICATES 5

Q

FUSUM REPORT FOR

SUMMARY REPORT FOR STORET 1000 0 ARSENIC+DISSOLVED

SPINE ANALYSIS RESULTS
 TARGET CONC. 5.0000 FOUNO CONC. 5.4700
 5.0000 4.9371 2 RECOVERY 109.3993 TARGET CONC. 5.0000 FOUNO CONC. 5.7332 2 RECOVERY 114.6630
 5.0000 98.1423 5.0000 4.2447 64.8943
 AVERAGE 2 RECOVERY= 3.4212 76.4239
 96.82 STANDARD DEVIATION= 16.113 # OF SPINES 5
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B 2 DIFFERENCE REPLICATE A REPLICATE B 2 DIFFERENCE
 0.0286 0.0286 0.00 -0.1097 -0.1097 0.00
 0.1657 0.1630 12.51
 AVERAGE CONCENTRATION AVERAGE 2 DIFFERENCE # OF VALUES
 0.0312 4.1649 3
 TOTAL # OF REPLICATES 3

FUSION REPORT FOR

SUMMARY REPORT FOR STONE 1002 0 ARSENIC TOTAL (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 5.0000 FOUND CONC. 5.4624 Z RECOVERY 109.2470 Z RECOVERY 109.9195
 AVERAGE Z RECOVERY= 109.33 STANDARD DEVIATION= 0.110 # OF SPIKES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

-0.1097	-0.1097	0.00	0.0563	0.0563	0.00
0.1117	0.1117	0.00	0.2228	0.1673	28.49
0.7814	0.7814	0.00	24.8922	24.3151	2.35
47.8639	45.0066	6.15			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 10.2962 5.2836 7

TOTAL # OF REPLICATES 7

FGSON MFLUAT FOR

SUMMARY REPORT FOR STUDENT 1005 1 BARIUM-DISSOLU/L

SPINE ANALYSIS RESULTS
 TARGET CONC. 100.0000
 FOUND CONC. 57.3450
 Z RECOVERY 37.3450
 100.0000 100.0000 100.0000 100.0000 100.0000 100.0000
 100.0000 100.0000 100.0000 100.0000 100.0000 100.0000

AVERAGE Z RECOVERY= 93.7050
 90.26 STANDARD DEVIATION= 30.131 # OF SPINES 5

REPLICANT ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

871.4099	876.1299	0.53	27.6400	27.2200	1.53
49.2600	40.1800	18.84	30.1600	30.1200	0.13
25.4300	25.2600	0.47			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 200.3489 4.3403 5

TOTAL # OF REPLICATES 5

FGSM REPORT FOR

SUMMARY REPORT FOR STORE 1 1025 1 CADMIUM DISS (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 100.0000 FOUND CONC. 109.1950 Z RECOVERY 109.1950 TARGET CONC. 100.0000 FOUND CONC. 119.0600 Z RECOVERY 119.0600
 100.0000 114.1700 114.1700 100.0000 119.7350 119.7350

AVERAGE Z RECOVERY= 105.2950 105.2950 STANDARD DEVIATION= 6.247 # OF SPIKES 5

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

1-4900	1-0300	36.51	0.4400	1.8600	123.48
2-7100	0-0000	200.00	0.1500	1.2000	155.56
0-0500	0-2400	111.93			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.9970 125.4937 5

TOTAL # OF REPLICATES 5

FGSUM REPORT FOR
SUMMARY REPORT FOR STOKLI 1027 1 CADMIUM, TOTAL (UG/L)

SPINE ANALYSIS RESULTS		Z RECOVERY		TARGE CONC.		FOUND CONC.		Z RECOVERY	
TARGET CONC.	FOUND CONC.	109.1950	109.1950	100.0000	100.0000	119.0600	119.0600	119.0600	119.0600
100.0000	114.1700	114.1700	114.1700	100.0000	119.1350	119.1350	119.1350	119.1350	119.1350
AVERAGE Z RECOVERY = 105.2950		105.2950		105.2950		105.2950		105.2950	
STANDARD DEVIATION = 113.49		113.49		113.49		113.49		113.49	
REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT		REPLICATE A		REPLICATE B		REPLICATE A		REPLICATE B	
REPLICATE A		REPLICATE B		REPLICATE A		REPLICATE B		REPLICATE A	
1.4900	1.0300	36.51	0.4400	1.8600	1.8600	123.48	123.48	123.48	123.48
2.7100	0.8000	200.00	0.1500	1.2000	1.2000	155.56	155.56	155.56	155.56
0.6500	0.2400	111.93							
AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES		125.4937		125.4937		125.4937		125.4937	
0.9970		5		5		5		5	
TOTAL # OF REPLICATES		5		5		5		5	

SUMMARY REPORT FOR SITE 1030 1 CHROMIUM, DISS (UG/L)

SPIKE ANALYSIS RESULTS				Z RECOVERY		Z RECOVERY	
TARGET CONC.	FOUND CONC.	TARGET CONC.	FOUND CONC.	TARGET CONC.	FOUND CONC.	TARGET CONC.	FOUND CONC.
100.0000	100.0000	110.0000	105.0000	105.0000	105.0000	105.0000	105.0000
100.0000	103.0000	103.0000	100.0000	86.1150	86.1150	86.1150	86.1150
100.0000	96.9850	96.9850	100.0000	90.8250	90.8250	90.8250	90.8250
100.0000	96.7500	96.7500	100.0000	82.0150	82.0150	82.0150	82.0150

AVERAGE Z RECOVERY= 96.44 STANDARD DEVIATION= 9.444 # OF SPINES

REPLICATE ANALYSIS RESULTS FOR REPLICATES 1 DELIMITED		REPLICATE 1 DIFFERENCE		REPLICATE 2 DIFFERENCE	
REPLICATE A	REPLICATE B	REPLICATE A	REPLICATE B	REPLICATE A	REPLICATE B
1	2	3	4	5	6
7	8	9	10	11	12
13	14	15	16	17	18
19	20	21	22	23	24
25	26	27	28	29	30
31	32	33	34	35	36
37	38	39	40	41	42
43	44	45	46	47	48
49	50	51	52	53	54
55	56	57	58	59	60
61	62	63	64	65	66
67	68	69	70	71	72
73	74	75	76	77	78
79	80	81	82	83	84
85	86	87	88	89	90
91	92	93	94	95	96
97	98	99	100	101	102
103	104	105	106	107	108
109	110	111	112	113	114
115	116	117	118	119	120
121	122	123	124	125	126
127	128	129	130	131	132
133	134	135	136	137	138
139	140	141	142	143	144
145	146	147	148	149	150
151	152	153	154	155	156
157	158	159	160	161	162
163	164	165	166	167	168
169	170	171	172	173	174
175	176	177	178	179	180
181	182	183	184	185	186
187	188	189	190	191	192
193	194	195	196	197	198
199	200	201	202	203	204
205	206	207	208	209	210
211	212	213	214	215	216
217	218	219	220	221	222
223	224	225	226	227	228
229	230	231	232	233	234
235	236	237	238	239	240
241	242	243	244	245	246
247	248	249	250	251	252
253	254	255	256	257	258
259	260	261	262	263	264
265	266	267	268	269	270
271	272	273	274	275	276
277	278	279	280	281	282
283	284	285	286	287	288
289	290	291	292	293	294
295	296	297	298	299	300
301	302	303	304	305	306
307	308	309	310	311	312
313	314	315	316	317	318
319	320	321	322	323	324
325	326	327	328	329	330
331	332	333	334	335	336
337	338	339	340	341	342
343	344	345	346	347	348
349	350	351	352	353	354
355	356	357	358	359	360
361	362	363	364	365	366
367	368	369	370	371	372
373	374	375	376	377	378
379	380	381	382	383	384
385	386	387	388	389	390
391	392	393	394	395	396
397	398	399	400		

Account	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397</
---------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	--------

AVERAGE CONCENTRATION 1.1142
AVERAGE Z DIFFERENCE 74.7591
OF VALUES 6

TOTAL N. OF REPLICATES 6

FGSUN REPORT FOR

SUMMARY REPORT FOR STORE 1034 1 CHRONIUM, TOTAL (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 100.0000 FOUND CLAL 86.1150 Z RECOVERY 86.1150 FOUND CONC. 96.9850 Z RECOVERY 96.9850
 100.0000 90.8250 90.8250 100.0000 96.7500 96.7500
 100.0000 82.8150 82.8150
 AVERAGE Z RECOVERY= 90.70 STANDARD DEVIATION= 6.311 # OF SPINES 5
 REPLICATE ANALYSIS RESULTS FOR REPLICATES A DELTA 1000
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 0.3700 1.4000 116.10 0.0700 0.5200 152.54
 1.5500 2.9100 88.72 0.0000 0.0000 0.00
 0.1500 0.4000 90.91
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 1.3370 89.1109 5
 TOTAL # OF REPLICATES 5

FGSUM REPORT FOR

SUMMARY REPORT FOR SITE#1 1040 1 COPPER, DISSOLVED/L

SPIKE ANALYSIS RESULTS					
TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
100.0000	112.0000	112.0000	100.0000	110.0000	110.0000
100.0000	119.0000	119.0000	100.0000	97.0900	97.0900
100.0000	105.0050	105.0050	100.0000	99.8900	99.8900
100.0000	106.1950	106.1950	100.0000	93.4050	93.4050

AVERAGE Z RECOVERY = 105.33 STANDARD DEVIATION = 0.396 # OF SPIKES 8

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT

REPLICATE A	REPLICATE B	Z DIFFERENCE	REPLICATE A	REPLICATE B	Z DIFFERENCE
0.0000	0.0000	0.00	1.7200	1.9500	12.53
0.9900	1.5800	45.91	17.2900	16.3400	5.65
0.7900	0.5600	34.07	0.0900	0.5800	146.27

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

3.4900 40.7402 6

TOTAL # OF REPLICATES 6

FLUORIDE REPORT FOR

SUMMARY REPORT FOR SITE 1046 1 IRON, DESS (UG/L)

SPINE ANALYSIS RESULTS
 TARGET CONC. 100.0000
 FOUND CONC. 84.1700
 Z RECOVERY 84.1700
 Z RECOVERY 79.2250
 Z RECOVERY 100.0000
 Z RECOVERY 66.7550
 Z RECOVERY 100.6500
 Z RECOVERY 66.7550

AVERAGE Z RECOVERY = 83.20 STANDARD DEVIATION = 13.290 # OF SPINES 4

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE

36.2400 37.9600 4.44 16.9400 16.7800 12.09
 3564.8696 2960.5396 29.00 568.4696 569.6599 0.21

199.2500 200.1600 0.46

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 857.2066 9.2798 5

TOTAL # OF REPLICATES 5

FGSUN REPORT FOR

SUMMARY REPORT FOR STORE 1 1049 0 LEAD DISS (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 6.2500 FOUNO CONC. 5.5661 Z RECOVERY 89.0573 TARGET CONC. 25.0000 FOUNO CONC. 19.4309 Z RECOVERY 77.7236
 AVERAGE Z RECOVERY= 26.4304 105.1216
 AVERAGE Z RECOVERY= 50.83 STANDARD DEVIATION= 14.003 # OF SPIKES 3
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 0.7430 0.7430 0.00 5.1262 5.1262 0.00
 0.3073 0.3073 0.00
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 2.0591 0.0000 3
 TOTAL # OF REPLICATES 3

FUSION REPORT FOR

SUMMARY REPORT FOR STINKET 1051 0 LEAD, TOTAL (UG/L)

SPINE ANALYSIS RESULTS
 TARGET CONC. 19.3621
 25.0000
 20.1571
 83.91 STANDARD DEVIATION= 8.566 # OF SPIRES 3

25.0000
 20.1571
 83.91 STANDARD DEVIATION= 8.566 # OF SPIRES 3

REPLICABLE ANALYSIS RESULTS FOR REPLICATES > DEL-ATMII
 REPLICABLE A REPLICABLE B Z DIFFERENCE REPLICABLE A REPLICABLE B Z DIFFERENCE

7.7067 2.2271 19.51 16.9715 32.2652 13.59

9.0279 7.0719 24.30 23.0095 23.0095 0.00

6.0970 7.0719 14.79

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 14.9461 14.4401 5

TOTAL # OF REPLICATES 5

FUSUM REPORT FOR

SUMMARY REPORT FOR STONE 1065 1 NICKEL-DISSOLUG/L)

SPTIME ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
100.0000	96.1150	96.1150	100.0000	97.0400	97.0400
100.0000	93.5450	93.5450	100.0000	101.6750	101.6750

AVERAGE Z RECOVERY = 87.2500 87.2500 STANDARD DEVIATION = 5.293 # OF SPTIMS 5

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT

REPLICATE A	REPLICATE B	Z DIFFERENCE	REPLICATE A	REPLICATE B	Z DIFFERENCE
2.1900	1.4800	38.69	3.2200	2.1400	40.10
7.4000	3.9300	61.25	1.0700	4.0000	121.09

-0.2003 0.4600 507.69

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

2.6490 155.0046 5

TOTAL # OF REPLICATES 5

FOCUS REPORT FOR

SUMMARY REPORT FOR SITE 1067 1 MICHEL, Y. (UG/L)

SPIKE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
100.0000	96.1150	96.1150	100.0000	97.0400	97.0400
100.0000	93.5450	93.5450	100.0000	101.6750	101.6750

100.0000 87.2500 87.2500
 AVERAGE Z RECOVERY = 95.12 STANDARD DEVIATION = 5.293 # OF SPIKES 5

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

2.1900	1.4800	18.69	3.2200	2.1400	40.30
7.4000	3.9300	61.25	1.0700	4.8000	127.09
-0.2000	0.4400	507.69			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 2.6490 155.0046 5

TOTAL # OF REPLICATES 5

FGSM REPORT FOR

SUMMARY REPORT FOR STONE 1075 1 SILVER DISS (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 100.0000 FOUND CONC. 113.2100 Z RECOVERY 113.2100 Z RECOVERY 120.7900 Z RECOVERY 120.7900
 100.0000 117.7250 117.7250 100.0000 124.4150 124.4150
 100.0000 109.1350 109.1350
 AVERAGE Z RECOVERY= 117.05 STANDARD DEVIATION= 6.043 # OF SPIKES 5
 MULTIPLE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 1.5000 0.0000 200.00 1.5600 1.3800 12.24
 0.0100 0.1000 156.04 1.7950 0.9400 59.18
 0.6300 1.1200 56.00
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.9030 96.8930 5
 TOTAL # OF REPLICATES 5

FGSUN KLEPCHY FOM

SUMMARY REPORT FOR STORE# 1060 I ZINC DISS (UG/L)

SPIKE ANALYSIS RESULTS

	NET CONC.	FUND CONC.	Z RECOVERY	PURCH CONC.	FUND CONC.	Z RECOVERY
100.0000	100.0000	111.0000	111.0000	100.0000	100.0000	106.0000
100.0000	100.0000	121.0000	121.0000	100.0000	111.5150	117.5150
100.0000	100.0000	110.5100	110.5100	100.0000	118.1200	116.1200

100.0000	101.9700	101.9700	6.659	# OF SPINES
AVERAGE Z RECOVERY=		112.60	STANDARD DEVIATION=	

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMITED BY
REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0000	0.0000	0.00	659.6790	662.2198	0.36
-3.5500	0.0000	0.00	109.9500	81.8100	29.35
46.7200	46.7200	4.06	21.3200	22.2300	4.18

AVERAGE CONCENTRATION	AVERAGE Z DIFFERENCE	# OF VALUES
137.4299	6.3292	6

TOTAL # OF REPLICATES 6

FGSUM REPORT FOR

SUMMARY REPORT FOR STORET 1092 1 ZINC, TOTAL (UG/L)

SPINE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
100.0000	117.5150	117.5150	100.0000	110.5700	110.5700
100.0000	118.1200	118.1200	100.0000	101.9700	101.9700

AVERAGE Z RECOVERY= 112.8% STANDARD DEVIATION= 7.559 # OF SPINES 4

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT

REPLICATE A	REPLICATE B	Z DIFFERENCE	REPLICATE A	REPLICATE B	Z DIFFERENCE
659.6796	662.2198	0.38	-3.5500	0.0000	0.00
109.9500	81.4100	29.35	18.7200	46.7800	4.06
21.3200	22.2300	6.18			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
164.9159 7.5951 5

TOTAL # OF REPLICATES 5

EDSUM REPORT FOR
 SUMMARY REPORT FOR STORE 1 1145 1 SELENIUM-01SS(CG/L)

SPINE ANALYSIS RESULTS
 TARGET CONC. 5.0000 FOUND CLAC. 5.9558
 Z RECOVERY 119.3161
 AVERAGE Z RECOVERY= 113.32 STANDARD DEVIATION= 8.485 # OF SPINES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.1322	0.1322	0.00	0.1322	0.1322	0.00
0.1322	0.1322	0.00			
AVERAGE CONCENTRATION		AVERAGE Z DIFFERENCE	# OF VALUES		
0.1322		0.0000	3		
TOTAL # OF REPLICATES			3		

FGSM REPORT FOR

SUMMARY REPORT FOR STUNE1 32730 0 PHEOLS (UG/L)

SPIKE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
59.6421	61.0823	107.1093	59.6421	6.3826	107.0153
59.6421	61.2762	102.7432	59.6421	57.0505	95.6546
59.6421	64.1819	107.6116			

AVERAGE Z RECOVERY = 104.03 STANDARD DEVIATION = 5.075 # OF SPIKES 5

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DER-LIMIT

REPLICATE A REPLICATE B Z DIFFERENCE

6.0750	6.3043	3.70	3.7411	6.2174	11.97
6.8917	7.7457	13.78	1.5806	1.6541	4.55
9.3451	7.6980	19.33	2.1116	1.7407	19.25

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

5.0921 12.0961 6

TOTAL # OF REPLICATES 6

FGSUM REPORT FOR

SUMMARY REPORT FOR STUCL 39340 0 8HC/GALLINDANE (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 0.0230 FOUND CONC. 0.0156 Z RECOVERY 67.1364
 AVERAGE Z RECOVERY= 72.71 STANDARD DEVIATION= 3.037 N OF SPIKES 2
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 0.0010 0.0010 0.00
 TOTAL N OF REPLICATES 1

FOCUS REPORT FOR
SUMMARY REPORT FOR STOREI 39390 0 ENDRI (UG/L)

SPINE ANALYSIS RESULTS
TARGET CONC. 0.0342 2 RECOVERY 18.7637 2 RECOVERY 97.0721
0.0342 0.0399

AVERAGE 2 RECOVERY= 85.42 STANDARD DEVIATION= 9.410 # OF SPINES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
REPLICATE A REPLICATE B 2 DIFFERENCE REPLICATE A REPLICATE B 2 DIFFERENCE

0.0050 0.0050 0.00

TOTAL # OF REPLICATES 1

FGSM REPORT FOR

SUMMARY REPORT FOR STORE 1 39400 0 TORAPHENE (UG/L)

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.1200 0.1200 0.00

TOTAL N OF REPLICATES 1

FGSM REPORT FOR

SUMMARY REPORT FOR SITE 1 39480 0 METHOXYCHLOR (UG/L)

SPINE ANALYSIS RESULTS
 TARGET CONC. 0.2317 FOUND CONC. 0.2081 Z RECOVERY 89.8387 TARGET CONC. 0.2317 FOUND CONC. 0.2082 Z RECOVERY 89.8634
 AVERAGE Z RECOVERY= 89.85 STANDARD DEVIATION= 0.017 N OF SPINES 2
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 0.0300 0.0300 0.00
 TOTAL N OF REPLICATES 1

FGSUM REPORT FOR

SUMMARY REPORT FOR STONE 1 19730 0 2.4-0, TOTAL (UG/L)

SPINE ANALYSIS RESULTS
 TARGET CONC. 0.4060 FOUND CONC. 0.4029 Z RECOVERY 74.8159 TARGET CONC. 0.4061 FOUND CONC. 0.1701 Z RECOVERY 41.8402

AVERAGE Z RECOVERY= 56.23 STANDARD DEVIATION= 23.176 # OF SPINES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0303	0.0303	0.00	0.0303	0.0303	0.00
--------	--------	------	--------	--------	------

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.0303 0.0000 2

TOTAL # OF REPLICATES 2

FCSUM REPORT FOR

SUMMARY REPORT FOR STORE 1 39760 0 2445-TP/SILVER LUG/LJ

SPINE ANALYSIS RESULTS
 TARGET CONC. 0.0940 FOUND CONC. 0.0701 Z RECOVERY 74.5665 TARGET CONC. 0.0940 FOUND CONC. 0.0555 Z RECOVERY 69.8551

AVERAGE Z RECOVERY= 72.11 STANDARD DEVIATION= 3.472 # OF SPIRES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT
 REPLICATE A RECOVERY 8 Z DIFFERENCE REPLICATE A RECOVERY B Z DIFFERENCE

0.0000 0.0070 200.00 0.0070 0.0070 0.00

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.0052 100.0000 2

TOTAL # OF REPLICATES 2

FCSUM REPORT FOR

SUMMARY REPORT FOR STORET 70100 0 RESIDUE+DISS(MG/L)

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

1375.0000	1360.0000	0.95	86.0000	65.0000	3.47
51.0000	57.0000	11.11	65.0000	69.0000	5.97
123.0000	120.0000	2.47			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 339.1000 6.1940 5

TOTAL # OF REPLICATES 5

FGSUM REPORT FOR

SUMMARY REPORT FOR STURET 70353 0 TOR (UG/L-CL)

SPINE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
2.4999	2.0300	113.2032	2.4999	2.0200	112.0029

AVERAGE Z RECOVERY = 113.00 STANDARD DEVIATION = 0.203 # OF SPINES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

32.4000	31.3000	3.45	36.4000	24.2000	40.26
---------	---------	------	---------	---------	-------

AVERAGE CONCENTRATION	AVERAGE Z DIFFERENCE	# OF VALUES
31.0750	21.0500	2

TOTAL # OF REPLICATES 2

FGSUM REPORT FOR:

SUMMARY REPORT FOR SITE# 71090 0 MERCURY DISS. (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 5.0000 FOUND CONC. 4.3133 Z RECOVERY 86.2662 TARGET CONC. 5.0000 FOUND CONC. 4.6216 Z RECOVERY 92.4281

AVERAGE Z RECOVERY= 5.1265 102.5304
 STANDARD DEVIATION= 6.211 # OF SPIKES 3

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DELIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0429	0.0429	0.00	0.0429	0.0429	0.00
0.0429	0.0429	0.00	0.0429	0.0429	0.00
-0.0058	0.0421	241.02			

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.0400 48.2040 5

TOTAL # OF REPLICATES 5

FGSM REPORT FOR

SUMMARY REPORT FOR STUKEI 71900 0 MERCURY, TOTAL (UG/L)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 5.0000 FOUND CONC. 5.039% Z RECOVERY 100.7881 FOUND CONC. 3.9468 Z RECOVERY 78.9358

AVERAGE Z RECOVERY= 89.86 STANDARD DEVIATION= 15.452 # OF SPIKES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0318 0.0318 0.00 1.2536 1.1951 6.76

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.6201 2.3889 2

TOTAL # OF REPLICATES 2

FGSUN REPORT FOR

SUMMARY REPORT FOR STORET 721 0 CYANIDE SED (UG/G- DRY)

SPIKE ANALYSIS RESULTS
 TARGET CONC. 12.9870 FOUND CONC. 9.9221 Z RECOVERY 76.4000 TARGET CONC. 15.1515 FOUND CONC. 12.5000 Z RECOVERY 82.5000

AVERAGE Z RECOVERY= 79.45 STANDARD DEVIATION= 4.313 # OF SPIKES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0600	0.1300	73.60	0.4000	0.1000	54.55
--------	--------	-------	--------	--------	-------

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 0.3225 54.1140 2

TOTAL # OF REPLICATES 2

FGSDM REPORT FOR

SUMMARY REPORT FOR STUWET 1003 0 ARSENIC, SED (UG/G- DRY)

SPK ANALYSIS RESULTS
 TARGET CONC. 0.0050 FOUND CONC. 0.0056 Z RECOVERY 112.4292 Z RECOVERY 121.1323
 AVERAGE Z RECOVERY= 116.98 STANDARD DEVIATION= 6.324 # OF SPIKES 2
 REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET. LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE
 3.9915 3.9915 0.00 7.3424 0.1912 189.85
 3.2646 3.5340 7.87
 AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
 3.7189 65.9041 3
 TOTAL # OF REPLICATES 3

SUMMARY REPORT FOR STORE# 1020 1 CADMIUM,SED (UG/G-DAY)

SPIKE ANALYSIS RESULTS			
TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.
0.1000	0.1011	101.1200	0.1000
0.1000	0.1006	100.6450	0.1000
0.1000	0.1208	120.8400	0.1000
AVERAGE Z RECOVERY =		114.50	STANDARD DEVIATION =
		10.917	# OF SPIKES
		0.1263	Z RECOVERY
		126.2850	

AVERAGE % RECOVERY=	114.50	STANDARD DEVIATION=	10.917	# OF SPIRES	6
---------------------	--------	---------------------	--------	-------------	---

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
REPLIATE 1 REPLICATE 2 DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0122	0.0139	12.70	0.0032	0.0019	50.70
0.0010	0.0009	11.66	0.0052	0.0047	8.91
0.0022	0.0025	13.11	0.0009	0.0038	123.77
0.0019	0.0004	66.06	0.0006	0.0003	65.17
0.0031	0.0023	29.65	-0.0001	0.0003	333.33
0.0146	0.0135	7.26	0.0073	0.0069	6.07
0.0021	0.0000	200.00	0.0011	0.0013	10.88
0.0017	0.0001	180.33	0.0001	0.0035	187.91
0.0008	0.0000	200.00	0.0007	0.0023	101.66
0.2699	0.2692	0.28	0.0016	0.0016	4.33
0.0054	0.0079	10.20	0.0101	0.0089	12.27
0.0053	0.0041	24.52	0.0119	0.0129	8.70
0.0233	0.0225	3.41	0.0084	0.0131	42.98
0.0302	0.0340	11.04	0.0197	0.0189	4.41
0.0237	0.0251	5.66	0.0086	0.0094	8.20
0.0089	0.0106	12.19	0.0116	0.0103	11.13

	AVERAGE CONCENTRATION	AVERAGE Σ DIFFERENCE	# OF VALUES
1	0.0000	0.0000	1
2	0.0000	0.0000	1
3	0.0000	0.0000	1
4	0.0000	0.0000	1
5	0.0000	0.0000	1
6	0.0000	0.0000	1
7	0.0000	0.0000	1
8	0.0000	0.0000	1
9	0.0000	0.0000	1
10	0.0000	0.0000	1
11	0.0000	0.0000	1
12	0.0000	0.0000	1
13	0.0000	0.0000	1
14	0.0000	0.0000	1
15	0.0000	0.0000	1
16	0.0000	0.0000	1
17	0.0000	0.0000	1
18	0.0000	0.0000	1
19	0.0000	0.0000	1
20	0.0000	0.0000	1
21	0.0000	0.0000	1
22	0.0000	0.0000	1
23	0.0000	0.0000	1
24	0.0000	0.0000	1
25	0.0000	0.0000	1
26	0.0000	0.0000	1
27	0.0000	0.0000	1
28	0.0000	0.0000	1
29	0.0000	0.0000	1
30	0.0000	0.0000	1
31	0.0000	0.0000	1
32	0.0000	0.0000	1
33	0.0000	0.0000	1
34	0.0000	0.0000	1
35	0.0000	0.0000	1
36	0.0000	0.0000	1
37	0.0000	0.0000	1
38	0.0000	0.0000	1
39	0.0000	0.0000	1
40	0.0000	0.0000	1
41	0.0000	0.0000	1
42	0.0000	0.0000	1
43	0.0000	0.0000	1
44	0.0000	0.0000	1
45	0.0000	0.0000	1
46	0.0000	0.0000	1
47	0.0000	0.0000	1
48	0.0000	0.0000	1
49	0.0000	0.0000	1
50	0.0000	0.0000	1
51	0.0000	0.0000	1
52	0.0000	0.0000	1
53	0.0000	0.0000	1
54	0.0000	0.0000	1
55	0.0000	0.0000	1
56	0.0000	0.0000	1
57	0.0000	0.0000	1
58	0.0000	0.0000	1
59	0.0000	0.0000	1
60	0.0000	0.0000	1
61	0.0000	0.0000	1
62	0.0000	0.0000	1
63	0.0000	0.0000	1
64	0.0000	0.0000	1
65	0.0000	0.0000	1
66	0.0000	0.0000	1
67	0.0000	0.0000	1
68	0.0000	0.0000	1
69	0.0000	0.0000	1
70	0.0000	0.0000	1
71	0.0000	0.0000	1
72	0.0000	0.0000	1
73	0.0000	0.0000	1
74	0.0000	0.0000	1
75	0.0000	0.0000	1
76	0.0000	0.0000	1
77	0.0000	0.0000	1
78	0.0000	0.0000	1
79	0.0000	0.0000	1
80	0.0000	0.0000	1
81	0.0000	0.0000	1
82	0.0000	0.0000	1
83	0.0000	0.0000	1
84	0.0000	0.0000	1
85	0.0000	0.0000	1
86	0.0000	0.0000	1
87	0.0000	0.0000	1
88	0.0000	0.0000	1

U-6157 56-2360 32

TOTAL & UF REPLICATES 32

FUSION REPORT FOR

SUMMARY REPORT FOR STONE 1029 1 CHRONOMETERED (UG/G- GRAY)

SPIKE ANALYSIS RESULTS											
TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY						
0.1000	0.0955	98.4500	0.1000	0.1013	101.2750	0.1000	0.1000	0.1207	0.1050	120.6600	105.1900
0.1000	0.1020	102.8300	0.1000	0.1020	102.8300	0.1000	0.1000	0.1112	0.1112	111.1700	111.1700
AVERAGE Z RECOVERY=		106.70 STANDARD DEVIATION=									
REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF-LIMIT											
REPLICATE A			REPLICATE B			REPLICATE A			REPLICATE B		
Z DIFFERENCE			Z DIFFERENCE			Z DIFFERENCE			Z DIFFERENCE		
0.0162	0.0181	11.26	0.0016	0.0019	17.54	0.0025	0.0025	70.18	0.0082	31.44	26.82
0.0037	0.0021	52.67	0.0051	0.0120	0.0050	0.0023	0.0204	23.70	0.0012	23.98	12.72
0.0060	0.0064	6.58	0.0120	0.0030	0.0008	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0059	0.0034	51.77	0.0030	0.0030	0.0008	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0025	0.0022	13.39	0.0008	0.0008	0.0008	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0161	0.0130	21.17	0.0197	0.0009	0.0009	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0035	0.0012	98.28	0.0009	0.0009	0.0009	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0031	0.0040	43.02	0.0041	0.0121	0.0121	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.0031	0.0036	15.07	0.0121	0.0121	0.0121	0.0197	0.0009	0.0012	0.0138	4.15	4.53
1.0680	1.0677	0.08	0.0610	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.1471	0.1401	0.68	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.1062	0.1153	8.29	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.5142	0.5422	5.29	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.4793	0.4939	3.01	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.7176	0.7258	1.14	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
0.4829	0.4673	1.19	0.3005	0.3005	0.3005	0.0197	0.0009	0.0012	0.0138	4.15	4.53
AVERAGE CONCENTRATION			AVERAGE Z DIFFERENCE			# OF VALUES					
0.1992			20.7474			32					
TOTAL # OF REPLICATES			32								

FGSUN REPORT FOR

SUMMARY REPORT FOR STORET

1043 1 COPPER, SED (UG/G- DRY)

SPIKE ANALYSIS RESULTS						103.40 STANDARD DEVIATION=						10.344 # OF SPIKES					
TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	Z RECOVERY	FOUND CONC.	Z RECOVERY	TARGET CONC.	Z RECOVERY	TARGET CONC.	Z RECOVERY	FOUND CONC.	Z RECOVERY	TARGET CONC.	Z RECOVERY	FOUND CONC.	Z RECOVERY	
0.1000	0.0928	92.8500	0.1000	0.0993	99.2950	0.0928	0.1000	0.1000	0.1000	0.1033	103.3450	0.1126	0.1000	0.0937	93.6650	0.1000	
0.1000	0.1164	116.4000	0.1000	0.1164	116.4000	0.1164	0.1000	0.1000	0.1000	0.1033	103.3450	0.1126	0.1000	0.0937	93.6650	0.1000	
AVERAGE Z RECOVERY=						103.40 STANDARD DEVIATION=						10.344 # OF SPIKES					
REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET.LIMIT																	
REPLICATE A						REPLICATE B						Z DIFFERENCE					
0.0260						0.0277						0.79					
0.0004						0.0015						114.56					
0.0101						0.0100						1.19					
0.0100						0.0070						36.33					
0.0036						0.0050						31.16					
0.0663						0.0660						0.48					
0.0077						0.0096						22.56					
0.0076						0.0064						17.87					
0.0165						0.0101						9.06					
0.3950						0.3965						0.89					
0.1775						0.1798						1.29					
0.0074						0.0943						7.57					
0.6963						0.7327						5.09					
0.7966						0.6219						2.87					
0.7291						0.7289						0.02					
0.2375						0.2342						1.41					

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

0.2075 12.5643 32

TOTAL # OF REPLICATES 32

FUSUM REPORT FOR

SUMMARY REPORT FOR STORE 1052 1 LEAD-SED (UG/G-DRY)

SPINE ANALYSIS RESULTS
 TARGET CONC. 0.1000 FOUND CONC. 0.0869 Z RECOVERY 86.9050
 0.1000 0.0939 93.9000
 0.1000 0.1053 105.2949
 AVERAGE Z RECOVERY= 101.33 STANDARD DEVIATION= 14.750 # OF SPINES 6

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.0086	0.0014	143.46	-0.0110	0.0000	0.00
-0.0002	0.0000	0.00	0.0172	0.0062	93.69
-0.0106	0.0055	0.00	0.0198	0.0225	12.72
0.0058	0.0000	200.00	-0.0077	0.0017	0.00
0.0132	0.0027	131.49	-0.0059	0.0000	0.00
0.1082	0.1051	2.90	0.1157	0.1608	2.89
-0.0240	0.0000	0.00	-0.0082	0.0000	0.00
0.0010	0.0000	200.00	0.0011	0.0115	163.69
0.0156	0.0110	35.13	0.0028	0.0207	152.32
5.8900	5.8335	0.96	0.1573	0.1753	10.82
1.1239	1.1510	2.56	1.5633	1.6664	6.39
0.3053	0.3696	1.16	3.3498	3.5919	6.98
2.4434	2.6278	7.27	1.3284	1.2119	7.14
3.4614	3.7327	7.54	9.3473	9.3271	0.22
7.0259	7.0556	0.38	1.2096	1.1809	2.40
1.3548	1.1270	2.08	2.3361	2.2168	5.24

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

1.3202 37.8826 32

TOTAL # OF REPLICATES 32

FUSUM REPORT FOR

SUMMARY REPORT FOR STORE# 1049 1 MICHEL, SED (UG/G- DRT)

SPIKE ANALYSIS RESULTS			
TARGET CONC.	FOUND CONC.	Z RECOVERY	Z RECOVERY
0.1000	0.0865	86.4950	116.4950
0.1000	0.1010	100.9550	100.2850
0.1000	0.1015	101.4600	97.3900

AVERAGE Z RECOVERY= 101.91 STANDARD DEVIATION= 10.784 # OF SPIKES 6

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF.LIMIT

REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

0.1667	0.1616	3.13	0.0028	0.0031	12.52
0.0087	0.0083	5.18	0.0228	0.0219	4.82
0.0500	0.0517	3.34	0.0166	0.0165	9.89
0.0413	0.0400	3.05	0.0479	0.0456	4.81
0.0100	0.0079	23.96	-0.0035	0.0024	305.82
0.2830	0.2793	1.31	0.3519	0.3563	1.24
0.0070	0.0095	30.17	0.0046	0.0061	24.26
0.0087	0.0098	12.74	0.0056	0.0062	10.01
0.0049	0.0126	34.42	0.0344	0.0383	10.71
0.9432	0.9317	1.23	0.0267	0.0302	12.23
0.1750	0.1739	0.44	0.0508	0.0563	10.26
0.0195	0.0241	21.18	0.0978	0.1003	2.56
0.1665	0.1586	6.27	0.1413	0.1631	10.21
0.1891	0.1962	3.71	0.2741	0.2700	1.50
0.1871	0.1854	0.95	0.1226	0.1200	2.09
0.1586	0.1568	1.17	0.1413	0.1401	0.85

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES

0.1190 17.9769 32

TOTAL # OF REPLICATES 32

FGSUM REPORT FOR

SUMMARY REPORT FOR STONEY 1093 1 ZINC-SED (UG/G-DRY)

SPINE ANALYSIS RESULTS
TARGET CONC. 0.1000 FOUND CONC. 0.1134 Z RECOVERY 113.3400 Z RECOVERY 95.6350

AVERAGE Z RECOVERY= 104.50 STANDARD DEVIATION= 12.533 # OF SPINES 2

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF.LIMIT
REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

14.3118	14.3118	0.00	0.0264	0.0509	76.27
0.8421	0.8706	3.35	4.1203	4.1189	0.04
6.3492	6.4033	2.09	2.1700	2.1079	0.46
7.1965	7.1493	0.66	6.0081	6.0126	0.06
1.4469	1.4365	0.72	0.0706	0.0161	41.35
146.8278	144.7201	1.45	174.3127	176.0262	0.16
0.0283	0.9177	188.02	0.0844	0.7270	158.43
0.1554	0.0755	139.72	0.0195	0.6682	166.66
0.0444	0.6658	173.96	1.9076	2.4542	25.06
396.1058	396.3146	0.05	2.0324	1.6894	7.10
2.7576	3.0183	9.03	0.6661	0.7307	6.29
0.1865	0.2054	9.64	1.5133	1.6025	5.73
2.8726	3.0232	5.11	1.8077	1.9040	5.19
4.4018	4.7409	6.07	8.1190	8.0928	0.32
3.2451	3.2663	0.65	1.1612	1.1528	0.73
1.1287	1.1008	2.51	2.1727	2.1315	1.92

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE # OF VALUES
24.9219 33.1554 32

TOTAL # OF REPLICATES 32

FGSM REPORT FOR

SUMMARY REPORT FOR STONE 1 10320 0 MOISTURE/CMET M13

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DET-LIMIT				
REPLICATE A	REPLICATE B	Z DIFFERENCE	REPLICATE A	REPLICATE B
2.0000	2.0000	0.00	1.0000	1.0000
2.0000	2.0000	0.00	1.0000	1.0000
1.0000	1.0000	0.00	1.0000	1.0000
AVERAGE CONCENTRATION		AVERAGE Z DIFFERENCE	# OF VALUES	
1.0000		0.0000	5	
TOTAL # OF REPLICATES		5		

FCSUR REPORT FOR

SUMMARY REPORT FOR STORET 71921 1 MERCURY, SED (UG/G- DRY)

SPINE ANALYSIS RESULTS						
TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY	
0.1000	0.0912	81.2400	0.1000	0.1215	121.4100	
0.1000	0.1064	106.4050	0.1000	0.1095	109.4800	
0.1000	0.1023	102.3450	0.1000	0.1049	104.9150	
AVERAGE Z RECOVERY=		106.31 STANDARD DEVIATION=		13.130 # OF SPINES 4		
REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF-LIMIT						
REPLICATE A		REPLICATE B		REPLICATE A		REPLICATE B
Z DIFFERENCE	Z DIFFERENCE	Z DIFFERENCE	Z DIFFERENCE	Z DIFFERENCE	Z DIFFERENCE	Z DIFFERENCE
-0.0073	0.0000	0.00	-0.0106	0.0000	0.00	0.00
-0.0113	0.0000	0.00	-0.0130	0.0000	0.00	0.00
-0.0075	0.0000	0.00	-0.0124	0.0000	0.00	0.00
-0.0100	0.0000	0.00	-0.0103	0.0000	0.00	0.00
-0.0091	0.0000	0.00	-0.0152	0.0000	0.00	0.00
-0.0145	0.0000	0.00	-0.0144	0.0000	0.00	0.00
-0.0180	0.0000	0.00	-0.0100	0.0000	0.00	0.00
-0.0152	0.0000	0.00	-0.0091	0.0000	0.00	0.00
-0.0182	0.0000	0.00	-0.0037	0.0000	0.00	0.00
0.0050	0.0047	7.39	-0.0134	0.0000	0.00	0.00
-0.0109	0.0000	0.00	-0.0001	0.0000	0.00	0.00
-0.0079	0.0000	0.00	-0.0063	0.0000	0.00	0.00
0.0116	0.0057	69.13	-0.0023	0.0000	0.00	0.00
0.0000	0.0033	119.80	0.0076	0.0048	36.55	0.00
-0.0016	0.0015	0.00	-0.0070	0.0000	0.00	0.00
0.0002	0.0014	158.70	0.0064	0.0009	148.09	0.00
AVERAGE CONCENTRATION				AVERAGE Z DIFFERENCE # OF VALUES		
-0.0032				16.8644 32		
TOTAL # OF REPLICATES				32		

FGSUM REPORT FOR

SUMMARY REPORT FOR STINLET 99344 0 TUE+SED (UG/S-0PT)

SPIKE ANALYSIS RESULTS

TARGET CONC.	FOUND CONC.	Z RECOVERY	TARGET CONC.	FOUND CONC.	Z RECOVERY
530.3030	549.3199	103.5860			

REPLICATE ANALYSIS RESULTS FOR REPLICATES > DEF.LIMIT
 REPLICATE A REPLICATE B Z DIFFERENCE REPLICATE A REPLICATE B Z DIFFERENCE

553.5833	334.3923	5.58	183.0723	211.6788	14.49
----------	----------	------	----------	----------	-------

AVERAGE CONCENTRATION AVERAGE Z DIFFERENCE N OF VALUES
 270.4886 10.0362 2

TOTAL N OF REPLICATES 2

APPENDIX P--ANALYTICAL RESULTS FOR GROUND WATERS
AND SURFACE WATERS

ENVIRONMENTAL SCIENCE & ENGINEERING				STATUS: FINAL			
PROJECT NUMBER 84120100				PROJECT NAME MAXWELL AFB			
FIELD GROUP: CHA				PROJECT MANAGER: JOHN BOND			
PARAMETERS: ALL SAMPLES: ALL				FIELD GROUP LEADER: TOM PARK			
PARAMETERS	STORET #	GWI-1	GWI-2	GWI-3	GWI-4	SAMPLE NUMBERS	
DATE	METHOD #	1/18/85	1/18/85	1/18/85	1/18/85		
TIME		1400	1515	1645	1545		
PH, FIELD (STD UNITS)	400	6.80	6.80	5.80	6.90		
CADMIUM, DISS (UG/L)	1025	<3.0	<3.0	<3.0	<3.0		
CHROMIUM, DISS (UG/L)	1030	<6.0	<6.0	<6.0	<6.0		
COPPER, DISS (UG/L)	1040	<3.0	<3.0	<3.0	<3.0		
NICKEL, DISS (UG/L)	1065	<9.0	<9.0	<9.0	<9.0		
ZINC, DISS (UG/L)	1090	<3.0	21.0	56.0	12.0		
CARBON, TOC (MG/L)	680	2.5	5.1	2.7	4.4		
PHENOLS (UG/L)	32730	12	4	4	7		
RESIDUE, DISS (MG/L)	70300	54	153	26	80		
SP. COND., FIELD (UMHOS/CM)	94	75.0	203	95.0	77.0		
WATER TEMP (C)	10	19.2	17.0	18.1	17.5		
CYANIDE (UG/L)	99315	<10	<10	<10	<10		

ENVIRONMENTAL SCIENCE & ENGINEERING

PROJECT NUMBER: 04420100

FIELD GROUP: GMC

PARAMETERS: ALL SAMPLES: ALL

04/11/85

STATUS: FINAL

PROJECT NAME: MAXWELL AFB
PROJECT MANAGER: JOHN BORDS
FIELD GROUP LEADER: TOM PARK

PARAMETERS	STORET #	DATE	TIME	PH	FIELD(SD UNITS)	GWS-1 469500 1/15/85	GWS-2 469501 1/15/85	GWS-3 469502 1/15/85	GWS-1 469503 1/16/85	GWS-2 469504 1/16/85	GWS-3 469505 1/16/85	GWS-1 469507 1/17/85	GWS-2 469508 1/16/85	GWS-3 469509 1/16/85	GWS-4 469510 1/17/85
PH	400			7.00		17.00	15.80	11.45	12.45	12.15	10.30	18.00	16.45	16.00	15.45
ARSENIC DISS (UG/L)	1000			5.40		5.40	5.20	5.90	5.40	5.50	5.20	5.70	5.30	5.70	4.80
BARIUM DISS (UG/L)	1005			<1		<1	<1	<1	<1	<1	<1	<1	<1	<1	<1
CAIUM DISS (UG/L)	1025			3.0		3.0	3.0	3.3	7.4	3.2	2.2	1.9	4.1	2.5	2.6
COPPER DISS (UG/L)	1040			<3.0		<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0
CHROMIUM DISS (UG/L)	1030			<3.0		<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0
IRON DISS (UG/L)	1046			<6.0		<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
MERCURY DISS (UG/L)	71890			5.68		5.68	7.0	9.1	5	<4	<4	6.0	2.2	1.99	2.53
NICKEL DISS (UG/L)	1065			<0.2		<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
LEAD DISS (UG/L)	1049			<9.0		<9.0	<9.0	<9.0	<9.0	<9.0	<9.0	<9.0	<9.0	<9.0	<9.0
SILVER DISS (UG/L)	1075			<20.0		<20.0	<20.0	<20.0	<20.0	<20.0	<20.0	<20.0	<20.0	<20.0	<20.0
ZINC DISS (UG/L)	1090			<5.0		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
	1090			48.1		48.1	<3.0	17.0	5.6	<3.0	<3.0	<3.0	10.6	21.3	<3.0

NITROGEN+NO ₂ +NO ₃ (MG/L-AS N)	630	0.085	0.712	0.655	0.802	0.567	0.749	0.462	0.252	0.597	1.03
SULFATE (MG/L)	945	41	14	43	80	60	150	18	27	44	11
RESIDUE+ACISSING/L)	70300	101	55	145	121	69	76	92	122	150	63
PHENOLS (UG/L)	32730	6	41	6	8	1	3	3	2	5	2
OIL+GR+TRING/L)	540	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TOX (UG/L-CL)	70353	32	25	21	26	20	16	34	32	36	49
CARBON+TOC(MG/L)	660	3.5	1.4	3.2	4.9	1.9	2.8	1.4	3.4	3.2	<1.4
CHORIN (UG/L)	39190	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
	0										

ENVIRONMENTAL SCIENCE & ENGINEERING
 PROJECT NUMBER 84420100
 FIELD GROUP: GNC
 PARAMETERS: ALL SAMPLES: ALL

04/11/85

STATUS: FINAL

PROJECT NAME: HAYWELL AFB
 PROJECT MANAGER: JOHN BOUNDS
 FIELD GROUP LEADER: TOM PARK

PARAMETERS	STORE #	DATE	TIME	GM3-1	GM3-2	GM3-3	GM4-1	GM4-2	GM4-3	GM5-1	GM5-2	GM5-3	GM5-4
				1/15/85	1/15/85	1/15/85	1/16/85	1/16/85	1/16/85	1/17/85	1/16/85	1/16/85	1/17/85
BHC+GLINDANE(UG/L)	39340			<0.001	1530	1145	1245	1215	1030	1800	1645	1600	1545
METHOXYCHLOR (UG/L)	39400			<0.027	1.3	0.17	<0.001	<0.001	<0.001	0.17	0.26	1.3	1.5
FORAPHENE (UG/L)	39400			<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12
Zn-0, TOTAL (UG/L)	39330			<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030
Zn-5-IP/SILVER (UG/L)	39360			<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007
FLUORIDE (MG/L)	951			0.15	<0.10	0.11	<0.10	<0.10	0.12	0.14	<0.10	<0.10	<0.10
SP-COND. FIELD (UMHOS/CM)	94			91.0	67.0	264	149	88.0	92.0	146	186	170	79.0
WATER TEMP (C)	10			17.0	17.6	16.4	19.0	19.9	17.1	16.7	17.5	16.1	16.6
SELENIUM+DISS(UG/L)	1145			<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
CYANIDE(UG/L)	99315			<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

NITROGEN+NO ₂ +NO ₃ (MG/L-AS N)	630	0.360	0.604	3.78	1.50	2.43	1.37	0.581
SULFATE (MG/L)	0	30	14	48	226	7	23	65
RESIDUE+DISS(MG/L)	70300	74	304	262	224	51	71	136
PHENOLS (UG/L)	12730	3	3	2	3	1	3	3
OIL+GR+ING(MG/L)	560	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
TOX (UG/L-CL)	70353	23	14	24	36	12	30	10
CARBON+TC(MG/L)	680	<1.4	15.7	12.6	5.1	2.4	<1.7	3.9
EMORIN (UG/L)	39190	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
	0							

ENVIRONMENTAL SCIENCE & ENGINEERING

PROJECT NUMBER: 04420100

FIELD GROUP: GUC

PARAMETERS: ALL SAMPLES: ALL

04/11/85

STATUS: FINAL

PROJECT NAME: MARSHALL AFB
PROJECT MANAGER: JOHN BONDS
FIELD GROUP LEADER: TOM PARK

PARAMETERS	STORET #	METHOD #	DATE	TIME	GW6-5 469511	GW6-1 469512	GW6-2 469513	GW6-3 469514	GW7-1 469515	GW7-2 469516	GW7-3 469517
			1/17/85	1645	1800	1230	1315	1015	1130	1300	
BHC, GILINDANE (UG/L)	39340	0		0.34	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001
METHOXYCHLOR (UG/L)	39480	0		<0.027	<0.027	<0.027	<0.027	<0.027	<0.027	<0.027	<0.027
TOXAPHENE (UG/L)	39400	0		<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12	<0.12
2,4-D, TOTAL (UG/L)	39730	0		<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030	<0.030
2,4,5-TP/SILVER (UG/L)	39760	0		<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007
FLUORIDE (MG/L)	951	0		<0.10	0.14	<0.10	<0.10	<0.10	0.11	1.09	
SP. COND. FIELD (UMHOS/CM)	94	0		36.0	430	241	336	56.0	102	260	
WATER TEMP (C)	10	0		16.1	17.2	18.2	18.3	16.5	18.4	19.9	
SELENIUM, DISS (UG/L)	1145	0		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
CYANIDE (UG/L)	99315	0		<10	<10	<10	<10	<10	<10	<10	<10

ENVIRONMENTAL SCIENCE & ENGINEERING

PROJECT NUMBER 44420100

FIELD GROUP: SUB

PARAMETERS: ALL SAMPLES: ALL

STATUS: FINAL

PROJECT NAME MAXWELL AFB
PROJECT MANAGER: JOHN BOWDS
FIELD GROUP LEADER: VON PARK

SAMPLE NUMBERS

PARAMETERS	STORE #	SW2-1	SW2-2	SW2-3	SW2-4
DATE	METHOD	1/17/85	1/17/85	1/17/85	1/17/85
TIME		1400	1210	1135	050
PH, FIELO (STD UNITS)	400	NA	NA	NA	NA
ARSENIC, TOTAL (UG/L)	1002	6.0	23	30	25
CADMIUM, TOTAL (UG/L)	1022	<3.0	<3.0	<3.0	<3.0
CHROMIUM, TOTAL (UG/L)	1034	<6.0	6.1	<6.0	7.5
MERCURY, TOTAL (UG/L)	71900	<0.2	<0.2	<0.2	0.7
NICKEL, 1, (UG/L)	1067	<9.0	<9.0	<9.0	<9.0
LEAD, TOTAL (UG/L)	1051	26.1	25.0	30.2	37.0
ZINC, TOTAL (UG/L)	1092	57	117	66	110
RESIDUE, C155 (MG/L)	70300	67	87	82	68
PHENOLS (UG/L)	32730	8	8	6	11
BILEGB, IR (MG/L)	560	<0.1	0.8	0.8	0.9
TOX (UG/L-CL)	70353	88	80	82	45

CARBON, TDC (MG/L)	600	11.9	12.8	12.9	13.5
SP. COND., LAB (UMH/CM)	0	63.0	96.8	82.8	63.0
WATER TEMP (C)	95	NA	NA	NA	NA
SP. COND., FIELD (UMH/CM)	10	NA	NA	NA	NA
CYANIDE (UG/L)	0	NA	NA	NA	NA
	99315	<10	<10	<10	<10
	0				

ENVIRONMENTAL SCIENCE & ENGINEERING
PROJECT NUMBER: 88N20100
FIELD GROUP: SED
PARAMETERS: ALL SAMPLES: ALL

06/11/85

STATUS: FINAL

PROJECT NAME: MARWELL AFB
PROJECT MANAGER: JOHN BOND
FIELD GROUP LEADER: TOM PARK

PARAMETERS	STORE #	52-1	52-2	52-3	52-4	52-5	52-6	52-7	52-8	52-9	52-10
DATE	METHOD #	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85	1/17/85
TIME		1155	1150	1135	930	910	850	917	1050	1100	1045
PH-FIELDISTD UNITS)	400	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
MULTISTORET(MET WT)	10320	26.0	23.0	19.0	39.0	29.0	28.0	40.0	34.0	26.0	22.0
CADMIUM,SED (UG/G-DRY)	1028	0.3	0.2	0.4	0.9	0.3	1.0	0.8	0.9	0.3	0.3
CHROMIUM,SED (UG/G-DRY)	1029	9.8	3.3	11.2	20.0	16.0	16.0	27.6	24.1	13.0	15.1
COPPER,SED (UG/G-DRY)	1043	11	3	14	28	24	27	33	26	8	8
MERCURY,SED (UG/G-DRY)	71921	<0.07	<0.06	<0.06	0.47	<0.07	<0.07	<0.08	<0.07	<0.07	<0.06
NICKEL,SED (UG/G-DRY)	1068	2	0.6	3	8	5	6	11	7	4	5
LEAD,SED (UG/G-DRY)	1052	51	12	100	99	39	120	380	280	41	43
ZINC,SED (UG/G-DRY)	1093	22	6	46	116	63	149	334	118	39	36
CYANIDE,SED (UG/G-DRY)	721	<0.1	<0.6	<0.6	1	<0.7	0.7	0.8	0.8	0.8	<0.6
TOR,SED (UG/G-DRY)	99344	267	270	537	1590	207	511	226	11900	525	291
ARSENIC,SED (UG/G-DRY)	1003	7.4	3.6	4.0	7.1	2.0	1.3	3.6	3.4	1.1	1.4

Parameter	Value	Value	Value	Value	Value	Value	Value
PREMILSSED (UG/G-DRY)	81565	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
FOXPSED (UG/G-DRY)	98610	<5.00	<5.00	<5.00	<5.00	5.70	<5.00
IUCPSED (UG/G-DRY)	98611	1760	3120	4320	17400	5490	22300
							5380

ENVIRONMENTAL SCIENCE & ENGINEERING

PROJECT NUMBER 84420100
FIELD GROUP: SED
PARAMETERS: ALL SAMPLES: ALL

04/11/85

STATUS: FINAL

PROJECT NAME MAXWELL AFB
PROJECT MANAGER: JOHN BONDS
FIELD GROUP LEADER: TOM PARK

SAMPLE NUMBERS

PARAMETERS	STORET #	ST-11
DATE	METHOD #	469310
TIME		1/17/85
PH-FIELDISTO UNIT(S)	400	NA
MOISTURE(ZMET MT)	70320	26.0
CADMIUM,SED (UG/G-DRY)	1028	0.4
CHROMIUM,SED (UG/G-DRY)	1029	14.8
COPPER,SED (UG/G-DRY)	1043	17
MERCURY,SED (UG/G-DRY)	71921	0.21
NICKEL,SED (UG/G-DRY)	1060	5
LEAD,SED (UG/G-DRY)	1052	77
ZINC,SED (UG/G-DRY)	1093	72
CYANIDE,SED (UG/G-DRY)	721	<0.7
TOE,SED (UG/G-DRY)	99344	278
ARSENIC,SED (UG/G-DRY)	1003	1.5

PHENOLS SED (UG/G- DRY)	41565	<1.00
TOX SED (UG/G-DRY)	98610	<5.00
TOC SED (UG/G-DRY)	98611	5810

APPENDIX Q--REFERENCES

REFERENCES

- Engineering-Science (ES). 1984. Installation Restoration Program, Phase I - Record Search, Maxwell Air Force Base, Alabama. Atlantic, GA.
- Environmental Science and Engineering (ESE). 1983. Confirmatory Environmental Survey, Alabama Army Ammunition Plant. Final Report. Report No. DRXTH-AS-83221. Gainesville, FL.
- Knowles, D.B., Reade, H.L., and Scott, J.C. 1963. Geology and Resources of Montgomery County, Alabama. U.S. Geological Survey Water Supply Paper 1606.
- Powell, W.J., Reade, H.L., and Scott, J.C. 1957. Interim Report on the Ecology and Groundwater Resources of Montgomery, Alabama, and Vicinity. Geological Survey of Alabama Information Series 3.
- State of Alabama. 1982. Alabama Water Quality Criteria and Use Classifications Regulations. In: Environment Reporter, State Water Laws, 701:1001-1031.
- U.S. Environmental Protection Agency (EPA). 1976. Quality Criteria for Water. EPA-440/9-76-023. Washington, D.C.
- U.S. Environmental Protection Agency (EPA). 1980. Water Quality Criteria Documents: Availability. Federal Register, 45(231):79318-79379.
- U.S. Environmental Protection Agency (EPA). 1981. Water Quality Criteria; Corrections. Federal Register, 46(156):40919.
- U.S. Environmental Protection Agency (EPA). 1984a. National Interim Primary Drinking Water Regulations. Code of Federal Regulations, Title 40, Part 141.
- U.S. Environmental Protection Agency (EPA). 1984b. National Secondary Drinking Water Regulations, Secondary Maximum Contaminant Levels. Code of Federal Regulations, Title 40, Part 143.3.

END

DATE
FILMED

8-86

DTIC